VIC and VG CLAIMS
Whitehorse Mining Division
Yukon Territory
N.T.S. 115 I/3
62°09'N 137°10'W
U T M 6893000 m N
383000 m E

GEOLOGICAL, GEOPHYSICAL, GEOCHEMICAL and DRILLING REPORT

Date: November 1986
Owner: G. Dickson/Kerr Addison Mines Ltd.
Operator: Kerr Addison Mines Ltd.
Authors: K Heberlein, L. Lyons
Program: June 12 - September 12, 1986.

091907

TABLE OF CONTENTS

		Page
1.	INTRODUCTION	1
1.1	Summary	1
1.2	Location and Access	4
1.3	Physiography	4
1.4	Claims Description and History	6 & 7
2.	GEOLOGY	10
2.1	Regional Geology	10
2.2	Property Geology	12
2.3	Economic Geology, Alteration and Mineralization	17
3.	GEOCHEMISTRY	20
3.1	Rock Samples	20
3.2	Silt and Soil Sampling	25
4.	GEOPHYSICS SURVEYS	25
4.1	Magnetometer Survey	26
4.2	VLF-EM Survey	27
4.3	Self-Potential and Resistivity Surveys	28
5.	DRILLING PROGRAM 1986	30
5.1	Drilling	30
5.2	Transit Survey	33
6.	CONCLUSIONS AND RECOMMENDATIONS	33
	REFERENCES	34
	STATEMENT OF COSTS	35

TABLE OF FIGURES

Figure		Page
1.	VIC Claims Location	5
2.	VIC and VG Claims - Claim Map	9
3.	Regional Geology - Mt. Nansen Area	11
4.	Grid Location	11a
5.	VIC W Geology, Sample Locations, Geochemistry (1:5000)	In Back Pocket
6a.	VIC E Geology (1:5000)	"
6b.	VIC E Geochemistry (1:5000)	"
7a.	VIC E - Main and North Zones - Trench Geology (1:2000)	"
7b.	VIC E - Main and North Zones - Trench Geochemistry (1:2000)	"
8a.	Main Zone Trench Geology (1:500)	"
8b.	Main Zone Trench Geochemistry (1:500)	"
9a.	Magnetometer Survey - Profiles	"
9b.	Magnetometer Survey - Total Field Value	"
9c.	Magnetometer Survey - Gradient	"
10.	Self-Potential Survey - Profiles	"
12.a	DDH 1-19 Sections	"

Tables

1	Anomalous Sample Descriptions and Results	22
2.	Drill Hole details	32
3.	Drill Hole Locations	In Back Pocket
4.	Transit Survey Control Stations	"

Appendices

1.	Geochemical and Assay Result Sheets
2.	Drill Logs 1986
3.	VLF-EM Survey Data

VIC and VG CLAIMS

1. INTRODUCTION

1.1. SUMMARY

The VIC group, comprised of 126 claims is located approximately 70 km due west of Carmacks, Yukon Territory. The claims cover the northern periphery of the Mt. Nansen Gold camp which is presently being actively explored by Chevron Resources and Archer Cathro.

Access is good via a 4WD road from Carmacks to the edge of the property.

Research indicates that the Mt. Nansen Gold camp and the VIC claims lie on the edge of a NNE trending down dropped fault slice.

The VIC showings consist of approximately East-West trending, steep south dipping gold-bearing quartz veins in the central claim area.

Two zones were outlined, the WAR or MAIN Zone over the upper trenches, and the NORTH Zone over the lower trenches, where higher grades (to 114.79 g/t Au, averaging >34 g/t) are found only in float. The two zones together cover an area of approximately 1 km x 700 m.

Work in 1986 included extending mapping and sampling over the whole property, geophysics surveys (VLF, EM, S.P.,Magnetometer) over the trenched area, trenching and diamond drilling.

Property mapping found granitic intrusives at the east and west ends of the property, granitic intrusives separated by a hb-KF syenite porphyry. The syenite is intruded by numerous E-W to NE-SW trending closely associated dykes of 2 distinct types - massive felsic dykes and (?) later rhyodacitic feldspar +/- quartz porphyry dykes which may be feeders for the Mount Nansen volcanic rocks.

Quartz veins are associated with clay limonite-hematite alteration zones and felsic dykes. Veins tend to be lensy, but can be followed for up to 200m. Maximum width seen was 40cm. Stringer zones are more common than veins. Quartz breccia is found as float. Carbonate veining is rare.

In 1986, 19 holes were drilled on the VIC Claims totalling 1594.41 meters.

The primary targets were source quartz veins for the abundant, highly anomalous quartz float found throughout the trenched area and extensions of quartz veins outcropping in many trenches.

VLF-EM and S.P. surveys showed few clear conductors. The mag. survey was more useful in outlining areas of interest as follows:

1) L1850E-2050E 525N-450N

This is a zone of 2 or more subparallel quartz veins attaining a maximum width of 30cm. Values range to 192.0 g/t Ag and 98.5 g/t Au (in float). Quartz breccia float here carries 23 g/t Ag and 4.94 g/t Au. Scattered As and Sb anomalies are also found. This area has no associated soil geochem. or geophysics anomalies and little significant clay alteration. However, soil geochem. anomalies (to 620 ppb Au), clay alteration, and mag. lows to the east and west and rare float (4.0 oz/t Ag) in a projected fault alteration zone and VLF-EM, anomalies to the east suggests that this zone may extend from L1650E to L2400E, over 750 m. DDH 1 and 17, on strike with the south part of this trend, intersected quartz veining. As this trend cuts across the top of the North Zone, it is possible that this is the source of the high grade float.

2) L2200E 150N to L2400E +150N (Float)

Weakly anomalous Au and Sb values in quartz float is associated with a mag low, which joins at L2150E with an ENE trending soil/clay zone which in turn joins with an extensive mag. low and an S.P. conductor between L1950E and L1550E, from the baseline to 075N. No anomalous soils and no outcrop were found here.

3) Trench 7 quartz veins

The EW trending quartz lenses and stringer zones (to a maximum of 40cm width) in Trench 7 which was found on drilling (DDH 6,7, 10) to be cut off by a dacite dyke, is on strike to the west with a major mag. low (L1400E 350N). Au values range to 129.46 g/t found in float collected over a length of 61 m to the west of Trench 7. This zone is traced in float and outcrop from L1800E to L1550E (over 250 m). The mag. low anomaly is in an area of no outcrop or float. Overburden may be thick.

Other, unexplained mag. lows are found in this same grass covered depression in the west grid.

4) L2100E - L2200E, 800 N

Two short SP conductors trend E-W and NE. These both cut the North Zone trenches, but no outcrop is seen here.

Several scattered rock and silt anomalies were found away from the main showings which require more detailed follow-up.

VIC WEST;

5) Pyritic dacite porphyry float found on the lower road carried 190 ppb Au. This is interesting in that no silicification was evident, giving the possibility of mineralization other than quartz veining.

6) A silt taken from a creek draining the basal Mt. Nansen Volcanics contact carried 35 ppb Au. Quartz float here was not anomalous.

7) Two silt anomalies were found in Iron Creek, south of the main bend (45 ppb, 30 ppb Au). These are over 3 km south of the North Zone, with a number of non-anomalous silt samples between. This suggests the possibility of mineralization in the area of the anomalous samples.

8) A shear zone north of Iron Creek carried 120 ppm As. Brown chalcedonic quartz float here carried no anomalous values. A trench to the west of this zone contained quartz float carrying 85 ppb Au.

9) Scattered quartz float in intrusives collected below Victoria Peak assayed 2.54 g/t Au. Exploration should be exended south and east of the peak.

10) An anomalous (50 ppb Au) silt sample was taken from the creek 1 km north of Iron Creek. This is 1 km east of the "No Beans Zone" which was investigated in some detail in 1985 due to the presence of quartz veining associated with rhyodacite quartz feldspar porphyry dyke swarms. A reconnaissance follow-up of this area failed to locate a source of this anomaly.

RECOMMENDATIONS:

It is recommended that target areas found in the 1986 program be trenched, and that geophysics surveys (particularly magnetometer) be filled in and extended over these areas.

An analysis of alteration and mineralogy might be useful.

A more detailed follow-up is suggested for anomalous sample areas found elsewhere on the property. Any targets generated should be drilled.

1.2 Location and Access

The VIC claims are located approximately 47 km due west of Carmacks, in the mainly unglaciated Dawson Ranges of the Yukon Territory. The claims cover Iron Creek, 2 km northwest of Victoria Mountain. Access is good via a 60 km 4WD road from Carmacks to the west edge of the property, after which the road is passable only by cat. The drive from Carmacks to the claims is about 2 hours. A helicopter is available from Carmacks, 20 minutes flight time away.

1.3 Physiography

Topography on the VIC Claims is dominated by 2 broad backed NE-SW trending ridges with moderate slopes, and broad muskeg filled valleys. Elevation ranges from 1190 m (3900') in the west, where southwest flowing Iron Creek runs into the Klaza River headwaters, to ~1710 m (5600') in the east. Treeline is at ~1220 m (4000') elevation, so that most of the claims are covered with muskeg and thick buckbrush and alder. Higher slopes are grassy. Permafrost is found at as little as 25cm depth in summer. While much of the ground is wet, flowing water is intermittent except in Iron Creek.



FIG. I

KERR ADDISON MINES LTD	
VIC CLAIMS	
LOCATION MAP	
SCALE - 1 : 250 000	DATE - NOV., 1985
DRAWN BY: P.H., C.B.	DATA - C.B.
NTS - 115 I 3	REVISED -

Outcrop is <2% and forms tors and castles on the ridgetops. Felsenmeer is moderately abundant on the ridgetops. The climate is cold and dry, with temperature extremes of -45o to +30oC, and up to 30 cm of precipitation (more than half as snow).

1.4 Claims Description and History

The VIC group is comprised of the the VIC 1-118 claims and the VG 1-8 claims. Claims descriptions are as follows:

CLAIMS	RECORD NUMBERS	RECORD DATES.
VIC 1-6	YA 86308-YA 86313	Dec. 17, 1984
VIC 7	Y 76007	July 17, 1972
VIC 8	YA 86314	Dec. 17, 1984
VIC 9	Y 76009	July 17, 1972
VIC 10-232	YA 86315-YA 86328	Dec. 17, 1984
VIC 24	Y 76024	July 17, 1972
VIC 25	Y 86329	Dec. 17, 1984
VIC 27-32	YA 86330-YA 86335	Dec. 17, 1984
VG 1-8	YA 86404-YA 86413	Dec. 20, 1984
VIC 33-118	YA 93037-YA 93122	Aug. 15, 1985

The original VIC and VG Claims were recorded in Whitehorse Mining Division by G. F. Dickson, P.O. Box 4940, Whitehorse, Y.T. These claims were transferred to Kerr Addison Mines Ltd. on Sept. 9, 1985. At present the company is the registered owner of the whole 126 claims block.

The 1985 and 1986 assessment work was undertaken by Kerr Addison Mines personnel under the option agreement with G.F. Dickson.

HISTORY

Mt. Nansen District

1900 to 1910	Placer Exploration
1917	Staking of first lode claim at headwaters of Discovery Creek by. C.P. Mack.
1943	Discovery of Brown-McDade vein by Afe Brown and George McDade.
1945 to 1947	Underground work on Brown-McDade vein by Leitch Gold Mines Ltd. Trenching on Huestis vein by Huestis Syndicate. (H. H. Huestis).
1958	Renewal of prospecting the area.
1962	Discovery of Webber vein Gordon Dickson.
1963	Formation by Gordon Dickson of Mt. Nansen Exploration Syndicate, financed by Newmont, Noranda, Rio Tinto, Kerr Addison, Conwest, and Faraday Uranium and Joseph Rankin. Surface work on Huestis and Webber by successor of syndicate (Mt. Nansen Mines Ltd).
1964 to 1967	Control of Huestis and Webber properties taken by Peso Silver Mines Ltd. Surface and underground work.
1968	Brief production, mainly from Heustis vein. 18,000 tons milled, yielding 2484 oz. of Au 76,534 oz. of Ag, 108,621 lb. of Pb. Official reason given for termination of production were poor recovery (no cyanide circuit) and lower than forecast grades.
1969	Exploration of the porphyry Cu potential of the area immediately north of the veins by several groups including Mt. Nansen Mines Ltd., Cyprus Exploration Corporation and Cominco.
1976	Further brief production at the Huestis. 6429 tons milled yielding 1930 oz. Au, 45,000 oz. Ag, and approximately 128,000 lb each of Pb and Zn.
1981	Feasibility study on Webber, Huestis, Brown McDade and Cabin Creek veins by a party with an indirect interest in the claims, yielded total reserves of: Proven: 39,200 oz. Au, 1.10 m oz. Ag. Probable: 70,500 oz. Au, 1.38 m oz. Ag.
1985	Option of central Mt. Nansen Camp from B.Y.G. Natural Resources Inc. by Chevron Resources Ltd. Intensive drilling of the Brown McDade zone yielded a best intersection of 25.5 m with 0.247 oz/t Au, 2.82 oz/t Ag.
1986	Extensive trenching by Chevron Resources, Ltd., Archer Cathro and B.Y.G. Natural Resources, and underground exploration of Brown-McDade Vein.

VIC and VG CLAIMS

The vicinity of these claims was first prospected by Gordon Dickson in 1946 and the main zone has been held intermittently by him since then. Trenching was carried out by Peso Silver Mines Ltd. in 1965, soil sampling by Associated Geological Services Ltd. (for Peso?) in 1968, and further trenching by Skyline Exploration Ltd. in the 1970's. There has been no drilling reported.

Work by Kerr Addison in 1985 consisted of preliminary mapping establishment of a picket grid, and soil and rock sampling. This work outlined 2 zones, the WAR and MAIN zone over the upper trenches where quartz float, subcrop and outcrop up to 60cm width is seen; and the NORTH zone over the lower trenches, where higher grades (to 114.79 g/t Au, averaging 34.0 g/t) are found only in float. The 2 zones together cover an area of approximately 1 km x 700 m.

Work in 1986 consisted of property mapping at 1:5000, 1:2000 and 1:500; extensive rock sampling; some soil and silt sampling; VLF-EM, magnetometer and self-potential surveys; trenching; and diamond drilling. The picket grid was extended and magnetic problems with the location of this grid were overcome by a transit survey late in the summer.

Total physical work in 1986 was:

Magnetometer survey	11.950 line km
VLF-EM survey	10.725 line km
Self-Potential survey	8.920 line km
(Resistivity survey -	300 m useable)
19 BQ holes totalling	1594.41 m
Backhoe trenching	~1070 m. total
130 rock samples (for Au, Ag, As, Sb)	
62 silt samples (for Au, Ag, As, Sb)	
16 soil samples,(for Au, Ag, As, Sb)	
459 Drill core samples	



FIG. 2

KERR ADDISON MINES LTD	
VIC & VG CLAIMS	
CLAIM MAP	
SCALE - 1:50 000	DATE - SEPT., 1985
NTS - 115 I 3	REVISED -

2. GEOLOGY

2.1 REGIONAL GEOLOGY

Government regional mapping of the Mount Nansen area has been done by Bostock (G.S.C. Memoir 189; 1938) and by Tempelman-Kluit (G.S.C) Open File 200, 1974; and G.S.C. Open File 1101,1984) (See Figure 3).

The VIC Claims are located within the Yukon Cataclastic Terrane. The area is underlain by Proterozoic to Precambrian metamorphic rocks of the Yukon Group, intruded by 2 major multiphase intrusive events,one dated at ~100 m.y.a, and an earlier Triassic/Jurassic one. The later intrusive event gave rise to the felsic volcanics of the Mount Nansen Group.

A very generalized subdivision of the older and younger intrusives is: Older suite - frequent high hornblende, moderate to low biotite, glassy quartz, high plagioclase. Younger suite - low hornblende, higher quartz, smoky quartz, high K-feldspar.

The Mount Nansen Group is in turn overlain by plateau basalts of the Carmacks Group. General descriptions of the units are as follows:

Proterozoic to Precambrian<u>Yukon Group</u>
- quartz-amphibolite-mica schists and gneisses, amphibolite, granodiorite gneiss, leucogranite, marble and minor serpentinite.

Triassic to Jurassic Granitic Intrusives
- variable composition, from syenite to granite to hornblende quartz/diorite.

mid-Cretaceous<u>Mount Nansen Group</u>
- andesitic to rhyolitic porphyritic and pyroclastic rocks and related subvolcanic intrusives.

upper Cretaceous <u>Carmacks Group</u>
- basaltic to andesitic flows and tuffs.

The Mount Nansen Au-Ag bearing veins are hosted by the Yukon Group and rhyolite porphyries of the Mount Nansen Group. Research by Arscott (1983) indicates that the veins, hydrothermal hot spots and associated subvolcanic intrusives lie on the edge of a NNW trending down-dropped fault slice, with a relative drop of 215 m +.

Structure of the area is described as high angle block faulting contemperaneous with porphyry intrusions (Sawyer, 1976). Main structural orientations are 000o,120o, 160o, and 055o. (Saager, 1971).



LEGEND

Upper Cretaceous Carmacks Gp.

- uKcb — Basalt flows
- uKct — Interbedded sandy tuff & andesitic basalt flows
- uKcr — Flow banded rhyolite to dacite, felsic breccia & welded tuff

Mid Cretaceous Mount Nansen Gp.

- Kmn — Andesite plagioclase porphyry, andesite breccia
- Kmnb — Andesite breccia, minor porphyry
- Kmnr — Rhyolite to dacite quartz feldspar porphyry

Casino Granodiorite

- Kgd — Biotite hornblende granodiorite

Coffee Creek Granite

- Ky — Hornblende syenite to granodiorite, fine grained

Jurassic — Big Creek Syenite

- Jy — Hornblende syenite, coarse to very coarse, porphyritic

Upper Triassic — Granite Mountain Batholith

- TRgdm — Biotite hornblende granodiorite, foliated, medium to coarse grained

Paleozoic? - Devonian? — ?Pelly Gneiss

- Pnl — Biotite or hornblende gneiss
- Ps — Quartz mica schist
- Pm — Amphibolite, amphibolitic gneiss, biotite-amphibolite granodiorite gneiss

0 5 10

kilometres

KERR ADDISON MINES LTD.

REGIONAL GEOLOGY

Mt. Nansen Area

Scale: 1:250,000	Date: Oct. 1986
Drawn by:	Data: GSC O.F 1101
N.T.S. 115 I/3	Revised:



FIG. 4

KERR ADDISON MINES

VIC CLAIMS

YUKON TERRITORY

GRID LOCATION MAP

SCALE 1:50,000	DATE: OCT., 1986
DRAWN BY K.H.	DATA:
N.T.S. 115 I/3	REVISED:

2.2 PROPERTY GEOLOGY

Geologic mapping of the VIC claims was based mainly on felsenmeer and rock exposed in trenches. Outcrop on the property is restricted. Mapping was done at 1;:5000 over the whole property, and at 1:2000 and 1:500 over the MAIN and NORTH zones. It has been noted that trench walls do not always reflect underlying bedrock, giving some leeway in the interpretation of talus.

Geology is somewhat complex. Rocks are almost entirely intrusive with very little outcrop left of the once overlying Mount Nansen Volcanic rocks. (See Figures 5, 6a, 7a, 8a) Descriptions of rocks seen on the property are as follows:

Dt Dacite ? tuff,? tuff-breccia, ? crystal tuff and flows
- Caps southwest ridge
- Medium gray-green; weathers same to brown; blocky to angular chips.
- Varies from massive and fine-grained, to porphyritic with up to 10% white, vaguely defined feldspar crystals to 2mm; to a tuff or flow-breccia with angular to subangular fragments generally similar. Fragments show up on weathered surfaces. Rare fragments are seen of well rounded and altered ? granitic intrusive (3cm), and of a more felsic composition. No size sorting is apparent.
- Magnetic
- Rare pyrite cubes to 0.5 mm
- Weakly to moderately propylitically altered.
- No contacts seen

RDf(q)p-QM Rhyodacite feldspar + quartz porphyry to quartz monzonite.
- Forms numerous dykes and irregular bodies over the claims
- light to medium gray-green to pinkish gray (coarser variety); weathers same to orange-limonite; blocky and fresh looking.
- Varies from a fine to medium grained equigranular quartz monzonite; to a crowded feldspar porphyry with up to 45% white square feldspar crystals to 2mm (average ~mm) in a fine-grained moderately siliceous matrix. Hornblende content increases with grain size up to 5-7% maximum. Crystals are sub to euhedral (some look broken) and average 2mm (maximum 4mm).
  To the south, the porphyry varies to andesitic.
  To the north, the composition is more rhyolitic, and sub-hedral gray to clear quartz crystals to 2-3 mm make up to 7% of the rock. Feldspar crystals make up only ~7-10%.

- Noncalcareous; weakly to moderately magnetic.
- No visible sulphides.
- Weak propylitic alteration. Weak clay alteration of feldspars. Minor local sericitization.
- Rare xenoliths of syenitic porphyry, and greenstone.

RD Rhyodacite Dykes

- Found only in trenched areas.
- Variably white to pink to pale green; weathers same to strongly limonitic washed; angular to chippy and recessive.
- Massive to fine to medium grained.
- Varies from moderately hard to moderately soft; may be closer to a trachyte in composition.
- Pocking of weathered surfaces suggests up to 5-7% feldspar crystals to 2mm, but these are rarely seen.
- Pyrite as euhedral to subhedral cubes to 0.5mm is disseminated near contacts and makes up to 5% of the rock.
- Noncalcareous, Nonmagnetic.
- Contacts are strongly flow banded, with bands up to 2cm.
- Weakly to moderately locally sericitized; weakly to intensely clay altered; Manganese dendrites are very common on fracture surfaces.

BA Basandesite Dykes

- Found only in syenite porphyry.
- Dark gray-green fresh and weathered; rubbly.
- Massive, fine to medium-grained.
- Commonly somehwat hornfelsed to a greenstone.
- Feldspar crystals (plag.) to 2mm make up to 7% of the rock.
- Moderately calcareous. Moderately magnetic.

Sp Syenite to Granite porphyry

- Found in central claim group.
- Light gray to whitish weathered, blocky.
- Varies from medium grained equigranular to a coarse porphyry with K-feldspar megacrysts averaging 2cm (maximum 6cm) forming 5-20% of the rock. K-feldspar forms from 20-60% of the rock, which is weakly to strongly postassic altered. Euhedral hornblende crystals to 1.5cm (average 4mm) form between 15-80% of the rock.
- K-feldspar and hornblende crystals are commonly strongly aligned, with bands of amphibolite. Locally, shearing along this direction has produced lensoidal shaped K-feldspars and gneissose textures.
- Stongly magnetic. Noncalcareous.
- Weakly to strongly propylitically altered.
- Cut by quartz-K feldspar prgmatite dykes to 3cm, and minor aplite.

BiGDi Biotite +/- hornblende Granodiorite to Quartz Monzonite

- Found in west of VIC claims.
- Weathers gray to medium orange-gray. Moderately fresh looking.
- Massive, equigranular, medium grained (1-33mm)
- K-feldspar ~ plagioclase.
  Biotite to 2mm is euhedral (some secondary?) and forms 10-15% of the rock.
  Hornblende to 2mm is sub to euhedral and forms up to 2%.
  Quartz is gray and subhedral, and forms 15% of the rock.
- Noncalcareous. Locally weakly magnetic.
- No visible sulphides.

BiGDi-QM Biotite granodiorite to quartz monzonite.

- Found in northeast claims.
- Weathers gray to orange patched; large slabs and grusen.
- Medium grained, approximately equigranular (1-2mm)
- K-feldspar ~ plagioclase. Weakly porphyritic with up to 5% K-feldspar crystals to 3mm.
  Biotite crystals to 1mm are euhedral (some secondary?) and forms between 10-15% of the rock.
  Quartz is light gray and subhedral and forms 15% of the rock.
- Noncalcareous. Nonmagnetic.
- No visible sulphides.
- Strong fracture/cleavage at 045o/10-40oN forms 2-4cm thick slabs.

HbR Hornblende ? Rhyodacite

- found as rubble associated with biotite granodiorite in the northeast VIC claims.
- Medium to dark gray matrix, weathers brownish-gray; blocky.
- Matrix is very hard, aphanitic to very fine-grained with up to 10% well-formed prominent euhedral hornblende crystals averaging 4mm.
- Noncalcareous. Strongly magnetic.
- Trace pyrite is disseminated as very fine anhedral grains.

Gn Quartz-feldspar-hornblende gneiss

- Found in the central claims area.
- Gray weathered, recessive.
- Mostly fine to medium grained, poorly to strongly banded. Bands are parallel to moderately contorted, with thickest bands being ~30cm wide. Orientation is N-S, to ~020o.
- Varies from predominantly feldspar to locally predominantly quartz with bands to 30cm of coarse amphibolite (crystals to 5mm).
- Noncalcareous. Nonmagnetic to locally weakly magnetic.
- No visible sulphides.

Relationship between the various units were not easily discernable due to the lack of good outcrop.

The oldest rock on the claims is likely the quartz-feldspar-hornblende gneiss, which appears to belong to the basement Yukon Group. The gneiss seems to be either a fault wedge, or a screen within the syenite porphyry. Syenite porphyry outcrops near the gneiss are commonly gneissose, as are some outcrops of dacite feldspar porphyry which intrude the gneiss. Shearing may have taken place along the syenite-gneiss contact, but whether the syenite has intruded the gneiss, or the gneiss is faulted up into the syenite is unknown.

The syenite porphyry may be the oldest intrusive rock. The high hornblende content indicates that it belongs to the older intrusive suite, while K-feldspar content indicates the younger suite. The unit fits the description, by Templeman-Kluit, of the Jurassic Big Creek Syenite, a coarse to very coarse hornblende syenite porphyry, with "screens of basement gneiss". The syenite is intruded by basandesite, dacite feldspar porphyry and rhyodacite dykes. It appears to underlie the Mount Nansen Volcanics in the West Claim block. A later syenite porphyry dyking is found in some shear zones.

The relationship of the biotite granodiorite bodies is unknown. The composition of the 2 intrusives is very similar. The biotite content and lack of hornblende would seem to indicate that they belong to the younger intrusive suite. Contacts, while not seen, appear to be steep. The east contact of the eastern granodiorite with Carmacks basalts is a north-south striking, steep fault. The cleavage of the eastern body may be due to close proximity to this fault, but the appearance is more of an original alignment of crystals parallel to an intrusive contact. This suggests that the roof of the eastern body is being exposed, while the possibility related western body, at a slightly lower elevation, has been eroded to a deeper level. The description of these rocks is somewhat similar to that of the Cretaceous Casino granodiorite (equigranular biotite-hornblende granodiorite), in which case they are the "plutonic phase of the Mount Nansen Group".

The massive, rhyodacite dykes form a braided dyke swarm in syenite porphyry in the main area of trenching. They are not found elsewhere. The general strike of these dykes is northeast to north, dipping vertically to steep either way. These dykes appear to be cut off by the Dacite porphyry dykes, but locally, the reverse seems to be true, suggesting that while the dacite porphyry dykes are generally younger, there is some amount of contemperaniety. Both dyke sets follow the same trends, and show a major deflection from northeast south-west to north-south in the Main Zone. The rhyodacite dykes reach 40 m width where they have splayed into several branches.

The numerous dacite feldspar porphyry dykes to quartz monzonite stocks intrude all rock types, except, possibly, the biotite granodiorite. Contacts are wavy and very irregular. The strike of these dykes on most of the property is northeast to north with steep to moderate dips. Thickness reaches 50 m in the Main Zone. These dykes seem gradational to the dacite feldspar porphyry flow (?) in the West VIC claims , and are probably the subvolcanic feeders to the Mount Nansen Volcanics.

The Mount Nansen Volcanics are found capping the southwest ridge top, and have been completely eroded away elsewhere.

Structure on the property is on 3 main directions: 003-020o /subvertical, 060o-100o/vertical to steep north, and 120o-133o/steep northeast.

A major ~070° trending fault is seen on air photos to follow Iron Creek and Rowlinson Creek to the east. A later NW trending right-handed fault has offset Iron Creek by as much as 600m. There is some some suggestion of minor down-dropping of Mount Nansen Volcanics towards Iron Creek along a NW direction. A sharp deflection of the dyking in the Main Zone may be related to this NW trending structure. Air photos also show numerous braided lineaments on the ridges, trending overall at 070o. The numerous small shears seen on the ground commonly have associated clay-limonite-hematite alteration and minor quartz-calcite veining.

2.3 ECONOMIC GEOLOGY, ALTERATION AND MINERALIZATION

The VIC Claims are located on the northern periphery of the Mount Nansen Gold Camp. The Mount Nansen Mine is located 9 km due south, where four zones of Au-Ag bearing quartz veins are associated with silicified and argillic altered shear zones. Strike of the veins is northwest, with north splays, dipping vertically to steep east or west. The veins branch and anastomose extensively. Widths range to 3 m and average 0.9 to 1.2 m. Host rocks are Yukon Group Metamorphic rocks and rhyolite dykes. Some ore is associated with sulphides which include arsenopyrite, pyrite, minor sphalerite, chalcopyrite and stibnite. The Mount Nansen Mine operated briefly in 1968 and 1976 before closing down due to poor recovery and poor economics. Proven-probable reserves are given as 252701 m tons at 13.84 g/t Au and 305.51 g/t Ag.

Numerous other showings in the area include the Esansee Ag-Au showing on the TAWA claims, 1 km to the southwest; the RUSK Cu-Mo porphyry showing 8 km to the southwest; and the Freegold showing 12 km to the northeast, where a low-grade Au-bearing porphyry is being investigated for heap leaching potential.

On the VIC claims, property wide alteration includes very weakly to locally strongly developed pervasive propylitic alteration, and moderately to weakly developed local patchy sericitization. Minor potassic staining is seen in the granitic intrusives, but is more strongly developed in the area of the Main Zone. Propylitization is also locally strongly developed here.

In the Main Zone, east-west (and rarely, north-south) trending Au-Ag bearing quartz veins are associated with east-west to northeast-southwest trending intense clay-hematite-limonite alteration/shear zones. Dips are subvertical to steep south. At Mount Nansen, rhyolite dyking is considered to be pre-ore. On the VIC claims, mineralization appears to be associated with rhyodacite dyking, but is cut off by later dacite feldspar porphyry dykes.

Alteration is strongest in syenite prophyry, while dacite porphyry dykes are only locally moderately affected. Massive rhyodacite dykes commonly are weakly to strongly pervasively clay altered. Alteration has given the rocks a mottled to coarsely banded powdery white, rust and deep purplish-red colouration. Textures and mafic minerals are partially to totally destroyed, making indentification of original rock type impossible in some places.

Associated with the clay alteration is patchily developed weak to intense silicification, quartz stringers and veins. Weak sericitic alteration is rarely seen, and sericitic envelopes are locally developed on quartz veins.

Quartz veins can be grouped into 3 main areas, from north to south; 1) L1500E 550N to L2150E 450N; 2) L1850E 325N to L2100E 275N; and 3) L1550E 275N to L1800E 175N.

Quartz veins are lensy, with a maximum width seen of 40cm, but alteration zones can followed for some distance. The northwest group of veins can be followed for over 300m.

Quartz vein textures include: white, massive, fine-grained sugary; drusy; coxcomb; brown chalcedonic; and breccia. Limonitic washed fractures are locally commmon. Earthy limonitic masses may be derived from both carbonate and sulphides. Quartz-calcite veining is rare, but where seen consists of coarse crystalline calcite banded with massive gray to white quartz. Two episodes of veining have been suggested by cross-cutting gray quartz stringers within massive white quartz.

Stringer zones are moderately common. They appear to be concentrated within the massive rhyodacite dykes. The stringers vary from brown chalcedonic to fine grained gray quartz to 3mm thick. Main orientations of stringers is 003°-010° and 060°-088°.

Quartz breccia float is found at L1900E +475N, and at L2100E + 475 N(near drill hole 9), but none is seen in outcrop. Two types of breccia were seen: gray siliceous fragments in a coarse coxcomb (to 2cm) matrix; and white quartz fragments in a gray siliceous matriz. Fractures were drusy coated and limonitic.

Sulphides were not commonly associated with quartz veining, and where seen consisted of trace to 3-4% very fine to fine-grained pyrite. Rare malachite staining is present. Minute specks of a rare gray metallic mineral were unidentified. Up to 5% pyrite was seen in massive rhyodacite dykes, disseminated near the contacts. Earthy limonitic masses in open spaces in some vein material may be derived from sulphide. If so, then sulphide content originally would have been as much as 10% locally.

Talus of quartz veins hosted in relatively unaltered syenite porphyry is found on the north slope below the Main Zone. The talus looked like pegmatitic quartz, and carried some low Au values.

Due to the lack of outcrop and the lensy nature of the veins and alteration zones, the exact extent of mineralization is not known. Alteration is found over a strike length of about 600 m and a width of 550 m.(not including North Zone float). Several alteration zones are contained in this width, of which the largest is up to 250 m wide. To the west, the alteration zones strike into an area of no outcrop and into a quartz monzonite body which is believed to post-date mineralization. To the east, the zones seem to strike into sheeted dacite porphyry dykes. However, if the zones deflect to the northeast, parallel with dyking, then once again they strike into a large grassy depression. Quartz vein talus from below this last depression and 1985 silt and soil samples here were anomalous in gold.

If the alteration zones extend into both of these depressions a potential strike length of about 2.5 km is given.

The style of alteration and quartz veining on the VIC claims is similar to that described on the Mount Nansen deposits. Au-Ag mineralization is found in quartz veining and associated intense argillic altered shear zones. Sulphides are minor, but appear to be more abundant at Mount Nansen. Orientation of the mineralized structures differ considerably, from northwest to north at Mount Nansen, to northeast-west on the VIC. Host rocks differ somewhat, but at both properties, mineralization is associated with felsic dyking.

The mineralization on the VIC claims is probably epithermal, but the position of the VIC veins with respect to an idealized model is arguable. The intense argillic alteration with patchy silicification, the textures seen in quartz (including open-spaces, drusy coatings, banding, coxcomb quartz and breccia) and the presence of only minor amounts of sulphides might indicate that the VIC veins are in the upper reachs of an epithermal system. Closer studies of alteration and minealogy might be able to determine this. If so, there is the possibility that sulphide and bonanza mineralization exist below the present surface. There is also potential along strike for further mineralization.

Elsewhere on the property, only small amounts of quartz were found, though numerous small clay-limonite-carbonate altered shears are present. Vein float found was either massive white quartz for brown chalcedony. Minor quartz-calcite breccia and? anydrite-limonite breccia were found in the west of the claims. These appear to be related to shearing.

3. GEOCHEMISTRY

A total of 130 rock, 62 silt and 16 soil samples were taken on the VIC claims this year. A further 459 samples were taken of selected drill core.

Silt and soil samples were dried prior to shipment. Rock samples were split and a representative sample kept where possible. All samples were sent to Chemex Labs Ltd. of North Vancouver. Silts and soils were screened to -80 mesh, with the +80 fraction being saved. Rocks were crushed and pulverized to -140 mesh. Digestion was by Nitric-Aqua Regia, and a standard geochemical analysis by Atomic Absorption spectrometer was done for As, Ag and Sb. Samples from the Main Zone were fire-assayed for Ag and Au. A multielement ICP analysis was run on 22 of the rock samples, 5 silts and 1 soil. Results are listed in Appendix I. Drill core analyses are shown on the profiles (Figures 12A -).

3.1 ROCK SAMPLES

A large number of the rock samples were taken over the Main and North Zones. The results of the sampling show that while most precious metal values are found in quartz veins, mineralization locally extends into the clay-hematite-limonite altered rocks associated with the veining. Anomalous rocks are listed in Table I.

Of 130 rocks taken, 32 are anomalous in Au, 24 in Ag, 12 in As and 18 in Sb. Four samples carry >15 g/t Au, and 16 carry >3 g/t Au. Six samples carry >10 g/t Ag. Ranges of values are:

Au	<5 ppb to 98.5 g/t (6K24R,qv)
Ag	0.1 ppm to 192.0 g/t (6K24R,qv)
As	1 ppm to 5150 ppm (6K46R, q bx)
Sb	0.1 ppm to 50.0 ppm (6K86R, RD dyke, altered) (6K87R,qv)

Quartz veining of area 1 (furthest north) reaches a maximum width of 30cm (in float) and maximum values of 192.0 g/.t Ag and and 98.5 g/t Au (1985 sample). Quartz breccia here assays 23 g/t Ag and 4.94 g/t Au (6K33R). (Soil samples from here in 1985 reach 620 ppb Au). Other samples include 6K29kR-30cm at 13.2 g/t Au, 7 g/t Ag; 6K49klR-25cm at 8.78 g/.t Au, 6.5 g/t Ag; and 6K50R-13.4 g/t Au, 2.3 g/t Ag. Talus from a grassy depression to the north-east of here returned 4.08 g/t Au (6K107R). These veins are a possible source of the abundant high grade North Zone float.

Best values were predominantly in quartz veins with textures varying from massive to drusy to strongly limonitic fractured to brecciated. However, a large number of similar samples taken were not anomalous, showing that mineralization is sporadic, or has some control not yet identified. Good Au values are usually associated with Ag, but Ag also occurred without Au(6K36R- 32.3 g/t Ag, 50.0 ppm Sb). Au/Ag ratio in 25 samples ranged from 0.1 to 8.68 and averaged 1.97:1. A calcite vein carried low anomalous Ag (2.8 ppm) in the northwest grid.

Sporadic high As-Sb values were found, mainly in the south central grid (L1900E 350N) and in the northwest grid (L1600E 550N). These anomalies were not associated with Au-Ag anomalies, and are found in quartz veins, quartz breccia and clay altered syenite porphyry and rhyodacite dykes. While values of As and Sb are quite high in some samples, no arsenopyrite or stibnite were seen. Pyrite was the only sulphide identified. Sulphides content of the veins is generally low and this is reflected in the ICP analysis. Base metal content is generally low. Three rocks carried anomalous Cu (6K30R-229 ppm Cu; 6K33R-159 ppm Cu; 116 ppm Pb, 23 ppm Ag, 382 ppm Bi; 6K48R-214 ppm Cu, 154 ppm Pb). All of these showed slight malachite staining and up to 4% pyrite. They are samples of, respectively, massive quartz, quartz breccia, and feldspar porphyry dacite. One sample (6K34R) carried anomalous Pb and Ag (120 ppm Pb, 25 ppm Ag). Two samples carried anomalous Mo (6K32R-15 ppm Mo; 6K36R-9 ppm Mo). Tellurium content is generally low, indicating that Au is not carried in tellurides.

Scattered anomalous samples were found away from the Main Zone.

1) Pyritic dacite porphyry float found on the lower road carried 190 ppb Au. As no silicification was evident, the possibility is given of mineralization other than that in the quartz veining.(6K3R).

2) Shear zone material from northwest of Iron Creek carried 120 ppm, As (6K20R). Brown chalcedonic and white massive quartz float from here carried no anomalus values. A trench to the west of this zone contained quartz float with 85 ppb Au(1985 samples).

3) A lone (?) pegmatitic quartz sample from the north ridge carried 0.75 g/t Au. (6K38R).

4) A sample from north ridge carried 390 ppm As (608R).

5) Scattered quartz float in intrusives on Victoria Peak assayed 2.54 g/t Au. (6K59R)

These warrant some follow-up work.

TABLE 1

1986 Anomalous Rock Sample Descriptions

Sample No's	Description	Ag ppm	As ppm	Sb ppm	Au ppb
VIC WEST					
6K1R Ft.	Quartz, well fractured, sugary. No visible sulphides (15-10x5cm)	0.1	6	0.8	460
6K2R Ft.	Quartz-KF pegmatite. (20x20x15cm)	0.1	9	1.2	140
6K3R Ft.	fs Dacite. 1% pyrite cubes	0.1	3	0.1	190
6K20R Ft.	Limonite/Anhydrite? Shear zone material	0.1	120	8.4	< 5
VIC EAST		Ag g/t	As ppm	Sb ppm	Au g/t
6K23R Tr.Ft.	Quartz, massive, white to limonitic. (10x8x5cm)	11.5	77	1.0	18.40
6K24R Tr.Ft.	Quartz, limonitic parallel fractures, open cavities, drusy.	192.0	83	0.8	98.5
6K25R Tr.Ft.	Quartz, white massive, light limonitic wash. (10x10x4cm)	5.0	25	0.6	4.32
6K27R Tr.Ft.	Syenite porphyry, heavily limonitic	1.3	55	21.0	0.55
6K28R Tr.Ft.	Quartz, white to black, with 5% limonite specks (10x7x3cm)	0.5	5	1.4	0.34
6K29R s/c	Quartz, fine sugary to massive with lim-Mn coated fractures, coarse drusy open spaces. Banded (30cm wide)	7.0	2	0.8	13.20
6K30R Ft.	Quartz, white to gray, massive with 4% Pyrite, Malachite stained (12x8x5cm)	1.0	10	<10	0.89
6K31R Ft.	Silicified breccia; white quartz and silicified intrusive frags, in white massive quartz. Pyrite 5% locally.	2.8	7	8.0	3.09
6K32R Ft.	Quartz with sulphides and Mn-Ox fract. coating.	2.0	<10	<10	0.21
6K33R Ft.	Quartz, heavily fractured, limonitic, with gray mineral 4%.	23.0	<10	<10	4.94
6K34R Ft.	Quartz, white fine sugary. No visible sulphides (35x20x10cm)	14.5	9	10.4	6.65
6K35R Ft.	Quartz, white massive, heavily limonitic.	34.0	53	0.5	49.00
6K38R N.Ridge Ft.	Quartz, fine to medium grained, hematitic stained.	0.5	6	0.4	0.75
6K43R Tr.Ft.	Quartz breccia, silicified intrusive in coxcomb quartz.	0.5	73	6.0	1.17
6K44R o/c	Quartz veins + veinlets, sheeted over 10cm massive.	2.5	57	11.2	1.23
6K45R s/c	Syenite porphyry, mod. clay - hem-lim altered.	0.5	1380	10.4	0.07
6K46R Tr.Ft.	Quartz breccia. Clay altered fragments in coxcomb quartz.3% pyrite.	0.5	5150	34.0	0.07

TABLE 1

1986 Anomalous Rock Sample Descriptions

Sample No's		Description	Ag g/t	As ppm	Sb ppm	Au g/t
VIC WEST cont'd						
6K47R	Tr.Ft.	Quartz veins, in fs. dacite with ½-1% pyrite	0.3	120	2.4	<0.07
6K49R	o/c	Sheeted/braided quartz veins over 25cm. No sulphides	6.5	16	0.9	8.78
6K50R	o/c	As 6K49R	2.3	7	1.2	13.4
6K55R	o/c	Quartz vein, sugary brownish to drusy in clay altered syenite.	7.0	125	10.6	10.10
6K57R	Tr.Ft.	Quartz, medium sugary to drusy, with earthy limonitic masses.	<0.3	500	14.4	0.07
6K63R	Tr.Ft.	Quartz, white drusy to coxcomb with 50% earthy limonitic masses.(20cm wide)	1.0	800	40.0	<0.07
6K65R	Tr.Ft.	Quartz, white sugary fine to medium grained, limonitic fractures.	2.5	6.9	11.0	9.19
6K67R	o/c	Quartz massive to drusy to coxcomb Limonitic.	0.5	17	5.8	1.30
6K59R (Vic.Pk)	Ft.	Quartz, white barren looking chips (5x3x2cm)	0.2	<10	<10	2.54
6K72R	Tr.Ft.	intensely clay-hematite altered rock with silica.	0.3	20	9.4	0.48
6K74R	o/c	Quartz veinlets, drusy, in syenite porphyry.	0.8	85	4.4	4.05
6K75R	o/c	Quartz veins, braided over 8cm	2.8	6	1.2	24.30
6K76R	o/c	Quartz veins to stringers. No visible sulphides.	<0.3	11	0.4	0.34
6K82R	s/c	Quartz breccia. Chalcedony stringers form boxldsrK around earthy limonitic masses.	0.1*	100	14.4	<5*
6K84R	s/c	Shear breccia, very limonitic, silicified, with ? calcite molds.	22	22	18.0	<5*
6K100R	Tr.Ft.	Limonite-hematite-?gypsum + quartz, white, massive.	0.1	9	38.0	<5*
6K86R	Tr.c.c.	Stringer zone, 3-5% drusy quartz, with Mn, in strong, clay altered massive rhyodacite (1m)	32.3	60	50.0	0.07
6K87R	Tr.c.c.	Quartz vein 3-4cm, white to brown, transistent. Faint banding.	3.3	60	50.0	0.07
6K88R	Tr.c.c.	Quartz vein/shearing zone, strong clay-hematite (2M)	2.5	60	8.6	0.07
6K93R	Tr.c.c.	Quartz vein, massive white quartz. (23cm)	0.3	110	13.2	<0.07
6K96R	Tr.c.c.	? Rhyodacite, strong clay-limonite-silica alteration	0.5	1900	20.0	0.07

TABLE 1

1986 Anomalous Rock Sample Descriptions

Sample No's		Description	Ag g/t	As ppm	Sb ppm	Au g/t
6K99R	Tr.Ft.	Quartz vein/silicified zone in clay altered syenite. (60cm)	<0.3	600	5.2	<0.07
6K101R	Tr.Ft.	Rhyodacite, massive. Minor drusy quartz on fractures (2m)	<0.3	370	7.6	<0.07
6K102R	Tr.Ft.	Quartz vein/silicified zone, strongly limonitic. massive to fine sugary. 50-60% quartz. (2.5m)	0.5	25	2.0	1.51
6K103R	Tr.Ft.	Gouge, strong clay-hematite-carbonate. (70cm)	0.8	35	26.0	0.07
6K105R	Ft.	Quartz,? pegmatitic (15x15x15cm)	<0.3	60	0.4	0.41
6K107R	Ft.	Quartz, massive white. (8x8x5cm)	<0.3	29	0.3	4.08
6D2R	Tr.Ft.	Quartz vein breccia in altered granite	0.5	90	27.0	<0.07
6D4R	Tr.Ft.	Calcite vein. (20cmxlm) coarse crystalline.	2.8	2	0.2	<0.07
6D7R	Tr.Ft.	Quartz,massive, gray. (28cm)	8.0	77	6.4	13.40

* asterisks indicate ppb.

3.2 SILT AND SOIL SAMPLING

A number of soil samples were taken from a wide saddle to the north of the major bend in Iron Creek, and from scattered saddles on the property. No samples returned anomalous values. Soil sampling in 1985 found only sporadic Au anomalies even in areas of known Au mineralization, suggesting that Au is not being reflected in soils. (see Figures 5, 6a).

Silt samples were taken on Iron Creek, and on the creek to the northwest of the VIC claims at 150 m spacing. The creek in the south of the claims was sampled in 1985 with no interesting results.

Iron Creek samples returned surprisingly few anomalous results. Two Au anomalous samples were taken 3 km south of the main trenches, and south of the major bend in Iron Creek. (6M13T-45 ppb Au; 6M14T-30 ppb Au). These anomalies may be due to gold from the Main Zone, or may indicate potential mineralization in the vicinity of the samples.

A "creek" draining the basal Mount Nansen Volcanic contact carried 35 ppb Au (6M4T). Quartz vein float in the area was not anomalous. The possibility of mineralization below the Mount Nansen Volcanics is suggested.

4. GEOPHYSICS SURVEYS

Four geophysical surveys were run over the Main and North Zones to determine their potential usefulness for tracing the mineralization alteration zones and quarz veining.

A resistivity survey was abandoned early due to malfunctioning equipment. Self-potential, VLF-EM and magnetometer surveys were run over much of the existing grid. Results were mixed. The VLF-EM and S.P. surveys did not shed much light on the geology. The magnetometer survey was most useful.

4.1 MAGNETOMETER SURVEY

A total of 11.95 line-km of magnetometer survey was run on lines at 50 m or 100 m spcaing, with readings taken every 12.5 m. The instruments used were 2 EDA Instrumets Ltd., portable field magnetometers, one as a base station, the second as the field magnetometer. Drift corrections are made by the instrument itself, and results printed out with a base value deducted from the total measurements. Total field and gradient were measured. Total field values (TFV) were profiled, and both TFV and gradient were plotted on a 1:2000 plan map and contoured. (Figures 9a-9c).

As the alteration on the Main Zone appears to be magnetite destructive, it was hoped that the magnetometer would read the altered zones as magnetic lows. Results were generally successful.

Several magnetic lows were outlined which correspond with known alteration zones, and in part extend beyond into areas of no outcrop to the east and west.

Unaltered syenite porphyry and rhyodacite dykes have low to moderate magnetic backgrounds. Dacite feldspar porphyry dykes are associated with higher values. Clay alteration zones show the lowest magnetic background.

The overall trend shown by the mag. maps is east-west to northeast-southwest, parallel with dyking and alteration. Magnetic lows are divided into 6 areas on the TFV map:

1) L1550E to 1850E baseline to 100N. A broad zone trends NE and appears to be on strike with a second NE to E-W trending zone at L2150E 125N to L2300E 200N. There is no outcrop in the first of these areas, while the second is in sheeted dacite, rhyodacite and syenite porphyry with some clay alteration.

2) L1200E to L1500E, 200-500N. An area of irregular mag. lows in a grassy depression approximately on strike with alteration and quartz veining at L1700E 250N. However there is no low co-incident with the quartz veining here.

3) Immediately to the north of this last area, alteration zones and veining are co-incident with mag. lows at L1600E 600N and L1700E 400N. A few other lows here are in areas of no outcrop.

4.2 VLF-EM SURVEY

A total of 10.725 line-km of VLF-EM were done on the Main Zone and south of the Main Zone. Instrument used was a Geonics EM-16. Readings were taken at 12.5 km intervals on lines 50m, 100m and 200m apart. Station used was Annapolis, and direction of travel was south. VLF-EM survey techniques are discussed in available literature and will not be covered here. In-phase readings were fraser filtered and profiled (see Figures 11a-p and Appendix 3).

Profiles show numerous small and moderate conductors. The complexity probably reflects the complexity of numerous branching dykes, alteration zones and quartz veins. A few conductors are listed below.

L1400E + 350N - No outcrop. Coincides with a magnetic low.
L1800E + 150N to L1650E + 100N - A complex area of sheeted dyking, clay alteration and quartz veining.
L1600E B.L. to 100S - No outcrop. Probable sheeted dykes.
L1850E 275N-325N - Covers braided dykes and an alteration zone.
L1900E 350N - Alteration zone.
L2000E 350N - Quartz veining and mag. low.
L2000E BL to 100N - No outcrop. Soil clay zone, s.p. conductor.
L2200E to L2150E, 100N - Sheeted dacite porphyry dykes; south of a mag. low and alteration zone.
L2100E 100-150N - Corresponds with clay soil zone and mag. low.

The VLF-EM survey apparently successfully picked up many contacts; too many for easy interpretation.

4.3 SELF-POTENTIAL and RESISTIVITY SURVEYS

A total of 8.920 line-km of self-potential survey was run over the grid. The resisitivity survey was cut short by equipment malfunction. Only 300 line-m of resitivity survey was useable. The survey was run using a rental Scintrex RSP-6 unit. This survey technique is covered in available literature and will not be described here.

Readings obtained were profiled (Figure 10). The surveys were run with the intention of following quartz veining and shear zones. Few outstanding conductors were found. Most peaks were not traceable over a great distance. Four conductors found are as follows:

1) L1600E 075N to L1750E 050N. This coincides with a magnetic low. No outcrop is present, but geology is believed to be sheeted Dacite porphyry dykes in syenite porphyry.

2) L1700E 275N to L1800E 300N. This is 25 m north of ddh 6 and 7, and close to ddh 4, in an area of intense alteration and quartz veining. A high of >100 m V is preceded by fluctuating readings which were impossible to record. The trend is parallel to quartz veining and a massive rhyodacite dyke. The erratic readings here may also be due to the close proximity of a number of drill holes.

3) L2000E 050N to L2100E 025N. A short conductor in an area of no outcrop approximately coincides with an E-W structure on the residual mag. map. Geology is believed to be sheeted Dacite porphyry dykes in syenite porphyry.

The S.P. survey results are not really interpretable, as conductors are in areas of no outcrop, or in questionable areas. The conductors found may be shear zones. Trenching would be necessary to confirm this.

4) In the West of the grid, mag. lows at L2300E to 2400E, 400-500N are co-incident with a break in slope and a wide grassy depression possibly caused by a shear/alteration zone.
5) Magnetic lows at the northmost part of the grid between L1800E and L2200E, 1200N to 1400N may be related to major faulting along Iron Creek. Outcrop to the east of here is of relatively fresh syenite.
6) At L2000E to L2050E, 300-325N (ddh 9 + 16), a small mag. low corresponds with weak to intense clay-hematitie alteration and quartz vein float.

The gradient map was not used for interpretation.

A residual mag. map (Figure 9d) done by J. Wahl of Toronto shows a series of approximately east-west and north-south curving structures. This map is the most useful of the 3 mag. maps, as it shows the best correspondence with quartz veining and alteration. A structure trending from L1700E 250N to L1850E 150N is co-incident with alteration and quartz veining drilled in Area 3 (ddh 6 & 7). This map shows a potential extension of the zone to the east, in an area of no outcrop. Another structure, which is the most continuous on the map approximately corresponds with a series of quartz veins and alteration zones between L1850E 300N and L2100E 250N. (Area 2). The structure is 10m to 75 m north of the veining, as shown on the map, and curves to the northeast towards a break in slope above a wide grassy depression. A third lens shaped structure contains the northernmost known quartz veins and alteration (Area 1) between L1550E 600N and L2150E 400N. The veining is close to the north boundary at the lens-shaped structure and appears to cross-cut it somewhat.

Overall, the magnetometer survey was successful in tracing many of the known quartz veins and alteration zones, and indicates the possibilities of extensions to the east and west of the present grid.

5. DRILLING PROGRAM 1986

5.1 DRILLING

In 1986, two phases of BQ diamond drilling were conducted on the VIC property by Drilcor Industries Ltd. of Delta, B.C. Phase I was completed between June 25 and July 13 and consisted of 9 holes totalling 898.86 meters. Phase II consisted of 10 holes, totalling 695.55 meters, and was drilled between August 25 and September 9. In total, 1594.41 meters were drilled in the 1986 program.

In Phase I, mobilization, on site drill moves, and demobilization were conducted by a Kohmatsu cat and operator contracted from Carmacks, and by a Carmacks based, Trans North, Bell 206 helicopter. In Phase II, a John Deere 350 cat leased from Noranda Exploration, Whitehorse, was utilized in conjunction with the helicopter.

Drill holes on the property were consecutively numbered, as drilled, from YV 86-01 to YV 86-19. All holes, except holes 3 and 19, were located by transit and steel chain in relation to several survey stations, and were given survey coordinates. Holes 3 and 19 were tied into the compass grid located on the property.

All drill core was logged, split, and sampled by Kerr Addison personnel.

Samples were sent to Chemex Labs Ltd., North Vancouver, B.C for analysis.

The core from holes 4 to 9 was transported to Carmacks for storage while the remainder is stored on the property at four separate locations.

Phase II had to be cut somewhat short because of a blizzard and concurrent water supply freeze-up.

The primary targets of drilling were source quartz veins for the abundant, highly anomalous quartz float found throughout the trenched area and extensions of quartz veins outcropping in many trenches.

Mineralized areas intersected are summarized below:

AREA	INTERSECTION	SAMPLE LENGTH	ASSAYS g/t(oz/t)	REMARKS
Area 1				
Hole 1	1.15m silic. zone	1.15m	12.07 (0.35)	
17	50cm quartz vein	50cm	33.1 (0.97)	2m apart
	40cm quartz vein	40cm	11.4 (0.33)	-following RD dyke
18	10cm quartz vein	70cm	13.44(0.39	-50m west of Hole 17

Area 2

Trench	7	40cm quartz vein		23.3 (0.68)	-surface sample
Hole	6	40cm quartz vein	40cm	35.8 (1.04)	-8m downdip of sfc.
	7	1m qz-feld.zone	1m	18.4 (0.54)	-13m downdip of sfc.
		altered syenite	1m	4.66 (0.14)	-adjacent to preceding sample
	5	30cm quartz m.	30cm	n.d.	
		altered syenite	1m	3.4 (0.1)	-adjacent to preceding qz. vn.

Area 3

Hole	9	40cm quartz vein	40cm	17.8 (0.52)	-20m downdip of surface.
	13	40cm qz-carb-feld.	40cm	10.8 (0.32)	-30cm apart, 37m
		65cm qz-carb-feld.	65cm	n.d.	downdip of sfc.
	14	80cm qz-bx zone	80cm	n.d.	-72m downdup from surface.
	15	2.5m silicified zone with variable qz.vns.	2.6m	av.0.37(0.01)	-50m west of Hole 13.
	16	1.10m qz-shear zone	1.10m	av.0.31(0.01)	-50m east of Hole 13.
	8	25cm quartz vein		0.82 (0.02)	

Profiles and geochemical analyses are shown in Figures 13 a to

Drilling indicated that the quartz veins are discontinuous but that alteration zones have more continuity.

High values intersected in quartz veining in holes 1 and 17 indicates that the northmost quartz veining continues to the east of its durface expression.

Quartz veining in Trench 7 (L1750E 225N) was found to be cut off by a dacite feldspar porphyry dyke, showing that at least some mineralization was previous to the dacite porphyry dyking. The veins continue on the east of this dyke as indicated by float.

A third area of veining was intersected in several holes. Two short holes (ddh 2 and 3) drilled in the North Zone did not intersect mineralization or quartz veining. Hole 3 apparently missed a short S.P.conductor

TABLE 2

VIC - 1986 DRILL HOLE DETAILS

	HOLE #	LAT.	DEP.	ELEV.	DIP	AZ.	DEPTH(M)	DATES
	YV-86-01	506.1	2126.6	1617.1	-45	160°	149.96	June 25-29
	86-02	762.8	2100	1575.9	-49	160°	136.25	June 29-July 2
	86-03*	9+00N	20+78E		-47	160°	107.59	July 2-4
	86-04	290.4	1732.1	1644.5	-48	146°	173.74	July 5-8
	86-05	194.3	1692.1	1641.1	-47	343°	140.21	July 8-10
	86-06	250.3	1744.4	1643.1	-47	326°	48.77	July 10-11
PHASE I	86-07	249.7	1744.6	1643.6	-74	326°	14.63	July 11
	86-08	349.5	2063.5	1645.1	-47	160°	63.70	July 11-12
	86-09	297.4	1998	1652.0	-45	340°	64.01	July 12-13
	86-10	224.1	1741.5	1644.6	-54	338°	57.30	Aug. 25-28
	86-11	236.1	1654.1	1638.6	-46	336°	67.97	Aug. 28-29
	86-12	200.3	1786.9	1645.1	-45	339°	67.36	Aug. 29-30
	86-13	272.3	1997.5	1653.7	-46	340°	55.17	Aug. 30-31
	86-14	222.8	1998	1656.3	-48	340°	82.30	Aug. 31-Sept. 1
	86-15	271.4	1947.8	1655.7	-47	340°	60.35	Sept. 1-2
PHASE II	86-16	274.5	2047.6	1653.6	-47	340°	75.59	Sept. 2-3
	86-17	413.0	2125.2	1634.3	-47	340°	115.21	Sept. 4-6
	86-18	415.3	2070.9	1635.7	-47	340°	76.81	Sept. 7-8
	86-19*	4+15N	21+75E		-46	340°	37.49	Sept. 8-9
							1594.41 m	

* Not surveyed - compass grid coordinates given.

5.2 TRANSIT SURVEY

Drill hole locations were determined by transit and steel chain relating holes to 12 established survey stations. All survey stations and holes (except 3 and 19) have metric co-ordinates relative to survey grid origin 350N, 2100E (3+50N, 21+00E of pre-existing compass-hipchain grid). Holes 3 and 19 were not surveyed thus have compass-hipchain grid co-ordinates. Transit survey co-ordinate calculations were based on line 21+00E being used as grid north.

Drill hole coordinates given on drill logs and drill sections are transit survey coordinates (except 3 and 19).

6. CONCLUSIONS AND RECOMMENDATIONS

Work in 1985 and 1986 found Au-Ag mineralization to be associated with east-west to northeast trending alteration zones and lensy quartz veins, over an area 700 m x 1 km (including areas of mineralized float). Most mineralization is in the quartz, but locally extends into the clay altered host rocks. Quartz veining is grouped into 3 main areas -

1) L1500E 550N to L2150E 450N;
2) L1850E 325N to L2100E 275N;
3) L1550E 275N to L1800 175N.

Drilling of these areas located downdip extensions of some alteration and quartz veining in areas 1 and 2, but found that the veining in area 3 to be at least partly cut off by dacite porphyry dyking. The style of alteration and quartz veining suggests that the veins are perhaps in the upper reaches of an epithermal system, below major silicification and above sulphide ore. This gives the possibility of mineralization at some depth below the present surface, and also along strike to the northeast and west.

Of 3 geophysics surveys run, only the magnetometer was really useful. The Self-potential survey didn't seem to pick up much, while the VLF-EM survey appeared to pick up most of the numerous contacts making interpretation difficult.

Four areas of future interest were found:

1) L1400E 350N to 400N (mag.low, on line with known Au-bearing quartz veins and alteration).
2) L1650E 050N (extension of alteration zones; mag low; S.P. Conductor).
3) L2400E 400N to 500N (mag.low; residual mag. trend; soil clay and Au anomalies; Au bearing float in grassy depression - a possible alteration/shear zone)
4) L2200E 800N (S.P. conductors, above and in North Zone).

Areas to the east of 3) and to the west of 1) are also of interest.

A follow -up program consisting of an extended magnetometer survey followed by trenching on the above areas is recommended. Alteration and mineralogy studies of the quartz may be helpful in deducing the potential for ore below the present surface. Any targets generated by this should be drilled.

A more detailed follow-up of scattered anomalies found elsewhere on the property is needed. This covers mainly the West VIC claims, northwest of the VIC claims and south of Victoria Peak.

REFERENCES

Bostock, M.A; 1936. Carmacks District, Yukon Territory. G. S. C. Memoir 189.

Campbell (of Dolmage Campbell and Assoc.(1975))1982. Feasibility Report on the Mount Nansen Mine.

Kerr Addison Mines Ltd. Internal Reports:
VIC claims target report, 1985. L. Grexton, J. Pautler
B.C. Yukon 1985 Summary Report. D. Arscott
1985 Yukon Au-Ag Regional Report. L. Grexton, J. Pautler
1985 Program Report on VIC and VG claims; Dec. 5, 1985.
C. Baldys and D. Arscott.
Mt. Nansen Area structural study, 1984. D. Arscott.

Saager, R., and Bianconi, F; 1971. The Mount Nansen Gold-Silver Deposit, Yukon Territory, Canada. In Mineralia Deposita (Berl)6,209-224 (1971).

Sawyer, J.P.B. and Dickinson, R.A.; 1976. Mount Nansen. In CIM sp. vol. 15, part B. Porphyry Copper and Copper-Molybdenum Deposits of the Calc-Alkalie Suite - Paper 34.

Tempelman-Kluit, D, 1984. Carmacks, Yukon Territory . G.S.C. Open File 1101.

1974. Carmacks, YUukon Territory, G.S.C. Open File 200.

1986 PROGRAM COSTS

Labour (days)	Office	Field	Travel	Total
D. Arscott, Geologist 2275 W. 20th Ave. Vancouver, B.C.	6	20	3	29
K. Heberlein, Geologist 821 Pinemont Ave Pt. Coquitlam, B.C.	5	62	4	71
L. Lyons, Geologist 3685 W. 11th Ave. Vancouver, B.C.	2	53	4	59
R. Potter, Geologist R R #1, Fulford Harbour, B.C.	2	24	4	30
M. Allen, Assistant Whitehorse, Y.T.	-	45	3	48
	15	204	18	237

Total wages equivalent to $125/person day			$29,625.
Meals, accommodation, field and camp supplies			12,500.
Helicopter			24,600.
Ground Transportation			9,000.
Contract Drilling — Drilcor Ind. Ltd. 17-7449 Hume Ave. Tilbury Ind. Park Delta, B.C. V6G 1C3			
Coring 5231 ft. BQ x $18.50/ft	$96,774.		
Materials, camp, field labour, mob-demob	52,620.		
			149,394
Samples — Chemex Labs Ltd. 212 Brooksbank Ave North Vancouver, B.C.			
667 core , rock, soil and silt samples.			
Average $14/sample (assay grade)	$13,340		
Shipping @$2.60/sample	1,700.		
			15,040.
Radio, expediting, telephone			8,000
Total Direct Program Cost			$ 248,159.

SYMBOLS & ABBREVIATIONS

Outcrop		R.	Rhyolite	a.	Altered
Talus, subcrop, felsenmeer		D.	Dacite	q.	Quartz
Grid line		A.	Andesite	vn.	Vein
Trench		B.	Basalt	str.	Stringer
Cat trail		Amph.	Amphibolite	fract.	Fracture
Silt sample	x	QM.	Quartz Monzonite	cal.	Calcite
Soil "	•	S.	Syenite	xc.	Cross cutting
Rock " (outcrop)	o	G.	Granite	L.	Limonitic
Rock " (float)	△	GDi.	Granodiorite	bx.	Breccia
Diamond drill hole collar	○			cxcm.	Coxcomb
Geological contact		p.	Porphyritic	cl.	Clay
Fault, shear		sil.	Silicified	arg.	Argillite
Strike & dip - contact or bedding		chl.	Chlorite	ep.	Epidote
" & " - fractures		K+	Potassic	ser.	Sericite
" & " - foliation		py.	Pyrite	prop.	Propylitic
		hem.	Hematite	Mn.	Manganese
		equigr.	Equigranular	w.	Weak
				m.	Moderate
				s.	Strong
				i.	Intense

GEOLOGY

MID CRETACEOUS

MOUNT NANSEN GROUP

D.t. — Dacite to Rhyodacite, fine grained ? tuffs, lapilli tuffs, tuff-breccias and minor porphyries; grey-green. Sub rounded to angular fragments to 20 cm., average 2 to 4 cm. Fragment composition usually identical to matrix, but also see rare altered granitic intrusive and greyer felsic fragments.

RD.f.(q.)p — Rhyodacite feldspar ± quartz porphyry. Dykes and flows varies from Rhyolitic in the North to Andesitic in the Southeast claims. Square feldspar crystals to 2 mm average, from 10 to 45 % (in MAIN ZONE). Quartz crystals to 2 to 3 mm are rare to 7% maximum. Grades to Quartz Monzonite.

RD. — Rhyodacite dykes: massive, very fine to medium grained. Fresh surface is white to light grey to light green or pinkish. Weathers white to buff, recessive; common clay ± sericite alteration and Mn., dendrites on fractures. Pyrite to 5 %. Strong flow banding at contacts.

CRETACEOUS ?

CASINO GRANODIORITE ?

bio.GDi. — Biotite ± hornblende Granodiorite, grey to orange grey weathered. Equigranular, medium to coarse grained (1 to 3 mm), massive; relatively fresh looking. Biotite = 10 to 15 % (2 mm), hornblende = 2 % (2 mm), quartz = 15 %, K-feldspar = plagioclase.

bio.QM. — Biotite Granodiorite to Quartz Monzonite: mottled off-white and black to orange; medium grained. Biotite to 0.5 mm = 15 %. K-feldspar crystals to 3 mm, weakly porphyritic, 5 %. Feldspar = 65 %, quartz = 15 %. Strongly cleaved to foliated throughout. Weathers to gravel.

hb.R. — Hornblende Rhyolite porphyry: very fine grained, dense, hard, dark medium grey matrix with euhedral hornblende crystals to 4 mm, 7 to 10 % total, strongly magnetic.

B-A. — Basalt - Andesite, dark green, massive, fine to medium grained.

JURASSIC

BIG CREEK SYENITE ?

S.p. — K-feldspar hornblende Syenite to Granite porphyry: medium grained equigranular to coarsely porphyritic with K-feldspar megacrysts to 6 cm (average 2 cm) = 20 %; hornblende crystals to 1.5 cm (average 4 mm) = 70 % locally; quartz crystals rounded 5 to 12 %.

PRE-CAMBRIAN TO PROTEROZOIC

YUKON GROUP

Gn. — Feldspar quartz hornblende Gneiss: fine to coarse grained, poorly to well banded; varies from predominantly quartz to feldspar with bands of coarse amphibolite. Minor quartz - K-feldspar pegmatite.

FIG. 5

0 50 100 200 300 400
METERS

KERR ADDISON MINES LTD

VIC CLAIMS (WEST)

GEOLOGY 091907
SAMPLE LOCATIONS
GEOCHEMISTRY

SCALE - 1 : 5000	DATE - NOVEMBER, 1986
DRAWN BY - P.H.	DATA - K.H.
NTS - 115 I/3	REVISED -

SYMBOLS & ABBREVIATIONS

- Outcrop
- Talus, subcrop, felsenmeer
- Grid line
- Trench
- Cat trail
- X Silt sample
- Soil "
- Rock " (outcrop)
- Rock " (float)
- Diamond drill hole collar
- Geological contact
- Fault, shear
- Strike & dip – contact or bedding
- " & " – fractures
- " & " – foliation

R.	Rhyolite	q.	Quartz
D.	Dacite	vn.	Vein
A.	Andesite	str.	Stringer
B.	Basalt	fract.	Fracture
Amph.	Amphibolite	cal.	Calcite
QM.	Quartz Monzonite	xc.	Cross cutting
S.	Syenite	L.	Limonitic
G.	Granite	bx.	Breccia
GDI.	Granodiorite	cxcm.	Coxcomb
p.	Porphyritic	cl.	Clay
sil.	Silicified	arg.	Argillite
chl.	Chlorite	ep.	Epidote
K+	Potassic	ser.	Sericite
py.	Pyrite	prop.	Propylitic
hem.	Hematite	Mn.	Manganese
equigr.	Equigranular	w.	Weak
		m.	Moderate
		s.	Strong
		i.	Intense

GEOLOGY

MID CRETACEOUS

MOUNT NANSEN GROUP

D.f. — Dacite to Rhyodacite, fine grained ? tuffs, lapilli tuffs, tuff-breccias and minor porphyries; grey-green. Sub rounded to angular fragments to 20 cm., average 2 to 4 cm. Fragment composition usually identical to matrix, but also see rare altered granitic intrusive and greyer felsic fragments.

RD.f.(q.)p — Rhyodacite feldspar ± quartz porphyry. Dykes and flows varies from Rhyolitic in the North to Andesitic in the Southeast claims. Square feldspar crystals to 2 mm average, from 10 to 45 % (in MAIN ZONE). Quartz crystals to 2 to 3 mm are rare to 7 % maximum. Grades to Quartz Monzonite.

RD. — Rhyodacite dykes: massive, very fine to medium grained. Fresh surface is white to light grey to light green or pinkish. Weathers white to strong limonitic washed, recessive; common clay ± sericite alteration and Mn. dendrites on fractures. Pyrite to 5 %. Strong flow banding at contacts.

CRETACEOUS ?

CASINO GRANODIORITE ?

bio.GDI. — Biotite ± hornblende Granodiorite, grey to orange grey weathered. Equigranular, medium to coarse grained (1 to 3 mm), massive; relatively fresh looking. Biotite = 10 to 15 % (2 mm), hornblende ± 2 % (2 mm), quartz = 15 %, K-feldspar = plagioclase.

bio.QM. — Biotite Granodiorite to Quartz Monzonite: mottled off-white and black to orange; medium grained. Biotite to 0.5 mm, = 15 %. K-feldspar crystals to 3 mm, weakly porphyritic, 5 %. Feldspar = 65 %, quartz = 15 %. Strongly cleaved to foliated throughout. Weathers to gravel.

hb.R. — Hornblende Rhyolite porphyry: very fine grained, dense, hard, dark medium-grey matrix with euhedral hornblende crystals to 4 mm, 7 to 10 % total, strongly magnetic.

B. – A. — Basalt – Andesite, dark green, massive, fine to medium grained.

JURASSIC

BIG CREEK SYENITE ?

S.p. — K-feldspar hornblende Syenite to Granite porphyry: medium grained equigranular to coarsely porphyritic with K-feldspar megacrysts to 6 cm (average 2 cm) = 20 %, hornblende crystals to 1.5 cm (average 4 mm) = 70 % locally; quartz crystals rounded, 5 to 12 %

PRE-CAMBRIAN TO PROTEROZOIC

YUKON GROUP

Gn. — Feldspar quartz hornblende Gneiss: fine to coarse grained, poorly to well banded; varies from predominantly quartz to feldspar with bands of coarse amphibolite. Minor quartz K-feldspar pegmatite.

FIG. 6a

0 50 100 150 200 300 400
METERS

KERR ADDISON MINES LTD
VIC CLAIMS
GEOLOGY & SAMPLE LOCATIONS

SCALE – 1 : 5000	DATE – NOVEMBER, 1985
DRAWN BY – P.H., C.B.	DATA – C.B., L.L., J.P., L.G.
NTS – 115 I 3	REVISED –



△ Float grab sample. 0.3 oz/t Au (in grid)

× Stream sample.

49 Au (ppb) in soil
Ag (ppm), As (ppm), Sb (ppm), Au (ppb)

Trench

FIG. 6b

KERR ADDISON MINES LTD

VIC CLAIMS

GEOCHEMISTRY

091907

SCALE - 1 : 5,000	DATE - NOVEMBER, 1985
DRAWN BY - P.H., C.B.	DATA - C.B., L.L., J.P., L.G.
NTS - 115 I 3	REVISED - DEC., 1986

L14E L16E L17E L18E L19E L20E L21E L22E L24E L26E

1400N 1300N 1200N 1100N 1000N 900N 800N 700N 600N 500N 400N 300N 200N 100N

B.L. (070°)

L15E L15+50E L16+50E L17+50E L18+50E L19+50E L20+50E L21+50E L23E

VIC 22 □
Post No. 2

hb. K-f. S.p.

YV86-3

Mainly S.p. talus

D.f.p.

S., G.

A.dy.

S.p.

YV86-2

YV86-1

YV86-19

YV86-17

YV86-16

YV86-8

YV86-9

YV86-4

YV86-6, 86-7

YV86-11

YV86-10

YV86-5

YV86-15

YV86-13

YV86-14

B.-A.dy.

QM.-D.f.

B.-A.

QM.

B.

edge of ridge

Ridge centre

(R)D.f.p.

S. + RD.f.p.

Talus slope

S. + RD.q.f.p.

S. + G.p. + (R)D.f. + B.-A.

S., RD.f.p.

S.p., (R) D.f.p.

S. + G.p. + (R)D.f. + B.-A.

S., hb. QM., GDi., q.f.p. RD. rubble.

LEGEND

MID-CRETACEOUS

MOUNT NANSEN GROUP

D.f.p. — Dacite to Rhyodacite feldspar porphyry to Quartz-Monzonite : dark grey matrix, crowded feldspar porphyry, blocky weathering.

RD.L. — Rhyodacite : fine grained, massive with rare feldspar crystals, white, pink, buff & pale green. Fracture surfaces strongly limonitic, with Mn. dendrites. Contacts strongly banded.

CRETACEOUS

B.-A. — Basalt – Andesite : fine to medium grained, dark grey-green massive dykes.

JURASSIC

BIG CREEK SYENITE

S. — Hornblende K-feldspar to Granite porphyry to equigranular. Bands of Hornblendite to 30 cm. thick. K-feldspar crystals to 3 cm, 20 %.

Grid line	R.	Rhyolite	q.	Quartz
Drill hole	D.	Dacite	vn.	Vein
Trench	A.	Andesite	f.	Feldspar
Outcrop	B.	Basalt	p.	Porphyry
Talus / subcrop	QM.	Quartz Monzonite	L.	Limonitic
Strike & dip, banding / contact			S.	Syenite
" & ", foliation			GDi.	Granodiorite
" & ", fractures			hb.	Hornblende
Fault / shear zone.				
Geological contact (approx., assumed)				

FIG. 7a

0 50 100
metres

KERR ADDISON MINES LTD

VIC CLAIMS

MAIN (WAR) ZONE

GEOLOGY

091907

SCALE 1: 2000	DATE Oct. 1986, JANUARY 1987
DRAWN BY - K.H., P.H.	DATA - K.H.
N.T.S. 115 I / 3	REVISED



FIG. 7b

0 50 100
metres

KERR ADDISON MINES LTD

VIC CLAIMS
MAIN (WAR) ZONE

SAMPLE LOCATIONS
GEOCHEMISTRY
091907

SCALE 1: 2000	DATE Oct. 1986, JANUARY 1987
DRAWN BY K.H., P.H.	DATA - K.H.
N.T.S. 115 I/3	REVISED

SYMBOLS & ABBREVIATIONS

Grid lines	R.	Rhyolite	q.	Quartz
Drill hole	D.	Dacite	cal.	Calcite
Trench	A.	Andesite	carb.	Carbonate
Outcrop	B.	Basalt	vn.	Vein
Talus / subcrop	QM.	Quartz Monzonite	str.	Stringer
Strike & dip, banding / contact	S.	Syenite	cx.cm.	Coxcomb
" & " , foliation	G.	Granite	bx.	Breccia
" & " , fractures	Amp.	Amphibolite	xc.	Cross cutting
Fault / shear zone	p.	Porphyry (-itic)	py.	Pyrite
Geological contact (approx., assumed)	L.	Limonitic	fr.	Fracture
	chl.	Chlorite	a.	Alteration
	epid.	Epidote	w. m. s. i.	Weak moderate strong intense
	K⁺.	Potassic	cl.	Clay
	fel.	Feldspar	sil.	Siliceous
	hem.	Hematite	ser.	Sericite

LEGEND

D.f.p. — Dacite to Rhyodacite feldspar porphyry to Quartz-Monzonite dark grey matrix, crowded feldspar porphyry, blocky weathering.

RDL. — Rhyodacite – fine grained, massive with rare feldspar crystals, white, pink, buff, pale green. Fracture surfaces strongly limonitic with Mn dendrites. Contacts strongly banded.

(B) A. — (Basalt) Andesite – fine to medium grained, dark grey-green massive dykes.

S. — Hornblende K-feldspar to Granite porphyry to equigranular. Bands of Hornblendite to 30 cm. thick. K-feldspar crystals to 3 cm., 20%.

FIG. 8a

0 5 10 20 30 40
METERS

KERR ADDISON MINES LTD

VIC CLAIMS
MAIN (WAR) ZONE

GEOLOGY
SAMPLE LOCATIONS

091907

SCALE: 1:500	DATE: OCT 1986
DRAWN BY: K.H., P.H.	DATA: K.H.
N.T.S. 115 I/3	REVISED:



Ag (gm/t), Au (gm/t), As (ppm), Sb (ppm).

FIG. 8b

0 5 10 20 30 40
METERS

KERR ADDISON MINES LTD

VIC CLAIMS
MAIN (WAR) ZONE

GEOCHEMISTRY

091907

SCALE: 1:500	DATE: OCT. 1986
DRAWN BY: KH, P.H.	DATA: K.H.
N.T.S. 115 I/3	REVISED:

L 15+00 E

L 15+50 E

L 16+00 E

L 16+50 E

L 17+00 E

L 17+50 E

L 18+00 E

L 18+50 E

L 19+00 E

L 19+50 E

L 20+00 E

L 20+50 E

L 21+00 E

L 21+50 E

L 22+00 E

L 23+00 E

L 24+00 E

1000 Gammas
900 "
800 "
700 "
600 "
500 "
400 "
300 "

1100 Gammas
1000 "
900 "
800 "
700 "
600 "
500 "
400 "
300 "

B.L. 1N 2N 3N 4N 5N 6N 7N 8N 9N 10N 11N 12N 13N 14N 15N 16N 17N 18N

FIG. 9a

0 10 20 40 60 100 150
METERS

KERR ADDISON MINES LTD

VIC CLAIMS

MAGNETOMETER SURVEY

PROFILES

09-907

SCALE - 1:2000	DATE - OCTOBER, 1986
DRAWN BY - P.H.	DATA - K.H., M.A., B.P., L.L.
NTS - 115 I/3	REVISED -

L14E L16E L17E L18E L19E L20E L21E L22E L24E L26E

1400N 1300N 1200N 1100N 1000N 900N 800N 700N 600N 500N 400N 300N 200N 100N

B.L. (070°)

L15E L15+50E L16+50E L17+50E L18+50E L19+50E L20+50E L21+50E L23E

VIC 22
Post No. 2

LEGEND

0 - 200	Gammas
200 - 400	"
400 - 600	"
600 - 800	"
800 - 1000	"
>1000	"

NOTE - Base value deducted = 57500 Gammas

FIG. 9b

0 50 100
metres

KERR ADDISON MINES

VIC CLAIMS
YUKON TERRITORY

MAIN (WAR) ZONE 091907

MAGNETOMETER- SURVEY

TOTAL FIELD VALUE

SCALE 1" 200'	DATE Oct 1988
DRAWN BY - K.H., P.H.	DATA - K.H.
N.T.S. 115 I/5	REVISED

L14E L16E L17E L18E L19E L20E L21E L22E L24E L26E

1400N 1300N 1200N 1100N 1000N 900N 800N 700N 600N 500N 400N 300N 200N 100N

B.L. (070°)

L12E L14E L15E L15+50E L16+50E L17+50E L18+50E L19+50E L20+50E L21+50E L23E

VIC 22 □
Post No. 2

LEGEND

< - 60	Gammas
-40 - 60	"
-20 - 40	"
0 - 20	"
0 + 20	"
+20 +40	"
+40 +60	"
> + 60	"

FIG. 9c

0 50 100
metres

KERR ADDISON MINES

VIC CLAIMS
YUKON TERRITORY

MAIN (WAR) ZONE
MAGNETOMETER SURVEY
GRADIENT 091907

SCALE 1: 2000	DATE Oct. 1986
DRAWN BY K.H.	DATA
N.T.S. 115 I/3	REVISED

L2200E

L2150E

L2100E

L2000E

L1900E

L1800E

ERRATIC READINGS

L1750E

ERRATIC READINGS

L1700E

L1600E

L1500E

40 mV

20 mV

0

L1400E

-20 mV

-40 mV

-446

1000N 900N 800N 700N 600N 500N 400N 300N 200N 100N B.L.

FIG. 10

KERR ADDISON MINES LTD.

VIC CLAIMS
YUKON TERRITORY

SELF-POTENTIAL SURVEY
PROFILES 091907
091908

SCALE 1:2000	DATE: NOV 1986
DRAWN BY K.H.	DATA: K.H, M.A., D.A.
N.T.S 115 I/3	REVISED:



B – B´

SECTION 160°, ~2120 E - LOOKING EAST

A – A´

SECTION 160°, ~2126 E - LOOKING EAST

LEGEND

RD.	Rhyodacite.		
D.	Dacite.		
A.	Andesite.		
S.	Syenite.		
Amp.	Amphibolite.		
q.	Quartz.		
carb.	Carbonate.		
f., fel.	Feldspar.	i.	Intense.
hem.	Hematite.	loc.	Local.
bx.	Breccia.	var.	Variably.
O.B.	Overburden.	p.	Porphyritic.
dy.	Dyke	shr.	Shear(ed).
vn.	Vein.	sil.	Silicified.
str.	Stringer.	weath.	Weathered.
stwk.	Stockwork.	a.	Altered.

—·—·— Contact - approximate, inferred.

Sample section:

(sample number)	Ag - gm/T	Au - gm/T	(sample number)
YV1510	0.3	0.14	YV1510



C – C´

SECTION 160°, 2070.9 E - LOOKING EAST

FIG. 12a

0 10 20 30 40
METRES

KERR ADDISON MINES LTD

VIC CLAIMS

DIAMOND DRILLING SECTIONS - A, B, C

SCALE - 1:500	DATE - OCTOBER 1986
DRAWN BY - L. LYONS	DATA - L. LYONS
NTS - 115 I/3	REVISED -

091907



D – D′

SECTION 160°, ~2100 E – LOOKING EAST

LEGEND

RD.	Rhyodacite.
D.	Dacite.
A.	Andesite.
S.	Syenite.
Amp.	Amphibolite.

q.	Quartz.		
carb.	Carbonate.		
f., fel.	Feldspar.	i.	Intense.
hem.	Hematite.	loc.	Local.
bx.	Breccia.	var.	Variably.
O.B.	Overburden.	p.	Porphyritic.
dy.	Dyke	shr.	Shear(ed).
vn.	Vein.	sil.	Silicified.
str.	Stringer.	weath.	Weathered.
stwk.	Stockwork.	a.	Altered.

—·—··— Contact – approximate, inferred.

Sample section:

(sample number) Ag – gm/T, Au – gm/T (sample number).

YV1510 0.3 0.14 YV1510

Ag, Au — g/T

FIG. 12b

0 10 20 30 40

METRES

KERR ADDISON MINES LTD

VIC CLAIMS

DIAMOND DRILLING

SECTION – D

091907

SCALE – 1:500	DATE – OCTOBER 1986
DRAWN BY – L.L.	DATA – L.L.
NTS – 115 1/3	REVISED –

DDH YV 86-08
Dip - 47°, Brg. 160°



E - E´

SECTION 160°, 2063.5 E - LOOKING EAST

DDH YV 86-16
Dip - 47°, Brg. 340°



F - F´

SECTION 160°, 2047.6 E - LOOKING EAST

DDH YV 86-09
Dip - 45°, Brg. 340°

DDH YV 86-13
Dip - 46°, Brg. 340°

DDH YV 86-14
Dip - 48°, Brg. 340°



G - G´

SECTION 160°, ~ 2000E - LOOKING EAST

LEGEND

RD.	Rhyodacite.
D.	Dacite.
A.	Andesite.
S.	Syenite.
Amp.	Amphibolite.

q.	Quartz.		
carb.	Carbonate.		
f., fel.	Feldspar.	i.	Intense.
hem.	Hematite.	loc.	Local.
bx.	Breccia.	var.	Variably.
O.B.	Overburden.	p.	Porphyritic.
dy.	Dyke	shr.	Shear(ed).
vn.	Vein.	sil.	Silicified.
str.	Stringer.	weath.	Weathered.
stwk.	Stockwork.	a.	Altered.

Contact - approximate, inferred.

Sample section:

(sample number) Ag - gm/T, Au - gm/T (sample number).

YV1510 0.3 0.14 YV1510

DDH YV 86-15
Dip - 47°, Brg. 340°



H - H´

SECTION 160°, 1947.8E - LOOKING EAST

FIG. 12c

0 10 20 30 40
METRES

KERR ADDISON MINES LTD

VIC CLAIMS

DIAMOND DRILLING

SECTIONS - E, F, G, H

091907

SCALE - 1:500	DATE - OCTOBER 1986
DRAWN BY - L. LYONS	DATA - B.P., K.H., L.L.
NTS - 115 1/3	REVISED -



LEGEND

RD.	Rhyodacite.
D.	Dacite.
A.	Andesite.
S.	Syenite.
Amp.	Amphibolite.

q.	Quartz.		
carb.	Carbonate.		
f., fel.	Feldspar.	i.	Intense.
hem.	Hematite.	loc.	Local.
bx.	Breccia.	var.	Variably.
O.B.	Overburden.	p.	Porphyritic.
dy.	Dyke	shr.	Shear(ed).
vn.	Vein.	sil.	Silicified.
str.	Stringer.	weath.	Weathered.
stwk.	Stockwork.	a.	Altered.

Contact - approximate, inferred.

Sample section:

(sample number) Ag - gm/T, Au - gm/T (sample number).

YV1510 0.3 0.14 YV1510

ASSAYS

YV 86-06

	Ag	Au
YV0601	1.3	0.14
02	1.0	1.03
03	<0.3	0.21
04	0.5	0.14
05	0.3	0.07
06	0.3	0.48
07	13.8	35.8
08	0.5	0.31
09	0.3	<0.07
10	<0.3	<0.07
11	0.3	<0.07
12	0.3	<0.07
13	0.5	<0.07
14	0.5	0.07
15	2.3	1.10
16	0.3	0.27
17	<0.3	<0.07
18	<0.3	<0.07
19	<0.3	<0.07
20	<0.3	<0.07
21	<0.3	<0.07
22	<0.3	<0.07
23	<0.3	<0.07
24	<0.3	0.07
25	0.5	<0.07
26	0.5	<0.07

YV 86-07

	Ag	Au
YV0701	0.5	<0.07
02	0.3	0.07
03	<0.3	0.07
04	<0.3	0.14
05	<0.3	0.07
06	<0.3	0.14
07	1.7	2.47
08	0.5	0.14
09	0.5	0.82
10	<0.3	0.07
11	0.8	4.66
12	4.4	18.4
13	0.3	0.21
14	0.3	0.07
15	0.3	0.07

I - I´

SECTION 159°, ~1787E - LOOKING EAST

J - J´

SECTION ~ 146°, ~1741E - LOOKING EAST

K - K´

SECTION 163°, ~ 1693E - LOOKING EAST

L - L´

SECTION 156°, ~1654E - LOOKING EAST

FIG. 12d

0 10 20 30 40

METRES

KERR ADDISON MINES LTD

VIC CLAIMS

DIAMOND DRILLING

SECTIONS - I, J, K, L

SCALE - 1 500	DATE - OCT. 1986
DRAWN BY - L.L.	DATA - L.L., B.P.
NTS - 115 1/3	REVISED -

APPENDIX I

GEOCHEMICAL AND ASSAY RESULT SHEETS

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1
Phone: (604) 984-0221
Telex: 043-52597

JUN 27 1986

KERR ADDISON MINES LTD.

PER

CERTIFICATE OF ANALYSIS

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CC: K. HEBERLEIN

FILE COPY DO NOT REMOVE

CERT. # : A8613878-001-A
INVOICE # : I8613878
DATE : 26-JUN-86
P.O. # : NONE
Y-11

Sample description	Prep code	Ag ppm Aqua R	AS ppm	Sb ppm	Au ppb FA+AA		
~~YD-6K1R~~	~~207~~	~~0.1~~	~~23~~	~~1.2~~	~~370~~	--	--
YV-6K1R	207	0.1	6	0.8	460	--	--
YV-6K2R	207	0.1	9	1.2	140	--	--

VOI rev. 4/85

Certified by Hawk Richter

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1
Phone: (604) 984-0221
Telex: 043-52597

RECEIVED
JUN 26 1986
KERR ADDISON MINES LTD.
COPY

CERTIFICATE OF ANALYSIS

COPY
DO NOT REMOVE

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CC: K. HERBERLEIN

CERT. # : A8613877-001-A
INVOICE # : I8613877
DATE : 25-JUN-86
P.O. # : NONE
Y-11

Sample description	Prep code	Ag ppm Aqua R	AS ppm	Sb ppm	Au ppb FA+AA		
~~YD-6K1S~~	~~201~~	~~0.5~~	~~140~~	~~10.2~~	~~35~~	--	--
~~YD-6K2S~~	~~201~~	~~0.3~~	~~2000~~	~~19.4~~	~~30~~	--	--
YV-6K1T	201	0.2	27	0.8	<5	--	--
YV-6K2T	201	0.1	10	0.6	<5	--	--

VOI rev. 4/85

Certified by Ian Bichler .....

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1
Phone: (604) 984-0221
Telex: 043-52597

JUL 24 1986

PER

CERTIFICATE OF ANALYSIS

FILE COPY DO NOT REMOVE

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CERT. # : A8614241-001-A
INVOICE # : I8614241
DATE : 7-JUL-86
P.O. # : NONE
Y11

CC: K. HEBERLEIN

Sample description	Prep code	Ag ppm Aqua R	AS ppm	Sb ppm	Au ppb FA+AA		
YV-6K03R	205	0.1	3	0.1	190	--	--
YV-6K04R	205	0.1	3	0.2	5	--	--
YV-6K05R	205	0.1	2	0.6	10	--	--
YV-6K06R	205	0.1	15	2.2	<5	--	--
YV-6K07R	205	0.1	3	0.4	<5	--	--
YV-6K08R	205	0.1	3	0.1	<5	--	--
YV-6K09R	205	0.1	41	1.6	<5	--	--
YV-6K10R	205	0.2	4	0.4	<5	--	--
YV-6K11R	205	0.1	3	0.2	<5	--	--
YV-6K12R	205	0.1	11	8.2	<5	--	--
YV-6K13R	205	0.1	4	1.6	<5	--	--
YV-6K14R	205	0.1	6	1.2	<5	--	--
YV-6K15R	205	0.1	3	0.6	<5	--	--
YV-6K16R	205	0.1	3	0.6	<5	--	--
YV-6K17R	205	0.1	4	4.4	<5	--	--
YV-6K18R	205	0.1	4	1.0	<5	--	--
YV-6K19R	205	0.1	3	0.6	<5	--	--
YV-6K20R	205	0.1	120	8.4	<5	--	--
YV-6K21R	205	0.1	4	1.4	<5	--	--
YV-6K22R	205	0.1	6	6.6	<5	--	--

VOI rev. 4/85

Certified by Hart Bichler

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1
Phone: (604) 984-0221
Telex: 043-52597

RECEIVED
JUL - 8 1986
KERR ADDISON MINES LTD.

CERTIFICATE OF ANALYSIS

PER .....

FILE COPY DO NOT REMOVE

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CC: K. HEBERLEIN

CERT. # : A8614243-001-A
INVOICE # : I8614243
DATE : 7-JUL-86
P.O. # : YV-11

Sample description	Prep code	Ag ppm Aqua R	AS ppm	Sb ppm	Au ppb FA+AA		
YV-6 K01P	201	0.1	55	3.6	<5	--	--
YV-6 K02P	201	0.1	7	0.4	<5	--	--
YV-6 K03P	201	0.1	3	0.4	<5	--	--
YV-6 K04P	201	0.1	5	1.2	10	--	--
YV-6 K05P	201	0.1	5	0.8	<5	--	--
YV-6 K06P	201	0.1	5	0.8	<5	--	--
YV-6 K07P	201	0.9	7	2.2	<5	--	--
YV-6 K08P	201	0.2	1	0.6	<5	--	--
YV-6 K09P	201	0.1	6	4.4	<5	--	--
YV-6 K10P	201	0.1	6	0.2	<5	--	--
YV-6 K11P	201	0.1	6	0.8	<5	--	--
YV-6 K12P	201	0.1	5	0.4	<5	--	--
YV-6 K13P	201	0.1	9	3.0	<5	--	--
YV-6 K03T	201	0.1	11	4.4	<5	--	--
YV-6 K04T	201	0.1	2	0.1	<5	--	--
YV-6 K05T	201	0.1	1	0.1	<5	--	--
YV-6 K06T	201	0.1	1	0.1	<5	--	--
YV-6 K07T	201	0.1	5	0.9	<5	--	--
YV-6 M03T	201	0.1	9	1.4	<5	--	--
YV-6 M04T	201	0.2	5	1.8	35	--	--
YV-6 M05T	201	0.1	11	5.6	<5	--	--
YV-6 M06T	201	0.3	1	0.1	<5	--	--
YV-6 M07T	201	0.2	5	0.8	<5	--	--
YV-6 M08T	201	0.1	6	0.8	<5	--	--
YV-6 M09T	201	0.1	4	0.6	10	--	--
YV-6 M10T	203	0.1	7	0.8	<5	--	--
YV-6 M11T	203	0.1	7	1.0	<5	--	--
YV-6 M12T	203	0.1	12	2.2	<5	--	--
YV-6 M13T	203	0.1	6	1.0	45	--	--
YV-6 M14T	203	0.1	6	1.6	30	--	--
YV-6 M15T	203	0.1	10	1.9	5	--	--
YV-6 M16T	203	0.1	11	2.4	<5	--	--
YV-6 M17T	203	0.1	13	2.2	<5	--	--
YV-6 M18T	203	0.1	9	1.1	<5	--	--
YV-6 M19T	203	0.1	10	1.6	<5	--	--
YV-6 M20T	203	0.1	9	0.9	<5	--	--
YV-6 M21T	203	0.1	7	1.4	<5	--	--
YV-6 M22T	201	0.1	5	0.1	10	--	--
YV-6 M23T	203	0.1	4	0.4	<5	--	--
YV-6 M24T	203	0.3	5	0.6	50	--	--

VOI rev. 4/85

Certified by Hartwig Bichler

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1
Phone: (604) 984-0221
Telex: 043-52597

JUL - 8 1986
KERR ADDISON MINES LTD.
EER

CERTIFICATE OF ANALYSIS

FILE COPY DO NOT REMOVE

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CERT. # : A8614243-002-A
INVOICE # : I8614243
DATE : 7-JUL-86
P.O. # : YV-11

CC: K. HEBERLEIN

Sample description	Prep code	Ag ppm Aqua R	AS ppm	Sb ppm	Au ppb FA+AA		
YV-6 M25T	201	0.2	3	0.1	<5	--	--
YV-6 M26T	203	0.1	6	0.5	<5	--	--
YV-6 M27T	201	0.3	4	0.1	<5	--	--
YV-6 M28T	201	0.1	3	0.1	<5	--	--
YV-6 M29T	203	0.1	2	0.1	<5	--	--
YV-6 M30T	201	0.1	4	0.2	<5	--	--
YV-6 M31T	203	0.1	3	0.1	<5	--	--

VOI rev. 4/85

Certified by Hartt Bichler

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1
Phone: (604) 984-0221
Telex: 043-52597

RECEIVED
JUL 15 1986
KERR ADDISON MINES LTD.

PER .....

CERTIFICATE OF ANALYSIS

FILE COPY
DO NOT REMOVE

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CC: K. HEBEREIN

CERT. # : A8614715-001-A
INVOICE # : I8614715
DATE : 14-JUL-86
P.O. # : NONE
Y11

Sample description	Prep code	Ag ppm Aqua R	AS ppm	Sb ppm	Au ppb FA+AA		
YV-6K14S	201	0.1	12	24.0	<5	--	--
YV-6K15S	201	0.1	11	3.4	<5	--	--
YV-6M32T	201	0.1	3	0.2	<5	--	--
YV-6M33T	201	0.1	7	0.2	<5	--	--
YV-6M34T	201	0.1	3	3.2	<5	--	--
YV-6M47T	201	0.1	1	0.2	<5	--	--

Certified by Hartwig Richter

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1

Phone: (604) 984-0221
Telex: 043-52597

CERTIFICATE OF ANALYSIS

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CERT. # : A8614711-001-A
INVOICE # : I8614711
DATE : 22-JUL-86
P.O. # : NONE
Y11

FILE COPY
DO NOT REMOVE
JUL 23
KERR ADDISON MINES LTD.

CC: K. HEBEREIN FER

Sample description	Prep code	AS ppm	Sb ppm				
YV6D01R	207	6	0.4	--	--	--	--
YV6D02R	207	90	27.0	--	--	--	--
YV6D03R	207	17	1.2	--	--	--	--
YV6D04R	207	2	0.2	--	--	--	--
YV6D05R	207	15	3.4	--	--	--	--
YV6D06R	207	27	1.6	--	--	--	--
YV6D07R	207	77	6.4	--	--	--	--
YV6K23R	207	77	1.0	--	--	--	--
YV6K24R	207	83	0.8	--	--	--	--
YV6K25R	207	25	0.6	--	--	--	--
YV6K27R	207	55	21.0	--	--	--	--
YV6K28R	207	5	1.4	--	--	--	--
YV6K29R	207	2	0.8	--	--	--	--
YV6K31R	207	7	8.0	--	--	--	--
YV6K34R	207	9	10.4	--	--	--	--
YV6K35R	207	53	0.5	--	--	--	--
YV6K38R	207	6	0.4	--	--	--	--
YV6K40R	207	1	0.2	--	--	--	--
YV6K43R	207	73	6.0	--	--	--	--
YV6K44R	207	57	11.2	--	--	--	--
YV6K45R	207	1380	10.4	--	--	--	--
YV6K46R	207	5150	34.0	--	--	--	--
YV6K47R	207	120	2.4	--	--	--	--
YV6K49R	207	16	0.9	--	--	--	--
YV6K50R	207	7	1.2	--	--	--	--
YV6K51R	207	29	1.2	--	--	--	--
YV6K52R	207	55	5.0	--	--	--	--
YV6K53R	207	7	1.8	--	--	--	--
YV6K54R	207	29	3.4	--	--	--	--
YV6K55R	207	125	10.6	--	--	--	--
YV6K56R	207	14	1.0	--	--	--	--
YV6K57R	207	500	14.4	--	--	--	--
YV6K58R	207	25	3.0	--	--	--	--
YV6K60R	207	35	6.0	--	--	--	--
YV6K61R	207	71	6.0	--	--	--	--
YV6K62R	207	15	1.2	--	--	--	--
YV6K63R	207	800	40.0	--	--	--	--
YV6K64R	207	79	3.6	--	--	--	--
YV6K65R	207	69	11.0	--	--	--	--
YV6K66R	207	6	1.8	--	--	--	--

VOI rev. 4/85

Certified by Stan Bichler

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1

Phone: (604) 984-0221
Telex: 043-52597

CERTIFICATE OF ASSAY

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CC: K. HEBEREIN

FILE COPY DO NOT REMOVE
JUL 23 1986
KERR
FA/AA FINISH

CERT. # : A8614711-001-A
INVOICE # : I8614711
DATE : 22-JUL-86
P.O. # : NONE
Y11

Sample description	Prep code	Ag g/tonne	Au g/tonne				
YV6D01R	207	<0.3	<0.07	--	--	--	--
YV6D02R	207	0.5	<0.07	--	--	--	--
YV6D03R	207	<0.3	<0.07	--	--	--	--
YV6D04R	207	2.8	<0.07	--	--	--	--
YV6D05R	207	<0.3	<0.07	--	--	--	--
YV6D06R	207	<0.3	<0.07	--	--	--	--
YV6D07R	207	8.0	13.40	--	--	--	--
YV6K23R	207	11.5	18.40	--	--	--	--
YV6K24R	207	192.0	98.50	--	--	--	--
YV6K25R	207	5.0	4.32	--	--	--	--
YV6K27R	207	1.3	0.55	--	--	--	--
YV6K28R	207	0.5	0.34	--	--	--	--
YV6K29R	207	7.0	13.20	--	--	--	--
YV6K31R	207	2.8	3.09	--	--	--	--
YV6K34R	207	14.5	6.65	--	--	--	--
YV6K35R	207	34.0	49.00	--	--	--	--
YV6K38R	207	0.5	0.75	--	--	--	--
YV6K40R	207	0.8	0.14	--	--	--	--
YV6K43R	207	0.5	1.17	--	--	--	--
YV6K44R	207	2.5	1.23	--	--	--	--
YV6K45R	207	0.5	0.07	--	--	--	--
YV6K46R	207	0.5	0.07	--	--	--	--
YV6K47R	207	0.3	<0.07	--	--	--	--
YV6K49R	207	6.5	8.78	--	--	--	--
YV6K50R	207	2.3	13.40	--	--	--	--
YV6K51R	207	0.5	0.21	--	--	--	--
YV6K52R	207	0.5	0.14	--	--	--	--
YV6K53R	207	<0.3	0.07	--	--	--	--
YV6K54R	207	<0.3	0.14	--	--	--	--
YV6K55R	207	7.0	10.10	--	--	--	--
YV6K56R	207	<0.3	0.21	--	--	--	--
YV6K57R	207	<0.3	<0.07	--	--	--	--
YV6K58R	207	<0.3	<0.07	--	--	--	--
YV6K60R	207	<0.3	<0.07	--	--	--	--
YV6K61R	207	<0.3	<0.07	--	--	--	--
YV6K62R	207	1.7	<0.07	--	--	--	--
YV6K63R	207	1.0	<0.07	--	--	--	--
YV6K64R	207	<0.3	<0.07	--	--	--	--
YV6K65R	207	2.5	9.19	--	--	--	--
YV6K66R	207	0.5	0.07	--	--	--	--

VO rev. 4/85

B. Swaates

Registered Assayer, Province of British Columbia

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1

Phone: (604) 984-0221
Telex: 043-52597

CERTIFICATE OF ANALYSIS

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CC: K. HEBEREIN

FILE COPY DO NOT REMOVE.

CERT. # : A8614711-002-A
INVOICE # : I8614711
DATE : 22-JUL-86
P.O. # : NONE
Y11

Sample description	Prep code	AS ppm	Sb ppm				
YV6K67R	207	17	5.8	--	--	--	--
YV6K68R	207	12	12.4	--	--	--	--
YV6K69R	207	5	1.0	--	--	--	--
YV6K70R	207	4	0.7	--	--	--	--
YV6K71R	207	6	0.5	--	--	--	--
YV6K72R	207	20	9.4	--	--	--	--
YV6K73R	207	3	0.5	--	--	--	--
YV6K74R	207	85	4.4	--	--	--	--
YV6K75R	207	6	1.2	--	--	--	--
YV6K76R	207	11	0.4	--	--	--	--
YV6K77R	207	9	12.4	--	--	--	--
YV6K78R	207	9	3.2	--	--	--	--
YV6K79R	207	15	2.6	--	--	--	--
YV6K80R	207	83	4.6	--	--	--	--
YV6M01R	207	9	1.0	--	--	--	--
YXN6D01R	207	5	0.2	--	--	--	--

VOI rev. 4/85

Certified by .....

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1
Phone: (604) 984-0221
Telex: 043-52597

RECEIVED
AUG 22 1986
KERR ADDISON
PER

CERTIFICATE OF ASSAY

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CC: K. HEBERLEIN

FILE COPY
DO NOT REMOVE

CERT. # : A8616573-001-A
INVOICE # : I8616573
DATE : 21-AUG-86
P.O. # : NONE
Y11

Sample description	Prep code	Au g/tonne					
YV6K26R	214	<0.07	--	--	--	--	--
YV6K30R	214	0.89	--	--	--	--	--
YV6K32R	214	0.21	--	--	--	--	--
YV6K33R	214	4.94	--	--	--	--	--
YV6K36R	214	<0.07	--	--	--	--	--
YV6K37R	214	<0.07	--	--	--	--	--
YV6K39R	214	0.07	--	--	--	--	--
YV6K41R	214	<0.07	--	--	--	--	--
YV6K42R	214	<0.07	--	--	--	--	--
YV6K48R	214	<0.07	--	--	--	--	--
YV6K59R	214	2.54	--	--	--	--	--

VOI rev. 4/85

Marie Chatie
Registered Assayer, Province of British Columbia

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1

Phone: (604) 984-0221
Telex: 043-52597

CERTIFICATE OF ASSAY

REMARK COPY - DO NOT REMOVE
JUL 23 1986
KERR ADDISON MINES LTD.

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CC: K. HEBEREIN

CERT. # : A8614711-002-A
INVOICE # : I8614711
DATE : 22-JUL-86
P.O. # : NONE
Y11

PER _____

Sample description	Prep code	Ag g/tonne	Au g/tonne				
YV6K67R	207	0.5	1.30	--	--	--	--
YV6K68R	207	<0.3	<0.07	--	--	--	--
YV6K69R	207	<0.3	<0.07	--	--	--	--
YV6K70R	207	<0.3	<0.07	--	--	--	--
YV6K71R	207	<0.3	0.07	--	--	--	--
YV6K72R	207	0.3	0.48	--	--	--	--
YV6K73R	207	0.8	<0.07	--	--	--	--
YV6K74R	207	0.8	4.05	--	--	--	--
YV6K75R	207	2.8	24.30	--	--	--	--
YV6K76R	207	<0.3	0.34	--	--	--	--
YV6K77R	207	<0.3	0.07	--	--	--	--
YV6K78R	207	<0.3	<0.07	--	--	--	--
YV6K79R	207	<0.3	<0.07	--	--	--	--
YV6K80R	207	<0.3	<0.07	--	--	--	--
YV6M01R	207	<0.3	<0.07	--	--	--	--
YXN6D01R	207	3.0	<0.07	--	--	--	--

VOI rev. 4.85

Registered Assayer, Province of British Columbia

Chemex Labs Ltd.

212 Brooksbank Ave.
North Vancouver, B.C.
Canada. V7J 2C1

Analytical Chemists • Geochemists • Registered Assayers

Phone: (604) 984-0221
Telex: 043-52597

RECEIVED
AUG 25 1986
KERR ADDISON MINES LTD.

CERTIFICATE OF ASSAY

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

FILE COPY
DO NOT REMOVE

CERT. # : A8616347-001-A
INVOICE # : I8616347
DATE : 25-AUG-86
P.O. # : NONE
Y-11

ATTN: RAY DUJARDIN CC: K. HEBERLEIN

Sample description	Prep code	Ag FA g/tonne	Au g/tonne				
YV-6K 86R	207	32.3	0.07	--	--	--	--
YV-6K 87R	207	3.3	0.07	--	--	--	--
YV-6K 88R	207	0.8	0.07	--	--	--	--
YV-6K 89R	207	2.5	0.07	--	--	--	--
YV-6K 90R	207	0.5	0.07	--	--	--	--
YV-6K 91R	207	0.3	<0.07	--	--	--	--
YV-6K 92R	207	<0.3	0.07	--	--	--	--
YV-6K 93R	207	0.3	<0.07	--	--	--	--
YV-6K 94R	207	0.5	<0.07	--	--	--	--
YV-6K 95R	207	0.3	<0.07	--	--	--	--
YV-6K 96R	207	0.5	0.07	--	--	--	--
YV-6K 97R	207	<0.3	0.14	--	--	--	--
YV-6K 98R	207	<0.3	<0.07	--	--	--	--
YV-6K 99R	207	<0.3	<0.07	--	--	--	--
YV-6K 101R	207	<0.3	<0.07	--	--	--	--
YV-6K 102R	207	0.5	1.51	--	--	--	--
YV-6K 103R	207	0.8	0.07	--	--	--	--
YV-6K 104R	207	0.3	<0.07	--	--	--	--

V01 rev. 4/85

Registered Assayer, Province of British Columbia

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1
Phone: (604) 984-0221
Telex: 043-52597

AUG 25 1986

ADDISON MINES LTD.

PER .....

CERTIFICATE OF ANALYSIS

FILE COPY DO NOT REMOVE

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CERT. # : A8616347-001-A
INVOICE # : I8616347
DATE : 25-AUG-86
P.O. # : NONE
Y-11

ATTN: RAY DUJARDIN CC: K. HEBERLEIN

Sample description	Prep code	AS ppm	Sb ppm				
YV-6K 86R	207	60	50.0	--	--	--	--
YV-6K 87R	207	60	50.0	--	--	--	--
YV-6K 88R	207	53	6.0	--	--	--	--
YV-6K 89R	207	60	8.6	--	--	--	--
YV-6K 90R	207	20	4.6	--	--	--	--
YV-6K 91R	207	16	3.0	--	--	--	--
YV-6K 92R	207	69	6.2	--	--	--	--
YV-6K 93R	207	110	13.2	--	--	--	--
YV-6K 94R	207	15	4.0	--	--	--	--
YV-6K 95R	207	14	3.4	--	--	--	--
YV-6K 96R	207	1900	20.0	--	--	--	--
YV-6K 97R	207	69	1.0	--	--	--	--
YV-6K 98R	207	13	1.3	--	--	--	--
YV-6K 99R	207	600	5.2	--	--	--	--
YV-6K 101R	207	370	7.6	--	--	--	--
YV-6K 102R	207	25	2.0	--	--	--	--
YV-6K 103R	207	35	26.0	--	--	--	--
YV-6K 104R	207	6	2.6	--	--	--	--

Certified by .....

Chemex Labs Ltd.

Analytical Chemists · Geochemists · Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1
Phone: (604) 984-0221
Telex: 043-52597

RECEIVED
AUG 1 1986
KERR ADDISON MINES LTD.

CERTIFICATE OF ANALYSIS

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

COPY
DO NOT
REMOVE

CERT. # : A8615921-001-A
INVOICE # : I8615921
DATE : 10-AUG-86
P.O. # : NONE
YV-11

CC: K. HEBERLEIN

Sample description	Prep code	Ag ppm Aqua R	AS ppm	Sb ppm	Au ppb FA+AA		
YV-6D08AR	205	0.1	1	1.6	<5	--	--
YV-6D08R	205	0.1	500	6.4	<5	--	--
YV-6D09R	205	0.1	10	6.8	<10	--	--
YV-6D10R	205	0.1	14	2.2	<5	--	--
YV-6D11R	205	0.1	6	2.8	<5	--	--
YV-6K81R	205	0.1	5	1.0	<5	--	--
YV-6K82R	205	0.1	100	14.4	<5	--	--
YV-6K83R	205	0.1	3	0.4	<5	--	--
YV-6K84R	205	0.5	22	18.0	<5	--	--
YV-6K85R	205	0.1	9	4.0	<5	--	--
YV-6K100R	205	0.1	9	38.0	<5	--	--

Certified by Ian Bachler

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1
Phone: (604) 984-0221
Telex: 043-52597

RECEIVED
SEP 18 1986
KERR ADDISON MINES LTD.

CERTIFICATE OF ASSAY

FILE COPY DO NOT REMOVE

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CC: K. FEBERLEIN

CERT. # : A8617665-001-A
INVOICE # : I8617665
DATE : 16-SEP-86
P.O. # : NONE
Y-11 VIC

Sample description	Prep code	Ag FA g/tonne	Au g/tonne				
YV-6K105R	207	<0.3	0.41	--	--	--	--
YV-6K106R	207	<0.3	0.21	--	--	--	--
YV-6K107R	207	<0.3	4.08	--	--	--	--
YV-6K108R	207	<0.3	0.07	--	--	--	--
YV-6K109R	207	<0.3	0.14	--	--	--	--
YV-6K110R	207	0.3	0.07	--	--	--	--

W. Stewart Armstrong

Registered Assayer, Province of British Columbia

VOI rev. 4/85

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1

Phone: (604) 984-0221
Telex: 043-52597

RECEIVED
SEP 18 1986
KER
PER

CERTIFICATE OF ANALYSIS

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CC: K. HEBERLEIN

FILE COPY DO NOT REMOVE

CERT. # : A8617665-001-A
INVOICE # : I8617665
DATE : 16-SEP-86
P.O. # : NONE
Y-11 VIC

Sample description	Prep code	Cu ppm	AS ppm	Sb ppm			
YV-6K105R	207	--	60	0.4	--	--	--
YV-6K106R	207	--	41	0.2	--	--	--
YV-6K107R	207	--	29	0.3	--	--	--
YV-6K108R	207	--	9	0.8	--	--	--
YV-6K109R	207	--	9	0.2	--	--	--
YV-6K110R	207	250	10	1.6	--	--	--

Certified by Ian Bichler

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1
Phone: (604) 984-0221
Telex: 043-52597

AUG 12 1986

KERR ADDISON MINES LTD.

PER

CERTIFICATE OF ASSAY

FILE COPY DO NOT REMOVE

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CC: R. POTTER

CERT. # : A8616120-001-A
INVOICE # : I8616120
DATE : 11-AUG-86
P.C. # : NONE
Y-11

Sample description	Prep code	Ag g/tonne	Au g/tonne				
YV-TR 01	236	0.5	<0.07	--	--	--	--
YV-TR 02	236	<0.3	<0.07	--	--	--	--
YV-TR 03	236	<0.3	<0.07	--	--	--	--
YV-TR 04	236	<0.3	<0.07	--	--	--	--
YV-TR 05	236	<0.3	<0.07	--	--	--	--
YV-TR 06	236	<0.3	<0.07	--	--	--	--
YV-TR 07	236	<0.3	<0.07	--	--	--	--
YV-TR 08	236	<0.3	<0.07	--	--	--	--
YV-05 01	236	<0.3	<0.07	--	--	--	--
YV-05 02	236	<0.3	<0.07	--	--	--	--
YV-05 03	236	<0.3	<0.07	--	--	--	--
YV-05 04	236	<0.3	<0.07	--	--	--	--
YV-05 05	236	<0.3	<0.07	--	--	--	--
YV-05 06	236	<0.3	<0.07	--	--	--	--
YV-05 07	236	<0.3	<0.07	--	--	--	--
YV-05 08	236	<0.3	<0.07	--	--	--	--
YV-05 09	236	<0.3	<0.07	--	--	--	--
YV-05 10	236	<0.3	<0.07	--	--	--	--
YV-05 11	236	<0.3	<0.07	--	--	--	--
YV-05 12	236	0.3	<0.07	--	--	--	--
YV-05 13	236	0.3	<0.07	--	--	--	--
YV-05 14	236	<0.3	<0.07	--	--	--	--
YV-05 15	236	<0.3	<0.07	--	--	--	--
YV-05 16	236	<0.3	<0.07	--	--	--	--
YV-05 17	236	<0.3	<0.07	--	--	--	--
YV-05 18	236	<0.3	<0.07	--	--	--	--
YV-05 19	236	<0.3	<0.07	--	--	--	--
YV-05 20	236	0.5	<0.07	--	--	--	--
YV-05 21	236	<0.3	<0.07	--	--	--	--
YV-05 22	236	0.5	<0.07	--	--	--	--
YV-05 23	236	<0.3	<0.07	--	--	--	--
YV-05 24	236	<0.3	<0.07	--	--	--	--
YV-05 25	236	0.3	<0.07	--	--	--	--
YV-05 26	236	0.3	<0.07	--	--	--	--
YV-05 27	236	<0.3	<0.07	--	--	--	--
YV-05 28	236	<0.3	<0.07	--	--	--	--
YV-05 29	236	0.3	<0.07	--	--	--	--
YV-05 30	236	<0.3	<0.07	--	--	--	--
YV-05 31	236	0.5	3.40	--	--	--	--
YV-05 32	236	0.3	0.82	--	--	--	--

VOI rev. 4/85

Anne Christie
.....
Registered Assayer, Province of British Columbia

Chemex Labs Ltd.

Analytical Chemists • *Geochemists* *Registered Assayers*

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1

Phone: (604) 984-0221
Telex: 043-52597

RECEIVED
AUG1 1 1986
KERR ADDISON
PER
FILE

CERTIFICATE OF ANALYSIS

COPY
DO NOT
REMOVE

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CC: K. HEBERLEIN

CERT. # : A8615923-001-A
INVOICE # : I8615923
DATE : 10-AUG-86
P.O. # : NONE
YV-11

Sample description	Prep code	Ag ppm Aqua R	AS ppm	Sb ppm	Au ppb FA+AA		
YV-6D01T	201	0.1	6	0.8	<5	--	--
YV-6D02T	201	0.1	9	0.6	<5	--	--
YV-6D03T	201	0.4	11	0.6	<5	--	--
YV-6D04T	201	0.2	3	0.2	<5	--	--
YV-6D01S	201	0.1	9	8.8	<5	--	--
YV-6K15T	201	0.1	5	0.6	<5	--	--

Certified by Hart Bichler

Chemex Labs Ltd.

Analytical Chemists • Geochemists • Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1
Phone: (604) 984-0221
Telex: 043-52597

RECEIVED
SEP 17 1986
KERR ADDISON MINES LTD.

CERTIFICATE OF ANALYSIS

FILE COPY
DO NOT REMOVE

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CERT. # : A8617666-001-A
INVOICE # : I8617666
DATE : 16-SEP-86
P.O. # : NONE
Y-11 VIC

Sample description	Prep code	Ag ppm Aqua R	AS ppm	Sb ppm	Au ppb FA+AA		
YV-6K116T	201	0.3	10	2.0	<5	--	--

VOI rev. 4/85

Certified by Hartt Bichler

Chemex Labs Ltd.

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1

Telephone:(604) 984-0221
Telex: 043-52597

•Analytical Chemists •Geochemists •Registered Assayers

REJECTED RE-ANALYSIS

FILE / COPY DO NOT REMOVE

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST
VANCOUVER, B.C.
V6E 2S1

AUG 14 1986

KERR ADDISON MINES LTD.

EER

CERT. # : A8615933-001-A
INVOICE # : I8615933
DATE : 13-AUG-86
P.O. # : NONE
YV-11

Semi quantitative multi element ICP analysis.

Nitric-Aqua-Regia digestion of 0.5 gm of material followed by ICP analysis. Since this digestion is incomplete for many minerals, values reported for Al, Sb, Ba, Be, Ca, Cr, Ga, La, Mg, K, Na, Sr, Tl, Ti, W and V can only be considered as semi-quantitative.

COMMENTS :
CC: K. MCCARTHY

Sample description	Al %	Ag ppm	As ppm	Ba ppm	Be ppm	Bi ppm	Ca %	Cd ppm	Co ppm	Cr ppm	Cu ppm	Fe %	Ga ppm	K %	La ppm	Mg %	Mn ppm	Mo ppm	Na %	Ni ppm	P ppm	Pb ppm	Sb ppm	Sr ppm	Tl ppm	Ti %	U ppm	V ppm	W ppm	Zn ppm		
YV-6D08AR	0.24	0.2	<10	80	<0.5	<2	0.02	<0.5	1	123	5	0.67	<10	0.06	<10	0.02	170	<1	<0.01	3	40	4	<10	7	<0.01	<10	<10	5	<10	14	--	--
YV-6D08R	0.31	0.6	390	80	<0.5	<2	0.02	<0.5	.3	64	4	0.73	<10	0.14	<10	0.02	271	1	<0.01	2	50	10	<10	13	<0.01	<10	<10	5	<10	15	--	--
YV-6D09R	0.49	0.6	<10	200	<0.5	<2	0.12	<0.5	4	210	5	1.69	<10	0.09	<10	0.02	975	<1	0.01	7	150	10	<10	5	<0.01	<10	<10	24	<10	33	--	--
YV-6D10R	0.36	0.6	<10	40	<0.5	<2	0.02	<0.5	1	150	2	0.96	<10	0.03	<10	0.01	107	<1	<0.01	4	90	2	<10	9	<0.01	<10	<10	11	<10	20	--	--
YV-6D11R	0.28	0.2	<10	30	<0.5	<2	0.04	<0.5	<1	65	6	0.23	<10	0.07	<10	0.01	61	<1	<0.01	1	100	4	<10	6	<0.01	<10	<10	6	<10	3	--	--
YV-6K81R	0.26	0.4	<10	50	<0.5	<2	0.10	<0.5	<1	43	2	0.23	<10	0.14	<10	0.02	142	<1	0.02	<1	30	8	<10	12	<0.01	<10	<10	1	<10	4	--	--
YV-6K82R	0.36	0.4	60	160	<0.5	<2	0.17	<0.5	11	77	28	2.98	<10	0.03	10	0.02	799	<1	<0.01	5	700	28	<10	17	<0.01	<10	<10	72	<10	73	--	--
YV-6K83R	0.24	0.2	<10	50	<0.5	<2	0.07	<0.5	<1	53	1	0.14	<10	0.15	<10	0.01	170	<1	0.02	<1	90	8	<10	14	<0.01	<10	<10	<1	<10	13	--	--
YV-6K84R	0.21	22.0	10	90	<0.5	4	0.18	<0.5	5	96	49	2.18	<10	0.12	10	0.15	550	<1	<0.01	3	710	120	<10	23	<0.01	<10	<10	43	<10	96	--	--
YV-6K85R	0.96	0.4	10	40	<0.5	<2	1.23	<0.5	13	84	42	1.76	10	0.10	10	0.39	378	<1	0.01	4	550	16	<10	100	<0.01	<10	<10	36	<10	25	--	--
YV-6K100R	0.56	0.2	20	70	<0.5	<2	0.97	<0.5	9	59	15	2.15	20	0.04	<10	0.17	995	<1	0.01	5	370	18	<10	24	<0.01	<10	<10	72	<10	49	--	--

Certified by Hans Bichler

Chemex Labs Ltd.

•Analytical Chemists •Geochemists •Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1

Telephone:(604) 984-0221
Telex: 043-52597

COPY

CERTIFICATE OF ANALYSIS

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CERT. # : A8614716-001-A
INVOICE # : I8614716
DATE : 21-JUL-86
P.O. # : NONE
Y11

Semi quantitative multi element ICP analysis

Nitric-Aqua-Regia digestion of 0.5 gm of material followed by ICP analysis. Since this digestion is incomplete for many minerals, values reported for Al, Sb, Ba, Be, Ca, Cr, Ga, La, Mg, K, Na, Sr, Tl, Ti, W and V can only be considered as semi-quantitative.

COMMENTS :
CC: K. HEBEREIN

Sample description	Al %	Ag ppm	As ppm	Ba ppm	Be ppm	Bi ppm	Ca %	Cd ppm	Co ppm	Cr ppm	Cu ppm	Fe %	Ga ppm	K %	La ppm	Mg %	Mn ppm	Mo ppm	Na %	Ni ppm	P ppm	Pb ppm	Sb ppm	Sr ppm	Ti %	Tl ppm	U ppm	V ppm	W ppm	Zn ppm		
YV-6K26R	1.92	0.2	<10	70	<0.5	<2	1.50	<0.5	17	69	17	3.74	40	0.06	510	1.23	775	<1	0.02	16	3220	12	<10	204	<0.01	40	<10	90	<10	70	--	--
YV-6K30R	0.68	1.0	10	40	1.0	10	3.01	<0.5	5	127	229	2.01	10	0.08	10	0.24	735	<1	0.02	7	790	16	<10	154	<0.01	<10	<10	71	<10	30	--	--
YV-6K32R	0.46	2.0	<10	40	<0.5	14	1.25	0.5	5	99	16	2.34	<10	0.12	20	0.05	508	15	0.01	7	860	13	<10	23	<0.01	<10	<10	42	<10	20	--	--
YV-6K33R	0.72	23.0	<10	30	<0.5	382	0.84	2.5	24	183	159	2.43	<10	0.04	10	0.46	373	2	<0.01	10	370	116	<10	43	<0.01	<10	<10	35	<10	30	--	--
YV-6K36R	0.55	0.6	10	550	0.5	4	0.11	<0.5	3	73	4	1.64	<10	0.25	10	0.03	339	9	<0.01	5	340	14	<10	53	<0.01	<10	<10	4	<10	30	--	--
YV-6K37R	0.92	0.4	10	100	<0.5	<2	1.14	<0.5	8	68	6	3.58	10	0.13	20	0.70	714	<1	0.11	8	1450	9	<10	53	0.14	<10	<10	105	<10	50	--	--
YV-6K39R	0.07	0.2	<10	50	<0.5	2	0.02	<0.5	2	243	9	1.01	<10	<0.01	<10	0.01	356	3	<0.01	5	50	2	<10	4	<0.01	<10	<10	11	<10	10	--	--
YV-6K41R	0.68	0.2	<10	220	<0.5	<2	0.72	<0.5	25	167	79	4.53	10	0.46	20	1.94	572	1	0.06	98	1200	8	<10	24	0.25	<10	<10	154	<10	70	--	--
YV-6K42R	0.60	0.2	10	80	<0.5	<2	0.27	<0.5	9	124	13	0.77	<10	0.28	10	0.08	276	1	0.01	7	450	16	<10	22	<0.01	<10	<10	34	<10	20	--	--
YV-6K48R	1.60	1.2	<10	100	<0.5	2	1.29	<0.5	8	89	214	2.16	10	0.17	20	0.88	447	1	0.09	11	480	154	<10	90	0.04	<10	<10	41	<10	70	--	--
YV-6K59R	0.39	0.2	<10	10	<0.5	<2	0.40	<0.5	2	286	21	0.80	<10	<0.01	<10	0.08	146	<1	0.01	6	50	16	<10	32	<0.01	<10	<10	15	<10	10	--	--

FILE COPY
DO NOT
REMOVE

RECEIVED
JUL 22 1986
KERR ADDISON MINES LTD.
PER

Certified by Ian R Bickler

Chemex Labs Ltd.

•Analytical Chemists •Geochemists •Registered Assayers

212 Brooksbank Ave.
North Vancouver, B.C.
Canada V7J 2C1

Telephone:(604) 984-0221
Telex: 043-52597

FILE COPY DO NOT REMOVE

CERTIFICATE OF ANALYSIS

Semi quantitative multi element ICP analysis

Nitric-Aqua-Regia digestion of 0.5 gm of material followed by ICP analysis. Since this digestion is incomplete for many minerals, values reported for Al, Sb, Ba, Be, Ca, Cr, Ga, La, Mg, K, Na, Sr, Tl, Ti, W and V can only be considered as semi-quantitative.

TO : KERR ADDISON MINES LTD.
(ATTN: RAY DUJARDIN)
703 - 1112 W. PENDER ST.
VANCOUVER, B.C.
V6E 2S1

CERT. # : A8615924-001-A
INVOICE # : I8615924
DATE : 12-AUG-86
P.O. # : NONE
YV-11

COMMENTS :
CC: K. HEBERLEIN

Sample description	Al %	Ag ppm	As ppm	Ba ppm	Be ppm	Bi ppm	Ca %	Cd ppm	Co ppm	Cr ppm	Cu ppm	Fe %	Ga ppm	K %	La ppm	Mg %	Mn ppm	Mo ppm	Na %	Ni ppm	P ppm	Pb ppm	Sb ppm	Sr ppm	Ti %	Tl ppm	U ppm	V ppm	W ppm	Zn ppm		
YV-6D01T	0.69	0.2	<10	90	<0.5	<2	0.29	<0.5	13	88	8	2.26	<10	0.04	10	0.20	1797	<1	0.03	8	430	8	<10	21	0.07	<10	<10	56	<10	46	--	--
YV-6D02T	0.98	0.2	<10	230	<0.5	<2	0.37	<0.5	11	48	9	2.11	<10	0.05	10	0.22	1644	1	0.03	9	630	8	<10	27	0.05	<10	<10	46	<10	68	--	--
YV-6D03T	2.10	0.2	10	730	<0.5	<2	0.40	<0.5	7	24	23	1.92	<10	0.08	20	0.25	500	2	0.02	14	1130	12	<10	39	0.01	<10	<10	42	<10	78	--	--
YV-6D04T	1.08	0.2	<10	240	<0.5	<2	0.32	<0.5	4	12	12	1.00	<10	0.02	10	0.20	257	<1	0.01	8	800	6	<10	23	0.03	<10	<10	30	<10	54	--	--
YV-6D01S	1.03	0.2	10	470	<0.5	<2	0.92	<0.5	13	16	24	2.76	10	0.06	20	0.43	1863	<1	<0.01	11	1780	12	<10	45	0.01	<10	<10	82	<10	90	--	--
YV-6K15T	1.47	0.2	<10	90	<0.5	<2	0.41	<0.5	7	18	12	1.91	<10	0.04	10	0.40	245	<1	0.01	10	1040	10	<10	18	0.06	<10	<10	54	<10	46	--	--

Certified by Stan Bicheler

APPENDIX II

DRILL LOGS 1986

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 1 of 17 LATITUDE 506.1 DEPARTURE 2126.6

CORE SIZE BQ FINAL DEPTH 149.96 m DIP AT COLLAR -45° BEARING 160

STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. 1617.1 LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS g/T: SAMPLE NO.	ASSAYS g/T: % Ag	ASSAYS g/T: % Au
4.7	7.2							Syenite - very weathered to crumbly limonitic material, i.fr.				Extremely weathered, s. pervasive lim. m.-s. chl repl mafics	4.7 – 7.2	YV0134	14.0	0.07
7.2	12.7	100						Syenite - very weathered, fractionally more competent than top of hole. Med.-c.g., 15-25% mafics (hb altered to chlorite), ≈10-20% plagioclase, <10% quartz, 55-75% ksp i.fr.	1	magnetite - diss		"	10.1 – 11.6	YV0135	3.3	<0.07
12.7	13.4	100						Syenite - med.-c.g. 15-25% hb, ≈10-20% plagioclase, 55-75% ksp, <10% quartz, in light greyish green to pinkish in colour, w-m.fr.	1-2	magnetite - diss and repl hb		Lim on local fr. w. chloritization & some hb pyroclusite on local fr.				
13.4	13.5	100						Syenite - more pink in colour w. fr.		"		Epidote repl plag. and in small str.				
13.5	14.4	100						Syenite - w. fr.		"		Epidote locally repl plag and in small str.				
14.4								Epidote, qtz, cb str. 1-3mm, pinkish halo in surrounding syenite				Sauss. halo 3-4cm Lim. in hb 3-4cm around				

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 2 of 17 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 149.96m DIP AT COLLAR -45 BEARING 163

STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
14.4	17.8	100						Syenite - with local epidote str. 14.9 - 1mm	1-2	mag diss and repl hb		Sans around ep str.				
						60		15.3 - 1mm				Lim of hb around ep str				
						65		16.0 - ep in fr. 3cm zone								
						70		16.5 - ep in fr. 4cm zone								
						70		17.4 - " 2cm zone								
						80		17.55 - " 4cm zone								
						80		w.m. fr., pinkish around str.								
17.8		100				40		Fracture zone with heavily limonitic fr., altered hb to lim. and chl.				Lim., chl.				
17.8	18.15	100						Syenite	1	mag - diss and repl hb						
18.15						80		Epidote str. zone -				Lim alt hb Chl. alt hb Local hem blebs.				
18.15	19.0	100						Syenite with local minor ep str., w.m. fr.	1	mag diss + hb						
19.0	19.8	~100						Syenite with m. fr. and local s. fr. zones, ep. fills many fractures, pinkish colour,				Sans of plag lim on fr and in hb around major fr zones				
19.8	23.3	100						Syenite with local ep str. lim fractures, w.m. fr.	1-2	mag - diss and in hb		Lim on fr. saussuritic on local fr.				

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 3 of 17 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 149.96 m DIP AT COLLAR -45° BEARING 163

STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
23.3	23.8	100						Syenite - altered, s.-i. fr., hb altered to lim., ep. patches	1	Magnetite - diss. and within hb.		Oxidation of hb to lim Chl. of hb Lim. on fr. with hematite Sauss. of plag.				
23.8	24.0	100						Syenite - w. fr. chl repl. hb, ep repl. plag., ep in str. at 24.0 - 8mm zone	1	Magnetite - diss. and within hb		Sauss. of plag partial and patchy Chl. of hb				
24.0	24.1	100				85		Andesite porphyry dike - 10 - 15% mafic (sericitized), <1 - 2mm phenos, sub-euhedral <5% feldspar phenos to 8mm light grey green soft groundmass				ser. of phenos and groundmass lim repl. local phenos and on fractures.				
24.1	24.9	100						Syenite - m.-s. fr., chl + lim repl hb, ep repl plag and in small localized str.		Magnetite diss and within hb (chl-lim)		Sauss. of plag Chl. of hb Oxidation of margins Lim on fr.				
24.9	25.1	max width						Quartz vein, w.-m. fr., white to clear, limonitic fractures				Lim on fr.	24.6 - 25.4	XV0101	0.1	0.15
25.1	25.4	100						Syenite - s. fr., chl + lim repl hb ep repl. plag. and in local str.		Magnetite - diss and within hb.		Sauss. of plag Chl. of hb Oxidation of hb Lim on fr.				

#365

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 4 of 17 LATITUDE ____ DEPARTURE ____

CORE SIZE BQ FINAL DEPTH 149.96m DIP AT COLLAR -45 BEARING 163

STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. ____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
25.4	26.55	100						Syenite - m. fr., Chl + lim (ser?) repl. hb, sp, repl plag and in local str.	1	<1 vn, chl - diss and within hb		Saus of plag. Chl of hb Ser? lim on fractures and repl hb.				
26.55	28.6	100				45		Andesite porphyry dyke - Mafic phenocrysts 10-20%, ser., subhedral, <1-3mm Feldspar phenos - 5-10%, subhedral <1-3mm, sp Qz str. to 2mm locally - very small stringers containing red mineral locally present w.-m. fr.				m. ser., partial saus., lim. on fractures - intensely oxidized (lim.) near upper contact - pyroxenite on local fr.				
28.6	29.3	100						Syenite - w-m. fr., partial Chl. of hb, sp repl. zone plag and qz local str. to 3mm at 45°		mag. - diss and within hb		partial saus of plag. partial chl of hb lim on fr.				
29.3	29.55	100						Syenite - w-s. fr., a oxidation of mafics and fractures. sp repl plag		" with slight hematite alt.		lim on fractures and repl hb + chl. partial saus of plag.				
29.55	30.1	100						Syenite - w-m. fr., partial chl of hb and sp repl. plag.		mag - diss and within hb		partial chl of hb. Saus of plag, lim on fractures				

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 5 of 17 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 149.96m DIP AT COLLAR -45° BEARING 163

STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. _____ LOGGED BY C.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
30.1	30.4	[illegible]						Syenite - m-s. fr., [illegible] oxidation [illegible]		[illegible]		oxidation - [illegible]				
								[illegible]		[illegible]		[illegible]				
								[illegible]				partial seams & veining				
30.4	32.0	100						Syenite - m-m. fr. [illegible]		"		s. seams locally s. oxide locally				
								[illegible] oxidation, local zones of s. seams								
32.0	32.5	100						Syenite - m-s. fr., [illegible] oxidation [illegible] local s. seams. altered to gouge, limonite, malachite at 32.5		"		s. seams, oxid locally	32.0 - 32.5	XV0102	0.1	0.04
32.5	33.8	100						Syenite - m-m. fr., central zone of plag and chl of hb		"		lim on fr. s. seams and chl locally				
33.8	34.2	100						Syenite - oxidized strongly				s. oxid.				
34.2	35.7	100						Syenite - m-m. fr., with narrow zones of m-s. fr. and s. oxidation, local zones of s. seams, chl of hb		"		s. seams + oxid chl locally				
35.7	36.2	100						Syenite - m-s. fr., m-s. oxidation m-s. seams, chlorite repl. some hb, hematite present in small zones (oxides of mag.)		"		m-s. seams chl and oxid. chem repl mag	35.7 - 36.2	XV0103	0.1	<0.005

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 6 of 17 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 149.96 m DIP AT COLLAR -45° BEARING 163

STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
36.2	36.7	100						Syenite, w. fr., chlorite repl' hb, very little vp repl' hem replacing magnetite		Magnetite - partially repl. by hem.		m-s. chl m.-s. sauss hem. repl may.				
36.7	37.05	100						Syenite - s. fr. and oxidized				s. oxid (hem, lim)	36.7 - 37.05	YV0104	0.1	<0.005
37.05	37.35	100						Syenite - w.-m. fr., narrow zones of s. sauss, chl repl hb, limonite		Magnetite - diss and within hb		zones of s. sauss. chl of hb - partial lim. on fr. and repl mafics locally				
37.35	37.5	100						Syenite, w. fr. and oxidized								
37.5	38.2	100						Syenite - w. fr., very little vp repl, local chl repl hb., 10cm band of 75% hb		"		local sauss and chl alt.				
38.2	38.6	100						Syenite, s. fr. and oxidized, s. local sauss.				s. local sauss. & lim	38.2 - 38.6	YV0105	0.1	<0.005
38.6	39.0	100						Syenite - relatively unaltered								
39.0	39.2	100						Syenite - altered & limonitic, clay, s-i fr.		"		s. chl.	39.0 - 39.2	YV0106	0.1	<0.005
39.2	39.9	100						Syenite - w-m. fr, local ep, chl, lim				local m. sauss chl and lim.				
39.9	40.2	100						Syenite - s. fr. + ox								

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 7 of 17 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 149.96 m DIP AT COLLAR -45 BEARING 163

STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. _____ LOGGED BY C.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE A.	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
40.2	43.8	100						Syenite - w.-m.fr. with local zones of s.fr., chl. repl. hb and zones of s.vars. Ims St.		veggy - diss. and within hb.		local s. chl, sauss lim				
43.8	45.1	100						Syenite - s.fr. and oxidation				Limonite on fr. hem. repl. veg	43.8 - 45.1	YV0107	0.1	<0.005
45.1	46.7	100 /						Syenite, s.-i.fr. + oxidation local clay alt'n very crumbly zones, hem present in fr. Pyrolusite common on fr.		pyrolusite on fr.		local s. cl.	45.1 - 45.9	YV0108	0.1	<0.005
													45.9 - 46.7	YV0109	0.1	<0.005
46.7	58.8	100				65		Dacite porphyry - crowded 15-25%, sub-euhedral, 1-4mm feldspar (pred. Kspar) phenocrysts 5-10% chloritized mafics Groundmass - m. brown to pinkish local calcite + ep. str., m-fr., fr. locally limonite filled fr or brecciated		Magnetite diss. and within mafics		m.-s. arg. + lim towards top contact m. chl. (strong locally to crumbly)				
											-	local s. lim + cl. around fr.	50.9 - 51.45	YV0110	0.1	<0.005
											-	local pot. alt. around fr.				
58.8	70.1	100						Syenite - w.-m.fr., chl locally pratially repl hb, ep repl plag locally and ep str. common to 1-2 mm with carb + qz., locally oxidized	<1	Pyrite locally mound (small str. of ep + qz, and as small local dissemination		local s. sauss. ar. chl lim locally				
70.1						45		Quartz vein - 2cm white, m.fr. with ep filling many fractures. Other smaller Str to 7mm in same zone to 70.2					69.8 - 70.4	YV0111	0.1	0.1

#358

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 8 of 17 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 199.96 m DIP AT COLLAR -45 BEARING 163

STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
70.1	72.5	100						Syenite - w-m fr., chl + ep local		Magnetite - diss + in hb/chl		local m sauss + chl				
72.5	72.9	100						Syenite - m fr., massive ep and abundant chl		"		i. sauss. partial to total chl of hb				
72.9	80.6	100						Syenite - w-m fr., ep + chl local		"		local partial sauss + chl				
80.6	82.5	100				55		Rhyodacite porphyry (porphyritic dyke) - 5% pink, sub-euhedral +/- 2mm feldspar phenos (arg.) - <5% red (hematitic?) altered mafic phenos, anhedral, +/- 2mm groundmass - buff to greenish buff, partially moderately siliceous	<1	Pyrite - diss, cubic		m-s. cl. of fs phenos.	80.6 - 82.5	YV0112	0.1	0.66
82.5	86.4	100						Syenite - w-m fr., ep + chl local around fr. esp.		mag = diss. + within hb		local partial sauss + chl				
86.4	86.6	100						Syenite - m-s fr., ep and chl abundant as fracture fillings, chl. partially to totally replacing hb, ep. incpl. plag.		"		m-s. local sauss + chl.				

#358

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 9 of 17 LATITUDE _____ DEPARTURE _____
CORE SIZE BQ FINAL DEPTH 149.96m DIP AT COLLAR -45 BEARING 163
STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
86.6						25		Siliceous vein - 2-2.5 cm, m.fr., white and grey mottled, v.f.g. fractures often contain epidote and limonite.					86.5 - 87.65	YV0113	0.2	12.07
86.6	87.65							Syenite - very altered, s.sil (esp. near vein) m.-s.fr. chl and ep. fill fractures as does quartz locally, ep. repl. plag, chl repl hb.		magnetite - diss. and within hb/chl		s.sil, s.serc. s.chl.				
87.65	88.2	100						Syenite - w.-m.fr, ep and chl. locally common esp. around fr.		"		local s.serc and chl.				
88.2	88.8	100						Syenite - m.-s.fr. and moderized, 1m. abundant on fr. ep. repl plag, chlorite repl hb, patchy, very small qz str. in some fractures, local sections are completely altered to limonitic greasy material		Magnetite, them. dissem. and within hb, pyrrhotite in fr.		m. chl, m.-s serc, oxidation	88.2 - 88.8	YV0114	0.1	0.04
88.8	91.3	100						Syenite - w.-m. fr, ep and chl common, local sections contain brecciated fractures containing chl and qz.		"		local s. serc. and chl.				

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY — YII

DIAMOND DRILLING - 1986

DDH No. Yv-86-01 PAGE 10 of 17 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 199.8 m DIP AT COLLAR -45° BEARING 163

STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
91.3	92.3	100						Syenite - m.-s. fr., highly altered from strong fr. to chunky, gougy clay rich material	1	Magnetite - diss. and within hb pyroxenite or fr.		m.-s. cl., m-s chl., m-s. oxidation, lim on most fractures	91.3 - 92.3	YV0115	0.1	0.16
92.3	94.4	100						Syenite - w-m. fr., ep and chl common in local sections				local s. saus + chl				
94.4	94.8	100						Syenite - m.-s.fr., highly altered to clay rich gougy material in most of section, crumbly	1	magnetite weathered to hem -		s. cl.	94.4 - 94.8	YV0116	0.1	0.02
94.8	94.9	100						Syenite - w-m fr., ep and chl local	1	magnetite - diss + within hb		local s. saus, chl				
94.9	95.7	100						Syenite - m-s.fr, s. lim, m-s. chl, ep	1	magn. diss and within hb		strong lim, m-s chl of hb, partial to total saussuritization of plag, m. cl. (?)	94.9 - 95.7	YV0117	0.1	0.015
95.7	97.15	100						Syenite - s.-i. fr, crumbled / broken up section, chl. repl. hb, local ep., carb. stks. to 4mm at 25°,	1	magn - diss. and within hb.		m-s. lim, m-s. chl, local s. saus, m. cl. (?) ser(?)	95.7 - 97.15	YV0118	0.1	<0.005
97.15	98.15	100				45		Syenite - m. fr, and altered, slight very soft green mineral repl. hb (chl ± ser.), ep replaces local plag - brecciated fracture to 1.5cm - Feldspar vein 98.05		magnetite in hb - diss, pyrite around and in local stringers + within both hb		m-s. chl, m ± ? of hb, local saus.	97.15 - 98.15	YV0119	0.1	<0.005

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 11 of 17 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 149.96m DIP AT COLLAR -45 BEARING 163

STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
98.15	98.25	100				90		Rhyodacite porphyry dyke 10-15%, sub-euhedral, +/- 2mm, feldspar phenos. 5% altered mafic phenos, sub-euhedral (blocky - prismatic), <1-4mm, chloritic, Siliceous, brownish w.c. groundmass	1	magnetite disc and stringers + apices		m. chl.				
98.25	98.95	100						Syenite - w.-m. fr., ep. + chl locally common	1	" w. trace local pyrite		S. sauss + chl locally				
98.95	105.2	100				65		Rhyodacite porphyry dyke: 10-15%, sub-euhedral, +/- 2mm altered feldspar phenocrysts, <5% altered mafic cpx phenocrysts, subhedral, +/- 3mm, very soft and green groundmass - brown to light green, v.f.g., w. sil. Calcite veins/str. common to 3mm variable orientation (~45°), some areas around str. are lighter coloured with phenocrysts looking less masked by alteration, lim bleb around fractures common.	tr tr	magnetite disc pyrite - disc		m. cl. m. ser.				
105.2	106.3	100						dyke as above with m-s. lim stains and s. calt. lim filled frac. with calc str. ~40° to 1.3 cm		" pyrolusite on fractures		m-s. cl. m-s. lim. local s.w. sauss chl	105.2 - 106.3	YV0120	0.1	<0.005

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-11 PAGE 12 of 17 LATITUDE ____ DEPARTURE ____

CORE SIZE BQ FINAL DEPTH 149.96m DIP AT COLLAR -45° BEARING 163

STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. ____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
106.3	107.6	100						as above - lim. locally pervasive around some fract. lim. carb. filled	tr-1 tr	mag pyrite pyrolusite common on fract.		m.-s. cl. m. ser local lim.	106.3 - 107.6	YV0121	0.1	<0.005
107.6	108.5	100						as above - with pinkish colour					107.6 - 108.5	YV0122	0.1	<0.005
108.5	109.9	100						Syenite - altered, m. fr., chl pseudo repl. hb, lim stained, ser present filling fractures.		Magnetite - dis and within alt. hb - commonly hematite		m. cl. m. chl ser (?) m-s. lim	108.5 - 109.9	YV0123	0.9	0.01
109.9	115.3	100						Syenite - w.-m. fr. - ep, chl locally repl. grain and as fracture filled str.		"		w.-m. local sauss. m. chl				
115.3						45		Breccia zone - 3cm wide - clasts of syenite to 1.5 cm within dark green to grey silicic matrix, Epidote pervasive								
115.3	121.2	100						Syenite - w. fr., ep-chl alt. Local usually around ep filled fr., local calcite str (1mm)				local s. sauss, chl				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 13 of 17 LATITUDE _____ DEPARTURE _____
CORE SIZE BQ FINAL DEPTH 149.96m DIP AT COLLAR -45 BEARING 163
STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. _____ LOGGED BY L.C.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
121.2	121.5	100				35		Breccia zone - fragments of Syenite to 2cm, shallow ep. and feldspar fragments, mainly dark green to grey silicic matrix, calcite str.	1	Pyrite - diss to patchy Magnetite in Mafics.		Sauss + chl	121.2 - 121.6	YV0124	0.1	0.03
121.5	121.6	100						Silicic breccia - feldspar and syenite fragments in a pink to grey i. silicic matrix, green mafics are chloritic and are generally irregular patches to bands within matrix.	1-2	Pyrite, patchy to diss within matrix and fract.		local sauss. i sil.				
121.6	122.6	100						Syenite - w.fr., ep and chlorite locally around fractures usually	1	Magnetite in hb + diss		local sauss + chl.				
122.6	122.8	100						Syenite - m.fr., brecciated fractures to 1.5 cm, Syenite fragments, dark green chloritic matrix, calcite str., ep + chl common in surrounding rocks	1-2	Pyrite in matrix diss		local m sauss + chl.				
122.8	124.1	100						Syenite - w.fr., ep and chl locally usually around fractures	1	Magnetite in hb and diss		local sauss and chl				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 14 of 17 LATITUDE ____ DEPARTURE ____
CORE SIZE BQ FINAL DEPTH 149.96m DIP AT COLLAR -45 BEARING 163
STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. ____ LOGGED BY C.C.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
124.1	124.8	100						Syenite - m fr. ep ± chl ± qz fill many fractures, ep and chl common in section, 2cm section 5% 30% bb/chl at base of section	<1	Pyrite - irreg blebs in qz/ep str.		m-s. sauss. m-s chl.				
124.8	125.9	100						Syenite - w fr., ep + chl loc ground fractures often filled with ep ± chl.	1	magnetite - diss + within bb		local sauss + chl				
125.9	126.3	100						Syenite porphyry - 5-20% sub-euhedral, kfeldspar phenocrysts to 2cm, remainder as above syenite, ep + chl locally ground fractures commonly filled with ep ± chl	1	magnetite "		local sauss + chl				
126.3	126.7	100						Syenite porphyry - m-s fr ep, chl, clay common, clay zones around fractures	1	"		m-s chl. m-s sauss m-s chl. hem. repl. mag clay around fractures				
126.7	130.7	100						Syenite porphyry - w fr ep + chl. locally around ep + chl +hr. and fr., local calcite veinlets to 4mm, local brecciated fractures 1-2cm 127.15, 128.5, 129.4		magnetite "		s. sauss locally around fr. and bx fr. m chl around fr.			
									tr	pyrite in bx fr.						

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 15 to 17 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 149.96m DIP AT COLLAR -45 BEARING 163

STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. _____ LOGGED BY C.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
130.7	131.4	100						Syenite porphyry - m. fr. rep in abundant fr commonly with irregular qz chl aromd fr. repl hb and in local fr.	1	Magnetite - diss and within hb		M-S. Sauss M-S chl locally				
131.4	132.0	100				45° 35°		Syenite porphyry - with irregular qz veining, very non distinct edges to veins which contain rep. fractures and feldspars patches within 45° and 35° orientations, max. width 5cm, chl common repl hb and in fr.	1	magnetite "		S. Sauss. M-S. chl. sil.(?) causing irregular qz veins hem. repl mag	131.4 - 132.0	YV0125	0.1	0.055
132.0	132.4	100						Syenite porphyry - w-m. fr, abundant epidote and chlorite in patches and fractures	1	magnetite "		S. Sauss + chl.	132.0 - 132.9	YV0126	0.1	0.035
132.4	132.9	100						Syenite porphyry - w. fr. rep + chlorite in patches repl plag and hb and in local fractures, very siliceous zone at top contact	1	magnetite "		W. Sauss. + chl				
132.9	133.3	100						Syenite porphyry - s.fr. and altered to friably texture, abundant chl, hem, lim, arg, some feldspars w. alt hem gouge on fract. 65°				S. chl + cl. + ox hem + lim repl. mafics	132.9 - 133.3	YV0127	0.1	<0.005

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. Yv-86-01 PAGE 16 of 17 LATITUDE _____ DEPARTURE _____
CORE SIZE BQ FINAL DEPTH 149.96m DIP AT COLLAR -45 BEARING 163
STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
133.3	134.8	100						Syenite porphyry - m.-s.fr., oxidized locally, ep-chl abundant in fractures and as repl. minerals.	1	Magnetite - locally oxidized to hem.		S. sauss and chl, hem and lim locally strong				
134.8	135.9	80						Syenite porphyry - s.-i.fr. and altered, crumbly, abundant hem+lim on fr. and repl. mafics, abundant ep-chl, clay min, small fr filled with clay (?), chl + hem. (shears?)		-		S. oxidation to lim + hem. S. chl + sauss. S. cl.	134.8-135.9	Yv0128	0.1	<0.005
135.9	137.9	100						Syenite porphyry - w-m.fr., s.fr locally, abundant ep + chl, locally crumbly and oxidized with m.-s. lim, some hem, locally fr. contain calc. and ep	1	Magnetite - diss and with alt. hb (partially alt to hem + lim)		S. sauss. S. chl locally s. hem+lim				
137.9	138.9	100						Syenite porphyry - s.-i.fr. (to shear) s. hem + lim on fr. and patchy chloritic hb, local clay, fr/str. contain calcite, chl + ser, clay or hem/lim	1	Magnetite - mainly altered to hem		S. chl, ser locally s. cl. S. hem. + lim	137.9-138.9	Yv0129	0.1	<0.005
	138.8					55		Siliceous vein 8cm containing irreg. patches of syenite, mag. and hematitic fractures								

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 17 of 17 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 149.96 m DIP AT COLLAR -45° BEARING 160

STARTED 25/06/86 FINISHED 29/06/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
138.9	142.0	100						Syenite porphyry - w-m. fr. ep + chl locally abundant, ep, carbonate, hematite present in local fr str to 1 cm (ch). variable orientation 45-70°	<1-1	Py ite - local str. Magnetite - diss and within hb.		local s. saus + chl. local lim on fr.				
142.0	142.8	100						Syenite porphyry - s. fr., abundant chl repl. hb., fr contain calcite (to 4 cm irr vein at 70°), hematite <1mm, lim.		magnetite altered to hem		s. chl s. hem + lim	142.0 - 142.8	YV0130	0.1	<0.005
142.8	144.0	100						Syenite porphyry - w.fr., ep common in top of section, chl. is common throughout ep in top of section, calc in fractures to top of section		magnetite - diss and within hb		schl s. saus. at top of section lim on local fr.				
144.0	146.6	100						Syenite porphyry: s.-i. fr (to shear) highly altered, strongly hematitic, limonite with zones of 100% limonite, clay minls locally abundant, chl common				s.-i. oxidation s. chl. s. local cl	144.0 - 145.5	YV0131	0.1	<0.005
													145.5 - 146.6	YV0132	0.1	<0.005
146.6	147.2	100						Syenite porphyry				m.-s. saus.-chl				
147.2		100				15		Calcite Vein 0.5 - 1.5 cm, sericite in patches and lenses, lim on fractures in and around vein, hem within 10cm in syenite					147.0 - 147.4	YV0133	0.1	0.01
147.2	149.96	100						Syenite porphyry.		trace pyrite around vein		m-s saus + chl				

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-02 PAGE 1 of 7 LATITUDE 762.8 DEPARTURE 2100

CORE SIZE BQ FINAL DEPTH 136.25 m DIP AT COLLAR -49 BEARING 160

STARTED 29/06/86 FINISHED 02/07/86 COLLAR ELEV. 1575.9 LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% SO_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
0	6.7	10						Overburden - casing								
6.7	23.0	65						Syenite - syenite porphyry - very altered, due to weathering, s.-i. fr. to crumbly, ep. locally repl. plag and in small stn., chl repl. hb. locally, lim. abundant in section., hem. on local fr.	<1	Magnetite - fine diss and in hb pyrolusite on fr		m.-s. lim.	6.7 - 9.7	YV0230	0.5	0.07
												m.-s. sauss. locally	9.7 - 11.3	YV0231	0.5	<0.07
												m-s. chl (prop.)	11.3 - 12.8	YV0232	0.5	<0.07
												m-s cl. locally	14.3 - 15.8	YV0233	<0.3	<0.07
													17.3 - 18.9	YV0234	0.5	<0.07
													20.4 - 21.9	YV0235	0.5	<0.07
23.0	30.0	25						Rhyodacite - porphyry - m.-s. fr., 10-15%, sub-euhedral, <1-2mm, partially masked by alteration, feldspar phenocrysts. - very few mafics, groundmass light brown to buff siliceous		Pyrolusite on fractures			23.0 - 30.0	YV0201	0.1	0.015
30.0	41.1	100						Syenite porphyry - m-s fr. + alt.		mag - weathered		s. chl + lim. m. chl.	30.0 - 34.1	YV0202	0.1	0.005
41.1	42.3	100						Syenite porphyry - w.-m. fr.	1	mag - diss		partial chl. w. lim locally				
42.3	42.4	100						Syenite - fine to med. grained	1	mag - diss						

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-02 PAGE 2 of 7 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 136.25 DIP AT COLLAR -49 BEARING 160

STARTED 29/06/86 FINISHED 02/07/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE		%	GRAPHIC LOG				%	DESCRIPTION	MINERALIZATION		ALTERATION		STRUCTURE	ASSAYS		
FROM	TO	RECOVERY	ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE <	MoS_2		VOL. %	MODE OF OCCURRENCE	VOL. %	TYPE MODE OF OCCURRENCE	KIND, DENSITY, ETC.	SAMPLE NO.	% P_b	% A_u
42.4	43.1	100						Syenite porphyry - w fr + alt								
	43.1	100				40		Quartz-feldspar vein - 1cm					42.8 - 43.4	YV0203	0.1	<0.005
43.1	44.2	100						Syenite porphyry - w.fr + alt.								
44.2	46.8	100						Syenite porphyry - m-s.fr.				n. cl.. m. local chl local s. lim	44.2 - 46.8	YV0204	0.1	<0.005
46.8	49.5	100						Syenite porphyry - m fr., relatively unaltered				partial chl of hb locally				
49.5	50.6	100						Syenite porphyry - m.-s. fr.				m.-s. lim on fr. and repl hb m local chl	49.5 - 50.6	YV0205	0.1	<0.005
50.6	52.5	100						Syenite porphyry - m fr.								

#355

KERR ADDISON MINES LIMITED

VIC · PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-02 PAGE 3 of 7 LATITUDE ____ DEPARTURE ____

CORE SIZE BQ FINAL DEPTH 136.25 DIP AT COLLAR -49 BEARING 160

STARTED 29/06/86 FINISHED 02/07/86 COLLAR ELEV. ____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ←	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
52.5	56.8	90						Dacite porphyry - crowded 25-30%, sub-euhedral, <1-4mm feldspar phenos, 5-10% mafic bb/chl phenos, groundmass								
56.8	57.7	100				60		Dacite porphyry - altered, s-i fr. to crumbly gougy material.		magnetite - trace		s-i local cl. lin on fr. and as gouge (shear?) m-s. ser. ham. gougy and locally sparvasive	56.8 - 57.7	YV0206	0.1	<0.005
57.7	60.5	100						Dacite porphyry - as above					57.7 - 58.7	YV0207	0.1	<0.005
60.5	87.2	100						Dacite porphyry - crowded coarser grained than above								
87.2	88.2	100						Dacite as before f-m gr.								
88.2	90.9	100						Dacite porphyry - altered, s-i fr. to crumbly								

#385

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-02 PAGE 4 of 7 LATITUDE _____ DEPARTURE _____
CORE SIZE BQ FINAL DEPTH 136.25 DIP AT COLLAR -49 BEARING 160
STARTED 29/06/86 FINISHED 02/07/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
88.2	90.9	100						Dacite, porphyry - altered, s=c fr to crumbly, abundant				m-s. cl. locally m-s. chl	88.8 - 89.5	YV0208	0.1	<0.005
								local clay and limonite in crumbly zones.				lim. conc. locally in fractures and more pervasive red. mafics. hem loc.	89.5 - 90.9	YV0209	0.1	<0.005
								local quartz and carbonate veins								
	89.0					45		Quartz - 10 mm, lim fr, cb fr								
	89.15					35		Quartz with calcite, 10mm, lim fr	tr	Pyrite						
	89.3					35		Calcite - 2-3mm, lim on fr.								
	89.6					30		Calcite - 2 mm								
	89.63					30		"								
	89.5					30		"								
	90.05					40		"								
	90.85					30		" 1mm								
90.9	94.0	100						Syenite porphyry. s.fr. and alt.				m-s. chl + lim w. cl.	90.9 - 92.5	YV0210	0.1	<0.005
													92.5 - 94.0	YV0211	0.1	<0.005
94.0	100.5	90						Syenite porphyry - s.fr + alt				m-s. chl	94.0 - 95.3	YV0212	0.1	<0.005
(96.9 - 98.5)		61						Small hem and calcite filled s.fr.				s. lim, hem, cl.	95.3 - 97.2	YV0213	0.1	<0.005
													97.2 - 99.2	YV0214	0.1	<0.005
													99.2 - 100.5	YV0215	0.1	<0.005
	99.7							- irregular cherty, siliceous stringers								

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-02 PAGE 5 of 7 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 136.25 DIP AT COLLAR -49 BEARING 160

STARTED 29/06/86 FINISHED 02/07/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Av
100.5	101.1	100				25		Syenite porphyry - m-s fr. grey non limonitic except on few fractures, contains breccia filled fr. to 1-2cm with hem. and clay	1	Magnetite - diss		m-s. cl.	100.5 - 101.1	YV0216	0.1	<0.005
101.1	101.8	100						Syenite porphyry - s.fr + alt				s. chl, lim, cl. hem s. in local fracture fillings	101.1 - 102.0	YV0217	0.1	<0.005
101.8	101.85	100				60		Rhyoclacite porphyry - hem + lim f.-m.g., s.fr to blocky		ma of loc. fr.						
101.85	103.0	100						Syenite porphyry - s.fr. + alt				"	102.0 - 103.0	YV0218	0.1	<0.005
103.0	104.2	100						Syenite porphyry - m-s.fr., altered v hem, lm and calcite str. to 4mm common (~45°) in fr	1	Magnetite - diss. and within mafics		m.-s. cl. esp. around local fr. and calcite veins m-s. ser + chl lim perv. around local fr. hem. common on fr	103.0 - 104.2	YV0219	5.0	<0.07

#385

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-02 PAGE 6 of 7 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 136.25 DIP AT COLLAR -49 BEARING 160

STARTED 29/06/86 FINISHED 02/07/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
104.2	105.2	100						Syenite porphyry - m.fr. hem and Rus on local fr., calcite str (~45°),	1-2	Magnetite - diss and within mafics		m-s. chl + ser s. local cb.	104.2 - 105.2	YV0220	1.7	<0.07
105.2	105.7	100						Syenite porphyry - s. fr. and alteration, Limonitic and Hematitic		weathered		" with s. lim + hem	105.2 - 105.7	YV0221	1.7	<0.07
105.7	107.6	100						Syenite porphyry - m. fr. local ep, carbonate, hem, lim str., calcite str to 3mm ~ 35°		magnetite - diss and within mafics		local s. ser + chl esp. around dense fr. zones hem. pers locally around fr.	105.7 - 107.2	YV0222	1.7	0.07
	107.4					45		Feldspar rich vein - 2cm					107.2 - 107.6	YV0223	1.0	<0.07
107.6	108.9	100						Syenite porphyry - w.fr. and alt local very small ep and calcite str. in fr.		"		local m. sauss partial chl of bb. w. lim on fr.				
108.9	110.7	100						Syenite porphyry, m-s. fr. and alt, common s.fr. and hem. zones with calcite str.,				m-s. chl	108.9 - 109.4	YV0224	1.0	<0.07
						60		local hem. slickensides				m-s local hem. in str. and epl. mag. s. local saus.	109.4 - 110.7	YV0225	1.0	<0.07
	109.1					10-15		Calcite vein - ~ 1-1.5 cm, very fractured with lim. + hem filling fractures				lim + hem				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-02 PAGE 7 of 7. LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 136.25 DIP AT COLLAR -49. BEARING 160

STARTED 29/06/86 FINISHED 02/07/86 COLLAR ELEV. _____ LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
110.7	112	100						Syenite porphyry - w.-m.fr. (and alt.) 1% str, calcite and lim str. local.	1	Magnetite - diss and within hb		m-s. chl of hb locally. m. sauss. locally hem + lim locally on fr.				
1.2	115.3	100						Syenite porphyry - m.-s.fr. + altered, top of section very fractured and hematitic,	1	diss dark grey to black metallic mineral (non magnetic - altered magnetite ?		s. chl. locally s. hem + lim locally in fr. and repl. mafics and magnetite m-s chl	112 - 113.5 (hem) 113.5 - 114.1 (m. hem) 114.9 - 115.3 (lim)	YV0226 YV0227 YV0229	0.5 1.0 0.5	<0.07 <0.07 <0.07
						35		bottom of section intensely fractured to gouge limonitic material (shrecked zone?)								
	114.2					40-50		Calcite stockwork, vuggy calcite veins/str to 1-2cm in a f.g. calcareous matrix with 1-2m quartz fragments - zone is 5m wide				limonitic calcite	114.1 - 114.9	YV0228	0.5	0.07
115.3	136.25	100						Syenite porphyry - w-m fr. and alt.,	1	Magnetite - diss and within hb		local s. sauss avanel calcite and cpy veins/str m-s local chl hem locally in fr limonite locally on fr.				

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-03 PAGE 1 & 5

CORE SIZE BQ FINAL DEPTH 107.59 m

STARTED 02/07/86 FINISHED 04/07/86

NOT SURVEYED

LATITUDE 9+00 N DEPARTURE 20+78 E

DIP AT COLLAR -47 BEARING 160

COLLAR ELEV. LOGGED BY L.I.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
0	19.2	47						Rubble / Overburden with large boulders of rhyodacite, syenite porphyry and crowded rhyodacite / dacite feldspar porphyry.								
19.2	24.0	100						Rhyodacite - porphyritic biff, brown to reddish, f.-m.g., 10-15% sub-euhedral, 1-2 mm feldspar phenocrysts		1mm on fr. loc.		loc. lim. on fr.				
19.8	19.95	100				45		brecciated zone								
24.0	28.2	100						Dacite porphyry - crowded, d.gr. 10-25%, sub-euhedral, 1-4 mm feldspar phenocrysts, w-m. fr.				w-m - chl. loc. lim				
28.2	28.9	100						as 24.0 in Sauv w-m fr.				local sauv.				
28.9	38.6	100						as 24.0 w-m fr.				w-m chl loc. lim on fr.				

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-03 PAGE 2 of 5 LATITUDE 9+00N DEPARTURE 20+78E

CORE SIZE BQ FINAL DEPTH DIP AT COLLAR -47 BEARING 160

STARTED 02/07/86 FINISHED 04/07/86 COLLAR ELEV. LOGGED BY CL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
38.6	42.1	100						RHYODACITE - porphyritic as 19.2		Mn on fr.		lim. on loc. fr.				
42.1	44.2	100	1					Dacite porphyry - as 24.0				w-m chl				
44.2	44.7	100						as 24.0 - alt. lim				m-s lim.				
44.7	56.4	100						as 24.0								
56.4	58.0	100						RHYODACITE as 19.2		Mn on fr.		lim on loc. fr.				
58.0	60.0	25						as 19.2 - but crumbly, limonitic				m. lim., cl.				

#388

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-03 PAGE 3 of 5 LATITUDE 9+00 N DEPARTURE 20+78 E

CORE SIZE BQ FINAL DEPTH DIP AT COLLAR -47 BEARING 160

STARTED 02/07/86 FINISHED 04/07/86 COLLAR ELEV. LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
60.0	62.3	60						Syenite porphyry - s-i fr. and alt, limonite pervasive in and around dense fracturing to limonitic gouge zones. Clay altered, chloritic & abundant		weathered		s-i. lim m-s. cl. m-s. chl hem, repl. mag. and on fr.	60.0 - 62.3	YV0301	<0.3	<0.07
62.3	66.1	100						Syenite porphyry, w-m. fr.	1	mag - diss						
	64.5					10		Limonite and carbonate filled fracture								
66.1	68.0	100						Syenite porphyry - m-s fr., local dense fr. zones generally contain hem, lim, calcite, chl		weathered mag.		s. chl local s. hem, lim on fractures local m-s. cl.	66.1 - 68	YV0302	<0.3	<0.07
68.0	68.95	100						Syenite porphyry - s. fr + alt. Pervasive lim + hem				s. chl + cl. hem, lim	68.0 - 69.3	YV0303	<0.3	<0.07
68.95	69.3	100						Intense fracture zone in syenite porphyry lim + hem. gouge.				i. lim, hem.				

#385

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-03 PAGE 4 of 5 LATITUDE 9+00N DEPARTURE 20+78E
CORE SIZE BQ FINAL DEPTH DIP AT COLLAR -47 BEARING 160
STARTED 02/07/86 FINISHED 04/07/86 COLLAR ELEV. LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
69.3	75.2	~60						Hlered Syenite porphyry					69.3 - 71.3	YV0304	<0.3	<0.07
													71.3 - 73.3	YV0305	0.5	<0.07
													73.3 - 75.2	YV0306	<0.3	<0.07
75.2	79.7	~53						Syenite porphyry - s. fr w- no lin - blkns.		upgolvanite on fr. magnetite mostly weathered		s. chl + ser weathering of hb local s. saus. anom. of ep. str. m cl. locally w ken-lin				
79.7	81.5	100						as 75.2 - with w. fr + alt								
81.5	82.2	100						as 75.2 m fr. a-d alt.				m-s. chl				
	81.8					45		fracture/shear filled with grey gouge, tem, calcite + ep. 1-2cm.				m-lim on fr and weathering local hb local s. saus. pt. alt around str. (?)				
82.2	98.5	~100						Syenite porphyry - w-m fr. + alt		mag - diss		local m. saus, chl w. local cl.				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-03 PAGE 5 of 5 LATITUDE 9+00N DEPARTURE 20+78E
CORE SIZE BQ FINAL DEPTH DIP AT COLLAR -47 BEARING 160
STARTED 02/07/86 FINISHED 04/07/86 COLLAR ELEV. LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
98.5	107.59	100			irreg cont.			Dacite porphyry - crowded, dk gn 10-25% feldspar phenos.				w-m chl. loc. lim. on fx.				

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-04 PAGE 1 of 11

CORE SIZE BQ FINAL DEPTH 173.74

STARTED 05/07/86 FINISHED 08/07/86

LATITUDE 250.4 DEPARTURE 1732.1

DIP AT COLLAR -48 BEARING 146°

COLLAR ELEV. 1644.5 LOGGED BY LL.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
0	1.5							Overburden / casing								
1.5	6.7							Syenite - w. fr.		magnetite - diss and within bb		local partial sauss.				
6.7	10.6							Syenite - m-s. fr., oxidized with abundant lim repl. mafics and in fractures, hem. abundant in fr. locally with small qz str. 8.5, 8.8, 9.2, 9.7		" weathered		m-s. oxidation lim repl. mafics m.cl. with s.cl. in local sections	6.7 - 7.7 7.7 - 8.5 8.5 - 9.5 9.5 - 10.3 10.3 - 11.2	YV0401 YV0402 YV0403 YV0404 YV0405	<0.3 0.5 0.5 0.5 0.3	<0.07 <0.07 <0.07 <0.07 <0.07
10.6	10.7					50		Rhyodacite dykes - light green				m-s. cl. hem, lim oxidation				
10.7	11.2							Syenite - m.-str, oxidized as above				m-s oxidation lim repl mafics m-s cl.				
11.2	12.5					30		Quartz / feldspar vein - m fr. w. lim + hem on fr. qz is irreg. within limonitic feldspar rich vein (possibly reworked syenite)				limonitic	11.2 - 12.5	YV0406	<0.3	<0.07
12.5	13.4							Syenite - s-i fr.				s. oxidation lim - hem repl. m. cl.	12.5 - 13.4	YV0407	<0.3	<0.07
13.4	14.1							Syenite - w. fr.				m-cl. s. chl. local seric	13.4 - 14.1	YV0408	<0.3	<0.07

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-04 PAGE 2 of 11 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 173.74 DIP AT COLLAR _____ BEARING _____

STARTED 05/07/86 FINISHED 08/07/86 COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE AXIS	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
14.1	14.4	100				25		Syenite - s-i fr.				s. oxidation with lim	14.1 - 14.4	YV0409	0.5	<0.07
14.4	17.0	80						Syenite - m-s. fr.				m-s. el	14.4 - 15.7	YV0410	<0.3	<0.07
												m-s. chl	15.7 - 17.0	YV0411	<0.3	<0.07
												m - locally s. lim oxidation hem on local fr.				
17.0	19.7							Syenite - s fr.				s-i cl and	17.0 - 17.9	YV0412	<0.3	<0.07
						25		- small qz str at base and top of section 3mm				oxidation, lim	17.9 - 18.8	YV0413	<0.3	<0.07
													18.8 - 19.7	YV0414	<0.3	<0.07
19.7	22.9							Syenite - m-s. fr.				m-s. cl.	19.7 - 21.3	YV0415	<0.3	<0.07
												s. lim oxidation local s. chl.	21.3 - 22.9	YV0416	<0.3	<0.07
22.9	23.4							Syenite - s. fr.				s. cl. local s. lim oxidation	22.9 - 23.4	YV0417	<0.3	<0.07
23.4	24.8					30		Syenite with qz, ser stockwork, locally clayey and brecciated, very irregular veins, hem + lim in veins + fr.		pyrite/waste common on fr.		s-i cl.	23.4 - 24.1	YV0418	<0.3	<0.07
													24.1 - 24.8	YV0419	<0.3	<0.07

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-04 PAGE 3 of 11 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 173.74 DIP AT COLLAR _____ BEARING _____

STARTED 05/07/86 FINISHED 08/07/86 COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% pS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
24.8	28.7	100						Syenite, m.s. fr.				s.cl + locally i	24.8 - 25.8	YV0420	<0.3	<0.07
												s. local lim + hem	25.8 - 26.8	YV0421	<0.3	<0.07
												in fr. and perv.	26.8 - 27.8	YV0422	<0.3	<0.07
													27.8 - 28.7	YV0423	<0.3	<0.07
28.7	29.5	100				25		Syenite - m.fr., s. alt.		syenite common		i.cl	28.7 - 29.5	YV0424	1.0	<0.07
								very hematitic and limonitic		Coronal fr.		s. lim. esp. on fr.				
								fractures at top boundary of				sec?				
								section, qz irreg veining common								
								(stockwork) through section								
						40		variable orientation and								
								thickness to 2cm								
29.5	32.5	100						Syenite - m-s. fr. & s. alt				s. cl - loc i	29.5 - 30.5	YV0425	0.3	<0.07
	29.5					50		limonite fr.				m-s. lim	30.5 - 31.5	YV0426	<0.3	<0.07
	29.9					50		limonite fr and gouge				s. chl. & mafics	31.5 - 32.5	YV0427	0.5	<0.07
								local ep str.				local s. sevs.				
32.5	46.6	100						Syenite - w-m. fr., local				m-s. chl	32.5 - 34.0	YV0428	<0.3	<0.07
								sections ep str with hem,				local m. cl				
								halos common, local lim zones,				local s. lim				
								local qz + cb str in fr.				local s. sevs.				
						50		prominent str. orientation				around ep str.				
46.6	47.2	100						Syenite - m-s. fr., bottom 15cm				m-s cl	46.6 - 47.2	YV0429	<0.3	<0.07
								has qz stockwork str.				s. chl.				
	47.1					40		qz vein / cm., very crystalline				m-hem + lim				

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-041 PAGE 4 of 11 LATITUDE _____ DEPARTURE _____

CORE SIZE AQ FINAL DEPTH 173.74 DIP AT COLLAR _____ BEARING _____

STARTED 05/07/86 FINISHED 08/07/86 COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
47.2	49.6	100				45		Rhyodacite dyke - w. fr. light green, cp + fr. ser. small irreg. qz str. common, banded, limonite rich bands and fr.		parallel to core fractures		m-s. cl ser.? sec. lim	47.2 - 47.6	Yv0430	<0.3	<0.07
47.6	49.2	100						Syenite, m-s. fr., limonite, (hematite, calcite str in fractures common,		magnetite		m-s. cl s. lim s. chl.	47.6 - 49.2	Yv0431	0.3	<0.07
49.2	50.4	100				65		Rhyodacite dyke - w. fr., lim fr. irreg. qz str. common, banding prominent locally		pyrolusite on fr.		m-s. cl s. lim ser?	49.2 - 50.4	Yv0432	<0.3	<0.07
50.4						50		Quartz vein - 2-3cm, w-m fr. lim. fr. surfaces.					50.4 - 50.7	Yv0433	<0.3	<0.07
50.4	53.8							Syenite - m-s. fr. and alt lim and qz, cb str. common		chlorite		m cl, s. lim + chl.	50.7 - 51.7	Yv0434	0.3	<0.07
	51.5					30		qz - cb - brec lim str., Brwn				kem. in fr.	51.7 - 52.8	Yv0435	0.3	<0.07
													52.8 - 53.8	Yv0436	0.3	<0.07
53.8	54.1					45		Syenite with qz stockwork str. zone, 5-10% quartz in total rock				s cl and lim and chl.	[illegible]	[illegible]	<0.3	<0.07
54.1	54.7							Syenite - m-s. fr.		magnetite		m-s. cl + lim s chl	54.1 - 54.7	Yv0438	<0.3	<0.07
54.7	58.3							Syenite - w-m fr.	1-1	Pyrite - patchy to disseminated in small str.		w. cl s. lim + chl				
	55.6	55.8				25		qz str. zone lim, cb, qz common in fr.		Magnetite		kem. / ser.	55.4 - 56.7	Yv0439	0.3	<0.07
													56.7 - 58.3	Yv0440	0.3	<0.07

#388

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-04 PAGE 5 of 11 LATITUDE ____ DEPARTURE ____

CORE SIZE BQ FINAL DEPTH 173.74 DIP AT COLLAR ____ BEARING ____

STARTED 05/07/86 FINISHED 08/07/86 COLLAR ELEV. ____ LOGGED BY ____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
58.3	64.0	100						Syenite - s. fr and altered, qz str common, lim in fr.				s. cl	58.3 - [illegible]	YV04[illegible]	<0.3	<0.07
												m-s. lim	59.3 - 60.3	YV0449	<0.3	<0.07
	58.3					30		② qz str - 3 x 5 mm				s. chl.	60.3 - 61.3	YV0450	0.3	<0.07
	58.6					40		qz-hem str. 5mm					61.3 - 62.3	YV0451	<0.3	<0.07
	59.1					40		irreg qz veining - 0.5-2cm, grey					62.3 - 63.3	YV0452	0.3	<0.07
	59.9	60.3				40-45		zone of qz veining - stockwork str. < 1cm., grey qz					63.3 - 64.0	YV0446	0.3	<0.07
	61.3					45		qz str - grey								
64.0	64.6	100						Syenite - w. fr, m. alt.	1-2	Pyrite blebs and diss		local sauss.	64.0 - 64.6	YV0447	0.3	<0.07
	64.35					40		calcite str.				m-s. chl				
								ep in patches and str				m-s. lim locally				
64.6	67.9					65°	irreg	Dacite porphyry - carb. v.c. common	1	Pyrite diss		m-s local cl.	64.6 - 65.7	YV0448	0.8	<0.07
	65.3					45/135		② 1-2mm calc. str.				s. chl.				
	65.5					70		1-2mm calc str with lim				local pot. alt.?				
	65.6					40		5-8mm calc. str. with some brecciation								
67.9	70.9							Syenite - m-s fr. and alt.				m-s. cl	67.9 - 68.9	YV0449	0.5	<0.07
						60		qz/hem str. common				s. chl.	68.9 - 69.9	YV0450	0.5	<0.07
												m-i hem esp. around fr.	69.9 - 70.9	YV0451	0.5	<0.07
												s. lim.				
70.9	77.2					70°	irreg	Dacite porphyry - heavy lim. alt around local carb. str.				m-s. chl.				
								carb str. common.				local pot. alt. around				
	73.3					45		· calcite str. 1-2mm - lim alt 5cm				calcite/qz str.?				
	74.6					85		" 3-6mm - lim alt 7cm				local s. lim.				

#385

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-04 PAGE 6 of 11 LATITUDE _____ DEPARTURE _____
CORE SIZE BQ FINAL DEPTH 173.74 DIP AT COLLAR _____ BEARING _____
STARTED 05/07/86 FINISHED 08/07/86 COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
77.2	78.9	100						Dacite porphyry - altered locally to breccia.				s. chl.	77.2 - 78.9	YV04452	0.5	<0.07
												s. hem - lim				
	77.2 -	77.5						limonitic / hematitic / clay gouge material strong hem.								
78.9	86.9	100						Dacite porphyry - calcite str. common				m. chl.				
												local m. lim.				
												local m.				
												local pot. alt. ?				
86.9	87.9	100						Dacite porphyry - altered				s. cl.	86.9 - 87.9	YV04453	1.0	<0.07
	87.2 -	87.6						qz str stockwork - partly vuggy				s. chl				
												s. lim				
						30		lower contact								
87.9	88.8	100						Amphibolite / Syenite - 90% bk				w chl				
88.8	89.6	20						Syenite - altered to gouge / limonitic material				s. lim + cl.	88.8 - 90.7	YV04454	0.3	<0.07
89.6	91.8	100						Syenite - m-s. fr + alt. Irregular qz str. at top of section		limonite on local fr		s cl				
												s him locally	90.7 - 91.8	YV04455	<0.3	<0.07
												s. lim				
91.8	94.3	90						Syenite - m-s. fr, brecciated limonite, calcite, hematite locally				m cl	91.8 - 93.3	YV04456	0.5	<0.07
												s. lim	93.3 - 94.8	YV04457	0.3	<0.07
												s chl.				

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-04 PAGE 7 of 11 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 173.74 DIP AT COLLAR _____ BEARING _____

STARTED 05/07/86 FINISHED 08/07/86 COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
94.3	96.3							Syenite - w-m fr. amphibolite at base				m-s. chl. + lim	94.8 - 96.3	YV0458	0.3	<0.07
96.3	111.8					QD		Dacite porphyry								
								common qz + calcite str.								
	100.6					20		Calcite - 3mm with lim								
	100.75					55		② " 2mm								
	101.1					45		" 3mm								
	102.05					35		" several 1 - 5 mm								
	105.1					50		" + hem 4mm								
	108.1					65		" 4-5 mm								
	108.65					55		" + ep. 3mm					108.8 - 109.4	YV0459	0.5	<0.07
	108.9					45		Qz - 5mm								
	109.1					30		Qz - 2-3cm								
	110 - 110.4							Altered.				s. cl.	110 - 110.8	YV0460	0.5	<0.07
	110.4	110.6				30		Qz veins to 2-3cm								
	110.9					40		Qz - 3mm					110.8 - 111.8	YV0461	0.5	<0.07
	111.3					35		Qz - 10mm								
111.8	118.1					068		Syenite - w.fr., local ep, Calcite str., mod. alt at top contact.				m-s. chl. local s saus. lim on fr	111.8 - 112.8	YV0462	1.0	<0.07
118.1	119.1							Syenite - m-fr., lim fr abund quartz veins				m-s. cl m-s. lim + hem	118.1 - 119.1	YV0463	0.3	<0.07
	118.4					45		Qz - 1 cm								
	118.5					050		Qz - 1.5 cm, limonitic/hematitic breccia zone 1.5 cm wide below vein.								

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-04 PAGE 8 of 11 LATITUDE _____ DEPARTURE _____
CORE SIZE BQ FINAL DEPTH 172.74 DIP AT COLLAR _____ BEARING _____
STARTED 05/07/86 FINISHED 08/07/86 COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
119.1	123.5	100						Syenite - w.fr., minor ep, calcite str.				m-s chl limon fr.				
	123.3					25		c.g. feldspar vein - 2cm				local saus around ep. str.				
123.5	124.0	100						Syenite - m.fr. filled with hem, lim and minor calcite, mafics repl. by limonite				s. lim - hem	123.5 - 124.0	Y10464	<0.3	<0.07
						50	fr.									
	124.0					35		qz - 5mm								
124.0	124.4	100						Syenite - w. fr, ep str				m-s chl s. local saus w-m lim				
124.4	125.2	100						Syenite, m.fr., lim filled,					124.9 - 125.2	Y10465	<0.3	<0.07
	124.8					55		qz - vuggy, 2-8mm, limonitic				m cl.				
	125.1					40		qz - 10mm, m fr + lim				m-s lim local hem.				
125.2	125.6	100						Syenite - s. fr. to near cataclastic movement, very hematitic and ep. rich, small qz and carbonate str. common w/in fractures				w-m cl. s. hem. s. saus locally s. chl.	125.2 - 125.6	Y10466	0.3	<0.07
						45		prominent fractures								
125.6	126.4							Syenite - w-m. fr., ep. common				m-s. chl. local s. saus.				

#388

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-04 PAGE 9 of 11 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 173.74 DIP AT COLLAR _____ BEARING _____

STARTED 05/07/86 FINISHED 08/07/86 COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
126.4	127.0	100						Syenite - m-s. fr., hematitic, abundant ep, small calcite str., 1 small qz str.				s. hem	126.4 - 127.0	YV0467	<0.3	<0.07
127.0	127.4	100						Syenite, w fr.				m-s chl m lim				
127.4	127.8	100						Syenite - s. fr., abundant lim + hem on fr.				s. lim, hem, chl				
127.8	128.1	100				55°		Breccia zone - qz matrix lim fragments - gouge, limonitic	<1	Pyrite blebs		s. lim	127.6 - 128.3	YV0468	0.5	<0.07
	127.75															
128.1	128.4							Syenite - m-s. fr., limonitic, local ep + calcite str + blebs				s. lim. w. cl				
128.4	132.7							Syenite - w-m fr, local ep str., calcite str.				w-m chl.				
132.7	137.6							Syenite porphyry - w-s. fr. wide inconsistent crumbly section, ep str common, calcite str local.				m-chl s. sws. locally w-m lim.				
137.6	139.7							Syenite porphyry - m fr. 1 deg. calcite and ep str.				w. cl. m-s lim. m chl.				

#358

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-04 PAGE 10 of 11 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 173.74 DIP AT COLLAR _____ BEARING _____

STARTED 05/07/86 FINISHED 08/07/86 COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
139.7	143.1	100						Syenite porphyry - s.fr. hem. & lim., ep patchy, loc. gougy				s. cl. hem, lim, chl	139.7 - 140.7	YV0469	0.3	<0.07
	141.4					35		very strongly limonitic zone partially brecciated					140.7 - 141.8	YV0470	0.5	<0.07
													141.8 - 143.1	YV0471	0.3	<0.07
143.1	144.4	90						S.p. - m.fr., m.alteration, ep. str. locally				w.-m. cl. s.chl. m.lim.				
144.4	145.3	90						S.p. - s.fr., lim. + hem. abundant.				m.-s. cl. s.chl. s.lim.+ hem.	144.4 - 145.3	YV0472	<0.3	<0.07
145.3	146.1	100						S.p. - w.fr., local lim., hem. and calcite in str.				w. cl. s.chl. s. local lim.				
146.1	147.1	100				45		S.p. - s.fr., hem. filled fr.				s. hem. + lim. s. cl. s.chl.	146.1 - 147.1	YV0473	<0.3	<0.07
147.1	149.4	60						S.p. - m.-s. fr., ep + calcite in str.				w.-m. cl s.chl.				
	147.4							dark grey siliceous irreg. bleb				s. local lim. + hem s. local ep.				
149.4	150.4					70°		D.f.p. - grey, m.fr.				w.-m. cl s. local sauss.				

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-04 PAGE 11 of 11 LATITUDE DEPARTURE

CORE SIZE TPO FINAL DEPTH 173.74 DIP AT COLLAR BEARING

STARTED 05/07/86 FINISHED 08/07/86 COLLAR ELEV. LOGGED BY

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
150.4	152.4	95						S.p. - s.fr., local ep. in str. + patches, limonitic				m-s. cl.	150.4 - 151.4	Yv0474	<0.3	<0.07
												m. lim	151.4 - 152.4	Yv0475	0.5	<0.07
												s. chl.				
												s. local ep.				
152.4	158.0	100				20		RD. f.p. - m.fr., v.f.g., green, phenocrysts difficult to distinguish		pyrolusite on fr.		m. local lim.				
												w.-m. cl.				
158.0	164.0	100						S.p. - m.-s. fr., very hematitic and limonitic, ep. in local fr.				s.-i. cl.	158.0 - 159.5	Yv0476	0.5	<0.07
												s. hem. + lim.	159.5 - 161	Yv0477	0.5	<0.07
	161.7					25		Qz - f. vein, 8 mm.				s. chl.	161 - 162.5	Yv0478	0.5	<0.07
	161.8					25		Qz str. - 5mm				local ep.	162.5 - 164	Yv0479	0.5	<0.07
	161.95					25		Qz str. - 8 mm								
164.0	167.0							RD f.p. - m.-s. fr.,		pyrolusite on fr.		m.-s. local lim.				
												m. cl.				
167.0	168.8							S.p. - w.-s. fr., local ep. patches and str.				m.-s. cl., lim.				
												s. chl.				
168.8	172.6					irreg		RD f.p. - m.fr.,		pyrolusite on fr.		m.-s. cl.				
												m.-s. hem				
												m.-s. local lim.				
172.6	173.74							S.p. - w.-m. fr., local ep. str.				m.-s. chl.				
												m. local lim				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-05 PAGE 1 of 11
CORE SIZE BQ FINAL DEPTH 140.21 m
STARTED JULY 8/1986 FINISHED JULY 10/1986

LATITUDE 194.3 DEPARTURE 1692.1
DIP AT COLLAR -47 BEARING 343°
COLLAR ELEV. 1641.1 LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
0	2.7	—						Casing - no core								
2.7	3.1	100						D.f.p., m.fr.								
3.1	4.6	100						S.p., ep. str. local.	1	sporadic - disseminated in bt.		lim. local. m. chl. local.				
4.6	6.1	60						S.p., s.fr., hem. + lim. abundant on fr.				s. chl. m. hem + lim.				
	4.6					20		Brecciated hem. filled fr./cav.				w-m. ch.				
6.1	10.0	100						S.p., s.-i. fr., s.a., lim. - hem. in fr. and pervasive, brecciated				m.-s. cl.	6.1 - 7.1	YV0501	<0.3	<0.07
	8.1-8.2				1/10			- breccia zone with qz clasts and syenite clasts to 2cm.				s. lim. + hem.	7.1 - 8.1	YV0502	<0.3	<0.07
													8.1 - 9.1	YV0503	<0.3	<0.07
													9.1 - 10.0	YV0504	<0.3	<0.07
10.0	11.6	1/100						S.p., i.fr. to soft crumbly zones, very lim. + hem.,				s. cl. s. chl. i. lim. s. hem.	10.0 - 11.6	YV0505	<0.3	<0.07
11.6	12.7	1/100						S.p., m.-s. fr., locally hem., lim. on fr.		1% - disseminated in bt.		s. chl. s. loc. hem + lim. m. loc. cl.				
12.7	14.0	1/100						RD. f.p., green to limonitic, pervasively clay altered qz str + veins common from brecciated qz str. to veins 2-4cm, lim. in fr. in and surrounding qz		pyrolusite on fr.		s. cl. s. lim. loc. ep.?	12.7 - 14	YV0506	<0.3	<0.07
						60										

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-05 PAGE 2 of 11 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
14.0	17.9	100						S, s.-i. fr. + q., lim. + hem, loc. gouge				loc. grug.	14.0 - 15.0	YV0507	<0.3	<0.07
	16.5				str.	70		- qz str. - 1cm				m-i. hem + lim.	15.0 - 16.2	YV0508	<0.3	<0.07
	17.1							- brecciated to stockwork qz. str. 5cm zone				m. loc. cl.	16.2 - 16.8	YV0509	<0.3	<0.07
												s. chl.	16.8 - 17.3	YV0510	<0.3	<0.07
													17.3 - 17.9	YV0511	<0.3	<0.07
17.9	18.9	100						S, m-s. fr, occas calcite, hem in		loc. Mn (pyrolusite) on fractures		loc. hem around fr.	17.9 - 18.9	YV0512	0.3	<0.07
					fr.	45,60		in fr.				m. lim				
												m-m. cl.				
												s. chl.				
18.9	22.9	100						S. s. fr.,		loc. Mn on fr.		s. loc. hem, lim	18.9 - 19.9	13	0.3	<0.07
						40		qz stockwork - 8mm				loc. s. cl.	19.9 - 20.9	14	<0.3	<0.07
												s. chl.	20.9 - 21.9	15	<0.3	<0.07
												loc. yellow jar.	21.9 - 22.9	16	<0.3	<0.07
22.9	27.0	100			fr.	var.		- s. m-s. fr., limonitic, loc. s. hem.		"		m-s. cl.	22.9 - 24.4	YV0517	<0.3	<0.07
						60		loc. qz. str., 2mm				s. lim	24.4 - 25.9	18	<0.3	<0.07
												hem. in loc. fr. zones	25.9 - 27.0	19	<0.3	<0.07
27.0	27.1	100						- i. hem zone with silicous section				i. hem				
												m. sil.				
27.1	27.4	100				40		- brecciated and gouged, lim, & fr.		Mn.		s. cl., lim	27.0 - 27.4	20	0.5	<0.07
27.4	28.05							as 22.9					27.4 - 28.05	21	<0.3	<0.07
28.05						70		Quartz vein, fr. with hem. in fr., 1-1.5cm								
28.05	28.20							PORPHYRITIC DYKE				s. lim, cl. chl.				
								s. altered, dark green, soft matrix				loc. hem				
								light frs, 1-3mm, 25% phenos.								

#385

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. VV-86-05 PAGE 3 of 11 LATITUDE DEPARTURE
CORE SIZE BQ FINAL DEPTH DIP AT COLLAR BEARING
STARTED FINISHED COLLAR ELEV. LOGGED BY

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
26.2	30.5	20				45		GOUGE - gouge to very crumbled syenite qz - qz fs vein, 1-1.5 cm, lim				s. lim, chl, cl. loc. hem.	28.2 - 30.5	05 22	0.5	<0.07
30.5	32.7	100						SYENITE as 22.9, weathered				s. lim, m. cl.	30.5 - 32.7	05 23	<0.3	<0.07
32.7	33.9	100				5-10		- less lim. and weakened, siliceous veins - locally brecciated and cavitous, variable widths to 2cm, hem + lim abundant on fr.				m-s. lim s. cl.	32.7 - 33.9	05 24	<0.3	<0.07
33.9	35.1	40						- crumbled, s. lim.				s. lim, chl, cl.	33.9 - 35.1	05 25	0.3	<0.07
35.1	38.9	100						- m-s. fr., m-s. lim, loc. crumbly to blocky				m-s. lim, cl, chl	35.1 - 35.8	05 26	0.3	<0.07
	35.6					40		- siliceous irreg. brecciated veins to 1-1.5 cm					35.8 - 37.3	05 27	<0.3	<0.07
													37.3 - 38.9	05 28	<0.3	<0.07
38.9	52.9	100						DACITE PORPHYRY DYKE m. bn to greenish f.g. matrix, 25-40% sub-euhedral 1-4mm feldspar phenos, 5-10% mafics (chlorite), loc. crumbly and weakthered, calcite + qz stv common.		loc. py. diss.		w-m. loc. lim weathered, cl. at top of section m. chl, loc. ser.	52.3 - 52.9	05 29	0.3	<0.07
						45,80										
52.9	53.2	100				80		QUARTZ VEIN wh., w. fr., cockscomb growth from edges and in centre from later shear vein development, loc. drusy cavities, "swirly" pattern over much of vein		loc. dk gy to bk patches		lim. on fr.	52.9 - 53.2	05 30	<0.3	<0.07

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. Y11-86-05 PAGE 4 of 11 LATITUDE DEPARTURE

CORE SIZE FINAL DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
53.2	55.2	100						SYENITE					53.2 - 54.2	0531	0.5	3.4
								m-s. fr. + alt.,				m. lim, cl.	54.2 - 55.2	0532	0.3	0.82
								qz str common				s. chl.				
	53.4					40		12mm								
	53.5					50		irreg. to 20 mm,								
	53.55					65										
	53.75					65										
	53.9					45		15 mm								
55.2	55.7							m. fr., weakly altered, loc. ep.			w-m. lim., loc. ep., w-m. chl.					
55.7	55.75					65		DACITE PORPHYRY DYKE								
								as 38.9								
55.75	57.6							SYENITE								
								as 55.2								
57.6	59.0							as 53.2								
	58.85					45		qz str, irreg. to 2cm					57.6 - 58.3	33	<0.3	<0.07
													58.3 - 59.0	34	<0.3	<0.07
59.0	65.5							RHYODACITE DYKE		mn on fractures		m. ser./cl.				
								- pale green, m-s. fr to blocky, w.p.				lim. on fr.				
65.5	65.9							SYENITE								
					fr.	20,80		- fr., limonitic,				s. lim, chl m. cl., loc. hem ground fr.	65.5 - 65.9	35	<0.3	<0.07

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-05 PAGE 55 of 11 LATITUDE ____ DEPARTURE ____

CORE SIZE VR FINAL DEPTH ____ DIP AT COLLAR ____ BEARING ____

STARTED ____ FINISHED ____ COLLAR ELEV. ____ LOGGED BY ____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
65.9	66.4	100						SYENITE				m. cl., chl, lim.	65.9 - 66.4	38	0.3	<0.07
						65		m-s.fr., finer grained with distinct fractive texture of grains								
66.4	68.1	100						SYENITE								
					fr.	25		m.fr. and alt., hem. around local fr.	1	magnetite diss		w-m. lim. m. chl, m.cl.				
68.1	68.9	100				45		s.fr., s.alt., loc qz. str. drusy, 1cm max. width				s. loc. hem s. lim., loc. jar. m.cl., s. chl.	68.1 - 68.9	39	<0.3	<0.07
68.9	69.55	100						as 66.4								
69.55	72.5	100			fr.	35-45		s.fr. and alt., loc. crumbly				s. lim, chl.	69.55 - 71.0	38	0.3	<0.07
												s. loc. cl.	71.0 - 72.85	39	<0.3	<0.07
72.5	72.85	100				10		s.fr., hematitic				m. hem w. lim s. chl.				
72.85	73.3	100			c. fr	40 5,45		siliceous, very few mafics, s.fr.				m. lim.	72.85 - 73.3	40	<0.3	<0.07
73.3	74.85	100			fr.	25,70		w.fr., and alt.	1	Mag- lets		m. lim. m. chl.				
74.85	75.10	100						as 72.85					74.85 - 75.1	41	<0.3	<0.07
	74.85					30		qz vein - lim on fr., 1cm								
	75.1					30		qz vein - lim on fr., cavitous sections, 1.5cm	1							

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-11C PAGE 6 of 11 LATITUDE DEPARTURE

CORE SIZE FINAL DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
25.1	77.3	100						SYENITE	~1	mag - diss		m. lim. + chl.				
								as 73.3				loc. ep. + w. cl.				
77.3	77.41	100				35		CALCITE VEIN				m. lim.				
								- 3cm true width								
77.4	78.6	100						SYENITE		mag - diss		m lim - chl.				
								as 73.3, loc. ep in str, loc.				loc ep.				
								areas with no mafics								
16.6	79.6	100						ZONE OF BRECCIATION AND ~~DEFORMATION~~		"		m. hem, s. loc. hem	78.6 - 79.6	42	<0.3	<0.07
						40		- syenite developes directive				m - s. sil.				
								fixture with stretched and				s. chl.				
								alligned mafics and felsics,				loc. ep.				
								locally silicified and brecciated								
								to mylonite								
	78.95					50		- brecciated fracture - 1 cm - 1.5cm								
								mafic, chloritized matrix, Syenite								
								clasts to 10% and 2mm								
								- cross cuts directive textures								
	79.1-79.2					45		breccia - syenite clasts in s. hem								
								matrix 5-6cm true width								
								crosscutting directive textures								
19.6	80.4	100						SYENITE				m. lim - chl.				
								as 73.3				loc ep.				
80.4	83.1	100						DEFORMATION ZONE								
								as 78.6 - no brecciation with				m-s. hem	80.4 - 81.8	43	<0.3	<0.07
								generally weaker deformation				m-s sil.	81.8 - 83.1	44	<0.3	<0.07
												s. chl				
												loc ep.				

#385

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YY-86-[illegible] PAGE 7 of 11

CORE SIZE ____ FINAL DEPTH ____

STARTED ____ FINISHED ____

LATITUDE ____ DEPARTURE ____

DIP AT COLLAR ____ BEARING ____

COLLAR ELEV. ____ LOGGED BY ____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
82.1	83.5	100						SILICIFIED AND BRECCIATED ZONE				m-s hem	83.1 - 83.8	45	0.3	<0.07
								Zone of distinct dominantly mafic of alkalic syenite with lesser felsic bands original, brecciation and qz veining crosscut this texture and make up 50-70% of total section				m-s sil.				
												loc: lim.				
	83.1					25		qz vein 5mm								
	83.1 -	83.15				25-40		breccia - chloritic matrix syenite clasts.								
	83.2					35		qz vein - brecciated 1-2cm, chl. + syenite clasts								
	83.3					35		qz vein + breccia, mafic clasts irreg. qz vein to 2.5 cm.								
83.5	83.8	100				40		AMPHIBOLITE - 60-90% chloritized hb. with qz str. common		diss mag (+pl hb?)		s. chl. loc. ep.				
83.8	84.4	100						SYENITE PORPHYRY - feldspar phenocrysts to 1.2 cm up to 40% of total rock, var. mafic content - 10-60%		"		s. chl. w. lim. loc ep.				
84.4	85.9				fr.	40		SYENITE w. fr + alt, loc. ep. str.		"		s. chl w. lim. loc. ep.				
85.9	88.8							SYENITE PORPHYRY as 83.8		"		s. chl. w. lim loc ep.				

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-105 PAGE 8 of 11 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
88.8	91.5	100				20		SYENITE PORPHYRY				s.hem - lim	88.8 - 91.5	98	<0.3	<0.07
								i. fr. + altered, blocky to crumbled				s. cl.				
								gouge material, hem. lim. cl.								
91.5	94.0							w fr to s.loc.fr, loc. lim + hem.		mag. - diss		loc. lim-hem -				
								ep str. and sats. associated				ep.				
				fr.	35 -	55		with s.fr. zones.				m-s. chl.				
94.0	100.2							w.-m. fr., loc. s.fr, generally w. alt.				m-s. chl.				
								occas. calcite str. in fr.				loc. lim, ep.				
	94.7					30-50		calcite strs. 1-3mm								
	94.85					40		" 2-3mm								
	96.8					40		ep strs. - 2, 1-3mm								
	97.5					25		calcite str. 2mm								
	97.75							feldspar rich zone								
	97.9					30		calcite + ep str. zone - 1-2mm								
	98.0					35		calcite str. 2-3mm								
	98.1				35 -	75		ep str. zone.								
	98.7					45		calcite str. + ep. 5-7mm								
	100.1				10 -	15		feldspar vein 1cm.								
100.2	101.4							s. fr. + hem., blocky				s. loc. hem	100.2 - 101.4	97	0.3	<0.07
	100.6					irreg		qz vein - ~ 5cm, cavitous, irreg to				s. chl.				
								brecciated.				loc. cl., ep.				
								qz str. occas. in isolated blocks.								
101.4	105							s. fr., chloritic				s. chl				
								occas. calcite str.				lim on local fr.				
	102.4					50		8mm calcite str.								
	103.7					20		irreg qz str. 2mm, partly cavitous								

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-05 PAGE 9 of 11 LATITUDE DEPARTURE

CORE SIZE FINAL DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
105	105.7	100						s. fr + hem, loc s. chl., blocky to crumbled in bottom of section				s. hem + chl. loc cl. + lim.	105 - 105.7	48	0.3	<0.07
						45		irreg. qz str common 1-3mm								
105.7	107.3	100						as 101.4				s. chl loc. lim on fr. loc. ep				
107.3	108.5	100						as 105				s. hem + chl. loc. wi cl.	107.3 - 108.5	49	0.5	<0.07
108.5	115.1	100			fr	20-45		as 101.4, loc. ep str., lim on fr				s. chl., loc. lim on fr, loc. ep.				
115.1	115.35	100				45		i. hem + lim, s. fr.				i hem + lim m-s cl ?	115.1 - 115.35	50	0.3	<0.07
115.35	115.55	100						w. fr. + lim.		mag - diss		w. lim, s. chl., loc. ep.				
115.55	116.4	100			fr.	45		s. fr., hem + lim, top of section crumbled., hem + lim filled fr				s. hem + lim m-s. cl., s. chl.	115.55 - 1164	51	0.3	<0.07
116.4	116.95	45				50		i. lim. to gougy, crumbled material				i. lim	116.4 - 116.95	52	0.3	<0.07
116.95	118.9	100			fr	20, 35, 50		s-i fr. + lim., hem in fr. irreg. and locally making up matrix in small scale brecciation				s. lim, hem in fr. s. cl., s. chl.	116.95 - 118.4 118.4 - 119.6	53 54	0.3 0.3	<0.07 <0.07
118.9	119.6	n/100						i fr. crumbly section, loc lim				loc. lim, w-m cl., s. chl.				

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-05 PAGE 10 of 11

CORE SIZE ____ FINAL DEPTH ____

STARTED ____ FINISHED ____

LATITUDE ____ DEPARTURE ____

DIP AT COLLAR ____ BEARING ____

COLLAR ELEV. ____ LOGGED BY ____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
119.6	121.8	100						SYENITE PORPHYRY m-s. fr., w. altered		disc. mag.		s.chl., loc. lim on fr, loc. ep.				
121.8	122.1	100						- s. fr - i.fr. + lim., loc. crumbly				s. lim, chl, m.cl. loc., hem. on fr.	121.8 - 122.5	55	0.3	<0.07
122.1	122.25	100						BRECCIA + FRACTURE ZONE - hem, lim matrix, syenitic clasts				i. lim + hem s. cl.				
						55		multiple hem + lim filled fractures								
122.25	123.4	100						SYENITE PORPHYRY as 121.8				s. lim, chl, m.cl. hem in loc fr. ep. loc.	122.5 - 124.2	56	0.3	<0.07
123.4	124.2	20						- i fr. to crumbled, gouge material				s. lim, chl, m.cl.				
124.2	124.9	100						as 119.6		m		s.chl, loc. lim on fr.				
124.9	125.05	~100						s. fr. to crumbly, limonitic, loc ep.				m. lim, cl. s.chl, loc. ep.				
125.05	126.8	100						as. 119.6		mag-clay		schl., lim on fr. loc. ep.				
126.8	132.1	95						s. fr and alt. lim + loc hem loc. fr. zones with abundant hem + lim				s. lim, chl. m. s. cl. loc. hem.	126.8 - 128.5 128.5 - 130.3	57 58	0.3 0.5	<0.07 <0.07
	126.85					40		hem fr. zone, 1cm					130.3 - 132.1	59	0.3	<0.07
	128.1					5		calcite/lim str. 3mm								
	129.0					25		lim fr zone								
	130.7					45		lim, calcite, hem fr zone 3-5 cm.								

#385

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. Y-86-05 PAGE 11 of 11 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE		%	GRAPHIC LOG				%	DESCRIPTION	MINERALIZATION		ALTERATION		STRUCTURE	ASSAYS		
FROM	TO	RECOVERY	ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE <	MoS_2		VOL. %	MODE OF OCCURRENCE	VOL. %	TYPE MODE OF OCCURRENCE	KIND, DENSITY, ETC.	SAMPLE NO.	% Ag	% Au
132.1	132.6	40						GOUGE - LIMONITIC SYENITE P. - i. lim., crumbled to gouge				i, lim	132.1 - 133.8	60	<0.3	<0.07
132.6	133.0	100			fr.	5		SYENITE PORPHYRY - s-i. fr, limonitic				s. lim, m. cl.				
133.0	133.8	50						- s. fr., altered to crumbly				m. lim, s. cl. s. chl.				
133.8	134.6	100				60		- w-m fr, weakly altered		mag. disc		m. chl. loc. lim. on fr.				
134.6	135.6	50						- s-i fr, blocky to crumbled, m. lim				m. lim, s. cl., loc hem in fr. s. chl.	134.6 - 135.8	61	<0.3	<0.07
135.8	136.2	100			fr	45		m. fr. and altered				w. lim., m. cl. s. chl				
136.2	137.5	75				0,40		s. fr., lim., blocky, hem fr. abundant and variable				s. lim, s. cl. s. chl. loc hem in fr.	136.2 - 137.5	62	0.3	<0.07
137.5	140.2	100			fr.	45		as 133.8, loc. cp in blebs + str.		mag - disc		m. chl, loc lim on fr.				

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. XV-86-06 PAGE 1 of 4 LATITUDE 250.3 DEPARTURE 1744.4

CORE SIZE BQ FINAL DEPTH 48.77m DIP AT COLLAR -47 BEARING 326

STARTED JULY 10/1986 FINISHED JULY 11/1986 COLLAR ELEV. 1643.1 LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
0	0.7							casing / overburden								
0.7	1.5	100						S.a., s.-i. fr., s. hem. and lim., calcite fills local fr.		weathered avg.		s. arg. s. chl	0.7 - 1.5	YV-1601	1.3	0.14
	1.45					15		Qz vein - 10 - 15mm				s. hem. + lim.				
1.5	4.8	100						S.a., s.fr., s. local lim + hem esp. around local fr.		pyrolusite loc.		s. arg. s. chl s. hem + lim loc.	1.5 - 2.7 2.7 - 3.6 3.6 - 4.8	YV0602 YV0603 YV0604	1.0 <0.3 0.5	1.03 0.21 0.14
	3.6 -	4.2						irreg. qz common								
4.8	6.4	100						Fine grained altered rock with very similar alteration to Syenite., limonite in spots + around fr.		pyrolusite zone in fr		s. arg. m.-s. lim	4.8 - 6.4	YV0605	0.3	0.07
						10		fracture set								
						20		2. qz. stv. at base of section								
6.4	7.4	100						S.a., m.fr. lim on fr and around chl. mafics				s. arg. s. chl. ± ser.	6.4 - 7.4	YV0606	0.3	0.48
	6.8					45		qz stv. 8mm, very fr. + lim irreg. qz towards lower contact				s. lim				
7.4	7.8	100				40		Qz vein, m.-s. fr., lim on fr., contains patchy feldspars (a.)				s. arg. of altered patches s. lim. in fr.	7.4 - 7.8	YV0607	13.8	35.8
7.8	8.5	100				35		S.a., local qz stv. and lim. in fr., base of section has i. lim. around hem filled fr.				s. arg. s. chl. ± ser. s. local lim	7.8 - 8.5	YV0608	0.5	0.31

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. Y/06-86 PAGE 2 of 4 LATITUDE DEPARTURE

CORE SIZE FIN.' L DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY

FOOTAGE		%	GRAPHIC LOG				%	DESCRIPTION	MINERALIZATION		ALTERATION		STRUCTURE	ASSAYS		
FROM	TO	RECOVERY	ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE ∠	MoS_2		VOL. %	MODE OF OCCURRENCE	VOL. %	TYPE MODE OF OCCURRENCE	KIND, DENSITY, ETC.	SAMPLE NO.	% Ag	% Au
5.5	8.8	100				45		BD dyke? - a., green with irreg. silicified light coloured qz bands, fr. limonitic				s. ep. s. local lim.	B.C. - B.B	[illegible]	0.3	<0.07
						60+										
8.8	10.8	100						S., s.fr. + a., lim. + hem on fr.				s. arg.	8.8 - 10.3	Y/06 10	<0.3	<0.07
	10.55					40		- qz. vein, 1cm, strong, parallel to				s. chl s. lim	10.3 - 10.8	Y/06 11	0.3	<0.07
10.8	12.8	100						S., m.s.fr., s. loc. lim on fr.				w-m. arg. s. chl. s. lim. loc.				
12.8	25.9	100						S., w. fr., s. fr. loc., ep. loc. in small str., lim. loc., repl. hb. and on fr., calcite in loc. str.				m. chl. s. lim. loc.				
	16.2					30		- fractures filled with lim., hem + calcite								
25.9	28.4							S., s.-i. fr., s. hem + lim.				m. - s. arg.	25.9 - 27.1	Y/06 12	0.3	<0.07
	26.0					30		Shear zone - limonitic gouge				s. chl	27.1 - 28.4	Y/06 13	0.5	<0.07
	26.0					30		qz along shear - 1 - 1.5 cm.				s. hem + lim				
	26.2					?		qz vein - 2cm max. (broken up)								
	26.5					35		qz vein - 1cm.								
28.4	29.2							S., s.fr., loc. hem, lim. common on fr. and repl. mafics				s.-i. arg. s. chl. s. lim loc. hem.	28.4 - 29.2	Y/06 14	0.5	0.07
29.2	29.4					40		Quartz vein - m.fr., lim. on fr.					29.2 - 29.4	Y/06 15	2.3	1.10

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-06 PAGE 3 of 4 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
29.4	36.7	100						S., s.fr., abundant lim, loc. calcite str.				m-s. arg.	29.4 - 30.4	YV0616	0.3	0.27
												s. chl.	30.4 - 31.4	YV0617	<0.3	<0.07
	32.7					25		qz vein, 5-10mm				s. lim.	31.4 - 32.4	YV0618	<0.3	<0.07
						20		qz vein, 5mm, drusy					32.4 - 33.1	YV0619	<0.3	<0.07
	32.9					10		qz vein, 8-10mm, loc. drusy.					33.1 - 34.1	YV0620	<0.3	<0.07
	33.9					35		lam. fracture.					34.1 - 35.1	YV0621	<0.3	<0.07
													35.1 - 36.1	YV0622	<0.3	<0.07
36.7	37.6							S., s.fr., lim + qz str. stockwork abundant in centre of section prominent fr./str. orientation - str. less common to edges of section				s. arg	36.1 - 36.7	YV0623	<0.3	<0.07
												s.-i. lim.	36.7 - 37.6	YV0624	<0.3	0.07
						20-35										
37.6	38.4							S., m-s. fr., loc. lim., s.a.				s.-i. arg.	37.6 - 38.4	YV0625	0.5	<0.07
												s. chl.				
												s. lim. loc.				
38.4	39.9							Amphibolite i. lim at top of section, 80-90% hb				i. lim at top of section w chl.				
39.9	42.9							S., w. fr. + a.	<1-1	Magnetite dis.		w. arg.				
												w-m. chl.				
												w lim. loc.				
42.9	44.2							S., s-i. fr., lim throughout				m-s. arg.	42.9 - 44.2	YV0626	0.5	<0.07
												s. chl.				
												s. lim				

#355

KERR ADDISON MINES LIMITED
VIC · PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-06 PAGE 4 of 4 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
44.2	44.4	100						f, w.fr + a.		magnetite		w. arg. m. chl. w. lim				
44.4	44.6	100						s. s.fr. + lim				s. lim s. chl. w.-m. arg.				
44.6	46.5	100						s. w.fr + a.	1-1	magnetite		m. chl. lim on loc. fr.				
46.5	47.65	100						Amphibolite - 80-90% hb/chl	2	magnetite		w.-m chl.				
47.65	48.77	100						s, w.fr. + a.	1	magnetite - diss		m. loc. chl.				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-01 PAGE 1 of 1 LATITUDE 249.7 DEPARTURE 1744.6
CORE SIZE BQ FINAL DEPTH 14.63 DIP AT COLLAR -79° BEARING 326
STARTED JULY 11/1986 FINISHED JULY 11/1986 COLLAR ELEV. 1643.6 LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
0.0	0.4	–						Casing / no core								
0.4	1.0	100						S., m-s. fr., s.a., hem on fr. loc. lim.		altered mag		s-i. arg w. hem + lim	0.4 - 1.0	YV0701	0.5	<0.07
1.0	1.5	100						S., s.fr + a., hem. on fr.				s-i arg. s. hem.	1.0 - 1.5	YV0702	0.3	0.07
1.5	1.8	100						S., m.fr., s.a.				s-i arg. loc. hem. in fr. and rept. mag.	1.5 - 1.8	YV0703	<0.3	0.07
1.8	3.9	100						S., s.fr. + a. lim perv.				s. arg.	1.8 - 2.8	YV0704	<0.3	0.14
	3.0					5		qz vein, 10-15 mm				s. lim.	2.8 - 3.9	YV0705	<0.3	0.07
												m.-s. loc. hem.				
3.9	5.3	100						S., m. fr., s.a., lim on fr.				s-s. arg w. lim	3.9 - 5.3	YV0706	<0.3	0.14
	4.3							irreg qz str								
5.3	10.2	100						S., s.fr. + a., lim + hem. abund. on fr and rept. mafics, ep. loc.				m-s. arg.	5.3 - 5.8	YV0707	1.7	2.47
												s. lim	5.8 - 6.8	YV0708	0.5	0.14
	5.5					15		qz vein, 13mm, grey, fr, lim				s. chl.	6.8 - 7.8	YV0709	0.5	0.82
												s. lim. loc.	7.8 - 9.2	YV0710	<0.3	0.07
													9.2 - 10.2	YV0711	0.8	4.66
10.2	11.2	100						S., s.a., w-s.fr, contains qz w. irreg. blebs and str., lim common on fr.		pyrrhotite loc.		s.-i. arg. s. lim. loc.	10.2-11.2	YV0712	4.4	18.4
								base of section contains more qz in possible qz-fs vein					11.2 - 12.2	YV0713	0.3	0.21
													12.2 - 13.4	YV0714	0.3	0.07
11.2	14.63	100						S., s.fr., lim common on fr.				m arg. s. chl + lim	13.4 - 14.6	YV0715	0.3	0.07

#388

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-08 PAGE 1 of 8 LATITUDE 349.5 DEPARTURE 2063.5
CORE SIZE BQ FINAL DEPTH 63.7 m DIP AT COLLAR -47 BEARING 160
STARTED JULY 11/1986 FINISHED JULY 12/1986 COLLAR ELEV. 1645.1 LOGGED BY L.L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
0	4.6							OB – No CORE								
4.6	4.7	-						DACITE PORPHYRY DYKE - Blocky, dk gn., 20% sub-euh. (wl 1-3mm feldspar phenos.				w-m. chl.				
4.7	5.2	80						RHYODACITE PORPHYRY DYKE - pale pink to buff, blocky, m.g.		mn on fr.		w-m. lim. w. cl.				
5.2	6.1	70			fr.	60		- bn to bn/gn, limonitic, weathered hem in v. small fr.		"		m-s. lim, weathered				
6.1	7.2	85			fr	45		- as 4.7, more altered		"		loc. hem, lim m-s cl.				
7.2	7.4	100			fr.	60		BRECCIA - siliceous matrix, RDf.p. clasts 60-70% as 6.1				m. lim m. cl.				
7.4	7.9	90			fr	45		- RHYODACITE PORPHYRY DYKE as 6.1				m. lim. loc. hem s. cl.				
7.9	10.4	80						SYENITE - c.fr and alteration, blocky to crumbly, buff to wh. to pink,				i. cl. & chl. s. loc. lim	7.1 – 10.4	YV 25-01	0.5	0.07
					fr.	25		hem + lim in fr., clay rich				s. loc. hem.				
10.4	10.6	100				90		RHYODACITE DYKE s.fr, i. lim weathering to crumbly + bn		mn on fr.		i. lim + cl ?				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-08 PAGE 2 of 8

CORE SIZE ____ FINAL DEPTH ____

STARTED ____ FINISHED ____

LATITUDE ____ DEPARTURE ____

DIP AT COLLAR ____ BEARING ____

COLLAR ELEV. ____ LOGGED BY ____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Mg	ASSAYS: % Mo
10.6	14.0	80			fr	60, 75	85	SYENITE		Mn on loc. fr.		s-i. cl. s. hem,				
								- i. fr. and alt., blocky to crumbly, buff to pinkish purple clay, to abundant hem., loc. qz str. and small calcite str. small qz fragments to 1.5 cm.				loc. s. lim, chl.	10.6 – 12.5		∠0.3	0.07
													12.5 – 14.0		∠0.3	∠0.07
	11.1															
14.0	14.3	100			fr	60-65		RHYODACITE PORPHYRY DYKE pale gn, blocky, w.p., partially banded		Mn on fr.		app. ser? wi-m. cl., lim on fr.				
14.3	15.5	15						SYENITE as 10.6		"		s-i. cl., s loc. hem. lim on loc. fr	14.3 – 17.7	08-061	∠0.3	∠0.07
15.5	17.7	95						as 10.6, qz veins local, ep. loc.		"		s-i. cl., hem, lim,				
	17.65						35	qz vein, broken, lim on fr. 0.8m-1.0mm				s. chl., loc ep.				
17.7	18.7	95						- as 10.6 except less hem + lim.		"		s. cl., loc. lim, hem s. chl.				
18.7	19.9	75						RHYODACITE DYKE - s. fr., blocky, pale bn to orange/pink f.g., w.p., partially brecciated		"		m. loc. cl. m.-s. lim.				
19.9	20.2	95			fr.	45, 90		SYENITE as 17.7		"		s. cl., loc. lim; hem s. chl.				
20.2	20.5	85						RHYODACITE DYKE orange/pink as 18.7 bottom 10 cm, intensely altered (clay and lim), small qz stockwork		"		s. lim loc i. cl., lim hem in fr.				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-08 PAGE 3 of 8
CORE SIZE FINAL DEPTH
STARTED FINISHED

LATITUDE DEPARTURE
DIP AT COLLAR BEARING
COLLAR ELEV. LOGGED BY

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Mo_3	ASSAYS % Au
20.5	21.45	90			fr.	45-85		SYENITE		Mn on loc. fr.		s.cl., hem, loc. lim		YV		
								as 17.7 with s. hem				s.chl.	20.5 - 21.45	08-05	0.5	0.21
21.45	21.7	90				?		QUARTZ VEIN					21.45 - 21.7	06-06	2.3	0.82
								- very blocky, lim. on fr., contacts unknown								
21.7	21.95	100			fr.	45-85		SYENITE		Mn on loc. fr.		s.cl., hem, loc. lim. s.chl.				
								- as 20.5								
21.95	28.7	90						RHYODACITE DYKE		Mn on loc. fr.		m-s. lim, hem. w-m. cl. loc.				
					fr.	45-65		- pink-orangey to loc. buff, f.g. loc. w.p. s. fr. to blocky, hem spots at top of section								
28.7	30.9	90						- buff to slight pink, blocky		"		w. hem. loc. m.cl. w. lim.	28.7 - 30.0	YV0807	<0.3	<0.07
	29.5					70		- qz str zone - partially brecciated 2cm wide								
30.9	36.3	90						- as 21.95, local chl blebs, hem blebs		"		m-s. hem, lim w-m.cl.	33.7 - 34.3	YV0808	<0.3	<0.07
	33.9					50		siliceous vein, 1.2 cm								
	34.05					25		siliceous brecciated vein, 0.5 - 1.2cm								
36.3	36.6	90-100						- pale orange-pink to pale green, siliceous with irregular spots and lenses of qz, chl, ser. oriented at 60°		"		w-m. lim. m. sil, w. ser.?				
36.6	37.8	100						- as 36.3 - less siliceous, directive texture loc. (banding)		"		w-m lim., w. sil				
						70										

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-115 PAGE 4 of 8 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FIN'SHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: % STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
31.8	38.0	~100						as 36.6 with irregular siliceous cavitous patches / veins		lim. on fr.		lim. on fr. m sil.	37.8 - 38.0	YV0809	<0.3	0.14
36.0								GOUGE TO CRUMBLED RHYOLITE - rhyolite clasts in pale gn powdery gouge.		lim.		m-s. cl. loc. lim				
36.0	40.4	~100			fr.	35/40 30 25 25		RHYODACITE DYKE, blocky - pale gn to greyish, loc. banded fracture, loc. siliceous sections - siliceous band - grey, 1-2cm		lim.		loc. sil. w-m. lim.				
40.4	40.55	~20				25		UNIT - s.fr. and alt., limonite fr. and pervasive lim., irreg qz pebbles				s. lim. s. cl., s. chl.				
40.55	41.8	~100				55		RHYODACITE DYKE as 36.6, more limonite, loc banded				m. lim. w. cl.				
41.8	42.3	~100			fr/60			UNIT - c. unknown. s. fr. and limonite				s. lim, w.m.cl. s. chl.				
42.3	43.6	100						- s. fr., lim on fr, relatively unalt.				s. chl, lim. on fr. loc. hem blebs. loc. cp. stn.				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. VY [illegible] PAGE 5 of 8

CORE SIZE _____ FINAL DEPTH _____

STARTED _____ FINISHED _____

LATITUDE _____ DEPARTURE _____

DIP AT COLLAR _____ BEARING _____

COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS %	ASSAYS %
44.0	44.3	cm						RHYODACITE DYKE		mn in fr.		m-s. lim.				
								- reddish bn, buff, pale to dk gn, w.p.,				m. sil.				
						45.5°		banded, m.fr., hem + lim on fr.,								
								loc. calcite in irreg. fr., siliceous								
44.25						5°		- soft green bnd, ep-ser, 2cm,		"		s.ep. + ser.				
								narrow calcite/lim str.				loc. lim.				
44.25	44.55	100						- m.gn to orange, limonitic				m-s lim				
												sm ep.				
44.55	44.6	-				45		GOUGE TO CRUMBLED RHYOLOLITE				m. lim, s. cl.				
								- limonitic, clay, ser.				ser?				
44.6	45.5	100						RHYOLOLITE DYKE		w/in occ fr		m-s. lim				
								as 44.25, m.p.				loc. hem. around				
												fr.				
45.5	45.85	100						- contains 5-10% sericitic angular				loc. s. sem				
								clasts to 1cm, orange - m.gn -				s. ser., m. lim.				
					str.	45.6		purplish, occas small qz str.								
45.85	46.1	100				5°		as 44.6				m-s. lim.				
												m-s ser. + chl.				
46.1	47.9	100						- RHYODACITE PORPHYRY DYKE								
								dk gn and pinkish purple matrix,				m-s. hem				
								m-gn - dk gn phenocrysts. 5-15%,				m-s chl + ser				
								green sericitic + chloritic and				s. loc lim.				
								purplish brn altered phenos to 5mm,								
					str.	45.6		occas. calcite str. in fr. as well								
								as lim. fr.								

#385

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. 11-86-05 PAGE 6 of 8 LATITUDE ____ DEPARTURE ____

CORE SIZE ____ FINAL DEPTH ____ DIP AT COLLAR ____ BEARING ____

STARTED ____ FINISHED ____ COLLAR ELEV. ____ LOGGED BY ____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
47.9	48.1	100						RHYODACITE - DACITE PORPHYRY DYKE				s. chl				
								m.-dk gn matrix, pale-dk gn phenos,				m. cl + ser				
								10-15%, subhedral, altered feldspar				loc. lim				
								phenos, 5-10% irregular mafic								
								phenocrysts usu. alt. to chlorite								
					fr	45,60		lim + calcite in fr.								
48.1	48.4	100						pale bn to gy matrix, pale gn				s. cl. + ser.				
								phenos, lim in fr., irreg. calcite				m. lim.				
					vn	35		veining								
48.4	48.6	100			fr	45,60		as 47.9, calcite in fr.				s. chl, m. cl. + ser				
48.6	49.0	100						limonite				s. lim, m-s cl.				
												s. chl.				
49.0	49.5	100			fr	25,40		as 47.9, lim + calcite in str.				sehl., m.cl. loc. lim				
												ser.				
49.5	49.75	100						as 48.1				s.cl., ser.				
												m. lim.				
49.75	50.05	100			fr	45,60		limonite, s. fr. to locally crumbly				s. lim, m-s. cl.				
50.05	51.1	100						pale gn matrix with purplish				s-i ser. + cl.				
								patches, pale gn phenos,				loc. lim on fr.				
								very altered to gougy and								
								crumbly sections, irreg. calcite								
								veins, crack fillings and patches								
								common to 1cm wide.								

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. VV 86-08 PAGE 7 of 8 LATITUDE DEPARTURE

CORE SIZE FINAL DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE AXIS	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
51.1	51.3	100				75		as 50.05 with s. lim, central crumbled section				s-i. ser + cl. s. lim.				
51.3	52.25	100			f.	50		as 50.05, loc. hem in fx and in sections around hem fx.	1	Mn + hem in fx.		s-i ser + cl. loc. hem.	51.3 - 52.25	YV08 10	0.5	<0.07
52.2	52.3	100						as 51.1				s-i ser + cl s. lim.				
52.3	53.7	100						as 50.05				s-i ser + cl.				
53.7	54.6	100						as 50.05, more crumbled with loc lim and hem.				s-i ser + cl. m. loc. lim + hem.	53.7 - 54.6	YV08 11	0.5	<0.07
54.6	55.4	100						as 50.05, loc lim				s-i ser + cl. loc lim in fx.				
55.4	56.1	100						as 50.05 with s. patchy hem. and very irreg qz veining in more irreg. phenocrysts				s-i ser + cl. s. loc. patchy hem. loc. sil.	55.4 - 56.1	YV08 12	<0.3	<0.07
56.1	58.2							RHYODACITE PORPHYRY DYKE pale green with 5-10% irreg phenocrysts hem or ser alt, irreg qz str to qz stockworks common lim. zones loc., crumbly sections		Mn on fx.		s, ser - cl. loc. s. lim loc. sil.	56.1 - 57.2	YV08 13	<0.3	<0.07
	56.4							qz stwk					57.2 - 58.2	YV08 14	<0.3	<0.07
	56.9							" and ser gouge								
								qz over remainder of section at 45° 5-10%								

#365

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. V-86-115 PAGE 6 of 8 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
58.2	58.9	100						buff to orange, distinct silicious elongated blebs 10-20% of total rock, blebs become larger towards lower part of section, oriented at 70°		Mn Sph		m-s lim m. ser	58.6 - 59.35	Y-v0815	<0.3	<0.07
58.9	59.35	100						as 58.2 with larger silicious blebs to 60-70% of total rock.		Mn Sph fr.		m-s lim m. ser				
59.35	59.5	100				25		SYENITE fr - alt.		"		s. lim, cl, ser.				
59.5	59.8	100						RHYODACITE PORPHYRY DYKE - pale grey to limonitic, qz irreg + patchy at contact with syenite, mpc to base of section, 5-10% alt feldspar phenos, very blocky to crumbly section		Mn "		s. lim. loc. s ser. m. cl.				
59.8	60.9	100				60		- limonitic and hematitic, feldsp phenos 5-10%, loc brecciated		"		s. lim - loc hem m. cl. - ser				
60.9	61.35	100			c.	60		BRECCIA - siliceous, hematitic matrix, 10-20% limonite, fr, + RD fragments, gouge at bottom of breccia zone. (hematitic)		"		s. sil., lim, hem m. cl.	60.9 - 61.35	Y-v0816	<0.3	<0.07
61.35	63.7							RHYODACITE - DACITE PORPHYRY DYKE as 46.1 loc. ep str								

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-09 PAGE 1 of 4
CORE SIZE BQ FINAL DEPTH 64.0/m
STARTED JULY 12/1986 FINISHED JULY 13/1986

LATITUDE 297.4 DEPARTURE 1998
DIP AT COLLAR -45° BEARING 340°
COLLAR ELEV. 1652.0 LOGGED BY RP

~~FOOTAGE~~ METERS FROM	TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MODE OF OCCURRENCE	ALTERATION: VOL. %	TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	% Au g/T	% Ag g/T
0	3.1							Rubble								
3.1	6.0	85	A					Andesite Dyke:				Weathering				
								Medium grey green to rusty								
								Fine grained. Friable, numerous								
								rusty fractures, Fine vesicular					SAMPLES:			
														YV		
6.0	8.8	85	S					SEYENITE:		Quartz veining		Weathering	6.1 - 6.5	0901	<.07	<.3
								Light grey and rusty, weathered					6.5 - 8.8	0902	<.07	<.3
								Very friable broken core								
								Well fractured. Mn staining								
								6.1-6.5 coarse quartz veining								
								silicified, rusty								
								weathered out calcite molds								
													8.8 - 10.2	0903	<.07	<.3
8.8	10.2	100	S					SEYENITE:				Weathering				
								Pink fg rusty to black (mn)								
								Mod fr and broken, weathered								
10.2	10.7	100	Rd					RHYODACITE FELDSPAR PORPHYRY:								
								Grey green with rusty frac.								
								Fine grained								
								Dyke								
10.7	10.8	?						MUD:								
								Soft grey, sheared				Shearing				

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-09 PAGE 2 of 4

CORE SIZE _____ FINAL DEPTH _____

STARTED _____ FINISHED _____

LATITUDE _____ DEPARTURE _____

DIP AT COLLAR _____ BEARING _____

COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Au	ASSAYS: % Ag
10.8	14.5	100	S					SYENITE:							n/T	n/T
								Pink to rusty								
								Coarse grained. ~ 80% Kspar (pink)		—		Carbonatization				
								20% Hbld				minor chlor"				
								Alteration of Hbld from sl. chlor to complete carbonatization (to brown carbonate {siderite} with remnant magnetite)								
								Dense frac with hem stn.								
								10.8-11.5 = carbonatized hbld								
								11.5-12.2 = sl chlor of hbld, calc vlts @ 25°								
								12.2-13.3 hem stn, prom fracturing at 40° with epidote								
								13.3-13.4 Mud								
								13.9-13.9 hem stn, minor chlor of hbld								
								13.9-14.5 Carbonatized hbld								
														YV		
14.5	25.9	95						SYENITE:					14.5-15.9	0904	<.07	<.3
								Rusty, well frac, moderate argillization and sericitization				with 5cm QV →	15.9-17.0	0905	<.07	<.3
								Not calcareous					17.0-18.3	0906	.21	<.3
								15.9-15.95 Coarse textured QV with limonite residue				QV →	18.3-18.9	0907	.21	<.3
													18.9-20.1	0908	.35	<.3
								17.3 8mm QV @ 25° no siliceous envelope					20.1-22.5	0909	1.51	.5
								18.3-18.9 Coarse cockscomb tex QV. No carbonate								
								Trace of grey metallic hair cuts core at 30°								

#388

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-09 PAGE 3 of 4 LATITUDE DEPARTURE

CORE SIZE FIN^L DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	% Au	% Ag
			S					22.5 - 22.9 Qtz Vn, very broken up, rusty. Low core recovery here						YV	g/T	g/T
												Qv →	22.5 - 22.9	09 10	17.8	.8
													22.9 - 24.4	09 11	.07	<.3
								23.6 - 1 cm Qtz.					24.4 - 25.9	09 12	.07	<.3
25.9	26.4	100						ANDESITE DYKE: Grey to brown, soft Blocky fractured core No veining Contacts about 25°								
26.4	64.0	100						SYENITE: Light grey to pink. Relatively fresh Coarse grained 75% pink K-spar 20% hbld with 1% mag. Hbld ± chlorite to epidote Local diss. pyrite. Foliation defined by alignment of hbld @ ~ 60° 26.4 - 27.0 Rusty carbonatized mafics, calc vlts. 27.0 - 28.2 pervasive ± fracture hem staining, epidote on frac. 28.2 - 39.7 Fresh, scat hem and epidote frac 39.7 - 40.3 pervasive and frac hem. 40.3 - 48.3 Fresh, minor hem, cp, chlor Qv @ 43.2 1.5cm 30° 47.1 0.5cm 30°	—	—						

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-09 PAGE 4 of 4

CORE SIZE _____ FINAL DEPTH _____

STARTED _____ FINISHED _____

LATITUDE _____ DEPARTURE _____

DIP AT COLLAR _____ BEARING _____

COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: Au %	ASSAYS: Ag %
48.3	55.3	100	S					SYENITE: Section of carbonatized mafics, minor dark grey, gelatin veining and silicification		Veins: Depth Type Thick. ∠ 48.3 Q 2mm 30; 48.35 Q 2mm 30; 48.5 Calc 2mm 30; 49.1-49.6 Q/C 15cm 10; 49.6-52.1 Q/C Stockwork 10,45,60; 51.6 Q 8mm 30; 52.9 Q 10mm 45; 52.7 Sil 1/3mm 10/45; 54.8 Q 5mm 30; 54.9 Q 15mm 30		S.1	48.3-49.1	0913	<.07	<.3
													49.1-49.6	0914	<.07	<.3
													49.6-50.8	0915	<.07	<.3
													50.8-52.1	0916	<.07	<.3
													52.1-53.3	0917	<.07	<.3
													53.3-55.3	0918	<.07	<.3
55.3	57.6	100	S					SYENITE: Relatively fresh with minor chlor, ep and carbonatized sections.								
57.6	60.2	100	S					SYENITE: With wide spaced QV stockwork and carbonatized hornblende. 57.6-58.1 Flat braided fracture with qtz, calcite, siderite hmstn, av 5 mm wide @ 0 to 10° to core. 58.1-59.0 Stockwork of QV (20%) No silicified envelopes. 59.6-59.7 Stockwork 35% QV					S.1, carb²	58.4 59.0	0919	<.07	<.3
													59.6 59.9	0920	<.07	<.3
60.2	64.0							SYENITE: Fresh, minor ep, chlor,		Foliation (bbld) 65°		— EOH —				



#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-10 PAGE 1 of 6 LATITUDE 224.1 DEPARTURE 1741.5

CORE SIZE BQ FINAL DEPTH 57.3 m DIP AT COLLAR -54 BEARING 338

STARTED Aug 25/1986 FINISHED Aug 28/1986 COLLAR ELEV. 1644.6 LOGGED BY L.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
0	4.5	—						Overburden - Rubble								
														YV		
4.5	5.5	100						SYENITE - pinkish - m-c.g., 60-80% fs 20-40% hb or altered hb, m.-s. fr.		weathered orig. Mn st. on fr.		m-s.cl., s. lim, loc. s. hem, ser loc. carbonitization	4.5 - 5.5	1001	8.5	<0.07
5.5	5.75	100										s-i lim, loc. s hem	5.5 - 5.75	1002	7.3	<0.07
						45		5.6 m - Qz vn zone, 9cm, multiple stv to 4cm, cavities, mtx, hem + lim filled fr., loc. Syenite frags.				m-s.cl., carb				
5.75	7.6	100						- as 4.5, m.fr (25, 45, 55), - directive texture				s-i cl., w. lim	5.75 - 7.25	1003	2.8	<0.07
						50		7.05 - loc. siliceous stv.					7.25 - 8.15	1004	3.3	<0.07
7.6	7.8	100						- as 5.5								
						45		loc. hem fr.								
7.8	8.15	100						as 4.5								
8.15	8.4	100				40		as 5.5					8.15 - 10.1	1005	2.8	<0.07
8.4	8.5							as 4.5				s.i cl.				
8.5	10.1	10						as 4.5, broken				s cl., loc. hem, lim				
10.1	10.5	100						as 4.5				lim + hem in fr.	10.1 - 10.5	1006	1.3	<0.07
						25		s.fr.								

#365

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-10 PAGE 2 of 6

CORE SIZE _____ FINAL DEPTH _____

STARTED _____ FINISHED _____

LATITUDE _____ DEPARTURE _____

DIP AT COLLAR _____ BEARING _____

COLLAR ELEV. _____ LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Pb	ASSAYS: % Au
10.5	10.6	100				25		as 5.5, s. fr.								
10.6	11.3	100						as 4.5 m. hem. in fr. and around bb, m. fr.								
														YV		
11.3	13.2	100						- s-i fr., variable				m-s cl., s-i lim+hem, s. carb., loc. s. ser., s. chl.	11.3-13.2	1007	1.7	<0.07
						25-45		11.5-12.2 - i hem. in fr.								
						30°		12.8 Qz-lim brecciated fr. zone 0.5-1.0 cm, multiple fr.								
13.2	14.6	100						- i fr to crumbly				s. cl., lim, hem, chl	13.2-14.6	1008	1.7	<0.07
14.6	16.7	100						as 4.5					14.6-16.2	1009	1.7	<0.07
						20		loc. s. hem fr.								
													16.2-17.25	1010	1.0	<0.07
16.7						35		Qz VN, 1cm, in s. fr. zone with ser. + lim filling fr.								
16.7	17.4	100						SYENITE - as 4.5		loc. s. mn.			17.25-17.75	1011	0.8	<0.07
17.4	17.55	100				35		Qz VN - 8-10cm, contains s. fragments, lim + Mn in fr.								
17.55	19.35	100						SYENITE - as 4.5, loc. s. lim. zones					17.75-19.35	1012	1.0	<0.07
19.35	19.7	100				20		- s-i fr. zones,		s. mn.		s. lim, hem, ser	19.35-20.7	1013	0.8	<0.07

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-10 PAGE 3 of 6 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
19.7	21.1	100		15-25°		70°		SYENITE - as 4.5 loc. s.hem, lim fr. 20.85 - Sil. veining with abundant lim., irreg., 4-5cm				loc. s. lim, hem	20.7 - 21.1	1014	2.5	<0.07
21.1	22.2	100						- s-i fr, hematitic				s-i hem, s. chl, m.cl.	21.1 - 22.6	1015	1.0	<0.07
22.2	22.35	100						as 4.5								
22.35	23.95	100						as 21.1, fr at 55°		loc. Mn						
23.95	24.2	100						- m-s fr., loc. brecciated with hem. m. sil. matrix, S. + RD clasts				m.cl, lim., hem	22.6 - 24.2	1016	1.0	<0.07
24.2	29.0	100		c. irreg.		40°		RHYODACITE DYKE - pale gn - yel., broken, s. fr., loc. cavitous and partially brecciated, w.p.		Mn on fr.		w-m.cl, lim fr.				
29.0	29.5	100						SYENITE - as 4.5				loc. s. lim. + hem.				
29.5	29.95	100		c. 75 c. 60 var.				RHYODACITE DYKE - buff - pale gn, banded at 65°, w.p. s. fr. with hem. in fr.		Mn on fr.		m.cl. hem fr.				
29.95	30.1	100						SYENITE - s. fr.,				s.cl., loc. hem, lim	29.5 - 30.1	1017	0.5	0.14
30.1	30.15	100				60°		RHYDACITE BAND				m-s ser + lim				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-10 PAGE 4 of 6 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
30.15	32.7	100						SYENITE - m-s. fr., loc. irreg qz str.				s.cl., lim, chl loc. s. hem, carbō	30.15 - 31.4	1018	1.7	0.14
						40		30.3 1-3 mm, lim in fr.					31.4 - 32.7	1019	0.5	0.21
						40		30.35 1-3 mm								
						30		30.4 2-3 mm								
						20		30.9 3-6 mm								
						95		31.45 5-10 mm								
						45		31.5 1-5 mm - irreg to blebby								
						15		31.65 2-4 mm - "								
						35		31.85 5mm - irreg, fr, lim								
32.7	39.75	100						- w-m fr., loc. s. fr, lim fr. relatively unaltered				loc w.cl. carbō in loc.	36.5 - 37.15	1020	1.0	<0.07
						35		35.25 Calcite str., 1-2 mm				zones, m-s chl.	37.95 - 38.3	1021	0.5	<0.07
						20		36.75 Fs-qz vein, diffuse bdy ~1.5 cm				loc. ep.				
						30		38.15 " ~1.5-2.0 cm								
39.75	40.7	100						- crumbly zone				m-s ep, w.cl. s. lim + carbō	39.75 - 40.7	1022	1.0	0.07
40.7	42.9	100						- as 32.7								
42.9	43.5	100						- s. fr + alt.				s. lim., carbō, m. chl., w. cl.				
43.5	45.95	100						- s. fr. loc. qz str, ep str.				m-s. hem s. chl w. cl.	43.5 - 44.7	1023	0.5	<0.07
						do		43.95 - Qz str 4-6 mm, splits into mult. str.					44.7 - 45.95	1024	1.0	<0.07
						5°		44.25 - 44.4 Calcite in fr. with lim, 1-3 mm								

#385

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-10 PAGE 5 of 6 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	% Ag	% Au
45.95	47.55	100						SYENITE - m-s. fr., qz + calcite s/vr.				s.lim, loc. s. hem, s.chl, w-m cl. carbn	45.95 - 47.55	1025	0.3	<0.07
						15°		46.8 - qz + carb. str. irreg. in mult. fr 1-5 mm, lim								
						20°		47.2 - qz str., 2mm								
47.55	48.25	100						- s. fr., lim fr. at 25-40° qz common		Mn common on fr		m-s cl., m. ser, m-s lim,	47.55 - 48.25	1026	0.5	<0.07
						30		47.8 - QZ vn, 2cm, limonitic, feldspars common, cavitous, s/vr.								
					25-40			47.9 - 48.15 QZ VN zone - mult. irreg. qz + ser stks. in brecciated Syenite, 10-30% qz+ser in section, Mn								
48.25	50.45	100						- as 45.95		loc. py in stk.			48.25 - 49.9	1027	0.8	<0.07
						25		49.0 QZ VN with carb, 1.5cm Syenite fragments, s. lim					49.9 - 50.45	1028	1.0	<0.07
					40-50°			49.5 QZ STRS. - 1-3mm								
								49.55 QZ VN BX zone, var orientation, carb common in matrix and fr.								
						55		50.2-50.35 QZ VN with irreg. carbz blebs in fr., Syenite and sericite fragments, 10cm zone								
50.45	51.0	100				55		- w. fr, relatively unalt., loc. ep in fr. 5°				m-s chl, lim fr.				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-10 PAG 6 of 6 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: % STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
51.0	52.5	100				50		SYENITE - s. fr, lim, qz + carb in lov. str., loc. dir. texture		loc. py		s. lim, chl, loc. carbn	51.0 - 52.5	1029	0.5	<0.07
						40		51.1-51.2 irreg. qz str. - 1-3mm, carb str.		- blebby loc py						
						30		51.25 QZ CB str, zone to 2cm		- py blebs loc.						
						25		51.25-52.5 - common lim ± qz, cb fr.								
52.5	57.3							w-m fr., red. unalt., loc. ep. loc qz vns.		py - diss		m-s chl, lim fr, loc. carbn near qz str.	53.2 - 54.5	1030	0.5	<0.07
						20		53.35 - QZ str. 1-3mm lim. w. carbn surrounding					55.6 - 56.2	1031	0.5	0.07
						20		53.73 - QZ VN 1.5cm, carb blebs, fragments of Syenite, lim. common, Carbn surr.		py. blebs						
						25		54.25 - QZ VN 5-8mm, irreg in fr		py blebby, tr. bl, bk metallic min.						
						30		54.25-54.45° - occas. qz str. 1-2mm								
						20		54.7 - QZ str - 1-2mm, s. chl. in S.		py in surr S.						
								55.88 - QZ VN - 1.5cm, banding common, abundant parallel lim fr., carbn to 20cm either side								
						20		56.55 QZ str. 1-2mm, lim in str								
						40		56.9 QZ str. 1-2mm, lim								
						20		57.3 QZ str. 1-2mm, lim								

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-11 PAGE 1 of 6 LATITUDE 236.1 DEPARTURE 1654.1

CORE SIZE BQ FINAL DEPTH 67.97 m DIP AT COLLAR -46 BEARING 336

STARTED AUG 28/1986 FINISHED AUG 29/1986 COLLAR ELEV. 1638.6 LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
0	6.3	—						OVERBURDEN - RUBBLE								
6.3	12.6	100						SYENITE - light gy to pinkish, m-c.g., loc. dir. texture 60-70°, 70-80% fs, 20-30% hb or alt. hb., m-s fr., loc. broken, lim on fr.		magnetite		loc. s. chl, ep.				
12.6	14.35	100						s-i fr.				s. chl, m-s lim., loc. s. ep., w-m. loc. carbn				
						50		13.3 Qz STR. 1-2mm								
14.35	14.65	100						as 6.30								
14.65	16.15	100						as 12.6				loc. s-i hem				
16.15	17.65	15						as 14.65				loc. s-i hem				
17.65	22.2	100						as 6.30								
22.2	23.45	100						- strongly chloritic, chlorite banding at 85° loc. lim. in fr and bands at 85° Qz bands loc. 22.4 Qz VN - irreg. blebby 0-12mm within conc. of s. chl. bands				s. chl, m loc. ep. w. cl.	22.2 - 22.7	YV 1101	<0.3	0.07
23.45	24.4	100				65		- s-i fr, broken, limonitic 23.55 - Qz VN, irreg. to blebby 2.5-3cm zone, very few mafics in surr. S.				s-i lim, s chl loc ep.	23.45 - 24.2	1102	<0.3	0.07

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-11 PAGE 2 of 6 LATITUDE _____ DEPARTURE _____
CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____
STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
24.4	24.5	100						SYENITE - s.fr. lim fr., few mafics		Mn on fr.		m.cl., w. lim,				
24.5						75		QZ VN - 5-8mm, cavitous, drusy, clay rich gouge below vein					24.2 - 24.7	1103	<0.3	<0.07
24.5	24.85	100						SYENITE - as 23.45, loc. hem					24.7 - 25.95	1104	<0.3	0.07
24.85	25.65	100						- m-s fr., dir. texture 80° hematitic, lim fr.				s. hem, m-s lim, w.cl., s.chl.				
25.65	25.95	100						- cl. a.				m-s.cl., lim				
						60°		25.9 - QZ, blebby, 2-3cm								
25.95	26.82	25	c.	40°				RHYODACITE DYKE - pale gy-gn, v.f.g., w.p., often broken Mn + lim on fr. m-s fr.				w. . ser. cl.				
26.82	32.55	~100						- as 25.95, loc. i fr, fr at 45° 32 - 32.4 - i. lim + Mn				loc. m.cl. loc. i. lim.	30.85 - 32.0	1105	<0.3	<0.07
32.55	32.85	100						SYENITE - s.fr + a, KD, parts fill fractures at 25°, irregular		Mn		s.cl., lim. chl	32.0 - 32.85	1106	<0.3	<0.07
32.85	33.70	100	c.	25°				RHYODACITE DYKE, m.gy-gn, s.fr to broken, lim fr at 25-45° loc bx fr. at 25°		Lim fr		loc. w. cl.	32.85 - 33.70	1107	0.3	<0.07

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-11 PAGE 3 of 6

CORE SIZE _____ FINAL DEPTH _____

STARTED _____ FINISHED _____

LATITUDE 236.1 DEPARTURE 1654.1

DIP AT COLLAR _____ BEARING _____

COLLAR ELEV. 1638.6 LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
33.70	34.05	100						SYENITE - sfr. - a, loc gougy, loc. irreg. qz str. at various angles ~25°		Mn on fr.		s, cl. lim	33.70 - 34.50	1108	0.3	<0.07
34.05	34.50	100						- s.a, cl., hem. on fr. at 30°				s-i cl, lim, hem. fr., s. chl.				
34.50	36.25	100						- s.fr. + limonite, ep in 35-40° fr.				s. lim, chl, w-mod hem in loc. fr.	34.50 - 35.85	1109	<0.3	0.07
						35		34.9 loc. peg. vein, 1.2cm					35.85 - 36.25	1110	1.0	<0.07
						30		36.0 qz str, 2-3mm drusy								
						30		36.1 irreg. qz str 1mm with lim fr								
						25-30°		36.25 qz str., 2-5mm, drusy								
36.25	37.8	100						as 34.50 with s. hem, loc. gougy to crumbly occas. +/-1mm qz str. at 25-40°					36.25 - 37.8	1111	0.5	<0.07
37.8	38.2	100						as 34.50								
38.2	38.6	100						SYENITE PORPHYRY m-s fr., m.a., ep in blebs + str. at 35°; 20-30% sub-euhedral, 1-1.5cm Ksp phenos.				m. hem, lim, chl.				
38.6	40.45	100						m. fr + a., occas. +/-1mm calc. str.				m-s. chl, m lim, loc. ep.				
								39.5 - 1m fr zone with 1mm calcite str.								
						45		39.8 - bx, sil. zone, 1-1.5cm, banded with fs. fragments								
40.45	40.75	100						1-i fr and a., cla. seam lower contact.				s. lim, chl, carb? loc. cl. ew. hem				

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-11 PAGE 4 of 6 LATITUDE DEPARTURE

CORE SIZE FINAL DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY LL.

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
40.75	42.06	80						RHYODACITE DYKE - buff to pale gn, m-s fr to broken		Mn on fr.		lim on fr. w.cl. ± sx.				
42.06	46.63	100						as 40.75								
46.63	46.9	100						SYENITE PORPHYRY s fr, m-s a., hem±lim fr at 30 - 45°				w-m cl, s. lim, s. chl, loc. ep.	46.63 - 48.16	1113	0.5	<0.07
46.9	47.05	100						RHYODACITE DYKE - as 40.75								
47.05	48.16	100						SYENITE PORPHYRY - s-i fr, blocky + broken, loc gouge				s-i lim, hem on fr., s.chl, w cl. loc. carbn?				
48.16	48.85	100						- s. fr, loc ep in str at 35-50°				s. lim, chl, carbn? w-m cl,				
48.85	49.95	100						- m. fr., loc s-i fr zones at 35°				w-m chl, w lim, loc s lim, chl, ep str in s fr. zones				
49.95	51.21	30						- i fr to gouge + crumbled				s.chl, lim, cl.				
51.21	52.35	100						as 48.85								
52.35	52.4							- i fr to crumbled + gouge		Mn common		m chl, lim, cl.				
52.4	52.6	100						AMPHIBOLITE - HB SYENITE - 75% hb or alt hb				w-m chl, carbn, ep.	52.35 - 53.0	1113	0.5	<0.07

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-11 PAGE 5 of 6 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
52.6	55.25	100						SYENITE PORPHYRY s fr., m-s a., ep in fr 35-50° 52.7 - qz str, 1-2mm				m-s lim, chl, loc. cb., ep, carbn	55.1 - 55.5	1114	0.5	<0.07
55.25	55.35					50		QZ VNS ZONE in syenite, irreg. zone, 5 cm, brecciated s. lim.				s. lim				
55.35	55.5	100						as 52.6								
55.5	55.85	100						- s. fr., cavitous irreg. qz str. common at 35° to 5mm				m, lim, hem s. chl, loc cl. near qz str.	55.5 - 55.85	1115	0.5	0.07
55.85	57.28	100						as 52.6, brecciated fr. occas, qz str too					55.85 - 57.28	1116	0.5	0.14
						25		56.05 - brecciated fr, 5-8mm, sil matrix, ep str common in area								
						10		56.2 - qz strs, mult. strs from 1-5mm irreg in 2cm wide zone								
						30		56.75 - brecciated zone - 1.2 cm, qz str. along bdy, ep str. common below this zone								
57.28	57.6	100						- wmfr., m. a., ep strs at 15° occas.				s. chl, w. lim w-m carbn ep in s/s, + patches				
57.6	57.8	100			± 45°			- s-i fr,				s. lim, chl, loc ep				

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. Yv-R-11 PAGE 6 of 6 LATITUDE DEPARTURE

CORE SIZE FINAL DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY LL

FOOTAGE		%	GRAPHIC LOG				%	DESCRIPTION	MINERALIZATION		ALTERATION		STRUCTURE	ASSAYS		
FROM	TO	RECOVERY	ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE ∠	MoS_2		VOL. %	MODE OF OCCURRENCE	VOL. %	TYPE MODE OF OCCURRENCE	KIND, DENSITY, ETC.	SAMPLE NO.	%	%
57.8	59.0	100						as 57.28								
59.0	59.25	100			0.45°			s.fr., ep stx, loc qz stx. at 40°				s.lim, chl, carbs loc. ep.				
59.25	69.97	100						w-m fr + cc, loc s.fr zones with s.a., ser, wkalt., ep stx at 15-75°				w-m chl, lim fr loc s.chl, lim loc. ep.				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-12 PAGE 1 of 5 LATITUDE 200.3 DEPARTURE 1786.9
CORE SIZE BQ FINAL DEPTH 67.36 m DIP AT COLLAR -45 BEARING 339
STARTED AUG 29/1986 FINISHED AUG 30/1986 COLLAR ELEV. 1645.1 LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
0	3.0							OVERBURDEN - RUBBLE.								
3.0	10.5	100						RHYODACITE DYKE.								
								- pale gn to pale orange to buff, m-s fr, loc broken, occas.		Mn on fr		m-ser, loc lim + lim fr, near contact w-m cl.				
					c.	80°		Small 1mm qz str at 45°								
														YV		
10.5	11.1	100						SYENITE - s-i fr + a.				s. lim, cl, chl, loc hem, carbn.	10.5 - 11.1	1201	0.5	1.37
11.1	12.3	100						- s fr, w-m a.				w-m lim, loc s. lim + carbn, w-m cl. s. chl.				
12.3	12.9	100						- s-i fr + a. to crumbly		Mn on fr		i lim, s chl, m cl.	12.3 - 12.9	1202	0.5	0.14
12.9	17.65	100						- s fr, i loc. fr, common at 30°,				w-m lim pred fr, w cl., s chl loc. ep.				
17.65	22.25	100						- s-i fr, fr at 25, 45, 80, loc. qz str.				m-s lim, s chl w-m cl., loc. hem	19.34 - 19.82	1203	0.5	0.21
						80°		19.54 - qz str, 3-5 mm, drusy				a. of mag., loc. ep zones	21.2 - 22.25	1204	0.5	0.34
						80°		19.62 - "								
						50°		20.73 brecciated fr zone, 1 cm, s.lim								
						40°		21.4 gouge in fr - 3-5 mm, lim + chl.								
22.25	22.35	100						i fr, s a.				s lim, m hem in fr, at 45° +				

#385

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-12 PAGE 2 of 5 LATITUDE 200.3 DEPARTURE 1786.9
CORE SIZE FINAL DEPTH DIP AT COLLAR BEARING
STARTED FINISHED COLLAR ELEV. 1645.1 LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
22.35	22.46	100						i fr, pink to creamy coloured with distinct banded flow textures and lack of majics				s lim.	22.25 - 22.7	1205	0.5	1.37
22.46	22.48				85-90°			Qz VN - 2.-2.5 cm, partially banded, gouge at top contact.				lim + lim fr				
22.48	23.37	100						SYENITE - s-i fr, loc. dir. texture 80° loc small irreg qz str.				s lim, chl, loc hem w-m cl.	22.7 - 23.45	1206	0.5	0.48
23.37	23.45	100						- as 22.35, 90° banding								
23.45	24.2	100						s-i fr + a. 23.97 gouge zone S. hem + lim				s lim, cl, loc hem carbn?, loc ser.	23.45 - 24.4	1207	0.5	0.41
24.2	24.4	100						as 22.35, irreg. banding 85-90° loc. irreg qz				hem fr.				
24.4	25.7	100						s. fr + a				m-s lim, w-m cl., loc hem of Lib, loc s. chl, ser	24.4 - 25.7	1208	0.5	0.14
25.7	27.45	100						i fr, loc crumbly zones, fr at 50°				s. lim, chl, carbn m-s cl., loc hem fr at 45°, loc ep.	25.7 - 27.45	1209	0.5	0.27

#355

KERR ADDISON MINES LIMITED

VIC · PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-12 PAGE 3 of 5 LATITUDE DEPARTURE

CORE SIZE FINAL DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
27.45	28.5	100						SYENITE - s-i fr, m-s a., loc. banding as 22.35, loc irreg. qz str.				s.lim, w-m cl., loc. hem	27.45 - 28.5	1210	<0.3	0.62
						85°		27.45 - irreg. banding as 22.35								
						85°		27.57 - "								
						85°		27.58 - irreg qz vns, 1-1.5 cm								
						85°		27.58 - 27.65 - irreg. banding offset by 45° fr.								
						43°		27.85 - 28.05 - irreg. qz vns to 1.5cm								
						45°		28.15 - qz str., 1-3mm								
28.5	28.75	100			75-80°			as 22.35					28.5 - 28.75	1211	<0.3	0.34
28.75	29.87	15						i fr to crumbly				s.lim, chl, w-m cl.				
29.87	32.0	100						DACITE FELDSPAR PORPHYRY m.gn, soft chl. matrix with 26-30% sub-euhedral, cl.a. feldspar phenos, 1-4mm in size, 5-10% weathered mafic phenos, m fr, loc broken; spotty lim ± hem from all. if mag.		Mo on fr.		m-s cl, m, loc lim s chl.				
32.0	39.3	100						- fresh equiv of 29.87 - m gy-gn to purplish v.f.g matrix, pale gy-gn feldspar phenos, bb + chl make up mafics, loc. alt as 29.87 around loc fr, loc. ep str at 50° with surrounding pot. a.				m chl, w loc lim loc. cl., pot.				

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-12 PAGE 4 of 5 LATITUDE DEPARTURE

CORE SIZE FINAL DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
39.3	39.35	100				70		- crumbly lim-cl zone				s. lim + cl.				
														YV		
39.35	42.06	100						i fr + a.				i lim + hem, s.	39.3 - 40.54	1212	0.3	0.07
								40.1 - 40.54 - lim gouge. 20% Rec.				cl + ser a. of fs	40.54 - 42.06	1213	0.5	0.07
								41.9 - crumbly zone								
42.06	45.3	100						- m fr. s.a., loc carb. str at 45°				s. hem, loc s. lim	43.59 - 45.11	1214	0.5	0.07
												s. cl, ser of fs				
												s. cht, lim fr.				
45.3	46.25	100						as 32.0, rel. unalt.								
46.25	46.9	100						m fr, m-s a.				m-s hem, lim fr,				
						10°		46.35 - Two carb. str 1cm apart 2-5mm with lim				s cl + ser of fs.				
46.9	50.05	100						as 32.0, rel. unalt. loc. alt around fr.				loc cl, ser, lim				
						40		48.3 qz str, 2mm, light gn								
50.05	51.24	100						m-s fr + a., loc carb str at 30-40° with lim + hem				s hem, loc s lim, s. cl + ser of fs s. cht.				
51.24	57.75	100						as 32.0 rel. unalt. with loc zones as 50.05 around fr., loc carb str common 0-50° mainly 45°								

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-12 PAGE 5 of 5 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH 67.36 m DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
57.75	59.65	100						m-s fr, m-s a., common carb str at 30°, loc crumbly zones with s-i cl				m lim ± cl ± sw of fs, s chl,	58.78 – 59.13	1215	1.0	<0.07
					top	45		58.87-58.99 Qz-cb-lim vn								
					bot	25		very fr to brecciated with blk carb								
59.65	64.15							rel. unalt with loc alt around fr zones				loc s chem, lim, cl, sw chl.				
64.15	64.55				c.	70		- SYENITE - pink-gn mottled s.fr. with chl + ep in fr fs as fragments, loc carb str.				s. chl loc ep				
64.55	67.36				c.	45		rel unalt, m-fr, loc. carb str at 45-60° with lim + hem				m chl, loc ep, lim, hem				

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

#388

DDH No. YV-86-13 PAGE 1 of 4 LATITUDE 272.3 DEPARTURE 1997.5
CORE SIZE BQ FINAL DEPTH 55.17 M DIP AT COLLAR -46° BEARING GRID NORTH
STARTED Aug 30/86 FINISHED Aug 31/86 COLLAR ELEV. 1653.7 LOGGED BY RP

FOOTAGE METERS FROM	TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	% Ag	% Au
0	2.0							Overburden								
2.0	11.15	100	S	P	–	–		PORPHYRITIC SYENITE :				sl to mod chl prop. alteration				
								Pink K-spar phenos 1-2cm 25%				cp/chl				
								Patchy variable hornblende content 10–30%								
								Grey to pink K-spar matrix								
11.15	12.6	100	S	P				SYENITE :				sl to mod prop^n				
								Dark green to pink								
								Dense hornblende 60%								
								layering of hbld 70° @ 12.5m								
12.6	16.5	100	S	P				SYENITE :				Mod prop^n				
								pink, non porphyritic				cp/chl/ox of matrix,				
								broken to crushed core 14.0–14.6				hematite staining				
														YV		
16.5	19.15	100	S	P				SYENITE BRECCIA :				Mod prop^n	16.50 – 17.70	13-01	0.5	<0.07
								Red to pink								
								healed breccia								
								Strong hem staining on								
								and adjacent to dense fracture net.								
19.15	19.35	100	V	–		35		VEIN :					17.70 – 19.35	13-02	1.0	<0.07
								Qtz carbonate, mylonite								
								vein @ 35° with sheared								
								19.15 to 19.35 at 35°								
								Sy Sy								
								Grey Qtz								
								whitecomb sheared hematite								

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-13 PAGE 2 of 4 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

~~FOOTAGE~~ METERS FROM	TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MODE OF OCCURRENCE	ALTERATION: VOL. %	TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	% Ag	% Au
19.35	23.15	100						SYENITE: Pink to beige striped Foliation of hbld 70° Rusty shears: 19.8 – 20° 20.6-20.8 – 40° 21.3 – 35° coarse bx adj to both of these with hm stg good solid core.				Med prop^n patches of carbonatite & hornblende.				
23.15	23.8	100						SHEARED SYENITE: Shearing concentrated 23.15-23.3 and 23.6 – 23.8 Hybrid w/ qtz & carbonate Grays to red				Prop^n, carb^n	23.15 – 23.8	YV 13-03	0.5	0.21
23.8	35.15	100						SYENITE: Pink to grey to buff Scattered qtz veinlets 26.5 – 1 cm QV, rusty, 15° 27.9-28.0 – close spaced frac & QV @ 40° 29.1 – 29.2 – 1 cm QV with hbl selvage rusty halo 5 cm each side @ 60° Hbld foliation 70°				- Sl to mod prop^n - Minor carb^n of hornblende				
35.15	35.75	100						DACITE DYKE: Dark grey, fine grained Slightly fractured.				Sl prop^n (epidote spots)				

#358

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-13 PAGE 3 of 4 LATITUDE ____ DEPARTURE ____
CORE SIZE ____ FINAL DEPTH ____ DIP AT COLLAR ____ BEARING ____
STARTED ____ FINISHED ____ COLLAR ELEV. ____ LOGGED BY ____

~~FOOTAGE~~ METERS FROM	TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE AXIS	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MODE OF OCCURRENCE	ALTERATION: VOL. %	TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	% Ag	% Au
35.75	39.60	100						SYENITE: 35.75-36.4 bleached to orange mnor s/c vns, good core 36.4-36.8 broken rusty, crg 36.8-37.85 relatively fresh, minor prop^n along frac. 37.85-38.30 Muddy, shattered, ang^r prop^n 38.30-39.60 rel fresh good core 38.95-39.0 siliceous shear				Varies from rel fresh (sl prop^n) to crushed agillized (muddy) core.					
39.60	40.35	100						SYENITE: pnk to white (bleached) carbonatized mafics				carb^n	39.60 - 41.00	YV 13-04	<0.3	<0.03
40.35	40.43	100						VEIN: Dense grey quartz								
40.43	41.00	100						SYENITE: Bleached to rusty zoned core				carbonatized mafics				
41.00	41.95	100						SYENITE: White to red Brecciated with quartz stringers and rusty patches 41.3-41.4 Rusty shear with Qtz and carbonate, vuggy					41.00 - 41.95	13-05	<0.3	0.69
41.95	42.35	100				45		VEIN: Qtz/carbonate/feldspar @ 45°					41.95 - 42.35	13-06	1.0	10.8

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-13 PAGE 4 of 4 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: % STRUCTURE TO CORE ∠	GRAPHIC LOG: % MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
42.35	42.65	100						RHYODACITE DYKE : Buff to rusty Fine grained, fine qtz eyes				—		YV 13-07	0.8	0.14
42.65	43.30	100				45		VEIN : Qtz carbonate feldspar @45° Rusty, mottled Tight, good core					42.65 – 43.30	13-08	0.5	0.07
43.30	45.60	100						SYENITE : pink to white (bleached) Numerous qtz stringers (5%) @40° Mafics eliminated				carbonatized argillized	43.30 – 44.10 44.10 – 45.60	13-09 13-10	0.3 <0.3	<0.07 <0.07
45.60	48.60	100						SYENITE : pink to buff to rusty scattered QV (3%)				carbonatized hbld	45.60 – 47.25 47.25 – 48.60	13-11 13-12	0.3 0.3	<0.07 <0.07
48.60	48.90	100						SYENITE / VN Sheared syenite with quartz veining				carbonatized	48.60 48.90	13-13	0.8	1.44
48.90	50.10	100						SYENITE : pink to buff patchy carbonatization of hbld 49.6 – 49.8 rusty, broken 49.7 – 50.1 1-2cm hypersphenes		48.9 – 49.35 49.35 – 49.60 49.60 – 49.80 49.60 – 50.1	100% 50% 50%	carbonatized hbld " rusty, broken, argillized carb hbld	48.90 49.20	13-14	<0.3	0.07
50.10 EOH	55.17	100						SYENITE : Grey to pink fresh foliation of hbld @ 60°		—		Fresh	—			

KERR ADDISON MINES LIMITED

DDH No. YY-86-14 PAGE 1 of 9

CORE SIZE BQ FINAL DEPTH 82.30m

STARTED 31st AUG FINISHED 1st SEPT 86

VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

LATITUDE 222.8 DEPARTURE 1998

DIP AT COLLAR -48° BEARING GRID NORTH

COLLAR ELEV. 1660.3 LOGGED BY KH

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
0	2.8							O/B.						YY		
2.8	7.50			fr.	20, 30, 70		3-5	SYENITE PORPHYRY				l. wk $CO_3^=$	3.8 - 4.9	1401	0.5	0.07
			$CO_3^=$	str^s 1mm		30°		KF, pink, ⇒1.5cm 15-20% in use				W. cl.				
			" "	bleached ⇒				alaitic pink w. 15% mafics (Hb)				W-m. prop.				
				1.5cm		70°		⇒ Chl+ep+ $CO_3^=$. Vague splotches.				local S. hem				
			l. hem -	$CO_3^=$ 1mm		30-45		m. mafics								
								3.8-4.9m w-m. shear/fz 30-40°					6.2 - 6.5	02	1.0	<0.07
								6.2-6.5m " " "								
7.5	11.6m							↓ HEM a/SHEAR?ZONE					7.5 - 8.58	03	1.0	<0.07
								Brick red, no distinguishable texture.								
								m. lim, patchily pervasive. w-m. cl. a.					8.58 - 10.06	04	0.5	0.14
11.6	13.3			"				DACITE FELDSPAR PORPHYRITIC DYKE					10.06 - 11.60	05	1.7	0.14
				fr.			60°	↓ fract^d, m hem. Mottled gn-bn,								
								brick red, limonitic orange. W-m					11.60 - 13.30	06	1.0	0.14
								lim concentrated on fract^s (Carbonate?)								
13.3	16.5							RHYODACITE FELDSPAR PORPHYRY DYKE								
			str^s - cl-chl-	$CO_3^=$				Med-dk. gy.bn. f.gr^d mx, w/ vague								
			⇒ 2mm			20-30°		gy. fs ⇒ 2mm, 10-15%. Mafics								
			+ X-c			50-70°		(Hb) ⇒ s. chl+epid. W. Chl-lim								
			W gouge					fract^s, W. calc microfract^s. v. W.								
								patchy hem. W. ser. a.								
16.5	18.9							m. BX. Chl-ep-hem-$CO_3^=$ a. ZONE					16.50 - 18.90	07	1.0	0.27
			chl-epid	str^s				mod. abund. Chl-ep. str^s ⇒ 1mm								
			⇒ 1mm			10-20°		braided ⇒ 1cm. w-m hem patchy								
								a. W-m. cl, m. $CO_3^=$. all v.								
								patchy.								
								13.55-13.90 l. hem gouge 40°								

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-14 PAGE 2 of 9 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY KH

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Pb	ASSAYS: % Zn
18.9	20.2							RHYODACITE FELDSPAR PORPHYRY DYKE As at 15.3m								
20.32	37.50							m. hem, patchy. m. cl a. of fs → white, v. soft, 20%. Overall rock pink + dk. gy mottled. Mafics (HS) → Chl + epid. ~3mm splotches; avge 2mm. Fract^s - w-m ser-chl-$CO_3^=$; w/ w. ser-chl → 1cm selvedge; patchy s. hem. w-m magn.				Fract, mod abund 20-70°. 32.95-34.35m, s. hem. fract^s, @ 10° to core.					
37.50	39.15							As at 13.3m. Hb ~ 15%		Trace f-med. gr^d anhed. PY → 0.5mm, assoc^d w/ Mafic splotches.		Fract^s, w-m lim $CO_3^=$, @ 40-70° to core				
39.15	40.80							increased fract., w-m cl. a, espec. @ 39.9-40.0m & 40.45-40.55m. Patchy gn-bn				str^s + vnlts → 1cm, ANK @ 20°-40° to core.				
40.80	41.25							s. cl-hem. g: core v. soft, crumbly. i. cl. a fs. 41.20 cl. gouge @ 60°. s. hem. @ lower contact, 60°, 5cm					40.80-41.45 41.45-42.10	08 09	1.0 0.5	0.07 <0.07
41.25	41.45							RHYODACITE DYKE Buff, f-med gr^d, massive, hard. Mod. abund. Mn dendrites on fract^s. Core v. broken. Noncalc. Nonmagn. w-m cl. a on fracts. No vis. su				Fract.^{s} @ 30, 70° 41.35m - q-$CO_3^=$ vnlt, 1cm, 65°, M. gy. and brown, braided, w/ → 5mm open space.				
41.45	42.10							DACITE FS PORPHYRY DYKE Med. bn, w/ wh. f cl. a. fs to								

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YY-86-14 PAGE 3 of 9 LATITUDE DEPARTURE

CORE SIZE FINAL DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY KH

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
								2mm, ~35%. W hem. w Mn. No				Fract' @ 25°, 70° w/ W. $CO_3^=$, W.				
								vis. mafics. Mod well fract'				Mn.				
42.10	44.60							RHYODACITE DYKE								
								As a- @ 41.25m.				Fract' 15°-70°, W Mn dendr.				
								V well, ang. fract'. V. faint off-wh			43.0-43.30 - qzy str's, few, →2mm					
								i. cl. a specks → 1mm, ~3% = ?fs.				f.gr', lt. gy qz, w/ minor open				
								W. hem - lim on some fract's.				sp., @ 30-50° to core.				
44.60	50.0m							i HEM-LIM-CL a. ZONE (SY?)								
								contact v. broken, w/ m-s hem, lim				Fracts @ 20-80° to core				
								banded @ 50°.			47.0 m gouge @ 60°, 3cm.					
								Med. bn. to pk. red patchy. Mod.			47.6m-48m gouge @ 60°					
								soft. V. well fract', s. crumbled, espec.			47.2-47.6m - qzy str's @ 25°, 2mm.					
								btwn 46.40-46.50m.				s. lim. fract'.				
								Below 48.0m, have less total destruction								
								of texture; see vague suggestions of					44.6 - 46.0	10	0.5	0.34
								pk-bn fs xls → 5mm, and gn-bk					46.0 - 47.5	11	0.5	<0.07
								mafic splotches → 5mm (Chl-Ep),					47.5 - 49.0	12	0.5	<0.07
								irreg. distributed thro'out.					49.0 - 50.0	13	0.5	<0.07
50.0	58.33							SYENITE PORPHYRY								
								Top contact - 5cm i. epid then into				fracts - W-m ep-chl to 2cm, W-m				
								less a. syenite, pk + dk. gy mottled				$CO_3^=$, m. lim. (@ 20° to core)				
								KF, pk, irreg. to subhedral shapes to 2cm long, 15-20%				W. ser.?				
								Mafics, dk. gy-gn splotches to 1cm become				@ 52.0m - 2cm ep-chl vn. @ 60°.				
								incr. diffuse d/h. s. chl, s. magn. W-m								
								$CO_3^=$ thr'out. W. Lineation of KF								
								+ mafics at 60° to core. Mod fract'.								
54.8	55.25							m-s. lim, w-m cl, w calc. mod				fracts 45°-70° to core, w lim. $CO_3^=$				
								well fractured. By 53.0 m, mafics								

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-14 PAGE 4 of 9 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY KH

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Au	ASSAYS: % Au
								subhed. to ragged, ± magnetic. W. chl-ep. on fracts. W. str. a offs.								
57.75	58.33							Broken rock. m. lim. staining, W. cl. a. Mafics → chl + epid. splotches, 3mm, 15%. KF ⇒ large pink areas to 2cm. m-s CO_3= on fracts, W. CO_3= thruout. Epid. incr d/h.					57.75 - 58.83	14	0.8	<0.07
													58.83 - 59.64	15	0.5	<0.07
													59.64 - 61.87	16	0.5	<0.07
58.33	58.45							SHEAR ZONE @ 25° to core s. hem-epid-chl banding. X-C by gy. CO_3= str^s to 3mm, @ 50° to core. Dark reddish-purple + green.								
59.45	60.18							s. chl + epid, s. fract^d/bx^d rock, DK gn. overall, w/ pk KF remnants. Angular shapes to 1.5cm. W CO_3= thruout, conc^d on microfract^s. hem. incr. d/h.								
59.1	59.64							s. hem-ep-chl mottling/banding @ 50° to core.								
60.18	61.08							Pink streaked/sheared rock. No sy. Texture lost. i. fract on v. fine scale. W. CO_3=, few CO_3= str^s to 2mm @ 20-35° to core. w-m lim. staining. Nonmagnetic. Rare broken cubes of PY to 3mm, v. fract^d + X-C by CO_3= str^s. Minor displacement to 1cm, RH, on fract^s.								

KERR ADDISON MINES LIMITED

DDH No. YV-86-14 PAGE 5 of 9

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

CORE SIZE BQ FINAL DEPTH

STARTED FINISHED

LATITUDE DEPARTURE

DIP AT COLLAR BEARING

COLLAR ELEV. LOGGED BY KH

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
61.03	61.87							m-s. lim. staining. Coarsely fract^d.								
61.87	62.32							SYENITE Salmon pk w/ dk gn. gy mafic splotches to 4mm, 5-15%, w-m magnetic. w. prop. a, s. K^t. w-m lim. fract'g, mod abund. x-c by $CO_3^=$-ep.-hem str^s <.5mm. @ 50-70° to core.								
62.32	62.40							s. hem. microfract'g abund. m-s epid-chl thr'out. w-m $CO_3^=$, lim.				Fracts, main direction @ 70° to core				
62.40	64.78							As at 61.87. No obvious KF phenos, cse grd thr'out. v. w. lineation of mafics @ 60°-45° to core. w. ser a.				fracts @ 50-80°, few. w-m lim-$CO_3^=$. w-m ep.				
64.78	64.85							i. hem. microfract'g + epid.								
64.85	65.63							As at 62.40m. Incr. mafics destruction a/h. Grades to								
65.63	66.15							SHEARED SYENITE? Mottled pk, high K^t. w. cl. a. s. lim. fracts @ 30°, 60° to core. w-m hem (pp) streaks + irregular patches of hem (SPEC) to 2mm. Nonmagnetic. w. $CO_3^=$, hem streaks at ∠10° to core.								
66.15	66.32							i. lim/$CO_3^=$? zone, or bn, w. irreg.								

KERR ADDISON MINES LIMITED

#388

DDH No. VV-86-14 PAGE 6 of 9

CORE SIZE _____ FINAL DEPTH _____

STARTED _____ FINISHED _____

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

LATITUDE _____ DEPARTURE _____

DIP AT COLLAR _____ BEARING _____

COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE AXIS	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
								lenses of CA to 2mm wide, <2% overall @ 30-45° to core. Micro bx								
66.32	67.0							As at 65.63m. Alteration of mafics decr. d/h.								
67.0	69.78							SYENITE l. pk, K+ flooded, w/ ak gn-bk subhedral to ragged mafics (Hb) to 4mm, avge 2mm, ~10-15%. m chl-epid - CO_3= a. s. magnetic. Poor lineation of mafics @ 45° to core. (Similar to 61.67m)			Fel.	s. lim. fracts, w. ser.	10-20% 60-70%			
											Or.	microfract/hairline fracts abund.				
69.78	70.0							Carbonate str's/vn lt's to 4mm, parallel at 30° to core. ~3% of rock. Or. bn + wh. striped. w. hem. in spots + around CO_3= fract's.								
70.0	71.08							As 67.0m								
71.08	71.61							DACITE (FELDSPAR PORPHYRITIC) Top contact, v. irreg. + ~@ 90° to core. DK. gn. bn, f.gr'd, mod. silic. rock, w/ pk-red hem stained fs, m cl. a, to 3mm, 5-7%, vaguely visible. w-m pp. hem patches, w-m lim-CO_3= str's to 3mm, @ 30-50° to core, mod abundant. w. magnetic, patchy. w. ser. on fract. Lower contact is mod. sharp, at								

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

#388

DDH No. YV-86-14 PAGE 7 of 9

CORE SIZE _____ FINAL DEPTH _____

STARTED _____ FINISHED _____

LATITUDE _____ DEPARTURE _____

DIP AT COLLAR _____ BEARING _____

COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Au
								35° to core, w/ m-s hem-lim over 10cm, and Tr – ½% v.f. diss'd PY in fracts.								
71.61	72.20							SYENITE s. ser a. pK to v. pale gn-gy mottled. s-l K+ thr'out. No obvious large KF phenos. w-m pp-red hem. patches to several cm. Pale gn gy patches are i. ser. a., up to 5mm across, avge 2-3mm, ~10% (a. mafics?) Ser. str's to 0.5mm @ 15-30° to core. w-m epid, few bleached looking areas.				w-m lim fracts @ 15-30°, 70° Few PY distrib'd along fracts, to 0.5mm, overall ~1%.	71.61 - 72.5	17	<0.3	<0.07
72.20	72.27							Bleached section								
72.27	72.50							As 71.61m								
72.50	72.64							i-s. lim staining @ 60° to core. i. ser. a mafics contain v. small black specks, <0.25mm, ? hem. Non magnetic. w. $CO_3^=$ thr'out.					72.5 - 73.8	18	<0.3	<0.07
72.64	72.78							As 72.27								
72.78	74.35							i. lim stng. Mod well fract'd, abund. gr-lim. microfract/network. No vis. sx. Nonmagnetic. Few areas of i. ser. a. pale gy.				Few $CO_3^=$ ± qz str's to 2mm @ 20-40° to core, f-gr'd, white to lt gy	73.8 - 74.35	19	<0.3	<0.07
74.35	75.15							QZ FLOODED BRECCIA ZONE Top 'contact' at 60° to core					74.35 - 75.15	20	0.3	<0.07

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-14 PAGE 5 of 9 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS %	ASSAYS %
								Creamy/pale bn mottled.		Tr. PY, po in c. to 1mm						
								i-c silica flooding, v. f. gr'd at		on fracts + in more						
								35° to core. $CO_3^=$ Strs, wh, f.gr'd		rhic. areas.						
								1, 2mm @ 30°, rare. Loc. w. ser.								
								a.								
								11.83 - 76.03 - i. bx', 2ng. silic frags								
								1 to 2cm in yell-bn, w-m ser,								
								i. sil. mx. Frags yellish-gy to bk,								
								v. f. gr'd (?). Nonmagnetic. Wh. xlline								
								CA in 5mm patches in mx. Bottom								
								of bx 30cm. marked by 1.5cm CA								
								vn, ese xln, lensy @ 30° to core								
								approx subparallel w/ lim. fracts.								
15.15	76.3							SYENITE i. ser. a.								
								Bleached/cm. coloured w/ pale				FEW CO_3 93 str's	1-2mm, @			
								gy-gn i. ser. mafics to 2mm, 5-1%				30°-60° to core.				
								Vaguely defined, FK specks = HEM?								
								Local. 5. lim fracts w/ selvedges ea			78.0	QV, 2cm, lt-gy	massive @ 70° to			
								10cm @ 50° to core. W-m hem				core.				
								str's to 1mm @ 30-60° to core.					75.15 - 76.15	21	<0.3	<0.07
								Lim. micro/hairline fract. network					76.15 - 77.7	22	<0.3	<0.07
								at 75.73 - 75.72, 76.03 - 76.07, 76.62 -					77.7 - 78.3	23	<0.3	<0.07
								76.80, 77.10 - 77.70m.								
								Alteration generally decr. dwn.								
								At 77.70m, have i. ser, w cl. a,								
								mafics ~ 7-10%.								
78.3	92.3							SYENITE PORPHYRY								
								Wh-pk mottled. Mafics to 2-3mm,				Few. sp. str'g @ 60° to core				
								gn-bk splotches ~10%. Magnetic.				Rare qzy str to 1mm @ 60°				
								W-m K^+, w. ser, w-m prop. a.								

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. VV-86-11 PAGE 3 of 3 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY S.H

FOOTAGE		%	GRAPHIC LOG				%	DESCRIPTION	MINERALIZATION		ALTERATION		STRUCTURE	ASSAYS		
FROM	TO	RECOVERY	ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE <	MoS_2		VOL. %	MODE OF OCCURRENCE	VOL. %	TYPE MODE OF OCCURRENCE	KIND, DENSITY, ETC.	SAMPLE NO.	%	%
								m-m lim. fract's @ 30°-60° to core [illegible], especially btwn 86.0 - 86.25m.								
32.30								E.O.H.								

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-15 PAGE 1 of 4
CORE SIZE BQ FINAL DEPTH 60.35 m
STARTED ____ FINISHED ____

LATITUDE 271.4m N DEPARTURE 1947.8E
DIP AT COLLAR -47 BEARING 0.0 (Grid North)
COLLAR ELEV. 1655.7m LOGGED BY JP

~~FOOTAGE~~ METERS FROM	TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS %	ASSAYS %
0	3.96							Surface rubble				Note: contamination from is to alteration		Generally fair to good preservation of primary texture		
3.96	6.6	100	Sy					SYENITE: Pink to white, c.g. slight frac		3cm s/l stringer @ 5:49 30°		slight: carb° of fracs ic prop° / chlor fcp				
6.6	7.0	100	Dy					MAFIC DYKE: Hand black, sl frac		—		Fresh				
7.0	13.8	100	Sy					SYENITE: pink to white to rusty, cg mod frac		—		slight prop°				
13.8	13.9	100	SH					SHEAR rusty, soft		—		arg°, sl prop°				
12.9	14.63	100	Sy					SYENITE: pink, fresh		—		—				
14.63	14.80	100	Da					DACITE: dark grey, fine grained strong rusty fracturing		—		mod chlor°				
14.80	15.90	100	Sy					SYENITE: Hematite stained		—		mod. prop°				
15.90	24.60	90	Sy					SYENITE: white to pink to green moderately hard		—		slight prop°				
24.6	31.60	100	Sy					SYENITE: buff, cg, soft well frac, numerous dark hairline Imonitic frac		—		Strong carb° of bbld.				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-15 PAGE 2 of 4 LATITUDE ____ DEPARTURE ____
CORE SIZE ____ FINAL DEPTH ____ DIP AT COLLAR ____ BEARING ____
STARTED ____ FINISHED ____ COLLAR ELEV. ____ LOGGED BY ____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	Ag gm/T	Au gm/T
31.60	31.90	100	Sy					SYENITE: Soft, rusty, sheared @ 30°								
31.9	37.10	100	Sy					SYENITE pink to white, cg sl frac, hard		—		slight: sil'n carb'n strong: chlor'n				
37.10	39.0	100	Sy					SYENITE: green to pink Silicified, cut by stringers of qtz carb @ 30°, hard Mafics reduced to lt grn chlor/carb with remnant magnetite.		3% QV, trace py		strong: sil'n carb'n chlor'n				
39.0	35.5	100	Sy					SYENITE: buff, cg, hard rusty frac @ 30°		—		strong carb'n mod chlor'n				
35.5	37.55	100	Sy					SYENITE: pink to rusty, mod fr		—		mod: carb'n chlor'n slight epid'n				
37.55	39.50	100	Sy					SYENITE: buff, cg, sl frac		—		strong carb'n mod chlor'n				
														YV	~~0.04~~	~~0.5~~
39.50	41.60	100	Sy					SYENITE: buff to rust, soft		—		intense carb'n/bkd sl chlor'n	39.50 – 40.54 40.54 – 42.06	01 02	~~0.3~~ <0.3	~~0.07~~ <0.07
41.60	42.06	100	Sy					SYENITE: buff to rust, soft muddy crush zone		—		intense carb'n sl chlor'n				
42.06	42.70	100	Sy					SYENITE: buff to rust		QV: 1cm @ 42.2 ~ 70° 2cm @ 42.3 ~ 70°		intense carb'n sl chlor'n	42.06 – 42.70	03	0.3	0.09

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-15 PAGE 3 of 4 LATITUDE ____ DEPARTURE ____

CORE SIZE ____ FINAL DEPTH ____ DIP AT COLLAR ____ BEARING ____

STARTED ____ FINISHED ____ COLLAR ELEV. ____ LOGGED BY ____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS %	ASSAYS %
42.70	44.50	100	Sy					SYENITE: buff to rust. soft crush zone		—		mtause carb?	42.70-44.50	YV 04	<0.3	<0.01
44.50	45.60	100	Sy					SYENITE: pink to white to rusty cg		—		moderate carb" chlor slight epid?	44.50-45.60	05	"	"
45.6	46.63	90	Sy					SYENITE: rusty, soft, crush zone		—			45.6-46.63	06	"	"
46.63	48.30	100	Sy					SYENITE: pink to white to rusty		—		moderate-carb" chlo" slight epid"	46.63-48.30	07	"	"
48.30	49.68	85						SYENITE: rusty, soft, crush zone		—			48.30-50.40	08	"	"
49.68	50.40	100	Sy					SYENITE: buff to rusty, well frac, soft		—		mtause carb? mod chlor?				
50.40	51.21	100	Sy					SYENITE, soft, rusty, crush zone		—		mtause carb" mod chlor"	50.40-51.21	09	"	"
51.21	52.40	100	Sy					SYENITE cream to buff to rust, brecciated		moderate silicification		mtause carb" slight chlor"				
52.40	52.73	100	Sy					SYENITE: rusty, soft, crush zone		—		mtause carb? slight chlor"	51.21-52.73	10	0.3	0.14
52.73	53.70	100	Sy					SYENITE: rusty with white qtz brecciated		10% stringers @ 25°		mod sil" mtause carb"	52.73-53.70	11	0.8	0.41

#358

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-15 PAGE 4 of 4
CORE SIZE _____ FINAL DEPTH _____
STARTED _____ FINISHED _____

LATITUDE _____ DEPARTURE _____
DIP AT COLLAR _____ BEARING _____
COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
53.70	54.70	100	Sy					SYENITE: rusty with milky dense Qtz veins		50% QV		Strong si/□	53.70-54.70	YV 12	0.8	0.27
54.70	55.30	100	Sy					SYENITE rusty, brecciated		10% QV		moderate si/□	54.70-55.30	13	0.8	0.48
55.30	59.30	100	Sy					SYENITE: buff to green		—		strong carb□ mod chlor□ slight epid□	—	—		
59.30	60.35 EOH	100	Sy					SYENITE white to pink		—		mod chlor□ slight carb□ epid□	—	—		
								END of HOLE								

#385

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YY-86-16 PAGE 1 of 3 LATITUDE 274.5 DEPARTURE 2047.6

CORE SIZE BQ FINAL DEPTH 75.50m DIP AT COLLAR -47° BEARING 5.41 - 340°

STARTED 2nd Sept 86 FINISHED 3rd Sept 86 COLLAR ELEV. 1653.6 LOGGED BY KH

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% FeS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Pb_3	ASSAYS: % Zn
0	7.62							CASING								
7.62	17.70							F SYENITE i. weathered								
								v. Rotten rock. i. cl, m. lim, loc. w-m			Rare	q-str to 1mm, 20°	30° to core			
								hem. Easily crumbled by hand.			Abund	m. lim fract.	network			
					15 - 15.70m			- see vague, c.gr^d texture - wh.								
								i. cl. a fs 2-3mm, ~50% and								
								gn-bk mafic splotches, i. chl-ep to								
								3mm. Intense weath^g may be								
								in part due to i. shrg? Hard to tell.								
17.70	19.40							SYENITE PORPHYRY								
								s weath^d. pK KF to 2cm, 30%.			Abund	t. w-m lim mafic	fracture fract^n			
								gn-bk mafics, s ep-chl. a (Hb) to								
								2mm, anh-subhedral, 20%.								
								w-m lineation of fs @ 50° to core								
								Loc. s. epid, espec. on fracts @ 50-80								
								w-m. cl. a, s. prop. a, w. K^+; alteration								
								variable.								
19.40	20.67							Same as 7.62m.						01		
								i. cl-lim a. Looks sheared,			Rare	$CO_3^=$ str to 2mm	@ 35° to core			
								espec. btwn 20.00 - 20.67m.						YY		
								Large subround - subang frags of					19.4 - 20.67	16D1	0.5	<0.01
								less i. altered rock to 6cm, in m.								
								incm, i. lim v. soft, crumbly mx. Frags								
								~70%. v w. loc $CO_3^=$ patches								
20.67	20.82							RHYODACITE DYKE								
								Upper contact at 45° to core, w/			Few	$CO_3^=$ str to 0.5mm	@ 20°-50° to			
								s. cl, white gouge, 1cm; 2cm w. banded				core, w/ up to 1cm	offsets.			
								Buff-beige, f gr^d, massive, w/ 1-2%								
								qz subhedral qz xls to 3mm, variable sized.								

#358

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-16 PAGE 2 of 9 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Mo	ASSAYS: % Au
								s. hem specks to 0.5mm dissem' thruout.								
								3-5% m-c cl. a, W. ser, W lim.								
								Wash on fracts.								
								Lower 10cm is i. lim. stained +								
								W. banded @ 30° to core. Broken								
								lower contact.								
													20.88 – 21.75	02	0.5	<0.03
20.88	21.75							Same as 19.40m.								
								i. lim, i. cl. a.			$CO_3^=$	str^s to 2mm, 20°, 45°, 50°.				
21.75	22.40							SYENITE PORPHYRY m.a.								
								Ragged 'contact' at ~ 60° to core.			FEW	$CO_3^=$ str^s to 3mm, @ 10-30° to				
								Pale green, w/ pale pink KF remnants				core.				
								to 1cm, rounded + fract^d ~20%.					21.75 – 22.4	03	0.5	<0.03
								Some are a rounded tabular shape,								
								W/ W. lineation at 60° to core. Matrix								
								is L. ser - ep - chl, W. $CO_3^=$; quite								
								soft.								
					22.15 – 22.25m			– less sheared looking, more clk +								
								chl. patches.								
						21.5m		– $CO_3^=$ - lim vnlt, 1cm, @ 70° to core.								
								w lim. envelope.								
22.1	22.80							Same as 20.88m					22.4 – 22.8	04	<0.3	<0.03
22.80	23.18							– RHYODACITE DYKE								
								i. lim, v. cl thruout, locally v.			Fracts @ 50° predom, 20°					
								Soft. W-m Mn dendr. on fracts.			Tr. v. f.gr^d dissem' PY					
								V W. $CO_3^=$.					22.8 – 23.88	05	<0.3	<0.03
								Lower contact broken, @ ~50°?								
23.18	23.88							SYENITE (PORPHYRY?) i. sheared								

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-16 PAGE 3 of 9 LATITUDE ____ DEPARTURE ____
CORE SIZE BQ FINAL DEPTH ____ DIP AT COLLAR ____ BEARING ____
STARTED ____ FINISHED ____ COLLAR ELEV. ____ LOGGED BY KH

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Mo	ASSAYS % Cu
								i. sheared, i. lim, m. loc. hem.				Fracts variable 10°-80°.				
								s. cl. a. m-s epid - ser? chl								
								Similar to 22.40m.								
23.88	24.44							QV/ser. a/SHEAR ZONE					23.88 - 24.44	03	<0.02	<0.01
						23.83		QV, 2cm lt. gy, @ 50° to core,								
								strongly fract'd/crackled.								
								Then mixed i. lim-ser. a w/								
								hem-silic frags to 2cm, rounded, for								
								10cm. Then sharp wh. gougey								
								contact @ 60° w/ wh-v. pale								
								gn mottled i. ser. a zone.				w lim fracts @ 60° to	core			
								v. w. Mn. PK clasts to 1cm are				Tr. bk. su. coating, 1	fract.			
								possibly KF? V. W. loc. CO_2=. Spotty								
								hem, incr. d/h to pp. band! +								
								streaks at 50-60° to core.								
								Lower cont. s. hem, @ 60° to core								
24.44	27.93							SYENITE PORPHYRY i. a, shrd					24.44 - 24.98	01	<0.03	0.56
								Similar to 23.13m. Loc. s. bx'd,								
								w/ pk. frags to 4mm. s-i cl,					24.98 - 26.48	02	<0.03	0.27
								m-s lim, m-s epid.					26.48 - 27.93	09	0.8	<0.01
					24.38-25.32			s. shearing at 30°-40° to core								
					25.43-26.58			a. decr'd; pk KF xl frags vis.				s. lm/hem fract's @ 30°-50°, few				
								Mafics dk gn + i. chl, w epid, to				26.13 - QV, 2cm lt gy - bn, v. fgr'd,				
								4mm splotches, ~20%.				noncalc, W. banded, mod botry				
								Hem. incr. d/h.				@ 80° to core.				
						26.98		core reddish + dk gn mottled due to								
								s hem. a, W. ser a.								
								Broken lower contact, at 45°? to core								
27.93	30.88							ANDESITE DYKE								

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-16 PAGE 4 of 9 LATITUDE DEPARTURE

CORE SIZE BQ FINAL DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
								Lt-med olive-gn to gy-gn. f.gr^d at				w. lim fracts @ 15°-20° to c.a.				
								contacts, f med. gr^d by 28.73m.				some w/ .5mm $CO_3^=$	str^s.			
								Mod fract^d. Minute bl. specks to								
								0.5mm, avge ~0.25mm, ~3-1% anh.								
								Assoc^d w/ wh/gy anhed. specks to 1mm,								
								2-5%. ($?CO_3^=$). These are loc. leasy,								
								@ 30° to core. Minute hem. specks								
								~5-7%. No vis. su. Nonmagn. ?Nonscale.								
				28.2	3-4	0.25		- v broken rock + wh. cl. gouge.								
30.82	31.34							SYENITE PORPHYRY, s-i.s								
								Both contacts are intrusive. Top								
								contact at 20° to core, lapped w/								
								few lenos of SYP. left in AND.								
								W-m ser. at contact. Rest is								
								DK. gn-med gn + pk-gy coarsely								
								infilled. PK. areas to 2cm, anhed,								
								are prob. remnant KF, 15-20%.								
								i. chl-epid, v.w $CO_3^=$, m-s magnet.								
								Some MGNT assoc^d w/ chl-epid masses,								
								Mafics ~5-20%, concentrated near								
								contacts. LOWER contact at 15°								
								to core.								
31.34	32.48							ANDESITE DYKE								
								Same as 27.93m								
32.48	37.98							IIb SYENITE								
								Broken top contact.				ep-hem str^s to 1mm,	at 30°-45°			
								W. ppy, w/ segregations of pale to				± $CO_3^=$.				
								salmon pink KF, rather fine grn dmy			33.13m – m-s. epid str^s to 1mm					
								true crystal shapes, to 2cm, 30-40%.				w-lim-hem fracts.				

#388.

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. YV-86-116 PAGE 5 of 9

CORE SIZE _____ FINAL DEPTH _____

STARTED _____ FINISHED _____

LATITUDE _____ DEPARTURE _____

DIP AT COLLAR _____ BEARING _____

COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: %	ASSAYS: %
								Mafics – dk gn, bk, mod to strongly chl-ep mgnt. W. $CO_3^=$, to 4mm max, avge 2-3mm, 7-15%.								
					21.3	1-2	36	s. loc. KF stng. W. ser. a.								
					36.3	1-2	.33	s. hem-clpd staining of fract's. V. broken rock.								
								W. lineation of mafics at 45° to cor								
27.93	33.71							DACANDRE SITE DYKE								
								Broken top contact.			$CO_3^=$	stgr at 10-20° to cor				
								DK gn gy, v.f.–f.gr^a, massive mod soft; m-s chl-ep, v.w. $CO_3^=$, esp. on microfract's. No vis. su.								
								W-m magnetic. W. ser. a, perv. + in 2mm round patches, ≈2%.								
								Few gy fs (?) to 2mm, subeuhed. Rare 1-2 gy grains to 1mm. Each end in Kfm.								
33.71	42.51							SYENITE								
								Broken top contact			Fract's 10°-10°, w m clp-chl.					
								Dr. pk gy mottled thruout, no large KF phens. DK gn-bk Hb, subhed, to 4mm (1cm Hb at 40.5m) 10-15%.			$CO_3^=$ stgr's to 2mm	10°-15°, f-w.				
								S. lineation of mafics at 50° to core, becoming more pronounced as mafics go from individual grains to stngrs/flagged bands. (41.2m)								
								In hem. w m clp-chl. Rock is m magn near top, decr. d/h so at 40.73m is nonmagn-bc.								

#385

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-16 PAGE 6 of 9
CORE SIZE ____ FINAL DEPTH ____
STARTED ____ FINISHED ____

LATITUDE ____ DEPARTURE ____
DIP AT COLLAR ____ BEARING ____
COLLAR ELEV. ____ LOGGED BY ____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Ag	ASSAYS: % Mo
42.07	43.07							SYENITE. sheared c.l.					42.07 - 43.07	10	<0.3	<0.07
								c. lim, cl. a. rotten rock.			Tr W	CO_3 str' to 3mm				
/						-1.2		v. sheared, m-s. hem, c-i lim, cl. a				at 20° to core	43.07 - 44.60	11	0.3	<0.07
								m. epid. v.v. falls apart. soil like.								
								Nonmagnetic. No VIS. Sul								
44.6	45.35							SYENITE								
								Abrupt change from 42.07m. Not								
								well fract'd. Hb, subhed chl+epid. a			5	lim. fracts 40-45°	44.6 - 45.35	12	<0.3	<0.07
								masses to 3mm, 1%, in lim, or. f.								
								ph. m cl. a mx. w-m lim.								
								Poor location of mafics at 45° to cor.								
45.35	47.0							SYENITE c-lim-cl. a								
								Rotten rock, soil-like, or lim throut.			Tr	fr at 10, 30-50°	45.35 - 47.0	13	<0.3	<0.07
								Most texture destroyed except in								
								short sections at 41.8 - 43.15, 47.4 -					47.0 - 48.57	14	<0.3	<0.07
								47.55 m. m hem throut								
								Nonmagnetic. No VIS. Sul. W. ser. on								
								few fracts.								
48.57	50.40							SYENITE								
								Similar to 44.60 m, but w/ m hem								
								incr'd dth.					48.57 - 49.68	15	<0.3	<0.07
						49.7cm		- QV/silic'd zone; 3cm med gy f.gr'd qz								
								@ 55° to core, parallel w/ m-s					49.68 - 50.40	16	<0.3	<0.07
								lineation w/ KF/image lining for								
								~10cm bel w QV. m ser a. m.								
								chl. Chl. fracts xc band/lensing								
								at 30° to core.								
50.40	51.21							c. lim - cl. a (SY)					50.40 - 51.21	17	<0.3	<0.07

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. Y-86-11 PAGE 1 of 9 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Mo	ASSAYS: % Cu
								Same as -to.35m. V broken fract'd core								
51.21	52.3							SYENITE					51.21 - 52.3	18	0.03	0.01
								Similar to 48.5/m as here but			Irr/sep. stks to 3mm		intg at 50°			
								cut/cut by 1-2 mm stks of musc.			1-2% 1mm stks		to core			
52.3	53.4							RHYOLITE (FS PORPHYRITIC) DYKE								
								Sharp intrusive contact @ ~25° to					52.3 - 53.4	19	0.03	0.003
								core. V fract'd, brittle rock. Core								
								mm-dm scale family banded. generally								
								massive dk.gy. to dk. brn-gy v. fract'd,								
								silic. W. pyrite-fs xls to 1mm are								
								concd' sem. here & there and disperse								
								through rock (~1-2%), incl. dissem.								
								& in thin fractures. W. patchy magnetic.								
								Aphanitic. Lower contact is 1mm,								
								is banded at 25° to core, &								
								parallel w/ several Qtz+ stks to 4mm								
								& irreg. Lower contact vague,								
								at ~50° to core.								
53.4	54.4							SYENITE					53.4 - 54.4	20	0.03	0.01
								or. pk to sh-lt-gy mottled. W-m			2-3%	1-2 mm at 40-60°	to core.			
								loc. hm. s. Flakes + subhed. lts			1-2%	CO2 stks to 3mm at ~50° to				
								to 4mm, ave. 2mm, m-s Chl-Cpy s.				cut off by bleaching.				
								V. magnetic. W. ser. s. Poor-mod.								
								fract'g. W. loc. hem matting incl.								
								Alb. 1cm bx/hairline fract'g incl.								
								dk. Noncalc.								
								54.0m – Nonmagnetic. Flakes s. epit.								

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – Y11

DIAMOND DRILLING - 1986

DDH No. Y-86-11 PAGE 8 of 9 LATITUDE _____ DEPARTURE _____

CORE SIZE BQ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY MH

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS %	ASSAYS %
0/3.0	3.0 m							RHYODACITE massive DYKE								
								Top contact sharp at 50° to cor.								
								s. flow bnd'g at 45-50°, buff/pk/yel								
								gn near contacts, incr. pk as								
								becomes more mass. Bands are								
								~0.25mm - 2mm thick to 5380m. m.d.l.								
								w-m. cp. str's to 3mm thick parallel								
								to flow banding. Hardness varies								
								from m.d. to v. hard. w-m kln								
								dendrites.								
					6L	5-0.2m		- m. banded section, v.fn pk gn.								
								Then ~massive again but more								
								irreg								
3.3	15.0							FS DACITE DYKE								
								Broken contact, vaguely defined.								
								pp-fg m-l.d, f.gr'd, m.d. silic.								
								th num 1- 6-10%, then w-m hem.								
								Seric. blebs to 2mm to 6-8.5m, ~1%								
								decr. d/h. Grain size incr. dn								
						6m-		m-c.gr'd (0.5-1.0mm)								
						7m-		more like f.gr'd QPM, v. vague			W-m. lim-hem fracts,		10°, 50, 75° to			
								gy-wh fs 1- 2mm, 5-15%				core.				
								Noncalc! patchy s. musgn.			CO_3	= str's to 3mm,	f.vnd, few.			
								w. chl-cp. w. patchy ser.								
								BK unid. specks <0.5mm, ~5%								
					7	6-15.0		Rock v. frkn, becoming soft +								
								crumbly s. chl-cp. w mod. s.								
15.0	15.5							Breccia								
								Autobreccia? Ang. frags outlined by								
								s. lim. network, flagstone lim fabric								

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. [illegible] PAGE [illegible]
CORE SIZE [illegible] FINAL DEPTH
STARTED FINISHED

LATITUDE DEPARTURE
DIP AT COLLAR BEARING
COLLAR ELEV. LOGGED BY

FOOTAGE		%	GRAPHIC LOG				%	DESCRIPTION	MINERALIZATION		ALTERATION		STRUCTURE	ASSAYS		
FROM	TO	RECOVERY	ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE <	MoS_2		VOL. %	MODE OF OCCURRENCE	VOL. %	TYPE MODE OF OCCURRENCE	KIND, DENSITY, ETC.	SAMPLE NO.	%	%
								[illegible]			[illegible]					
								[illegible]								
[illegible]								[illegible] (12 Bags.)								

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-17 PAGE 1 of 8 LATITUDE 413.0 DEPARTURE 2125.2
CORE SIZE BQ FINAL DEPTH 115.21 m DIP AT COLLAR -47° BEARING GRID NORTH
STARTED SEPT 4/1986 FINISHED SEPT 6/1986 COLLAR ELEV. 1634.3 LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
0	11.58							OVERBURDEN - a few pieces of broken rubble								
11.58	13.11	75						SYENITE - s fr, w-m a., pred. broken				s. chl, loc. hem, lim, cp in blebs and stks.				
13.11	14.33	50						as 11.58								
14.33	19.9	100						m-s fr, loc. broken, w-m a., ep + occas. sil. stx.				s. chl., loc. hem on fr, loc s lim ep ab. in patches and stx.,		YV		
					0-5°			17.9 ep+sil. stxs, 1-3mm wide					17.9-19.05	1701	<0.3	<0.07
								19.0 "								
19.9	20.53	100						w fr. and a., 50-70% hb in upper part of section				w-m chl, loc. ep.				
20.53	22.4	100						as 14.33								
22.4	25.9	100						s fr + m.a., common ep stx. at 25-35°				s chl, lim, s. loc.				
						70°		23.27 Amphibolite band 1.5 cm				ep., loc m. hem	24.9-25.9	1702	<0.3	<0.07
						65°		25.18 Shear, slickensides, gouge lim + chl								
								m. fem below shear zone								
25.9	28.25	100						w-m fr + a., loc ep stx at 45°				w-m chl, loc ep				
28.25	29.1	100						m-s fr, m.a., loc crumbly ep. stx at 30-45, lim fr 20-70°				s. chl, s loc. ep., loc lim (+carb?)				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. Yv-86-17 PAGE 2 of 3 LATITUDE 413.0 DEPARTURE 2125.2
CORE SIZE BQ FINAL DEPTH 115.21 DIP AT COLLAR BEARING
STARTED FINISHED COLLAR ELEV. 1634.3 LOGGED BY IL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Pb	ASSAYS % Mo
29.1	29.85	100						as 25.9, rel. unalt.								
29.85	30.0	100						m fr., w a.				s. chl, lim fr and partial coatn of hb, patchy cp.				
						25		29.87 - qz str, 2mm, drusy								
30.0	36.37	100						as 25.9 rel unalt. with loc m-s fr zones								
36.37	36.87	100						s fr, m-s.a., broken to crumbly cp str at 15°				m-s lim, s chl.	36.37 - 37.26	17203	0.3	<0.01
36.87	37.04	100		c.	50	0		FINE GRAINED SYENITE - grains 1-2mm, homogeneous zone 15-20 cm wide cp str at 0°, s calc.				m-s lim, s chl				
37.04	37.26	100						SYENITE m fr - a.				s. chl, m. lim.				
37.26	39.22	100						SYENITE PORPHYRY w-m fr, w a., ksp phenos 20-30%, .5-2 cm 38.15 alt band 1.5 cm, m. lim, s chl				w-m chl, lim fr.				
39.22	39.42	100						SYENITE - w fr, m.a.				s cpy, chl.				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-17 PAGE 3 of 8 LATITUDE DEPARTURE

CORE SIZE FINAL DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % Mo	ASSAYS: % Au
37.42	39.47	100						SYENITE - siliceous, banded at 65°, irreg qz str. 65° to 1.5cm				m. chl.	39.12 - 40.25	17014	<0.3	0.34
39.47	40.25	100						- f. mg with very few mafics unclear contacts				chl. of mafics Mn + lim on fr.				
40.25	40.6	100						SYENITE PORPHYRY as 37.26 w.a.								
40.8	42.0	100						- s fr, m.a., ep common in patches + str at 25°				s chl, ep, m.lim w.cl.				
42.0	42.4	100						s.fr., m-s.a., sheared with fr at 35° slickensides and minor gouge + Mn				s hem, chl m.cl.	42.0 - 43.59	17015	<0.3	<0.07
42.4	45.60	60-70						- s-i fr to crumbly + broken, m.a., loc. gouge in 5° fr				m.lim, chl loc. s.lim + chl, cl.	43.59 - 45.6	17016	<0.3	<0.07
45.6	47.33	100						- m fr, w.a., directive fract. 60°				w-m chl loc ep. lim in fr.				
47.33	48.16	100						- s-i fr. to crumbly + broken				m-s lim, s chl loc ep.				
48.16	48.8	100						as 45.6								
48.8	49.2	100						as 47.33								
49.2	49.5	100						as 45.6								

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-17 PAGE 4 of 8 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE ∠	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	Ag oz/t	Au oz/t
49.5	49.68	100						as 47.33								
49.68	59.7	100						as 45.6								
								52.35 - sp str at 30° lim sp chl surrounding								
								54.05 - " 45°								
								- incr chl a down section to most intense below 57.4 m, ab. sp.					58.83 - 59.7	1707	0.3	0.21
59.7	60.25	100				70		QUARTZ VEIN - 45-50 cm, m.fr., white, lim on fr., loc spots and cavities with lim or hem.					59.7 - 60.25	1708	0.5	33.1
60.25	60.28	100				65		GOUGE/BRECCIA ZONE, 3cm, gy-gn clay rich gouge with qz + rhyodacite fragments, m. lim				s. cl., m. lim	60.25 - 61.25	1709	<0.3	1.17
60.28	62.02	100						RHYODACITE DYKE - PORPHYRITIC - pale gn to pinkish orange, phenocrysts 1mm fs 5%, m-s. fr. to broken, common fractures at 40-60°				m. cl., m-s lim Mn on fr with lim				
			cont. var.			80°										
62.02	62.3	100						SYENITE - w-m fr, very few matiss, ab. patchy ep., loc, 1mm qz seams				prop.	62.02 - 62.30	1710	0.3	2.06
62.3	62.7	100		con. var		70°		QUARTZ VEIN, 35 cm - 40 cm, m. lim on fr, slight banding at 60°					62.3 - 62.7	1711	1.0	11.4

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-17 PAGE 5 of 8 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS % Ag	ASSAYS % Au
62.7	68.2	100						SYENITE - pink, m-s fr, w-m a ep ab m blebs and stx at var. angles, loc AMPH. bands				S. chl, m. lim loc. carbon?	62.7 - 63.4	1712	0.5	0.21
													63.9 - 68.2	1713	<0.3	0.14
68.2	86.26	100						DACITE PORPHYRY DIKE - m-dk gn, gy matrix with m gn-gy euhedral to subhedral, 2-4mm fs. phenos, 25-40% 5-10% alt mafic phenos of chl + ep. - upper contact 15-30° with loc. early qz vein in Syen. crosscut by dacite, qz vn at 15-20°				m. chl, loc lim			
															
								loc zones of broken core with low angle fx filled with carbonate +/or ep. with pink fs phenos adj to fx. (possible pot. alt)							
						5-10		86.06 Carb - lim stx, 1-3mm							

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-17 PAGE 6 of 8 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE		%	GRAPHIC LOG				%		MINERALIZATION		ALTERATION		STRUCTURE	ASSAYS		
FROM	TO	RECOVERY	ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE ∠	MoS_2	DESCRIPTION	VOL. %	MODE OF OCCURRENCE	VOL. %	TYPE MODE OF OCCURRENCE	KIND, DENSITY, ETC.	SAMPLE NO.	%	%
86.26	86.98	100						DACITE PORPHYRY DYKE m-s a., s. lim in 0-10° fr with CB, s. fr to crumbly				s. chl, m-s ch, ser				
86.98	89.05	100						as 68.2 with loc. crumbly, alt zones and CB strs.								
						10-15°		88.0 CB VN, 1-2cm, mult. str. in crumbly ser a. zone								
						"		88.35 eBVN - 1cm in ser a. zone								
89.05	90.23	~100	C.	60°				- i fr - crumbled, 60% gouge material with CB fragments				s lim loc, s. cl. ser.				
90.23	96.05	100						as 68:2								
96.05	96.4	100		irr.		0-5°		CONTACT ZONE								
96.4	97.5	100						SYENITE - w-m fr, w.a.				w-m chl, lim fr, patchy ep.				
97.5	98.0	100						- as 96.4 with DACITE contact 0-5°								
								~~FAULT / DIKE~~								
98.0	98.45	100						- as 96.4 with loc crumbly zone				m-s lim in fr.				
98.45	99.95	100						- s. fr, m.a., broken				s chl, m-s lim, loc. hem + cl.				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-17 PAGE 7 of 8 LATITUDE ____ DEPARTURE ____

CORE SIZE ____ FINAL DEPTH ____ DIP AT COLLAR ____ BEARING ____

STARTED ____ FINISHED ____ COLLAR ELEV. ____ LOGGED BY ____

FOOTAGE		%	GRAPHIC LOG				%	DESCRIPTION	MINERALIZATION		ALTERATION		STRUCTURE	ASSAYS		
FROM	TO	RECOVERY	ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE ∠	MoS_2		VOL. %	MODE OF OCCURRENCE	VOL. %	TYPE MODE OF OCCURRENCE	KIND, DENSITY, ETC.	SAMPLE NO.	% Ag	% Au
99.95	101.7	100						SYENITE PORPHYRY				s lim, chl,	99.95 - 100.85	1714	0.5	0.07
								- s-i fr ; s.a., fr at 30-40°		py on fr.		m hem, cl.	100.85 - 101.7	1715	0.5	<0.07
101.7	102.2	100		c.	20°			- pale gn, i fr to crumbly				s-i chl, w-m cl.	101.7 - 102.6	1716	0.3	<0.07
102.2	102.6	100						- s-i fr to crumbly				s lim, chl, w. cl.				
102.6	103.52	100						as 101.7					102.6 - 103.52	1717	1.0	<0.07
103.52	104.5	100						as 102.2 with loc. cp.					103.52 - 104.5	1718	0.5	<0.07
104.5	104.95							m. fr + a.				m lim, s chl loc. cp.	104.5 - 105.25	1719	0.5	<0.07
104.95	105.25	100						as 103.52, crumbly								
105.25	106.57	100						as 104.95					105.77 - 106.37	1720	0.5	0.41
								106.07 - qz vn 1.5-2cm no orientation possible, white, lim fr loc. cavities								
106.57	107.59	75						s-i fr, loc. crumbled, fr 35-40°				m-s lim, s chl s. hem + lim on 35-40° fr				
107.59	110.1	100						m-s fr, loc. broken, loc. lim fr at 30-45°				m-s chl, w-m lim loc. s cp				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-17 PAGE E 57 8

CORE SIZE _____ FINAL DEPTH _____

STARTED _____ FINISHED _____

LATITUDE _____ DEPARTURE _____

DIP AT COLLAR _____ BEARING _____

COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE		%	GRAPHIC LOG				%	DESCRIPTION	MINERALIZATION		ALTERATION		STRUCTURE	ASSAYS		
FROM	TO	RECOVERY	ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE ∠	MoS_2		VOL. %	MODE OF OCCURRENCE	VOL. %	TYPE MODE OF OCCURRENCE	KIND, DENSITY, ETC.	SAMPLE NO.	%	%
110.1	111.4	100						m-i fr to loc. crumbly loc. CB str at 20-45°				m-s lim, loc hem s ch, loc ep				
111.4	113.9	100						m-s fr, loc zones with few mafics at 65°				w-m lim, m-s chl loc ep in patches and 20° str.				
113.9	115.21	100						-w-m fr, lim fr				m chl, loc ep				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. YV-86-18 PAGE 1 of 5 LATITUDE 415.3 DEPARTURE 2070.9
CORE SIZE BQ FINAL DEPTH 76.81 m DIP AT COLLAR -47 BEARING GRID NORTH
STARTED SEPT 7/1986 FINISHED SEPT 8/1986 COLLAR ELEV. 1635.7 LOGGED BY LL

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	• STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS %	ASSAYS %
0	7.01	<5						Overburden - Rubble Syenite + Dacite								
7.01	10.06	80-90						SYENITE, s. weathered to crumbly				s. lim., m hem, s chl.				
10.06	10.65	100						f-m.g resistive to s. weathering, directive texture 55°, 10-15% chl. speckled throughout, 85-90% feldspar, m. fr to loc. broken				m-s chl, lim fr				
10.65	11.58	40						as 7.01								
11.58	11.68	100						as 10.06								
11.68	12.8	40						as 7.01 with loc hem				s. hem, loc cp				
12.8	13.25	100						as 10.06, loc. bands of massive fs dir. at 55°, loc. cp.								
13.25	14.63	90						- c.g., m-s.fr, bottom contact is crumbled and lim.				s. chl., lim. fr.				
14.63	15.0	100						as 10.06								
15.0	15.8	100						as 7.01								
15.8	16.35							- m.g. m-s fr, broken, loc cp str				s. chl				

#355

KERR ADDISON MINES LIMITED

VIC PROPERTY – YII

DIAMOND DRILLING - 1986

DDH No. YV-86-18 PAGE 2 of 5 LATITUDE DEPARTURE

CORE SIZE FINAL DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY

FOOTAGE		%	GRAPHIC LOG				%	DESCRIPTION	MINERALIZATION		ALTERATION		STRUCTURE	ASSAYS		
FROM	TO	RECOVERY	ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE ∠	MoS_2		VOL. %	MODE OF OCCURRENCE	VOL. %	TYPE MODE OF OCCURRENCE	KIND, DENSITY, ETC.	SAMPLE NO.	%	%
16.35	19.1	100						SYENITE, c.g. w-m fr + a, loc lim on fr, loc 40° ep str, loc broken				s. chl, w-m ser				
19.1	20.53	60						s-i fr to crumbly, w-m a.				s chl, loc s. lim w.el.				
20.53	20.73	100						m fr + a, loc crumbly				s lim, chl carb?				
20.73	21.55	100						m-i fr, m.a., loc crumbly				loc s lim hem fr, s chl				
21.55	27.12	100						m fr, w a, ep str occas. 20-45°				w-m chl, lim + hem on fr, loc w el.				
						10		25.7 - f.g. band, 3cm, few mafics								
27.12	29.05	100						s-i fr, s a, loc i gouge + crumbly				m-s lim, s chl loc. hem.				
29.05	32.6	100						w-m fr + a, loc ep str at 45°				w-m chl, loc. lim. on fr.				
32.6	32.7	100						s. fr, ab. chl zone 30°				s-i chl.				
32.7	33.64	100						m-s fr, w-m a, fr at 0-75°				m-s lim, s chl, m qz				
33.64	38.2	100						s-i fr, loc crumbly, i fr at 5-20°, lim fr common at 45°, mn fr common				s-i lim, s chl, loc ep				
38.2	39.4	100						m. fr., w.a.,				m chl, loc ep, m lim on fr.				

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. VV-86-15 PAGE 3 of 5 LATITUDE _____ DEPARTURE _____

CORE SIZE _____ FINAL DEPTH _____ DIP AT COLLAR _____ BEARING _____

STARTED _____ FINISHED _____ COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG: ROCK TYPE	GRAPHIC LOG: ALTERATION	GRAPHIC LOG: MINERALIZED ZONE	GRAPHIC LOG: STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION: VOL. %	MINERALIZATION: MODE OF OCCURRENCE	ALTERATION: VOL. %	ALTERATION: TYPE MODE OF OCCURRENCE	STRUCTURE: KIND, DENSITY, ETC.	ASSAYS: SAMPLE NO.	ASSAYS: % [illegible]	ASSAYS: % [illegible]
39.4	39.5	100				75-80°		SYENITE, i fr + a, crumbly				i lim, hem, chl	39.4 – 40.55	VV		
														1801	0.5	<0.01
39.5	40.55	100						s fr + a, loc. crumbly		rrm fr.		s. lim, hem, cc, chl				
40.55	43.6	100						m. s fr, loc crumbly, loc qz str 0-30°				m lim, s chl				
43.6	44.8	100						s fr., m a. hem in fr at 0-20°				s lim, chl, loc cp.				
								44.0 - CB in fr at 10°								
44.8	46.65	100						as 40.55								
46.65	57.55	100						- m fr, w a, cp common in str and patches, lim fr 40° loc occas CB str 1-2m				m chl, loc. s. chl lim pred in fr				
						30		50.4 - qz str 1-2mm, cp.								
						35		52.95 - qz-chl-cp in fr, 1-4mm mult fr to 52.95								
57.55	58.35	100						as 46.65° with mult. breccinted fr at 50-55°, chl + cp in fr								
58.35	60.65	100						as 46.65								
60.65	61.6	100						- s fr to crackle brecciated sections, loc CB in str 30°				hem, chl fr.	60.65 – 61.6	1802	0.5	<0.01
61.6	63.2	100						as 46.65								

#385

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-18 PAGE 4 of 5 LATITUDE DEPARTURE

CORE SIZE FINAL DEPTH DIP AT COLLAR BEARING

STARTED FINISHED COLLAR ELEV. LOGGED BY

FOOTAGE		%	GRAPHIC LOG				%	DESCRIPTION	MINERALIZATION		ALTERATION		STRUCTURE	ASSAYS		
FROM	TO	RECOVERY	ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE ∠	MoS_2		VOL. %	MODE OF OCCURRENCE	VOL. %	TYPE MODE OF OCCURRENCE	KIND, DENSITY, ETC.	SAMPLE NO.	% Ag	% Au
63.2	63.8	100						SYENITE - as 46.65 with abundant qz, chl, ep bands at 55°, 30+ strs in section from <1mm – 3mm, chl + ep in parallel bands				s. chl, loc hem pot a?				
63.8	63.9	90-100				55-65°		QZ VEIN ~10cm, gy, m.fr w lim on fr, chl + ep ni fr occas.					63.2 - 63.9	1803	1.0	13.44
63.9	67.4	100						SYENITE - as 46.65 with s.chl ep zone at base of Sxn 67.0 - 67.1 - Psd of porphyritic dyke? with s.ser, chl, hem + 1mm alt fs phenos 67.18 - 67.4 - brecciated with s.chl. matrix					67.0 - 67.9	1804	0.5	0.07
67.4	67.9	100		cont.		10-15°		ALTERED DYKE - small 1mm white elongate phenos as well as 2-4mm pink ksp phenos +/or fragments, loc. irreg. banded at 30°				s chl, ser matrix m-s lim				
67.9	69.05	100						SYENITE - pink, m.fr., loc CB str 60°				m-s chl + ep.				
69.05	69.17	100						- s. silicified				s. sil. chl	68.9 - 69.17	1805	0.5	<0.07
69.17	70.45	100				80°		RHYOLITE/RHYODACITE DYKE as 67.4, banded at 80° pinkish gy with phenos				s. chl, ser m-s lim				

#385

KERR ADDISON MINES LIMITED
VIC PROPERTY – Y11
DIAMOND DRILLING - 1986

DDH No. W-86-18 PAGE 5 5 5 0

CORE SIZE _____ FIN L DEPTH _____

STARTED _____ FINISHED _____

LATITUDE _____ DEPARTURE _____

DIP AT COLLAR _____ BEARING _____

COLLAR ELEV. _____ LOGGED BY _____

FOOTAGE FROM	FOOTAGE TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	GRAPHIC LOG ALTERATION	GRAPHIC LOG MINERALIZED ZONE	GRAPHIC LOG STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MINERALIZATION MODE OF OCCURRENCE	ALTERATION VOL. %	ALTERATION TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	ASSAYS %	ASSAYS %
70.45	71.5	100						SYENITE w-m a. -m fr, common fr at 45°				s chl, loc. ep				
71.5	72.85	100						- s-i fr, loc. crumbly, loc CB str at 30 + 55°				s/lim, chl, carbn? loc cl.				
72.85	73.6	100						- i fr to crumbly and gougy				i/lim, m-s cl. s chl.				
73.6	76.05	100						- m fr, w.a., lim on fr + ep str 0-10°				m chl, loc ep				
76.05	76.6	60						- crumbly r a.				s/lim., cl.				
76.6	76.81	100						as 73.6								

#355

KERR ADDISON MINES LIMITED
VIC PROPERTY – YII
DIAMOND DRILLING - 1986

DDH No. YV-86-19 PAGE 1 of 1
CORE SIZE BQ FINAL DEPTH 37.49 M
STARTED Sept 7/86 FINISHED Sept 8/86

LATITUDE 415N * DEPARTURE 2175E *
DIP AT COLLAR -46° BEARING Grid North
COLLAR ELEV. — LOGGED BY RP

FOOTAGE METERS FROM	TO	% RECOVERY	GRAPHIC LOG ROCK TYPE	ALTERATION	MINERALIZED ZONE	STRUCTURE TO CORE <	% MoS_2	DESCRIPTION	MINERALIZATION VOL. %	MODE OF OCCURRENCE	ALTERATION VOL. %	TYPE MODE OF OCCURRENCE	STRUCTURE KIND, DENSITY, ETC.	ASSAYS SAMPLE NO.	%	%
0	7.0							Surface rubble								
7.0	9.7		Sy					Syenite: Weathered, rusty, soft								
9.7	37.49	100	Sy					Syenite: Pmk, relatively fresh, medgr 20% hbld, 25% K-spar Mag diss within hbld						NO SAMPLES		
								Details: 9.7-11.0 Fresh, pmk to grey								
								11.0-11.7 Moderately propylitized ep filled frac, sl contn of hbld								
								11.7-19.2 Fresh, sl local ep in frac								
								19.2-19.6 Mod fr in epidote hbld foliation 60°								
								19.6-37.49 Fresh pmk to grey. Sl frac, rare ep along frac.								
								Hole shutdown @ 09:00 on Sept 8 due to blizzard and concurrent water supply freeze-up.		Casing left in hole for possible completion in 1987						
								* Hole not surveyed. Location by chain & compass is 50 metres grid-east of YV-86-17.								

APPENDIX III

VLF-EM SURVEY DATA

EM SURVEY DATA (1986)

LINE 1400E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-5	4	5+37.5 N	10	2
	0+12.5 N	-6	-3	5+50 N	13	6
	0+25 N	-4	1	5+62.5N	12	0
	0+37.5N	-2	5	5+75 N	20	4
	0+50 N	-2	7	5+87.5 N	16	-2
	0+62.5N	-2	7	6+00 N	14	2
	0+75 N	0	4	6+12.5 N	—	— E.O.L.
	0+87.5N	2	6	6+25 N		
	1+00 N	1	8	6+37.5 N		
	1+12.5 N	5	5	6+50 N		
	1+25 N	3	10	6+62.5N		
	1+37.5N	3	8	6+75 N		
	1+50 N	2	6	6+87.5 N		
	1+62.5N	3	14	7+00 N		
	1+75 N	1	7	7+12.5 N		
	1+87.5 N	-2	13	7+25 N		
	2+00 N	-1	10	7+37.5 N		
	2+12.5N	2	8	7+50 N		
	2+25 N	-5	13	7+62.5N		
	2+37.5N	-3	9	7+75 N		
	2+50 N	-3	10	7+87.5 N		
	2+62.5N	0	6	8+00 N		
	2+75 N	-4	3	8+12.5 N		
	2+87.5 N	-10	6	8+25 N		
	3+00 N	-11	6	8+37.5 N		
	3+12.5 N	-9	8	8+50 N		
	3+25 N	-6	2	8+62.5 N		
	3+37.5N	-2	10	8+75 N		
	3+50 N	3	5	8+87.5 N		
	3+62.5N	5	12	9+00 N		
	3+75 N	9	6	9+12.5 N		
	3+87.5N	8	7	9+25 N		
	4+00 N	12	4	9+37.5 N		
	4+12.5N	6	6	9+50 N		
	4+25 N	10	1	9+62.5 N		
	4+37.5N	9	4	9+75 N		
	4+50 N	14	-2	9+87.5 N		
	4+62.5N	12	0	10+00 N		
	4+75 N	11	2			
	4+87.5N	8	5			
	5+00 N	17	10			
	5+12.5N	10	2			
	5+25 N	17	-3			

VIC CLAIMS – VLF EM SURVEY DATA (1986)

LINE 1500E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-6	-1	5+37.5 N	14	8
	0+12.5 N	-5	2	5+50 N	15	5
	0+25 N	-6	1	5+62.5N	9	3
	0+37.5N	-7	-1	5+75 N	11	4
	0+50 N	-6	1	5+87.5 N	14	8
	0+62.5N	-4	-1	6+00 N	15	6
	0+75 N	-10	3	6+12.5 N	–	– E.O.L.
	0+87.5N	-8	1	6+25 N		
	1+00 N	-8	0	6+37.5 N		
	1+12.5 N	-4	9	6+50 N		
	1+25 N	-1	5	6+62.5N		
	1+37.5N	-2	8	6+75 N		
	1+50 N	-3	7	6+87.5 N		
	1+62.5N	-1	2	7+00 N		
	1+75 N	1	10	7+12.5 N		
	1+87.5N	3	5	7+25 N		
	2+00 N	5	11	7+37.5 N		
	2+12.5N	4	13	7+50 N		
	2+25 N	2	3	7+62.5N		
	2+37.5N	-3	6	7+75 N		
	2+50 N	-1	5	7+87.5 N		
	2+62.5N	-2	4	8+00 N		
	2+75 N	-5	5	8+12.5 N		
	2+87.5N	-5	7	8+25 N		
	3+00 N	-7	6	8+37.5 N		
	3+12.5 N	-3	5	8+50 N		
	3+25 N	-4	6	8+62.5 N		
	3+37.5N	-4	5	8+75 N		
	3+50 N	-6	10	8+87.5 N		
	3+62.5N	-5	6	9+00 N		
	3+75 N	-5	6	9+12.5 N		
	3+87.5N	-3	4	9+25 N		
	4+00 N	1	7	9+37.5 N		
	4+12.5N	2	6	9+50 N		
	4+25 N	3	5	9+62.5 N		
	4+37.5N	5	4	9+75 N		
	4+50 N	3	4	9+87.5 N		
	4+62.5N	1	3	10+00 N		
	4+75 N	3	6			
	4+87.5N	4	5			
	5+00 N	6	12			
	5+12.5N	10	8			
	5+25 N	17	12			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 1550E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-15	-13	5+37.5 N	14	6
	0+12.5 N	-16	-4	5+50 N	13	9
	0+25 N	-14	-12	5+62.5N	17	13
	0+37.5N	-12	-10	5+75 N	16	10
	0+50 N	-2	-1	5+87.5 N	15	10
	0+62.5N	-4	0	6+00 N	12	6
	0+75 N	-6	1	6+12.5 N	—	- E.O.L.
	0+87.5N	-10	0	6+25 N		
	1+00 N	-9	2	6+37.5 N		
	1+12.5 N	-6	4	6+50 N		
	1+25 N	-3	3	6+62.5N		
	1+37.5 N	-1	4	6+75 N		
	1+50 N	2	6	6+87.5 N		
	1+62.5N	3	10	7+00 N		
	1+75 N	1	6	7+12.5 N		
	1+87.5 N	4	3	7+25 N		
	2+00 N	5	12	7+37.5 N		
	2+12.5N	4	7	7+50 N		
	2+25 N	2	6	7+62.5N		
	2+37.5N	1	8	7+75 N		
	2+50 N	-2	4	7+87.5 N		
	2+62.5N	-5	8	8+00 N		
	2+75 N	-1	6	8+12.5 N		
	2+87.5 N	-4	10	8+25 N		
	3+00 N	-3	7	8+37.5 N		
	3+12.5 N	-1	0	8+50 N		
	3+25 N	2	10	8+62.5 N		
	3+37.5N	1	7	8+75 N		
	3+50 N	0	6	8+87.5 N		
	3+62.5N	-1	7	9+00 N		
	3+75 N	-3	6	9+12.5 N		
	3+87.5N	-1	8	9+25 N		
	4+00 N	1	6	9+37.5N		
	4+12.5N	3	7	9+50 N		
	4+25 N	4	6	9+62.5 N		
	4+37.5N	4	5	9+75 N		
	4+50 N	6	6	9+87.5 N		
	4+62.5N	8	5	10+00 N		
	4+75 N	10	8			
	4+87.5 N	13	5			
	5+00 N	15	7			
	5+12.5 N	17	10			
	5+25 N	16	12			

VIC CLAIMS – VLF EM SURVEY DATA (1986)

LINE 1600E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-16	-5			
	0+12.5 S	-17	-6			
	0+25 S	-17	-7			
	0+37.5 S	-18	-10			
	0+50 S	-16	-6			
	0+62.5 S	-17	-5			
	0+75 S	-15	-4			
	0+87.5 S	-21	-9			
	1+00 S	-23	-11			
	1+12.5 S	-30	-17			
	1+25 S	-33	-6			
	1+37.5 S	-35	-7			
	1+50 S	-39	-9			
	1+62.5 S	-40	-12			
	1+75 S	-38	-5			
	1+87.5 S	-39	-8			
	2+00 S	-38	-10			
	2+12.5 S	-39	-10			
	2+25 S	-38	-9			
	2+37.5 S	-40	-12			
	2+50 S	-38	-8			
	2+62.5 S	-39	-10			
	2+75 S	-38	-7			
	2+87.5 S	-38	-10			
	3+00 S	-40	-14			

VIC CLAIMS – VLF EM SURVEY DATA (1986)

LINE 1600E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-9	-12	5+37.5 N	9	5
	0+12.5 N	-11	-8	5+50 N	8	6
	0+25 N	-15	-7	5+62.5N	14	8
	0+37.5N	-13	-7	5+75 N	16	8
	0+50 N	-17	-8	5+87.5 N	14	4
	0+62.5N	-18	-8	6+00 N	17	8
	0+75 N	-16	-9	6+12.5 N	—	— E.O.L.
	0+87.5N	-14	-3	6+25 N		
	1+00 N	-12	1	6+37.5 N		
	1+12.5 N	-13	4	6+50 N		
	1+25 N	-10	8	6+62.5N		
	1+37.5N	-8	2	6+75 N		
	1+50 N	-7	-2	6+87.5 N		
	1+62.5N	-5	2	7+00 N		
	1+75 N	-6	3	7+12.5 N		
	1+87.5N	-2	8	7+25 N		
	2+00 N	-3	8	7+37.5 N		
	2+12.5N	-1	4	7+50 N		
	2+25 N	-3	-1	7+62.5N		
	2+37.5N	1	7	7+75 N		
	2+50 N	1	4	7+87.5 N		
	2+62.5N	2	6	8+00 N		
	2+75 N	3	5	8+12.5 N		
	2+87.5N	4	7	8+25 N		
	3+00 N	-1	8	8+37.5 N		
	3+12.5 N	-1	6	8+50 N		
	3+25 N	2	7	8+62.5 N		
	3+37.5N	2	4	8+75 N		
	3+50 N	3	6	8+87.5 N		
	3+62.5N	2	7	9+00 N		
	3+75 N	1	3	9+12.5 N		
	3+87.5N	1	2	9+25 N		
	4+00 N	5	2	9+37.5N		
	4+12.5N	2	4	9+50 N		
	4+25 N	2	5	9+62.5 N		
	4+37.5N	7	7	9+75 N		
	4+50 N	10	2	9+87.5 N		
	4+62.5N	9	4	10+00 N		
	4+75 N	11	6			
	4+87.5N	9	5			
	5+00 N	13	3			
	5+12.5N	10	0			
	5+25 N	13	4			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 1650E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-16	-8	5+37.5 N	10	6
	0+12.5 N	-15	-11	5+50 N	9	6
	0+25 N	-17	-6	5+62.5N	10	6
	0+37.5N	-17	-6	5+75 N	13	8
	0+50 N	-18	-9	5+87.5 N	14	10
	0+62.5N	-16	-8	6+00 N	12	8
	0+75 N	-15	-6	6+12.5 N	—	— E.O.L.
	0+87.5N	-17	-8	6+25 N		
	1+00 N	-17	-9	6+37.5 N		
	1+12.5 N	-18	-6	6+50 N		
	1+25 N	-14	-8	6+62.5N		
	1+37.5N	-12	-9	6+75 N		
	1+50 N	-8	-5	6+87.5 N		
	1+62.5N	-4	2	7+00 N		
	1+75 N	-4	2	7+12.5 N		
	1+87.5N	-1	3	7+25 N		
	2+00 N	1	6	7+37.5 N		
	2+12.5N	-2	3	7+50 N		
	2+25 N	-5	4	7+62.5N		
	2+37.5N	-3	5	7+75 N		
	2+50 N	-3	6	7+87.5 N		
	2+62.5N	-3	3	8+00 N		
	2+75 N	-1	4	8+12.5 N		
	2+87.5N	-3	4	8+25 N		
	3+00 N	-1	7	8+37.5 N		
	3+12.5 N	-1	5	8+50 N		
	3+25 N	-4	8	8+62.5 N		
	3+37.5N	-2	3	8+75 N		
	3+50 N	-1	6	8+87.5 N		
	3+62.5N	-1	4	9+00 N		
	3+75 N	1	4	9+12.5 N		
	3+87.5N	4	-1	9+25 N		
	4+00 N	6	6	9+37.5 N		
	4+12.5N	3	5	9+50 N		
	4+25 N	4	8	9+62.5 N		
	4+37.5N	4	7	9+75 N		
	4+50 N	2	4	9+87.5 N		
	4+62.5N	1	2	10+00 N		
	4+75 N	2	4			
	4+87.5N	4	2			
	5+00 N	6	5			
	5+12.5N	8	4			
	5+25 N	8	5			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 1700E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-19	-15	5+37.5 N	9	8
	0+12.5 N	-18	-9	5+50 N	8	6
	0+25 N	-16	-8	5+62.5N	10	6
	0+37.5N	-14	-5	5+75 N	8	5
	0+50 N	-15	-7	5+87.5 N	9	7
	0+62.5N	-17	-8	6+00 N	7	8
	0+75 N	-15	-6	6+12.5 N	—	— E.O.L.
	0+87.5N	-16	-9	6+25 N		
	1+00 N	-18	-14	6+37.5 N		
	1+12.5 N	-19	-8	6+50 N		
	1+25 N	-16	-10	6+62.5N		
	1+37.5N	-14	-5	6+75 N		
	1+50 N	-15	-8	6+87.5 N		
	1+62.5N	-8	-2	7+00 N		
	1+75 N	-5	-2	7+12.5 N		
	1+87.5N	-3	3	7+25 N		
	2+00 N	-1	2	7+37.5 N		
	2+12.5N	1	4	7+50 N		
	2+25 N	4	6	7+62.5N		
	2+37.5N	5	4	7+75 N		
	2+50 N	4	5	7+87.5N		
	2+62.5N	3	3	8+00 N		
	2+75 N	5	4	8+12.5 N		
	2+87.5N	6	8	8+25 N		
	3+00 N	3	1	8+37.5 N		
	3+12.5 N	3	2	8+50 N		
	3+25 N	4	4	8+62.5 N		
	3+37.5N	5	4	8+75 N		
	3+50 N	6	5	8+87.5 N		
	3+62.5N	5	4	9+00 N		
	3+75 N	8	6	9+12.5 N		
	3+87.5N	9	6	9+25 N		
	4+00 N	9	10	9+37.5 N		
	4+12.5N	11	10	9+50 N		
	4+25 N	13	8	9+62.5 N		
	4+37.5N	15	8	9+75 N		
	4+50 N	16	12	9+87.5 N		
	4+62.5N	15	10	10+00 N		
	4+75 N	11	9			
	4+87.5N	14	12			
	5+00 N	13	6			
	5+12.5N	11	4			
	5+25 N	10	4			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 1750E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-24	-10	5+37.5 N	12	9
	0+12.5 N	-21	-8	5+50 N	11	11
	0+25 N	-20	-14	5+62.5N	-7	5
	0+37.5N	-15	-8	5+75 N	8	4
	0+50 N	-10	-4	5+87.5 N	11	8
	0+62.5N	-12	-6	6+00 N	10	5
	0+75 N	-12	-6	6+12.5 N	—	— E.O.L.
	0+87.5N	-16	-8	6+25 N		
	1+00 N	-17	-5	6+37.5 N		
	1+12.5 N	-20	-12	6+50 N		
	1+25 N	-18	-7	6+62.5N		
	1+37.5N	-20	-10	6+75 N		
	1+50 N	-20	-10	6+87.5 N		
	1+62.5N	-19	-8	7+00 N		
	1+75 N	-7	0	7+12.5 N		
	1+87.5N	-2	4	7+25 N		
	2+00 N	-3	5	7+37.5 N		
	2+12.5N	-2	2	7+50 N		
	2+25 N	-1	2	7+62.5N		
	2+37.5N	-1	2	7+75 N		
	2+50 N	1	3	7+87.5 N		
	2+62.5N	2	1	8+00 N		
	2+75 N	4	-2	8+12.5 N		
	2+87.5 N	4	8	8+25 N		
	3+00 N	1	2	8+37.5 N		
	3+12.5 N	3	4	8+50 N		
	3+25 N	2	2	8+62.5 N		
	3+37.5N	1	2	8+75 N		
	3+50 N	4	4	8+87.5 N		
	3+62.5N	7	4	9+00 N		
	3+75 N	10	6	9+12.5 N		
	3+87.5N	9	5	9+25 N		
	4+00 N	8	5	9+37.5N		
	4+12.5N	11	8	9+50 N		
	4+25 N	11	8	9+62.5 N		
	4+37.5N	9	4	9+75 N		
	4+50 N	10	4	9+87.5 N		
	4+62.5N	10	6	10+00 N		
	4+75 N	9	4			
	4+87.5 N	11	6			
	5+00 N	9	5			
	5+12.5 N	7	5			
	5+25 N	8	8			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 1800E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-25	-10	5+37.5 N	13	4
	0+12.5 N	-25	-10	5+50 N	13	4
	0+25 N	-26	-12	5+62.5N	11	6
	0+37.5N	-25	-11	5+75 N	12	4
	0+50 N	-24	-13	5+87.5 N	10	6
	0+62.5N	-23	-10	6+00 N	8	5
	0+75 N	-21	-8	6+12.5 N	—	— E.O.L.
	0+87.5N	-22	-8	6+25 N		
	1+00 N	-18	-5	6+37.5 N		
	1+12.5 N	-17	-4	6+50 N		
	1+25 N	-18	-6	6+62.5N		
	1+37.5N	-17	-6	6+75 N		
	1+50 N	-15	-4	6+87.5 N		
	1+62.5N	-15	-4	7+00 N		
	1+75 N	-13	-4	7+12.5 N		
	1+87.5 N	-9	-1	7+25 N		
	2+00 N	-8	1	7+37.5 N		
	2+12.5N	-7	0	7+50 N		
	2+25 N	-6	-2	7+62.5N		
	2+37.5N	-5	-3	7+75 N		
	2+50 N	-6	-2	7+87.5 N		
	2+62.5N	-7	-3	8+00 N		
	2+75 N	-6	0	8+12.5 N		
	2+87.5 N	-4	3	8+25 N		
	3+00 N	-2	3	8+37.5 N		
	3+12.5 N	-3	-1	8+50 N		
	3+25 N	-2	-1	8+62.5 N		
	3+37.5N	-1	3	8+75 N		
	3+50 N	5	2	8+87.5 N		
	3+62.5N	5	2	9+00 N		
	3+75 N	7	3	9+12.5 N		
	3+87.5 N	8	4	9+25 N		
	4+00 N	7	6	9+37.5 N		
	4+12.5N	8	4	9+50 N		
	4+25 N	9	3	9+62.5 N		
	4+37.5N	12	5	9+75 N		
	4+50 N	11	3	9+87.5 N		
	4+62.5N	14	6	10+00 N		
	4+75 N	12	3			
	4+87.5 N	10	4			
	5+00 N	13	8			
	5+12.5 N	12	5			
	5+25 N	12	5			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 1850E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-28	-10	5+37.5 N	10	8
	0+12.5 N	-36	-13	5+50 N	11	9
	0+25 N	-29	-12	5+62.5N	7	6
	0+37.5N	-27	-9	5+75 N	8	6
	0+50 N	-26	-10	5+87.5 N	8	4
	0+62.5N	-23	-8	6+00 N	7	5
	0+75 N	-21	-7	6+12.5 N	—	— E.O.L.
	0+87.5N	-17	-7	6+25 N		
	1+00 N	-17	-6	6+37.5 N		
	1+12.5 N	-15	-8	6+50 N		
	1+25 N	-12	-4	6+62.5N		
	1+37.5N	-16	-1	6+75 N		
	1+50 N	-8	-3	6+87.5 N		
	1+62.5N	-6	-2	7+00 N		
	1+75 N	-4	-2	7+12.5 N		
	1+87.5 N	-2	2	7+25 N		
	2+00 N	-3	2	7+37.5 N		
	2+12.5N	-5	-1	7+50 N		
	2+25 N	-5	-2	7+62.5N		
	2+37.5N	-4	-1	7+75 N		
	2+50 N	-5	-4	7+87.5 N		
	2+62.5N	-9	-4	8+00 N		
	2+75 N	-7	-6	8+12.5 N		
	2+87.5 N	-1	-1	8+25 N		
	3+00 N	1	-2	8+37.5 N		
	3+12.5 N	3	0	8+50 N		
	3+25 N	4	1	8+62.5 N		
	3+37.5N	10	0	8+75 N		
	3+50 N	10	3	8+87.5 N		
	3+62.5N	11	6	9+00 N		
	3+75 N	11	4	9+12.5 N		
	3+87.5 N	12	4	9+25 N		
	4+00 N	12	4	9+37.5 N		
	4+12.5N	12	5	9+50 N		
	4+25 N	12	6	9+62.5 N		
	4+37.5N	13	8	9+75 N		
	4+50 N	13	6	9+87.5 N		
	4+62.5N	13	7	10+00 N		
	4+75 N	13	7			
	4+87.5 N	12	6			
	5+00 N	12	7			
	5+12.5 N	10	6			
	5+25 N	9	6			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 1900E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-26	-10	5+37.5 N	16	4
	0+12.5 N	-26	-10	5+50 N	10	5
	0+25 N	-28	-12	5+62.5N	12	6
	0+37.5N	-27	-10	5+75 N	11	6
	0+50 N	-26	-12	5+87.5 N	14	8
	0+62.5N	-26	-8	6+00 N	14	7
	0+75 N	-26	-10	6+12.5 N	—	— E.O.L.
	0+87.5N	-25	-10	6+25 N		
	1+00 N	-17	-8	6+37.5 N		
	1+12.5 N	-16	-5	6+50 N		
	1+25 N	-16	-4	6+62.5N		
	1+37.5N	-16	-6	6+75 N		
	1+50 N	-10	-3	6+87.5 N		
	1+62.5N	-7	0	7+00 N		
	1+75 N	-5	-1	7+12.5 N		
	1+87.5N	-4	-2	7+25 N		
	2+00 N	-4	-1	7+37.5 N		
	2+12.5N	-3	3	7+50 N		
	2+25 N	-4	0	7+62.5N		
	2+37.5N	-1	0	7+75 N		
	2+50 N	-3	-1	7+87.5 N		
	2+62.5N	-5	-3	8+00 N		
	2+75 N	-5	-2	8+12.5 N		
	2+87.5N	-8	-6	8+25 N		
	3+00 N	-7	-2	8+37.5 N		
	3+12.5 N	-3	-1	8+50 N		
	3+25 N	1	0	8+62.5 N		
	3+37.5N	3	3	8+75 N		
	3+50 N	5	4	8+87.5 N		
	3+62.5N	10	6	9+00 N		
	3+75 N	13	5	9+12.5 N		
	3+87.5N	15	6	9+25 N		
	4+00 N	15	4	9+37.5 N		
	4+12.5N	14	3	9+50 N		
	4+25 N	14	3	9+62.5 N		
	4+37.5N	18	6	9+75 N		
	4+50 N	17	8	9+87.5 N		
	4+62.5N	20	10	10+00 N		
	4+75 N	20	11			
	4+87.5N	18	9			
	5+00 N	17	7			
	5+12.5N	14	5			
	5+25 N	12	4			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 2000E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-38	-10			
	0+12.5 S	-39	-10			
	0+25 S	-40	-8			
	0+37.5 S	-43	-15			
	0+50 S	-40	-12			
	0+62.5 S	-40	-12			
	0+75 S	-40	-7			
	0+87.5 S	-41	-10			
	1+00 S	-42	-9			
	1+12.5 S	-43	-11			
	1+25 S	-42	-14			
	1+37.5 S	-41	-15			
	1+50 S	-40	-14			
	1+62.5 S	-41	-12			
	1+75 S	-40	-10			
	1+87.5 S	-39	-10			
	2+00 S	-38	-12			
	2+12.5 S	-37	-8			
	2+25 S	-38	-9			
	2+37.5 S	-39	-13			
	2+50 S	-38	-18			
	2+62.5 S	-37	-9			
	2+75 S	-39	-12			
	2+87.5 S	-38	-8			
	3+00 S	-38	-8			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 2000E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-33	-12	5+37.5 N	8	4
	0+12.5 N	-32	-11	5+50 N	7	4
	0+25 N	-30	-12	5+62.5N	6	5
	0+37.5N	-30	-12	5+75 N	7	4
	0+50 N	-27	-9	5+87.5 N	8	6
	0+62.5N	-25	-10	6+00 N	7	5
	0+75 N	-20	-10	6+12.5 N	—	— E.O.L.
	0+87.5N	-20	-8	6+25 N		
	1+00 N	-15	-10	6+37.5 N		
	1+12.5 N	-10	-6	6+50 N		
	1+25 N	-5	-1	6+62.5N		
	1+37.5N	-3	2	6+75 N		
	1+50 N	-3	2	6+87.5 N		
	1+62.5N	-4	4	7+00 N		
	1+75 N	-3	0	7+12.5 N		
	1+87.5N	-1	1	7+25 N		
	2+00 N	1	0	7+37.5 N		
	2+12.5N	1	1	7+50 N		
	2+25 N	-2	2	7+62.5N		
	2+37.5N	-2	3	7+75 N		
	2+50 N	-2	4	7+87.5 N		
	2+62.5N	-4	1	8+00 N		
	2+75 N	-4	1	8+12.5 N		
	2+87.5N	-3	2	8+25 N		
	3+00 N	-3	2	8+37.5 N		
	3+12.5 N	-4	-2	8+50 N		
	3+25 N	-2	1	8+62.5 N		
	3+37.5N	2	2	8+75 N		
	3+50 N	5	3	8+87.5 N		
	3+62.5N	15	8	9+00 N		
	3+75 N	15	7	9+12.5 N		
	3+87.5N	16	8	9+25 N		
	4+00 N	14	5	9+37.5 N		
	4+12.5N	11	1	9+50 N		
	4+25 N	11	-3	9+62.5 N		
	4+37.5N	12	5	9+75 N		
	4+50 N	12	4	9+87.5 N		
	4+62.5N	13	3	10+00 N		
	4+75 N	14	4			
	4+87.5N	13	6			
	5+00 N	14	8			
	5+12.5N	12	6			
	5+25 N	11	5			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 2100E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-29	-12	5+37.5 N	16	5
	0+12.5 N	-28	-11	5+50 N	18	6
	0+25 N	-29	-12	5+62.5N	19	8
	0+37.5N	-29	-13	5+75 N	17	5
	0+50 N	-30	-14	5+87.5 N	16	4
	0+62.5N	-31	-11	6+00 N	17	4
	0+75 N	-30	-10	6+12.5 N	17	4
	0+87.5N	-29	-9	6+25 N	18	5
	1+00 N	-20	-7	6+37.5 N	16	4
	1+12.5 N	-16	-4	6+50 N	17	5
	1+25 N	-14	-4	6+62.5N	15	2
	1+37.5N	-10	-1	6+75 N	15	-1
	1+50 N	-5	2	6+87.5 N	14	-1
	1+62.5N	-3	2	7+00 N	15	3
	1+75 N	-2	4	7+12.5 N	17	1
	1+87.5 N	-2	0	7+25 N	16	2
	2+00 N	-1	-2	7+37.5 N	15	4
	2+12.5N	-2	-3	7+50 N	15	3
	2+25 N	-2	1	7+62.5N	17	4
	2+37.5N	-1	1	7+75 N	16	3
	2+50 N	-1	0	7+87.5N	18	4
	2+62.5N	0	3	8+00 N	17	3
	2+75 N	4	2	8+12.5 N	16	6
	2+87.5N	7	5	8+25 N	16	3
	3+00 N	9	7	8+37.5 N	15	3
	3+12.5 N	10	5	8+50 N	15	6
	3+25 N	12	4	8+62.5 N	14	4
	3+37.5N	12	5	8+75 N	14	3
	3+50 N	11	6	8+87.5 N	15	4
	3+62.5N	11	5	9+00 N	16	6
	3+75 N	12	7	9+12.5 N	16	6
	3+87.5N	13	6	9+25 N	16	8
	4+00 N	14	6	9+37.5 N	16	8
	4+12.5N	16	5	9+50 N	17	7
	4+25 N	15	-4	9+62.5 N	15	5
	4+37.5N	15	4	9+75 N	15	5
	4+50 N	14	-2	9+87.5 N	—	— E.O.L.
	4+62.5N	13	4	10+00 N		
	4+75 N	12	4			
	4+87.5 N	12	4			
	5+00 N	12	4			
	5+12.5 N	14	4			
	5+25 N	14	2			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 2150E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-26	-10	5+37.5 N	16	6
	0+12.5 N	-27	-9	5+50 N	18	4
	0+25 N	-29	-14	5+62.5N	17	2
	0+37.5N	-28	-12	5+75 N	19	3
	0+50 N	-28	-14	5+87.5 N	17	2
	0+62.5N	-28	-12	6+00 N	15	-1
	0+75 N	-27	-14	6+12.5 N	17	-4
	0+87.5N	-25	-16	6+25 N	18	-4
	1+00 N	-21	-10	6+37.5 N	17	1
	1+12.5 N	-21	-8	6+50 N	16	2
	1+25 N	-13	-6	6+62.5N	15	3
	1+37.5N	-10	-5	6+75 N	15	3
	1+50 N	-6	-3	6+87.5 N	16	1
	1+62.5N	-3	3	7+00 N	15	0
	1+75 N	-1	2	7+12.5 N	12	4
	1+87.5 N	1	2	7+25 N	13	4
	2+00 N	3	3	7+37.5 N	14	0
	2+12.5N	3	1	7+50 N	15	3
	2+25 N	4	2	7+62.5N	16	6
	2+37.5N	5	2	7+75 N	15	0
	2+50 N	10	4	7+87.5 N	16	3
	2+62.5N	10	3	8+00 N	17	2
	2+75 N	10	4	8+12.5 N	17	6
	2+87.5 N	11	8	8+25 N	16	4
	3+00 N	10	7	8+37.5 N	14	3
	3+12.5 N	10	5	8+50 N	15	4
	3+25 N	11	6	8+62.5 N	13	2
	3+37.5N	13	5	8+75 N	15	5
	3+50 N	13	6	8+87.5 N	13	5
	3+62.5N	12	3	9+00 N	15	5
	3+75 N	14	2	9+12.5 N	16	7
	3+87.5N	15	3	9+25 N	15	8
	4+00 N	15	5	9+37.5 N	15	5
	4+12.5N	16	6	9+50 N	17	9
	4+25 N	15	6	9+62.5 N	16	6
	4+37.5N	11	5	9+75 N	14	5
	4+50 N	13	4	9+87.5 N	—	— E.O.L.
	4+62.5N	12	2	10+00 N	—	—
	4+75 N	14	3			
	4+87.5 N	16	4			
	5+00 N	16	4			
	5+12.5 N	17	6			
	5+25 N	17	4			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 2200E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-26	-10	5+37.5 N	15	4
	0+12.5 N	-26	-10	5+50 N	16	6
	0+25 N	-25	-10	5+62.5N	16	6
	0+37.5N	-25	-12	5+75 N	16	8
	0+50 N	-24	-8	5+87.5 N	17	10
	0+62.5N	-25	-11	6+00 N	15	4
	0+75 N	-26	-14	6+12.5 N	17	6
	0+87.5N	-24	-10	6+25 N	14	2
	1+00 N	-25	-8	6+37.5 N	15	5
	1+12.5 N	-19	-10	6+50 N	15	4
	1+25 N	-15	-6	6+62.5N	13	1
	1+37.5N	-8	-8	6+75 N	13	1
	1+50 N	-7	-4	6+87.5 N	13	1
	1+62.5N	-1	-4	7+00 N	10	2
	1+75 N	3	-2	7+12.5 N	10	2
	1+87.5N	6	2	7+25 N	9	2
	2+00 N	10	4	7+37.5 N	10	0
	2+12.5N	10	3	7+50 N	10	0
	2+25 N	11	2	7+62.5N	13	4
	2+37.5N	12	3	7+75 N	14	-1
	2+50 N	15	6	7+87.5 N	14	-1
	2+62.5N	14	6	8+00 N	17	5
	2+75 N	16	10	8+12.5 N	16	6
	2+87.5N	15	8	8+25 N	14	6
	3+00 N	17	10	8+37.5 N	14	4
	3+12.5 N	15	4	8+50 N	12	2
	3+25 N	14	7	8+62.5 N	10	0
	3+37.5N	16	6	8+75 N	15	5
	3+50 N	15	6	8+87.5 N	15	10
	3+62.5N	15	5	9+00 N	14	8
	3+75 N	16	4	9+12.5 N	13	8
	3+87.5N	15	6	9+25 N	12	2
	4+00 N	15	6	9+37.5 N	12	3
	4+12.5N	16	12	9+50 N	13	5
	4+25 N	16	12	9+62.5 N	13	7
	4+37.5N	12	6	9+75 N	14	6
	4+50 N	13	5	9+87.5 N	—	— E.O.L.
	4+62.5N	10	-2	10+00 N		
	4+75 N	13	0			
	4+87.5 N	14	3			
	5+00 N	15	6			
	5+12.5 N	17	10			
	5+25 N	18	12			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 2400E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-30	-11			
	0+12.5 S	-29	-14			
	0+25 S	-30	-12			
	0+37.5 S	-32	-15			
	0+50 S	-32	-16			
	0+62.5 S	-37	-12			
	0+75 S	-38	-12			
	0+87.5 S	-35	-8			
	1+00 S	-32	-5			
	1+12.5 S	-33	-4			
	1+25 S	-34	-6			
	1+37.5 S	-34	-14			
	1+50 S	-36	-6			
	1+62.5 S	-38	-8			
	1+75 S	-38	-12			
	1+87.5 S	-35	-10			
	2+00 S	-32	-10			
	2+12.5 S	-33	-8			
	2+25 S	-35	-12			
	2+37.5 S	-34	-10			
	2+50 S	-30	-6			
	2+62.5 S	-27	-4			
	2+75 S	-16	0			
	2+87.5 S	-10	5			
	3+00 S	-5	6			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

L2400 E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-26	-14	5+37.5 N	6	2
	0+12.5 N	-25	-16	5+50 N	7	4
	0+25 N	-25	-14	5+62.5N	10	8
	0+37.5N	-24	-11	5+75 N	14	10
	0+50 N	-24	-12	5+87.5 N	16	5
	0+62.5N	-23	-10	6+00 N	17	3
	0+75 N	-24	-11	6+12.5 N	—	— E.O.L.
	0+87.5N	-23	-15	6+25 N		
	1+00 N	-22	-10	6+37.5 N		
	1+12.5 N	-17	-6	6+50 N		
	1+25 N	-14	-4	6+62.5N		
	1+37.5 N	-9	-4	6+75 N		
	1+50 N	-9	-6	6+87.5 N		
	1+62.5N	-7	-4	7+00 N		
	1+75 N	-7	-3	7+12.5 N		
	1+87.5 N	-5	-1	7+25 N		
	2+00 N	-5	-2	7+37.5 N		
	2+12.5N	-3	-1	7+50 N		
	2+25 N	-1	-2	7+62.5N		
	2+37.5N	4	4	7+75 N		
	2+50 N	9	10	7+87.5 N		
	2+62.5N	10	11	8+00 N		
	2+75 N	11	9	8+12.5 N		
	2+87.5 N	13	8	8+25 N		
	3+00 N	13	5	8+37.5 N		
	3+12.5 N	14	7	8+50 N		
	3+25 N	13	8	8+62.5 N		
	3+37.5N	12	10	8+75 N		
	3+50 N	12	10	8+87.5 N		
	3+62.5N	8	4	9+00 N		
	3+75 N	11	7	9+12.5 N		
	3+87.5N	10	8	9+25 N		
	4+00 N	8	8	9+37.5N		
	4+12.5N	6	6	9+50 N		
	4+25 N	5	5	9+62.5 N		
	4+37.5N	3	6	9+75 N		
	4+50 N	3	5	9+87.5 N		
	4+62.5N	3	6	10+00 N		
	4+75 N	3	5			
	4+87.5 N	2	4			
	5+00 N	2	2			
	5+12.5 N	-2	3			
	5+25 N	4	4			

VIC CLAIMS — VLF EM SURVEY DATA (1986)

LINE 2600E

LINE	Station	In Phase	Quad.	Station	In Phase	Quad.
	0+00	-28	-16	5+37.5 N	13	0
	0+12.5 N	-25	-13	5+50 N	14	1
	0+25 N	-24	-11	5+62.5N	16	2
	0+37.5N	-19	-12	5+75 N	17	2
	0+50 N	-17	-14	5+87.5 N	17	1
	0+62.5N	-17	-12	6+00 N	16	1
	0+75 N	-16	-14	6+12.5 N	—	— E.O.L.
	0+87.5N	-13	-9	6+25 N		
	1+00 N	-10	-8	6+37.5 N		
	1+12.5 N	-7	-4	6+50 N		
	1+25 N	-6	-6	6+62.5N		
	1+37.5N	-7	-4	6+75 N		
	1+50 N	-4	-4	6+87.5 N		
	1+62.5N	-4	-2	7+00 N		
	1+75 N	-1	-2	7+12.5 N		
	1+87.5 N	4	-4	7+25 N		
	2+00 N	5	-1	7+37.5 N		
	2+12.5N	5	2	7+50 N		
	2+25 N	5	2	7+62.5N		
	2+37.5N	4	2	7+75 N		
	2+50 N	5	-1	7+87.5 N		
	2+62.5N	7	-3	8+00 N		
	2+75 N	8	4	8+12.5 N		
	2+87.5 N	8	4	8+25 N		
	3+00 N	11	5	8+37.5 N		
	3+12.5 N	9	4	8+50 N		
	3+25 N	10	4	8+62.5 N		
	3+37.5N	9	6	8+75 N		
	3+50 N	9	6	8+87.5 N		
	3+62.5N	9	4	9+00 N		
	3+75 N	10	6	9+12.5 N		
	3+87.5N	10	3	9+25 N		
	4+00 N	7	6	9+37.5N		
	4+12.5N	8	8	9+50 N		
	4+25 N	7	-8	9+62.5 N		
	4+37.5N	5	6	9+75 N		
	4+50 N	4	-4	9+87.5 N		
	4+62.5N	4	3	10+00 N		
	4+75 N	5	4			
	4+87.5 N	6	6			
	5+00 N	8	4			
	5+12.5 N	8	5			
	5+25 N	10	3			

091907

STATEMENT OF QUALIFICATIONS

I, Kim Heberlein, certify that:

1. I am a geologist residing at 821 Pinemont Avenue, Port Coquitlam, B.C.
2. I graduated from the University of British Columbia in 1979 with a B.Sc. in geology.
3. I have worked in geological exploration since 1976.
4. I have no direct or indirect interest in the said property.

Signed: K. Heberlein

Date: 6th Feb 1987