MAP NO.:	**ASSESSMENT REPORT**	X	**DOCUMENT NO:**	092143
	PROSPECTUS		**MINING DISTRICT:**	WHITEHORSE
105 D 3	**CONFIDENTIAL**	X	**TYPE OF WORK:**	DIAMOND DRILLING
	OPEN FILE			

REPORT FILED UNDER:		Omni Resources Inc.		
DATE PERFORMED:		January - December 1987	**DATE FILED:**	May 1988
LOCATION:	**LAT.:**	$60^{O}10'N$	**AREA:**	Wheaton River Valley
	LONG.:	$135^{O}24'W$	**VALUE $:**	

CLAIM NAME & NO.: WH 1-8 Y75547-54; ERN 1-15 YA81543-57; TREE 1-5 YA82961-65; ERN 16-27 YA85503-14; ERN 30-33 YA85515-18; KIM 1-52 YA92781-832; TEX 1-22 YA92833-54; KIR 1-33 YA92967-99; OMNI 1-12 YA93743-54

WORK DONE BY: R.J. Robinson

WORK DONE FOR: Omni Resources Inc.

DATE TO GOOD STANDING:

REMARKS: #21 MT. REID (SKUKUM CREEK) EIP Report
In 1987, 81 surface and underground holes were drilled totalling 7446 m. Reserves were estimated at 406761 tonnes grading 6.7 g/t Au and 365.1 g/t Ag in the RAINBOW zone and 166 475 tonnes grading 19.7 g/t Au and 288.3 g/t Ag in the KUHN zone.

Yukon
Economic Development:
Mines & Small Business
Box 2703, Whitehorse, Yukon Y1A 2C6
(403) 667-5811 Telex 036-8-260

Our File:
Your File:

22 May 1988

Trevor Bremnar
Exploration and Geological Services Division
Northern Affairs Program
200 Range Road
Whitehorse, Yukon

Dear Trevor,

Please find enclosed 1987 Exploration Incentives Program Report for EIP87-026/OMNI RESOURCES INC.. The report is confidential until 1 April 1990.

Respectfully,

David A. Downing
Mining Development Officer

encl.

092143

DESIGNATION NUMBER EIP 87-026

Report on Diamond Drilling and Underground Exploration for claims listed (claim sheet No. 105D/3)

Claim/ Lease No.	Record No.
WH 1 - 8 incl.	Y75547 - 54 incl
ERN 1 - 15 incl.	YA81543 - 57 incl.
TREE 1 - 5 incl.	YA82961 - 65 incl.
ERN 16 - 27 incl.	YA85503 - 14 incl.
ERN 30 - 33 incl.	YA85515 -18 incl.
KIM 1 - 52 incl.	YA92781 - 832 incl.
TEX 1 - 22 incl.	YA92833 - 54 incl.
KIR 1 - 33 incl.	YA92967 - 99 incl.
OMNI 1 - 12 incl.	YA93743 - 54 incl.

Latitude 60 10' North
Longitude 135 24' West

Holder of Claims: Omni Resources Inc.

Author: R. James Robinson B.Sc. (Geol.)

Report prepared for: Omni Resources Inc.

092143

REPORT ON THE SKUKUM CREEK PROPERTY

Whitehorse Mining District, Yukon Territory.

Location: NTS Map No. 105 D/3
40 miles south of Whitehorse, Yukon
Latitude 60 10' north
Longitude 135 24' west

For: Yukon Economic Development
Mines and Small Business
Box 2703, Whitehorse, Yukon
Y1A 2C6

By: R. J. Robinson (B. SC.)

February, 1988

092143

INTRODUCTION

The following report is submitted in compliance with Schedule B of the Yukon Economic Development, Mines and Small Business, Exploration Incentives Program.

092143

ACKNOWLEDGMENTS

Portions of the text of this report have been taken in whole or in part from Montgomery, 1987, and from a presentation made to the Yukon Geoscience forum by Lang et al, 1987. The location Map (Fig.1) was adapted from Foster et al, 1986.

092143

TABLE OF CONTENTS

INTRODUCTION	i
ACKNOWLEDGMENTS	ii
TABLE OF CONTENTS	iii
LIST OF FIGURES	iv
LIST OF APPENDICES	iv
LIST OF TABLES	iv
LOCATION AND ACCESS	1
CLIMATE TOPOGRAPHY AND VEGETATION	1
HISTORY	3
REGIONAL GEOLOGY	4
GEOLOGY OF THE MOUNT REID AREA	5
UNDERGROUND EXPLORATION	7
DIAMOND DRILLING	8
ORE RESERVES	8
METALLURGY	9
ENVIRONMENTAL	9
FUTURE WORK	10
REFERENCES	12
QUALIFICATION STATEMENTS	13-14

092143

LIST OF FIGURES

		Page No.
FIG 1	PROPERTY LOCATION	2
FIG 2	CROSS CUT NO.1 SAMPLE LOCATIONS & ASSAY RESULTS	18
FIG 3	CROSS CUT NO. 2 SAMPLE LOCATIONS & ASSAY RESULTS	19
FIG 4	CLAIM MAP AND DRILL LOCATIONS	Pouch 1
FIG 5	DETAILED SURFACE DRILL LOCATIONS	Pouch 2
FIG 6	RAINBOW ZONE 1300 LEVEL PLAN	Pouch 3
FIG 7	KUHN ZONE 1307 LEVEL PLAN	Pouch 4
FIG 8	VERTICAL LONGITUDINAL SECTION; RAINBOW ZONE	Pouch 5
FIG 9	VERTICAL LONGITUDINAL SECTION; KUHN ZONE	pouch 6

LIST OF APPENDICES

APPENDIX 1	ABBREVIATED STATEMENT OF COSTS AND INVOICES	-
APPENDIX 2	CLAIM STATUS	-
APPENDIX 3	CONTRACTORS AND EMPLOYEES	-
APPENDIX 4	REPORT BY F. MARSHAL SMITH	-
APPENDIX 5	DIAMOND DRILL LOGS	-
APPENDIX 6	ASSAY RESULTS	-

LIST OF TABLES

TABLE 1	DRILL LOCATION SUMMARY AND DRILL HOLE DATA	15

092143

LOCATION AND ACCESS


The Skukum Creek property is located about 50 kilometers by air or 70 kilometers by road southwest of Whitehorse in the Wheaton River valley area. The claim area covers the Wheaton River valley, Mount Ward, Mount McNeil, Mount Reid, and the lower slopes of Chieftain Hill. The main focus of exploration thus far, and the subject of this report is the area centered on the eastern flank of Mount Reid. Access to the property is via the Annie Lake road, an all - weather gravel road which joins the South Klondike highway seventeen kilometers south of the Alaska Highway junction. Omni has constructed a five kilometer road to Berney Creek, where a fully winterized thirty-five man camp was built last year.

CLIMATE, TOPOGRAPHY AND VEGETATION

Elevations on the property range from 1,000 to 2,100 m ASL, and tree line is at approximately 1225 m. The Wheaton River valley is broad, flat-bottomed and deeply covered by glacial overburden. The south-east slopes of Chieftain Hill, Mount Reid and Mount McNeil and the north-west slope of Mount Ward are cut by steep cliffs and deep, sharp gullies, while the other slopes are more gentle with broader, deep gullies. The high plateaus are covered with felsenmeer, and above 1500 m, permafrost becomes a problem.

Vegetation below the tree line is primarily stunted spruce, popolar, and willow, while on the upper slopes grasses and other alpine shrubs and low vegetation prevail.

092113



OMNI RESOURCES INC.			
SKUKUM CREEK PROPERTY			
LOCATION 092143			
Aurum Geological Consultants Inc.	January, 1986		
Drawn by N.H.	Checked by R.H.	Scale 1:1,000,000	FIGURE 1

Precipitation is low year round with light rainfall in the summer and snow cover to one and a half meters in winter. Summers are mild but short with occasional high temperatures to thirty degrees Celsius, although snow flurries and frost can be expected at any time. Snow cover on the property lasts from late October to mid June with low temperatures to -45 degrees Celsius.

HISTORY

Although the existence of gold-bearing mineralization on the property has been known since 1922, the area has only recently attracted large-scale exploration activity since the discovery by AGIP Canada of the Mount Skukum ore body. Omni's Skukum Creek deposit is located just five kilometres from the Mount Skukum Mine.

The claims which are currently the main focus of exploration on the Skukum Creek property were originally staked in 1922, rock trenching was carried out and a 41 metre adit driven. In 1930-31, J. Stenbraten improved road access and did more trenching. He restaked the ground several times and eventually drove a 30 metre adit. In 1965 Yukon Antimony built a tote trail to the showings and did some bulldozer trenching. The ground was restaked by Bill Kuhn in 1973 on behalf of El Paso Mining and Milling Co. who mapped and soil-sampled in 1974 and returned the ground to Kuhn in 1976. Con-Am Resources acquired the ground in 1977, marked out a new grid, and resampled old trenches. Minor assessment work

092143

was done on the property by various owners up to 1985, when the WH 1-8 claims (the original claim group) were acquired by Omni from Skukum Gold Inc.

In 1984 and 1985 a total of 296 contiguous claims were consolidated under various option agreements, and in essence the Skukum Creek property became wholly owned by Omni resources Inc.

In 1985 Omni conducted a percussion and diamond drilling program, mapped, prospected took 597 soil samples, and ran 1.47 line kilometers of dipole - dipole apparent resistivity geophysics. During the 1986 field season the focus was on diamond drilling and detailed mapping of 4 main zones; the Rainbow, Road, Kuhn and Sterling. Fifty-three NQ holes totalling about 8200 m were drilled, the majority in the Kuhn and Rainbow zones. In addition, two NQ holes totalling 43 meters were drilled to test the overburden depth and rock quality at a proposed adit site.

REGIONAL GEOLOGY

The Skukum Creek property is located on the eastern flank of the Coast Plutonic Complex. The Coast Plutonic Complex is composed of foliated and non-foliated granitoid - mainly granodiorite, granite, and quartz diorite- rocks of primarily Upper Mesozoic age. This unit is flanked by older metamorphosed and unmetamorphosed sedimentary and volcanic rocks of the Yukon Lewes River, and Laberge Groups, and Tantalus Formation to the east. Northwest of the Wheaton

River, volcanic flows and pyroclastic rocks of the Paleocene-Eocene age Mount Skukum Complex unconformably overlie the Coast Plutonic and Yukon Group rocks. The volcanics range in composition from basalt to rhyolite, and have been divided into a basal andesitic unit, a medial assemblage of felsic rocks, and an upper basaltic unit. The Mount Skukum Complex has been downfaulted by a series of moderate to vertical faults, and the structure to the south and east is of particular interest. This structure, the Berney Creek Fault is a nearly straight, north-easterly striking fault easily spotted on air photos and Landsat images as a lineament extending from Mount McNeil, across Mt. Reid and Chieftain Hill, and on through Vesuvius Hill. This fault is believed to be a major conduit for metallogenic fluids, due to the number of showings of economic interest located along its strike.

GEOLOGY OF THE MOUNT REID AREA

The main fracture set on the property trends northeast, parallel to the Berney Creek Fault , and it is along these faults and shears that the main mineralization occurs. The Rainbow zone strikes 55 degrees and dips southward at about 78 degrees over most of its length, but shallows out to about 65 degrees to the southeast in the Rainbow - Kuhn bend. The Kuhn zone generally strikes about 72 degrees and dips very steeply to the south- usually about 85 degrees, but in some short sections it dips vertically or steeply to the north.

Rock types found on the property include Jurassic age quartz arenites and chert pebble conglomerates of the Tantalus Fm., granodiorites, quartz monzonites, and granites of the Coast Plutonic Complex, Skukum Group volcanics, rhyolite and andesite dykes coeval with the Skukum Volcanics, and later dykes and veins of uncertain age, including the mineralized quartz and carbonate veins comprising the Skukum Creek deposit.

The rhyolite and andesite dykes are concentrated in zones of weakness along faults or lithologic contacts and may have been conduits for the Skukum Volcanic magma. The rhyolite is tan to pale green, aphanitic, flow banded,and in some zones, spherulitic and/or auto-brecciated. Andesite is generally dark greenish-grey to black, and very fine grained. Alteration varies from fresh to strong propylitic and phyllic alteration adjacent to and in the shear zones.

The mineralization occurs mainly as brecciated quartz - sulfide veins with carbonates, clays, and rare barite present as gangue, within - or proximal to - rhyolite or andesite dykes along shear zones in the granodiorite host rock. Metallic minerals recognized to date include pyrite, galena, sphalerite, chalcopyrite, stibnite, arsenopyrite, pyrargerite, tetrahedrite, argentite, electrum and native gold. Sulfide content in the mineralized zone is generally moderate to high, and high gold-silver assays coincide with high lead-zinc values, especially in the Rainbow zone.

A petrographic study of fifteen drill core samples, by

Vancouver Petrographics Ltd. concluded that two distinct phases of mineralization occurred; an initial event with pyrite intergrown with quartz, and a second stage which involved fracturing, shearing, and the introduction of stibnite, sphalerite, galena, tetrahedrite, chalcopyrite, argentite and electrum.

UNDERGROUND EXPLORATION

A production sized adit was collared on the 1300 m level in January of 1987. Between April and July, about 823 metres of underground work was completed. Excellent ground conditions were encountered which permitted mining rates of up to 12 metres per day. The work consisted of a 9' X 11' adit driven on the footwall side of the vein with two crosscuts through the Rainbow Zone which allowed for sampling of the vein and access for drilling. We expected to hit the Rainbow Zone again when we made the turn to the Kuhn Zone but quickly discovered the vein itself made the same sharp bend to the south. A total of six diamond drill stations were cut. As expected, we found that the Rainbow and Road zones were one and the same, part of the same structure, and connected at depth. Somewhat surprisingly however, we found that the Rainbow and Kuhn zones are also connected, and what was called the "Kuhn Splay" and part of the Sterling zone is in fact a continuous, sinusoidal structure joining the two zones.

DIAMOND DRILLING

A total of 81 diamond drill holes were drilled in 1987, 69 underground and 12 from surface, for a total of 7,446 metres. Ten of the surface holes were targeted in the Rainbow Zone and two tested for an eastward extension of the Kuhn Zone south of the Rainbow Zone. Of the underground holes, 36 intersected the Rainbow Zone, 21 the Kuhn Zone and 12 were drilled into the Rainbow close to the crosscuts to test for correlation between drillholes, between drillholes and underground mapping, and after the next mining phase, between drill core assay results and actual "Mine grade". All of the drill core is of NQ size.

The drill core is stored on site at the permanent Omni camp. The core from the intersections was split in half for analysis and stored on racks in locked wooden sheds, and the barren country rock was labelled and stacked near the sheds.

ORE RESERVES

Ore reserves were calculated both from cross sections and long sections. The polygonal area method on the vertical longitudinal section produced the most easily reproducible results, so that reserve value is the one most commonly quoted. Based on current estimates the Rainbow zone contains 447,138 tons (drill indicated plus proven) grading 0.196 ounces gold and 10.65 ounces silver per ton. The current reserve on the Kuhn zone is 373,536 tons (drill indicated plus proven) grading 0.261 ounces gold and 4.95 ounces silver.

092143

per ton. Within this reserve are a number of high grade blocks. Within the Kuhn zone there are 183,000 tons grading 0.575 ounces gold and 16.5 ounces silver per ton. The total reserve including drill inferred blocks consists of 951,814 tons grading 0.230 ounces gold and 8.41 ounces silver per ton, for a total of 218,917 ounces contained gold and over 8,000,000 ounces of silver. The structures are still both open to depth and to the east and west along strike.

METALLURGY

Metallurgical testing of the ore is being carried out by Bacon, Donaldson, and Associates under the direction of Orocon Inc. A 450 pound sample was shipped to Vancouver in September for metallurgical testing. The work to date has indicated that we will have no trouble achieving gold and silver recoveries of over 90 percent. It is expected that a conventional cyanide leach circuit will be employed followed by a flotation circuit which will produce a high-grade silver concentrate. The company plans to build a mill with an initial capacity of 300 tons per day which is capable of rapid expansion to 500 tons per day.

ENVIRONMENTAL

Baseline water volume and quality testing has been ongoing for the last two years by and under the supervision of Norecol Environmental Consultants limited. A comprehensive environmental report has been prepared for Omni

992143

Resources by Norecol (Norecol, 1987). A major element of this year's program has been the identification and selection of a suitable tailings site. Three sites have been investigated and all are located in the Wheaton River Valley within a glacio-lacustrine environment. The surface sediments are composed of silts and clays similar to those found at the Mount Skukum tailings site located just two kilometres away. A tailings dam design is currently underway by Steffen, Robertson, and Kirsten, our geotechnical consultants, and is expected to be completed shortly.

FUTURE WORK

Permitting and a pre-feasiblity study will be undertaken early this spring. A second mining phase is planned to begin before spring. This program will involve extending the crosscuts in the Kuhn and Rainbow Zones to permit deeper drilling, as well as further drifting on the 1300 m level to obtain a correlation factor between drill hole grade and true grade. A raise will be driven in the Kuhn Zone to permit subdrifting on the 1350 m level. In addition to proving up further reserves, this program will also permit a further evaluation of the mining conditions needed for the eventual stope design.

A 15,000 to 20,000 foot diamond drill program is planned for 1988. Holes will be drilled from both surface and underground. In addition to drilling, the Rainbow and Kuhn zones, we plan to execute further mapping, sampling and

diamond drilling on the Polaris Ridge and especially the King zones. It is expected that Omni will be in a position to make a production decision sometime in 1988.

092143

REFERENCES

FORSTER, C.N., R.W. HULSTEIN, & H.J. KEYSER, 1986: Report on Skukum Creek Property. Private report for Omni Resources Inc.

LANG, B.D.A., AND ROBINSON, R.J., 1987: Text of presentation to the Whitehorse Geoscience Forum, December 2, 1987.

LITTLE JOHN, A.L., 1986: Untitled Petrographic Report by Vancouver Petrographics Ltd. for Omni Resources Inc.

MONTGOMERY, A.T., 1986: Report on Diamond Drilling, Geology and Geochem on Skukum Creek Project. Private report for Omni Resources Inc.

NORECOL ENVIRONMENTAL CONSULTANTS LTD., 1987: Environmental Report for The Skukum Creek Project. Private report for Omni Resources Inc.

OMNI RESOURCES INC., 1987: Project Overview of Omni Resources Inc.'s Skukum Creek Project. An internal report.

PRIDE, M.J., 1985: Preliminary Geological Map of Mt. Skukum Volcanic Complex, 1:25,000 Scale Map, D.I.A.N.D., open file.

ROBERTON, J., 1987: Project 64101: Tailings Site Selection and Design. Private report for Omni Resources Inc.

WHEELER, J.O., 1961: Whitehorse Map Area, Yukon Territory. 105D. G.S.C. Memoir 312.

092143

STATEMENT OF QUALIFICATIONS

I, RONALD JAMES ROBINSON OF #414, 80 Sandcastle Drive, Nepean, Ontario, do hereby certify that:

1. I have been employed as a geologist by Omni Resources Inc. since May, 1987.

2. I am a graduate of the University of British Columbia, Vancouver, B.C. with a B.Sc. degree in Geology.

3. I supervised the work described in this report.

4. I have been practising my profession on a full and part time basis in Canada for seven years.

Respectfully submitted,

R.J. Robinson

Ronald James Robinson

February 19, 1988

STATEMENT OF QUALIFICATIONS

I, BRENNAN DAVIS ALLAN LANG of #306-922.5 Alaska Highway Whitehorse, Yukon certify that:


1. I have been employed as a mining Engineer by Omni Resources Inc. since May, 1987.

2. I am a graduate of the University of British Columbia, Vancouver, B.C. with a B.A.Sc. degree in Mining and Mineral Processing Engineering.

3. I supervised the work described in this report.

4. I have been practising my profession on a full and part time basis in Canada for seven years.

Respectfully submitted,



Brennan D.A. Lang
February 21, 1988

TABLE 1: DRILL LOCATION AND DRILL HOLE DATA

Hole Number	Azimuth (deg.)	Dip (deg.)	Collar Coordinates Northing	Easting	Elevation	Length (m)	Advance (m)	Depth (m)	Length to H.W.	Advance to H.W.	Depth to H.W.	Elevation of H.W.	Length to F.W.	Advance to F.W.	Depth to F.W.	Elevation of F.W.	H.W. Grid North	F.W. Grid North
87-D1	7	-67	71177.0	78070.0	1354.0	167.03	65.27	-153.75	149.10	58.26	-137.25	1216.75	155.60	60.80	-143.23	1210.770	1087.8	1088.2
87-D2	335	-76	71177.0	78070.0	1354.0	274.32	66.37	-266.17	219.25	53.05	-212.74	1141.26	268.30	64.91	-260.33	1093.671	1086.6	1088.5
87-D3	318	-76	71177.0	78070.0	1354.0	250.85	60.69	-243.40	209.15	50.60	-202.94	1151.06	224.80	54.39	-218.12	1135.878	1070.4	1070.1
87-R4	333	-65	71085.0	78057.5	1395.3	253.53	107.15	-229.77	282.05	119.20	-255.62	1139.68	310.39	131.18	-281.31	1113.993	1030.1	1031.6
87-G1A	331	-76	71255.8	78181.4	1292.7	269.14	65.12	-261.14	207.26	50.15	-201.10	1091.60	213.36	51.62	-207.02	1085.678	1219.1	1219.2
87-R6	314	-54	71202.7	78121.7	1331.0	132.89	78.11	-107.51	110.37	64.88	-89.29	1241.71	121.80	71.59	-98.54	1232.462	1121.1	1119.9
87-R7	314	-64	71202.7	78121.7	1331.0	163.98	71.89	-147.38	140.94	61.79	-126.67	1204.33	154.84	67.88	-139.17	1191.832	1121.8	1120.5
87-R8	298	-58	71202.7	78121.7	1331.0	156.36	82.86	-132.60	128.93	68.32	-109.34	1221.66	141.12	74.78	-119.68	1211.324	1103.6	1100.5
87-R9	335	-72	71177.0	78070.0	1354.0	195.99	60.57	-186.40	167.61	51.80	-159.41	1194.59	184.95	57.16	-175.90	1178.103	1086.8	1087.7
87-K1	180	-62	71140.0	78001.0	1400.0	342.60	160.85	-302.49	319.00	149.77	-281.66	1118.34	342.60	160.85	-302.49	1097.505	908.2	914.6
87-K2	180	-55	71140.0	78001.0	1400.0	345.34	198.08	-282.88	293.22	168.19	-240.19	1159.81	302.73	173.64	-247.98	1152.020	900.3	903.7
87-U61R	325	-38	71160.3	77984.3	1300.0	58.52	46.11	-36.03	44.00	34.67	-27.09	1272.91	53.03	41.79	-32.65	1267.351	972.2	972.2
87-U62R	325	-66	71160.3	77984.3	1300.0	88.39	35.95	-80.75	67.97	27.65	-62.09	1237.91	82.05	33.37	-74.96	1225.044	972.2	972.2
87-U63R	325	-77	71160.3	77984.3	1300.0	124.36	27.98	-121.17	97.70	21.98	-95.20	1204.80	121.00	27.22	-117.90	1182.101	972.2	972.2
87-U64R	291	-34	71160	77986.5	1300.0	64.0	53.07	-35.79	45.25	37.51	-25.30	1274.70	60.35	50.03	-33.75	1266.253	974.8	967.1
87-U65R	299	0	71086.5	77890.2	1303.5	50.90	50.90	0.00	33.95	33.95	0.00	1303.50	48.00	48.00	0.00	1303.5	862.1	855.7
87-U66R	278	1	71086.5	77891.1	1302.4	49.38	49.37	0.86	36.67	36.86	0.64	1303.04	49.00	48.99	0.86	1303.255	849.5	841.3
87-U67R	265	1	71084.9	77889.0	1303.5	60.65	60.64	1.06	37.40	37.39	0.65	1304.15	45.00	44.99	0.79	1304.285	843.4	836.2
87-U68R	199	3	71082.9	77890.5	1303.7	185.62	185.37	9.71	89.12	89.00	4.66	1308.36	130.45	130.27	6.83	1310.527	?	?
87-U68K	199	3	71082.9	77890.5	1303.7	185.62	185.37	9.71	168.65	168.42	8.83	1312.53	172.94	172.70	9.05	1312.750	?	?
87-U69R	258	-40	71084.9	77888.9	1302.6	69.49	53.23	-44.67	44.59	34.16	-28.66	1273.94	48.74	37.34	-31.33	1271.270	844.1	841.2
87-U610R	260	-67	71084.9	77888.9	1302.4	89.61	35.02	-82.49	62.18	24.30	-57.24	1245.16	75.89	29.65	-69.86	1232.543	853.2	848.7

continued....

092143

Hole Number	Azimuth (deg.)	Dip (deg.)	Collar Coordinates Northing	Easting	Elevation	Length (m)	Advance (m)	Depth (m)	Length to H.W.	Advance to H.W.	Depth to H.W.	Elevation of H.W.	Length to F.W.	Advance to F.W.	Depth to F.W.	Elevation of F.W.	H.W. Grid North	F.W. Grid North
87-U611R	319	-37	71087.3	77891.1	1302.4	55.78	44.55	-33.57	39.50	31.55	-23.77	1278.63	53.58	42.79	-32.24	1270.155	875.6	874.6
87-U612R	318	-66	71086.7	77890.6	1302.4	75.59	30.75	-69.05	54.44	22.14	-49.73	1252.67	69.49	28.27	-63.48	1238.918	875.1	873.8
87-U613R	319	30	71086.1	77890.2	1305.5	86.56	74.96	43.28	60.96	52.79	30.48	1335.98	71.63	62.03	35.81	1341.314	871.7	870.5
87-U614R	354	1	71092.0	77897.5	1304.0	71.02	71.01	1.24	52.49	52.48	0.92	1304.92	61.42	61.41	1.07	1305.071	912.1	916.4
87-U615R	10	-32	71092.1	77897.7	1302.6	81.69	69.28	-43.29	60.78	51.54	-32.21	1270.39	75.59	64.10	-40.06	1262.544	912.4	923.1
87-U616R	14	-47	71091.9	77897.7	1302.4	94.18	64.23	-68.88	70.38	48.00	-51.47	1250.93	91.53	62.42	-66.94	1235.460	923.0	933.5
87-U617R	15	-56	71091.8	77897.7	1302.3	124.66	69.71	-103.35	78.73	44.03	-65.27	1237.03	119.33	66.73	-98.93	1203.372	920.2	937.6
87-U618K	311	1	70855.7	77758.9	1306.9	61.57	61.56	1.07	45.17	45.16	0.79	1307.72	50.32	50.31	0.88	1307.808	527.0	524.2
87-U619K	20	3	70856.8	77768.0	1307.0	76.50	76.40	4.00	46.24	46.18	2.42	1309.40	68.92	68.83	3.61	1310.586	582.5	596.0
87-U620K	21.8	-30.8	70856.4	77762.9	1306.1	76.81	65.98	-39.33	49.07	42.15	-25.13	1280.94	58.13	49.93	-29.76	1276.305	580.9	586.1
87-U621K	21	-54	70856.4	77762.9	1306.0	96.62	56.79	-78.17	74.68	43.90	-60.42	1245.58	81.08	47.66	-65.59	1240.405	581.6	584.1
87-U622K	156	35	70954.7	77767.0	1306.9	64.31	52.68	36.89	59.83	49.01	34.32	1341.18	43.25	35.43	24.81	1331.666	593.4	591.8
87-U623K	156	54	70854.7	77767.0	1308.2	61.57	36.19	49.81	46.60	27.39	37.70	1345.90	61.57	36.19	49.81	1358.010	591.6	590.6
87-U624K	289	2	70854.1	77753.3	1307.0	87.78	87.73	3.06	59.59	59.55	2.08	1309.12	73.49	73.45	2.56	1309.604	502.3	491.0
87-U625K	272	0	70853.1	77759.2	1307.1	127.71	127.71	0.00	100.40	100.40	0.00	1307.08	119.73	119.73	0.00	1307.08	454.8	436.2
87-U626K	312	39	70855.4	77759.3	1309.1	86.56	67.27	54.47	63.09	49.03	39.70	1348.84	74.37	57.80	46.80	1355.941	525.0	520.3
87-U627K	289	30	70854.6	77759.0	1308.9	97.54	84.47	48.77	75.90	65.73	37.95	1346.85	81.99	71.01	40.99	1349.894	497.5	493.0
87-U628K	346.5	-34.7	70854.8	77761.4	1305.9	74.07	60.90	-42.17	43.80	36.01	-24.93	1280.92	49.16	40.42	-27.99	1277.864	554.7	555.0
87-U629K	350	37	70857.5	77761.0	1309.0	71.02	56.72	42.74	48.92	39.07	29.44	1338.44	62.48	49.90	37.60	1346.600	557.7	559.2
87-U630K	350	56.5	70855.5	77761.0	1309.5	108.81	60.06	90.73	83.85	46.28	69.92	1379.42	104.24	57.54	86.92	1396.423	558.3	559.9
87-U631K	265.7	0	70852.5	77759.4	1307.1	179.83	179.83	0.00	148.74	148.74	0.00	1307.11	170.69	170.69	0.00	1307.11	403.8	383.2
87-U632K	316	54	70852.5	77759.4	1307.6	106.38	62.53	86.06	83.70	49.20	67.71	1375.31	97.84	57.51	79.15	1386.753	528.8	524.8
87-U633K	303	38	70854.4	77753.3	1307.0	90.83	71.58	55.92	71.02	55.97	43.72	1350.72	79.64	62.76	49.03	1356.030	514.1	510.0
87-U634K	4	0	70856.4	77762.9	1308.2	8.23	8.23	0.00	-	-	-	-	-	-	-	-	-	-
87-U635K	132	3	70955.0	77768.0	1304.8	72.54	72.44	3.80	60.47	60.39	3.16	1307.96	39.84	39.79	2.09	1306.885	618.7	608.5
87-U636K	147	-22	70954.0	77766.9	1304.2	67.66	62.73	-25.35	65.01	60.28	-24.35	1279.81	45.87	42.53	-17.18	1286.982	603.0	598.6
87-U637K	123	-34	70954.8	77767.6	1304.2	99.97	82.88	-55.90	90.49	75.02	-50.60	1253.59	66.26	54.93	-37.05	1267.139	635.1	622.5
87-U638R	122.3	-46.5	71257.9	77999.4	1300.0	83.82	57.70	-60.80	72.82	50.13	-52.82	1247.18	66.54	45.80	-48.27	1251.734	1085.5	1083.6
87-U639R	155	-53	71257.3	77998.3	1300.0	85.04	51.18	-67.92	73.55	44.26	-58.74	1241.29	66.66	40.12	-53.24	1246.788	1057.1	1058.8
87-U640R	156	-35	71257.1	77998.4	1300.4	62.18	50.94	-35.66	47.67	39.05	-27.34	1273.09	42.95	35.18	-24.63	1275.801	1056.0	1058.8
87-U641R	189	45	71256.9	77997.1	1303.6	71.02	50.22	50.22	58.83	41.60	41.60	1345.20	48.73	34.46	34.46	1338.056	1035.6	1043.3
87-U642R	165	55	71257.9	77997.8	1304.1	59.13	33.92	48.44	55.08	31.59	45.12	1349.22	45.72	26.22	37.45	1341.551	1052.3	1056.5

092143


continued....

Hole Number	Azimuth (deg.)	Dip (deg.)	Collar Coordinates Northing	Easting	Elevation	Length (m)	Advance (m)	Depth (m)	Length to H.W.	Advance to H.W.	Depth to H.W.	Elevation of H.W.	Length to F.W.	Advance to F.W.	Depth to F.W.	Elevation of F.W.	H.W. Grid North	F.W. Grid North
87-U643R	164.5	0	71256.8	77998.4	1301.3	41.45	41.45	0.00	38.37	38.37	0.00	1301.29	29.35	29.35	0.00	1301.291	1055.7	1057.6
87-U644R	1.2	1.8	71160.4	77988.7	1301.9	63.40	63.37	1.99	49.07	49.05	1.54	1303.41	53.92	53.89	1.69	1303.563	1029.5	1032.6
87-U645R	6.6	-28.6	71159.8	77988.8	1300.6	63.40	55.66	-30.35	57.00	50.05	-27.29	1273.35	58.52	51.38	-28.01	1272.619	1033.5	1034.5
87-U646R	8	-54	71159.8	77988.8	1300.6	89.61	52.67	-72.50	71.90	42.26	-58.17	1242.46	79.43	46.69	-64.26	1236.372	1030.5	1033.8
87-U647R	10	-67.7	71158.9	77989.2	1300.5	129.20	49.03	-119.54	101.68	38.58	-94.07	1206.47	121.31	46.03	-112.24	1188.311	1028.2	1033.3
87-U648R	275	-51.8	71156.8	77985.7	1300.5	101.50	62.77	-79.76	76.60	47.37	-60.20	1240.25	94.24	58.28	-74.06	1226.392	951.3	959.7
87-U649R	279.5	-61.5	71156.7	77986.1	1300.4	110.95	52.94	-97.50	83.73	39.95	-73.58	1226.82	102.20	48.77	-89.81	1210.588	968.0	961.7
87-U650R	156.3	-21.2	71190.7	77899.4	1301.2	51.51	48.02	-18.63	42.82	39.92	-15.48	1285.72	30.02	27.99	-10.86	1290.352	937.6	940.0
87-U651R	174.9	29.6	71190.8	77898.9	1303.8	43.89	38.16	21.68	39.31	34.18	19.42	1323.17	24.65	21.43	12.18	1315.929	934.2	928.0
87-U652R	102.7	38.8	71192.0	77900.7	1304.0	49.07	38.24	30.75	46.21	37.06	29.79	1333.83	36.18	28.20	22.67	1326.709	965.9	972.3
87-U653R	343	-23	71192.5	77952.8	1302.6	51.66	47.55	-20.18	39.78	36.62	-15.54	1287.06	49.25	45.33	-19.24	1283.356	896.8	899.5
87-U654R	347	-53	71192.5	77952.8	1302.4	67.66	40.72	-54.04	48.34	29.09	-38.61	1263.79	63.64	38.30	-50.82	1251.575	896.5	899.9
87-U655R	345	45	71192.5	77952.8	1304.1	112.16	79.30	79.31	92.90	65.69	65.69	1369.79	110.34	78.02	78.02	1382.121	908.3	912.5
87-U656R	265	44	71084.9	77889.0	1304.9	70.56	50.76	49.01	50.87	36.59	35.34	1340.24	65.13	46.85	45.24	1350.142	834.6	843.4
87-U657R	115	-14.8	954.7	7767.8	1304.5	85.95	83.10	-21.96	79.52	76.68	-20.31	1284.17	53.43	51.66	-13.65	1290.836	645.5	627.0
87-TH1	316.5	0.4	1190.6	7963.8	1302.6	9.45	9.45	0.07		0.00	0.00	1302.55		0.00	0.00	1302.553		
87-TH2	308.2	1.9	1190.1	7963.9	1301.4	10.67	10.66	0.35		0.00	0.00	1301.44		0.00	0.00	1301.435		
87-TH3	345.4	1.4	1194.5	7964.7	1302.4	10.67	10.67	0.26		0.00	0.00	1302.45		0.00	0.00	1302.449		
87-TH4	342.7	0	1194.6	7964.9	1301.5	10.67	10.67	0.00		0.00	0.00	1301.47		0.00	0.00	1301.471		
87-TH5						15.54	15.54	0.00		0.00	0.00	0.00		0.00	0.00	0		
87-TH6						18.29	18.29	0.00		0.00	0.00	0.00		0.00	0.00	0		
87-TH7						18.90	18.90	0.00		0.00	0.00	0.00		0.00	0.00	0		
87-TH8						16.46	16.46	0.00		0.00	0.00	0.00		0.00	0.00	0		
87-TH9						15.54	15.54	0.00		0.00	0.00	0.00		0.00	0.00	0		
87-TH10						18.29	18.29	0.00		0.00	0.00	0.00		0.00	0.00	0		
87-TH11						18.90	18.90	0.00		0.00	0.00	0.00		0.00	0.00	0		
87-TH12						16.46	16.46	0.00		0.00	0.00	0.00		0.00	0.00	0		


092143

093143

CHANNEL SAMPLES



PANEL AND MUCK SAMPLES



CHANNEL SAMPLE AVERAGE

W. WALL - 9.2'/0.067 Au/9.60 Ag

E. WALL - 17.0'/0.051 Au/1.44 Ag

AVG. - 13.1'/0.057 Au/4.31 Ag

DIAMOND DRILL HOLE

85-15 - 11.9'/0.075 Au/9.14 Ag

PANEL SAMPLE AVERAGE

E. WALL - 16.0'/


MUCK SAMPLE AVERAGE

13.4'/0.067 Au/3.26 Ag

FIGURE 2


OMNI RESOURCES INC.	
SKUKUM CREEK PROPERTY CROSSCUT NO. 1 SAMPLE LOCATIONS & ASSAY RESULTS	
JULY 15, 1987	SCALE 1"=10'

CHANNEL SAMPLES





PANEL AND MUCK SAMPLES



92148

CHANNEL SAMPLE AVERAGE

W. WALL - 27.0'/0.250 Au / 10.14 Ag

E. WALL - 25.0'/0.122 Au / 16.61 Ag

AVG. - 26.0'/ 0.189 Au/ 13.25 Ag

DIAMOND DRILL HOLE

86-R1 - 18.5'/0.100 Au / 9.83 Ag

PANEL SAMPLE AVERAGE

W. WALL - 27.0'/ pending

MUCK SAMPLES

3 Rounds - 20.1'/0.175 Au/9.86 Ag

1 Round - 6.7'/0.036 Au/2.27 Ag

Figure 3


OMNI RESOURCES INC.

SKUKUM CREEK PROPERTY

CROSSCUT NO. 2

SAMPLE LOCATIONS & ASSAY RESULTS

JULY 15, 1987 | SCALE 1"=10'



LEGEND

LITHOLOGIES

QUATERNARY
- Qs surficial deposits

TERTIARY EOCENE
- Esk SKUKUM GROUP volcanics

CRETACEOUS
- Kgd granodiorite

JURASSIC
- JKT TANTALUS GROUP conglomerates, arenites

SYMBOLS

- lithological contact, approximate
- vein (defined with dip, assumed)
- diamond drill hole, projected to surface
- rotary drill hole, projected to surface
- adit, caved
- trench
- road
- creek
- elevation contours, metres
- helicopter pad
- claim boundary
- airphoto target
- sump
- vein surface projection, assumed, approximate

100 0 100 200 300 METRES

250 0 250 500 750 1000 1250 FEET

Note: topography and roads taken from Hugh Hamilton Ltd. survey

OMNI RESOURCES INC.
SKUKUM CREEK PROPERTY

092140

DRILL HOLE LOCATION MAP

OMNI RESOURCES INC.		FEBRUARY, 1988
NTS 105D/3	DRAWN BY A.M.	SCALE 1:5000

454

092140

092143

OMNI RESOURCES INC.
SKUKUM CREEK PROJECT

SURFACE PLAN OF RAINBOW ZONE SHOWING DIAMOND DRILL COLLARS WITH DIPS, PORTAL, VERTICAL PROJECTIONS OF INTERSECTIONS, AND INTERSECTION ELEVATIONS.

Date Drawn: SEPT. 3 1987	Revised:	
NTS: 105 D/3	Drawn By: RJR	Scale: 1:500

455

LEGEND

- SURVEY STATION - NO. & ELEVATION
- 86-R16 /67° DIAMOND DRILL COLLAR - HOLE NO. & INCLINATION
- ROAD AND DRILL PAD
- REPLOTTED COLLAR LOCATION - OLD AND NEW

10 5 0 10 15 20 METERS

055° REFERENCE LINE

8+00 N 8+50 N 9+00 N 9+50 N 10+00 N 10+50 N 11+00 N 11+50 N 12+00 N 12+50 N

6671800N 6671850N 6671900N 6671950N 6672000N 6672050N 6672100N 6672150N 6672200N 6672250N 6672300N 6672350N 6672400N 6672450N

477175E 477225E 477275E 477325E 477375E 477425E 477475E 477525E 477575E 477625E 477675E 477725E 477775E 477825E 477875E 477925E 477975E 478025E 478075E 478125E 478175E 478225E 478275E 478325E

77,825 E.

77,875 E.

77,925 E.

71,300 N

77,975 E.

78,025

71,250 N

71,200 N

71,150 N

71,100 N

71,050 N

71,000 N

70,950 N

70,900 N

REFERENCE LINE

8+50N 9+00N 9+50N 10+00N 10+50N 11+00N

Note:-Vein shown in true width

092143

OMNI RESOURCES INC.
SKUKUM CREEK PROPERTY

RAINBOW ZONE
1300 LEVEL

JUNE 10, 1987	SCALE 1:500
DRAWN BY B.L.	

456

HOLE	DIP
UG-5	0°
UG-6	0°
UG-7	0°
UG-8	-3°
UG-9	-40°
UG-10	-67°

HOLE	DIP
UG-18	0°
UG-19	0°
UG-20	-34°
UG-21	-34°
UG-22	+34°
UG-23	+54°
UG-24	+2°
UG-25	0°
UG-26	+39°
UG-27	+30°
UG-28	-34.5°
UG-29	+37°
UG-30	-56°
UG-31	0°
UG-32	+34°
UG-33	+38°
UG-34	0°
UG-35	+2°
UG-36	-22°
UG-37	-34°
UG-57	-15°

OMNI RESOURCES INC.
SKUKUM CREEK PROPERTY

KUHN ZONE

1307 LEVEL

092143

JULY, 1987 | SCALE 1:500

DRAWN BY: B.L.

457

SW

8+50N | 9+00N | 9+50N | 10+00N | 10+50N | 11+00N | 11+50N | 12+00N

NE

1450m

1400m

1350m

1300m

1250m

1200m

1150m

1100m

1050m

86-R7
0.012,0.97/0.47m

86-R10
0.130,9.32/0.78m
0.159,0.16/0.47m
0.109,4.49/1.64m
1.212,102.55/0.91m
0.071,8.40/0.17m

85-21
0.57,36.20/2.46m

86-R9
0.124,6.90/2.65m

85-14
0.163,20.51/3.82m
0.116,3.47/0.80m

85-4
0.175,11.23/5.09m

192

Drill pad and large gossan

APPROXIMATE SURFACE PROFILE

Main road

87-UG55R

0.229,4.85/0.23m
87-UG13R

85-18

0.083,5.03/0.09m
85-17
0.193,16.58/1.51m
0.116,13.21/4.77m
0.029,0.66/2.96m
0.208,36.50/0.64m

0.602,55.13/0.30m
85-5
0.112,6.65/3.41
0.468,15.84/0.19m

0.203,29.27/1.50m
87-UG41R

0.143,5.30/1.66m
87-UG42R

0.078,3.54/0.98m
87-UG52R

85-16
0.212,21.37/0.42m
0.083,8.03/0.76m

86-R1
0.051,2.66/0.75m
1.295,5.21/0.26m
0.255,12.49/0.14m
0.178,13.05/0.98m
0.230,57.75/0.16m

0.112,1.786/1.77m
87-UG51R

85-6
0.005,0.88/2.38m

0.023,1.04/6.15m
0.023,7.66/12.91m
No. 2 X-Cut
87-UG5R
0.054,12.99/2.87m

87-UG14R
0.067,1.60/1.61m

85-20
0.074,5.07/0.29m
0.070,5.88/0.90m

0.122,34.17/0.57m
85-15
0.075,9.14/3.62
0.144,7.96/0.96m

87-UG44R
0.125,3.41/1.61m

87-UG43R
0.138,13.05/1.60m

87-UG50R
0.157,26.22/4.07m

85-8
0.308,9.50/0.89m

85-7
0.052,1.83/0.66m
0.014,0.52/2.73

87-UG53R
0.217,10.37/3.23m

87-UG11R
0.073,4.68/2.44m

0.046,2.83/0.98m
87-UG4R
0.051,4.87/1.64m

87-UG1R
0.253,11.36/3.41m

87-UG45R

87-UG40R

0.409,4.48/0.56m
0.190,0.54/0.44m
0.227,1.00/1.48m
85-10
0.125,0.83/6.04m
0.160,0.64/3.12m

APPROXIMATE BEDROCK PROFILE

87-UG15R
0.287,30.96/1.96m
0.091,7.25/10.59m

86-R15
0.297,35.52/0.74m
0.165,16.20/2.24m

85-9
0.070,4.34/0.89m
0.062,3.31/1.29m
0.305,10.15/0.2m

87-UG12R

87-UG54R
0.094,5.06/0.90m

85-19
0.105,4.40/0.46m

87-UG16R
0.067,2.73/2.57m

87-UG38R

87-UG39R
0.194,5.53/0.32

87-UG46R
0.115,5.36/3.19

0.159,2.16/1.99m

86-R11
0.100,1.66/1.22m

87-UG48R
0.123,4.58/1.67m
0.207,3.66/2.13m

87-UG17R
0.606,10.90/0.24m

87-UG2R
0.096,12.84/1.74m

85-11
0.012,0.06/0.42

87-R6
0.063,4.34/7.47m
0.111,7.47/4.14m

shear, no mineralization

rhyodacite dyke with possible fault contacts

85-13
intermediate volcanics and conglomerate

86-R8
1.111,20.12/1.48m
0.876,10.72/2.05m

87-UG49R
0.102,7.20/2.45m

0.647,18.43/4.40m
0.310,7.92/12.31m
0.095,2.08/7.91m

87-R8
0.189,7.74/2.17m

87-D1
0.107,5.21/6.04m
0.106,0.93/3.67m
0.455,1.37/2.26m

86-D2

no mineralization
cross cutting Rhyodacite Dyke

87-UG3R
0.098,5.01/3.01m

87-UG47R
0.232,2.002/1.55m

87-R7

87-R9
0.077,3.81/3.50m

86-R13
0.063,1.26/1.74m

86-R12
1.26,18.55/0.86m

87-D3
0.048,3.24/4.42m
0.069,4.59/1.87m

87-D2
0.172,12.46/1.92m
0.035,2.04/21.17m

87-R4
0.087,8.12/1.87m

86-R14

0.224,2.69/0.66m
0.268,16.12/1.06m
0.195,12.22/1.69m
0.180,6.31/0.17m

LEGEND

86-R16 — Hole number
Diamond drill hole intersection
0.221,2.69/0.66m — Au(opt),Ag(opt)/True width in meters
Solid triangle denotes footwall contact.
Sample interval; weighted average
Sample interval
Survey station

NOTES:
- Grades not shown are less than the minimum true width of 1.5m and 0.10(opt) Au equivalent cutoff.

SCALE
10m 8 6 4 2 0 5m 10m 20m 30m

OMNI RESOURCES INC.
SKUKUM CREEK PROJECT

VERTICAL LONGITUDINAL SECTION
THROUGH RAINBOW ZONE
055°-235° LOOKING N.W.

092143

DATE: 88/01/17	REVISED:	
N.T.S.: 105-D/3	DRAWN BY: RJR Geological Drafting Services	SCALE: 1:500

458

1700m
1650m
1600m
1550m
1500m
1450m
1400m
1350m
1300m
1250m
1200m

86-K1 (SHEAR ZONE)
86-K2
0.020, 0.60 (1.9m)
86-K10
0.131, 2.69 (1.21)
86-K11
0.023,3.05 (1.43)
86-K8
0.132,13.01(0.21m)
0.179, 3.99 (2.4m)
0.134,7.45 (1.43m)
0.235, 0.50 (1.05m)
86-K9
0.133,651(0.33)
0.124,1.50 (2.07)
86-K12
0.044, 0.45 (1.21)
0.186,1570.69)
86-K7
0.170, (4.77) (1.38)
0.21(10.7) (0.46)
0.632, 96.45 (0.1)
0.078, 3.00 (1.83)
86-K17
0.19,5,432.66)
0.099, 4.81 (3.16)
0.170,3560.86)
86-K23
0.330,1833 (0.29)
0.053,2,390(0.62)
0.473, 3.08(1.20)
0.215,(0.41) (0.28)
0.942,34.03(0.29)
0.172, 3.21 (5.83)
86-K18
0.419,25.810.27)
0.184,565(1.22)
0.186, 4.61(4.88)
0.476,9.68(10.51)
0.173,1.70 (1.48)
86-K24
0.661, 11.03 (1.84)
0.060, 1.23 (1.81)
86-K26
0.046, 1.78 (0.93)
0.146,6.41 (0.26)
0.088, 1.89 (0.36)
0.363, (5.91 (2.89)
86-K25
0.190, 3.52(0.61)
0.092, 2.69 (1.97)
86-K28
0.102,662(0.94)
0.205, (2.26 (0.41)
86-K19
0.110, 1.20(0.11)
0.182, (.39(0.08)
86-K22
0.142, 2.90(0.25)
86-K21
0.417,4.69(0.11)
0.101, 1.06 (1.57)
0.078,0.79(7.00)
0.081, 0.79 (1.82)
0.190, 0.77 (0.77)
86-K20
0.125, 6.04(0.02)
0.075, 0.25 (0.12)
87-UG30K
0.142,5.53(1.60)
86-K27
0.362, 1.31(1.20)
0.343,1.84 (0.81m)
0.186,(.87 (178 m)
1.238, 4.17(0.07 m)
87-UG32K
87-UG32K
87-UG 33K
87-UG26K
0.967, 5.91(5.20)
87-UG27K
87-UG29K
0.066, 1.08(1.07 m)
87-UG23K
87-UG22K
87-UG31K
87-UG25K
87-UG24K
87-UG18K
Kuhn x-cut
0.087,0.94(2.61m)
0.142,(98 (2.67)
0.285,5.01(4.35)
0.15,2.26(3.02)
87-UG19K
87-UG35K
87-UG28K
87-UG20K
87-UG36K
0.621,5.16(4.58m)
87-UG57K
0.242,11.57 (0.80m)
0.164,1.80(1.42m)
87-UG37K
87-UG21K

3+00E
3+50E
4+00E
4+50E
5+00E
5+50E
6+00E
6+50E
7+00E

86-K11
0.023, 3.05 (1.43)
HOLE NUMBER
DIAMOND DRILL HOLE INTERSECTION
Au(opt), Ag(opt) (TRUE WIDTH (m))
Closed triangle denotes footwall contact.
SAMPLE INTERVAL; WEIGHTED AVERAGE
SAMPLE INTERVAL

NOTES: -Grades shown do not reflect native gold prep.
-Grades not shown are less than the minimum true width of 1.5m and 0.10(opt) Au equivalent cutoff.

LEGEND

0m 10m 20m 30m
10 6 2

092143

OMNI RESOURCES INC.
SKUKUM CREEK PROJECT

VERTICAL LONGITUDINAL SECTION
THROUGH KUHN ZONE
072°-252° LOOKING NW.

Date Drawn:	Revised:	
OCT, 1987		
NTS: 105D/3	Drawn By: RJR	Scale: 1:500

459

APPENDIX 1

ABBREVIATED STATEMENT OF COSTS AND INVOICES

UNDERGROUND MINING COSTS:

(TOTAL):.....$1,009,000.00

(DRIFTING).....940 m @ $957.00/m=$ 899,850.00

SURFACE AND UNDERGROUND DIAMOND DRILLING

(TOTAL):.....$ 579,009.07

(FOOTAGE):.....7,446 m @ $75.46/m=$ 561,873.42

0.07
838 .770 .06 +
170 176 .06 +
143 099 .79 +
196 241 .48 +
104 025 .90 +
95 324 .56 +
21 075 .99 +
C

INVOICE

MAIN STREET MINING LTD.
200-100 MAIN ST
WHITEHORSE Y.T.
Y1A 2A8

101204

DATE MAY 1 / 87 19

ORDER NUMBER

REPRESENTATIVE

TERMS

F.O.B.

SOLD TO OMNI RESOURCES INC.

SHIP TO FIELD COST & MATERIAL

ADDRESS APRIL - 15 - 30 / 87 VIA

QUANTITY	DESCRIPTION	PRICE	AMOUNT
153 MH	MAN HOURS	33 00	5049 00 ✓
91.3 M	DRIFT.	957 00	87,374 00 ✓
14 HRS	SCOOP TRAM	82 50	1,155 00 ✓
70 HR	TRUCKS	5 00	350 00 ✓
4 DAYS	TRUCK (HIAB) RENTAL + MILEAGE + 10%)		857 78
	MATERIALS.		
	EXPLOSIVES (GLACIER REMOVAL)		211 65
	GAS		183 50
	ELECTRICAL (FOR SHOP)		94 65
	CHARGES AT 10%		118 98
	TOTAL		95,324 56 ✓

REDIFORM 7M31

MAIN STREET MINING LTD. 101206
200-100 MAIN ST
WHITEHORSE Y.T Y1A 2A8

DATE 05 · 20 · 87

SOLD TO OMNI RESOURCES INC.

ORDER NUMBER

REPRESENTATIVE

SHIP TO FOOTAGE ADVANCE.

TERMS

ADDRESS MAY 1 - 15 / 87 VIA

F O B

QUANTITY	DESCRIPTION	PRICE	AMOUNT
108·7	METER'S TOTAL	957 00	104,025 90 ✓
71·8	MAIN DRIFT.		
25·5	CROSS "		
10·2	REMUCK		
1·2	SLASH		
		TOTAL	104,025 90 ✓

REORDER 7M31

INVOICE

MAIN STREET MINING LTD. 101203
200-100 MAIN ST
WHITEHORSE YT. Y1A 2A8

DATE 04 · 21 · 87

SOLD TO OMNI RESOURCES INC

ORDER NUMBER

REPRESENTATIVE

SHIP TO

TERMS

ADDRESS FIELD COST & MATERIAL. VIA

F O B

QUANTITY	DESCRIPTION	PRICE	AMOUNT
155	MAN HOURS	33 00	5115 00 ✓
80	TRUCK 4X4	5 00	400 00 ✓
5	" 3TON	12 50	62 50 ✓
5	" 5TON	12 50	62 50 ✓
2 DAYS	" HIAB. (RENTAL)	125 00	250 00 ✓
	10%		25 00 ✓
			6915 00
	MATERIAL - PORTAL LUMBER #07		3130 68 ✓
	BUILDING CONSTRUCTION		12730 30 ✓
	MOBILIZATION		5000 00 ✓
		092143	
	TOTAL		27,075 98

REORDER 7M31

MAIN STREET MINING LTD.

101207

SOLD TO Cyprus Resources Inc

ORDER NUMBER

REPRESENTATIVE

SHIP TO

TERMS

ADDRESS May 16-31/1978 VIA

F.O.B.

QUANTITY	DESCRIPTION	PRICE	AMOUNT
166.6 m	Footage Advance	@ 947.00	178776.20 ✓
1324 m³	Slash	120.00	159021.00 ✓
	Field Cost		
245	Miner Hours	33.00	8085.00 ✓
15	Scoop Hours	82.50	1237.50 ✓
11	Compressor Hours	33.00	363.00 ✓
9 days	Chipper (Rental)	27.00	243.00 ✓
137 cm	Fuel Deisel @ 1.025 + 10%		3775.03 ✓
	Material		
1 EA	L. Bay Mine Lamp Charger c/w 6 EA		1767.65 ✓
	Miners Lamps		
	TOTAL		196029.16 ✓

7M31

196,241.46

INVOICE

101212

DATE 1

SOLD TO Cyprus Resources Inc

ORDER NUMBER

REPRESENTATIVE

SHIP TO Footage Advance Jan 16-30 1978

TERMS

ADDRESS Canmet Project VIA

F.O.B.

QUANTITY	DESCRIPTION	PRICE	AMOUNT
158.8 m	Main Drive 117 - Footage 125 Cum Cost to Date	957.00	151971.60 ✓
151.2 m³	Slash Cossut #1 10.3 m	@ 1.25	15150.00
1 Hour	Compressor	33.00	33.00 ✓
8 gals	diesel fuel 1.025 + 10%	16.06	16.06 ✓
		Total	170176.66

MAIN STREET MINING LTD
200 - 100 MAIN ST.
Whitehorse Y.T
Y1A 2S8

101211

DATE June 17 87

ORDER NUMBER

REPRESENTATIVE

TERMS

F.O.B

SOLD TO Omni Resources Inc.
FOOTAGE ADVANCE / Feild Cost / MATERIALS

SHIP TO Omni Project

ADDRESS June 1 - 15 1987 VIA

QUANTITY	DESCRIPTION		PRICE		AMOUNT	
145.4 m	TF. Line Drive 95.122, X cut # 2 50%	C	957	00	139,147.	80 ✓
32	MAN HOURS	C	33	00	1056	00 ✓
3	Scoop hours	C	82	50	247	50 ✓
38	Compressor hours	C	33	00	1,254	00 ✓
18	Genset hours	C	16	50	297	00 ✓
20	Truck hours	C	5	00	100	00 ✓
5 days	Skipper Rental 27.00 + 10%		148	50	148.	50 ✓
55	18" J bolts 4.45 ea + 10%		269	23	269	23 ✓
55	1 3/8 expansion shells 2.15 ea + 10%		130	08	130	08 ✓
224	gallons diesel fuel 1.825 + 10%		449	68	449	68 ✓
			Total		1,430	99.79 ✓

7M31

INVOICE

101215

DATE July 17 1987

ORDER NUMBER

REPRESENTATIVE

TERMS

F.O.B

SOLD TO Omni Resources Inc.
Feild Cost Drift Advance

SHIP TO Omni Project

ADDRESS July 1 - 15 1987 VIA

QUANTITY	DESCRIPTION		PRICE		AMOUNT	
90.38 m	Line drive	C	957	00	86,493.	66 ✓
8.53 m	D.D.S. # 3	C	957	00	8163	21 ✓
59.93 m³	Slash DDS # 3	C	120	00	7191	60 ✓
2.6 m linear	Bolting and Screening	C	160	00	416	00 ✓
			Total		102,264.	47 ✓
6	Man hours		33	00	198	00 ✓
20	Genset hours		16	50	330	00 ✓
20	Gallons Genset Fuel 1.825 + 10%				40	15 ✓
		Total			102,832.	62 ✓

7M31

092143

INVOICE

MAIN ST. MINING LTD. 101212
200-100 Main St.
YIA 2A8.

DATE 19

ORDER NUMBER

REPRESENTATIVE

TERMS

F.O.B.

SOLD TO Omni Resources Inc

SHIP TO FOOTAGE ADVANCE: June 16-30 1987.

ADDRESS Omni Project. VIA

QUANTITY	DESCRIPTION	PRICE	AMOUNT
158.8 m.	Main Drive. 117.2 - Remuck. 13.3. Cross Cut #2 Drive	957.00	151,971.60
1513 m^3	Slash	C 120.00	18,156.00
C Hour	Compressor.	33.00	33.00
8. gallons	deisel fuel. 1.825 + 10%	16.06	16.06
		Total	170176.66

REDIFORM 7M31

092143

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

June 15, 1987

Invoice #-2092

IN ACCOUNT WITH:

Omni Resources Inc.,
706 - 575 Howe Street,
Vancouver, B. C.
V6C 2T5

Drilling Charges May 26 to June 15, 1987: (Wheaton River)

Hole: 87-03/66/NQ				
Moving				
34 man hrs.	@ $30.00 per hr.	=	$ 1,020.00	
Drilling Ops.				
4 man hrs.	@ $30.00 per hr.	= $ 120.00		
2 machine hrs.	@ $20.00 per hr.	= $ 40.00	$ 160.00	
Waterline				
11 man hrs.	@ $30.00 per hr.	=	$ 330.00	
Tractor Hours				
1 machine hrs.	@ $75.00 per hr.	=	$ 75.00	
Casing				
0 - 13 = 13 ft.	@ $22.00 per ft.	=	$ 286.00	
Coring				
13 - 548 = 535 ft.	@ $23.00 per ft.	=	$12,305.00	$14,176.00
Hole: 87-D-2/76/NQ				
Waterline				
12 man hrs.	@ $30.00 per hr.	=	$ 360.00	
Testing				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hrs.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Casing				
0 - 10 = 10 ft.	@ $22.00 per ft.	=	$ 220.00	
Coring				
10 - 900 = 890 ft.	@ $23.00 per ft.	=	$20,470.00	$21,130.00
Hole: 87-D-3/76/NQ				
Moving				
8 man hrs.	@ $30.00 per hr.	=	$ 240.00	
Tractor Time				
9 machine hrs.	@ $75.00 per hr.	=	$ 675.00	

092143

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

Casing				
0 - 10 = 10 ft.	@ $22.00 per ft.	=	$ 220.00	
Coring				
10 - 823 = 813 ft.	@ $23.00 per ft.	=	$18,699.00	$19,834.00
Hole: 87-K-1/62/NQ				
Moving				
14 man hrs.	@ $30.00 per hr.	=	$ 420.00	
Drilling Anchor				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hrs.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Waterline				
13 man hrs.	@ $30.00 per hr.	=	$ 390.00	
Casing				
0 - 7 = 7 ft.	@ $22.00 per ft.	=	$ 154.00	
Coring				
7 - 336 = 329 ft.	@ $23.00 per ft.	=	$ 7,567.00	$ 8,611.00
Items Consumed & Chargeable				
2 NQ Rods	@ $134.00 per length	=		$ 268.00
			Total Invoice	$64,019.00

02143

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

June 15, 1987
Invoice #-2093
Tractors

IN ACCOUNT WITH:

Omni Resources Inc.,
706 - 575 Howe Street,
Vancouver, B. C.
V6C 2T5

Tractor Charges April 26 to June 15, 1987: (Wheaton River)

Tractor D-6C					
96 machine hrs.	@ $75.00 per hr.	=	$7,200.00		
Tractor D-6C (Omni Employee)					
6 machine hrs.	@ $55.00 per hr.	=	$ 330.00		
Backhoe (Omni)					
9 man hrs.	@ $30.00 per hr.	=	$ 270.00		
Tractor D-7E (400 free hrs. as per contract)					
103½ machine hrs.		=	No Charge		
Moving (Culverts)					
7½ man hrs.	@ $30.00 per hr.	=	$ 225.00		
Standby Time					
5 man hrs.	@ $30.00 per hr.	=	$ 150.00		
Travelling Time					
4 man hrs.	@ $30.00 per hr.	=	$ 120.00	$8,295.00	
Fuel					
1932 l	@ 56¢ per l	=		$1,081.92	$9,376.92
			Total Invoice		$9,376.92

Fuel
light plant--1431 l
Coleton Construction--205 l
Melberg --296 l

D-7E
Balance of free hrs. 296½

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

June 30, 1987
Invoice #-2103
Drill: #-3

IN ACCOUNT WITH:

Omni Resources Inc.,
706 - 575 Howe Street,
Vancouver, B. C.
V6C 2T5

Drilling Charges June 16 to 30, 1987: (Wheaton River)

Hole: 87-K-1/62/NQ				
Reducing & Pulling Reducing Casing				
29 man hrs.	@ $30.00 per hr.	= $ 870.00		
14½ machine hrs.	@ $20.00 per hr.	= $ 290.00	$ 1,160.00	
Reaming Cave (Bad Hole had to Reduce)				
27 man hrs.	@ $30.00 per hr.	= $ 810.00		
13½ machine hrs.	@ $20.00 per hr.	= $ 270.00	$ 1,080.00	
Testing				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hrs.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Coring				
336 - 1069 = 733 ft.	@ $21.00 per ft.	= $15,393.00		
1069 - 1124 = 55 ft.	@ $19.50 per ft.	= $ 1,072.50	$16,465.50	$18,785.50
Hole: R-4-87/66/NQ				
Moving				
14 man hrs. - 10 hrs. = 4 man hrs.	@ $30.00 per hr.	=	$ 120.00	
Casing				
0 - 13 = 13 ft.	@ $22.00 per ft.	=	$ 286.00	
Coring				
13 - 803 = 790 ft.	@ $21.00 per ft.	=	$16,590.00	$16,996.00
Tractor Hours (Omni Employees)				
21 machine hrs.	@ $55.00 per hr.	=		$ 1,155.00
Tractor Hours				
4 machine hrs.	@ $75.00 per hr.	=		$ 300.00
			Total Invoice	$37,236.50

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

June 15, 1987
Invoice #-2095
Drill: Superdrill

IN ACCOUNT WITH:

Omni Resources Inc.
706 - 575 Howe Street,
Vancouver, B. C.
V6C 2T5

Drilling Charges June 6 to 15, 1987: (Underground-Wheaton River)

Hole: U-6-87-1/38/NQ					
Installing Cable & Generator					
26 man hrs.	@ $30.00 per hr.	=		$ 780.00	
Moving Drill & Setting Up					
47 man hrs.	@ $30.00 per hr.	=		$1,410.00	
Waterline					
3 man hrs.	@ $30.00 per hr.	=		$ 90.00 ?	
Casing					
2 man hrs.	@ $30.00 per hr.	=	$ 60.00		
1 machine hr.	@ $20.00 per hr.	=	$ 20.00	$ 80.00	
Drilling					
0 - 77 = 77 ft.	@ $23.00 per ft.	=		$1,771.00	$4,131.00
			Total Invoice		$4,131.00

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

June 30, 1987
Invoice #-2104
Drill: Superdrill

IN ACCOUNT WITH:

Omni Resources Inc.,
706 - 575 Howe Street,
Vancouver, B. C.
V6C 2T5

Drilling Charges June 16 to 30, 1987: (Underground-Wheaton River)

Hole: UG-87-1/38/NQ				
Coring				
77 - 192 = 115 ft.	@ $21.00 per ft.	=		$ 2,415.00
Hole: UG87-2/66/NQ				
Travelling Time/Contract				
12 man hrs.	@ $30.00 per hr.	=	$ 360.00	
Coring				
0 - 290 = 290 ft.	@ $21.00 per ft.	=	$6,090.00	$ 6,450.00
Hole: UG-87-3/77/NQ				
Reaming Casing in Bedrock				
3 man hrs.	@ $30.00 per hr.	= $ 90.00		
1½ machine hrs.	@ $20.00 per hr.	= $ 30.00	$ 120.00	
Travelling Time per Contract				
12 man hrs.	@ $30.00 per hr.	=	$ 360.00	
Coring				
0 - 408 = 408 ft.	@ $21.00 per ft.	=	$8,568.00	$ 9,048.00
Hole: UG87-4/34/NQ				
Travelling Time per Contract				
6 man hrs.	@ $30.00 per hr.	=	$ 180.00	
Coring				
0 - 210 = 210 ft.	@ $21.00 per ft.	=	$4,410.00	$ 4,590.00
Hole: UG87/5/0/NQ				
Standby (no setup) Miners				
8 man hrs.	@ $30.00 per hr.	= $ 240.00		
4 machine hrs.	@ $20.00 per hr.	= $ 80.00	$ 320.00	

092143

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

Moving				
24 man hrs. - 10 hrs. = 14 man hrs.	@ $30.00 per hr.	=	$ 420.00	
Travelling Time per Contract				
12 man hrs.	@ $30.00 per hr.	=	$ 360.00	
Coring				
0 - 167 = 167 ft.	@ $21.00 per ft.	=	$3,507.00	$ 4,607.00
Hole: UG-87-6/0/NQ				
Travelling Time per Contract				
6 man hrs.	@ $30.00 per hr.	=	$ 180.00	
Coring				
0 - 162 = 162 ft.	@ $21.00 per ft.	=	$3,402.00	$ 3,582.00
Hole: UG-87-7/0/NQ				
Travelling Time per Contract				
6 man hrs.	@ $30.00 per hr.	=	$ 180.00	
Coring				
0 - 149 = 149 ft.	@ $21.00 per ft.	=	$3,129.00	$ 3,309.00
			Total Invoice	$34,001.00

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

July 15, 1987
Invoice #-2125 Credit
Drill: #-3

IN ACCOUNT WITH:

Omni Resources Inc.,
706 - 575 Howe Street,
Vancouver, B. C.
V6C 2T5

To Credit Invoice #-2119 dated July 15, 1987: (Wheaton River)

Foreman Time				
Tractor D-6C				
4 machine hrs.	@ $75.00 per hr.	=	$ 300.00	
Picking Up Catskinner				
2 man hrs.	@ $30.00 per hr.	=	$ 60.00	$ 360.00
(the above to be charged to Island)				
Hole: 87-R-5/76/NQ				
Moving				
Split Cost		=	$ 165.00	
Reaming Casing (over 50 ft.)				
Split Cost		=	$ 560.00	
Standby for Decision				
No charge to Omni		=	$ 540.00	
Casing				
Split Cost		=	$ 594.00	$1,859.00
		Total Credit Invoice		($2,219.00)

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

July 15, 1987
Invoice #-2119
Drill #-3

IN ACCOUNT WITH:
Omni Resources Inc.,
706 - 575 Howe Street,
Vancouver, B.C.
V6C 2T5

Drilling Charges July 1 to July 15, 1987 (Wheaton River)

Hole: R4-87/-66/NQ				
Testing				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hr.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Coring				
803-1068 = 265 ft.	@ $21.00 per ft.	= $	$5,565.00	$ 5,645.00
Hole 87 -K2/-55/NQ				
Moving				
20 man hrs.- 10 man hrs.				
= 10 man hrs.	@ $30.00 per hr.	= $	$ 300.00	
Drilling Anchor Rod				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hr.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Reaming casing in Bedrock				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hr.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Grease Rods due to Vibration				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hr.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Casing				
0-15= 15 ft.	@ $22.00 per ft.	= $	$ 330.00	
Coring				
15-1133 = 1118 ft.	@ $21.00 per ft.	= $	$23,478.00	$24,348.00
Hole 87R-5/-76/NQ				
Moving				
21 man hrs. - 10 man hrs.				
= 11 man hrs.	@ $30.00 per hr.	= $	$ 330.00	
Reaming Casing (over 50 ft.)				
28 man hrs.	@ $30.00 per hr.	= $ 840.00	$ 1,120.00	
14 man hrs.	@ $20.00 per hr.	= $ 280.00		

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

Standby for decision on hole & waiting on set-up				
18 man hrs.	@ $30.00 per hr.	= $	$ 540.00	
Casing				
0-54 = 54ft.	@ $22.00 per ft.	= $	$ 1,188.00	$ 3,178.00
Hole 87R5A/-76				
Reaming Casing				
10 man hrs.	@ $30.00 per hr.	= $ 300.00		
5 machine hrs.	@ $20.00 per hr.	= $ 100.00	$ 400.00	
Reaming Cave				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hr.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Casing				
0-71=71 ft.	@ $22.00 per ft.	= $	$ 1,562.00	
Coring				
71-206 = 135 ft.	@ $21.00 per ft.	= $	$ 2,835.00	$ 4,877.00
Tractor D-6C				
3½ hrs.(machine)	@ $75.00 per hr.	= $	$	$ 262.50
Items Consumed & Chargeable				
Used for Anchors				
Hole 03/D-Z/D3/K1/R4/KZ				
R-5/R-SA				
8 NQ Rods	@ $140.00 per rod	= $	$	$ 1,120.00
Foreman Time				
Tractor D 6c				
4 Machine hrs.	@ $ 75.00 per hr.	= $	$ 300.00	
Picking up Catskinner				
2 man hrs.	@ $ 30.00 per hr.	= $	$ 60.00	$ 360.00
		TOTAL INVOICE		$39,790.50

092143

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

July, 15 1987
Invoice # -2118
Drill: Superdrill

IN ACCOUNT WITH:

Omni Resources Inc.,
706 - 575 Howe Street,
Vancouver, B.C.
V6C 2T5

Drilling Charges July 1 to 15, 1987: (Underground- Wheaton River)

Hole 87-7/0/NQ				
Coring				
149-199 = 50 ft.	@ $21.00 per ft.	= $		$ 1,050.00
Hole 87-8/0/NQ				
Reaming Cave				
4 man hrs.	@ $30.00 Per hr.	= $ 120.00		
2 machine hrs.	@ $20.00 Per hr.	= $ 40.00	$ 160.00	
Conditioning Hole				
4 man hrs.	@ $30.00 per hr.	= $ 120.00		
2 machine hrs.	@ $20.00 per hr.	= $ 40.00	$ 160.00	
Coring				
0-609 = 609 ft.	@ $21.00 per ft.	= $	$12,789.00	$ 13,109.00
HOLE 87 -9/-45/NQ				
Coring				
0-228= 228 ft.	@ $21.00 per ft.	= $	$	$ 4,788.00
Hole 87-10/-68/NQ				
Coring				
0-294 = 294 ft.	@ $21.00 per ft.	= $	$	$ 6,174.00
Hole 87 - 11/-40/NQ				
Coring				
0-183 = 183 ft.	@ $21.00 per ft.	= $	$	$ 3,843.00
Hole 87 - 12/ -66/NQ				
Coring				
0-248 = 248 ft.	@ $21.00 per ft.	= $	$	$ 5,208.00
Hole 87 -13/+30/ NQ				
Standby waiting to have Hole Spotted				
2 man hrs.	@ $30.00 per hr.	= $ 60.00	$	
1 machine hr.	@ $20.00 per hr.	= $ 20.00	$ 80.00	

092143

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

Coring				
0-284 = 284 ft.	@ $21.00 per ft.	= $	$ 5,964.00	$ 6,044.00
Hole 87-14/0/NQ				
Standby waiting to have hole Spotted				
4 man hrs.	@ $30.00 per hr.	= $ 120.00		
2 machine hrs.	@ $20.00 per hr.	= $ 40.00	$ 160.00	
Coring				
0-233 = 233 ft.	@ $21.00 per ft.	= $	$ 4,893.00	$ 5,053.00
Hole 87-15/-32/NQ				
Coring				
0-88 = 88 ft.	@ $21.00 per ft.	= $	$	$ 1,848.00
Sold to Mine				
5 Gal. Hydr. Oil				$ 40.00
	Total Invoice			$47,157.00

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

June 30, 1987
Invoice #-2112 Credit
Drill: Superdrill

IN ACCOUNT WITH:

Omni Resources Inc.
706 - 575 Howe Street,
Vancouver, B. C.
V6C 2T5

To Credit Invoice #-2104 Dated June 30, 1987:

Travelling Time			
54 man hrs.	@ $30.00 per hr.	=	($1,620.00)
	Total Credit Invoice		($1,620.00)

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337


July 30, 1987
Invoice #2133
Drill: *-Superdrill

IN ACCOUNT WITH:

Omni Resources Inc.,
706 - 575 Howe Street,
Vancouver, B. C.,
V6C 2T5

Drilling Charges July 16 to 31, 1987: (Underground-Wheaton River)

Hole:87-15/30/NQ				
Standby (Waiting for Smoke to Clear)				
1 man hrs.	@ $30.00 per hr.	= $ 30.00		
.5 machine hrs.	@ $20.00 per hr.	= $ 10.00	$ 40.00	
Coring				
88 - 268 = 180 ft.	@ $21.00 per ft.	=	$3,780.00	$ 3,820.00
Hole:87-16/54/NQ				
Coring				
0 - 309 = 309 ft.	@ $21.00 per ft.	=		$ 6,489.00
Hole:87-17/67/NQ				
Coring				
0 - 408 = 408 ft.	@ $21.00 per ft.	=		$ 8,568.00
Hole:87-18/0/NQ				
Moving				
49 man hrs. - 10 hrs. =				
39 man hrs.	@ $30.00 per hr.	=	$1,170.00	
Coring				
0 - 197 = 197 ft.	@ $21.00 per ft.	=	$4,137.00	$ 5,307.00
Hole:87-19/0/NQ				
Coring				
0 - 251 = 251 ft.	@ $21.00 per ft.	=		$ 5,271.00
Hole:87-20/32/NQ				
Coring				
0 - 252 = 252 ft.	@ $21.00 per ft.	=		$ 5,292.00
Hole:87-21/54/NQ				
Coring				
0 - 317 = 317 ft.	@ $21.00 per ft.	=		$ 6,657.00



E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

Hole: 87-22/34/NQ				
Moving				
14 man hrs. - 10 hrs. =				
4 man hrs.	@ $30.00 per hr.	=	$ 120.00	
Coring				
0 - 211 = 211 ft.	@ $21.00 per ft.	=	$4,431.00	$ 4,551.00
Hole # 87-23/54/NQ				
Coring				
0 - 202 = 202 ft.	@ $21.00 per ft.	=		$ 4,242.00
Hole: 87-24/0/NQ				
Coring				
0 - 143 = 143 ft.	@ $21.00 per ft.	=		$ 3,003.00
			Total Invoice	$53,200.00

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337


July 31, 1987
Invoice #2134
Drill: #-3

IN ACCOUNT WITH:

Omni Resources Inc.,
706 - 575 Howe Street,
Vancouver, B. C.,
V6C 2T5

Drilling Charges July 16 to 31, 1987: (Wheaton River)

Hole:R-5/76/NQ				
Coring				
206 - 557 = 351 ft.	@ $21.00 per ft.	=	$7,371.00	
557 - 883 = 326 ft.	@ $19.50 per ft.	=	$6,357.00	$13,728.00
Hole: R-6/54/NQ				
Moving				
22 man hrs. - 10 hrs	=			
12 man hrs.	@ $30.00 per hr.	=	$ 360.00	
Drilling Anchor Rod				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hrs.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Mud Time)Lost Circulation)				
3 man hrs.	@ $30.00 per hr.	= $ 90.00		
1.5 machine hrs.	@ $20.00 per hr.	= $ 30.00	$ 120.00	
Standby Waiting for Geolgist				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hrs.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Casing				
0 - 21 = 21 ft.	@ $22.00 per ft.	=	$ 462.00	
Coring				
21 - 436 = 415 ft.	@ $21.00 per ft.	=	$8,715.00	$ 9,817.00
Hole: R-7/64/NQ				
Reaming Cave (fault zone)				
4 man hrs.	@ $30.00 per hr.	= $ 120.00		
2 machine hrs.	@ $20.00 per hr.	= $ 40.00	$ 160.0	
Casing				
0 - 10 = 10 ft.	@ $22.00 per ft.	=	$ 220.00	
Coring				
10 - 538 - 528 ft.	@ $21.00 per ft.	=	$11,088.00	$11,468.00



E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

Hole: R-8/58/NQ				
Reaming Cave				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hrs.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Waterline				
4 man hrs.	@ $30.00 per hr.	= $ 120.00 →		
Standby (No Tractor due to Company Decision)				
49 man hrs.	@ $30.00 per hr.	= $1,470.00		
24.5 machine hrs.	@ $20.00 per hr.	= $ 490.00	$1,960.00	
Casing				
0 - 11 = 11 ft.	@ $22.00 per ft	=	$ 242.00	
Coring				
11 - 513 = 502 ft.	@ $21.00 per ft.	=	$10,542.00	$12,944.00

Items Consumed & Chargeable				
Used for Anchor				
1 NQ rod	@ $140.00 each	=		$ 140.00
			Total Invoice	$48,097.00

F CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

August 31, 1987
Invoice #-2150
Drill: #Superdrill

IN ACCOUNT WITH:

Omni Resources Inc.,
706 - 575 Howe Street,
Vancouver, B.C.
V6C 2T5

Drilling Charges August 1 to 15, 1987: (Underground-Wheaton River)

Hole: 87-24/0/NQ				
Coring				
143 - 288 = 145 ft.	@ $21.00 per ft.	=		$ 3,045.00
Hole: 87-25/0/NQ				
Coring				
0 - 419 = 419 ft.	@ $21.00 per ft.	=		$ 8,799.00
Hole: 87-26/39/NQ				
Conditioning Hole				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hrs.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Coring				
0 - 284 = 284 ft.	@ $21.00 per ft.	=	$5,964.00	$ 6,044.00
Hole: 87-27/30/NQ				
Coring				
0 - 320 = 320 ft.	@ $21.00 per ft.	=		$ 6,720.00
Hole: 87-28/35/NQ				
Reaming Casing				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hr.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Coring				
0 - 242 = 242 ft.	@ $21.00 per ft.	=	$5,082.00	$ 5,162.00
Hole: 87-29/36/NQ				
Coring				
0 - 233 = 233 ft.	@ $21.00 per ft.	=		$ 4,893.00
Hole: 87-30/56/NQ				
Coring				
0 - 172 = 172 ft.	@ $21.00 per ft.	=		$ 3,612.00
			Total Invoice	$38,275.00



E ARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

August 15, 1987
Invoice #-2151
Drill: #-3

IN ACCOUNT WITH:

Omni Resources Inc.
706 - 575 Howe Street,
Vancouver, B. C.
V6C 2T5

Drilling Charges August 1 to 4, 1987: (Wheaton River)

Hole: R-9/72/NQ				
Demobilization				
4 man hrs.	@ $30.00 per hr.	=	$ 120.00	
Drilling Anchors				
3 man hrs.	@ $30.00 per hr.	= $ 90.00		
1.5 machine hrs.	@ $20.00 per hr.	= $ 30.00	$ 120.00	
Waterline (over Spec)				
3 man hrs.	@ $30.00 per hr.	=	$ 90.00	
Standby Geologist (not available)				
4 man hrs.	@ $30.00 per hr.	=	$ 120.00	
Tractor Hrs.				
4 machine hrs.	@ $75.00 per hr.	=	$ 300.00	
Casing				
0 - 10 = 10 ft.	@ $22.00 per ft.	=	$ 220.00	
Coring				
10 - 643 = 633 ft.	@ $21.00 per ft.	=	$13,293.00	$14,263.00
Items Consumed & Chargeable				
1 - 10 ft. NQ rod	@ $140.00 each	= $ 140.00		
1 - 5 ft. NQ rod	@ $86.80 each	= $ 86.80		$ 226.80
			Total Invoice	$14,489.80

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

August 31, 1987
Invoice #-2189
Drill: Superdrill

IN ACCOUNT WITH:

Omni Resources Inc.
706 - 575 Howe Street,
Vancouver, B.C.
V6C 2T5

Drilling Charges August 16 to 28, 1987: (Skukum)

Hole:87-30/56/NQ				
Mixing Heavy Mud in Ore Zone				
2 man hrs.	@ $30.00 per hr.	= $ 60.00 ✓		
1 machine hr.	@ $20.00 per hr.	= $ 20.00 ✓	$ 80.00 ✓	
Coring				
172 - 357 = 185 ft.	@ $21.00 per ft.	=	$ 3,885.00 ✓	$ 3,965.00 ✓
Hole:87-31/0/NQ				
Demobing Drill				
8 man hrs.	@ $30.00 per hr.	=	$ 240.00 ✓	
Grouting Hole				
4 man hrs.	@ $30.00 per hr.	= $ 120.00 ✓		
2 machine hr.	@ $20.00 per hr.	= $ 40.00 ✓	$ 160.00 ✓	
Waterline				
16 man hrs.	@ $30.00 per hr.	=	$ 480.00 ✓	
Mixing Heavy Mud in Ore Zone				
6 man hrs.	@ $30.00 per hr.	= $ 180.00 ✓		
3 machine hrs.	@ $20.00 per hr.	= $ 60.00 ✓	$ 240.00 ✓	
Heavy Water in Hole				
18 man hrs.	@ $30.00 per hr.	= $ 540.00 ✓		
9 machine hrs.	@ $20.00 per hr.	= $ 180.00 ✓	$ 720.00 ✓	
Standby for Company Decision				
5 man hrs.	@ $30.00 per hr.	= $ 150.00 ✓		
2.5 machine hrs.	@ $20.00 per hr.	= $ 50.00 ✓	$ 200.00 ✓	
Coring				
0 - 585 = 585 ft.	@ $21.00 per ft.	=	$12,285.00 ✓	$14,325.00 ✓
Items Consumed & Chargeable				
1-5 ft. NQ rod	@ $86.80 each	=		$ 86.80 ✓
			Total Invoice	$18,376.80 ✓

Grout plug and adapters
charges to follow.

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

September 15, 1987
Invoice #-2213
Tractor

IN ACCOUNT WITH:

Omni Resources Inc.
706 - 575 Howe Street,
Vancouver, B. C.
V6C 2T5

To Charge for the following Tractor Work :

Tractor D-7
5machine hrs. @ $130.00 per hr. - $ 650.00

Total Invoice $ 650.00

This was charged to Island and should of been to Omni..

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337


September 15, 1987
Invoice #-2201
Drill: Scoopdrill

IN ACCOUNT WITH:

Omni Resources Inc.
706 - 575 Howe Street,
Vancouver, B.C.
V6C 2T5

Drilling Charges September 3 to 15, 1987: (Skukum)

Hole: 87-32/54/NQ				
Moving & Setting Up Drill				
12 man hrs.	@ $30.00 per hr.	=	$ 360.00	
Travelling Time (re: Mob.)				
4 man hrs.	@ $30.00 per hr	=	$ 120.00	
Coring				
0 - 349 = 349 ft.	@ $21.00 per ft.	=	$7,329.00	$ 7,809.00
Hole: 34-87/0/NQ				
Moving				
11 man hrs.	@ $30.00 per hr.	=	$ 330.00	
Repairing Vent Tube				
4 man hrs.	@ $30.00 per hr.	=	$ 120.00	
Coring				
0 - 27 = 27 ft.	@ $21.00 per ft.	=	$ 567.00	$ 1,017.00
Hole: 87-33/38/NQ				
Moving				
26 man hrs.	@ $30.00 per hr.	=	$ 780.00	
Reaming Rods Out of Hole				
4 man hrs.	@ $30.00 per hr.	= $ 120.00		
2 machine hrs.	@ $20.00 per hr.	= $ 40.00	$ 160.00	
Coring				
0 - 298 = 298 ft.	@ $21.00 per ft.	=	$6,258.00	$ 7,198.00
Items Consumed & Chargeable				
Hole: 87-31				
1 Grout Plug	@ $117.25 each	= $ 117.25		
1 Adapter	@ $162.00 each	= $ 162.00		$ 279.25
Fuel re: Lorne (geologist)				
500 gal. diesel	@ $3.00 per gal.	= $1,500.00		
60 gal. gas	@ $3.50 per gal.	= $ 210.00		$ 1,710.00



E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

Canamet Sales (underground supplies)		
Invoice #-024553	= $ 182.65	
+ 15%	= $ 27.39	$ 210.04
Trans North Air (missed on earlier invoices)		
April 26/87 Invoice #69759	=	$ 463.20
	Total Invoice	$18,686.49

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337


September 30, 1987
Invoice #-2222
Drill: Scoopdrill

IN ACCOUNT WITH:

Omni Resources Inc.
706 - 575 Howe Street,
Vancouver, B.C.
V6C 2T5

Drilling Charges September 16 to 30, 1987: (Skukum)

Hole:87-34/0/NQ				
Moving				
24 man hrs.	@ $30.00 per hr.	=	$ 720.00	
Drilling Anchor				
4man hrs.	@ $30.00 per hr.	=$120.00		
2 machine hrs.	@ $20.00 per hr.	=$ 40.00	$ 160.00	
Coring				
0 - 238=238 ft.	@ $21.00 per ft.	=	$4,998.00	$ 5,878.00
Hole:87-36/-22/NQ				
Moving				
13 man hrs.	@ $30.00 per hr.	=	$ 390.00	
Anchor				
3 man hrs.	@ $30.00 per hr.	=$ 90.00		
1.5 machine hrs.	@ $20.00 per hr.	=$ 30.00	$ 120.00	
Condtioning Hole				
2 man hrs	@ $30.00 per hr.	=$ 60.00		
1 machine hr.	@ $20.00 per hr.	=$ 20.00	$ 80.00	
Coring				
0 - 222 = 222 ft.	@ $21.00 per ft.	=	$4,662.00	$ 5,252.00
Hole:87-37/-34/NQ				
Moving				
21 man hrs.	@ $30.00 per hr.	=	$ 630.00	
Drilling Anchor				
2 man hrs.	@ $30.00 per hr.	=$ 60.00		
1 machine hrs.	@ $20.00 per hr.	=$ 20.00	$ 80.00	
Coring				
0 - 328 = 328 ft.	@ $21.00 per ft.	=	$ 6,888.00	$ 7,598.00
Hole:87-38/-46/NQ				
Moving				
8 man hrs.	@ $30.00 per hr.	=	$ 240.00	



E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

Condtioning Hole (ore zone)				
2 man hrs	@ $30.00 per hr.	= $ 60.00		
1 machine hr.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Coring				
0 - 275 = 275 ft.	@ $21.00 per ft.	=	$ 5,775.00	$ 6,095.00
Hole: 87-39/54/NQ				
Conditioning Hole (ore zone)				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hrs.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Coring				
0 - 118 = 118 ft.	@ $21.00 per ft.	=	$ 2,478.00	$ 2,558.00
		Total Invoice		$ 27,381.00

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337


October 15, 1987
Invoice #-2236
Drill: Scoopdrill

IN ACCOUNT WITH:

Omni Resources Inc.
706 - 575 Howe Street,
Vancouver, B.C.
V6C 2T5

Drilling Charges October 1 to 15, 1987: (Skukum)

Hole: 87-39/54/NQ				
Conditioning Hole (ore zone)				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hr.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Standby (no ventilation)				
9 man hrs.	@ $30.00 per hr.	= $ 270.00		
4.5 machine hrs.	@ $20.00 per hr.	= $ 90.00	$ 360.00	
Coring				
118 - 274 = 156 ft.	@ $21.00 per ft.	=	$ 3,276.00	$ 3,716.00
Hole: 87-40/38/NQ				
Standby (no ventilation)				
5 man hrs.	@ $30.00 per hr.	= $ 150.00		
2.5 machine hrs.	@ $20.00 per hr.	= $ 50.00	$ 200.00	
Coring				
0 - 204 = 204ft.	@ $21.00 per ft.	=	$ 4,284.00	$ 4,484.00
Hole: 87-41/45/NQ				
Conditioning Hole (ore zone)				
4 man hrs.	@ $30.00 per hr.	= $ 120.00		
2 machine hrs.	@ $20.00 per hr.	= $ 40.00	$ 160.00	
Coring				
0 - 233 = 233ft.	@ $21.00 per ft.	=	$ 4,893.00	$ 5,053.00
Hole: 87-42/55/NQ				
Standby (no ventilation)				
11 man hrs	@ $30.00 per hr.	= $ 330.00		
5.5 machine hr.	@ $20.00 per hr.	= $ 110.00	$ 440.00	
Coring				
0 - 194 = 194 ft.	@ $21.00 per ft.	=	$ 4,074.00	$ 4,514.00
Hole: 87-43/0/NQ				
Water (lack of)				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hrs.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Coring				
0 - 136 = 136 ft.	@ $21.00 per ft.	=	$ 2,856.00	$ 2,936.00



E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

Hole: 87-44/0/NQ				
Moving				
19 man hrs.	@ $30.00 per hr.	=	$ 570.00	
Drilling Operations				
7 man hrs.	@ $30.00 per hr.	= $ 210.00		
3.5 machine hrs.	@ $20.00 per hr.	= $ 70.00	$ 280.00	
Standby (no Water)				
7 man hrs.	@ $30.00 per hr.	= $ 210.00		
3.5 machine hrs.	@ $20.00 per hr.	= $ 70.00	$ 280.00	
Coring				
0 - 208 = 208 ft.	@ $21.00 per ft.	=	$ 4,368.00	$ 5,498.00
Hole: 87-45/32/NQ				
Standby (no water)				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hrs.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Standby Ventilation (none)				
6 man hrs.	@ $30.00 per hr.	= $ 180.00		
3 machine hrs.	@ $20.00 per hr.	= $ 60.00	$ 240.00	
Repairs Standby Caron Mechanic on Vent				
3 man hrs.	@ $30.00 per hr.	=	$ 90.00	
Coring				
0 - 208 = 208 ft.	@ $21.00 per ft.	=	$ 4,368.00	$ 4,778.00
Hole: 87-46/52/NQ				
Waiting for Water				
8 man hrs.	@ $30.00 per hr.	= $ 240.00		
4 machine hrs.	@ $20.00 per hr.	= $ 80.00	$ 320.00	
Coring				
0 - 294 = 294 ft.	@ $21.00 per ft.	=	$ 6,174.00	$ 6,494.00
Hole: 87-47/66/NQ				
Conditioning Hole (ore zone)				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hrs.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Coring				
0 - 424 = 424 ft,.	@ $21.00 per ft.	=	$ 8,904.00	$ 8,984.00
Hole: 87-48/54/NQ				
Coring				
0 - 1 = 1 ft.	@ $21.00 per ft.	=		$ 21.00
Mud				
13.5 pails DD-2000	@ $125.00 each	=		$ 1,687.50

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

Fuel			
500 gals Diesel	@ $3.00 per gal.	=	$ 1,500.00
Propane Sent to Job			
Aug. 31	6 refills		
Sept. 2	10 "		
30	14 "		
Oct. 16	4 "		
	34 refills @ $48.00 each	=	$ 1,632.00
		Total Invoice	$51,297.50

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

October 30, 1987
Invoice #-2249
Drill: Superdrill

IN ACCOUNT WITH:

Omni Resources Inc.
706 - 575 Howe Street,
Vancouver, B.C.
V6C 2T5

Drilling Charges October 16 to 30/Days 1987: (Skukum)

Hole: 87-48/54/NQ				
Waterline				
2 man hrs.	@ $30.00 per hr.	=	$ 60.00	
Mud (ore zone)				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hrs.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Coring				
1 - 332 = 331 ft.	@ $21.00 per ft.	=	$ 6,951.00	$ 7,091.00
Hole: 87-49/64/NQ				
Mud (ore zone)				
2 man hrs.	@ $30.00 per hr.	= $ 60.00		
1 machine hrs.	@ $20.00 per hr.	= $ 20.00	$ 80.00	
Coring				
0 - 364 = 364 ft.	@ $21.00 per ft.	=	$ 7,644.00	$ 7,724.00
Hole: 87-50/0/NQ				
Coring				
0 - 31 = 31 ft.	@ $21.00 per ft.	=		$ 651.00
Hole: 87-51/15/NQ				
Moving				
6 man hrs	@ $30.00 per hr.	=	$ 180.00	
Coring				
0 - 35 = 35 ft.	@ $21.00 per ft.	=	$ 735.00	$ 915.00
Hole: 87-52/NQ				
Coring				
0 - 35 = 35 ft.	@ $21.00 per ft.	=		$ 735.00
Hole: 87-53/NQ				
Coring				
0 - 35 = 35 ft.	@ $21.00 per ft.	=		$ 735.00

ARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

Hole: 87-50R/21/NQ				
Moving				
20 man hrs.	@$30.00 per hr.	=	$ 600.00	
Waterline				
4 man hrs.	@$30.00 per hr.	=	$ 120.00	
Standby (vent tube & water)				
3 man hrs.	@$30.00 per hr.	= $ 90.00		
1.5 machine hrs.	@$20.00 per hr.	= $ 30.00	$ 120.00	
Coring				
0 - 169 = 169 ft.	@$21.00 per ft.	=	$ 3,549.00	$ 4,389.00
Hole: 87-51R/30/NQ				
Standby for Water				
1 man hrs.	@$30.00 per hr.	= $ 30.00		
.5 machine hrs.	@$20.00 per hr.	= $ 10.00	$ 40.00	
Coring				
0 - 144 = 144 ft.	@$21.00 per ft.	=	$ 3,024.00	$ 3,064.00
Hole: 87-52R/37/NQ				
Moving				
8 man hrs.	@$30.00 per hr.	=	$ 240.00	
Coring				
0 - 161 = 161 ft.	@$21.00 per ft.	=	$ 3,381.00	$ 3,621.00
Hole: #-1/0/NQ				
Moving				
13 man hrs.	@$30.00 per hr.	=	$ 390.00	
Waterline				
2 man hrs.	@$30.00 per hr.	=	$ 60.00	
Coring				
0 - 51 = 51 ft.	@$21.00 per ft.	=	$ 1,071.00	$ 1,521.00
Hole: #-2/0/NQ				
Moving				
18 man hrs.	@$30.00 per hr.	=	$ 540.00	
Coring				
0 - 60 = 60 ft.	@$21.00 per ft.	=	$ 1,260.00	$ 1,800.00
Hole: #-3/0/NQ				
Standby for Vent Tubing				
4 man hrs.	@$30.00 per hr.	= $ 120.00		
2 machine hrs.	@$20.00 per hr.	= $ 40.00	$ 160.00	
Coring				
0 - 62 = 62 ft.	@$21.00 per ft.	=	$ 1,302.00	$ 1,462.00



ARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

Hole: #-4/0/NQ				
Standby for Water				
1 man hrs.	@$30.00 per hr.	= $ 30.00		
.5 machine hrs.	@$20.00 per hr.	= $ 10.00	$ 40.00	
Coring				
0 - 54 = 54 ft.	@$21.00 per ft.	=	$1,134.00	$ 1,174.00
Hole: 87-53R/23/NQ				
Moving				
12 man hrs.	@$30.00 per hr.	=	$ 360.00	
Standby (water)				
5 man hrs.	@$30.00 per hr.	= $ 150.00		
2.5 machine hrs.	@$20.00 per hr.	= $ 50.00	$ 200.00	
Coring				
0 - 170 = 170 ft.	@$21.00 per ft.	=	$3,570.00	$ 4,130.00
Hole: 87-54R/59/NQ				
Moving				
* 5 man hrs.	@$30.00 per hr.	=	$ 150.00	
Reaming Casing in Bedrock				
1 man hrs.	@$30.00 per hr.	= $ 30.00		
.5 machine hrs.	@$20.00 per hr.	= $ 10.00	$ 40.00	
Standby for Water				
5 man hrs.	@$30.00 per hr.	= $ 150.00		
2.5 machine hrs.	@$20.00 per hr.	= $ 50.00	$ 200.00	
Coring				
0 - 222 = 222 ft.	@$21.00 per ft.	=	$4,662.00	$ 5,052.00
Hole: 87-55R/45/NQ				
Standby for Water				
1 man hrs.	@$30.00 per hr	= $ 30.00		
.5 machine hrs.	@$20.00 per hr.	= $ 10.00	$ 40.00	
Coring				
0 - 124 = 124 ft.	@$21.00 per ft.	=	$2,604.00	$ 2,644.00
		Total Invoice		$46,708.00

Charges for Propane to follow on next invoice. - DONE TO CHANGE

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

November 15, 1987
Invoice #-2265
Drill: Superdrill

IN ACCOUNT WITH:

Omni Resources Inc.
706 - 575 Howe Street,
Vancouver, B.C.
V6C 2T5

Drilling Charges October 30 to November 13, 1987: (Skukum)

Hole: 87-53R/45/NQ				
Standby for Water				
15 man hrs.	@$30.00 per hr.	= $ 450.00		
7.5 machine hrs.	@$20.00 per hr.	= $ 150.00	$ 600.00	
Coring				
124 - 368 = 244 ft.	@$21.00 per ft.	=	$ 5,124.00	$ 5,724.00
Hole: 56R/29/NQ				
Moving				
12 man hrs.	@$30.00 per hr.	=	$ 360.00	
Standby Slow Water				
4 man hrs.	@$30.00 per hr.	= $ 120.00		
2 machine hrs.	@$20.00 per hr.	= $ 40.00	$ 160.00	
Coring				
0 - 231 = 231 ft.	@$21.00 per ft.	=	$ 4,851.00	$ 5,371.00
Hole: 57K/14/NQ				
Standby Slow Water				
8 man hrs.	@$30.00 per hr.	= $ 240.00		
4 machine hrs.	@$20.00 per hr.	= $ 80.00	$ 320.00	
Standby Vent Tubing & Fan Down				
14 man hrs.	@$30.00 per hr.	= $ 420.00		
7 machine hrs.	@$20.00 per hr.	= $ 140.00	$ 560.00	
Coring				
0 - 282 = 282 ft.	@$21.00 per ft.	=	$ 5,922.00	$6,802.00
Four Flat Holes				
Coring				
0 - 66 = 66 ft.	@$21.00 per ft.	= $1,386.00		
0 - 58 = 58 ft.	@$21.00 per ft.	= $1,218.00		
0 - 28 = 28 ft.	@$21.00 per ft.	= $ 588.00		
0 - 28 = 28 ft.	@$21.00 per ft.	= $ 588.00		$ 3,780.00
Moving Out of Adit to Demob				
46 man hrs.	@$30.00 per hr..	=		$ 1,380.00

CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

Tractor Hours			
6 machine hrs.	@ $75.00 per hr.	=	$ 450.00
Truck Hours			
6.5 trucks hrs.	@ $75.00 per hr.	=	$ 487.50
Items Consumed & Chargeable			
350 gals Diesel	@ $3.00 per gal.	= $ 1,050.00	
2 - 45 gals. drums	@ $85.00 each	= $ 170.00	$ 1,220.00
Core Splitters			
2	@ $780.00 each	=	$ 1,560.00
		Total Invoice	$26,774.50

E. CARON DIAMOND DRILLING LTD. 7 Roundel Road Whitehorse, Yukon Y1A 3H3 Phone (403) 668-2424 Telex 036-8-337

November 30, 1987
Invoice #-2272

IN ACCOUNT WITH:

Omni Resources Inc.
706 - 595 Howe Street,
Vancouver, B.C.
V6C 2T5

To Charge Rental for Light Plant (Skukum)

November 13 to 30/87				
18 days	@ $66.67 per day.	=	$1,200.06	
December 1 to 31, 87				
1 month	@ $2000.00 per mo.	=	$2,000.00	$3,200.06

Total Invoice $3,200.06

APPENDIX 2

CLAIM STATUS

CLAIM NAME/ NUMBER	HOLDER
WH 1 - 8	OMNI RES.
ERN 1 - 27, 30 - 33	OMNI RES.
KIR 1 - 30, 31 - 33 FR	OMNI RES.
KIM 1 - 52	OMNI RES.
OMNI 1 - 12 FR	OMNI RES.
TEX 1 - 22, TREE 1 - 5 FR	OMNI RES.

APPENDIX 3

CONTRACTORS & EMPLOYEES

ACME ANALYTICAL LABORATORIES LTD.
852 E. Hasting Street
Vancouver, B.C.
V6A 1R6

BACON, DONALDSON AND ASSOCIATES LTD.
2036 Columbia Street
Vancouver, B.C.
V5Y 3E1

ERIC BERGVINSON (Geological Assistant)
1235 Chartwell Place
W. Vancouver, B.C.
V7S 2S2

BIG FOOT CONSTRUCTION
RR 2 - Fite 5, comp. 46
Whitehorse, Yukon
Y1A 5A5

BONDAR-CLEGG & CO. LTD.
5420 Canotek Road
Ottawa, Ontario
K1J 8X5

E. CARON DIAMOND DRILLING
7 Roundel Road
Whitehorse, Yukon
Y1A 3H3

CANADIAN AIRLINES INTERNATIONAL
ONE GRANT MCCONACHIE WAY
Vancouver International Airport, B.C.
V7B 1V1

COLETON CONSTRUCTION
15 Juniper Drive
Whitehorse, Yukon

SHELLEY CHVALA (Bull Cook)
#5 - 7227 7th Avenue
Whitehorse, Yukon
Y1A 1R7

RUSS DAVIS (Engineer)
32742 Nicola Place
Abbotsford, B.C.
V2S 6A9

TERENCE ELLIOTT (Geologist)
#3 - 1406 Fir Street
Potter Creek, Yukon
Y1A 4C6

GRAHAM ENNIS (Laborer)
#5 - 7227 7th Avenue
Whitehorse, Yukon
Y1A 1R7

FRONTIER HELICOPTERS LTD.
P.O. Box 220
Abbotsford, B.C.
V2S 4N9

GEOLOGICAL DRAFTING SERVICES
36 Redwood Street
Whitehorse, Yukon

ROBIN HAMILTON (Bull Cook)
Box 4242
Whitehorse, Yukon
Y1A 3T3

SANDY HUGHES (Bull Cook)
#5 - 7227 7th Avenue
Whitehorse, Yukon
Y1A 1R7

NICOLE HULSTEIN (Drafts-person)
#29 - 100 Lewes Blv.
Whitehorse, Yukon
Y1A 3W1

BRENNAN D.A. LANG (Project Engineer)
#306 - 922.5 Alaska Highway
Whitehorse, Yukon
Y1A 3Y9

MAIN STREET MINING
200 - 100 Main Street
Whitehorse, Yukon
Y1A 2A8

A.D. MCCUTCHEON, P.ENG.
933 Marchant Road
Brentwood Bay, B.C.
V0S 1A0

ALLAN MONTGOMERY (Geologist)
Suit 103 - 6622 Willingdon Avenue
Burnaby, B.C.
V5H 2V8

NORECOL ENVIRONMENTAL CONSULTANTS LTD.
#600 - 1281 W. Georgia Street
Vancouver, B.C.
V6E 3J7

NORTHERN CADWORKS
#203 - 4133 4TH Avenue
Whitehorse, Yukon
Y1A 1H8

OROCON INC.
1458 Main Street
North Vancouver, B.C.
V7J 1L8

BRIAN RICHARDS (Engineer)
2355 Bellevue Avenue
West Vancouver, B.C.
V7V 1C9

J.B. RICHARDSON (Geological Assistant)
4883 Cedar Crecent
Delta, B.C.
V4M 1J9

R.J. ROBINSON (Project Geologist)
#414 - 80 Sandcastle Drive
Nepean, Ontario
V2H 9E7

LORNE ROWAN (Geologist)
32595 Dahlstrom Avenue
Clearbrook, B.C.
V2T 4E4

ARI SEPPANEN (Laborer)
#5 - 7227 7th Avenue
Whitehorse, Yukon
Y1A 1R7

PAT SLANEY (Environmental Consultant)
8150 Wiltshire Blv.
Delta, B.C.
V4C 6T4

F.M. SMITH, CONSULTING INC.
6580 Mayflower Drive
Richmond, B.C.
V7C 2X6

STEFFEN, ROBERTSON AND KIRSTEN CONSULTING ENGINEERS
Suit 801, The Burrard Building
1030 West Georgia Street
Vancouver, B.C.
V6E 2Y3

VANCE THORNSBERRY (Project manager)
W. 5701 Shawnee
Spokane, Wa. 99208
U.S.A.

JERRY TURNER (Laborer)
RR 1 - Suit 20 , Comp 69
Whitehorse, Yukon
Y1A 4Z6

STAN UKKULA (Laborer)
N/A
Whitehorse, Yukon

MARCO VANWERMESKERKIN (Geologist)
5443 Wildwood Crescent
Delta, B.C.
V4M 3S8

DEBORAH WEATHERBY (Bull Cook)
#3 - 880 Homer Street
Vancouver, B.C.

PHYLLIS WEATHERBY (Head Cook)
#3 - 880 Homer Street
Vancouver, B.C.

APPENDIX 4

REPORT BY F. MARSHALL SMITH CONSULTING INC.

F. Marshall Smith Consulting Inc.
218-744 West Hastings Street, Vancouver, British Columbia, Canada, V6C 1A5
Phone: (604) 684-2361

January 12, 1988

Mr. E. Bergvinson, President
Omni Resources Inc.
706-595 Howe Street
Vancouver, B C
V6C 2T5

Dear Mr. Bergvinson:

RE: Updated reserve estimate and budget for report of September 3, 1986, and February 24, 1987, Skukum Creek property, Yukon.

This letter should be considered as a qualification of the work performed, and the related reports.by your staff during the 1987 work year. As you are aware, I have visited the property and consulted with your staff during 1987, and concurred with all modifications of my original plan and budget.

As requested, I reviewed the work and the drafts of the final reports, and submit the following recommendations based on the results of this last season. The attached budget was discussed with your staff, and agreed by all parties to be adequate to fund the completion of the projected 1988 work plan.

Since the last report the following changes have taken place outside of the work on the Rainbow and Kuhn zones:

1. The acquisition from Noranda Mines of 34 claims.

2. The staking of 133 additional claims.

3. The construction of a permanent camp.

4. The completion of the applicable environmental work and permit applications necessary for a major development or mining operation.

5. The completion of the upgrading to 'two wheel drive' road access to the property.

6. The assembling of sufficient permanent staff to carry out the development of the property.

The main effort this year was directed to the development of a reserve on the Kuhn and Rainbow Zones.

This effort was recommended by both the undersigned and Mr. Archie McCutcheon, P.Eng., acting as consulting Mining Engineer to the company. Specifically, the recommendations were to enter the mountain that hosts the Rainbow and Kuhn zones, on the footwall of the Rainbow vein, and by drifting and raising, test the relation between the grade in drill holes and the 'run-of-mine' grade from samples. The second, and equally critical task, was to attempt to expand the known reserves, as of February 24 last, by formulating a preliminary feasibility study for a production decision.

In summary, work on the Rainbow and Kuhn zones consisted of 2850 linear feet of underground work and 23,000 feet of surface and underground drilling.

The attached "Reserve Estimates" for both the Kuhn and the Rainbow define the success of the second task of the 1987 project. The first task has been started with the crosscuts in the Rainbow, but this effort must be considered critical in the next phase of work as recommended below.

The following is a summary of the data on the property:

The Skukum property of Omni Resources Inc., consists of 296 mining claims located in the Wheaton River district, approximately 55 kilometres south of Whitehorse, Yukon Territory. The district has recently become the focus of intense exploration activity as a result of the discovery of the epithermal gold-silver mineralization, near Mt. Skukum, by AGIP Canada in 1981. Subsequent exploration has resulted in the delineation of 183,000 tons of ore grading 0.73 ounces per ton gold and 0.61 ounces per ton silver in one of several potential zones of mineralization.

The predominant rock outcrops on the property owned by Omni, consist of granodiorite of Cretaceous age. This unit is composed of several phases with varying hornblende and biotite content with variations brought in contact by the Eocene age faulting. Dykes of andesite and rhyolite fill the faulting, as does slightly younger epithermal to mesothermal-type vein filling, with related wallrock alteration around the veins.

The faults are filled with several periods of quartz and sulphides, with varying quartz colours and silver/gold ratios. The first filling contains no economically significant mineralization. The second phase has considerable sulphides, and high silver to gold ratios, at the near surface changing downward into lower ratios. The third filling consists of coloured and banded quartz with no significant intercepts of gold and/or silver values as yet. There appears to be a fourth filling of quartz/calcite starting to appear at the bottom of the drill information.

Gold to silver ratios within each of the two zones show an increase with depth, and that the Kuhn zone has an overall higher gold to silver ratio than the Rainbow zone (see Figures 1 and 2 following). This probably means that the Rainbow zone will have a Kuhn type zone at depth.

The soil geochemistry and prospecting have identified a large number of gold-bearing veins throughout the property. The gold geochemical anomalies tend to cluster in areas or patches and may reflect a zone of several vein/faults as yet untested by drilling.

There are a large number of 'epithermal low pH' zones on the property that are in areas as yet untested by drilling and geochemistry. Each of these has the potential of capping a vein carrying significant gold and/or silver values, and most of these peripheral targets will have to be evaluated after the upgrading of the drill-proven Kuhn and Rainbow zones into the expected proven reserve, and the detail evaluation of the close in targets.

Based on current estimates (see Page 1, 2 following) the Rainbow zone has 447,138 drill proven tons grading (weighted) 0.196 ounces gold and 10.65 ounces silver per ton. There are additional drill indicated tons based on the interpretation of geology, core recovery and the continuity of the shoot, which will be described once the raises have been completed.

The current drill-proven reserve on the Kuhn zone (see Page 3 and 4 following) is 373,536 tons grading (weighted) 0.261 ounces gold and 4.95 ounces silver per ton. There is an additional reserve of drill indicated mineralization of 131,139 tons grading the same as above.

Within the above reserve estimate (see Page 5 following) are a series of blocks where the 'gold equivalent' exceeds 0.50 ounces per ton (based on $630 for gold and $9.00 for silver in Canadian dollars). This higher grade portion consists of 183,000 tons at 0.575 ounces gold per ton and 16.5 ounces silver per ton. These blocks could easily be mined before removing the lower grade portions.

The total reserve, including drill indicated blocks, consists of 951,814 tons grading on average 0.230 ounces gold and 8.41 ounces silver per ton. This gives a 'gold equivalent' grade of 0.35 ounces per ton gold.

In both the Kuhn and Rainbow, the mineralization is open to depth on the rake, with sufficient drilling to determine the grade/tonnage over most of the intervals tested. There are a few remaining gaps in the drill-proven section between the selected 'proven' reserve blocks.


The next stage in the development of a reserve of gold and silver on the Omni Resources Inc., Skukum Creek property, is to continue the current drift into the veins along strike. This work should determine the mining method best suited for the underground conditions. The work will involve the collection of bulk samples from representative portions of the vein, and the evaluation of the accuracy of drill grades versus actual bulk sampling grades, to verify the drill indicated mineralization.

Raises should be constructed into the Kuhn and/or Rainbow zone to test both the lower grade intersections and the higher grade zones indicated by drilling. Until the relation between drill hole grade and 'run-of-mine' grade is determined, the current reserve estimate is drill proven reserves, but should only be called probable 'ore'.

The programme to deepen and extend the current reserves on the Kuhn and Rainbow must continue, as the size of the plant to treat the potential ore is dependent on the level of drill proven reserves. The spacing of the drill intersections should be expanded to about 150 feet apart, as the current spacing does not improve the variability of the reserve calculations.

A budget of $2,512,400 (see attached detail) is recommended to continue the exploration to completion of a feasibility study on the property.

The attached budget will carry out the programmes described in this report. The location of the drifts and raises proposed by the staff must be sited by a Mining Engineer, but the costing will be approximate for each of the two larger portions of the budget.




F. Marshall Smith, P.Eng.
January 12, 1988.

(604) 684-2361 **F. Marshall Smith, P.Eng.** (604) 684-2361
218-744 West Hastings Street, Vancouver, B.C., Canada, V6C 1A5


Local Exploration and Pre-development Budget

Item	Exploration	Pre-development	Totals
Mining			
Phase A			
Drifting @ $320 per foot		$130,000	
Mobilization & Field Costs		$40,000	
Bulk Sampling		$40,000	**$210,000**
Phase B			
Raising; Rainbow @ $185/ft		$31,000	
Raising: Kuhn @ $185/ft		$29,000	
Slash and Sumps		$14,000	
Drill Stations		$12,000	
Bulk Sampling		$30,000	
Sublevel Drift @ $320/ft		$64,000	
Demobilize & Field Costs		$80,000	**$470,000**
Drilling			
Underground @ $35/ft for 5000 feet	$100,000	$75,000	
Surface @ $30/ft for 8000 feet	$240,000		
Drill Pads	$20,000		
Helicopter Support	$26,000		**$931,000**
Sampling and Assays			
Core	$16,000	$10,000	
Underground		$7,000	
Freight	$7,000	$7,000	**$978,000**
Metallurgy			
Preliminary		$30,000	
Final		$38,000	**$1,046,000**
Feasibility			
Preliminary		$40,000	
Final		$180,000	**$1,266,000**

Continued Page 2



Continued from Page 1 Item	Exploration	Pre-development	Totals
Total carried over from Page 1			$1,266,000
Geotechnical		$35,000	
Environmental		$15,000	
Legal Surveys		$10,000	
Camp Support	$12,000	$50,000	
Supplies	$5,000	$13,000	
Field Office	$2,000	$4,000	
Travel and Transportation	$8,000	$9,000	
Equipment Rentals		$10,000	
Communications - Safety		$25,000	
Vehicles	$6,000	$20,000	
Staff Salaries	$16,000	$80,000	
Consultants	$6,000	$33,000	
Project Overhead	$30,000	$85,000	$1,740,000
Contingencies at 10%	$49,400	$124,600	$1,914,000
Local Exploration Programme			
Drilling			
Surface Drilling 10000 ft @ $30/ft	$300,000		
Drill Pads & Roads	$30,000		
Hellicopter Support 2 months	$35,000		
Geochemistry	$12,000		
Geophysics	$15,000		
Sampling and Assaying			
Core	$28,000		
Geochemical	$14,000		
Freight and Supplies	$4,000		
Camp Support @ $40/day	$19,000		
Suplies	$10,000		
Travel and Transport	$6,000		
Communications - Safety	$2,000		
Vehicles	$6,000		
Staff Salaries	$23,000		
Consultants	$15,000		
Project Overhead	$25,000		$2,458,000
Contingencies at 10%	$54,400		$2,512,400
Total Exploration	$1,141,800		
Total Pre-development		$1,370,600	
Total Budget			$2,512,400



Reserve Estimate Rainbow Zone F. M. Smith, P.Eng. 6/Jan/1988				Area = 100 foot radius Imperial Measurements			
Zone	Area	Width	Gold	Silver	Tons	Gold ounces	Silver ounces
1 X-CUT	14746.56	4.99	0.086	8.99	7022	602.32	62963.61
2 X-CUT#	16038.23	20.51	0.210	15.46	31321	6577.36	484218.69
85-04	6565.98	16.90	0.175	11.23	10566	1849.02	118654.06
85-05	12459.23	11.52	0.111	6.62	13665	1516.76	90459.02
85-08	11947.94	5.02	0.184	5.86	5712	1050.99	33471.70
85-10	7104.18	10.20	0.160	3.11	6904	1104.56	21469.92
85-14	10414.08	15.09	0.151	17.10	14968	2260.22	255959.17
85-15	15015.65	11.19	0.112	9.41	15999	1791.89	150551.12
85-16	26371.58	4.99	0.081	7.43	12558	1014.52	93060.26
85-18	17895.00	14.27	0.116	13.21	24323	2821.47	321306.49
85-19@	5059.04	6.99	0.207	3.66	3367	696.97	12323.22
85-21	21985.29	7.94	0.507	36.20	16624	8428.52	601799.44
86-R08	7776.92	6.79	0.876	17.63	5030	4406.34	88680.12
86-R09	7857.65	7.91	0.124	6.90	5917	733.71	40827.69
86-R10	10871.55	5.58	0.108	4.53	5775	623.68	26159.79
86-R12	8503.49	4.99	0.690	10.19	4049	2786.67	41153.87
86-R15	12593.77	24.80	0.165	16.21	29749	4908.60	482232.47
86-R16	13697.08	5.54	0.195	12.22	7233	1410.41	88385.59
87-D1	10871.55	4.99	0.160	1.01	5177	826.13	5214.97
87-D2	16872.43	6.30	0.172	12.47	10122	1741.02	126223.73
87-D3	20478.34	8.14	0.061	4.59	15869	967.99	72837.46
87-R06	10952.28	13.58	0.125	7.47	14168	1770.97	105833.01
87-R08	6835.08	7.12	0.179	7.74	4634	829.57	35870.73
87-R09	5973.97	11.48	0.078	3.80	6533	509.59	24826.21
87-UG01R	7776.92	8.99	0.214	13.70	6658	1424.85	91216.78
87-UG02R	16468.78	4.99	0.111	14.63	7842	868.21	114431.38
87-UG03R	6512.17	9.88	0.098	5.01	6125	600.22	30684.95
87-UG04R	6808.17	5.48	0.064	5.11	3553	227.36	18153.64
87-UG07R	23653.69	8.01	0.213	6.96	18034	3841.17	125514.45

Continued on page 2

Zone	Area	Width	Gold	Silver	Tons	Gold ounces	Silver ounces
87-UG11R	13535.62	4.82	0.077	5.78	6446	478.72	35935.11
87-UG12R	23599.87	6.00	0.132	2.92	13494	1781.27	39403.91
87-UG15R	15822.95	9.78	0.207	22.95	14733	3049.79	338128.72
87-UG17R	11086.83	14.40	0.735	18.40	15208	11177.76	279824.25
87-UG42R	8288.21	5.12	0.143	5.30	4040	577.72	21411.99
87-UG43R	20160.80	5.25	0.138	13.05	10079	1390.92	131532.79
87-UG44R	12593.77	4.99	0.132	3.59	5997	789.53	21472.85
87-UG46R	6350.71	10.47	0.115	5.36	6330	727.96	33929.17
87-UG47R	14746.56	5.09	0.232	20.02	7142	1656.94	142982.25
87-UG49R	8072.93	8.14	0.102	7.20	6256	638.09	45041.33
87-UG50R	10656.27	13.35	0.157	26.22	13552	2127.62	355326.88
87-UG51R	10171.89	5.81	0.112	17.86	5626	630.07	100473.68
87-UG53R	18567.74	10.60	0.217	10.37	18739	4066.47	194328.35
AVERAGE GRADE			0.196	10.65		2078.19	131054.16

	Tons	Gold	Silver
TOTALS	**447138**	**87284**	**5504275**
Weighted averages		**0.195**	**12.31**

Duplicates as noted:

86-R1#	10414.08	5.94	0.181	20.30	5891	1066.34	119595.33
86-R1#	10171.89	4.00	0.178	13.05	4844	689.75	50568.85
87-UG48R@	10171.89	5.91	0.168	4.09	5721	961.12	23398.79



Reserve estimate Kuhn Zone Based on 30 metre radius of drilling

F.M. Smith, P.Eng. January 6, 1988 All measurements below are Imperial

Drill Hole	Area	Width	Gold	Silver	Tons	Gold ounces	Silver ounces
K86-07	13643.26	6.00	0.078	3.00	7801	608.50	23403.78
K86-07	14342.91	4.53	0.170	14.77	6830	1051.38	91346.64
K86-08	9552.97	3.44	0.235	0.50	4549	736.53	1567.09
K86-08	19181.29	7.91	0.179	3.99	14444	2585.49	57631.96
K86-08	19052.12	4.69	0.134	7.45	9072	1140.72	63420.75
K86-09	12378.50	6.79	0.124	1.50	8006	992.79	12009.51
K86-17	10037.35	10.37	0.099	4.81	9911	981.15	47670.18
K86-17	14773.47	8.79	0.191	5.43	12371	2362.91	67175.79
K86-18	14773.47	16.01	0.186	4.60	22527	4189.97	103622.91
K86-21	14854.20	5.15	0.101	1.57	7287	735.98	11440.48
K86-21	23842.06	5.97	0.081	0.79	13558	1098.24	10711.20
K86-23	17101.16	19.46	0.172	3.21	31687	5450.10	101714.08
K86-24	7992.20	6.36	0.661	11.03	4845	3202.33	53436.68
K86-25	17006.98	6.46	0.092	2.69	10469	963.11	28160.57
K86-26	15812.18	9.48	0.363	15.91	14279	5183.13	227172.41
K86-28	27663.25	3.08	0.102	6.62	13173	828.76	53787.92
K86-S1	21635.46	8.14	0.103	15.10	16765	1726.83	253157.30
K87-UG19	21635.46	42.72	0.119	2.26	88018	10474.17	198921.28
K87-UG26	21635.46	17.06	0.967	5.91	35153	33993.17	207755.56
K87-UG30	17652.81	5.25	0.142	5.53	8825	1253.19	48803.92
K87-UG36	17652.81	16.34	0.621	5.16	27469	17058.10	141738.77
K87-UG57	13643.26	4.99	0.141	6.59	6497	913.64	42701.46
AVERAGE GRADE			0.230	5.84		4433.19	83970.47
TOTALS					373536	97530	1847350

Kuhn Zone continued:

Additional tons based on drilling understating grade

Drill Hole	Area	Width	Gold	Silver	Tons	Gold ounces	Silver ounces
K87-UG35	11732.66	9.96	0.261	4.95	11129	2904.59	55087.11
K87-UG37	18406.29	9.96	0.261	4.95	17459	4556.75	86421.06
K87-UG32	17948.82	9.96	0.261	4.95	17025	4443.49	84273.17
K87-UG22	11517.38	9.96	0.261	4.95	10925	2851.30	54076.34
K87-UG23	25053.00	9.96	0.261	4.95	23763	6202.24	117628.67
K87-UG20	11813.39	9.96	0.261	4.95	11205	2924.58	55466.15
K87-UG28	12378.50	9.96	0.261	4.95	11741	3064.48	58119.43
K87-UG29	16092.05	10.07	0.261	4.95	15436	4028.89	76410.06
K87-UG18	13131.97	~~996.00~~ 9.96	0.261	4.95	12456	3251.02	61657.20
	Totals		0.261	4.95	131139	34227	649139

	tons	ounces gold	ounces silver
Projected totals Kuhn	504676	131758	2496489
Total Rainbow	447138	87284	5504275
Final values	951814	219041	8000764
Grade ounces per ton		0.230	8.406

Gold equivalent ounces per ton 0.350

as of 6 January 1988

Reserve blocks over 0.50 opt Gold equivalent $630/oz Au, $9/oz Ag

F. M. Smith, P.Eng. 6/Jan/1988 Kuhn and Rainbow zones

Zone	Area	Width	Gold	Silver	Tons	Gold equiv.
85-21	21985.29	7.94	0.507	36.20	16624	1.02
86-R08	7776.92	6.79	0.876	17.63	5030	1.13
86-R12	23599.87	4.99	0.690	10.19	11238	0.84
87-UG15R	15822.95	9.78	0.207	22.95	14733	0.53
87-UG17R	11086.83	14.40	0.735	18.40	15208	1.00
87-UG47R	14746.56	5.09	0.232	20.02	7142	0.52
87-UG50R	10656.27	13.35	0.157	26.22	13552	0.53
K86-24	7992.60	6.36	0.661	11.03	4845	0.82
K86-26	15812.18	9.48	0.363	15.91	14279	0.59
K87-UG19	21635.46	8.60	0.406	8.38	17720	0.53
K87-UG26	13643.26	17.06	0.967	5.91	35153	1.05
K87-UG36	17652.81	16.34	0.621	5.16	27469	0.69
AVERAGE GRADE		arithmetic	0.535	16.50	182993	0.84
		weighted	**0.575**	**14.75**	**182993**	**0.79**



Omni Resources Inc.
Rainbow Zone
Ratio Silver to Gold
80
70
60
50
40
30
20
10
0
1300
1200
1100
Median depth in metres of cluster of drill holes
Values averaged for each cluster

Figure 1



Omni Resources Inc.
Kuhn Zone
Ratio of Silver to Gold
35
30
25
20
15
10
5
0
1550
1450
1350
Average values for Holes grouped by depth

Figure 2



Omni Resources Inc.
Rainbow Zone
50000
40000
30000
20000
10000
0
Tonnage
Gold X 40000
Gold Values in front of
Related Tonnage Blocks

Figure 3



Omni Resources Inc.
Kuhn Zone
1.2
1
0.8
0.6
0.4
0.2
0
Tons Divided by 60000
Tonnage
Gold values
Sorted drill hole gold values with Tonnage blocks behind

Figure 4



Omni Resources Inc.
Kuhn Zone
1.4
1.2
1
0.8
0.6
0.4
0.2
0
Gold
Silver / 16
Silver
Gold
Sorted Gold values
Related silver behind

Figure 5



Omni Resources Inc.
Rainbow Zone
1.2
1
0.8
0.6
0.4
0.2
0
Gold
Silver / 40
Sorted Gold in front of
Related Silver Values

Figure 6

APPENDIX 5

DIAMOND DRILL LOGS

[redacted] **DIAMOND DRILL LOG** HOLE No. 87D[redacted] Page 1 of 4

Property SKUKUM CREEK	NTS 104B/12	Claim W.H.	Elevation 1354	Azimuth 335°	Length 167.63	Dip 66° -67°	
Coordinates 7[redacted]N 78077.1E	Dip Tests 68.5° @ 167.63m	Advance 64.58m	Depth 154.00	Date Collared MAY 28/87	Date Completed MAY 31/87		
Purposes TEST ROAD ZONE [redacted] 1225 m. LEVEL	Drilled by E. CARON DIAMOND DRILLING	Assays by ACME	Logged by RJR				

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0	3.96			CASING IN OVERBURDEN: SAND & GRAVEL				
3.96	72.25		162	MODERATELY FRESH COARSE-GRAINED GRANODIORITE.				
				BANDED AND ZONES OF ALTERATION TO 1M. SEDIMENT				
				SHEAR ZONES AND FRACTURES - SOME FILLED, SOME WITH				
				RED + GREEN SERICITE.				
				7.62m SHEAR RUSTY FRACTURE ZONE				
				11.90 5 cm SILICIFIED LESS THAN 5 cm SHEAR ZONE				
				FOLLOWED BY SILICIFY CRACKS SUB-PARALLEL @				
				25° TO CORE AXIS FOR 15 cm.				
				15.00 - 16.50 M: PERVASIVE FRACTURE CONTROLLED HEMATITE				
				ALTERATION ACT.				
				16.5 - 21.6 SMALL HEMATITE VEINLETS TO 1 cm. NO PARTICULAR				
				ORIENTATION.				
				23.9 - 24.4 SHEAR ZONE SAND AND CLAY GOUGE				
				24.4 - 25.15 VERY FRACTURED AND ALTERED.				
				SLIGHTLY VUGGY & VUGGY QUARTZ FILLED FRACTURES				
				42.4 1 cm HEMATITE VEIN @ 20° TO CORE AXIS				
				SOME VEINLETS TO SMALL STRINGERS.				
				48.1 40 cm BLOCK OF VUG. SILICIFIED. MUCH				
				52.3 - 52.3 PORPHYRITIC ANDESITE XENOLITHS TO 5 cm.				
				51.5 2 cm SHEAR ZONE				
				53.5 - 53.9 MORE PERVASIVE CL, EP, SL ALTN. HEMATITE				
				SMALL CO STRINGERS				
				55.9 - 56.6 : ABUNDANT BLACK HEMATITE STRINGERS. SEVERAL				
				[redacted] TO 30° TO CORE AXIS. PERVASIVE ALTN.				
				57.4 2 cm APLITE DYKE 30° TO CORE AXIS. SHARP				
				VUG. VERY FEW MINERALS				
				57.7 XENOLITHS OF APLITE & TRACE MALACHITE IN FRACTS.				
				58.75 - 59.1 APLITE DYKE - MUCH REDDISH TAN FELDS 12° TO CORE AXIS				

[redacted] DIAMOND DRILL LOG HOLE No. 87D1 Page 2 of 4

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	
				61.2 - 68.9 LESS GREEN ALT'N MORE GARNISH WITH LT. BANDS ON MARGINS. BANDS TO 2cm WIDE. LOOKS THE SAME AS ORIG GDR BUT LIGHTER.					
				62.4 - 65.0 MOD. CL, SE, EP ALTN & LT BANDS TO 2cm ON MARGINS. MATRIX ALMOST COMPLETELY CHLORITIZED					
				65.0 - 68.5 - INTENSE SER, CL, SI, LT ALT'N & CALCAREOUS CLAY-FILLED FRACTURES. VERY SOFT GRN. QZ EYES BADLY DISSOLVED. SOME SMALL HEMATITE BANDS.					
				68.5 - 72.25 MODERATE CL, SE, EP ALT'N					
72.25	77.05	72.35	74.00	~~FRAG~~ VFG GREENISH-BLACK ANDESITE DYKE					
		3PCS	.29	APPROX 5 FRACTURES/CM. FRACT. COMMONLY CL+EP. SE. NUMEROUS CA STRINGERS & FILLED SHEARS. SOME HEMATITE. SL, GL, PY					
74.00	83.43	74.00	83.43	72.9 - 77.25 PERVASIVE SUB-PARALLEL SHEARS					
		32 PCS	.72	@ 30° TO CORE AXIS. MANY FILLED WITH GROUND CA. 73.25: 1cm CA VEIN, OTHER CA VEINS TO 5mm, ALL @ 30° TO CORE AXIS. ONE FRACTURE SLIP PARALLEL TO CORE AXIS					
				73.15: 5cm CLAST OF GDR.					
		83.43	92.35	73.25 - 74.9 SULFIDE ZONE. 1-2% COMB. SX. SL, GL,	96D2	73.25	73.90	.65M	560 ppb Au, 18.3 ppm Ag .534
		31 PCS	.65	PY, AS. DISS. & ASSOC. & CA VEINLETS. VFG. SX FILLING SOME FRACT. FILLING QZ VEINS					
				74.9 - 77.05 ~~FRAG~~ FG GREENISH ALT. ANDESITE DIMINISHING CA STRINGERS .5MM TO 5MM. SOME FRACT. FILLING. SOME TENSION GASHES.					
				75.55 5MM STRINGER FG PY @ 20° TO CORE AXIS					
77.05	94.70			ALTERED CG GDR. GREENISH GREY. XTALS TO 7MM.					
		92.35	105.2	CL, SE, EP, SI ALT. EPIDOTE, CA, QZ STRINGERS.					
		30 PCS	.69	MINOR PY DISS. THROUGHOUT. ZONES OF MORE SX.					
				79.3 - 80.0 INTENSE GRN. ALT. 1CM QZ-CA VEIN SUB-PARALLEL TO CORE AXIS. 10% SX IN VEIN. 70% PY, 25% GL, 5% CP	K9601	79.55	80.00	.45M	.69 oz/t Ag, .008 Au oz/t
				ZONES OF MORE INTENSE GRN ALT'N TO 40cm. AND OF SILICIC AND POTASSIC ALT'N TO 20 cm.					

[redacted] DIAMOND DRILL LOG HOLE No. 87 DB Page 3 of 4

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width		
94.70	106.0			FELDSPAR PORPHYRY ANDESITE DYKE						
				DARK GREENISH GREY FS WITH TO 2MM WIDE & 7MM LONG						
				IN SOME ZONES NUMEROUS RANDOM CA STRINGERS						
				TO 2MM. MINOR ZONE SLIGHTLY 20% PROPYLITIC						
		105.7	RE.9	FAINT SLIGHTLY REDDISH-PURPLE DISCOLORATION IN						
		105 PCS	.58	SOME CA STRINGERS						
106.0	135.15			SLIGHT TO MODERATELY ALTERED C.G. GDR. MOD. FRACT.						
				(1 FRACT/15 cm) MOST FRACTS. N65° TO CORE AXIS						
				VARIES FROM MINOR TO MOD. FP, CL, SE ALT ZONES						
				OF POTASSIC ALTE - SOME COINCIDENT W MOD EPIDOTE.						
				ZONES OF APPLE GREEN SERICITE ALTE TO 30 cm. IN						
				FRACTS. MINOR CA VEINLETS TRACE DISS. PY & SC						
				2 DEATH. MOST SHEARED & FRACTURED W DOMN.						
				CLAY GOUGE IN SHEARS						
				122.8-123.2 - SHEAR & FRACT. ZONE. CLAY & CHLORITE GOUGE.						
				124.2 BEGINNING OF MINOR PY. CORE VERY FRACTURED						
				& CEMENTED WITH CA + ATE EPIDOTE						
		126.9	148.6	128.9 SMALL SHEAR						
		67 PCS	.55							
				129.3-129.8 SHEAR & FRACT ZONE. CC AT 32.8						
				132.5-132.8 AS ABOVE						
135.15	139.05			PORPHYRITIC ANDESITE DYKE						
				AS AT 94.70 MINOR PY IN FRACTS & DISS.	9603	138.0	139.05	1.05m	1ppb Au	.018 .6ppm Ag
139.05	140.50			MED. GRAINED MODERATELY ALT. GDR.						
				MINOR DISS. PY. SHOT PRESENT. CA + QZ FILLING	9604	139.05	140.50	1.45m	5ppb Au	.020 .7ppm Ag
				CL, SE, FP PERVASIVE ALTERATION ALONG FRACTURES						
				<1% PY NO OTHER SX VISIBLE	9605	140.50	141.45	0.95m	36ppb Au	.090 3.1ppm Ag
140.50	142.34			AS ABOVE BUT COARSE-GRAINED GDR.						
					9606	141.45	142.70	1.25m	1ppb Au	.038 1.3ppm Ag
142.34	146.65			BRECCIA. GDR CLAST SUPPORTED WITH QZ, CA, EPIDOTE						
				MATRIX. ABUNDANT CA STRINGERS MINOR PY.	9607	142.70	144.10	1.50m	8ppb Au	.041 1.4ppm Ag
					9608	144.10	145.45	1.35m	47ppb Au	.163 5.6ppm Ag

[redacted] DIAMOND DRILL LOG HOLE No. 87 D2 Page 4 of 4

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width			
146.65	149.10			INTENSELY ALTERED AND BRECCIATED GDR. GREENISH-GREY FRAGMENTS OF SHATTERED AND FRACTURE FILLING QTZ	9610	145.45	146.60	1.15M	7ppb Au	.058 2.0ppm Ag	
				[illegible] LESS FRACTURED [illegible]	9611	146.6	148.2	1.60M	5ppb Au	.045 .5ppm Ag	
		148.6	15.1%	[illegible] VERY LIGHT. DG MATRIX. CAL FRACTURES	9611	146.7	149.1	0.90M	7ppb Au	.023 .8ppm Ag	
		10 PCS	.73								
149.10	[illegible]			SHEAR ZONE SMALL CLASTS OF V. ALT. LT GREY GDR [illegible] SOFT FRIABLE [illegible] SHEAR GOUGE ITS CONTACTS.	9612	149.10	149.30	.70M .7	.098 oz/t Au	2.18 oz/t Ag	AU STARE
149.30	149.75			RHYOLITE BRECCIA CLASTS UP TO 1.5 CM. DK GREY MATRIX <1% DISS. PY	9613	149.30	149.75	.45M 1.5	.006 oz/t Au	.13 oz/t Ag	
149.75	151.50			GRANODIORITE - QTZ-RHYOLITE SULFIDE BRECCIA	9614	149.75	UD-10	.35M 1.1	.062 oz/t Au	1.05 oz/t Ag	
		151.4	154.2	CLASTS OF INTENSELY ALTERED PALE GDR [illegible] CUTS QZ VEIN							
		1PCS	.97	AND GREENISH RHYOLITE CLASTS IN V.F.G SX MATRIX MATRIX SLIGHTLY BRECCIATED IN PATCHES OF V.F.G PY AND QZ. ARGILLIC BLEACHING FOR [illegible] QZ VEINS [illegible] PY AND CHLORITE. LOCALLY BANDED WITH CLASTS OF VARIED BETWEEN 30° TO CA. GREY CLAY-FILLED FRACTURES.	9615	151.5	152.30	1.40M 3.6	.037 oz/t Au	1.73 oz/t Ag	
151.50	154.30			RHYOLITE DIKE - IT TAN TO GREENISH GREY. VERY FEW FRACTURES. ANGLE CA. LIKE FRACTURES. NO VISIBLE SX.	9616	151.50	152.30	0.90M	1ppb Au	.015 .5ppm Ag	
					9622	152.30	154.20	1.90M (0.9)	10ppb Au	.023 .8ppm Ag	
154.20	155.30			MULTILITHIC BRECCIA: CLASTS OF BROWN, BLACK & GREY [illegible] IN MATRIX OF QZ, PY + AS. 15% SX	9617	154.20	155.30	1.10M 3.6	.065 oz/t Au	1.36 oz/t Ag	Nat. Au Fraction 0.056
155.30	155.60			30CM BAND OF QZ SX BRX CUTTING GDR @ 30° TRUE THICKNESS 20 CM. CLASTS OF GHOSTED, MILKY QZ IN V.F.G. SX MATRIX. ONLY PY + AS IDENTIFIABLE	9618	155.30	155.60	0.30M 1.0	1.180 oz/t Au	3.96 oz/t Ag	1.757
155.60	156.95			BRECCIATED PALE, MODERATELY ALTERED GDR. CL, SR, EPAT. VERY LITTLE VISIBLE MAFICS REMAINING. BANDS OF EPIDOTE TO 2MM SHEAR @ 156.20.	9619	155.60	156.30	0.60M	.003 oz/t Au	.16 oz/t Ag	
					9620	156.30	156.95	0.75M	33ppb	.05 1.7ppm Ag	
156.95	167.03			PALE GREEN-GREY ALTD GDR. LESS FRACTURED WITH DEPTH. CL/EP/SE ALT.	9621	156.95	157.95	0.75M			
	167.03			EOH							

21.3

AURUM GEOLOGICAL CONSULTANTS INC. — **DIAMOND DRILL LOG** — HOLE No. 87 DZ — Page 1 of 7

Property SKUKUM CREEK	NTS 105 D/3	Claim WH	Elevation 1354m	Azimuth 335°	Length 274.32	Dip -76°	
Coordinates 7113117 N 780732 E	Dip Tests 76° @ 400 76° @ 900	Advance 46.32m	Depth 266.17m	Date Collared May 31, 1987	Date Completed June 7/87		
Purposes TO TEST ROAD ZONE @ 1150 m. LEVEL beneath hole # 85-7	Drilled by CARON DIAMOND DRILLING	Assays by ACME	Logged by R.J.R.				

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0	3.05	——	——	CASING IN OVERBURDEN: WEATHERED GLACIALLY DERIVED COBBLES, SAND AND SILT.				
3.05	70.30m	95	.56	GRANODIORITE:				
		221 p/m		USUALLY COARSE-GRAINED, GREY TO GREENISH GREY. ALTERATION VARIES FROM NONE TO INTENSE CHLORITIZATION, SERICITIZATION AND EPIDOTE ALTERATION. MORE MINOR ZONES OF SILICIC AND POTASSIC ALTERATION. VARYING AMOUNTS OF CALCITE VEINING. FAIRLY COMPETENT OVERALL, WITH SOME WEATHERED FRACTURES AND SHEAR ZONES. MAFIC XTALS V. LARGE (10 mm) AT TOP OF HOLE. VARY FROM LARGE TO V. SMALL THROUGHOUT HOLE. MOST ALTERATION ALONG CRACKS & SHEARS.				
				7.55 - 7.75 = FINE GRAINED. VERY GREEN ALTERED.				
				13.10 - 14.90 : VERY BRECCIATED. BLACK MATRIX. CLAST SUPPORTED. MOSTLY PALE GREY.				
				21.0 - 21.3 FINE GRAINED LT. GREY				
				22.5 30 cm POTASSIC ALTN.				
				A FEW CLASTS OF V.F.G GREENISH-BLACK ANDESITE.				
				29.57 - 29.87 QUARTZ VEIN ± K-SPAR ± CHLORITE. CLASTS OF HOST GDR. V.F.G KSPAR IN PLACES.				
				30.35 = 5 cm APLITE DYKE.				
				31.65 - 31.95 APLITE DYKE ± GDR CLASTS.				
				34.5 7cm EPIDOTE VEIN WITH GDR CLASTS.				
				40.3 - 41.5 VERY FRACTURED - SOME HEALED - SOME NOT.				
				43.6 1cm EPIDOTE STRINGER				

AURUM GEOLOGICAL CONSULTANTS INC. DIAMOND DRILL LOG HOLE No. 87-D2

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
				53.5 - 53.8 INTENSE LIGHT APPLE GREEN ALTERATION.				
				56.15 - 70 cm BAND OF BLACK ALTN				
70.35	77.10	100	.73 16 p/m	ANDESITE DYKE : DARK GREENISH BLACK WITH FELDSPAR PORPHYRBLASTS. TO 5mm x 3mm. ZONES WITH MORE OR LESS FELDSPAR. SOME EPIDOTE STRINGERS SOME CALCITE STRINGERS AND FRACTURE FILLING. FRACTURED ZONE FROM 75.8 - 76.2. NUMEROUS SMALL CRYSTALS OF HB AT BASE OF ZONE				
77.10	79.70			GRANODIORITE AS ABOVE. 77.25. FRACTURE COATED WITH SOFT, FLAKEY RED MINERAL. LOOKS LIKE DRIED BLOOD.				
79.70	80.77			ANDESITE DYKE AS ABOVE BUT WITH AS MUCH HORNEBLEND IN SMALL XTALS AS FELDSPAR IN LARGE ONES.				
80.77	81.35			GRANODIORITE AS ABOVE. 3x5 cm CLAST OF ANDESITE. AT 81.00m				
		77.10-81.35	.44 12 p/m					
81.35	87.80			ANDESITE DYKE AS ABOVE. LESS MAFIC XTALS (N 10%) SOME TO 15mm x 5mm.				
87.80	89.65			GRANODIORITE. AS ABOVE BUT MOSTLY DARK GREEN ALTN. WITH V. LARGE MAFIC XTALS. MUCH FELDSPAR ALTERED ALMOST RED.				
89.65	92.50			ANDESITE DYKE. SHEAR ZONE FROM 89.65 TO 89.80. VERY CRUMBLED AND BROKEN. SOME POWDERED ABUNDANT CALCITE.				
92.50	96.50			GRANODIORITE. (AS ABOVE [AT 87.8])				
		81.35-94.10	.63					
95.85	102.35		33 p/m	ALTERED, VERY FINE GRAINED ANDESITE DYKE.				
		94.10-102.35	.62	CLASTS OF GRANODIORITE TO 30 cm ABUNDAND QZ + CA				
			31 p/m	STRINGERS. PERVASIVE CL, EP, SE, ALTERATION. AND CO_2				

AURUM GEOLOGICAL CONSULTANTS INC. DIAMOND DRILL LOG HOLE No. B7-02

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag (ppm)	Au (ppb)
95.85	102.35			CONTAINS ZONES WITH ABUNDANT DISSEMINATED PYRITE						
Cont'd				AND QTZ-CA STRINGERS WITH UP TO 80% GL OVER 2-5cm.						
				SEVERAL FINE GRAINED PURPLE HEMATITE ZONES IN CA + QTZ.	9623	95.85	97.25	1.40m	3.0	705
				96.45 - 96.85: SHEAR ZONE. VERY CRUMBLED AND SOFT						
				ABUNDANT CA STRINGERS - MANY WITH 50% HEMATITE						
				96.93 - 97.13: SHEAR ZONE. ONLY SOFT CALCAREOUS GREENISH-GREY GOUGE REMAINING.						
				97.13 - 98.05: GRANODIORITE (CLAST?), VERY ALTERED, SHEARED, BRECCIATED AND MINERALIZED GRANODIORITE. MUCH CALCITE, ANDESITE, QTZ, HEMATITE FLOODING, STRINGERS AND CLASTS. 1-2% VIS PY. 1-2% HEMATITE	9624	97.25	98.05	0.80m	1.0	14
				98.05 - 99.50 INTENSELY ALTERED, ~~SILICIFIED~~ GREEN ANDESITE PY DISS. THROUGHOUT, GL IN QTZ, CA, THE STRINGERS. 2-3% PY, .5-1% GL.	9625	98.05	99.50	1.45m	16.2	61
				99.50 - 102.35 LESS PERVASIVELY ALTERED ANDESITE. DARKER, VIVID APPLE GREEN ALT^{N} ON FRACTURES AND STRINGERS. 5% IN CA + QTZ VEINLETS. VERY LITTLE DISS. PX. ~1-2% COMB PY+GL.	9626	99.50	101.00	1.5m.	10.9	42
					9627	101.00	102.36	1.35m	8.3	32
102.35	209.30	98	.11	MODERATELY ALTERED CG GDR. AS ABOVE DYKE. GREENISH GRY. ZONES MORE AND LESS INTENSELY ALT'D. ZONES +BANDS TO 3cm WHERE FELDSPAR ALT'D BLOOD RED. NUMEROUS FRACTS + SHEARS FAIRLY COMPETENT. TRACE SX AT TOP, NONE BELOW						
				133.4 - 134.3 GREY WITH VERY FEW MAFIC XTALS						
				135.4 - 136.5 VERY BROKEN UP AND SHEARED. ABUNDANT CA CEMENT.						
				142.1 - 142.3 SHEAR + BRECCIA ZONE + MINOR HE.						
				MORE BROKEN, ~~AND~~ FRACTURED AND CRUMBLY ? DEPTH. ESP. AFTER 160 m						
				174.2 - 177.6 : SHEAR ZONE. SAND + CLAY GOUGE. VERY SOFT IN PLACES. ~~MAXIMUM~~ SIZE UNBROKEN ~5cm. NO VIS MIN.						
				184 - BEGINNING TO SEE TRACE DISS PY ON ~~AND~~ NEAR FRACTS & VEINLETS						

AURUM GEOLOGICAL CONSULTANTS INC. DIAMOND DRILL LOG HOLE No. _____ Page 4 of 7

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	
				196.95 - 200.80 : GRADES INTO EXTREMELY ALTERED CG GDR QZ XTALS BARELY VISIBLE ALL MAFICS & FELDSPARS ALTERED GREEN. SLIGHT RUSTY. TRACE VIS PY.					
				197.7 25cm SHEAR ZONE					
				200.80 - 202.60 REGULAR, ALTERED C.G GDR.					Ag (ppm) Au (ppb)
				202.60 - 203.15 AS ABOVE BUT 3-5% PY. AND MORE SHEARED.	9628	202.60	203.15	0.55m.	8.4 295 .009 opt
				203.15 - 203.70 1-2% PY					
				209.15 : 15cm FLOW BANDING @ 30° TO CORE AXIS					
204.30	207.45			ANDESITE DYKE : CONTACT WITH FLOW BANDING 30° TO CORE AXIS. MODERATELY GREEN ALTERED WITH NUMEROUS FRACTURES FILLED WITH CA					
		204.30-204.90 1.4% Cpy	.61						
207.45	215.10			GRANODIORITE AS ABOVE <<1% PY SMALL ZONE OF CA VEINING @ 209.50 ± A FEW GALENA XTALS. SOME LARGE (10cm) CLORITE XTALS.	6075	209.35	210.30	0.95m.	~~53~~ 3.6 .11 ~~285~~ 102 .003 opt
		204.30-210.25 30 qtz vns.	.79	209.50 - 210.25. PYRITE-RICH ZONE. 3% PY DISS. & IN STRINGERS & ALONG CA VEINLETS.					
215.10	219.25			PROPILITICALLY ALTERED GRANODIORITE. CRUMBLED & SHEARED LOCALLY MUCH QTZ & RHYOLITE FELDSPAR. ABUNDANT CA STRINGERS.	9629	215.10	216.38	1.28	~~154~~ 5.9 .17 ~~1060~~ 285 .008 opt
				2-3% DISS PY. TRACE CP. SX. V.F.G. MINOR ARSEN	9630	216.38	217.85	1.47	15.4 .45 1060 .031 opt
				215.20: 10cm SHEAR ZONE (CRUMBLY) THEN 1m SOFT, PARTIALLY CRUMBLED SHEAR	9631	217.85	219.25	1.40	10.8 .31 295 .009 opt
				ABUNDANT SERICITE, CLORITE, CALCITE, QUARTZ					
				216.90: 2cm WIDE, BANDED QZ VEIN + AS NEEDLES & PY CLUMPS. ~10% SX IN VEIN					
				417.7: SMALL BLEB OF CP.					
				418.10: 10cm CLAST OF CLORITIC CALCITE. TRACE DISS PY LARGE (1cm) CL XTALS.					
				419.30 RHYOLITE CLASTS OR INTRUSIONS 5cm ACROSS					

AURUM GEOLOGICAL CONSULTANTS INC. **DIAMOND DRILL LOG** HOLE No. 87D2 Page 5 of 7

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	*Au (oz/ton) or(ppm)	*Au (oz/ton) (ppb)
219.75	219.55			HANGING WALL SHEAR ZONE. BLACK GOUGE, RHYOLITE, QZ + GDR CLASTS & FRAGS, 3-4% PY 1% AS ARSENOPYRITE. INCLINED ~30° TO CORE AXIS.	9632 *	219.75	219.55	.30m * LD	*.98*	~~.044~~ .015*
219.55	220.84			RHYOLITE BRECCIA: CLASTS OF RHYOLITE IN QZ SX MATRIX OVERALL N 5% PY, 1% AS. SX UFG. RHY CLASTS TO 7CM. MINOR CHLORITE. SHEAR @ 220.70 ORIENTED @ 23° TO C/A.	9633 *	219.55	220.84	1.29* 4.2	*2.22 5311-5419 2300-2317.34	~~.015~~ .099*
220.84	221.52			QZ SX BRECCIA: AFEW CLASTS OF RHY TO 5CM AT TOP, GRADING TO FEWER AND SMALLER ↓ DEPTH. ABUNDANT SULFIDES. OVERALL 5% PY, 2% AS, <1% GL, <<1% CP. CP MORE COMMON IN GL RICH ZONES. PYRARGARITE VISIBLE IN GL ZONES. 41% SL. 220.84-221.52 ~50:50 QZ SX + LARGE CLASTS OF RHY. SOME CA IN RHY.	9634 *	220.84	221.52	0.68m * 2.2	*10.13	~~.099~~ .292*
				221.52-222.03 F.G. QZ SX BRX. N3% SL IN QZ LT + DK. 10CM SAND OF DARK, VFG PY AT START OF INTERVAL ORIENTED @ 25° TO C/A. 1% PY IN RHY, MINOR (<1%) GL WITH TRACE PR.	9635 *	221.52	222.03	0.51m * 1.7	*10.69	~~.297~~ .081*
				222.03-222.55 2% GL, 2% SL, 1% PY, 1% AS, MINOR PR, MINOR CP VERY LITTLE RHY.	9636 *	222.03	222.55	0.52m * SEC. PREP 1.7	*55.53	~~.081~~ .269*
				222.55-224.00 5% PY/SL (VFG DARK MIXTURE) 1% AS MINOR GL. ~50% RHY. LAST 80 cm - DARKER, LESS QZ, MORE PHYLLITIC SX MASS, WITH CLASTS OF RHY + QZ TO 1CM.	9637 *	222.55	224.00	1.45m 4.8	*7.86	~~.269~~ .178
224.00	224.17			SHEAR ZONE: NO VIS SX. GREEN, VERY SOFT. 30° TO C/A. BANDED.						
224.17	224.62			MULTI-LITHIC BRECCIA: PROPYLITIC ALT BRECCIA MUCH EPIDOTE + SERICITE. VERY SOFT. SOME SX IN QZ. SOFT RHY.	9638	224.00	225.30	1.30m	10.7 .312	545 .016 opt
224.62	224.97			HARD, BARREN BANDED RHYOLITE.						0.025, 0.66/2.13
224.97	225.30			SOFT GREEN BANDED ALT RHY: ABUNDANT CHLORITE SOME CA. NO VIS SX.						
225.30	226.13			MULTI-LITHIC BRECCIA: AS AT 224.17-	9639	225.30	226.13	0.83m	41.3 1.205	1360 .040 opt
226.13	229.18			RHYOLITE: ZONES OF SOFT, LT. GRN ALT'N ~ ZONES OF HARD, CHERTY-LOOKING RHY.	9640	226.13	227.10	0.97m	4.2 .123	33 .001 opt

AURUM GEOLOGICAL CONSULTANTS INC. DIAMOND DRILL LOG HOLE No. 87-D1 Page 6a of 7

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag (ppm)	Au (ppb)	
					9641	227.10	228.15	1.05m	~~47~~ 1.2 .035	~~33~~ 21	.001
					9642	228.15	229.18	1.03m	3.1 .090	15	.001
229.18	231.43			MULTI-LITHIC BRECCIA: BANDED, BANDING ORIENTED 30° TO C/A	9643	229.18	230.30	1.12m	101.9 2.972	5660	.165 opt
				3-5% PY IN FG DARK MATRIX, CLASTS OF	9644	230.30	231.43	1.13m	59.6 1.739	2100	.061 opt
				QZ + RHY TO 4 cm							
				230.30 - 230.90 : VERY SOFT, ALTERED SHEAR ZONE							
				BANDS ORIENTED 25° TO C/A.							
231.43	233.89			M.G. QDR : VERY PROPYLITIC ALT. V. SOFT, GRAIN. QZ XTALS	9645	231.43	232.31	0.88m	12.0 .350	52	.002
				BARELY VISIBLE, BARR TRACE DISS. PY. BANDED	9646	232.31	233.21	0.90m	2.9 .085	31	.001
				@ 30-40° TO C/A. CRUMBLY, CLAY-FILLED SHEAR	9647	233.21	233.89	0.68m	2.2 .064	42	.001
				@ 231.80m & at 233.20m. ABUNDANT CHLORITE,							
				SERICITE, CLAY ALTN. SOME SMALL (<5mm) VUGS.							
				SOME CA STRINGERS + FRACT. FILLINGS							
233.77	250.92			RHYOLITE : BARREN, MASSIVE, GREENISH TAN. NO VIS SX.	9648	233.89	235.10	1.21m	.5 .015	7	.001
				SEVERAL BLACK VEINS TO 3mm WITH QZ XTALS TO 1mm. CLAY-	9649	235.10	236.65	1.45m	.7 .020	3	.001
				FILLED FRACTURES. MODERATELY VUGGY.							
				236.55 CLAY-FILLED FRACTURE AND V. THIN SMALL BLACK	9650	236.65	238.10	1.45m	2.6 .076	10	.001
				VEINLET.							
				238.10 2mm BLACK VEINLET.	9651	238.10	239.45	1.35m	1.1 .032	4	.001
				238.65 - 239.15 2mm BLACK VEINLET PARALLEL TO CORE AXIS	9652	239.45	241.18	1.73m	.9 .026	7	.001
				241.05 CLAY-FILLED SHEAR	9653	241.18	242.35	1.17m	1.1 .032	3	.001
				242.65 CLAY-FILLED SHEAR ZONE 5cm THICK 30° TO C/A	9654	242.35	243.80	1.45m	1.3 .038	1	.001
				245.66 - 245.96: 5 SMALL 1mm BLACK VEINLETS SEMIPARALLEL TO CORE AXIS	9655	243.80	245.18	1.38m	1.1 .032	1	~~.001~~ .001
				245.96 - 247.40 - RHYOLITE SLIGHTLY DARKER. BLACK VEINLETS	9656	245.18	247.19	2.01m	3.0 .088	37	~~.001~~ .001
				PERVASIVE THROUGH CORE. CONTACT AT END							
				WITH ~~GRAD~~ NORMAL LT. GRN. RHY @ 5° TO C/A.	9657	247.19	248.72	1.53m	.4 .01	7	.001
					9658	248.72	250.24	1.47m	.8 .023	8	.001

0.001, 0.08 / 3.05

0.001, 0.05 19.2

AURUM GEOLOGICAL CONSULTANTS INC. DIAMOND DRILL LOG HOLE No. 87-02 Page 7 of 7

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag (ppm)	Au (ppb)	
-					9659	250.24	250.92	0.68m	.7 .02	1 .001	
250.92	268.30			MULTI-LITHIC BRECCIA: CLASTS OF GREENISH TAN RHYOLITE AND GDR. WITH QZ AND SX VEINLETS, STRINGERS AND MATRIX. OCCASIONALLY MATRIX IS RHYOLITE WITH CLASTS OF OTHER MATERIAL, OCCASIONALLY RHY AND GDR MIXED TOGETHER WITH NO MATRIX. SOME CLASTS SHARP-EDGED. SOME SUB-ROUNDED/MELTED. BANDING GENERALLY 20-30° TO C/A.	9660	250.92	253.10	2.22m	63.4 1849	2020	.059
	210.25	267.75	.75		9661	253.10	253.50	0.40m	2.6 .076	14	.001
					9662	253.50	254.75	1.25m	19.9 580	595	.017
					9663	254.75	255.85	1.10m	12.6 368	295	.009
				250.92 - 253.19: RHY + GDR WITH DISS + FRACT FILLING SX. 1-2% PY, 1-2% SL							
					9664	255.85	257.30	1.45	~~6.7~~ 227.1 6625 ~~500~~ 2890		.084
				253.19 - 253.50: BARREN RHY + VUGS TO 2mm							
					9665	257.30	258.17	0.87	13.5 394	310	.009
				253.50-254.75: BRECCIATED RHYOLITE WITH QZ + SX MATRIX N1% SL, 1% PY	9666	258.17	259.69	1.52	40.1 1170	695	.020
				254.75 - 255.85: SWIRRLED, BANDED, U.ALT'D GDR WHICH GRADES OUT OF RHY AT TOP AND INTO RHY AT BOTTOM. SOME CA VEINLETS 1% TOTAL SX - MOSTLY PY.	9667	259.69	261.21	1.52	298.4 8.704	2060	.060
				255.85 - 258.17: LARGE CLASTS TO 15 cm OF GDR + RHY MELTED TOGETHER. JUST MINOR DISS PY + SL.	9669	261.21	261.95	0.94	2.7 .079	73	.002
				258.17 - 259.69 RHYOLITE WITH STRINGERS OF PY @ 20° TO C/A AND BLEBS OF QZ + CA TO 1cm. N1% PY, <1% SX.	9670	261.95	263.04	1.09	12.1 .353	495	.014
				259.69 - 261.21 RHY SHOT THROUGH WITH QZ SX VEINS. TO 2.5cm NO CA. N2% PY, 1-2% SL.	9670	263.04	264.57	1.53	88.1 2.570	3250	.095
				261.21-263.04: EXTREMELY ALTERED, SWIRRLED, BANDED GDR. HIGH LEVEL OF PROPYLITIC ALT'N MINOR PY.	9671	264.57	266.45	1.88	26.6 .776	660	.019
				263.04 - 264.70: QZ PY + SL WITH BLEBS OF VUGGY ALT'D RHY. N3% SL, 2% PY	9672	264.45	266.33	1.85	1.7 .050	140	.004
				264.70: 16 cm SOFT CLAY GOUGE SHEAR ZONE							
				264.3 - 266.45 VERY NICE BRECCIA WITH SUB-ROUNDED CLASTS OF QZ, RHY, BANDED RHY, GDR, ALT'D GDR IN MATRIX OF (PROBABLY) LT GREEN APLITE. MUCH EPIDOTE, SERICITE AND CHLORITE ALT'N.							
	267.55	274.32	.53								
		16pieces		266.45 - 268.30: BANDED ALT'D GREENISH YELLOWISH GREY GDR.							
268.30	274.32			RHYODACITE DYKE WITH FELDSPAR XTALS TO 1cm							
	274.32			EOH.							

7498

[redacted]

DIAMOND DRILL LOG

HOLE No. 87-D3 Page 1 of 5

Property SKUKUM CREEK	NTS 105 D3	Claim WH	Elevation 1354 m	Azimuth 318°	Length 250.85m	Dip -76°	
Coordinates 7171.7 N 78672.1E	Dip Tests -76 @ EOH	Advance 60.69 m	Depth 243.40	Date Collared JUNE 17/87	Date Completed JUNE 21/87		
Purposes TO TEST 115 m LEVEL 30 m SW OF HOLE 87-D2	Drilled by CARON DIAMOND DRILLING	Assays by ACME	Logged by R.T. ROBINSON				

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0.0	3.05	—	—	OVERBURDEN: GLACIALLY DERIVED: GRANITOID BOULDERS, SAND AND SILT.				
3.05	69.47	96	.54	GRANODIORITE: GREEN TO GREY, COARSE GRAINED, PROPYLITIC ALTERED. SOME BANDS / ZONES MORE AND LESS ALTERED AND MORE AND LESS FRACTURED & SHEARED. A FEW SMALL ZONES OF POTASSIC ALTN. SMALL BANDS AND STRINGERS OF HEMATITE. ALSO STRINGERS OF CA and QZ. VERY LITTLE, IF ANY SULFIDES.				
		24 pieces		3.05 - 5.49: MED. DK GRY GDR ± PALE ALT° BANDS. [redacted]				
				5.49 - 18.06: LIGHTER GREENISH GREY ALT'D GDR ± SOME POTASSIC ALTN [redacted] in BANDS TO 1 CM. CLAST OF APLITE 4x7 cm. LT MAFICS ± FELDSPAR PHENOCRYSTS.				
				10.56: @ 20 cm DK GREEN ALT'D BAND MOST FRACTS. 35-45° TO C/A. A FEW MINOR SHEARS ± HEMATITE STRINGERS.				
				18.06 - 20.55 MORE ALT'D, SHEARED, FRACTURED & BRECCIATED. SOME BANDS QUITE DARK GREEN				
				20.55 - 46.15 SLIGHTLY GREENISH, GREY, CG GDR. BANDS OF MINOR POTASSIC, CHLORITIC ± SERICITIC ALT'N. A FEW BANDS OF FG CHLORITE ± ALT° HALOS. FG GRY BAND to 20 cm @ 35.75, 36.15: 20 cm BRN. GRN. ALT. BAND MAFICS → CL, FELD → BRN SERICITE. 32.80: SHEAR ZONE - CLAY ALT, FG BRN ± MALLISH-GREY ALT BANDS @ 38.60, 43.90 ± 44.25. Crumbly fract ZONE @ 44.90.				
				46.15 - 48.20: MORE CHLORITE ALT'D. FEWER BLACK MAFICS. CRUMBLED, CLAYEY SHEAR @ 46.32.				
				48.20 - 52.73 ± MORE GREY, LESS ALT'D. OVERALL WITH BANDS OF MOD. ALTD TO 20 cm 51.40 FRACTURE SYSTEM FILLED WITH HE. 2CM WIDE WITH CLASTS OF GDR.				
				52.73 - 53.25 MORE CL - EP - SE ALT'D. FRACTURED & BLOCKY CLAY GOUGE SHEAR.				

[redacted] DIAMOND DRILL LOG HOLE No. 87-D3 Page 2 of 5

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
				53.25-66.85: MOD. ALT GREENISH-GREY GDR ± BANDS MORE OR LESS ALT'D. GREEN BAND @ 57.05-57.30, 20 cm F.G. MAUVISH-TAN ZONES WITH ORANGE FELDSPARS - NO MAFICS AT 60.60 & 65.10				
				66.85-67.20 VERY DARK, GREENISH-BLACK ALT'D BAND M.G. MAFICS → CL. FS → SE.				
				68.80-69.10: BAND AS ABOVE. OTHERWISE AS AT 53.25'				
				69.11 : GRADES DARKER, FINER GRAINED - GRADES INTO:				
69.47	74.98	100	.54	Qz.FS.HB PORPH ANDESITE - OR DIORITE WITH 50% APHANITIC GROUNDMASS: V.DK. GRY WITH GREENISH TINGE IN ZONES AND CHLORITE STRINGERS. A FEW CALCITE STRINGERS. NO VIS SX. 50% GG PLAG: MAFICS WITH MINOR Qz ± 50% DARK APHANITIC GROUNDMASS. A FEW HEMATITE STRINGERS.				
				73.30-73.77: LT. CHLORITIC, ALTERED GDR.				
				73.77 SHEAR @ 20° TO C/A. HE. CL. CA. SE. IN SHEAR				
				74.40-74.98: CRUMBLED, MUDDY FRACTURE ZONE.				
74.98	78.47	100	.27	ALT'D. CG GDR: V. CRUMBLED & BLOCKY MUCH CHLORITE IN SHEARS				
				40 cm BAND OF DIORITE/ANDESITE @ 77.15. V. FRACT/SHEARED.				
78.47	83.64	100	.51	DARK, SLIGHTLY GREENISH AND/DIOR TO AT 96.47: BAND OF DARKER FINER-GRAINED ANDESITE, AND BANDS OF DIORITE.				
83.64	85.90			MOD. ALT'D GDR: SOME FELDSPAR ALT'D/STAINED BLOOD RED - MUCH CL. CG. GRADATIONAL CONTACT OVER 30 cm.				
85.90	89.46		.60	AND/DIOR. AS ABOVE:				
89.46	90.80		.47	GRANODIORITE AS ABOVE: GRADES BACK INTO:				
90.80	93.38		.61	PORPH AND/DIOR.:				
93.38	96.45	100	.91	GREENISH-TAN, REDDISH-ORANGE ALT. GDR AS ABOVE.				

[redacted] DIAMOND DRILL LOG HOLE No. 87-D3 Page 3 of 5

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag (Oz/T)	Au (Oz/T)
96.45	97.26			AUTOBRECCIATED PORPH. AND/F.G DIOR. AS ABOVE: CA VEINLETS OFFSET BY SMALL FRACTS.	9673	97.26	99.00	1.74m 5.7'	.02	.001
97.26	99.00	96%	111.97 .63 20 pieces	GDR: SMALL SHEAR FILLED WITH BLACK FG. GRAY GOUGE + CALCITE, : GDR HIGHLY ALTD WITH CL, EP, SE, CLAY-FILLED CRUMBLED SHEAR ZONE @ 98.00: 1-2% PY						
99.00	107.59			ANDESITE DYKE: V. DK GRY, FG. ABUNDANT CHLORITE STRINGERS A FEW STRINGERS OF CA + HEMATITE. QZ + FSPAR PHENOCRYSTS MORE ABUNDANT AFTER 102.60. RESEMBLES A FINE-GRAINED DIORITE MORE THAN AND. AFTER THIS PT. 1-2% PY IN STRINGERS + BLEBS TO 101.50, THEN VERY LITTLE PY.	9674	99.00	100.95	1.45m 4.8'	.01	.001
107.59	108.45			GDR: HIGHLY ALTERED, V. ABUNDANT SL. C.G. SECONDARY K ALTN.						
108.45	110.35			AND/DIOR AS ABOVE: SOME FSPAR CRYSTS ALT'D SALMON PINK/RED TRACE DISS. PY.						
110.35	194.95	97%		GRANODIORITE: COARSE GRAINED, PROPYLITIC ALTERATION, ABUNDANT CL A FEW SHEARS AND FRACTURED ZONES. MINOR ZONES OF POTASSIC ALT'N. SOME FRACTURES FILLED WITH CALCITE + A FEW CA VEINLETS + STRINGERS. MINOR QZ OPENING. A FEW BLEBS + STRINGERS OF MINOR PY + TRACE GL. ZONES OF MORE AND LESS INTENSE ALTERATION. A FEW DARK ERGS OF AND. OR QZ DIOR.	9675	118.35	119.75	1.40m 4.6'	.05	.001
				118.35-119.75: POTASSIC ALT'N, 1-2% HEMATITE STRINGERS + PY STRINGERS. ~1% PY. SLIGHTLY DARKER GREEN TO 120.03.						
	101.97-122.98	96%	.59 76 pieces	122.65-123.15: V. ALT'D, SHATTERED, BRECCIATED ZONE. DK GRN.						
				129.05: 10 cm Band of intense, REDDISH K SPAR ALTN, POTASSIC ALT'N MORE COMMON AFTER THIS POINT.						
	123.98-139.40		.58 61 pieces	VERY FRACTURED BETWEEN 139.60 and 145.39						
	139.40-145.40		.18 7 pieces	40 cm CORE LOST BETWEEN 142.2 + 142.7						
				PY STRINGER @ 147.40 IN QZ						
				PY STRINGER @ 149.7 IN QZ + SHEAR ZONE.						
	145.40-167.80		.42 67 pieces	SHEAR @ 154.6 TO 154.7						

[redacted] DIAMOND DRILL LOG HOLE No. 87-03 Page 4 of 5

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag (opt)	Au (opt)	
				1mm WIDE VEG GL+PY STRINGER IN CL @ 161.61m							
				MORE CHLORITIC AFTER 165m. MINOR DISS PY THROUGHOUT	9676	171.95	173.37	1.42	.22	.001	
	167.80	212.69	.67	MINOR DISS GL XTALS FROM 171.95 - 173.37. NOT OPE.				4.7			
			13% fract	MINOR DISS GL + PY FROM 175.60 - 178.00							
		98		MUCH MORE EPIDOTE; LESS CL AFTER 176.00. QUE MORE BANDED & SWIRLED.	9677	175.6	178.00	1.4m	.10	.001	
				MINOR CHALCOPYRITE (2 grains) @ 189.90m.				4.6			
				193.60 : 5 cm SANDY, CLAYEY SHEAR ZONE.							
				INCREASING ALTERATION AND FRACTURING WITH DEPTH							
				ABUNDANT CALCITE NEAR END OF ZONE IN VEINLETS, STRINGERS, FRACTURE FILLING.							
194.95	195.89			EXTREMELY ALTERED, BRECCIATED, GDR. DARKER, STILL COARSE GRAINED. MINOR PY, TRACE GL.	9678	194.95	195.89	0.96	.28	.005	
								3.1			
195.89	200.35			AS ABOVE BUT LIGHTER GREEN, AND ONLY MINOR PYRITE							
200.35	201.10			ANDESITE DYKE ONLY MINOR QZ + FSPAR PORPHS. FRACTURE ZONE 201.10 - 201.19.							
201.19	209.15			GRANODIORITE AS AT 194.95 BUT ONLY MINOR PY TO 204.70, THEN ~1% PY. ALMOST UNRECOGNIZABLE AS GDR.	9679	204.70	206.10	1.40	.27	.012	
				CHLORITIC PARTINGS PARALLEL TO CORE AXIS. ABUNDANT CALCITE,	9680	206.10	207.55	4.6 1.45	.41	.006	
				IN STRINGERS, FRACT-FILLING + FLOODED ZONES.				4.8			
					9681	207.55	209.15	1.60	.22	.005	
								5.2			
209.15	210.55			RHYOLITE WITH CLASTS OF GDR ABOVE; AUTOBRECCIATED, CHLORITIC. ALMOST BARREN.	9682 *	209.15	210.55	1.40m * 4.6	.56	.012	Native Au HW Prep
210.55	211.10			QZ SX-BRX. ~10% SX. MOSTLY PY. MINOR GL GALENA-RICH POD @ 111.00m	9683 *	210.55	211.10	0.55m * 1.8	22.47	.239	0.259
211.10	212.00			MULTI-LITHIC BRECCIA. CLASTS OF RHY, QZ, FS, GDR IN ANDESITIC MATRIX. MAX. CLAST SIZE : 1cm. TR PY.	9684 *	211.10	212.00	0.90m * 3.0	2.79	.045	0.051
212.00	212.15			SHEAR ZONE ORIENTED 30° TO C/A. BANDED, RHY, EP, GDR. MINOR PY.	9685 *	212.00	213.30	1.30m * 4.3	1.91	.047	0.046 0.041, 212.75
					9686	213.30	214.85	1.55m 5.1	1.55	.032	0.031
212.15	217.80			MULTILITHIC BRECCIA AS @ 211.10 BUT WITH LARGE RHY. FRAGS TO 40cm. RHY FRAGS BRECCIATED WITH SOFT, ROUNDED EDGES. MINOR PY. BARE TRACE GL IN STRINGERS.	9687	214.85	216.25	1.40m 4.6	4.59	.040	0.046
	217.69	218.85	.84								

[redacted] DIAMOND DRILL LOG HOLE No. 87-03 Page 5 of 5

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag (oz/T)	Au (opt)	
					9688	216.35	217.90	1.55 m 5.1	1.54	.035	0.041
217.80	218.85		.61 9%	RHYOLITE WITH STRINGERS OF MULTI-LITHIC BRECCIA TO 5mm MINOR (<1%) PY. IN STRINGERS. ABUNDANT QZ XTALS OR FRAGS.	9689	217.90	218.85	1.05 m 3.4	3.11	.050	0.041
											0.CA: 2.40 /8-2
218.85	219.30	99	.17 1m	F.W. SHEAR ZONE: BANDED, SHEARED & ALTERED ANDESITE + RHYOLITE SILICIFIED UNDER & SMALL XTALS OF SIDERITE? XTALS IN UNDS. ABUNDANT EPIDOTE. ORIENTED ~25° TO C/A. MINOR CA. CL.	9690	218.85	219.30	0.45 m 1.5	.47	.015	
219.30	224.80	98	.52 16%	RHYOLITE: AUTOBRECCIATED AND SLIGHTLY ALTERED WITH CLAY IN FRACTURES. MORE COMPETENT / LESS FRACTURED - ALT'D. & DEPTH. MINOR CA FRACT FILLING. LIGHT GREENISH-TAN. MINOR PY FRACT FILLING.	9691	219.30	220.70	1.40 m	.01	.001	
					9692	220.70	222.30	1.6 m	.01	.001	
					9693	222.30	223.60	1.30 m	.01	.001	
					9694	223.60	224.80	1.21 m	.09	.001	
224.80	226.35	100	.57 43%	PROPYLITICALLY ALTERED ANDESITE DYKE: GREENISH BLACK FINE-GRAINED. NO PHENOCRYSTS. NO UNS. SX. ABUNDANT CA STRINGERS. A FEW CLASTS OF GDR.	9695	224.80	226.30	1.50 m	.44	.005	
226.35	250.85	100	.46 54	PROPYLITICALLY ALTERED GRANITE: PINK GRANITE WITH FEW MAFICS AND ABUNDANT EPIDOTE, SERICITE, CHLORITE IN BANDS, FRACTURES AND FLOODED ZONES							
	250.85			EOH-							

297.38

[redacted] **DIAMOND DRILL LOG** HOLE No. A7-84 Page 1 of 2

Property SKUKUM CREEK	NTS 105 D/3	Claim WH	Elevation 1384m	Azimuth 333°	Length 1068'/325.53m	Dip -66°
Coordinates	Dip Tests -64@500' -66@1068	Advance 132.40m	Depth 297.38m	Date Collared JUNE 22/87	Date Completed JULY 2	
Purposes TO TEST RAINBOW ZONE 1150m LEVEL SW OF HOLE D3		Drilled by CARON DIAMOND DRILLING		Assays by ACME	Logged by RJR	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0.0	3.66			NO CORE: CASING IN OVERBURDEN				
3.66	46.83		39	GRANODIORITE: CG. LT GRY TO DK. GRNISH-GRY. WEAK TO STRONG PROP. ALT'N. SOME NARROW ZONES OF MODERATE POTASSIC ALT'N. STRONG WEATHERING AND OXIDATION IN SOME ZONES.				
				- FRACTURES WEATHERED RUSTY TO 17.37.				
				- STRONGLY RUSTY-WEATHERED FOR 35cm @ 21.20.				
				- 36.50-38.00 STRONG RUSTY WEATHERED FRACTURE ZONE				
				- 40.07 1cm WIDE BARREN QZ VEIN.				
46.83	51.70		70	FS, HB AND DYKE ? MINOR AMOUNTS OF QZ PHENOS. HB ALT > CL.				
				- GREENISH GRY. (DK) STRONG PROP. ALT. MINOR CA STRINGERS				
				- 51.11-51.21 STRONG PHYLLITE + POTASSIC ALT. ZONE. PINKISH TAN				
				- AND GREEN - MAJOR EPIDOTE. AND SERICITE				
				- a FEW MINOR EPIDOTE AND SERICITE STRINGERS.				
51.70				GDR AS AT 3.66.				
				64.80-64.90 BLEACHED, POTASSIC ALT'D ZONE. MED BRN COLOR.				
				66.30-66.45 HIGHLY PROP. ALT. CLAY GOUGE SHEAR AND RUSTY CA VEINLETS.				
				68.17-68.56 NUMEROUS SMALL BLACK STRINGERS				
				72.10-72.24. RUSTY CLAY GOUGE FRACTURE ZONE.				
				82.93-83.40: SHEAR/FRACTURE ZONE. CLAY GOUGE. CRUMBLED AND SHATTERED				
				94.68-96.62 INTENSELY PROP./MOD PHYLLIC ALT'D. NUMEROUS THIN BLACK VEINLETS				
				100.55-100.75 ARGILLIC ALT'D SHEAR ZONE.				
				101.50-102.41 RUSTY FRACTURE ZONE.				
				110.70. CA VEINLET-BARREN				

[redacted] DIAMOND DRILL LOG HOLE No. 87-R4 Page 2 of 7

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
				110.83 - 111.02 MOD-STRONG ANGLE ACTIN BLEACHING VERY EPIDOTE-RICH				
				123.7 HEMATITE RICH CM [redacted] VEINLET				
				123.96 - 177.00 Some slight Potassic alt'n.				
				Shear Zones at 127.55-127.71; 129.[illegible]-129.[illegible]; 130.00, 130.15 Epidote - chlorite alteration				
				130.35 - 130.70 strong Epidote alt'n + some hematite staining + 131.10 - 131.35 orange iron stain				
				133.20 Andesite Xenolith 5cm diameter				
				134.76 - 5cm shear with Hematite + Epidote + Chl alt'n				
				135.00 1cm wide Andesite				
				135.85 - 5cm Andesite Xenolith				
				136.00 - 5cm Andesite Xenolith				
				136.30 1cm wide And Vein				
				140.65 - 140.75 11cm of Strong Potassic alt'n				
				145.45 - 145.65 Strong Epidote + Chl + Potassic alt'n.				
				151.00 - 151.10 - Shear - near a veinlet of And.				
				157.10 - 157.40 Shear Zone with Clay alteration Some Chl + Epi alteration				
				159.60 - 159.90 Potassic Alt'n with Cpy Stringer present (30cm)				
				166.25 - 167.05 Shear Zone, Strong Propylitic alteration Cpy filling in fractures. Epidote veinlets. Iron Mineralization.				

[redacted] DIAMOND DRILL LOG HOLE No. R4 Page 3 of 7

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by			Assays by	Logged by	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
				171.60-172.60 Hematite staining in fractures				
				175.30 Cct filled Shear.				
				177.10 And Xenolith				
5		51.3%	179.0-.63					
				179.60 - Strong Propyllitic Alteration Potassic Altn.				
				181.00 minor in Hbl + mafics.				
				181.10 stringers of Pyrite.				
				182.50-182.75 Strong Potassic Alteration. and Epidote in veins.				
				182.50-183.00 Andesite Xenolith with several Epidote Veinlets. also cct in stringers.				
				183.50-183.60 - Same as ~~cct~~ And. Above. with tr. Py.				
				191.25-191.50 Shear Zone clay Altn				
				191.00 192.30 Phyllic Alteration tr. Py.				
				194.55-196.50 Alternating Gdr + And. numerous cct stringers and veinlets.				
				199.05-199.30 Shear Zone cct veinlets Some Chl+ Epi. Altn.				
				201.25 - 5cm wide And Xenolith with cct veinlets				
				204.00-206.50 Mod. Altn. Epi Chl+ Magnetite present				
				209.80 1cm Cct Vein with slight Chl altn.				
				211.50-212.00 cct filling in Shear 10° to core axis				
				212.70-213.10 Strong Propyllitic Altn tr. Py. Epidote present in veinlets				

AURUM GEOLOGICAL CONSULTANTS INC. DIAMOND DRILL LOG HOLE No. _____ Page 4 of 1

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by			Assays by	Logged by	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
				214.20-214.30 Strong Propyllitic Alt'n Epidote in Vein lets				
				221.70-221.90 Shear Zone				
				221.90-223.70 Strong Propyllitic Alt'n. abund. cct.				
				223.70-234.00 Weak - Prop. Alt'n. numerous Epidote Stringers & veinlets				
				239.00-239.85 Cct + Hematite along fracture				
				240.30-240.50 Weak Phyllic Alt'n 30° to core axis cct veinlets 1% Py. Epi + Chl.				
				241.35- 2cm wide cct Vein				
				242.40- Shear with epidote - Qtz cct filling + 1% Py 80° to core axis				
				243.90- Shear with Qtz-Cct-filling. 30° core axis				
				244.60-85 ... CO3 alteration				
				245.80- 2cm Epidote Vein 40° to core axis				
				245.90 5cm wide Rhy Veinlets				
				249.75 Cct Vein 2cm wide				
				251.00-251.30 Numerous Epidote Stringers				
				259.80 Cct blebs 90° core axis				
				261.30-261.50 Chl. + Clay alteration Shear Zone				
				261.90-262.15 Shear Zone Strong Prop. Alt'n				

[redacted] DIAMOND DRILL LOG HOLE No. 82-84 Page 5 of 7

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by	Assays by	Logged by			

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width				
				262.90 Cct Vein + Violets								
				269.20 Cct + Hematite filling in Shear								
				276.00-276.15 Shear with Qtz Cct filling + numerous Cct Stringers								
				280.95-281.10 Sealed Shear Bx Grds Epi Chl Cct tr. Py.								
				281.35 281.45 Crackle Bx. with Qtz Cct, Epi Chl fillings some Magnetite stringers								
				282.05-282.30 Hanging Wall Shear.								
282.30	285.30			GRANODIORITE crackle Bx with many Cct Stringers + Veinlets also Intercalate to Shear Propylitic Alt. weak Silicification								
		179.0	285.30									
			.73									
285.30	288.82		.66	Mixed GRANODIORITE - RHYOLITE BRECCIA					tr. Py	.32	.005	
				Grds moderate to strong Propyllitic Alt.	9788	285.30	286.82	1.52				
				Rhy - a light tan brown nearly all barren with		936.1	941.1	5'				
				2mm wide Veinlets of Cct. and tr. Sx as stringers. (Py.)								
				More intense Brecciation later in the zone.	9789	286.82	288.45	1.63		.18	.007	
				Some Shearing in the zone 288.05-288.10		941.1	946.4	5.3'				
				Qtz vein // to core axis 1cm wide @ 285.50								
				Fracture Directions at 30° and 45°								
288.45	293.25		.50	RHYOLITE BRECCIA Tan Brown Rhy not strongly Brecciated	9790	288.45	289.97	1.52 5'	946.4-951.4'	.37	.021	
				Many small stringers of Sx. 1-5% minor Py visible minor Gn.	9791	289.97	291.50	1.53 5'	951.4'-956.4'	.69	.029	
				Upper contact 40° to core Axis	9792	291.50	292.65	1.15 3.8	956.4'-960.2'	.53	.031	
293.25	295.90		.55	RHYOLITE BRECCIA Tan Brown Rhy Bx with	9793	292.65	293.25	.60 2.0	960.2'-962.2'	.36	.012	
				up to 5mm Veinlets of Sx - Py visible 1% - tr. Sphal.	9794	293.25	294.57	1.32 4.3	962.2'-966.5'	.54	.013	
					9795	294.57	295.80	1.23 4.0	966.5'-970.5	.21	.022	0.01

AURUM GEOLOGICAL CONSULTANTS INC. DIAMOND DRILL LOG HOLE No. 87-R4 Page 6 of 7

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by			Assays by	Logged by	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t	
295.80	296.45		.85	Qtz Sx Breccia.							
				100% Sx - 2% Asp 1% Gn 5% Py 1% Sph tr. Cpy.	9796	295.80	296.45	0.65	35.52	.284	0.327
				Veinlets upto 4mm wide		970.5'	972.7'	2.2'			
296.45	297.70		.80	RHYOLITE BRECCIA	9797	296.45	297.70	1.25	.68	.085	0.028
				Fragments Upto 4cm in diameter. Some Quartz		972.7	976.8	4.1'			
				inclusions. Qtz Sx Bx (3cm) inclusion at 296.55							
				Cut Alt.							
				20cm Shear at 297.10-297.30							
297.70	298.60		100	MULTILITHIC BRECCIA	9798	297.70	298.60	0.90	.68	.019	
				Rhyolite and Granite Fragments upto 3cm tr Py		976.8	979.7	2.9'			
				in a fine grained Matrix (Dacite) Small Qtz eyes come							
				last 5cm mainly a barren Dacite Contacts 35° to core axis							
298.60	299.75		.70	RHYOLITE BRECCIA	9799	298.60	299.75	1.15	.08	.003	
				RHYOLITE AS MATRIX and fragments many MULTILITHIC		979.7	983.5	3.8'			
				Fragments aswell upto 5cm							
299.75	300.97		.72	RHYOLITE barren few Cpy Stringers	9800	299.75	300.97	1.22	.01	.001	
						983.5'	987.5'	4.0'			
300.97	305.15		.68	MULTILITHIC BRECCIA	6151	300.97	302.50	1.53 5.0'	983.5'-992.5'	.12	.001
				Rhy. + Gdr fragments upto 10cm in length. Carbonate	6152	302.50	303.49	3.30	992.5'-995.8'	.09	.001
				alteration and some slight Silica alt. Calcite veinlets contain	6153	303.09	304.39	2.90	995.8'-998.7'	.28	.009
				Py @ 304.35 305.15 Sx more abundant mixed with	6154	304.39	305.15	0.76	998.7-1001.2'	.67	.031
				Qtz tr Gn and minor Py. disseminated. Py				2.5'			
305.15	306.45		.63	RHYOLITE BRECCIA green tan crackled brx	6155	305.15	306.45	1.30	.04	.001	Notes & Prep
						1001.2	1005.5	4.3'			
306.45	309.50		.61	MULTILITHIC BRECCIA Brown matrix Rhyt Some Qtz	6156	306.45	307.97	1.52 5.0'	1005.5-1010.5'	1.66	.182	0.128
				fragments CO3 Alt.	6157	307.97	309.97	1.34		.16	.003
				First 20 cm about 50% Qtz Sx Bx		1010.5	1014.8	4.3'			
309.51	310.39		.50	5% Py 1% Gn. Other Parts have tr. of disem.							
				Py + Gn.							
				GRANODIORITE	6158	309.31	310.39	1.08	1.45	.037	0.042
				Strong Propylitic Alteration. Shear Zone @ 310.00-310.39		1014.8	1018.4	3.6'			
				5% Py							

AURUM GEOLOGICAL CONSULTANTS INC. DIAMOND DRILL LOG HOLE No. 87-R4 Page 7 of 7

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by			Assays by	Logged by	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t	Native Au Prsc
310.39	311.10		.47	ANDESITE - Strong Propyllitic Alt'n Py 2.5%	6159	310.39	311.10	.71	.42	.056	0.05?
						1018.4	1020.7	2.3'			
311.10	325.52			GRANODIORITE - Moderate - Strong Propyllitic Alt'n tr. Py.	6160	311.10	312.60	1.50	.01	.001	
						1020.7	1025.6	4.9'			
EOH	325.52		.71								

AURUM GEOLOGICAL CONSULTANTS INC. — **DIAMOND DRILL LOG** — HOLE No. 87-R5 (G1A) — Page 1 of 5

Property: Skukum Cr.	NTS 105 D-3	Claim WH	Elevation 1295	Azimuth 331°	Length 883	Dip -76°
Coordinates	Dip Tests		Advance 213.6'	Depth 856.8'	Date Collared July 14, 1987	Date Completed
Purposes To test a Rainbow Ext below 85-13.			Drilled by CARON D.D.		Assays by ACME	Logged by JBR

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	
0	70			CASING					
70	90		.14	RHYODACITE. Rainbow Well fractured through out all Rhyodacite zone. Rusty colour on fracture. Fracture planes at 10°, 45°, 90° to C.A. Also some small Plag. Phenocrysts					
90	110		.33						
110	130		.22						
			.42	115 Rhyodacite is a tan colour has flow banding and is less fractured (a slight rock/breccia) 128' Shear Rhyodacite - Andesite Contact.					
130	150			ANDESITE. green-grey And. with small phenocrysts of Qtz. Plag. 1-2mm in Some slight fracturing with in					
			.46	Pieces filled with Cst. found as blebs. tr Py. Clay + Hematite on fractures. Propyllitic Alt'n throughout. 143-145 3% Py + He. 148-	6304	141.6	145.5	3.9	
150	170			151.0 Shear Zone Rock well fractured and Altered to					on fracture surfaces to 2% Py. 163.6-170
			.63	Clay with hematite staining. 151.0-163.3 tuff in Andesitic with Strong Propyllitic - Weak Phyllic Alt'n also slight silicification Stringers of Calcite common Clay on fractures also some rust +	6305	153.0	158.0	5.0	And with Plag. Horn. Amph. Phenocrysts numerous Cst blebs and veinlets fracture pattern 25|45|90°
170	190								
			.46	Zone of tuff continuous Slight Zone at 182.1-182.5, 184.8-186.5 tr Py.	6306	175	177.4	2.4	
190	210			tuff Zone continuous to 219.0 core well					
			.14	Sheared in zone clays on fractures.					
210	230		.50	Contact at 30° to C.A.					
				At 219 Zone ends And Olive Colour with small white Plag. Phenocryst altered to Cst Strong Prop. Alt'n with clays on fractures					

DIAMOND DRILL LOG

HOLE No. 87-RS Page 2 of —

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	
230	250		110	Continuous And. zone. with Cct fillings on small fractured surfaces. Shear Zone 234-237 and at 244-248. with a fine grained groundmass Cct + Hematite Phenocrysts tr Py.					
250	270		30	Andesite Zone Continuous to 259.5-260.2 Brecciated Zone of a soft tan Volcanic Rock with 5% Py and a dark fine grained groundmass. Quartz in blebs small calcite stringers Andesite Zone at 260.2-					
270	290		54	Andesite through all 20' 289-290. Many more Xenoliths upto 5mm					
			58						
290	310			294 Bleached Brecciated And. to tan colour. 295.8 Slightly coarse grained Andesite in a crackle Breccia dark Green Propyllitic Altn.	6324	294.0	295.0	1.0	
			54	299.0 to 299 Bleached tan And. Brecciated with 5% Py. 299.9 DARK Green Crackled Andesite Propyllitically altered 303.5 Shear In the shear is a small tan And. Alt. And with 1% Py. 303.8-304.2 304.2-310 Dk. green And. cct + Hematite Altn + 1% Py.	6325	298.7	303.7	5.0	
310	330			311.0 Change to lighter green olive colour Andesite. with Cct/Cinlets + small 2mm phenocrysts At 325.0 Brecciated And. with Phyllic to Argyllic -					+ tr Py.
			38	Altn. 325.4-326.5 Shear zone with clay on fractures- 326.5-330 Crackle Bx Propyllitic Altn. Qtz Cct fillings					
330	350			331.1 Andesite is tuffaceous Crackle Bx. Fracture Zone 332.8-333.2. 336.0 tuffaceous And Crackle Bx with rounded glassy pebbles Quartz. Well fractured from					336.0-336.6 Pyrite Stringers 1cm wide upto 2" long. tr Py throughout
			116	339.2-350.0 2" Strong Ep. Altn @ 347.3 348.5-349.0 numerous					Small pebbles as clasts.
350	370			Andesite Bx with Quartz + glass clasts quartz + cct fillings and blebs. Propyllitic Altn. At 355.0 fracturing Altn increases					
			32	clay on fractures. 363.5-365.5 Volcanic Bx fine grained tuffy groundmass with rounded Quartz + glassy clasts. 367.5-368. Rhyolite tan brown crackle Bx v. soft, 10% Py 367.4-367.8 in And Xenolith. 368.8-370.0 Shear Zone Clay alteration of And / Rhy Bx.	6326	365.0	370.0		

DIAMOND DRILL LOG — HOLE No. 87-R5 — Page 3 of —

Interval From	Interval To	Recy %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
370	390			Mod/Rhy Bx large clasts up to 5cm Qtz vein	6327	370	375	
			.51	fill cavs w/10 1% Py. Stream 378-378.5				
				3785 Chert Pebble Conglomerate				
				The clasts are rounded to subrounded clasts range				
390	410			in size from 1cm-5cm with moderate sorting in a				
				dark grey siliceous matrix Chl+Ep. Alt'n can be moderate to Py.	6328	403	408	
			.93	Silicic Alt'n. to 1% Py				
410	430							
			.89					
				426.7-429.0 1% Py.				
430	450							
			.87					
450	470		.80					
470	490		.76					
				grey, Fine grained, siliceous zone 1.3' few Qtz pebbles				
				3cm in size, tr Py.				
490	510		.78					
			.91					
510	530							
			.92					
				And. Olive green with small white phenocrysts of Qtz eyes. 548b				
530	550							
			89					

DIAMOND DRILL LOG HOLE No. 87-R5 Page 4 of —

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
550	570			Andesite continuous to 553.0 2" Rhyolite well fractured, Andesite as above 566.4 566.6 Fracture Zone with on fracture ~ 10° to C.A. 3mm Cst vein.						
570	590		.83	Crackled (lightly) Andesite with Cst fillings 581.8-2 cm Xenoliths of Quartz Fpy Agglomerate. Andesite becomes a lighter green with more Stwlts or blebs of Cst - Veinlet at 587.0 588.1 @ QUARTZ-						
590	610		.72	Chert Pebble Conglomerate (Strongly silicified) 604.0 Chill margin contact with RHYOLITE BRECCIA						
610	630	80	.13	first 2' along contain about 50% Chert Conglomerate clasts. Rhyolite Clasts making most of the Bx (70%) Tan to grey in colour. Fine grained black matrix also with Cst-Qtz fillings. 618-623 Shear Zone in Rhyolite Bx with clay altn. tr-1% Py	6390	618	623		.05	.001
630	650		.51	Continues to 633.6 to And And Crackle Bx well fractured fractures 10°, 40° to Core. Epidote and Chl altn in veinlets and on fractures Qtz Cst above closer. Bleaching of And. from 641.0-641.2 (Contact) tr-2%						
650	670		.37	INTENSELY crackled and Epidote Cst Veinlets. 651.6-652.8 ANDESITE Rhyolite Bx. [illegible] with Rhyolite 3-5% clasts. Minor Qtz Veins 5° to C.A. from 651.8-652.5 ANDESITE CRACKLE Bx 653.8-655.2 with Cst fillings Py 1%, 5% in altered 655.7-660.0 RHYOLITE- BRECCIA 10% And. Strong Epidote Altn. strong green colour 658.7 1 inch calcite blebs, cst fillings in fractures. tr-5% Py. 660-667.9 And (crackle Bx) Prop. Altn disseminated Py up to 1% Shear 661.6-662.6, 667.9-672.1	6391	658	663		.04	.001
670	690		.98	ANDESITE with epidote Altn in a crackle Breccia the last half of Tr. zone is moderately-strongly silicified also with Cst. 672.1 Porph. And Feld. Phenocrysts strongly silicified from 672.1-673.0 Grey matrix - And. 680.7-689.7 Rhy - And Bx. 4 stages of Brecciation.	6392	680.3	685.3		.01	.001
690	710			RHYOLITE green & Tan predominately tan and black colour (clasts) Cst Veining with offsets. Hematite staining on fractures & with calcite veins running 0° to C.A. 699.1-703.0 Monzodiorite with grey matrix slightly Crackle	6393	685.3	690.3		.03	.001
					6394	690.3	695.3		.01	.001
					6395	695.3	700.3		.01	.001

DIAMOND DRILL LOG

HOLE No. 87-R5 Page 5 of 5

Interval From	Interval To	Recy %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width		
			67	703.6 Rhyolite slightly Crackle Breccia with a light tan colour 709.5 And as above - 710.0	6396	710	9738		.03	.001
710	730			Rhy Breccia tan colour small clasts giving way 720.6 to a Qtz Cut Rhy-Bx with stringers of sulfide. 721.5 Rhy crackle Bx. 720.5 Microdiorite dark grey. 724.3 Rhyolite - light white colour						
730	750		67	730.6 - 733.4 And as above \ 733.4 - 739.6 Rhyolite as above \ 739.6 - 763.6 Microdiorite						
750	770		57	bleached Microdiorite 752.3-753.7 763.6 Brecciated Microdiorite with light Potassic Altn. 764.7 Microdiorite Moderate Propyllitic Altn. 768.8 Rhyolite slightly Brecciated. - 771.8						
770	790		47	771.8 Microdiorite with moderate to strong Propyllitic Altn Qtz-Cut blebs in small gash fractures. Shear at 788.0 - 796.0						
790	810		55	791.3 Bleached to white Microdiorite has same texture and slightly fractured. this section is homogenous silicic Altn.						
810	830		64	825.2 end of bleached zone still grey Microdiorite						
830	850		68	839.8 Rhyolite Bx tan-yellow 843.0 Rhyolite Crackle Bx						
850	870		74							
870	885 EOH		89	Microdiorite - 870 grey weak altn. propyllitic. 871 · Qtz Cut Vein ¼" 30° to C.A. 876.3 Flow banded Rhyolite with Epidote Altn. Slight Brecciated last 2' contain Xenoliths of Microdiorite.						

AURUM GEOLOGICAL CONSULTANTS INC. — **DIAMOND DRILL LOG** — HOLE No. 87-R6 — Page 1 of 4

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
SKUKUM CREEK	105 D/3	WH		312°	436'	-54°

Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed
	NONE TAKEN	256.3'	352.7'	JULY 22/87	JULY 25

Purposes: TO TEST 1236 m. LEVEL BENEATH HOLE # 85-9 IN RAINBOW ZONE. — Drilled by: CARON DIAMOND DRILLING — Assays by: ACME ANALYTICAL — Logged by: R.J.R

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0.0	20.0			NO CORE 0.0 - 21.0 CASING IN OVERBURDEN.				
				GLACIAL BOULDERS AND SAND OVER ROCK WEATHERED IN PLACE.				
20.0	40.0			21.0 - 144.2: C.G. GRANODIORITE.				
				BLEACHED PALE GRN-GRY TO DARK GRN-GRY.				
				MOSTLY MOD - STRONG PROPYLITIC ALTERATION. NARROW ZONES OF POTASSIC ALT.				
				ABUNDANT EP + CA VEINS. ABUNDANT HEMATITE/CA VEINS.				
				MINOR ARG. ALT. IN FRACTS. SOME FRACTS. CLAY-COATED.				
40.0	60.0			BROKEN + BLOCKY TO 61.3'. V. WEAK CRACKLE.				
				42.0: 4 cm BLACK BAND IN GDR. ABUNDANT CA + SMALL FRACTS				
				FRACTURES 45-65° TO C/A				
60.0	80.0			61.3 - 66.8 ABUNDANT EP. STRINGERS + FRACT FILLING.				
				& STRONG ALT'N HALOS AROUND STRINGERS.				
				STRONG PHYLLIC + WEAK POTASSIC				
80.0	100.0			86.0 - 99.0 VERY ABUNDANT SMALL FRACTS FILLED WITH EPIDOTE AND				
				NARROW HALOS OF POTASSIC ALT. AROUND THEM.				
100.0	120.0			101.0 1 cm HEMATITE VEIN LET: VERY RED + XENOS OF GRN. GDR + ALT. FSPAR.				
				104.0 - 111.5 STRONG PROP/WEAK PHYLLIC ALT. V. ABUND HEM.				
				REDDISH + YELLOWISH OXIDE COATINGS FROM HERE DOWN.				
120.0	140.0			MORE LOW ANGLE FRACTURES ALMOST PARALLEL TO C/A.				
				130. 1 cm CA STRINGER @ 40° TO C/A.				

DIAMOND DRILL LOG

HOLE No. 87-R6 Page 2 of 4

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
140.0	160.0			CONTACT = ANDESITE VERY FRACTURED				
				144.2-150.2 ANDESITE DYKE: DK GRN-BLK. ABUNDANT CA. RUSTY FRACTS @ 60° TO CA				
				150.2-362.1: C.G GRANODIORITE. CONTACT VISIBLY INTRUSIVE.				
				AS ABOVE BUT MORE STRONGLY ALTERED COLOUR BLEACHED				
				CONTAINS AS BEFORE + RED+ YELLOW OXIDE COATINGS ON FRACTS.				
160.0	180.0			FRACTS @ 75° & 0° TO C/A. MORE CRACKLED/AUTO BXVD.				
				XTAL STRUCTURE LESS VISIBLE - MORE BLEACHED.				
				WEAK TO MOD. PHYLLIC ALT'N + SOME DK GRN PROP.				
				ZONES.				
180.0	200.0			MINOR K-ALT'N. MODERATE AUTO/BXN.				
				ABUNDANT EPIDOTE + @ CHLORITE & SERICITE. MINOR CA.				
200.0	220.0			200-215. STRONG PHYLLIC ALTN				
				215-230 MOD-STRONG PHYLLIC ALTERATION.				
				ABUNDANT CL/EP WEAK TO MOD AUTO/BXN.				
220.0	240.0			220-240 STRONG PHYLLIC ALT'N. XTAL BOUNDARIES				
				V. HAZEY AND INDISTINCT.				
			N	V. MINOR POTASSIC BANDS ALONG FRACTS.				
240.0	260.0			246: 5% EP IN SMALL STRINGERS OVER 10 cm				
				247-252 STRONG SILICIFICATION BEFORE EP FLOODING, V. LITTLE PY.				
				253 1MM CA STRINGER + 80% PY. MINOR. 15° TO C/A				
260.0	280.0			—MORE BRITTLE & BROKEN IN THIS AREA. (235-268)				
				265.8. RED HEMATITE-FILLED SHEAR PARALLEL TO C/A.				
				CA SHEAR @ 30° X-CUTTING.				
				279: 1MM EP STRINGER + 2 cm ALT'N HALO.				
280.0	300.0			285': 2' FRACT. ZONE + CLAYEY GOUGE OVERTS. ABUNDANT CA/HC.				

DIAMOND DRILL LOG

HOLE No. 87-R6 Page 3 of 4

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag ozs	Au ozs	
				STRONGLY SCHISTOSED AND ALTERED. MINOR ROTATION.							
				STRONG ALT'N AROUND EP. STRINGERS							
				291: CA STRINGERS AND SMALL SHEAR ± CA + V.DED HEMATITE STAINING							
				298.4 ABUNDANT CA + FRACTURES ± CA + HE FOR 1 FT.							
300.0	320.0			302.5 V. DK GRN INT. ABUNDANT EP + CLY SZ. BLACK FLOOD ZONE.							
				303.5 2cm EP FLOODED ZONE							
				VERY STRONG ALTERATION FOR REMAINDER OF UNIT							
				317: RED FELDSPARS - K-ALT'N.							
				319. CLAYEY SHEAR ± HEMATITE STAINING V. PRO GOUGE.							
320.0	340.0			321: ABUNDANT CA STRINGERS, CLAYEY SHEAR, THEN ABUND. HE STRINGERS							
				FRACTS AT 45 + 65° TO C/A ± A FEW SHEARS PARALLEL.							
				235: 10cm CA STRINGER ± 30% PY.							
				235.6 1M CLAYEY, CHLORITIC FRACTURE ZONE.							
				338: 1FT FRACTURE SET @ 20° TO C/A							
340.0	360.0			343: 1FT CLAYEY, CALCITIC FRACT ZONE							
				ABUNDANT HEMATITE STAIN ON FRACT SURFACES							
				SLIGHTLY MORE BXD ± DEPTH							
360.0	370.0			360: 1-FT CLAYEY SHEAR ZONE. VERY BXD + ALT'D.							
				362.1 - 371.0: BRECCIATED, SHEARED, FRACTURED, ALTERED GDR.							
				ABUNDANT BLACK-BANDED, CLAY-FILLED SHEARS	6402	366.0	371.0	5.0	.13	.002	
				STRONG PHYLLIC AND ARGILLIC ALTERATION		111.56	113.08				0.002, 6.26
				BRECCIATED ± CHLORITE, EP. + QZ MATRIX. <1% PY IN MATRIX	6403	371.0	372.1	1.1	.78	.009	
370.0	390.0			371.0 - 372.1: MULTILITHOLOGIC AX. VEG BLACK MATRIX ± CLASTS OF GDR FRGT.			113.42				
				372.1 - 376.7: EXTREMELY PHYLLIC + ARGILLIC ALT'D GRANODIORITE. PALE	6404	372.1	376.7	4.6	.27	.001	
				GREEN, ABUNDANT CLAY. FRACTURED + BRECCIATED - SHARP SHEAR CONT. TOP + BASE			114.82				
				376.7 - 381.0: SHEAR ZONE. BANDS OF SHEARED CLAYEY GDR + ML BX	6405	376.7	381.0	4.3	1.63	.019	0.013
				BANDS @ 40° TO C/A. ML BX @ 377.7 + 379.3. GRAD. CNTC. @ BASE.			116.43				
390.0	390.0			381.0 - 385.2: QUARTZ SULFIDE BX IN SHEARED, ALT. GDR.	6406*	381.0	385.2	4.2	25.85	.265	0.238
				30% QZ 20% SX, MOSTLY PY + AS. MINOR GL + SL. GRAD CNTC @ BASE		116.43	117.41	1.2Bm	GB 2.6	2.95	
				385.2 - 389.5: EXTREMELY SHEARED + ALT'D GDR ± BANDS OF QSBX.	6407	385.2	389.5	4.3	1.93	.052	0.051
				ZONE OF ML BX @ 387.9 - 388.6 ± SHARP CNTCS. INTRUSIVE @ CONT. + BASE			118.72				
				389.5 - 394.4: RHYOLITE: CLEAN, FG. FEW QZ EYES. MOD. ALTD BXXD.	6408	389.5	393.2	3.7	.78	.011	0.010
390.0	400.0			* MINOR - MOD. FRACT FILLING BXSX. (<1%) FRACTS @ ALL ANGLES.			119.85				
				MORE SX TO END OF UNIT. 12 CM BAND OF QSBX @ END	6409	393.2	394.4	1.2	7.97	.093	0.106
				394.4 - 395.3: BANDED, SHEARED + BXXD ZONE: ML BX + BAND GDR			120.21				

Notes: HW ↓ ; Not a Prf

DIAMOND DRILL LOG

HOLE No. 87-R6 Page 4 of 4

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag OZ/T	Au OZ/T	
				IN SHEAR BANDS. BNDS @ 45° N 50% MLBX.	6410	394.1	395.1	0.9	4.93	.310	0.259
				395.3 397.4: BANDED, SHEARED GBR Banded @ 50° TO C/A.	6411	395.3	397.4	2.1	.16	.006	0.010
400.0	410.0			397.4-399.6: BANDED MLBX. BNDS @ 65° TO CA. MINOR QSBX IN BANDS	6412	397.4	399.6	2.2	2.17	.250	0.197
				399.6 - 428.0: GRANODIORITE, SHEARED, ALT'D + BANDS OF QSBX @	6413	399.6	404.6		.11	.007	
				TOP OF UNIT, DECREASING AND STOPPING @ DEPTH.	6414	404.6	409.6		.01	.002	
				LESS SHEARED + ALT'D AT DEPTH.							
				CA STRINGERS DECREASING @ DEPTH. MINOR AUTO-BX							
410.0	420.0										
				RUSTY CRUMBLED ZONE @ 413 - 414. MINOR CLAY							
		415	420	416: 1 Ft CA + BLACK BANDS @ 45° TO C/A + MINOR PY.							
		60%		MISLATCH, CORE LOST + GROUND. PIECE OF ANDESITE (BLACK) 7cm LONG							
420.0	430.0	420	425	421: 2mm. YELLOW CA VEIN @ 15° TO C/A.							
		75%									
				427: 1 Ft. RUSTY FRACTURE ZONE, MINOR CLAY. CA/HG BAND @ END							
				428.0 - 430.1 ANDESITE DYKE BLK TO GRN-BLK. ABUND. CL, CA. TR PY. CORE SHEARED @ 45° TO C/A							
430.0	440.0			430.1 - 436 C.G. GRANODIORITE. ABUNDANT CL/CA/EP/HG.							
				AND @ XENO @ 435.0. TR PY. MINOR AUTO BXXN.							
				FRACTS @ 45°							
				436 END OF HOLE 87-R6.							
440.0											
				18.0					0.125	7.47	

FW (399.6')

DIAMOND DRILL LOG

HOLE No. 87R7- Page 1 of 3

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
SKUKUM CREEK	105 D 3	WH		318°	538.0'	-64°

Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed
		235.85'	483.55'	JULY 25	JULY 28

Purposes	Drilled by	Assays by	Logged by
TO TEST RAINBOW ZONE AT 1' n level	CARON D.D.	ACME	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
0	20			0-13' Casing						
			.05							
20	40			GRANODIORITE: Green - moderate to Strong Propyllitic Alt'n with zones of weak silicification Boxwork & Blebs of Hematite Alteration. Predominate fracture angle 70°.						
			.42	Weak Brec - Qtz Vein is very common Usually Epidote						
				36' Epidote Vein 6mm wide 38-38.7 Brecciated						
40	60			40' Alteration is Strong Propyllitic with						
				small zones of weak Potassic Stockwork Quartz						
			.34	Vein-Veinlets are usually Epidote						
60	80									
				65.7 Fault Fracture ?						
			.59							
80	100			Zone of Weak Propyllitic Alt'n 80.4-81.1						
			.69	87.4-87.7 Weak Potassic Alt'n throughout 88.5-90.6						
				98.0 Strong Propyllitic Alt'n Epidote Veinlets very frequent						
100	120		.49	some of the zone weakly Potassic Alt'd.						
				109.5 Weak Propyllitic Alt'n with Patches of Potassic						
				Alt'n.						
120	140		.50							
				129' Moderate-Strong Propyllitic Alt'n Epidotic						GS @ 129'
				fractures rock Slightly crackled.						
140	160		.45	141.0 Qtz-Cst Vein 30° to C.A. 5mm wide						
				144.1 Strong-Propyllitic-Weak Phyllic Alt'n Epidote						
				fillings in cracks. Hematite on fractures. 149.0 Potassic						
			.46	alteration is also in the zone. 156.4-156.75 Strong Potassic Alt'n.						
160	180			163.2-165.3 ANDESITE BRECCIA-Propyllitically altered with						Andesite contact @ 163.2 is a C" shear
				Qtz-Cst & Hematite as fillings. 165' Qtz-Cst Vein		163	165	2.0	.25	.026

DIAMOND DRILL LOG

HOLE No. 87-87 Page 2 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
			.36	163-168.0 GRANODIORITE, Phyllic Alt'n. Crackle Breccia, 166 Pervasively Altered Gdr (Strong) with some slight brecciation and small zones of Potassic Alt'n (extreme) 185.0 - Weak to Moderate Propyllitic Alt'n. Main fracture pattern at 45 + 70°.				
180	200							
			.47					
200	220			199.3-202.7 Zone of Strong propyllitic Alt'n with Epidote. 202.7 Moderate - Weak Propyllitic Alt'n. 206 Crackle brecciation begins. 217 Strong Propyllitic with bands of Potassic alt'n-weak-moderate. Epidote veinlets are frequent in the bands of Potassic Alt'n. 10°-20° to C.A.				
			.60					
220	240		.63					
				234.5 Strong Propyllitic Alt'n continues Epidote veins less frequent and at 70-80° to C.A. the Gdr is				
240	260		.60	altered to a near black colour with white-green plag. 267.2 Fractured Zone 1' Long.				
260	280	90%	.96					
			.43					
280	300							
				285.5-288.2 fine grained Gdr, slight crackled Breccia strong Propyllitic alt'n with Epidote veinlets and blebs of qtz. 287-288. Moderate. Strong Propyllitic Alt'n in				
			.65					
300	320			Coarse grained Gdr. still slight crackle. With Epidote. some cal as fillings.				
			.38					
320	340							
			.44					
340	360							
			.36					

DIAMOND DRILL LOG

HOLE No. 87R7 — Page 3 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
380	400		.22	GRANODIORITE						
				Strong Propyllitic - Weak Phyllic Alt'n mafics nearly						
			.46	completely destroyed. Cst in places as fracture fillings.						
400	420			Fractures mainly 45° to Core Axis. Clay on fractured Rocks.						
				404.5 - 410.5 ± Pyrite Stringers and patches 4% Py.						
			.18	Crackle Bx 414.5 - 416.0						
				tr. Py throughout						
420	440			421 - ½" Cst Vein at 45° to C.A. 420 Strong Propyllitic						
				Alt'n 429.0 - 429.6 Black stringers - magnetite + Cst stringers						
		90	.21	437.0 ± Clay Gouge						
				437.6 Cst vein'd 45° to C.A. with minor Gn + Py						
440	460			Mod Phyllic Alt'n - moderate to strong 439.0 - 453.6						
				Dark green bleaching. Crackle Breccia 451.7 2mm Epidote						
		85	.37	vein 85° to C.A. 451.7 - 452.7 Cst blebs + Alt'n 453.6						
				Phyllic-Argyllic. Numerous black stringers as fillings in						
460	480			cracks. 460.7 GRANODIORITE BRECCIA dark matrix with						
			.51	mainly Phyllically Alt'd. Gdr clast - 462 - GRANODIORITE	6416	468	473	5.0	.01	.001
				Moderate to Strong Phyllic Alt'n. Many Epidote Veins + Alt'n	6417	473	478	5.0	.01	.001 {0.001, 0.02/3.5
480	500			479.5 - 480.5 Very Altered ANDESITE dyke - Phyllic Alt'n.	6418	478	479	1.0	.08	.006
				480.5 - Strong to Extreme Phyllic Alteration, rock bleached	6419	479	480	1.0	1.12	.076 480'
		90	.65	green-silicified Epidote veinlets + stringers throughout.	6420	480	481	1.0	.59	.008
				Shear Zones 480.0 - 481.1, 486.2 - 486.6, 496.0 - 496.9	6421	481	486	5.0	.63	.004 {0.005, 1.00/3
				496.0 RHYOLITE - BRECCIATED LIGHT TAN-BROWN Very	6422	486	491	5.0	1.45	.005
				Altered. 1% Py.	6423	491	496	5.0	.66	.031 {0.030, 0.44/2
				499.3 MULTILITHIC BRECCIA - Phyllically Altered Gdr + Rhy Agt	6424	496	499.3	3.3	.12	.029
500	520	97	.63	Clasts, varied - Py Matrix Py + c 1% - 502.0 - 503.0 Alt'n Py	6425	499.3	502.0	2.7	1.55	.061
				as above Flow banded 503.0 GRANODIORITE STRONG PHYLLIC	6426	502	507.0	5.0	.10	.002 1 507
				EXTREME PHYLLIC ALTN. FLOW BANDS OF ALTN - CREAM/BROWN COLOUR					RHYODACITE CONTACT -	CONTACT
				@ 15° to C.A. 507.0 RHYOLITE - RHYODACITE ALTERNATING dark					NOT FAULTED	
520	540		.71	and light bands of Rhyolite + Rhyodacite 509.3 RHYODACITE						
				TAN BROWN with 2mm black Phenocrysts - 516.3 RHYODACITE						
			.68	DARK RUST COLOUR WITH 1mm - 5mm Plag Phenocrysts - 538.0						
				538 - EOH						

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling: TO FILL IN INFORMATION BTWN DDH 87-R1 + 87-D-2.

Explanation of Results:

LEGEND

PROJECT	SKUKUM CREEK	HOLE No.	87-R8
COORDINATE N.	71202.65	DEPTH	513'
E.	78121.72	AZIMUTH	298
ELEVATION	1331.0	INCLINATION	-58
DATE STARTED	JULY 29, 1987	DRILLED BY	CARSON DIAMOND DRILLING
COMPLETED	JULY 30, 1987	ASSAYED BY	ACME ANALYTICAL LABS
HOLE SURVEY		LOGGED BY	V. TILLOTSON/BERRY

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE AZIMUTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
126					CASING								
1					GRANODIORITE - green-grey with Moderate-strong propyllitic Altn. (Chl+Epi) - Small Bands of K-Altn upto 6" are common.			10					
159			100	0	26.0-33.0 Mal+ MnO staining on fractures.			20					
					Weak Silicic Altn - rock bleached to a light green 29.6-30.0 33.1-33.5.			30					
2													
405			100	.17	Aplite vein 65° to C.A. 1cm wide. Core altd to a dark grey. texture barely visible. Epi+Cct in fracture fillings. 401-58.2			40					
					44.2-44.5 Bleached - Strong Silicic Altn.								
3					60.2 Weak Phyllic Altn. (Epi+Ser) Altn. rock well cracked.			50					
338			95	.115									
					54.2- throughout box weak-moderate propyllitic Altn Chl, mafics- some Epi. Epi. frequent as crack fillings.			60					
4					64.2-65.2 patches. of dark altn. as above.								
509			100	.58				70					
					Weak-Moderate Propyllitic Altn.								
					72.0-74.9 Magnetite veinlets running 0° to C.A. <1mm wide			80					
5					Epi as fillings in cracks + along fractures.								
816.5			100	.38	86.0 Altn intensifies more Epi core bleached green.			90					
					Strong propyllitic Weak Phyllic Epi Sericite bleached green. 88.7-89.2 Weak Potassic Altn. with Strong Propyl/Altc. Altn. - 20								
6								100					
1026			100	.50									
					Strong Propyllitic Altn (Chl+Epi) Magnetite Altn			110					
7					113.9-114.6 Cct-Cct+Hem Veinlets cut core @ 80° <2mm wide 114-118								
1193			100	.54				120					

OMNI RESOURCES INC. PROJECT DIAMOND DRILL HOLE No. 87RB Sheet 7 of 4

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION
8					Strong - Mod. Propyllitic Alth (Chl, Epi) Cct+Epi as fracture fillings.	
1967			95	.49	fracture	
					Mod-Strong Propyllitic Alth (Chl+Epi)	
9					Abundant Epi fracture direction 70° to C.A. and 0°.	
1986			95	.58		
					155.1-156.1 Fracture Zone.	
10					158.0 Clayey Shear 0° to CA 158.2-165.3 Potassic Alth. (Weak)	
1786			100	.54	Plags turn to orange.	
					170.1 ANDESITE cut 45° to C.A. dark green. Epi veinlets	
					172.3-173.0 Shear	
11					180.3 contact 60° with Med-Crs gr. GRANODIORITE	
1880			95	.32	Mod. propyllitic Alth.	
					Moderate-Strong Propyllitic Alth.	
12					198.4 Bleb of Cct about 1cm with Py around the outside	tr. Py.
					201.0± Slight Potassic Alth of Plags.	
2061			100	.67	Potassic Alth continues to 207.2 Weak-Mod Propyllitic Alth. throughout 216.1-218.5.	
13						
2237			95	.44	222.6-223.0 Hem on fractures.	
					Mod-Strong Propyllitic Alth. Epi veinlets common. at 0°+50° to C.A.	
14					232.0 Fractured zone	
2440			95	.27	235.0 alth - bleaches core to a dark green ground mass with Qtz eyes. Epi Alth. + in veinlets.	
					Zone as above.	
15						tr Py
2584			95	.32		
					Zone ends at 269.0	
					Fracture zone 263.9-265.2.	
					Fracture Zone at 268.6-269.0	

GRAPHIC LOG

FT.

SAMPLE: Sample No. | INTERVAL | CORE LENGTH

ANALYTICAL: O.P.T. Au | O.P.T. Ag

DIAMOND DRILL LOG

HOLE No. 87-RB Page 13 of 42

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
270		90	.31	270						
				280 Blocky Fracture 0° to Core axis 283.0-287.1						
280				Hem. Cl + Epi Alt'n. Mod-Strong Prop/Vitic Alt'n continues to 409.0						
		95	.30	290						
		100	.50	300 2990 Healed shear with .4cm Hem Band at 60°						
				Hematite + clay on Fractures 307.8-308.0 Argill.-Clay Alt'n. with cct veinlets 2-3mm						
		100	.72	314.1 cct veinlet 30°to C.A.						
				320 Clayey Shear 45°to CA.						
				322.0-322.5 Cct in Slightly Brecciated Calc						
				Hematite on Fractures						
		100	.32	Fracture direction at 10°+60°						
				340 340.4-344.1 Brecciated Calc with cct veining 341.5-341.8 Qtz vein with 30% Sc						
				Mostly Mod 35% Sc-45% Ser Alt 35% Cl-Ep Alt 30°to C.A.						
		95	.27	350.6-351.2 Shear with Cct veining						
				355.2-355.5 Fracture zone.						
				360 360-360 Shear zone						
		100	.60	369.3-371.2 Brecciated Calc with CB as matrix+fillings.						
				380 Fracture at 0° +/- C.A. Hem. + Cct on fractures.						
		100	.82							
				Fracture at 0° with Cct + Hem along Fracture.						
				400						
		100	.43	Fracture Zone 402.1-403.6						
				408 scale 1"=10'+						
	(5.0)									
408	413	100	.45	ALC GRADATIONAL CNT						
				413-418 INT ALT GRANODIORITE (FRAGILE ZX						
	(5.0)	100		Greenish-Tan "Bleached" ARGILL & PROP. grades with						
413	418		.47	Cuprous ppt. Cct in Fe2O3, QTZ + Calc vns Shows Stained	6486	413.0	418.0	5.0	.01	.001

DIAMOND DRILL LOG

HOLE No. 87-R8 Page 1 of 1

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag ozt	Au ozt
418	423 (5.0)	100	.98	GRANODIORITE AS AT 416. ALTERATION INT. SHEARS	6487	418.0	423.0	5.0	.02	.001
			.97	AS STRENGTHEN IS APPROACHED. 1-3% diss Py	6488	423.0	425.5	2.5	1.64	.001
	(5.0)			Minimum VITS of Py & DARK MINERAL T.S. 2%						
423	428	100	.67	426 (2') STRONG SHEARING @ 20° INT BLEACHING	6489	425.5	428.0	2.5	.31	.001 Native Au?
	(4.1)	94		430 ANGLE 20° SHEAR 0 CNT	6490	428.0	430.0	2.0	.13	.001
428	433		.51	(3.9') STRONGLY MIN QTZ/SULFIDE BX. 40% or more stages of Bx Py 5-7% Asp 1% TR Gn, Sph, as disse. clots, vlts T.S. 7-10% Zone is Sheared @ 20°-30°, Pol @ 70°	6491	430.0 (431.0 lost)	433.9	3.9	N.P.	11.75 .213 .204
				433.9 → 6" of Rhy-buff Brec. Bx similar 40° intermixed CNT						
	(4.1)	94	.30	(7.6') MULTI L.ITE BX (DIATREME?/FRAGLE DIKE?) Frags are sub rounded Rhy, GD., f Py/Silic 4mm-8cm, Dark Grey matrix, wk silicified matrix. Zone is Sheared @ 40° w/ Grade, Chl/Hematite & Py. [Bx wash] Bx Core (1m Run 94%) PY 1-2% in matrix & Diss in Frags T.S. 5-7% FRACTURED 428.8-441.5 MULTI-STAGE BX	6492	433.9	438.8	4.9	N.P.	7.09 .179 0.214
433	438									
	(4.9)				6493	438.8	441.5	2.7	N.P.	3.17 .131 0.122
438	443	100	.53	441.5 INT ALT GRANODIORITE OR MINOR DIKE. Apple Green (2.2') 443.7 Feldspar porphyritic Rhyolite dike, 30° to CA, 20° to CORE, IRR CONTACTS OR VITS, TS=NIL (DYR SAYS 30°)	6494	441.5	443.7	2.0	N.P.	.05 .002 .001
	(5.1)			(2.0') WHITE RHYOLITE BX, CUT BY Q/S/BX - Auto Bx comp CORE 443.7 2" Zone of QTZ, Py, Gn, Asp VNLTS. T.S. 5-7% [30° INT CNT]	6495	443.7	445.7	2.0	N.P.	1.56 .035 .0.033
443	448	100	.60	(1.9') SEE MIN. QTZ/SULF/BX BX - 10% Py, 1% Asp, TR Gn (2) Sph 445.6 QTZ VNS, 30° to CA - Py-Gn Rich Frags TS. 1-3% [30° INT CNT]	6496	445.7	447.6	1.9	N.P.	10.04 .135 0.143
	(4.8)	96	.67	(4.6') BUFF GREEN RHYOLITE CRACKLE BX cut by Q/S/CARB VITS 3 Py, Gn DARK Angular VITS 45° mm T.S. 2%	6497	447.6	452.2	4.6	N.P.	1.16 .015 0.025
448	453			452.2 INT CNT ↑ 50°					N.P.	
				(3.8') STR MIN QTZ/SULF BX SECTION OF Bx, CRUMBLY IRREGULAR 452.2-453 10% Py, 3% Asp / 1% Gn 453.2-456 5% Py VBDN, 20% RHY FRAGS [FELT CNT] T.S. 5-7%	6498	452.2	456.0	3.8		11.86 .151 0.117
	(5.0)	100	.47	456.0						
453	458			(3.2') Multi L. BX (DIATREME?) Frags subrounded 30% Rhy, 5% Q/S/B Py TR Gn DIPT T.S. 1-3%	6499	456.0	459.2	3.2'	N.P.	.33 .008 0.010
	(5.0)	100	.73	459.2 - 460.5 (1.3') Q/S/BX 460.5-461 (0.5') Multi L. BX as min T.S. 3-5% CA						.022
458	463			461.0 FAULT CNT @ 40° 2" GOUGE 4" Q/S/BX @ 463	6500	459.2	462.2 (460.88)	3.0'	1.31	.123 ON NT
				(5.3') NVB ANDESITE / MULTI BX 1% INTENSE 10 down Bleaching/Alt DISS PY 3-5%						
	(5.2)	100	.50	466.2 CNT BRN Q/S/PY VITS @ 35°, SMP CNT @ 35°	6501	462.2	466.3	4.1	.17	.026
463	468			INT ALT GRANODIORITE CRACKLE BX	6502	466.3	468.0	2.0	.36	.050
	(4.8)	100		"Bleached Pink" Salicified Bx. cut by Q/S/PY/CHLB	6503	468.0	470.5	2.5	.11	.026
468	473		.48	vlts Reheated, minor Fel & SILKs T.S. 1-3% 1-5% Py as diss & VNLTS	6504	470.5	473.0	2.5	.07	.001
	(5.0)	100	.51	476 GRADATIONAL CHANGE ALT DECREASES	6505	473.0	476.0	3.0	.11	.004
473	478			479 Moderate Propylitic Alth with SILKs 10° to CA Scale change (1"=20')						
				4843. Stronger Alth, 10 matches Plugs; dark green waxy small black stringers	6506	4843	486.7	2.4	1% Py + minor Gn.	
	490		.78	ends at 486.7. Epi, Chl, Clay Alth also in vts slight crackle to core.						
	498									
				4992 Dio. Mons with Chl + Epi Alth Plugs are pale green						
			.44	505.0 Aplite Vein ½" wide 20° to CA						
	518		EOH	Strong Chl + Epidote Alth						
	513									

15' Aplite

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling: TO TEST RAINBOW ZONE BETWEEN D1 + D2

Explanation of Results:

LEGEND

PROJECT	SKUKUM CREEK	HOLE No.	87-89
COORDINATE N.		DEPTH	643.0'
E.		AZIMUTH	335° 335°
ELEVATION	1354	INCLINATION	-68° -72°
DATE STARTED	AUGUST 1, 1987	DRILLED BY	CARON DIAMOND DRILLING
COMPLETED	AUGUST 4, 1987	ASSAYED BY	ASME ANALYTICAL LABS
HOLE SURVEY		LOGGED BY	R.J. ROBINSON

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag
					CASING								
10			95	.14	GRANODIORITE/GREY COLOUR WEAK PROPYLLITIC ALTN MAFICS - ALTD TO CHL PLUS VLITLE ALTN SMALL ZONES OF STRONGER ALTN, POTASSIC & PHYLLIC			10					
1					22.1 + 22.6 1cm banded Altn Plags bleached white + Epidote mutes Chl with 30°+20° to core axis								
24			95	.14	21.6-27.2 Potassic Altn in Cor with Med gr QUARTZ MONZONITE + Aplite dykes Chl+Ep. Altn to 30.5			20					
					Increase in Chl+Ep. Altn Plags altered to pale green.								
2					36.1 Porph Aplite dyke 1" wide 45° to Cot			30					
					32.5 - 40.5 Strong Propyllitic - Moderate Phyllic Ep-Sericite+Chl Altn. 40.5-46.7 Strong Phyllic Altn. light green Ser+Qtz.								
464			100	.42				40					
					467-472 Zone of Epidote Altn. Epidote Veinlets common								
3								50					
530			100	.55	558-605 Chl. Ep+K Altn Plag altered to an orange peach colour. Moderate Propyllitic Altn.			60					
					Weak Potassic Altn. - Plags to Pink colour with Epidote Veinlets. to 670. Ep+Chl Veinlets at 45° to CA								
4					724-750 Altered to a black matrix in many places Chl+Ep+Ser Altn.			70					
791			100	.49	Strong Propyllitic Ep+Chl Altn. Plags a light green			80					
					Dark Altn zone continues to 821.0								
5					Near Fresh Cor with small zones of Ep+Chl altn also a few K Altn zones with Epidote veinlets in the core 891 Clayey Shear 2°. 30° to CA			90					
960			100	.43				100					
6													
1133			100	.61	1133 1" fgr Cor Xenolith			110					
7								120.0					

OMNI RESOURCES INC. PROJECT DIAMOND DRILL HOLE No. 87-89 Sheet 2 of 5

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
					122.5-128.4 Zone of Plag + Sericite + K-altn with Strong propyllitic Altn. Chl + Ep			120					
132.7			100	.46									
					Strong propylitic Altn. Ep+Chl, some slight Potassic Altn. + Ser. Continues over many boxes.			130					
149.7			100	.68	Porphyritic And Xenolith 144.0-144.3			140					
					Fault Zones at 156.5-157.0 + 157.8-158.8.			150					
166.2			100	.50	165.1 Phyllic + Silicic Altn. rock is bleached to a pale green, silicified. (Ser.) Most intense Altn 165.2-166.2 167.3 Fracture along core axis with clayey film on fracture. Chl Altn. with some slight Ser. & Weak Potassic			160	6646	165.2-170.2	5.0'	.001	.27
183.5			100	.54	182.0 - 182.5 Fault zone. 70° to C.A.			170					
					186.4 - 193.5 Zone of stronger Altn. Ser. Epi + Chl well fractured. Rest of zone is less Altered Ser. less common			180					
201			75	.37				190					
					202.5 And Xenolith. 202.8 Alteration intensifies - Sericite. 205.5-207.3 Well fractured zone clay in fractures. upto 1cm filling. last 6" of zone filled with Cotrilem. 207.3 - 211.6 Rock bleached to a dark green (Epi + Ser. Altn) cotrilem as fracture fillings. 211.6 - 219.0 (Epi + Chl) Altn.			200	6647	209.0-209.0	3.0'	.001	.03
221			100	.48				210	6648	209.0-212.0	5.0'	.001	.01
					V. Weak Propyllitic Altn. Small patches of Potassic altn. continues to 249.6 And 247.6-			220					
234			100	.76				230					
					And 249.6 - 250.1 70° + 55° 252.2 - 252.1 Strong propyllitic + Potassic Alteration in between And.			240					
254.5			98	.71	Andesite 253.9-258 With Cotr Epi Veinlets			250					
					Fault zone 258.1 - 259.4 259.4 - 265.4 Porphyritic Andesite 254 - 266.9 Granodiorite Crackle Breccia Andesite Matrix 266.9 - 271.0 Andesite with Epi + Cot Veinlets.	.5% Py.		260					
								270					

OMNI RESOURCES INC. · PROJECT _____ DIAMOND DRILL HOLE No. 87-89 Sheet 3 of 5

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERSECT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.R.T Ag
2780			92	24	Porphyritic Andesite Some wk plagas. Ser. Alt. Cct Veinlets 70°+0° to C.A. 2780-280 Fracture zone.			270					
2980			100	48	continues to 294.2 80° contact 294.2-296.2 Gdr. with Andesite floating as veinlets. 296.2 Granodiorite Weak-Moderate Propyllitic Alt'n. slight crackle with cct as fillings.			280					
304.9			100	75				290					
314.9			95	.43	315.0-322.8 Andesite as above 70°/55° contacts 322.8-324.0 Gdr. as above. 324.0-324.2 Fault 324.2- Rhd. as above.			300					
324.4			100	.45	325.4 Gdr. strong Propyllitic Potassic Alteration. 327.7 Porphyritic Rhd. as above. 70° contact. 334.8 Granodiorite as above.			310					
339.4			100	.45				320					
349.6			95	.51	352.6 Alteration increases more Epidote, Sericite and small patches of Potassic Altered plass (red) strong Propyllitic Alt'n. continues 200'			330					
369.6			95	.51				340					
377.6			95	.37	369.7-370.7 Zone of dark alteration with 10° crossent. to C.A. Quartz lines edges. in blebs Cct in cracks 0° to C.A. Fractures are at 70°.			350					
395.3			95	.37	Fractures with clay at 383.0. 384.0 Epidote as crack fillings rather than Cct. Hem+ Epi on Fractures			360					
411.8			100	.76	Alt'n. as above abundant Epi. 401.6- 403.2 Fracture zone			370					
					418.6 Cct veinlet 2mm wide at 30° to C.A.			380					
								390					
								400					
								410					
								420					

OMNI RESOURCES INC. PROJECT DIAMOND DRILL HOLE No. 87-R9 Sheet 3A of 5

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
4290			100	51	Cot Veinlets common along 0° to C.A. unbothealed shears upto 2mm wide.			430					
					436.0-436.8 Fracture zone with clay on fractures. Pth. as above.	tr Py		440					
4470			95	36	448-452 Fracture zone clay on fractures.			450					
					453.1-461.0 Fracture zone with clay on fractures 1" Sheer with cot blebs tr. Py. Dark alt'n over 8" 461-461.8.								
4633			95	28		tr. Py.		460					
								470					

OMNI RESOURCES INC. · PROJECT Skukum Creek (WH Claims) DIAMOND DRILL HOLE No. 87-R9 Sheet 4 of 5

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	ANALYTICAL
					Still Propylitic Altn. Ch. matics + Ep. Plags. green.			470						
480			100	.46	486.0-486.7 Fracture zone. Altn as above			480						
3995			100	52	498.5-499.0 Fracture zone.			490						
					498.2-498.7 Shear.									
					506.5-510.8 M. gr. Gdr Cct+Hem. in fracture fillings: Hematite on fractures. at 30° dark altn.			500						
5137			100	.25	511.0-511.8 Fracture zone.			510						
					0.3' ZONE OF STRONG PROP ALT'N @ 514.0'. 7% CA. ABUNDANT EP LT. GRN-YELLOW.									
					DARK GREEN-GREY MCG GDR. MOD-STRONG PROP. ALT'N. STRONG OVERALL FRZ. ABUNDANT CA VRINLETS + STRINGERS. MOST CA YELLOW/CREAM. MOST FRACTS @ 60-70°									
5303					SCALE CHANGE 1"=10'			530						SCALE CHANGE 1"=10'
	533				MOD. ALTD-BX OVERALL & SOME ROTATION IN CA-FLOODED ZONES. MORE FRACTURED + ALT'D WITH DEPTH.	MINOR TO 1% DISS. PY.									
	538				CRUMBLY FRACTURE / SHEAR & CLAY + ABUND. CA COATG. @ 537.0' & 538'									
	543				543-545.7 - U. CRUMBLY SHEAR ZONE. ABUNDANT CL, CLAY, & CA. 20° FRACT TREND SEEMS TO PREDOMINATE.	A FEW SMALL (TO 1cm) BLEBS AND CONCENTRATIONS OF PY. V.F.G.		540							
5465					LOWER CONTACT SHARP @ 45° TO C/A IN CLAY/CA-FILLED SHEAR			545.7	6570	540.0-544.3	4.3'	0.002	0.02	
	5515				GRANODIORITE: CRUMBLED, BXD, SHEARED, STRONG PROP.	549.9 minor qtz+PY, GL, SL. AS.			6571	544.3-549.5	5.2'	0.001	0.02	HW SHEAR.
	553				HW SHEAR ALT'D. SHEARS @ 45° LOWER CONTACT SHARP @ 45°	552.9 VFG BLACK MINERAL.		550	6572	549.5-552.7	3.2'	0.001	0.06	W. Au Corp
					ML BX. RHY, GDR, ASSR BANDED BXD IN DARK BLACK APHANITIC GROUNDMASS. LOWER CONTACT SHARP FROM CONT.	40% QZ, 20% AS 40% VFG BLACK.		552.7	6573	552.7-554.2	1.5'	0.063	2.54	0.074
					QZ SX BX IN RHYOLITE. AS, QZ, VFG UNKNOWN BLACK MINERAL.	554.2		554.2	6574	554.2-555.5	1.3'	0.235	13.22	Au = .254 RE-ASSAY
	558				RHYOLITE: CLEAN, COMPETENT, APHANITIC. LT GREENISH-TAN. FRACTS @ 25-30° + 45-50°	555.5		555.5	6575	555.5-560.0	4.5	0.002	0.01	0.001, 0.02/4.8
	563				MINOR CA FRACT. FILLINGS.	(TOOTHING.)		560	6576	560.0-565.0	5.0'	0.001	0.03	
					WEAK-MOD. PROP. ALT'N.	MINOR PY ON A FEW FRACT. SURFACES.		565.0	6577	565.0-569.5	4.5'	0.001	0.01	
	568				A FEW WHITE QZ EYES TO 5mm.			569.5	6578	569.5-571.3	1.8'	0.002	0.05	
					TOP CONTACT SHARP BUT IN U. BROKEN CORE.			571.3	6579	571.3-575.5	4.2	0.032	0.57	0.035
	573				LOWER CONTACT CORE GROUND!	571.3								
					ANDESITE BX. STRONG, FRACT-CONTROLLED PROP. ALT'N. QZ, CA + PY MATRIX. CLAST SUPPORTED. BLACK + GREEN-TAN. FRACTS @ 45° TO CA.	1-2% PY DISS + FRACT-FILLING.								

OMNI RESOURCES INC. PROJECT SKUKUM CREEK (WH CLAIMS) DIAMOND DRILL HOLE No. 87-09 Sheet 5 of 5

BOX	Run	Core	% R	RQD
575				
580.3				
584				
588				
593				
595.8	598			
603				
608				
613				
616	618			
623				
628				
633				
634.9	638			
643		EOH		

LITHOLOGY, ALTERATION, STRUCTURE

- 575 - 580.3: QZ-SX BX. ALL QZ <10cm. XENOS OF ALTO GDR. RHY + AND. BANDS OF EP + VFG DK GRY SX @ 45° TO C/A. MLOX @ END. QZ SX VN IN RHY. QZ SX MATRIX AROUND RHY CLASTS. GRAD. CONT.
- 580.3 - 588.4: APHANITIC, LT GREENISH-TAN RHYOLITE. SLIGHTLY MINERALIZED ON FRACTS.
- 580.0 - 580.4: CLAY + CALCITE FILLED SHEAR. SLIGHTLY MINERALIZED. MILLING ROCKS. A FEW SMALL HEALED FRACTS + SL, GL + PY INFILLING @ 588.3.
- FRACTURES MOSTLY ~ 45° TO C/A
- MOD. PROP. ALT'N
- GRADATIONAL CONTACT AT BASE.
- 588.4 - 593.5: RHYOLITE ± PROGRESSIVELY MORE QZ SX FRACT-FILLING.
- 593.5 - 598.8: QUARTZ-SULFIDE BRECCIA IN RHYOLITE. 60% F-VFG SX, 20% QZ, 20% RHY FRAGS IN 25° LOWER CONTACT SHARP @ 20° TO C/A
- 598.8 - 603.0: ANDESITE DYKE. BXVD & BANDED AT TOP. STRONG PROP ALT'N. FRACTS @ 20+45° TO C/A. SHARP 45° CONT @ BASE.
- 603.0 - 608.8: STRONG PROP ALT'D BXVD GRANODIORITE SHARP 70° CONTACT AT BASE.
- 608.8 - 610.4: ANDESITE AS ABOVE BUT MORE SHEARED AT BASE. CONTACT BROKEN UP.
- 610.4 - 643: GRANODIORITE LT. GRN-GRY. WEAK PROP. MOD. SILICIC ALT.
- FRACTURES + BANDING ~ 45° TO C/A.
- ABUNDANT CA STRINGERS. MOD. ABUNDANT CL/FP.
- MINOR HEMATITE STAINING IN FRACTS AND SPOTTED THROUGHOUT GDR. FOR LAST 5'.
- MINOR CRACKLE.
- QZ VEINS 1½ cm WIDE RUNNING THROUGH CORE @ 614' ± PY, SL + CL.
- EOH

MINERALIZATION

- 575.5 - 580.3: VFG 50% AS, 20% PY, 40% QZ, 10% DEGREY WEISH.
- 580.0: PY, SL, GL IN BX.
- 580.4 - 588.4: < 1% SX OVERALL
- SL, GL + PY IN FRACTS
- 2.5 cm VEIN OF QZ SX (BX).
- 588.4 - 593.5: 7-10% SX
- 593.5: VFG PY, AS + GL. MOSTLY AS.
- 598.8: ~ 5% GDR MINERAL.
- 598.8 - 603.0: ~1% DISS PY.
- 603.0: TRACE DISS PY
- 608.8: TRACE DISS PY.
- TRACE DISS. PY.
- 643: EOH

GRAPHIC LOG

FT. 575 580 590 600 610 620 630 640

SAMPLE

Sample No.	INTERVAL	CORE LENGTH
6580	575.5 - 577.6	2.1'
6581	577.6 - 578.7	1.1'
6582	578.7 - 583.4	4.7'
6583	583.4 - 588.4	5.0'
6584	588.4 - 593.5	5.1'
6585	593.5 - 596.8	3.3'
6586	596.8 - 598.8	2.0'
6587	598.8 - 603.0	4.2'
6588	603.0 - 608.8	5.8'
6589	608.8 - 610.4	1.6'
6590	610.4 - 615.1	4.7'

ANALYTICAL

O.P.T. Au	O.P.T. Ag	Notes Au Prep
0.195		
0.270	10.61	
0.160	10.28	0.147
0.004	0.07	
0.001	0.04	
0.021		
0.018	0.58	146' @ .085 Au & 3.82 Ag
0.172		
0.138	9.38	
0.260	10.46	0.538
0.016	0.25	
0.003	0.20	FOOTWALL SHEAR.
0.042	0.44	575.5 - 608.8 = 33.3' .057 opt Au 2.73 opt Ag
0.008	0.21	
		0.102, 5.28 10.4'
		EOH

[redacted] **DIAMOND DRILL LOG** HOLE No. 87-K1 Page 1 of 5

Property SKUKUM CREEK	NTS 105 D/3	Claim WH	Elevation 13	Azimuth 180°	Length 342.60	Dip -62°
Coordinates	Dip Tests	Advance 160.84	Depth 302.50	Date Collared JUNE 13, 1987	Date Completed JUNE 23, 87	
Purposes TO TEST N.E. EXTENSION OF KUHN ZONE		Drilled by CARON DRILLING SUPER 38		Assays by ACME	Logged by R.J. ROBINSON	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0.0	2.29			CASING IN OVERBURDEN: WEATHERED GRANODIORITE, SAND AND GLACIAL BOULDERS.				
2.29	131.00			GRANODIORITE: MORE AND LESS PROPYLITICALLY ALTERED. ZONES OF ABUNDANT SERICITE, CHLORITE, CALCITE AND/OR EPIDOTE. MINOR HEMATITE. TRACE PYRITE. ZONES OF POTASSIC ALTERATION. A FEW ANDESITIC XENOLITHS TO 5CM. (SHARP EDGES) - MOSTLY COARSE GRAINED. VARIES FROM ROSE-GREY TO DARK GREEN. USUALLY SOME SHADE OF GREENISH-GREY. MOST MAFICS ALT'D TO CHLORITE. A FEW FRACTURES AND SHEAR ZONES WITH CHLORITE, CALCITE AND/OR CLAY SURFACES.				
				17.75 SHEAR ZONE FOR 5cm				
				23.50 CLAYEY SHEAR ZONE FOR 50 cm.				
				27.65 5cm POTASSIC + CHLORITIC ALTN.				
				38.40 RUSTY CALCITIC CLAYEY SHEAR FOR 40 cm ABUNDANT CL + EP. ABUNDANT K. ALT'N FOR 5 METRES.				
				48.15 - 54.35 : DK. GRN-GRY. ABUNDANT EP, CL. SE, SOMEWHAT SWIRRELED & BANDED.				
				55.17. 20cm CLAY ~~FILLED~~ LINED FRACTURE ZONE.				
				MORE ALTERED BELOW ~35 m. GREENER, SOFTER. ABUNDANT EPIDOTE & K SPAR ALT'N, MUCH SALMON/RED FSPAR.				
				74.82 - 77.00. V. DK GRN. SWIRRELED, BANDED. ~1% MT IN BANDS & QA + Q2 Q2 BANDS TO 1cm. (BARREN) ABUNDANT CL/EP				
				89.40 - 99.00. EXTREMELY ALTERED, FRACTURED & XENOLITHS OF ANDESITE ABUNDANT POTASSIC, EPIDOTE + CHLORITIC ALT'N. RUSTY SHEAR ZONES @ 88.4, 89.8, 90.75, & 97.5. MINOR PY + CLAY.				
	229-100	.56						

[redacted] DIAMOND DRILL LOG HOLE No. 87-K1 Page 3 of 5

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
		100.60	118.10	109.80 - 110.65 : ROCK OF QZ DIORITE/ANDESITE COMPOSITION WITH				
		68 PCS	.67	BIMODAL DISTRIBUTION OF XTAL SIZES. MED GRAINED QZ,				
				FSPAR, HB IN MATRIX OF ALMOST APHANITIC TEXTURE. DK. GRNISH-				
				GRY. CL-EP ALT'N.				
				110.55 - 118.07 : EXTREMELY ALTERED GDR. IN BANDS & ZONES TO 2 M.				
				BANDS OF PHYLLIC, POTASSIC AND EPIDOTE ALT'N. QUITE COMPETENT,				
				NO MAJOR SHEARS OR FRACTURE PLANES. SMALL TRACE PY. (DISS)				
				XENOLITHS OF AND. TO 5 cm.				
		118.10 - 134.20		118.07 : CLAY AND SAND FILLED SHEAR 3cm THICK				
		47 PCS	.77					
				118.10 - 131.00 MOD. ALT'D PURPLISH-GRN WITH BANDS OF POTASSIC				
				ALT'N TO 10 cm AND THIN SWIRLS AND EPIDOTE - FLOODED				
				ZONES TO 5 cm				
131.00	139.15			ANDESITE/DIORITE : BANDS OF ANDESITE AND QZ PORPH / BIMODAL QZ DIOR.				
		134.20	139.00	SOMEWHAT PROPYLITICALLY ALTERED. AFEW MAFIC XTALS TO 1 cm.				
		107 PCS	.77	NO VIS SX. GREENISH GRAY.				
139.15	157.90			SLIGHTLY PROPYLITIC ALT. QZ MONZODIORITE: MOSTLY LIGHT GREY, COARSE				
				GRAINED. AFEW GRNISH CHLORITIC / EPIDOTIC BANDS.				
				1% FEW QA + CL FILLED FRACTS. MINOR CLAY IN SOME SHEAR ZONES				
				A FEW ~~CB~~ XENOLITHS OF ANDESITE TO 5 cm. TRACE PY. MINOR HEM.				
				MINOR POTASSIC ALT'N. A FEW QA STRINGERS - SOME ± HE				
				157.90 2cm QZ QA VEINLET ± <1% PY.				
157.90	162.38	260.90		ANDESITE/QZ DIOR. AS AT 131.00				
				160.92 - 160.63 : BROKEN, SHATTERED, CRUMBLY SHEAR ZONE.				
				INTENSELY ALT'D. ABUNDANT CL, EP QA, HE.				
				160.64: 2cm HE/QA VEINLET @ 30° TO C/A. ANOTHER @ 162.00				
				OVERALL AFEW BANDS WITH MED QZ XTALS + F.G MATRIX.				
				BUT MOSTLY ALL VFG/APH. ANDESITE.				
162.38				MODERATELY ALTERED GDR. PROPYLITIC ALT'N. SOME POTASSIC.				
				BANDS TO 1 METER VARY FROM SLIGHT TO INTENSE ALTERATION.				
				A FEW SMALL APLITE DYKES. LARGEST 70 cm.				

137.30

[redacted] DIAMOND DRILL LOG HOLE No. 87-51 Page 3 of 5

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
		171.00	221.28	174.00 - 174.50 : SCURRIED, BANDED, QZ, EP, CL, CA ZONE, INTENSE				
		150MS	.56	ALTN, ~3% PY (DISS) 10% QZ, 5% EP, 5% CL				
				MORE OR WHERE MORE ALT'D, BLO NO SX OVER 1% ALL PY.				
				183.00 : 20 cm SHATTERED SHEAR ZONE. MINOR CLAY.				
				178.6 - 179.5 INTENSE POTASSIC ALTN				
				183.10 - 189.20 MOD ALT'D ZONE QUITE CHLORITIC, MUCH EPIDOTE, MINOR PY, CA/CL/FL INCL. @ 188.9 MINOR CA. VEINLETS				
				193.65 - 194.05. PINKISH-BROWN, SUGARY-TEXTURED APLITE DYKE				
				193.00 - 1 cm BAND EPIDOTE / CHLORITE.				
				198.72 - 10 cm EPIDOTE FLOODED ZONE				
				205.75 - 10cm APLITE DYKE as @ 193.65.				
				208.10, 208.18, 208.30, 208.50 : THIN APLITE DYKES				
				213.72. HEMATITE SHEAR ON SHEAR SURFACE.				
				217.48 3CM QZ VEIN CROSSING CORE @ 35°. BARREN.				
				220.70 - 221.00 CALCITIC, CRUMBLED SHEAR ZONE MINOR CLAY, SANDY				
		221.28	261.30	225.50 : 20 cm APLITE DYKE THEN 1m DYKE @ 225.30.				
		130RS	.78					
				MORE OR LESS EXTREMELY ALTERED TO 260.50 m BANDS TO 2m VERY DK GRN, FLOODED ZONES OF EP & CA. ZONES OF INTERMEDIATE FSPAR ALT'N.				
				250.24 : 20 cm bad VFG LT BRN-GRN ALTN.				
				STRINGERS OF CA, CL, EP. SOME MINOR QZ. MINOR TO TRACE PY.				
260.50	261.30			FELDSPAR PORPH AND DYKE. BLACK, APHANITIC, SLIGHTLY ALT'D. CL + HE ON				
		261.30	306.38	FRACTURES, MINOR CA. VEINLETS ; FRACT. FILLING.				
		152	.67					
261.30	319.35			GRANODIORITE : ALTERED TO VARIOUS DEGREES THROUGHOUT. VARIES FROM WEAK PROPHYTIC TO INTENSE PROP, PHYLLIC, ARGILLIC, & SILICIC AND POTASSIC.				

[redacted] DIAMOND DRILL LOG HOLE No. 87-K1 Page 4 of 5

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	
				MOSTLY INTENSE PROPYLITIC TO PHYLLIC THROUGHOUT, WITH ARGILLIC IN FRACTURES AND SHEARS, AND SILICIC AND POTASSIC HALOS AROUND VEINLETS. A FEW ANDESITE PHENOCRYSTS AND BROWNISH-PINK SUCROSIC APLITE DYKES AND PHENOCRYSTS. (WITH INCREASING DEPTH, MORE OPEN, VUGGY FRACTURES LINED WITH AGATE, CHALCEDONY (CHRYSOPRASE), AND CALCITE SPIRES.					
				262.93 - 263.45: ENTIRELY ALT'D. FELDS MOSTLY YELLOWISH-GREEN. NO MAFICS. ABUNDANT SERICITE & EPIDOTE.					
				266.30 EPIDOTE STRINGERS <1mm WIDE ALONG CORE					
				266.75 SHATTERED & FRACTURED ZONE. SHARP, ANGULAR FRAGS.					
				267.00-267.61 CAVE ZONE. NO CORE RECOVERED.					
				268.63 3cm BAND OF INTENSE EPIDOTIZATION.					
				270.25 2cm APLITE DYKE. WIDTH VARIES					
				270.65 10 cm BAND OF INTENSE PROP. ALT'N. EPIDOTE CL. CA.					
				270.95 15 cm APLITE DYKE					
				——— MORE SECONDARY PYRITE IN MORE INTENSELY ALT'D ZONES.					
				274.62 1mm CA STRINGER ALONG CORE					
				275.60-275.96: HIGHLY POTASSIC ALT. PLAGS ALMOST RED. ABUNDANT CA STRINGERS 275.75, 1cm CA VEINLET.					
				277-277.4: INTENSE PHYLLIC.					
				278.23-278.61: INTENSE PROP. AND SMEAR FCAS					
				280.30-280.55: POTASSIC					
				281.53-281.91: PHYLLIC					
				282.24-288.10: MED-FIN GRAINED. KSPAR RICH. BLACK MINERALS PRESENT. NOT HIGHLY ALT'D. JUST SLIGHT PROPYL.					
				282.73: GREENISH BLK. EPIDOTE-FILLED SHEAR.					
				284.85 CA STRINGER ? EPIDOTE ~1 cm WIDE.					
				287.20 - 301.10: MAFICS MOD. BLACK. FELDSPAR PINK-RED. ABUNDANT. BRIGHT APPLE GREEN MINERAL WITH BLACK SPECKS. ABUNDANT RED HEMATITE STAINING.					
				288.75 CLAY GOUGE. FAULTED SHEAR.					
				289.75-289.95 APLITE + CALCITE IN INTENSE PROP ALT. ZONE.					
				292.52 APLITE DYKE. 5cm					
				292.62 5cm QZ-FLOODED ZONE					

[redacted] DIAMOND DRILL LOG HOLE No. 87-K1 Page 5 of 5

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
				293.55 - 2cm QA VEIN WITH OPEN CENTRE 6mm WIDE				
				298.07 - 10cm CHRYSOPRASE / AGATE VEIN. PREP TO C/A.				
				298.36 3 SMALL (5mm) AGATE VEINS.				
				298.65 SMALL CHRYSOPRASE VEIN & QA LINING.				
				299.05 1.5 cm CHRYSOPRASE VEIN IN QA ENVELOPE.				
				300.12 1 cm AGATE VEIN & QA CENTER.				
				300.96 1 cm AGATE VEIN & QA center.				
				CHALCEDONY / CHRYSOPRASE / QA VEINS @ 302.92, 303.00, 303.95, 305.60				
				306.55, 308.60, 311.40, 315.25, (5cm) 315.35, 316, (50m) 317.45	9716	314.88	315.99	
				313.50 - 5 cm PORPH AND DYKE.				
				313.61 1 cm APLITE DYKE	9717	317.21	317.81	
				AGATE / CHRYSOPRASE @ 317.45 IS VUGGY + CALCITE-FILLED.				
319.35	326.54			SOFT, CRUMBLY, SHEAR ZONE. MOSTLY INTENSE PROP. ALT'N & ARG. IN SHEARS.	9618	319.35	320.51	
				CORE VERY CRUMBLY AND CLAYEY IN ZONES TO 30 cm WIDE. POOR				
				RECOVERY. ABUNDANT HEMATITE STAINING IN SOME SHEAR ZONES. ROCK	9619 *	320.51	322.03	
				SOFTER & DEPTH				
				320.65 - 15 cm clay with CRUMBLE DUPLEX MATERIAL. XTALS	9620 *	322.03	323.12	
				OF PURPLE FLUORITE AND BRIGHT GREEN CALCITE RHOMBS				
				CLAY + HEMATITE.	9621	323.12	324.61	
				322.40 - 323.75. SOFT, CLAYEY SHEAR ABUNDANT QA. SOME QZ STRINGERS				
				324.36 - 324.98 - BRITTLE FRACTURE ZONE, SHARD, TAGGED				
		30%		324.78 - 325.85 - ROUNDED RUBBLE ZONE 30% RECOVERY. REDUCE TO				
				BQ SIZE CORE.				
326.54	342.60			BRECCIATED, INTENSELY ALTERED PALE GREENISH-GREY GRANODIORITE WITH	9622	330.80	333.42	
				GREY RHYOLITE MATRIX. VERY CRUMBLY, FRACTURED & SHEARED. MORE K SPAR				
				IN GDR & DEPTH - ALMOST GRANITIC AT BASE OF UNIT. GDR/GRANITE →	9623	333.42	336.17	
				FINER-GRAINED WITH DEPTH				
				340.16 POSS. CHILL MARGIN OR CHILL ZONE IN GDR/GRANITE. CLASTS ARE	9624	336.17	338.83	
		306.35	-342.60	MAINLY BROWN RHYOLITE STILL IN GRN RHY MATRIX. VERY DISTINCTIVE.				
		174	.46	MEDIUM BROWN ANGULAR CLASTS IN DK. OLIVE GRN. CHRYSOPRASE	9625	338.83	340.16	
				NO SX, NO VG, NO DIAMONDS.				
	342.60			END OF HOLE.	9626	340.16	342.60	

[redacted] DIAMOND DRILL LOG HOLE No. 87-K2 Page 1 of 2

Property Skukum Creek	NTS 105 B/3	Claim WH	Elevation 1403m	Azimuth 180	Length 1133	Dip -55°	
Coordinates	Dip Tests 59°@ 1066	Advance 649.9'	Depth 928.1'	Date Collared July 3	Date Completed JULY 17		
Purposes To Test "Kulm Zone EXTENSION ABOVE K1	Drilled by CARON DD.	Assays by ACME	Logged by JBR				

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0	20			0-[illegible] Mafic Tuff Gdr 20% Pyrite				
			.37	[illegible]				
20	40		.51	[illegible]				
40	60		.58	[illegible]				
60	80		.57	[illegible]				
80	100		.34	[illegible]				
			.73	[illegible]				
100	120		.80	[illegible]				
120	140		.31	[illegible]				
140	160		.61	[illegible]				
160	180		.53	160-170.5 Mafic [illegible]				

[redacted] DIAMOND DRILL LOG HOLE No. 87-K2 Page 1 of 8

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by			Assays by	Logged by	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
			.66					
200	220		.42					
			.48					
			.74					
			.50					
			.69					
			.77					
			.85					
270			.86					

[redacted] DIAMOND DRILL LOG HOLE No. 87KZ Page 3 of 12

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by	Assays by	Logged by			

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
320	340			Weak [illegible]				
			.88	many [illegible]				
				Rusty flooding [illegible]				
				337' Aphanitic green [illegible]				
340	360		.78	[illegible]				
				[illegible]				
				[illegible]				
360	380		.80	360-379' Moderate Propylitic [illegible]				
				Fractured [illegible]				
				Zone also [illegible]				
				[illegible]				
380	400		.79	[illegible]				
				[illegible]				
				[illegible]				
420	440		.48	[illegible]				
				[illegible]				
				[illegible]				
				@ 447' [illegible]				
440	460		.60	Weak [illegible]				
				[illegible]				
				[illegible]				
			.65	452.9 [illegible]				
460	480			[illegible]				
				[illegible]				
				[illegible]				
			.48	[illegible]				
480	500			[illegible]				
				[illegible]				
				[illegible]				
			.61	[illegible]				
				[illegible]				
				[illegible]				

[redacted] DIAMOND DRILL LOG HOLE No. 27-K2 Page 1 of 2

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by	Assays by	Logged by			

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
			.61					
			.59					
			.75					
540	560							
			.30					
560	580							
			.35					
580			.27					
			.66					
			.68					

[redacted] DIAMOND DRILL LOG HOLE No. _____ Page 5 of 8

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by	Assays by	Logged by			

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
			.80					
			.69					
68.	70.							
			.66					
70	72.							
			.51					
720	74							
			.52					
740	760							
			.72					
760	780							
			.60	Moderate Propyllitic Alth.				
780	800			Weak Propyllitic Alth. 780.0-789.5, 789.5-795 Strong Propyllitic				
			.76	Alth with Potassic Alth of the Plag. Epidote-veinlets common on cracked surfaces. 791.3-791.7 Aplite lens. 791.900 moderate fading to weak Propyllitic Alth. The moderate Prop has small patches of Potassic Alteration.				

DIAMOND DRILL LOG — HOLE No. 87-K2 — Page 6 of 8

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	
800	820			Moderate Propyllitic Alt'n. 800-802.2 Weak to V. Weak					
			.77	Alt'n. 802.2-808.3, 808.3-808.5 Moderate Alt'n, Weak					
				808.5-812.2 Weak Prop Alt'n 812.8-818.5 Epidote-Potassic					
				Alt'n. Pkag. Kspar, 818.5-820 Weak Propyllitic Alt'n.					
820	840			Entire 20' is Altered Potassic, Epidote, some Magnetite) Feldspars					
			.74	are pink some sections show lesser amounts of this Alt'n. 830.2-					
				833.6 Porph. And. Also Altered.					
840	860			Zone ends at 843.2. From 843.2-848.1 Weak Propyllitic					areas where only Gdr is weakly Propyllitic Altered
			.93	with some bands of Epidote Kspar alt 848.1-849.2 Phyllic					
				Alteration bleached green Bio, Felds. ghosts 849.2-850.1					
				med. gr. Gdr., 850.1-860.0 Epidote-Potassic Alt'n. and base ~					
860	880			860.0-864.6 Weak Prop Alt'n with traces of Epi, Kspar Alt'n					bleached + Altered 870.6-875.5 Strong Propyllitic Alt
			.54	864.6-866.5 Porph. And. also Some K-spar Epidote Alt'n.					875.5 1" zone of Strong Potassic alt. 875.6-880.
				868.8-869.4 Phyllic Alt'n as above, 869.4-873.5 Moderate Propyllitic					Moderate Propyllitic Alt'n. with some Pot. continues
				Alt'n with some Potassic Alt'n 873.6-874.4 Strong Silicic Alt'n, rocks					
880	900		.84	zone continues to 884.0-886.1 Porph. And. 886.1-900.0					
				Potassic, Epidote Alt'n. With a Strong Phyllic Alt'n. 895.1-896.3					
900	920		.72	Potassically Altered Gdr. 900-903.2. 903.2-909.1					
				Weak propyllitic Alt'n. 909.1-920 Epidote+Potassic Alt'n of					
				Gdr. Moderate Alt'n with a 2" vein of Ch/Epi at 913.5					
920	940		.56	Brecciated (Slightly) Moderate-strong Potassic Alt'n Gdr.					
				900.0-925.2. 925.2-927.6 Shearzone 927.6-940.0					
				Moderate-Strong Potassic Alt'n. with Ch/Epi. Calcite filling in					
				fractures. Fracture Zones @ 931.3-932.6. 929.1-930.8					
940	960		.57	940.0-943.9 Moderate Potassic Alt'n with Ch/Epi.					
				943.9-946.0 Phyllic Alt'n. 946.0-948.2 Strong Potassic Alt.					
				Feldspars appear bright Red. Fault zone 948.2-950.2 Argyllic					
				Alt'n Clay with very altered Potassic) Gdr.					
960	980		.73	Zone continues th 962.0. 962.0-963.7 ML Bx composed of					
				96.4 Cet blebs. Very Altered Gdr. (Phyllic) Rhy also altered	6263	962.0	963.7	19	
				matrix is a silicified chloritic. Cracks filled with Cet. Mtg.					
				or rarely Chalcedony. (Amethyst or Chrysoprase) 963.7-967.0	6264	963.7	967.0	33	
				Gdr. Phyllic Alt'n. Brecciated, Vuggy. Magnetite Alt in cracks					

DIAMOND DRILL LOG

HOLE No. 87-K2 Page 1 of 2

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	
				967.0-969.0 M.L. Breccia Rhy. Gdr Qtz clasts in a dark grey matrix, black matrix from 967.5-969.0 Clasts 2mm - 3cm 1% f.g. in black matrix, vuggy	6265	967.0	969.0	2.0	
				969.0-970.8. Phyllic - Argillic Alt. of Gdr. Aplopore	6266	969.0	973.0	4.0	
				970.8-975.3 MULTILITHIC BRECCIA. Rhy. Gdr Clasts with a clay rich silicified matrix. Rhy + Gdr have been Phyllically Argillically altered 975.3-981.0 Shear Zone Strong	6267	973.0	978.0	5.0	
980	1000		.32	Argillic Alth of Gdr. 977-981 missing.	6268	978.0	985.0	7.0	Missing 2'
				GRANODIORITE Fractured, Vuggy, 981.0-985.5 Strong Propyllitic Alth. feld. seen moderately altered. Some chrysocolla in fillings. Granodiorite, Brecciated, Vuggy, with some Silicic Alth.	6269	985.0	990.0	5.0	
					6270	990.0	995.0	5.0	
				985.5-989.1 Granodiorite with Propyllitic Alth. fractured ±90° and 10° to core axis.	6271	995.0	1002	5.7	
				989.1-993.2 MULTILITHIC BRECCIA Rhy + Gdr. Clasts with a dark matrix (10% matrix) fillings of chrysoprase. Gdr + Rhyolite strong Silicic Alth. 993.2-1000.1 Argyllic Alteration with some Amethyst + Chrysoprase filling but Strongly Sheared. GRANODIORITE with Moderate Propyllitic					
1000	1020			Alteration Shear/fractured zones at 1005.3-1006.4, 1009.9-1011.0, 1012.6-1013.5					
			.45						
1020	1040			Phyllic Alth. 1020.2-1020.6, 1020.7 Altered band. 1020.6-1040 Moderate-Strong Propyllitic Alth.					
			.42	Shear Zones at 1022.0-1022.7, 1033.0-1033.4, 1037.4-1038.0					
1040	1060			Moderate to strong Propyllitic Alt. 1040-1055.0					
			.58	1051.4-1051.6 Silicic Alth 1055-1055.7, 1055.7-1057.2 Strong Propyllitic Alth Some shearing, 1057.2-1060.0 Moderate Propyllitic Alth continues to 1061.6					
1060	1080		.67	1061.6-1067.4 Qtz Vein with some very Silicified Gdr. fragments 90° to core axis 1067.4-1080 strong Propyllitic Gdr. with tr. Py in matrix					
1080	1100		.72	Strong Propyllitic Alth. Continues to 1089.4 Black stringers with Epidote 1084.3-1084.9, 1091.4-1090.5 Silicic Alth bleached green tr Py. 1095.0-1095.9 Fracture Zone + 1097.7-1098.6					

DIAMOND DRILL LOG HOLE No. 87-52 Page 8 of 8

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
1100	1120		.74	Strong Propyllitic Alt'n dark green colour mafics have tr-Py 1109.2-1110.0 Silicified Zone 1155-1168 Cct Alt'n. tr. Py.				
1120	1133		.40	Strong Propyllitic Alt'n 1120-1133, except 1134.4-1135.3 Phyllic Alt'n. tr. Py EOH 1133				

1086-1111

[redacted] — DIAMOND DRILL LOG — HOLE No. 87-SK-1 — Page 1 of 2

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
SKUKUM CREEK	105 D/3	WH	1300	325	58.83m	-38

Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed
1160.83N 7984.25E	N/A	46.36	36.72	JUNE 13, 1987	JUNE 17 1987

Purposes	Drilled by	Assays by	Logged by
TO TEST [redacted] ZONE AT 1230 LEVEL ADJACENT X-CUT #1	CARON DRILLING SUPER DRILL	ACME	R.J. ROBINSON

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	(Ag) oz/t	(Au) oz/t	Native Au
0.00	37.49			GDR: CG, GRN-GRY, PHYLLIC ALT. BANDS OF MORE AND LESS INTENSE ALT'N. - CL, EP, SE, CA BANDS, ZONES & STRINGERS. SOME RUSTY FRACTURE SURFACES. TRACE PY. A FEW ACNOLITHS OF ANDESITE TO 5cm.							
				FIRST FOOT: K ALT'N.							
				3.50: 75cm DK GRN ALT.							
				17.37: 30cm V. BROKEN UP - CRUMBLY.							
				21.45: 50cm V. BROKEN UP SHATTERED.							
				FROM 22.55 - 37.49 ROCK QUITE SHATTERED. FEW PIECES LONGER THAN 10 cm. MANY ZONES & NO PIECES > 5cm							
				37.9-37.49 CHLORITIC GRAVELLY SHEAR ZONE.							
37.49	43.50			MED-GRAINED GDR: ABUNDANT CA VEINLETS. TOTAL CORE V. CALCITIC.							
				MINOR PY. QUITE COMPETENT. MOSTLY CHLORITE ALT. AT END.					(Ag) 0.34	(Au) 0.24	
43.50	44.06			BRECCIATED GDR WITH CHLORITE ALT'N & QZ/CA MATRIX							
				NO VIS SX. SOME BANDING.	9696 *	43.50	44.45	0.95m	.06	.003	
						142.7	145.8	3.1'			
44.06	44.30			H.W. SHEAR ZONE BANDED & SHEARED GDR WITH BLACK BANDS AND CHLORITE BANDS. A FEW QZ EYES. V. CRUMBLED & CLAYEY.							
44.30	44.45			BANDED, ALT'D GDR AS AT 43.50.							
44.45	46.10			QZ SULFIDE BRECCIA WITH GDR CLASTS. ~70% GDR 25% QZ + 5% SX	9697 *	44.45	46.10	1.65m	7.79	.316	0.464
				~4% PY OVERALL & <1% GL. VERY FINE GRAINED SX.		145.8	151.2	5.4'			
46.10	46.36			MULTILITHIC BRECCIA WITH BLACK F.G. MATRIX AND CLASTS OF BARREN RHY. MINERALIZED RHY, QZ, FSPAR, QZ & CA STRINGERS, 1% COMB AS/PY	9698 *	46.10	46.86	0.76m	1.11	.022	0.031
						151.2	152.1	0.9'			
46.36	47.00			RHY BRX. & GREENISH RHY BRX & QZ SX MATRIX. ~2% PY/AS TRACE GL. CLASTS	9699 *	46.36	47.00	0.64m	5.76	.060	0.058
						152.1	154.2	1.8'			
47.00	47.50			QZ SX BRX: ~20% VEG SX. MOSTLY PY/AS/SL. MINOR GL.	9700 *	47.00	47.50	0.50m	4991	.177	0.184
				CLASTS OF CLEAR QTZ IN MATRIX OF VEG SX.		154.2	155.8	1.6'			
47.50	48.25			SLIGHTLY MINERALIZED, BRECCIATED RHYOLITE. MINOR VEG SX.	9701 *	47.50	48.25	0.75m	1.86	.052	0.079
						155.8	158.3	2.5'			

AURUM GEOLOGICAL CONSULTANTS INC. DIAMOND DRILL LOG HOLE No. B7UG1 Page 2 of 2

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag	Au
48.25	51.72			LESS BRECCIATED, LESS MINERALIZED, SLIGHTLY ALTERED RHYOLITE	9702	48.25	49.72	1.47	.43	.005
				VERY MINOR SULFIDES, SLIGHT BANDING, FEW STRINGERS OF PY		158.3	163.1	4.8'		
				A FEW THIN STRINGERS OF DARK MATRIX MULTI-LITHIC BRX.	9703	49.72	51.72	2.00m	.08	.002
						163.1	169.7	66'		
51.72	53.03			ANDESITE DYKE: BLACK, SOMEWHAT CHLORITIC, CA. FRACT. FILLING. APHANITIC, NO VIS SX.						
53.03	58.83			GRANODIORITE: PROPYLITIC ALTERATION. GREENISH-GREY, COARSE-GRAINED. ZONES OF MORE AND LESS INTENSE ALTERATION. SOME SWIRLING / PLASTIC DEFORMATION. BANDS TO 2MM OF CHLORITE AND EPIDOTE. MOST MAFICS ALT'D TO CHLORITE.						
58.83				END OF HOLE UG-1						

[redacted] **DIAMOND DRILL LOG** HOLE No. 8746-2 Page 1 of 2

Property SKUKUM CREEK	NTS 105D/3	Claim W H	Elevation 1300m	Azimuth 325°	Length 88.39	Dip -66°	
Coordinates 1160.46N 7984.25E	Dip Tests N/A	Advance 35.95m	Depth 80.75m	Date Collared JUNE 17, 1987	Date Completed JUNE 20/87		
Purposes TO TEST RAINBOW ZONE 60 M BELOW K-CUT #1	Drilled by CARON DIAMOND DRILLING (WILDCAT DRILL)	Assays by ACME ANALYTICAL	Logged by R.T. ROBINSON				

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0.0	1.50			CASING IN MUCK - NO CORE				
1.50	33.88		27 60pieces	GRANODIORITE: MODERATE TO INTENSE PROPYLITIC ALT'N. ABUNDANT CHLORITE, EPIDOTE, CALCITE. MINOR SECONDARY QUARTZ FLOODING IN NARROW ZONES. MINOR SERICITE. TRACE PYRITE. SEVERAL SMALL FRACTURE AND SHEAR ZONES. MINOR HEMATITE STAINING AND HEMATITE IN SECONDARY CALCITE STRINGERS. MINOR CLAY IN SOME FRACTURES. MANY FRACTURES HAVE CHLORITE LINING AND HEMATITE STAINING. A FEW SMALL XENOLITHS OF ANDESITE TO 5cm. CORE QUITE FRACTURED AND BLOCKY.				
33.88	45.75		.35 32pieces	ALTERNATING BANDS OF QZ-F-PORPH AND F GRANODIORITE & GRANODIORITE AS DESCRIBED ABOVE. ADD. DK. GREYISH-GREEN, SLIGHTLY ALTERED. MINOR CL, EP, SE, CA. SOME SECONDARY CA VEINLETS. QZ + FSPAR XTALS TO 4MM. A FEW SMALL HB XTALS. 33.88-34.18: ANDESITE. 34.18-37.14: GDR / 37.14-37.72: AND. / 37.72-38.04: GDR / 38.04-38.28: AND. 38.28-38.62: GDR / 38.62-40.08: AND. / 40.08-43.01: GDR. 43.01-45.75: ANDESITE.				
45.75	65.95		.46 54pieces	GDR AS DESCRIBED ABOVE BUT MORE ALT'D AND MORE DISS PY. 51.82-53.05: INTENSE PROPYLITIC ALT'D ZONE. ~1% PY V.DK GRN. 53.28-53.64: SHEAR ZONE. MINOR CLAY, SANDY. 59.20-60.20 ~1% PY DISS. AND IN SMALL (<1mm) STRINGERS. QZ FLOODED ZONE SMALL QZ VEINS + 1% PY MINOR CL. 64.92-65.12 + CA-FLOODED ZONE. MINOR PY. ABUNDANT CA.				

11 7 21 11 S 10
1 G A C A F A G

[redacted] **DIAMOND DRILL LOG** HOLE No. 87-46-7 Page 2 of 2

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
65.95	67.97		52	ANDESITE DYKE. INTENSELY ALT'D. VERY GREEN. BRECCIATED AND						
66.09	67.09		70.2%	SWIRLED/FLOWED. ABUND. CA. SP. CL. SE. N1% DISS PY.						
67.97	70.71		0	SHEAR ZONE: ORIGINAL ROCK U/K: MAYBE AND. OR GDR: BANDED, CLAYEY.	9704	67.97	69.16	1.19	.07	.005 ↓
67.09	69.79			LT. GREEN. ABUNDANT CA. MINOR PY. BANDS OF QZ. (YELLOW)				3.9'	67.09 - 69.16	
				BANDING @ 30° TO C/A. 30% SX IN LAST 10 CM.	9705	69.16	70.71	1.55	.86	.013
								5.1'	69.79 - 71.79	
70.71	71.28			QUARTZ SULPHIDE BRECCIA: ABUNDANT FINE GRAINED (<1MM) SULPHIDE	9706	70.71	71.28	0.57	53.99 ↓	.300 } 0.297
69.79	70.35			STALS IN CLEAR/WHITE QZ MATRIX. ~30% SX.				1.9'	69.79 - 70.35	
		70.71-71.19	0	~10% PY, 10% GL, 10% COMB. AS, SL, SB?.	9707	71.28	72.13	0.85	7.11	.118 }
			44 pieces	V. FRACTURED AT END. CORE GROUND + POLISHED. SOME LOST.				2.8'	70.35 - 71.19	
71.28	75.30			RHYOLITE: SLIGHTLY BRECCIATED, SLIGHTLY ALTERED AND MINERALIZED.	9708	72.13	73.67	1.54	.77 ↑	.009 0.010
70.35	74.32			BANDED IN SOME ZONES. SMALL PY BANDS. SOME PY + SL				5.0'	71.19 - 72.71	
				FRACT FILLING. A FEW ZONES OF QZ-SX BRX TO 15 CM.						
				BANDING ORIENTED ~28° TO C/A GREENISH-TAN.						
				72.03-72.13 QZ-SX-BRX.						
				71.93 GRAPHITIC SHEAR - CRUMBLY. SOME CLAY & CHLORITE						
				73.95 SHATTERED FRACT. ZONE FOR 10CM.	9709	73.67	75.07	1.40	2.36	.047
				74.22 BLACK MATRIX BRX-FILLED GASH 3CM WIDE.				1.6'	72.71 - 74.09	
				74.60 10 CM BAND OF QZ SX BRX.						
				74.75 15 CM BAND OF BRX RHY & QZ-SX MATRIX. GL/SL/PY/AS.						
				1% DISS PY IN LAST 10 CM OF INTERVAL.						
					9710	75.07	76.25	1.18	.12	.002
75.30	77.55			BRECCIATED SOFT ALTERED RHY: YELLOWISH-WHITE QZ FRACT-FILLING.				3.9'	74.09 - 75.26	
74.32	76.54			TRACE DISS PY. GREENER THAN ABOVE UNIT.	9711	76.25	77.55	1.30	.45	.016
				PY STRINGER @ 75.60				4.2'	75.26 - 76.54	
					4					
77.55	79.10			MINERALIZED, BRECCIATED RHYOLITE & SOME BANDS SOFT, SOME HARDER.	9712	77.55	79.10	1.55	1.55	.045
76.54	78.07			~5% QZ, 1-2% SX-MOSTLY PY. ABUNDANT EPIDOTE & SERICITE				5.1	76.54 - 78.07	
				IN LAST 20 CM OVERALL 1-2% PY DISS + IN FRACTURES.						
				1% COMB. SL/GL/AS. APPROX. EQUAL AMTS.	9713	79.10	80.82	1.72	.08	.001
79.10	82.05			BARREN RHYOLITE: LIGHT GREENISH-TAN. MODERATELY HARD. (NS)				5.8'	78.07 - 80.99	
78.07	80.99	71.19-82.17	.58	MINOR QZ. TRACE PY-DISS + IN QZ. LAST 20 CM.	9714	80.82	82.05	1.23	.98	.010
			35 pieces	YELLOWISH BAND 20 CM @ 80.36M				4.0'		↑
82.05	82.52			BRECCIATED GDR/CEMENTED SHEAR ZONE (FW SHEAR)? MINOR PY, CL, FESE	9715	82.05	83.21	1.16	.14	.003
80.99	81.45	82.17-88.39	.72					3.8'	80.99 - 82.13	
82.52	88.39		33 pieces	GDR. MOD. PROP. ALT'D. PLAG → EP + CA. SLIGHT FIZZ. AS USUAL.						
3.79	88.39	88.39	EOH.							

3.79, .047, 2.78

[redacted] **DIAMOND DRILL LOG** HOLE No. 83-G-3 Page 1 of 2

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
SKUKUM CREEK	105 D/3	WH	1300	325°	124.36	-77°

Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed
				JUNE 20, 1983	JUNE 23, 1983

Purposes	Drilled by	Assays by	Logged by
TO TEST RAINBOW ZONE 90 m BELOW X-CUT # 1	CARON DIAMOND DRILLING	ACME LABS.	R.T. ROBINSON

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
0.00	0.80			CASING IN GDR.						
0.80	35.90			WEAK PROPYLITICALLY ALT'D C.G GDR: PALE GRN-GRY. MINOR CL, TRACE PY, TRACE EP, SE. MINOR QZ VEINING ± SECONDARILY FROM PLAG ALT'N.						
				7.15 1cm QZ VEIN						
				9.87-10.80 SHATTERED FRACT. ZONE						
				11.20-11.97 SHAT. FRACT ZONE						
				12.75-22.75 CORE VERY BROKEN UP. ALMOST NO PIECES OVER 10cm. MOST LESS THAN 4cm						
				MORE ANK-POTASSIC ALT'N (OR MORE GRANITIC) FROM 20.34-35.90. SOME PLAG ALT'D COMPLETELY TO EPIDOTE. SLIGHT ☒ FIZZ.						
35.90	41.43			FELDSPAR-HB PORPH AND. V.DK GRN-GRY. PORPHS TO 3mm. STRONG PROPYLITIC ALT'N. ABUNDANT CA. SLIGHTLY MAGNETIC THROUGHOUT. MINOR PY.						
41.43	69.72			CG. PROP. ALT GDR. GRN GREY INITIALLY, THEN PINKISH GRN. WEAK PHYLLIC ALT'N WITH BANDS OF POTASSIC ALT'N AROUND SMALL FRACTS. AT ABOUT 52.12, UNIT BECOMES MOSTLY POTASSIC RICH WITH SOME SE ALT'N ON PLAG, AND SIMR POTASSIC ALT'N. (SALMON RED) NO MAJOR SHEARS OR STRUCTURES OF INTEREST.						
69.72	97.70			CG PHYLLIC ± PROP ALT GDR. APPLE GRN. ☒ PLAG ALT → SE. ALMOST NO POTASSIC ALT'N ± V. DK GRN. IN SOME ZONES						
				ALTERNATING BANDS OF PHYLLIC ± PROPYLITIC ALT'N. 65% PROP. 35% PHYLLIC.						
				82.50: 10cm SHEAR ZONE ± 2% PY ± QZ MINOR						
				86.20: 1cm WIDE QZ VEIN RUNNING ALONG CORE FOR 1.5m. MISSES CORE FROM 86.95-87.55 - THIS ZONE HIGHLY PHYLLIC ALT'D	9727	86.20	87.70	1.5m.		.009
				90.53: 1m ARGILLIC SHEAR ZONE. CRUMBLED ± BROKEN						
				94.25: 10cm ARG. SHEAR ZONE. AS ABOVE	9728	96.20	97.70	1.40		.001
		80-83-110	.63			316	321			
97.70	162.70			H.W. SHEAR ZONE: ROCK EXTREMELY DEFORMED, BANDING @ 25°TOC/a. ONLY MINOR SULFIDS. ABUNDANT CLAY. EVIDENCE OF MUCH GRINDING AND ALT'N.	9729	97.70	99.20	1.50		.001
							325.5			
		83-84-110	.68		9730	99.20	100.90	1.70		.001
							331			

[redacted] **DIAMOND DRILL LOG** HOLE No. 87-463

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t	
					9731	100.90	102.70 337	1.80 m.		.005	
102.76	106.10			RHYOLITE: BRECCIATED AND SHEARED AT TOP, MASSIVE BELOW. A FEW BANDS OF PY/AS/SL/GL? TO 1 cm. GREEN AND QUITE SOFT. YELLOW QZ STRINGERS AND FRACT. FILLING.	9732	102.70	104.08 341.5	1.38		.006	
				A FEW WHITE QZ EYES. SLIGHT BANDING @ 25° TO C/A	9733	104.08	105.65 346.6	1.57		.021	
					9734	105.65	107.10 351.4	1.45	1.8 3.10	.072	
106.10	107.10			GREEN RHYOLITE AS ABOVE WITH MORE BANDS OF QZ SX BRX. & 5-7% PY, MINOR SL, GL, AS. RHYOLITE SOMEWHAT BRECCIATED	9735	107.10	109.12 358	2.02 m	6.6 .39	.009	
107.10	107.71			BRX. DK. GRN RHY WITH MINOR PYRITE, YELLOW QUARTZ AND QZ EYES.							
107.71	109.71			MASSIVE, BANDED GREEN RHYOLITE WITH MINOR PY + SL IN V. THIN BANDS							
109.71	109.91			BRECCIATED GDR WITH 3% COMBINED SL/PY IN 5% QZ.							
109.91	111.25			BANDED GREEN AND BROWNISH GREEN RHYOLITE SLIGHT OILEY & QZ SX BRX m FILLING AT TOP, THEN MASSIVE, BANDED AND BROWNISH & DEPTH. A FEW WHITE QZ EYES.	9736	109.12	111.25 365	2.12	2.0 .64	.056	
111.25	112.37			MASSIVE, LT. GRN, SLIGHTLY ALTD-BRECCIATED RHY. A FEW BANDS OF QZ + SL/PY TO 5mm AT END.	9737	111.25	113.82 373.4	2.57	8.4 .26	.007	Natural Au Prep
112.37	113.82			MASSIVE GREENISH-BROWN RHYOLITE WITH FEW QZ + CA-FILLED FRACTURES. GREEN ALT'N AROUND FRACTURES.	9738 *	113.82	115.00 377.3	1.18	3.7 ↓ 7.14	.138	0.181
					9739 *	115.00	116.57 382.5	1.57	3.2 2.24	.070	0.073
113.82	118.68			30% QZ SX BRX IN PHYLLIC ALT'D LT. GRN RHY. SULFIDES ARE: 60% VEG AS/35% PY/15% SL/TRACE GL(<1%). ZONE OF LOW GRADE FROM 115.21-115.90	9740 *	116.57	118.08 387.6	1.51	5.0 9.44	.182	0.197
					9741 *	118.08	118.68 389.6	0.60	2.0 2.89 3.03 0.116	.075	0.078
118.68	121.00			MULTILITHIC BRECCIA - MATRIX SUPPORTED. SUB-ANGULAR TO SUB-ROUNDED CLASTS OF TAN RHY, GRN RHY, BANDED RHY, & GDR FROM .5mm TO 5 CM. DULL OLIVE GRN MATRIX ± SECONDARY CHLORITE. ZONE OF QZ SX BRX FROM 119.79-120.18. MINOR QZ ± SX FROM 120.65-120.80.	9742	118.68	120.40 395	1.72	5.6 .95	.014	0.019
		102.00/113.94	.86		9743	120.40	121.00 397	0.60	2.0 ↑ 10.91 3.0	.148	0.210
121.00	124.36			STRONGLY PROPYLITIC ALT'D GDR. ABUNDANT CL, CA, CLAY. CRUMBLY FOR LAST METER.	9744	121.00	123.10 403.9	2.10	.26	.002	
	124.36			END OF HOLE.							

[redacted]

DIAMOND DRILL LOG

HOLE No. 87-U64 Page 1 of 2

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
SKUKUM CREEK	105D/3	WH	1800	291°	64.01	-34°

Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed
		53.07	35.79	JUNE 23, 1987	JUNE 25/87

Purposes: TO TEST RAINBOW ZONE @ 1270m LEVEL BETWEEN X-CUT #1 & X-CUT #2 | Drilled by: ARON DIAMOND DRILLING | Assays by: ACME | Logged by: R.T. ROBINSON

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t	
0.0	1.26			NO CORE CASING IN GRANODIORITE.							
1.26	45.25			GRANODIORITE: WEAK PROPYLITIC ALT'N MODERATELY FRACTURED. MOSTLY PALE GREENISH-GREY COARSE GRAINED. TRACE DISS. PY. A FEW SMALL CA VEINLETS MINOR HEMATITE. AFEW ZONES OF WEAK POTASSIC ALT'N. SOME RUSTY STAINING ON FRACTURES. 20.60 - 21.00 SHATTERED FRACTURE ZONE.							
26.52	33.35	80%		24.28 - 24.58 FRACTURED ZONE VERY SHATTERED FROM 33.35 TO 36.22							
				38.85 2cm CA VEIN ± 30% SL + 5% PY.					.708		
		96.4%	1.45	A FEW MORE THIN (<1mm) BARREN CA VEINS FOR 3 M.							
45.25	48.52	80%		HANGING WALL SHEAR ZONE: SHEARED AND CLAY ALTERED GDR. VERY CRUMBLY. 20% CORE LOST. MINOR DISS PY.	9745	45.25	46.95	1.70	.22	.003	N.V. Au P.P.
					9746	46.95	48.52	1.57	.831	.021	0.009
48.52	49.07			QZ SY BRX IN GDR · 10% WHITE QZ, 5% PY, 1% GL, 1% SL. VFG, SOMEWHAT CRUMBLED & CRUSHED.	9747 *	48.52	49.07	0.55	18.20	.180	0.176
					9748	49.07	50.65	1.58	.23	.006	
49.07	50.65			BANDED, CG, MOD. PROP. ALT'D GDR: PARALLEL BANDS OF CA, QZ + STRINGERS OF PY.							
50.65	52.93			RHYOLITE: FG, CLEAN, LT GRNISH-TAN. WITH STRINGERS OF SX. N1% GL 2% PY VFG IN SMALL STRINGERS. MASSIVE.	9749	50.65	52.93	2.28	.93	.042	
52.93	54.16			COARSER GRAINED GREENISH-TAN GDR RHY. ABUNDANT VFG QZ IN STRINGERS. SOME BLEBS + STRINGERS OF WHITE QZ. TRACE PY IN LIN QZ. 3cm BAND BK BRXN @ 53.97.	9750	52.93	54.16	1.23	.13	.001	
54.16	55.23			WEAKLY PROP. ALT'D GDR, CG, LT GRNISH-GRY. TRACE DIS PY. SOMEWHAT SHEARED + BANDED.	9751	54.16	55.23	1.07	0.003, 0.02 = 4.3	.002	
55.23	59.06			MULTI LITHIC BRECCIA: NOT NORMAL MLBRX ZONES OF PRIMARILY RHY, THIN GDR. THEN ANDESITE WITH MIXTURES OF VARIOUS PROPORTIONS BETWEEN.	9752	55.23	57.10	1.87		.004	
		94.2%	1.39								

[redacted] DIAMOND DRILL LOG HOLE No. 87-464 Page 2 of 2

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
				55.23 - 56.55: SLT. BNDED RHY BRX. MINOR PY FRACT. FILLING +	9753	57.10	58.71	1.61		.002
				GRADES INTO BRX QDR ± 10% RHY CLASTS. TRACE PY. FROM			60.35			
				56.55 - 57.10.	9754	58.71	60.35	1.64		.004
				57.10 - 58.12 BRX of RHY (WHITE), BLACK DYKE ROCK + BROWNISH GREY			60.35			
				DYKE ROCK. PROBABLY ALT'D AND MINOR HEM STAIN. A FEW						
				CLASTS OF QDR PRESENT.						
				58.12 - 59.06 MOSTLY BRX QDR WITH CLASTS OF WHITE +						
				GREEN RHYOLITE. MINOR CA VEINLETS + TR PY.						
59.06	60.35			ANDESITE DYKE. FEW SMALL (1mm) PLAG. PHENOCRYSTS. DK. GRY						
				WITH BLACK MOTTLING. MINOR CA + YELLOW QZ STRINGERS.						
60.35	64.00			GDR: CG. WEAK PROP ALT. MINOR CA STRINGERS TO 1cm.	9755	60.35	61.90	1.55		.001
				MINOR DISS PY.			64.00			
				62.10 1cm CA STRINGER ± 10% PY + 2% SL.						
		56.37/64.00	.68	GDR MORE COMP. - LESS FRACT. THAN HW.						
	64.00			EOH.						

[redacted] DIAMOND DRILL LOG HOLE No. 87-465 Page 1 of 23

Property SKUKUM CREEK | NTS 105D/3 | Claim WH | Elevation 1302m | Azimuth 298° | Length 50.90 m | Dip FLAT

Coordinates | Dip Tests | Advance 50.90 | Depth 0 | Date Collared JUNE 25, 1987 | Date Completed JUNE 28/87

Purposes TO TEST FOR EXTENSION OF RAINBOW ZONE AT BEND ON 1300m LEVEL | Drilled by CARON DIAMOND DRILLING | Assays by ACME | Logged by RJR/TME

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	% Py	OPT Au	OPT Ag
0.0	33.95	82	.25	GRANODIORITE: COARSE GRAINED. ALT'N INTENSITY VARIES BTWN STRONG PROPYLITIC AND STRONG PHYLLIC WITH NARROW BANDS OF POTASSIC AND IN AREAS FRACTURES; ARGILLIC. VERY FRACTURED AND SHEARED ENTIRE HOLE IS IN SHEAR ZONE. COLOR VARIES BETWEEN PALE GREENISH GREY AND DARK GREEN, WITH BANDS OF LT GREENISH TAN AND SALMON PINK/RED FELDSPARS, FRACTURES RUSTY.							
				5.24-5.28: CLAY GOUGE - FILLED FRACTURE. CLAY YELLOWISH.							
				7.24-10.90: FRACTURE ZONE. MINOR CLAY ON SOME BREAKS. CORE SHATTERED.							
				11.20-11.47 = POTASSIC ALT'D ZONE.							
				10.92-14.15: SHATTERED FRACTURE ZONE. NO PIECE BIGGER THAN 10 cm.							
				15.85-18.00: SHATTERED FRACTURE ZONE AS ABOVE							
				19.85-20.30: SHATTERED ZONE AS ABOVE							
				21.00-21.30: VERY BROKEN UP. FRAGS < 2cm.							
				22.80-22.90: QZ-EA VEIN ± EPIDOTE HALO. 1cm VEIN OFFSE BY FAULT.							
				23.70-23.77 = Local phyllic alt'n; 1% pyrite Thereafter = locally strong chlorite alt'n up to 7 cm. across.							
				27.84-28.04m = Strong magnetite-chlorite alt'n.							
				28.00-32.00m = Strong fracturing w. some shear gouge on fractures							
				28.55-28.95m = Orangish-red clay alt'n of feldspars							
				32.30-33.95m = Strongly bleached or propylitically alt'd. coarse grained Gd; only minor pyrite	9756	32.30	33.95	1.65m	<0.1%	0.001	0.03

[redacted] DIAMOND DRILL LOG HOLE No. 87-46 5 Page 2 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	% Py	OPT Au	OPT Ag
				* Assay intervals laid out by RJR						Native	
33.95	36.70	72	.24	33.95 - 34.30m = MINERALIZED GRANODIORITE 2mm - 2cm Qtz - sulphide and qtz - sulphide breccia veins cutting bleached Gd 2% Py, 3-4% Aspy, 1% sphalerite and 0.1% Galena	9757	33.95	34.30	0.35m	2	0.125	0.093 58.92
				34.30 - 36.70 = UNMINERALIZED, BLEACHED C. Grained GRANODIORITE - some brecciation	9758	34.30	36.70	2.40m	0.1		0.001 0.10
36.70	39.00	98	27	36.70 - 39.00m - BUFF RHYOLITE w. SECTIONS OF RHYOLITE BRECCIA - euhedral 2mm Qtz eyes 37.10m = 1mm Q - Carb - Sl - Py veinlet - some sericite alteration. 37.63 - 37.65 = Bleached, pyritic inclusion of c. gr. Granodiorite 37.85m = 2mm volt of Q - Go - Py - Aspy	9759	36.70	38.40	1.70	0.1		0.001 0.84
				38.40 - 39.00 MINERALIZED RHYOLITE - banding 45° to the core axis. Some tiny Qtz veins set 60° to the core axis 1-2% Py, 3-4% Aspy, 1% Sl, 0.2% Gn Qtz veins and Q - Sulphide bxn infillings up to 3cm across.	9767	38.40 126'	39.00 128'	0.60	1-2	* 0.130	0.109 63.86
39.00	39.62	98	.26	BLEACHED c.gr. GRANODIORITE INCLUSION	9760	39.00	39.62	0.62	0.1		0.001 1.02
39.62	41.25	82	.23	GREEN ANDESITE DYKE - bleached near contacts - 40m → 4mm Q-Py-Aspy veins partly brecciated adjacent to 1-6mm. creme carbonate veinlet. → 3-4 mm vein of same comp'n as above readily parallel to the core axis. - creme carbonate veins constitute ~ 3-4% of rock by volume	9761	39.62	41.25	1.63	0.2		0.003 0.63

[redacted] DIAMOND DRILL LOG HOLE No. 87-46 5 Page 3 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	% Py	Nat. Au Prep	OPT Au	OPT Ag
41.25	ca. 42.50	43	20	WEAKLY MINERALIZED RHYOLITE CRACKLE BRECCIA w. some quartz infilling and veining 1-2% Py ± minor galena. Very poor core recovery from 41.76 – 44.81 m.	9762	41.25	41.76	0.51	1-2	0021	0.023	3.22
					9763	41.76	44.75	2.99m	3-5%		0.054	12.99
ca. 42.50	44.75m	50	Nil	STRONGLY MINERALIZED QUARTZ SULPHIDE AND RHYOLITE BRECCIAS – FAULT ZONE 3-5% Pyrite, 1-2% galena, 0.1-0.2% Cpy mainly in last 0.30 m of interval.					0.053			
44.75	48.00m	100	40	MAINLY STRONGLY MILLED GRANODIORITE BRECCIA w. <10% RHYOLITE and QUARTZ FRAGMENTS – average bleached fragment size less than 1 cm; fragments are rotated (milled). 46.80m = 4mm Q-Py vn at 45° to the core axis. 47.40 – 48.00 = FAULT ZONE (Footwall fault)	9764	44.75	47.40	2.65m	0.1%		0.001	0.10
48.00	50.90	100	38	PROPYLITICALLY – ALTERED Medium Grained GRANODIORITE – 5% – 7% mafics – quartz veins (baiclase to 2mm) common. – several small rhyolite dykes up to 5cm across	9765	47.40	48.40	1.00			0.001	0.16
					9766	48.40	50.05	1.65			0.001	0.15
				50.90 m (167') = E.O.H.								

[redacted] DIAMOND DRILL LOG HOLE No. 87-UG 6 Page (1) of 3

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
SKUKUM CREEK	105 D/3	WH	1302 M		49.38	0° (HORIZONTAL)

Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed
	N/A	49.38	0	JUNE 28/1987	JUNE 29

Purposes	Drilled by	Assays by	Logged by
Step out 30m along curve in Rainbow Zone.	CARON D.D.	ACME	T.M.E.

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
0	27.60	96	12	PROPYLITICALLY ALTERED COARSE GRAINED GRANODIORITE w. 5-10% matics (chloritized) - plagioclase weakly to moderately altered. 2.85m = 1/cm bull qtz. vein to broken Gd. attitude? - some sections of strong propylitic alt'n such as from 3.50m - 5.40m; here is strong sericitic alt'n. & matics are strongly chloritized 8.43 - 8.50 m = strong MAGNETITE ± PY alt'n. 16.87 - 21.99m = strongly fractured; longest piece of core only 7cm 16.20 - 16.35m = strong MAGNETITE alt'n. 16.35 - 16.95m = MAGNETITE locally in strongly bleached Gd. From 16.95m = less matics (3%) and rock is finer grained (3mm grains rather than 4-5mm grains) - rock is also fresher. 24.95 - 25.80 m = strong silicification. - Lower contact 30° to the core axis						
27.60	29.05	100	28	MEDIUM GRAINED GRANODIORITE - greenish gray w. 1-3 mm grains.						
29.05	36.87	100	32	ALTERED COARSE GRAINED GRANODIORITE Upper contact 45° to core axis 33.15 - 33.22 m = 1 cm. Qtz. vein at 10-15° to the core axis 33.00m on → Gd strongly bleached; minor dissem. PYRITE; some fracture pyrite	9768	35.35	36.87	1.52m	<0.1% Py	.11	.001
36.87	37.40	100	50	BANDED GRAY TO BUFF RHYOLITE BRECCIA - frags. in bands less than 1 cm across - Upper contact 35-45° to core axis	9769	36.87	38.40	1.53	<0.1% Py	.03	.001

[redacted] DIAMOND DRILL LOG HOLE No. 87-46 6 Page 2 of 3

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by			Assays by	Logged by	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t	Natural Au Prop
				- lower contact 45° to the core axis. - unmineralized							
37.42	39.49m	100	52	UNMINERALIZED GREEN ANDESITE DYKE - <½% 1-3 mm. white carbonate veinlets. - lower contact 45° to the core axis.	9770	38.40	39.92 1.31	1.52 5	.05	.001	
39.49	39.73m	100	50	ALTERED C. Gr GRANODIORITE BRECCIA - minor disseminated pyrite - frags. < 5 mm							
39.73	42.38m	100	48	MIXED ZONE OF GRANODIORITE (C. Gr.), RHYOLITE and ANDESITE - 1 cm bands of Rhyolite – Granodiorite common. Banding 50° to the core axis. - some pyrite stringers - some andesite is bleached - 41.26m = 2-4 mm band of Q - Carb - Py (50% Py) at 50° to core axis; minor shear fracture offset of band. - irregular lower contact ca. 10-15° to core axis.	9771	39.92	41.44 1.36	1.52 4.5	0.1% Py .03	.001	
					9772	41.44	42.38 1.39	0.94m 3	0.1% Py .04	.001	
42.38	43.65	96	62	POST-MINERAL BRECCIATED RHYOLITE DYKE - minor (0.1%) disseminated pyrites; some py. on fractures. - lower contact sharply irregular & ~70° to the core axis.	9773	42.38	43.65 1.43.2	1.27m 4.2	0% Py .16	.002	
43.65	44.35m	90	39	STRONGLY MINERALIZED & ALTERED RHYOLITE BRECCIA w. QTz-SULPHIDE BRECCIA VEINS up to 4 cm. across - 5% Py, ½-1% Gn, 1% Sl, ⅓% Aspy.	9774	43.65	44.35 1.45.5	0.70 2.3	5% Py 9.66	.077	0.085
44.35	46.33m	85	29	MIXED ZONE OF ALTERED GRANODIORITE and RHYOLITE	9775	44.35	46.32 1.53	1.97 6.5	<0.1% Py .18	.002	

[redacted] DIAMOND DRILL LOG HOLE No. 87-46-6 Page 3 of 3

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes		Drilled by		Assays by	Logged by	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
46.33	49.00m	90	.72	GREEN ANDESITE DYKE w. GD. INCLUSIONS up to 10cm long.	9776	46.33	47.85	1.53	.01	.001
				- white calcite veins common; ½-4mm. thick.			1.7	5		
					9777	47.85	49.38	1.53	.01	.001
49.00	49.38m	90	.10	PROPYLITICALLY ALTERED COARSE GRAINED GRANODIORITE			16	5		
				- 2mm quartz vein at end of hole						
				E.O.H. = 49.38m = 162 feet.						

[redacted] DIAMOND DRILL LOG HOLE No. 87-46 7 Page (1) of 3

Property SKUKUM CREEK	NTS 105D/3	Claim WH	Elevation 1300m (?)	Azimuth ?	Length 60.7m (199')	Dip 0°
Coordinates	Dip Tests		Advance 60.7m (199')	Depth 0	Date Collared June 29, 1987	Date Completed July 1, 1987
Purposes Trace Rainbow Zone around bend from the second crosscut.			Drilled by CARON D.D.		Assays by ACME	Logged by T.M. Elliott

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0	12.74m	100	32	PROPYLITICALLY ALTERED COARSE GRAINED GRANODIORITE - 5-7% chloritized mafics - plagioclase weakly altered 2.06 - 2.13m = dark gray phyllic alt'n (1% Py) 2.44m = 1-2cm zone of dark gray Q-calcite -pyrite at 15° to the core axis 3.00 - 3.55m = dark green alt'n rich in MAGNETITE 10.67 - 11.30m = brick orange clay alteration of plagioclase.				
12.74m	13.80m	100	37	DYKE OF MEDIUM GRAINED GRANODIORITE - "salt & pepper" texture; 3-5% 1mm. alt'd. mafics - occasional plag. phenos up to 4mm long alt'd to sericite - upper contact 80°(?) to core axis.				
13.80	31.30	93	37	PROPYLITICALLY ALTERED COARSE GRAINED GRANODIORITE 17.43m - 18.75m = zone of dark green mgt-py (1-2%) chl. alteration; lower contact 60° to the core axis. 19.06 - 21.25m = strong light green sericitic alt'n. Lower contact 40° to the core axis 20.59 - 20.79m = silicified zone. 26.50 - 26.60 = Med. Gr. Gd dyke along shear contact ca. 10° to core axis. 26.80 - 28.00 = Strong MAGNETITE alteration				
31.30	32.50	100	34	DYKE OF MEDIUM GRAINED QUARTZ MONZONITE - sheared contact ca. 40° to the core axis - pink K-spar; green alt'd (sericite) plagioclases - minor speck of dissem. MoS_2 near lower contact.				

[redacted] DIAMOND DRILL LOG HOLE No. 87-116-7 Page 4 of 3

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes		Drilled by		Assays by	Logged by T.M. Elliott	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
32.50	37.53	100	58	GRAYISH PINK GRANITE CRACKLE BRECCIA - fragments 3 mm - 4 cm - broken (? attitude) upper contact. - leucocratic (1% tiny mafics). - 34.50 m - rock becomes gray and more mafic-rich (4% mafics). - 35.80 m - back into bleached GRANITE. - 37.40 - 37.49 = fault zone = Hanging Wall Fault.						
37.53	38.90	95	65	CREME RHYOLITE BRECCIA DYKE - 1-2 cm fragments in a rhyolitic matrix. - post mineral. - lower contact sharp and 30° to the core axis.	9778	37.49	39.01	1.52	.23	.001
38.90	40.68	95	60	Mixed zone of altered GRANITE(?) BRECCIA and RHYOLITE DYKES - 3 fresh rhyolite dykes 3 cm, 4 cm, and 12 cm wide at ca. 45-60° to the core axis - Granite (?) brecciated to 2 mm - 1 cm fragments - 4% rhyolite fragments in granite breccia near upper contact	9779	39.01	40.68	1.67m	.03	.001
40.68	41.35	100	75	STRONGLY MINERALIZED QUARTZ SULPHIDE AND RHYOLITE - SULPHIDE BRECCIAS - banding ca. 45° to the core axis - 10-15% ASPY, 2-3% PY, 3% Sl. and 1% GN. MINERALIZED.	9780	40.68	41.35	0.67m	2-3% Py. SPEC. PREP - (RUSH) 20.44	.690
41.35	43.18	95	50	CRUDELY BANDED CARBONATE - ALTERED ANDESITE and RHYOLITE BRECCIA 41.35 - 42.47 m = mineralized Andesite breccia. cut by white Q-carb. vns 42.47 - 43.18 = mineralized Rhyolite breccia - 42.26 - 42.39 m = multilithic breccia	9781	41.35	43.18	1.83m	SPEC. PREP (RUSH) 2.02	.039

Nat. wt. Prep
0.642
0.065

[redacted] DIAMOND DRILL LOG HOLE No. _____ Page 4 of 3.

Property	NTS	Claim	Elevation	Azimuth	Length	Dip 0°
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed July 1/87	
Purposes	Drilled by	Assays by	Logged by T.M. Elliott			

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
				- banding is 45° to the core axis - 2mm - 8cm irregular bands of mineralization - overall ca. 2% pyrite, ½% sphalerite, ½% arsenopyrite, 0.1% galena						
43.18	45.00	97	Fair	WEAKLY MINERALIZED ANDESITE BXA; RHYOLITE BRECCIA and MULTILITHIC BRECCIA - multilithic bxa clgs. some rounded quartz fragments & ½% dissem. py - poor recovery in this zone - last 70 cm is footwall fault zone w. crude banding 45° to the core axis.	9782	43.18	45.00	1.82m	.12	.006
45.00		100	Fair	COARSE GRAINED GRANODIORITE cut by ANDESITE DYKES. 45.00 - 45.57' = Gd w. 1-2mm Q and Q - carb veins approx. 45° to the core axis 45.60 - 46.52 = Calcite-veined Andesite dyke lower contact ca. 30° to the core axis 48.00 - 48.26m = greenish gray andesite dyke; upper contact ca. 25° to the core axis 48.55 - 50.16m = abundant small Andesite dykes; contacts with Gd. ca. 45° to the core axis 54.15 - 54.46m = 1 - 1½ cm. Q - calcite - sericite - pyrite vein at 10° to core axis; some mm (1cm) shear offsets of vein Hole ends in weakly propylitized c.gr. Gd E.O.H. = 60.67m (199')	9783	45.00	46.52	1.52m	.01	.001

[redacted] **DIAMOND DRILL LOG** HOLE No. 87-46B Page 1 of 5

Property OMNI – SKUKUM CREEK	NTS 105 D/3	Claim W/H	Elevation 1303 (?)	Azimuth ~ 197°	Length 609' (185.6m)	Dip 0° (FLAT)
Coordinates	Dip Tests NONE	Advance 609' (185.6m)	Depth 0	Date Collared July 2/87	Date Completed July 7th	
Purposes TEST STRIKE EXTENSION OF NEW ZONE W. of RAINBOW ZONE	Drilled by CARON BD.	Assays by ACME	Logged by V.T Y T.E.			

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
				0–34' C.Gr. Granodiorite, fair prop Alt, minor Ser on Fel & Plag → Ser, mafics Alt → chl ± mica ± py replacing mafics				
		95	73	and 28° Dominant Set @ 30°/60° to Core w/ chl ± wk Fol & chl ± Ser, occ qtz, cal v/lts 1-3 mm Nonoriented Set, wk crackle				
0	20			mx mod/dry @ 3',				
		100	63	Shear/fracture/vein set 60 w/ incl & 60				
				34'				
20	40			34–68 mgr. Por GRANODIORITE, mod prop Alt, mafics less Alt, less chl, Plag → Ser, Ext Silicification 42–65' Core highly Fract, Rehealed almost to a Crackle Bx, 30° Core, mod dol 45° Fol				
40	60		50	30° CNT + DIKE IS LATER W/ INCLUSIONS OF				
				66 mgr–f.gr. ANDESITE ± ANDESITE PORPHYRY DIKES w/ Inclusions of Silicified GRANODIORITE AS ABOVE, SHP CNT @ 45° w/ DIKE @ 67' ANDESITE is med Silicified, 10–15% Qtz ± Py Veins & v/lts, wk rehealed Fol's & minor Crackle Bx tex, Vein PROP ALT				
60	80	95	76	SHP CNT @ 30° SINGLE MONZ DIKE 68.2 mgr–f.gr. MONZONITE to GRANODIORITE, Fel's Resilicified wk Crackle, INT Silicification, wk–mod Prop Alt, acc mg-int Fol & Plag w/ lgs Alt, mafics wk Alt, dominant 30 & 45° Fol pattern				
				76' GRADATIONAL CNT				
80	100		48	med Gr. GRANODIORITE, INTENSE PROP ALT, Cracked & Rehealed with Complete "SILICIFICATION" & later minor Fel's w/ minor Alt, Crack acc mod, 30°, 60° & wk 45° Fol pattern SUBTLE WK ALT & CNT BY Fol PATTERN WITH MINOR EPIDOTE				
			51	SHARP 30° Contact				
100	120			121.5 med Gr. QTZ MONZONITE v few mafics, SILICIFIED CHL AS PROP. mod Crackled w/ Resil. CRACKLE BX				
				122.1 SHP 30° CNT				
			57	POR. ANDESITE DIKE, plag WK ALT, 2–5mm 30–40% Plag Phenos mod CHL, occ Qtz Carb wisps, minor chl Silks on Fel's, 30°				
120	140			141.6 SHARP 30° CNT w/ 4" Dike, 2' post PROP ALT				
				HIGHLY ALT QTZ MONZONITE, SILICIFIED, STR MAGNETITE, EPIDOTE				
			53	146 Pyr Pyrr CRACKLED 30/60° Fol				
				Med-C.Gr. QTZ MONZONITE CRACKLE BX, Cut by Ser, Chl Fol, minor Qtz, Carb, SILICIFIED throughout OCC BX Fol				
140	160			161.5 C.Gr. GRANODIORITE INCLUSION, mod–Str PROP ALT. wk Sil, Plag wk Alt & mod Chl & wk Fol, minor Silks				

AURUM GEOLOGICAL CONSULTANTS INC. — **DIAMOND DRILL LOG** — HOLE No. 87-116 8 — Page 2 of 5

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by			Assays by	Logged by	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag OZ/T	Au OZ/T
160	180		69	MAINLY C.GR. QUARTZ MONZONITE w. Gd. inclusions. Contacts 15° and 30° to the core axis.						
				169.3-170.1' = 3mm. Py-Carb-Chl-Ser-Q vnlt. at 80° to core axis cuts Q.M.						
180	200			178.1' = C.GR. GRANODIORITE - upper contact 40° to c.axis						
			47	179.7-180.0 = Hem-epid. alt^n down core axis; brecciated						
				Zone is mod propylitized; 183.4-183.8 = aplite at 80° to c.a.						
				FRACTURES 60° and 90° to c.a. - chl. on fract.						
200'	220'			207' = chl-ser. sheared healed → 55° to core ax.						
			68	212-213' = 3cm. wide bxa zone healed w. hematite → 30° to c.a.						
				218.5'-221' = Composite dyke of, FOR. AND GREEN PORPH. & RHYO. → contacts 45° to c.a. & sc. contact 70° to c.a.; 0.7' K-spar alt^n zone.						
220'	240'			From 221', K-spar increases to nearly ½ total feldspar; fract:						
			59	45°, 60° & 90° to c.a.						
240'	260'		24.5	243.5'-247.8' = PINK APLITE, contact zone; contact 70° to c.a.						
			24.8	247.5'-250.9' = silicification w. K-spar & later sericite						
		95	81	247.9' = MAFIC-RICH (12%) MED. GR GRANODIORITE (1-3mm grains)						
				Abunds random chl. fract, some silicification and some K-spar alt^n; mod. prop. alt^n.; 252' = 1½cm. dk gray Q ± Carb vn at 25° to c.a (broken by shear fract. offsets). From 268' on = mod silicification and local (1' sections) brecciation; From 274' = several 1-6 mm Q. vns.; 1 clgs. py-carb. at 276.6'; vns. 30-45° to c.a.	6161	283'	288'	5'		.02	.001
			71		6162	288'	293'	5'		.06	.001
280	300'		81	287.8-288.6 = DYKE OF GRANITE CRACKLE BXA						
				282.5' to contact = BLEACHING 45° to core axis	6163	293	297'	4'		.01	.001
				292.4'-297' = RHYOLITE BXA - light greenish gray w. creme Q-Carb in matrix, 297-301.4' = Carb-cemented	6164	297	301.4	4.4'		.07	.001
			78	Silicified m. gr. Gd as from 247.5' (CONTACT) 60° to c.a. Soft!						
300	320'			301.4' = LIGHT GREEN RHYO. BXA w. 5-20% creme	6165	301.4	306.4	5'		.09	.001
				carb. cement <1% Green Fuchsite(?) Py vnlts pre bration.	6166	306.4	311.4	5'		.36	.001
			59	306.7-307.6' = Black Rhyo. Porph. frags; 310.6' = 4cm x 5cm. incl. of	6167	311.4	316.4	5'		.02	.001
320'	340'			grey-green colour becomes light grey Rock becomes Q DOMINANT w. matrix-granular material	6168	316.4	321.4	5'		.01	.001
				321.4' RHYO. PORP. is Q-F PORPHYRY (3% 5mm Q. eyes, and 3-5% 4 mm. clay-alt^n feldspars.	6169	321.4	326.4	5'		.04	.001

Contact 15-20° to c.a

Q.M. — Gd — aplite — M.gr.Gd — Rhy. Brx — QFP

Ag OZ/T: To Border-Clgs .36

Au OZ/T: Bleaching .001

[redacted] DIAMOND DRILL LOG HOLE No. 87-UG8 Page 4 of —

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by			Assays by	Logged by	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Au oz/t	Au oz/t
				329.4' = 4mm. Q-py vn at 60° to c.a.; 333' = 3mm.	6170	326.4	331.4	5'	.02	.001
		85	59	Py vn w. minor Gn (30° to core axis). Fract. 30° & 45° to c.a.	6171	331.4	336.4	5'	.01	.001
				Clay-ser-chl on fract; 341.4' = 3mm. Q vn. no Py-Sl-Gn	6172	336.4	341.4	5'	.01	.001
340'	360'			at 70° to c.a. axis; 342' = 1cm banded Q vn w/ Py at	6173	341.4	346.4	5'	.09	.001
				30° to c.a.; 343.5-344.5' = Bxa (Rhyo? - silicified) cemented						
				by creme Q-carb as from 297'-Post QFP.	6174	346.4	351.4	5'	.02	.001
				Local 1' sections of bxa or strong sericitization						
			77	Fract 30°, 45° & 70° to c.a.	6175	351.4	356.4	5'	.02	.001
					6176	356.4	361.4	5'	.01	.001
360'	380'				6177	361.4	366.4	5'	.01	.001
					6178	366.4	371.4	5'	.03	.001
				irregular						
				369.8' = 3mm Q vn w. 2% Py at 75° to c.a.	6179	371.4	376.4	5'	.01	.001
			55	371.2' = Brated Q vn w. minor Py at 45° to c.a.						
				375.2-377.6' = Strong fracturing w/ gouge on fract.	6180	376.4	381.4'	5'	.08	.001
				378.4-379.5' = 6 x 2 to 3 mm. Q vns w. Py, Gn, Sl	One set cut by Q-Carb. vn	VEINS ARE 35° & 70° to core axis			Veins	
380'	400'			380.1' = Still QFP w. coarser texture; now subporph-	6181	381.4	386.4	5'	.03	.001
				yritic w. 50% of grains 1-3 mm in very fgr. gdmass	6182	386.4	390.6	4.2'	.20	.017
				383.4' = 4mm. Q vn at 60° to c.a.; Massive fract 30° & 60°	6183	390.6	393.4'	2.8'	.30	.016
			65	to c.a.; 386.6-387.4' = Buff to gray RHYO.-AND. composite	6184	393.4	398.4	5'	.06	.002
				dyke → bxa in center & cut by creme Q-carb veins; 390.6'-	6185	398.4	403.4	5'	.07	.001
				393.4' = BXA OF QTZ-PY-SL-GN at 10-30° to c.a.	3% Py 1% Sl 1% Gn	0.5% Gn	VEIN IS FAULT & QUIGG	2-4'	Com. wide	
400'	420'			402.1' 403.1' = 1cm healed shear at 25° to c.a.;	6186	403.4	408.4'	5'	.09	.001
				406.7'-407' = Breccia of Q-Py at 60° to c.a. From	6187	408.4	413.4'	5'	.05	.001
				407' = Strong clay alt'n ass'd w. shearing and bxation						
			69	Irreg. carb-Q vns (creme) from 415'-417' CREME CARB FROM 407-428'	6188	413.4	418.4	5'	.19	.010
				416.9' BUFF RHYOLITE BRECCIA - upper contact 15°				Carb	To Border - Clegg	
				to c.a. → 5-15% creme carbonate in irreg vns & fillings.	6189	418.4	423.4'	5'	.12	.001
420'	440			423.4'-423.9' = 1-2cm Q-Sx bxa vn down core axis					Rhyo Bxa / Silic Rhyo	
				5% Py w. minor Gn & Sl; 426.8-427.5 = Silic. AND. DYKE	6190	423.4	428.4	5'	.29	.040
			70	Contacts 30° to c.a.; and intermittently silicified					Rhyo	
				428' = C. GR. QUARTZ MONZ. - bleached zone to	6191	428.4'	433.4'	5'	Q.M. .04	.001
				453'; 432.5-434.4' = BUFF RHYO. DYKE contact	6192	433.4	438.4	5'	.13	.009
				70° to c.a.; Fract. 5°, 30° & 45° to c.a.	6193	438.4	443.4	5'	.07	.001
440	460		64	3% metics in Gd						

AURUM GEOLOGICAL CONSULTANTS INC. — **DIAMOND DRILL LOG** — HOLE No. 87-116 B — Page 1 of 5

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by			Assays by	Logged by	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag OZ/T	Au OZ/T
				Fract. at 30°, 50° & 70° to c.a.						
				Local 1' sections of bxation.						
				3% alt^d matrix; moderate prop. alt^n.						
460'	480'									
		95	68	489' - Fracturing becomes more intense.						
				500' - Bleaching increases; abundant chlorite veins or fract. fillings. Fractures 25°, 45° & 60° to c.a.						
480'	500'		52		6194	506.4	511.4	5'	.01	.001
				511.4 FAULT ZONE BEGINS — ca. 60° to the core axis. Abundant gouge & bleaching.	6195	511.4	516.4	5'	.02	.001
			54		6196	516.4	521.4	5'	.13	.009
500	520			523.4' = 2-3mm Q-Py vnlt at 45° to c.a. Fract. in gouge = 15°, 45° and 60° to c.a.	6197	521.4	526.4	5'	.10	.001
				528.5' = Quartz clast in sheared & bxated Q.M.					Qtz.	
		0%	41	Shear fabric varies from 25°-45° to c.a.	6198	526.4	531.4	5'	.06	.001
520'	540'			Strong fracturing and gouge.	6199	531.4	536.4	5'	.10	.001
			37							
					6200	536.4	541.4	5'	.03	.001
					6201	541.4	546.4	5'	.06	.005
540	560			541-544' = Strong bxation and shearing; 545' = minor	6202	546.4	551.4	5'	.07	.001
				pyrite in hairline vnlt.	6203	551.4	555.2	3.8'	.10	.008
		90	23		6204	555.2	558.7	3.4'	.36	.007
				553.3' RHYOLITE BRECCIA MINERALIZED WITH Q-Py vns (hairline - 2mm) Overall pyrite content = 1%. Frags. 2mm - 3cm.	6205	558.7	562.2	3.5'	1% Py .76	.063

AURUM GEOLOGICAL CONSULTANTS INC. DIAMOND DRILL LOG HOLE No. 87-UG8

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed	
Purposes	Drilled by			Assays by	Logged by	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Au 0.2A	Au 0.2A
				Broken contacts (? attitudes); some f.gr. black sulphides(?)	6206	562.2	567.4	5.2'	.08	.005
560	580			— 562.2 = MULTILITHIC BRECCIA – frags. mostly white Rhyo. & <1 cm. access; 75% frags <3 mm. 2% buff/tan grey Qtz. frags; Fault east of 568'	6207	567.4	572.4	5'	.06	.001
				→ 567.4' = Q.GR. QTZ. MONZONITE 30° to c.a.	6208	572.4	577.4	5'	.07	.001
				-K-spar is flesh coloured; 3% chl. mafics; weak PROP. ALT'N. Strong PROP – PHYLLIC ALT'N TO 574'						
580	600			574.5' = 2-3 mm GN-PY vn at 45° to c.a.						
				Fractures 20°, 45° & 60° to c.a.						
				594.7' – 596.9' = Breccia zone ca. 50° to c.a. Silicified and some bleaching.						
				600' – Fract. zone 40° & 45° to c.a.; Mod prop. alt'n.						
				Hole finished in massive f.gr. Q.M. at 609'						
				E.O.H. = 609'						

Rhyo 40°
Multi-lithic
Q.M.
E.O.H. 609'

[redacted] DIAMOND DRILL LOG HOLE No. 87-UG9 Page 1 of 3

Property OMNI - SKUKUM CK.	NTS 105 O/3	Claim WH	Elevation 1305m?	Azimuth ?	Length 228'	Dip -45°
Coordinates	Dip Tests NONE	Advance	Depth	Date Collared July 7, 1987	Date Completed July 8	
Purposes Determine dip of zone under 87-UG7.		Drilled by CARON D.D.		Assays by ACME	Logged by T. Elliott R.S.R.	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0	20'			C. GR. GRANODIORITE – moderate propylitic alt'n 5% chl. matics, plagioclase alt'd. to apple green sericite. Massive → fractures 45° & 60° to c.a.				
				Chl – sec. on fract.; occas. epidote.				
			.46					
				18-20' – healed shear fabric 60° to c.a.				
20	40'			21.5 - 27.9' = GRAY SILICIFIED M. GR GRANODIORITE – 3% chl matics. Upper contact 40° to c.a. and lwr. contact 30° to c.a.				
				27.9' = C. GR. QUARTZ MONZONITE – mod. propy. alt'n; 3-4% chl. matics.				
			.47					
				35.3' = GREEN ANDESITE PORPHYRY DYKE				
40'	60'			10-30% white Sp. phenos to 4mm. long. Fract. 45° and 70° to c.a.; Moderate SILICIFICATION.				
				46.3' = QTZ. MONZ. BXA – silicified & bxated w. magnetite-chl. introduction; Upper cont. 60° to c.a. – lwr cont. broken.				
			.60		6209	51.3'	56.3'	5'
				57.5' = SILICIFIED AND PORPHYRY as from 35.3'				
60'	80'			64.7' = SILICIFIED C. GR. QTZ. MONZONITE BRECCIA – upper cont. 60° to c.a.; lwr. cont. 55° to c.a.				
			.52	76.1' = ANDESITE PORPHYRY as logged earlier. 72.3-73.5' – incl. of c.gr. Q.M.; A.Por. is SILICIFIED; lwr. cont. 40° to c.a.				
				78' = PINKISH GRAY QUARTZ MONZONITE CRACKLE BRECCIA – strongly SILICIFIED				
80'	100'			104 ON → = texture destroyed by silicification				
			65	103.3' = 2-3mm Q-Py ± Mgt vn at 30° to c.a.				
				104' = Py on fract.; Fract. 60° & 45° to c.a.				
100'	120'			114.5' = 2% two to 4mm. Qtz-Py vns. at 20° to c.a.				
			.66	Strong silicification continues; Fract. ca. 65° to c.a.				

	OTT Au	OTT Ag
	0.001	0.04

DIAMOND DRILL LOG

HOLE No. 87-169 Page 2 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
			.71					
120 (36.58)	140 (42.67)	100%		121.5' - Mod. fracturing begins. Fract. 60°, 45° & 30° to c.a. (37.03)				
				130.0 (39.62) - Less fractured - mostly @ 90° to c/a				
				132.5 (40.38) - CA VEIN 1cm. wide abundant Cl. 15° to c/a				
			.42					
				135.5 (41.30) Small black stringers and QZ & minor PY+AS over 3in.				
140 (42.67)	150 (45.72)	100%		142.5 (43.43) M.G. GRANODIORITE DK GRN-GRY. Strong Prop Alt. minor Secondary PY, CA. Abundant Cl. FRACTURES @ 70-90°				
				Sharp contact @ 30° to c/a.	6210	143.3 (43.68)	146.3 (44.59)	3.0' 0.91
				146.3 (44.59) BANDED RHYOLITE: sharp contact @ 20° to c/a DK bands of fg. SX to 1%. Banding 20-30° to c/a. green.	6211	146.3 (44.59)	149.3 (45.51)	3.0' 0.91
150 (45.72)	160 (48.77)	95%			6212	149.3 (45.51)	152.8 (46.57)	3.5' 1.07
				153' (46.63) MULTI-LITHOLOGIC BRECCIA. Clasts of green RHY, QZ and m.g. GDR to 5cm in vfg black matrix. Minor VIS SX.	6213	152.8 (46.57)	154.6 (47.12)	1.8' 0.55
			.47	Banded @ 40° to C/A. WHITE QZ vein @ 153.8 WITH Fract-filling yellow QZ				
				within. 154.6 (47.12) GRADES INTO: autobrecciated GDR & some Yellow QZ + RHY	6214	154.6 (47.12)	158.9 (48.43)	4.3' 1.31
				infilling. Strong Prop ALT. 1% VFG PY-BSS. More RHY At end.				
				158.9 (48.43) CLAY-FILLED FAULT ZONE. CORE GROUND. PEBBLES OF QZ & BRX AND RECOVERY	6215	158.9 (48.43)	159.7 (48.67)	0.39 1.0
				159.9 (48.74) m-C.G. GRANODIORITE Weak to Mod. prop alt'n. Minor SX and				
160	180	80%	.37	leucocene. Fracts. @ 60 & 80°. LT GRNISH-GRY.	6216	159.9 (48.74)	164.9 (50.26)	5.0' 1.52
				164.9 (50.26) LT GRN TO GRN-GRY ANDESITE. Intense Prop. alt'n Abundant CA				
				stringers. Some QZ. Minor PY in QZ. TRACE DISS. Fracts 60° to c/a. internal	6217	164.9 (50.26)	169.4 (51.63)	4.5' 1.37
				bedding 35° to c/a. 169.4 (51.63) CG. GRANODIORITE. DK greenish-grey. Strong propylitic alt'n.				
				Abundant Cl, FP, SE. Somewhat auto-brecciated. Tr to Minor Py. Bands				
				of more & less intense alt'n. GDR appears banded in green areas. 40-50°	6218	190 (57.91)	191 (58.22)	1.0' 0.30
180	200		.77	192.3 (58.63) ABUNDANT epidote - chlorite - sericite. 30% of feldspar potassic.				
				Light pinkish hue to core.				

Scale Change	OPT Au	OPT Ag
	0.001	0.01
	0.001	0.11 ↓ 0.004, 0.15 / 1.98
scale change	0.006	0.18
	0.059	1.67
	0.046	0.26 0.046, 0.82 / 2.16
	0.022	1.74
scale change	0.001	0.02
	0.001	0.03
	0.004	0.01

DIAMOND DRILL LOG

HOLE No. 87-469 Page 3 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
200	220		.68					
			.91	219-222 Bands of F.G. Pinkish dyke-like rock to 5cm.				
220	240			Resemble aplite dykes, but have been observed in situ				
				to be xenoliths or discrete bands or zones in the surrounding				
				rock				
				228 END OF HOLE.				

[redacted] **DIAMOND DRILL LOG** HOLE No. 87-46 10 Page 1 of 3

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
SKUKUM CREEK.	105 D/3	WH	1301	260°	294'	-67°

Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed
	NONE TAKEN	114.9'	270.6'	JULY 8, 1987	JULY 9

Purposes To test head in Rainbow zone at 1270m Level BELOW HOLE 9 — Drilled by Capon Diamond Drilling — Assays by Acme — Logged by RJR.

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0.0	20.0			CG GRANODIORITE MOD PROP ALT'N MED GRN-GRY RUSTY FRACTS				
				ABUNDANT EP, CL, CA. MOD AUTO-BRXX. FRACTS BTWN 65-85° TO C/A				
			.20	CL & CA ON FRACTURE SURFACES DEEPER DOWN				
				ABUNDANT SMALL CA STRINGERS OFFSET BY BRXXING.				
20.0	40.0			MINOR SECONDARY K SPAR				
			.30	30.0-38.1 MG. GRANODIORITE OR QZ MONZONITE. SLIGHT PINKISH HUE. SILICIFIED				
				FRACTS @ 60°. KSPAR MAY BE SECONDARY. SHARP CONTACT AT END. (70°)				
				38.1-47.8 MG. GDR. STRONG PROP. ALT'N. DK GRN. MAFICS GONE.				
40.0	60.0			CRYSTAL STRUCTURES WITHOUT QUITE COMPETENT. FRACTS @ 60° & 90°				
				SHARP CONTACT @ END @ 55° TO C/A				
			.68	47.8-53.3 LT GRN-TAN MG GDR. STRONG SECONDARY K SPAR ALTN. PHYSICALLY AS ABOVE. WITH A FEW XENOS OF DK GRN MG GDR TO 3cm				
				53.3-72.8 MG. GRANODIORITE BANDS OF DK GRN PROP ALT - LT				
				PINKISH-TAN ALT GDR OR QMZ. BANDED @ 65° TO C/A. FRACTS @ 70°				
60.0	80.0			~65° SHARP 75° CONTACTS AT BEGINNING - END.				
			.45					
				72.8-204.0 QUARTZ MONZONITE:				
				LT PINKISH HUE OVERALL. WEAK TO MODERATE PROPYLITIC ALT'N				
				ABUNDANT CHLORITE ON FRACT SURFACES AND DISS THROUGHOUT.				
80.0	100.0		.45	MINOR POTASSIC ALT'N IN THIN ZONES.				
				FRACTURES AT 50-60° and 80-90° TO C/A				
				QUITE COMPETENT OVERALL WITH ONLY A FEW ZONES OF INTENSE FRACTS.				
			.47					
100.0	120.0			106: MOD. FRACT. ZONE. ABUNDANT CL 2ff				
			.29	116: MOD FRACT ZONE ABUNDANT CL 1ff				
				119: FRACT. ZONE 1ff				
120.0	140.0			125 FRACT ZONE 1ff				
			.44					

DIAMOND DRILL LOG

HOLE No. 87-UG10 Page 2 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	OPT Au	OPT Ag
				139.0 FRACT ZONE + QA 1 FT						
140.0	160.0		.56	148 BANDS + STRINGERS OF CL THROUGH CORE @ 75°						
				MORE BRECCIATED WITH INC DEPTH						
				159 3CM BAND OF CL/FP @ 20° TO C/A						
160.0	180.0		.45	169 1FT FRACT ZONE MINOR CLAY, ABUNDANT CL						
				MORE ARGILLIC ALT'N & DEPTH						
				BECOMES MORE CRUMBLY ON FRACTURES. ABUNDANT CLAY IN FRACT. ZONE						
180.0	200.0		.65	MINOR GRAPHITIC BANDS + STRINGERS APPEARING						
				199: 20cm WIDE GRAPHITIC, CHLORITIC, ARGILLIC BAND @ 15° to C/a 60.65	6219	199.0 60.65	204.0 62.18	5.0 1.52	0.001	0.10
200.0	210.0			204.0: Banded Chloritic RHYOLITE. Trace PY. Clay-filled Shear^ contacts @ 36° 62.18 @ 206.3, 35° 2cm	6220	209.0 62.18	206.5 62.94	2.5 .76	0.001	0.03
			.68	206.5 Banded, Clean^ hard RHYOLITE. Trace PY, blebs of yellow QTZ 62.94 black bands. (UFG SX?) AUTO Brecciated. MINOR chlorite. Q2 eyes TO 5 mm.	6221	206.5 62.94	211.5 64.47	5.0 1.52	0.001	0.17
210.0	220.0			ALT 64.47	6222	211.5 64.47	216.5 65.99	5.0 1.53	0.001	0.05
					6223	216.5 65.99	220.5 67.21	4.0 1.22	0.001	0.05
										0.002, 0.08 0.14
220.0	230.0		.68	224.0 RHYOLITE. Darker green. Abundant yellow Q2 / white Q2 eyes, clasts of GDR 68.27 TO 4cm Brecciated	6224	220.5 67.21	224.0 68.27	3.5 1.07	0.001	0.03
				225.5 CLEAN LT GRN BANDED RHYOLITE AS AT 206.5. SHARP STRAIGHT Contact @ 68.73 beginning 1 end.	6225	224.0 68.27	225.5 68.73	1.5 .46	0.001	0.06
				TO TO	6226	225.5 68.73	230 70.10	4.5 1.37	0.006	0.08
230.0	240.0		.71	230.0 BRX GDR = GRN Q2 + LT GRN RHY MATRIX. PROP. ALT'D. GDR. MINOR PY.						
				TO 71.41 231: Banded & Brx. RHYOLITE, ~1% Q2-SX. BRX AS MATRIX. CLASTS Partially rotated.	6227	230.0 70.10	231.0 70.41	1.0 .30	0.008	0.30
				71.52 231.8 F.G. DK. GRN RHY BRECCIA. CLASTS to 1cm. 1-2% PY/AS. FRACTS @ 20°						
				71.60 235: Brecciated RHY AS ABOVE BUT 5% Q2-SX BRX. CLASTS TO 5 cm.	6228	231.0 70.41	234.0 71.32	3.0 .91	0.004	0.10
				72.05 239: BRX. RHY, Q2 SX BRX + GDR MIXED - GRADING INTO ANDESITE BRX + GDR MATRIX						
240.0	260.0			72.15 240: ANDESITE, FG. DK. Greenish-black. Trace Sx. Abundant CA. Fracts @ 40-50°	6229	234.0 71.32	239.0 72.85	5.0 1.52	0.048	0.39

DIAMOND DRILL LOG

HOLE No. 87-46 10 Page 3 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	PPT Au	PPT Ag
				XENOLITHS OF CG GDR TO 5CM. BANDS OF ANDESITE IN	6230	239.0	244.0	5.0	0.002	0.01
			.81	GDR FOR FINAL 10 FT.		72.85	74.37	1.53		
					6231	244.0	249.0	5.0	0.003	0.01
						74.37	75.89	1.52		
260	280			259-292 CG GRANODIORITE STRONG PROP. ALT MOD.						
				78.94 89.00 POTASSIC ALT'N. ABUNDANT CA + EP IN STRINGERS TO						
			.76	1cm. DISS THROUGHOUT. MINOR DISS PY.						
				BANDS OF CL, CA + EP @ 20° TO c/a @ 285.5						
				FRACTS. @ SD + 65° WEAK AMTO-BX. CA INFILLING						
280	300									
			.77	291.2 - END. MG GDR. STRONG PROP. ALT'N MAFICS GONE.						
				XTAL STRUCTURE INDISTINCT. V. WEAK AMTO-BX + CA INFILLING						
				294. END OF HOLE						

[redacted] **DIAMOND DRILL LOG** HOLE No. 87-4G11 Page 1 of 2

Property SKUKUM CREEK	NTS 105D/3	Claim WH	Elevation 1301	Azimuth 325°	Length 183' 55.78	Dip -40°
Coordinates	Dip Tests NONE TAKEN	Advance 140.2	Depth 117.6'	Date Collared JULY 9, 1987	Date Completed JULY 10	
Purposes TO TEST RAINBOW ZONE BELOW X-CUT # 2 @ 1270 m LEVEL		Drilled by Caron Diamond Drilling		Assays by Acme	Logged by R.J.R./TME	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width				
0.0	20.0	100%		COARSE GRAINED GRANODIORITE - 0 - 121.6 37.0°								
			.30	MOD-STRONG PROPYLITIC AND POTASSIC ALT'N.								
				ABUNDANT CL, CA, EP, MINOR PY								
				STRONG SALMON PINK - RED POTASSIC STAINING IN FELDSPARS.								
20.0	40.0	100%		ALMOST NO PRIMARY K-SPAR. 30% Qz. 40% PLAG.								
			.47	10% K SPAR 20% ALT'N MAFICS.								
				OVERALL ~ 1-2% HEMATITE IN VEINS & CA + DISS								
				RUSTY WEATHERED FRACTS FROM 0.0 - 51.0 (ABUNDANT LIMONITE)								
40.0	60.0	100%										
			.56	FRACTS. @ 20°, 30°, 60 - 90° TO C/A.								
				MOST STRINGERS ORIENTED @ 20°								
60.0	80.0			WEAK ANKD BX. OVERALL								
		100%	.76	CORE MODERATELY BLEACHED FROM 69' DOWN.								
		100%		FRACTURES VERY CHLORITIC FROM 73.0 DOWN								
		85%		VERY FRACTURED - BLOCKY FROM 73 - 92' WITH CORE LOST								
		85%										
80.0	100.0	95%										
			.18									
100.0	120.0	95%		ABUNDANT EPIDOTE IN FRACTS @ 103 - 114'								
			.24									
				C. GR. QUARTZ MONZONITE - strong propylitic alt'n from 113' on (mild bleaching). Fractures 45° and 60° to c.a.								
				37.06 - 37.92								
120.0	130.0	95%		121.6' - 124.4' = Dark greenish - gray Q.M. BRECCIA w. fcags up to 2cm. access; ca. 3% diss. pyrite	6232	121.6'	124.4'	2.8'			0.007	1.21
			.79	124.4' - Breccia w. mod. silicification continues to rhyo. contact	6233	124.4	124.4	5'		Q.M Brn	0.001	0.11

UG 12 = 66°?
UG 13 = 430° } 325°

DIAMOND DRILL LOG

HOLE No. 87-UG11 Page 2 of 2

Interval From	Interval To	Recy %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width			OPT Au	OPT Ag
				32.50 BANDED.								
				129.6' = BUFF RHYOLITE PORPHYRY - banded contact	6234	129.4' 39.44	134.4' 40.97	5' 1.52			0.002	0.18
130.0	140.0		.32	39.88 90° to c.a. QTZ								
				135.4' - 138' = Several irregular PYRITE - SPHALERITE 41.27 42.06	6235	134.4' 40.97	139.9' 42.49	5' 1.53		Rhyo.	0.012	0.70
				vns ± Gn. running 10° to c.a. Vns up to 3mm across								
				Poorly mineralized section. Fract. 40° to c.a.	6236	139.4' 42.49	144.9' 44.14	5.5' 1.68			0.003	0.24
				44.23								
140.0	150.0			144.9' - 146.4' = SHEARED GD. or Q.M.(?) BRECCIA 44.17 44.62	6237	144.9' 44.17	146.4' 44.62	1.5' .46			0.058	3.39
				w. local banded buff rhyolite; ca. 3% pyrite;						Q.M. Bxa.		
				Shearing (brecciated) at 55° to c.a.; Gd frags. strongly bleached	6238	146.4' +4462 - 147.9'	149.4' 45.54	3' .91				
				& silicified 145.37 146.12	½% Py		GD	SI		Rhyo Bxa.		
				149.4 - 151.3' = STRONGLY MINERALIZED QUARTZ	6239	149.4' 45.54	151.3' 46.12	SP 1.9' .58			0.133	13.20
150.0	160.0			- SULPHIDE BRECCIA w. 5% Aspy + 1-2% Py						Q.Sr. Bxa.		
				151.3-154' = RHYOLITE BRECCIA w. Q cement. 2% Py	6240	151.3 46.12	154' 46.94	SP 2.7' .82		Rhyo Bxa	0.048	1.88
			.56	minor cpy, go & sl.						Q.Sr. Bxa		
				154 - 155' = 0.5' of QTZ. SULPHIDE BRECCIA w	6241	154 46.94	155' 47.24	SP 1.0' .30		Mixed Bxa	0.099	1.84
				7% Aspy, 4% Py, 1% SI ± minor go and 0.5' of Rhyolite								
160.0	170.0			155.0 - 155.4' = Fault gouge at 70° to c.a.; 155 - 160' =	6242	155' 47.24	160' 48.77	5' 1.52		Carb	0.043	2.90
				MINER ZONE of Q.M., RHYO, AND 4' Q Sx BXA. 1-2%								
				Py. 160' = BLEACHED ANDESITE w. local brecciation	6243	160' 48.77	165' 50.29	5' 1.52			0.004	0.11
				162 - 164' = Creme carb. infillings (10% of rock)						And		
			.61	Lwr. contact shared at ca. 60° to c.a.	6244	165' 50.29	170' 51.82	5' 1.53			0.002	0.07
170.0	183.0'		55.78	175.8' = MEDIUM GRAINED GRANODIORITE -								
				propy. alt'n (mod. - weak) Fract. 30° & 45° to c.a.	6245	170' 51.82	174.9' 53.31	4.9'			0.001	0.04
				E.OH. = 183' 55.78	6246	174.9' 53.31	179.9' 54.83	5' 1.52		Mod. Gd	0.002	0.06

SHOULD COMBINE 6238 AS SAMPLE APPEARS TO BE SAME ROCK TYPE 6238? 6239 combine?

.078, 6.04

[redacted] **DIAMOND DRILL LOG** HOLE No. 87-UG12 Page 1 of 3

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
SKUKUM CREEK	105 D/3	WH	1301 M	325°	248'/75.5M	-66°

Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed
	N/A	100.9'	226.5'	JULY 10, 1987	JULY 11, 1987

Purposes TO TEST RAINBOW ZONE @ 90 M BELOW SECOND X-CUT | Drilled by CARON DIAMOND DRILLING | Assays by ACME | Logged by RJR

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0.0	20.0			0.0 - 55.0 [illegible] CG GRANODIORITE. LT TO DARK GRN-GRY.				
	36		.73	STRONG PROPYLITK → MOD. PHYLLIC AND MOD POTASSIC				
				ALTERATION. STRONG RUSTY WEATHERED FRACTS TO 13'				
				SALMON-PINK STAINING OF FELDSPARS N30% QZ				
				STRONG ANTI-BX TO 18 FT ABUNDANT (3%) HEMATITE TO 18 FT.				
20.0	40.0							
17	12.11			LARGE CA BLEB + STRINGERS @ 25°				
			.68					
				BANDS AND FRACT-CONTROLLED BLEBS OF V DK GRN ALT'D GDR.				
40.0	60.0							
17			.58	SHARP FRACTURE CONTACT @ END @ 90° TO C/A				
				20cm APLITE DYKE 20° TO CA CUT BY FAULT @ 51.5'				
				55.0 - 75.0 [illegible] DARK GREEN M.G. GRANODIORITE				
				MAFICS → CL + EP, PLAG GREEN-STAINED.				
60.0	80.0			MOD. ALTD-BX. ZONES TO 5cm WITH XTAL PATTERN BRASED (OR CLASTS OF GRN. ANDESITE)				
			.79	MINOR HEMATITE STRINGERS				
				MOD-ABUNDANT CA FRACT FILLING + STRINGERS. PERVASIVE EPZZ.				
				75.0 - 127.8 [illegible] GRANODIORITE				
				LT. GRN-GRY, MED-CRS GRAINED.				
80.0	100.0			STRONG PHYLLIC - MOD. POTASSIC ALT'N BLEACHED.				
			.57	MOST K-SPAR SECONDARY - SALMON PINK OR RUSTY RED STAINED				
				QUITT STRONGLY AUTOBRECCIATED AT ALL ANGLES				
				FRACTURES = 60-70° TO C/A. 1 FOOT FRACTURE ZONES @ 90, 91.5,				
				98' + 102' CHLORITIC-CLAY BANDS @ 65° 93-94'				
100.0	120.0		.71					
				VERY MINOR PY.				
				SHARP 65° CONTACTS TOP + BOTTOM.				
			.64	MINOR - MOD. ARG ALT. LAST 10' OF UNIT.				
120.0	140.0			35.4 - 39.0				
				TZC - TIB PROP. ALT. LT DK GRN GDR.				
				TZB - TIB SILICIC + POTASSIC ALT'D LT GRN-YELLOW-TAN GDR.				
				130.0 V. Strongly Alt'd m.g GRANODIORITE. Associated 2% PY. POTASSIC + SILICIC ALT'N.				
			.59	131.1 QUARTZ VEIN OR FLOODED ZONE. Minor PY. 50% MULTILITHIC BRECCIA.	6247	131.1	134.0	2.9'

OPT Au	OPT Ag
0.001	0.01

						From	To	Width				
				137.0 m.c GRANODIORITE. Strong propylitic Alth. Abundant CA, CL, EP. Minor Py. A few Small fmgs. of Mafic to 5cm faulted in at top of zone. Top contact sharpe 20° Bottom is gradational. Swirls & stringers of EP.							
140.0	150.0			144.3 grades from above into Bleached, Silicic Alt'd M.G. GDR. V. Hard. Lt. yellowish, Greenish tan. Crackled. Abundant V. Small yellow Qz Stringers.							
				Abrupt contact at end.							
150.0	160.0		.74	153.4. V. strongly Alt'd, m.g. GRANODIORITE. fractures @ 65-75° minor Py. Propylitic and weak Potassic alt'n. Some zones so alt'd no mafs visible, whole rock fizzes slightly. Minor, small CA + Qz stringers.							
160.0	170.0			A few small yellow Qz stringers near end of zone.							
			.82	slightly autobrecciated, very competent.							
										OPT Au	OPT Ag	
170.0	180.0											
				5361	6248	173.4	178.6	5.2		0.002	0.28	
				175.9 1cm WIDE Chloritic/calcitic vein with 5% Py. cuts core @ 50°. Offset by small shear along core axis.		52.85	54.44	1.59			
			54.44	178.6 Clean, hard, crackled, yellow-greenish-tan RHYOLITE, minor Py,	6249	178.6	182.1	3.5		0.001	0.13	
180.0	190.0		.60	diss'd in Stringers with calcite. Slight movement on fractures. VFG		54.44	55.50	1.07				
			55.50, 55.50	182.1 Brecciated silicic Alt'd M.G. GRANODIORITE as at 144.3'	6250	182.1	186.6	4.5		0.006	0.05	
				abundant Cl diss, and many small yellow Qz stringers.		55.50	56.87	1.37				
			56.87	186.6 CLEAN, hard RHYOLITE AS @ 178.6 BOTTOM contact @ 50°.	6251 *	186.6	192.0	5.4		0.039	0.74	
			58.52	187.5 MINERALIZED RHYOLITE coarser-grained than above.		56.87	58.52	1.65				
190.0	200.0			3-5% Qz SX BRX in bands, stringers and blebs. Abundant yellow, clear + white Qz stringers + fract-filling. 1% Py/As 1% Sl/Gl	6252 *	192.0	194.0	2.0		0.016	0.58	
						58.52	59.13	.61				
					6253 *	194.0	196.0	2.0		0.232	7.54	0.483
						59.13	59.74	.61				
				LOWER CONTACT 65° TO C/A.	6254 *	196.0	200.0	4.0		0.012	0.22	0.015
200.0	210.0		64.67	200-202 M-L BRX. 30% VFG SX MIX. NOT ABLE TO IDENTIFY INDIVIDUAL MINERALS.		59.74	60.96	1.22				
			61.79	202.0 CLAY SHEAR ZONE IN RHY.	6255 *	200.0	202.0	2.0		0.272	4.02	0.306
				202.6 SLIGHTLY ALTERED CLEAN HARD LT GRN-TAN RHY.		60.96	61.57	.61				
			62.18	204.0 BRX GDR. SILICIC ALT'D. 3% PY + MINOR GL DISS'd IN QZ STRRXXXXXX.								
			.75	206.6 CLEAN, HARD SLIGHTLY AUTO-BRX. VFG. LT GRN-TAN RHYOLITE,	6256 *	202.0	204.0	2.0		0.022	0.34	0.019
			62.97	MINOR SX IN QZ FRACT. FILLING. MINOR SL/CA.		61.57	62.18	.61				
210.0	220.0				6257 *	204.0	206.6	2.61		0.112	1.22	0.130
						62.18	62.97	.79				

From	To	Recovery %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	OPT Au	OPT Ag
				67.67 222 AS ABOVE BUT DARKER GRN & SLIGHTLY LARGER STKS. BANDED & MORE BRKX	6258	206.6 / 62.97	211.8 / 64.56	5.2' / 1.59	0.013	0.26
				66.75 219 CRUMBLY SHEAR ZONE 2cm WIDE.	6259	211.8 / 6456	216.6 / 6602	4.8' / 1.46	0.010	0.30
220.0	230.0			67.06 220 SOFTER, COARSER GRAINED BAND 6 CM WIDE 7% PY	6260	216.6 / 6602	227.0 / 6767	3.4 / 1.04	0.011	0.11
			.77	67.67 222 RHYOLITE: SLIGHTLY COARSER-GRAINED, MORE INTENSELY BRXX, MORE MANY CA BANDS & BANDS	6261	222.0 / 67.67	226.0 / 68.88	4.0 / 1.22	0.009	0.24
				68.88 226 COARSER-GRAINED, DARKER GREEN RHY. & 5% EYES TO 1cm. MORE BRX = MATX						
230.0	250.0			69.49 228 Mod. GRAINED GRANODIORITE. SILICIC + PROPYLITIC ALTN. (MODERATE) TRACE PY + LEUCOXENE. SLIGHT MOD-BRXX. MINOR CA & S.L. COMPETENT. MOD GRN-GRY. GRADATIONAL CONTACT ON TOP, FAIRLY SHARP AT BOTTOM	6262	226.0 / 68.88	229.3 / 6989	3.3 / 1.01	0.001	0.02
			72.18 .54	72.18 236 8: SHEAR ZONE. U. ARGILLIC ALT'D. ABUNDANT CA. CLAY. SOFT, CRUM. GRY. MOD. PROP ALT. SHEARING INCLINED 20° TO CA. STILL GRANODIORITE						
	248.0		75.59	END OF HOLE.						

1.4

[redacted] DIAMOND DRILL LOG HOLE No. 87-116B13 Page 1 of 3

Property OMNI – SKUKUM CREEK	NTS 105 D/3	Claim WH.	Elevation 1300m.	Azimuth 325°	Length 284'	Dip +30°
Coordinates	Dip Tests		Advance 245.9'	Depth +142'	Date Collared July 11, 1987	Date Completed July 13
Purposes TEST AREA ABOVE 2ND X-CUT (30 m ABOVE)			Drilled by CARON D.D.		Assays by ACME	Logged by T.M.E. & R.J.R.

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0'	20'			0.0 – 173.2 (57.7m) COARSE-GRAINED GRANODIORITE.				
		100	.38	VARYING COLORS AND DEGREES OF ALTERATION. MOSTLY MOD-STRONG PROPYLITIC WITH ZONES OF MOD. STRONG POTASSIC, STRONG ARGILLIC ON/IN SOME FRACTURE ZONES.				
				ABUNDANT CA + CL THROUGHOUT. MINOR HEMATITE DISS'N IN STRINGERS				
20'	40'			FOR FIRST 40' (12.19) (36.59) FRACTS WEATHERED RUSTY FROM 0.0 – 118.4				
		100	.49	MOD. DROP TO 36' (11.0)				
				FRACTS @ 65° TO C/A.				
40'	60'							
		100	.35	STRONG PROP + WEAK POTASSIC TO 69' (21.03)				
60	80'							
		100	.50	MOD PROPK + MOD POTASSIC TO 98' (29.87) MINOR CLAY IN FRACTS.				
80	100'	100	.52					
				8814" LUMP OF HEMATITE IN CLAY/CL FRACT. ZONE.				
			.10	STRONG PROP/WEAK PHYLLIC + MOD ARGILLIC IN FRACTS. TO 123 (37.49)				
100'	120'							
		70%		MOD-STRONG PHYLLIC ALT'N TO 173 (52.73) BLEACHED, APPLE GREEN.				
				CLAY + CALCITE IN FRACTURES. CORE VERY SOFT.				
120	140'	90%		CORE VERY BLOCKY + BROKEN UP FROM 100 – 165' (30.48) (50.29)				
			.09					

DIAMOND DRILL LOG

HOLE No. 87-46 13 Page 2 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width			opt Au	opt Ag
140	160'			ROCK QUITE BX. SOME ROTATION. INC ? depth.								
		100	.23	VERY BROKEN UP & BLOCKY 159-161 (#46 29.07)								
160	170'									SCALE CHANGE		
		100	.39	MINOR SILICIC ALT'N IN THIN BANDS FROM 161-166' (#107 52.60)								
				CL/CA BANDING @ 45° TO CA, 166'-171' 52.12								
				1cm BAND HEMATITE @ 168' 51.21								
170	180'			GRADATIONAL CONTACT AT BOTTOM OF ZONE.								
				SILICIFIED C. GR. GRANODIORITE BRECCIA								
				-local phyllic alt'n; strongly bleached.	6273	174 53.03	179' 54.55	5'			0.001	0.12
				-light greenish grey								
		100	.67		6274	179' 54.55	184' 56.08	5'		Silic. C. gr. Gd Brx	0.001	0.01
180'	190'											
				Seicicite infills between fragments							0.001	
					6275	184' 56.08	189' 57.61	5'				0.01
				Fract. ca 45° x 60° to c.a.								
190'	200'											
				Local, ½ foot sections of strong fract. and gouge	6276	189' 57.61	194' 59.13	5'			0.001	0.01
										Rhyo Brx		
		59.53-59.68		195.3' - 195.8' = RHYOLITE BRECCIA - lwr. contact ca.	6277	194' 59.13	199' 60.65	5'			0.002	0.10
				30° to c.a.								
200	210'	60% 67.27-66.87	62.27	199.9' (60.97) - 204.3' (62.27) = HW SHEAR in GD. BXA - shears @ 45° to c.a	6278	199' 60.65	204.3' 62.27	5.3'		HW shear	0.035	1.50
				204.3' (62.27) = LIGHT GRAY MULTILITHIC BRECCIA.						Multilithic Brx		
		100	.40	30% RHYO. clasts, 5% GD., 1% QUARTZ	6279	204.3' 62.27	209.3' 63.79	5'			0.032	1.28
				in a sandy matrix; ie. matrix-supported.						Q. Sx. Brx Clast.		
			63.55	208.5' (63.55) = 4cm. Q-Sx Brx clast w. 5% Aspy,								
210	220'			2% Py	6280	209.3 63.79	214.3' 65.32	5'			0.015	0.39
		64.42-64.77		212 (64.62) ≤ 212.5' (64.77) = Strong banding w. 5% PYRITE;								
				banding ca. 45° to c.a.	6281	214.3 65.32	219.3' 66.84	5'		M.L. Brx	0.039	2.25
		65.23		214' (65.23) frags. rnd up to 7 cm across								
		66.4	66.60	219-218.8 (66.60) = 3-5% pyrite.	6282	219.3' 66.84	222.3' 67.74	± 3'			0.003	0.19
220	230'		66.87	219.4' (66.87) = Contact ca. 60° to c. axis						Gd Brx		

DIAMOND DRILL LOG

HOLE No. 87-11613 Page 3 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width		OPT Au	OPT Ag	
		100	.16	219.4 (64.47) - 220' (67.96) = RHYO. BXA								
				220 - 222.3 (67.76) = C.GR GD. BXA - Inc. contact 70° to c.a	6283	222.3 (67.76)	223 (69.28)	5'		0.001	0.14	
		67.8%	71.32	222.3' - 234' (71.32) = BARREN, BUFF RHYOLITE BRECCIA					Rhyo Bxa			
					6284	227.3' (69.28)	232.3' (70.81)	5		0.001	0.22	
230'	240'											Native Au Prop
		100	.43	232' (70.71) Banding 40° to c.a					Mineral And Andesite			
				Broken lower contact.	6285	232.3' (70.81)	234' (71.32)	1.7'		0.007	0.24	
			71.32	234' = ANDESITE DYKE - strongly mineralized								
				from 234 - 235' (71.63) w. 10% Py, 10% Aspy, 1% Gn.	6286	234 (71.32)	235 (71.63)	1.0'		0.229	4.85	0.149
240	250'	72.5%	80.3%	238' - PROPYLITIZED MRD. GR. GRANODIORITE								
				- upper contact 50° to c.axis; fault 45° & 70° to c.a.	6287	235 (71.63)	238' (72.54)	3.0'		0.002	0.10	
		75.35	75.50	247.2 (75.32) - 247.7' (75.50) = ANDESITE DYKE at 30° to c.a.								
					6288	238 (72.54)	243' (74.07)	5'	And Dyke	0.001	0.06	
		79.3%	78.33						Sericite Chlorite			
250	270'	100	.17	253.7 (77.32) - 257' (78.33) = Brecciated section								
				VERY BROKEN UP. 262 (79.91) - 274' (83.52) ONLY 6 PCS OVER 4"								
270	290'											
		100	.55									
			86.56	86.56								
				284' END OF HOLE								

[redacted]. **DIAMOND DRILL LOG** HOLE No. 87-46 14 Page 1 of 2

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
SKUKUM CREEK	105D/3	WH	1301'	358°	233'	FLAT (0)

Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed
	N/A	233'	0	JULY 13, 1987	JULY 14

Purposes TO TEST RAINBOW ZONE 1500 m LEVEL 30 m N.E. OF X-CUT # 2 | Drilled by CARON DIAMOND DRILLING | Assays by ACME LABS | Logged by RJR.

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0.0	20.0'			0.0-158.0 COARSE GRAINED GRANODIORITE.				
				DARK, GREYISH GREEN. MINOR HEMATITE.				
			39	MOD-STRONG PROPYLITIC ALTERATION OVERALL.				
				A FEW MINERAL BANDS OF POTASSIC ALT'N.				
20.0	40.0'			VERY MINOR PY FROM MAFICS				
			55					
				36.9: 6" ZONE OF V. PERVASIVE SMALL HEMATITE STRINGERS				
				37.9: 6" ZONE OF STRONG POTASSIC ALTERATION				
40.0	60.0'							
			35	43.0-52.0 RUSTY WEATHERING IN FRACTURES. SOME CLAY IN SHEARS AND FRACS.				
				MAIN FRACTURE SET @ 65° TO CORE AXIS.				
60.0	80.0'	90		MINOR SET AT 20°.				
			27					
				AFEW SMALL FRACTURE ZONES BETWEEN 70.0 & 87.0				
				MINOR HEMATITE STAINING AND MODERATE CHLORITIZATION				
80.0	100.0'		38					
				92.0-97.0 STRONGLY FRACTURED ZONE, MINOR CLAY. VERY BROKEN UP. MODERATELY CHLORITIC.				
			12					
100.0	120.0'							
			73					
				117: 2' FRACTURE ZONE ABUNDANT CHLORITE.				
120.0	140.0'							
				121.0: 3 FOOT FRACTURE ZONE WITH ABUNDANT CHLORITE.				
				125.0-155.0 FRACTURE ZONE: V. BLOCK. ABUNDANT CL & CLAY.				
			07					

DIAMOND DRILL LOG

HOLE No. 87-UG14 Page 2 of 2

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag	Au	
		90									
140.0	160.0			AS ABOVE							
		95	.20								
				158.0-172.2 BRECCIATED, SILICIFIED GRANODIORITE (CG)							
160.0	170.0'			MODERATE PHYLLIC ALT'N AFTER SILICIFICATION AND							
				BRECCIATION. CHIPS ARE STILL FAIRLY HARD, BUT	6289	162.5	167.5	5.0		.16 .002	
				MATRIX IS SOFT, GREENISH-TAN & CHLORITIC. ABUNDANT							
				QTZ-FSPAR XTALS NOT DISCERNABLE. MINOR PY.							
				FRACTURES @ 60° TO C/A. HAZEY CONTACTS TOP & BOTTOM.	6290	167.5	172.5	5.0'		.48 .014	
170.0	180.0'		.29								
		95		172.2-176.5 SHEAR ZONE							Native to Prep
				SOFT, CRUMBLY ALT'D. BANDS @ 60° TO C/A. V. CHLORITIC MINOR CLAY	6291	172.5	176.5	4.0'		.44 .017	
				176.5 - 179.4 BANDED BRECCIATED, CHLORITIC GRANODIORITE ± 4cm ANDESITE BANDS	6292	176.5	179.5	3.0'		.11 .016	
				179.4 - 181.7 WEAK BX, WEAK PROP. ALT. LT GRN-TAN RHYOLITE	6293	179.5	181.7	2.2'		.18 .011	0.006
180.0	190.0'	100		181.7 - 182.7 QZ-SX-BRX 15% AS, 10% PY, MINOR CL VTG SX.	6294	181.7	182.7	1.0'		9.19 - .342	0.325
				182.7 - 186.9 SLIGHTLY BX, RHYOLITE ± MINOR PY BANDS. FOLIATION @ 80°	6295	182.7	186.9	4.2'		.31 .007	0.017
				186.9 - 191.5 BANDED, SWIRLED, BRECCIATED, ALT'D GRANODIORITE / MG	6296	186.9	191.5	4.6'		.21 .002	
				ABUNDANT YELLOW QZ + WH CA STRINGERS. MINOR DISS PY							
190.0	200.0'		.54								0.001, 0.16 / 4.45 m
				191.5 - 201.5 MOD. PROP. ALT. SLIGHTLY CG GREY-GREEN RHYOLITE.	6297	191.5	196.5	5.0'	a	.12 .001	
				SLIGHT ALTD-BX ± YELLOW QZ BETWEEN CLASTS. ALMOST NO ROTATION							
				MINOR DISS. PY ABUNDANT DISS VFG LEUCOXENE	6298	196.5	201.5	5.0'	a	.16 .001	
200.0	220.0		.162	201.5 - 202.6 BANDED BX. GDR. NO VIS SX LOOKS LIKE F.W BANDS	6299	201.5	202.6	1.1		.60 .017	
				202.6 - 212.6 MOD PROP. ALT MG. GRN-GRY GRANODIORITE. MINOR PY	6300	202.6	207.6	5.0'		.05 .001	
				BAND OF AND. 212-213.9 AS BELOW. SLIGHTLY CRACKLED	6301	207.6	212.6	5.0		.01 .001	
				212.6 - 225.0 GREY-BLACK ANDESITE. WEAK-MOD. PROP. ALT'N.	6302	212.6	217.6	5.0'		.01 .001	
			.75	NON-MAGNETIC. ABUNDANT LEUCOXENE. MINOR CL. NO VIS SX. V. COMPETENT.							
220.0	240.0			ATEN FRACTS < 10° TO C/A. 5cm ZONE ± PY IN CA @ 218.5. 3cm CA VNS @ 220.8	6303	217.6	222.6	5.0'		.15 .005	
				225.0-233.0 MG. MED GRN-GRY GRANODIORITE MOD. PROP ALT'N.							
				V. COMPETENT. FEW FRACTURES @ 30 & 45° TO C/A MINOR PY							
			.38	233.0' END OF HOLE 87-UG14							
240.0											

[redacted] DIAMOND DRILL LOG HOLE No. 87UG-15 Page 1 of 3

Property SKUKUM CREEK	NTS 105 D3	Claim WH	Elevation 1301 M	Azimuth 002°	Length 268'	Dip -32°
Coordinates	Dip Tests	Advance 227.3'	Depth 147'	Date Collared JULY 14, 1987	Date Completed JULY 17	
Purposes TO TEST RAINBOW ZONE 1270 LEVEL 30M EAST OF X-CUT #2		Drilled by CARON DIAMOND DRILLING		Assays by ACME ANALYTICAL	Logged by R J ROBINSON	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0.0	20.0	95	.111	0.0 - 149.6 GRANODIORITE. COARSE-GRAINED, ALTERED, UNMINERALIZED. LT. GREENISH GREY TO DARK GREEN. ALTERATION RANGES FROM MOD. PROP. STRONG PROP, WEAK PHYLLIC, WEAK TO STRONG POTASSIC, WEAK TO STRONG SILICIC AND WEAK TO MOD ARGILLIC IN FRACTS AT DEPTH. AREA NARROW, STRONG CALCITIC HEMATITE BANDS				
20.0	40.0	100	.57	IN TOP 20 FT RUSTY FRACTS. 0-80 FT: FRACTS @ 40×65° TO CA				
				MOD-STRONG PROP ALT'N. 0-57.8				
40.0	60.0		.68	WEAK POTASSIC ALT'N 48-50				
				MOD-STRONG PROP. ALT'N TO 110 PROPT AS NOTED				
60.0	80.0		.49	THIN (CM) BAND OF APLITE OR CONCENTRATION OF VFG POTASSIC-SILICIC MATL FROM INTRN MELT				
80.0	100.0		.111					
				STRONGLY FRACTURED ZONE 89.0-91.0				
				91.0-93.8 WEAK TO MOD. PHYLLIC ALT'N				
			.119	94.6 THIN ZONE POTASSIC ALT'N 99.0 THIN BAND POTASSIC ALT'N				
100.0	120.0			100-101 BANDS OF CP-CL, THEN 1FT ZONE POTASSIC + STRONG SILICIC ALT'N.				
				110-147.0 STRONG PROP/WEAK PHYLLIC + ~30% MOD POTASSIC IN 6-10" BANDS + VEINS				
			46					
120.0	140.0							
			.46					

DIAMOND DRILL LOG

HOLE No. 87-46IS Page 2 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t	Notes Au Prep
140	160'										
			.46	149.6 - 192.0 mg GRANODIORITE							
				STRONG PROPYLITIC ALTERATION, VERY BROKEN UP MINOR PY							
				FRACTS @ 30° & 60° TO C/A MINOR DISS. PY							
160	180'			MED. GRN-GRY. WEAK ALTD BX.							
			.18	165: CLAYEY SHEAR + BANDED ZONE FOR .7'							
				169: 1cm. CA VEINS ± 50% PY							
180.0	190.0			181.5: .5' ZONE ± CA STRINGERS + 10% PY BLEBS							
				ABUNDANT (1-2%) CA STRINGERS.							
			.35								
190.0	200.0'				6307	191.7	195.7	4.0'	.01	.001	
				191.8 CG. GDR. MOD-STRONG PROP ALTN.	6308	195.7	200.7	5.0'	.02	.002	
				INCREASING ARGILLIC ± DEPTH							
				WEAK ALTD-BX AT TOP INCREASING TO STRONG BXX ±							
				ROTATION AT 60°C.							
200.0	210.0'		.20	199.4 VERY SHEARED AND BANDED GDR. CLAY + CHLORITE ABUNDANT.	6309 *	200.7	205.7	5.0'	7.35	.055	0.058
				VERY SOFT 3-5% PY							
				205.6 1" BAND VFG GNEISS 5% PY · 6% CL IN GDR							
				205.9 QZ SULFIDE BRECCIA. VERY SHATTERED + BROKEN UP	6310 *	205.7	209.9	4.2'	53.70	.480	0.455
				LARGEST PIECE 0.4'. 15-20% SX OVERALL. 8% AS, 5% PY, 5%	6311 *	209.9	211.4	1.5'	40.10	.145	0.138
210.0	220.0'			QL, SL and UNIDENTIFIED VFG MED. GREY MINERAL DISS. IN QZ.							
				211.4-215.4 MULTILITHOLOGIC BRECCIA ± BANDS OF QSBX	6312 *	211.4	215.4	4.0'	3.66	.132	0.166
				ALT'D + SHEARED. ABUNDANT CLAY. MOSTLY SMALL CLASTS.							
				215.4-228.0 MULTILITHOLOGIC BRECCIA. CLASTS OF ALT'D +	6313	215.4	220.4	5.0'	.94	.038	
220.0	230.0'		.58	UNALT'D GREEN + TAN RHY. GDR + QZ-SX BX TO 3 cm - MOSTLY							
				<1cm. IN MATRIX OF APHANITIC TO VFG DK GRNISH-GREY GRNDMASS.	6314	220.4	225.4	5.0'	.47	.025	
					6315	225.4	228.0	2.6'	.38	.055	
				228.0-229.7: V STRONGLY ALT'D, BANDED GDR. ABUND. EP, SE, CL. MINOR DISS PY							
230.0	240.0'			229.7-232.0 BANDED BX. ALT. RHY. MINOR SX	6316	228.0	233.0	5.0'	.55	.015	

DIAMOND DRILL LOG

HOLE No. 87 46 15 Page 3 of 12

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t	Natural Au Prep
				232.0-242.1 VFG MOD PROP ALT'D RHYOLITE: - MINOR BXX WITH VFG SX + QZ INFILLING BANDS OF QZSX TO 15CM CUTTING CORE @ ~ 65° FRACS @ 65°	6317	232.0	238.0	5.0	.42	.058	0.022
			.74		6318	238.0	243.0	5.0	1.34	.057	0.039
240.0	250.0			242.1-243.3 BXX V. ALT'D GDR + QZ SX MATRIX ~50% MATRIX	6319	243.0	248.0	5.0	4.43	.266	0.161
				243.3-247.5 BXX V ALT'D GDR & ML BX MATRIX · 80% MATRIX ML BX CONSISTS OF SMALL CLASTS OF GDR, RHY, QZ + SX IN VFG GREENISH-GREY MATRIX. ALSO LARGER CLASTS OF QSX AX TO 5CM	6320	248.0	253.0	5.0	.10	.008	
				247.5-248. F.W. BANDED ZONE. ABUNDANT V.F.G. SX. BANDS @ 50°	6321	253.0	258.0	5.0	.04	.002	
250.0	260.0		.62	248.0-255.8 M-CG GRANODIORITE. STRONG PHYLLIC ALT'N ABUNDANT CL, EP, CA, SE IN BANDS + DISS. BANDING @ 50° TCA	6322	258.0	262.0	4.0	.01	.001	
				MINOR PY. AFEW BLEBS + STRINGERS.							
				255.8-265.0 FG GRN-GRY ANDESITE. MOD PROP ALT. ABUNDANT CA. MINOR PY. XENOLITHS OF GDR AS ABOVE @ 258.0-258.5	6323	262.0	265.0	3.0	.02	.005	
260.0	280.0			259.4-259.8 + 262.9-263.5.							
				265.0-268.0 MOD PROP. MG LT GRN GRY GDR.							
			.83	268.0 END OF HOLE							

[redacted] DIAMOND DRILL LOG 13024 HOLE No. 87-UG-16 Page 1 of 3

Property	NTS	Claim	Elevation	Azimuth	Length	Dip
SKUKUM CREEK	105 D/3	WH	[redacted]	007° 014	309'	-45 -47

Coordinates	Dip Tests	Advance	Depth	Date Collared	Date Completed
	N/A	181.6'	250.0'		JULY 19

Purposes	Drilled by	Assays by	Logged by
TO TEST RAINBOW ZONE @ 1240 m LEVEL BELOW X-CUT #2	CARON DIAMOND DRILLING	ACME	R.J.R

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0.0	20.0			0.0-40.0 GRANODIORITE LT GRNISH GRY				
				FRACTS 60-80° TO C/A. FEW SMALL (<5cm) XENOLITHS				
			.28	THIN BANDS OF HEMATITE-RICH CA. AND SMALL HE STRINGERS				
				MINOR DES PY. 2 MINOR GRAPHITE SLIPS @ 52'				
20.0	40.0							
			.52	MINOR POTASSIC ALT'N 29-34'				
40.0	60.6			40.0-43.0 VERY DARK, GREENISH-GRY ALT'D ZONE MINOR CL SE.				
			.48	43.0-68.4				
				MOD POTASSIC ALT'N 52-55. AS TRACE OF MINOR HE @ 52.3'				
				MOD PHYLLIC 55-57 - CLAY SHEAR 57-58				
60.0	80.0		.57					
				STRONG PROP + WEAK TO MOD POTASSIC 58-68.4' BROKEN CONTACT @ BASE				
				68.4-73.0 FELD. PORPH ANDESITE DYKE BROKEN 70-71 DK GRN-GRY.				
				73.0-77.9 GDR AS AT 58-68.4				
			.37	77.9-95.9 FP AND. AS ABOVE + A FEW QTZ EYES TO 3mm MINOR CA.				
80.0	100.0			@ 81.5-82.7 KSPAR RICH COARSE-GRAINED XENO-BX CONTACT.				
				84.3-86.0 CGGDR XENOLITH POTASSIC ALT'N.				
				OVERALL 20-30% FSPAR PHENOS IN DARK GRN-GRY APHANITIC GROUNDMASS				
			.17	95.9-99.7 CG GDR MOD PROP ALT'N ABUNDANT CL/SE. AS ABOVE				
				+ FRACT @ 2-3° TO CA OTHERS @ 60°-70°				
100.0	120.0			99.7-115.2 FP ANDESITE AS ABOVE, BUT SLIGHTLY MORE				
				CA STRINGERS, LIGHTLY CRACKLED. FRACTS @ 65° + 90°				
			.19					
				115.2-118.5 STRONGLY POTASSIC ALT. CGGDR SHARP 70° TO 35° BASE.				
120.0	140.0			118.5-148.0 ANDESITE DYKE AS ABOVE.				
				MOD PROP ALT'N.				
			.74	ABUNDANT SE, CL, FP AT BASE.				
				SOME HEMATITE IN CA.				

DIAMOND DRILL LOG

HOLE No. A7-4616 Page 2 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Au oz/t	Au oz/t
				FRACTS MOSTLY AROUND 60° TO C/A.						
140.0	160.0			BROKEN CONTACT @ BASE						
				148.0-197.4 WEAK TO MOD PROP ALT CG GRANODIORITE.						
			.41	MINOR LOCALIZED POTASSIC ALT'N INCREASING ± DEPTH						
				FRACTS @ 60-70° TO C/A.						
160.0	180.0									
			.65	MINOR CRACKLE / ALTO BX.						
				A FEW FG. DARK XENOLITHS.						
				A FEW STRINGERS OF CL/SE SOFT MAFICS						
				MINOR SECONDARY CA THROUGHOUT.						
180.0	200.0									
			.53	1.5' STRONG POTASSIC ALT'N 191-192.5						
				197.4-214.1 GRANODIORITE M-CG. LT GREEN-GREY						
200.0	210.0			ABUNDANT CL. MODERATE SILICIFICATION AND STRONG PHYLLIC						
			.63	ALT'N.						
				FRACTS @ 40 x 60° BANDING VISIBLE						
				MODERATE BXXN A FEW THIN YELLOWISH QZ VEINS.						
				MINOR TO TRACE PY. SHARP CONTACT @ 80° TO C/A.						
210.0	220.0			212.6-2cm BAND FG BX. LT GRN-GRY, SOFT MUCH CHLORITE						
				214.1-230.9 INTENSELY PHYLLIC ALT'D GRANODIORITE. SHEARED ±	6330	214.1	219.1	5.0'	.16	.001
				BANDED. MOD. CRACKLED TO STRONGLY BXX. ABUNDANT CL SE, FP.						
				1-2% PY. THIN BANDS OF CA WITH GRAPHITE. FRACTS @ 25°, 45° &	6331	219.1	224.1	5.0'	.03	.001
			49	60° TO C/A. 1 FT CRUSH + SHEAR @ 214.5 & @ 218'						
220.0	230.0			X-CUTTING FRACTS. OF SAME AGE.	6332	224.1	228.9	4.7'	.03	.001
				1cm BAND of FG GRN-TAN BRX @ 228.9 @ 15° TO C/A						
									.0	
					6333	228.9	230.9	2.0'	.09	.001
				VERY BRIGHT, LIGHT GREEN AT END, V. BXX.						
230.0	240.0			230.9-250.4 RHYOLITE V. ALT'D. .4' BAND YELLOW GRN CLAY, THEN	6334	230.9	236	5.1' Lost	.21	.001
		80%		1' SOFT GREEN-TAN RHY, THEN .4' BANDED YELLOW-GRN CLAY. FOLLOWED						
		80%	.11	BY BANDED, YELLOW-TAN-GRY. RHY. V. BROKEN & BLOCKY. BANDING	6335	236.0	241.0	5.0	.01	.001
				15-20° TO C/A. BROKEN @ ALL ANGLES. 0 TO TRACE VIS SX.						
240.0	250.0	80%			6336	241	247	6.0'	CORE LOST .05	.001

DIAMOND DRILL LOG

HOLE No. 87-4GK6 Page 3 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t	
				CLAY ZONE 243-245 MINOR QA/GRAPH VEINS @ 246.5							
				MORE COMPETENT - LESS BANDED AT END.							
					6337	247.0	250.4	3.4'	.01	.001	
250.0	260.0			250.4-256.6 GRANODIORITE: EXTREMELY ALT'D & BXX.	6338	250.4	253.3	2.9'	.04	.001	0.001, 0.04/3.4*
				SOFT, DK GRN; SILICIFIED + BANDED. SMALL DYKE OF RHY @ 253-253.3							
		100	58	BANDS OF EPIDOTE + CL LOWER CONTS @ 15° TO C/A	6339	253.3	256.6	3.3'	.04	.001	
				256.6-273.3 ANDESITE GRN-GRY TO YELLOW-GRN. M-CG							
				ABUNDANT YELLOW QZ VEINLETS + FRACT FILLING MINOR ROTATION.	6340	256.6	260.0	3.4'	.02	.001	
260.0	270.0			NO VIS SX. SILICIFIED FROM 266-268.6 CRUMBLY + BRECC'D @ 268.6							
					6341	262.0	267.0	5.0'	.18	.006	
					6342	267.0	268.6	1.6'	.71	.021	0.011 Au 0.47 Ag/4.05
270.0	280.0				6343	268.6	273.3	4.7'	.21	.006	
				273.3-275.4 LT GRN TAN RHY MUCH QZ FRACT-FILLING 1cm SX VN @ 274-274.5							Native for prop. 0.012
		100	113	275.4-278.6 QZ SX BX 10-15% SX 6 PL, 6 AS 2 GL MINOR CLASTS OF GRN-TAN RHY, OTHERWISE ALT'D QZ. RPST.	6344*	273.3	275.4	2.1'	1.53	.023	
				278.6-280.3 TAN RHY ± 30% QSBX ~5% SX OVERALL SHARP CONT + BASE	6345*	275.4	278.6	3.2'	8.73	.187	0.187
280.0	290.0			280.3-282.4 OLIVE GRN ANDESITE DYKE CRACKLED.	6346*	278.6	280.3	1.7'	2.74	.075	0.055
				282.4-284.2 ARG ALT SHEAR ?GROUND SX? MUCH CLAY.	6347	280.3	284.2	3.9'	.31	.012	
				284.2-300.3 RHYOLITE BRECCIA ± 5% QZ SX MATRIX	6348	284.2	289.0	4.8'	1.19	.059	
				1-7% SX OVERALL. MORE SX @ 284.8, 287-290, DARK GREY							
				MINOR CA MOD ARG. ALT'D	6349	289.0	294.0	5.0'	.18	.009	
290.0	300.0	100	96	FG LAMINATED SHEAR ZONE 1 cm wide @ 294, 2cm wide @ 300.3'							
				BLACK FG MATRIX FOR 2m.	6350	294.0	299.0	5.0'	.08	.002	
				ALMOST TOTALLY UNFRACTURED. ABUNDANT CLAY OVERALL (2-3%)							
				BLACK GOUGE-FILLED SHEAR AT END OF ZONE. ARG ALT.	6351	299.0	303.5	4.5'	.17	.001	
300.0	310.0			300.3-308.7 GDR BX. ABUNDANT FP, SE, CL MINOR CA							
				TRACE SX PHYLLIC ALT'D TWO FRACTS @ 55°.	6352	303.5	308.5	5.0	.01	.01	
				304.8 5MM CA VEIN. MINOR HEMATITE. 70° TO CA. MINOR CA STR. // TO CA							
			77	308.7-309.0 MOD. PROP. ALT'D M.G. GDR. minor FP, CL, SE.							
	309.0			EOH							

DIAMOND DRILL LOG

HOLE No. 87-UG17 Page 1 of 4

Property SKUKUM CREEK.	NTS 105 D/3	Claim WH	Elevation 1302.3	Azimuth 015	Length 408	Dip -47°-56°	
Coordinates	Dip Tests NONE TAKEN	Advance 159.4	Depth 375.6	Date Collared JULY 19, 1987	Date Completed JULY 21, 1987		
Purposes TO TEST 1210 LEVEL 30 M E OF X-CUT #2	Drilled by CARON DIAMOND DRILLING	Assays by ACME ANALYTICAL	Logged by RJR				

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0.0	20.0			0.0 - 55.9 GRANODIORITE. CG MED GRY TO DK GRN-GRY				
				WEAK TO STRONG PROP ALT + MOD POTASSICS. FRACTS @ 20, 60 + 80°				
			37	ABUNDANT CA THROUGHOUT. RUSTY FRACTS 0-45' MOD. AUTO BXX				
				MOD. PROP 0-23				
20.0	40.0			23.0-.2' RED HEMATITE-STAINED ZONE. 5% CA.				
			117	STRONG PROP. 23-33 CRUMBLED + CRUSHED 33-36'				
				MOD PROP 33-55.9. WITH FRACT. INTRODUCED ZONES TO 5cm OF				
				MOD PHYLLIC ALT'N.				
40.0	60.0		31	BLACK XFRNO. 3cm @ 41.6'				
				MOD POT. ALT. 50.6 - 53.0 2cm WIDE BLACK FG. SHEAR ZONE @ 46.0'				
				55.9-60.5 FELDSPAR PORPHYRITIC ANDESITE DYKE. MOD. PROP. ALT.				
				PHENOS TO 3mm QZ EYES TO 4mm DARK GREENISH GRY. SHARP MELT CONTACT TO/B @ 55°.				
60.0	80.0		36	60.5-80.2 CG GDR AS ABOVE, BUT WITH MORE STRINGERS + FRACS.				
				PARALLEL TO C/A. MOST SHRS EARLIER CA + HE, LATER RUSTY				
				71-72- 2mm QA + HE VEINLET // TO C/A. 76.0- SOMEWHAT BANDED +				
				SHEARED. MOD CRACKLE.				
			58	CLEAR, CLEAN CONTACT @ 80.2. MINOR BRKN + MELTING OF GDR.				
80.0	100.0			80.2-113.4 ANDESITE DYKE				
				FSPAR PHENOS TO 4mm, QZ EYES TO 5mm STRONG PROP ALT'N,				
				ABUNDANT CA STRINGERS + SMALL FRACT-FILLING.				
			67	@96' SMALL TENSION GASH CA-FILLED				
100.0	120.0			@87.8-90.3 10cm WIDE MINERALIZED QA VEIN // TO C/A. IN VEIN: 15% P/3% GL 1% SP				
				MOD-STRONG AUTO BXX + QA FILLING + HEALING. POT ALT 108-110.5				
				113.4-129.4 CG GRANODIORITE. BLEACHED GRN-GRY TO APPLE GREEN.				
			44	MOD-STRONG PHYLLIC ALT'N. NARROW BANDS POTASSIC ALT'S				
				WEAK SILICIFICATION. MINOR CA + QZ VEINS				
120.0	140.0							
				129.4-132.8 V STRONGLY SILIC/PHYLLIC ALT MG GDR. STRONG BXXN.				
			36	132.8-147.0 MOD-STRONG PHYL/SILIC ALT. MG GDR. LT GRN GRY-LT GRY.				
				FRACS @ 65° TO CA				

DIAMOND DRILL LOG

HOLE No. 87-UG17 Page 2 of 4

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag 0/4	Au 0/4
				ROCK FAIRLY COMPETENT.						
140.0	160.0			GRADES INTO LOWER UNIT.						
				147.0 - 149.2 V.DARK - BLACKISH GREY GRADING TO ITE						
			.37	149.2 - 163.6 C.G GRANODIORITE PALE GREENISH-GREY						
				MOD PROPYLITIC ALT'N WITH ZONES OF INTENSE PHYLLIC,						
				MOD. SILLIC. MOSTLY V. HARD MINOR AUTO. BX. FRACTS @ 60°						
160.0	180.0			TRACE PY 2 APLITE DYKES 1cm wide 160-161						
			.58	163.6 - 166.0 DARK BLACKISH GREY ALT'D GDR. 1% PY.						
				166.0 - 167.5 STRONG PHYLLIC + SILICIC ALT'D MG GDR						
				167.5 - 172.0 FP AND DYKE SHARP MELT CONTACT AS @ 80.7.						
				172.0 - 182.7 BLEACHED, BRX, SILK. MG GDR. STRONG BRX 172-174						
180.0	200.0		.70	182.7 - 188.6 FP ANDESITE DYKE PHENOS TO 2 mm MOD MAFICS & MOD PROPAC						
				188.6 - 236.8 MG GRANODIORITE. BLEACHED GRN-GRY.						
				MOD PHYLLIC ALT'N. STRONG SILICIC ALT'N. ZONES TOTAL OF						
				MOD TO STRONG POTASSIC ALT'N. SOME ZONES V. BRECCIATED/SILICIFIED						
200.0	220.0		.47	POTASSIC ALT'D ZONE 213						
				FRACTURES @ 50 - 65° TO C/A						
			.19							
220.0	240.0			MORE SWIRLED "BANDED" THAN CRENULED OR FRACTURED						
				BLEBS OF K-RICH ? SEMS @ 226 - 228'						
				CL. FP. SX. QZ - MINOR PY + LEUCOXENE						
			.51	236.8 - 237.2 QUARTZ MONZONITE OR GRANITE STRONG SILICIC ALT.						
				MOD. BXX SAME ROTATION.						
240.0	250.0			LT. PINKISH TAN VERY BLEACHED. XTAL PATTERN ALMOST ERASED.						
				ABUNDANT CL. MINOR CLAY, MINOR SX. FRACTS 60 TO 70° BLACK SHEAR @ 248						
				F.G. BLACK MATRIX + SMALL (1-2 mm) CLASTS. 70° TO C/A						
				PROBABLY PHYLLIC ALT'N BEFORE SILIC.						
				MINOR ARGILLIC IN RECESSIVE FRACTS.						
250.0	260.0	95%		BROKEN - BLOCKY @ 249 - 250 + 252.5 - 253.8.						
				SHARP CONTACT AT BASE WITH SHEAR	6353	253.1	258.1		.20	.003
			.58	MINOR MOLY ON FRACTS + SLIPS.						
					6354	258.1	261.3		.17	.003
				258.3 - 266.0 SHEAR / BRECCIA ZONE BLACK, FG MATRIX SMALL GRAINED						
260.0	270.0			CLASTS @ 0M @ BASE. 1% PY FRACTS @ 70° ABUNDANT CLAY	6355	261.3	266.3	5'	.01	.001

DIAMOND DRILL LOG

HOLE No. 87-4617 Page 3 of 4

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t	
				260.8-261.3 BXX-SHATTERED CHLORITIC CLAYEY RHYOLITE. TOP CONTACT 60° BAX 45°							
				261.3-304.1 RHYOLITE. LT TAN TO LT GREEN GRAY.							
				VFG SLIGHT SILICIFIED APHANITIC GROUNDMASS.	6356	266.3	271.0	4.7	.15	.004	
				CA VEINLET @ 268' 4mm WIDE MINOR PY+CL							
270.0	280.0			FAINT BANDING VISIBLE ALMOST PARALLEL TO C/A	6357	271.0	276.0	5	.03	.001	
		100	.51	NO MINERALIZATION							
				MINOR, SHAT ZN SOME BXXD ZONES							
					6358	276.0	281.0	5	.02	.001	
				FRACTURES ORIENTED @ 45 & 65° TO C/A							
280.0	290.0			CLAYEY ZONE @ 280.4 & 283.5 - 285.0	6359	281.0	286.1	5.1	.04	.001	0.001, 0.9 42.2
					6360	286.1	291.2	5.1	.07	.001	42.9
		71	.21								
290.0	300.0			RHYOLITE AS ABOVE.							
					6361	291.2	296.3	5.1	.10	.001	
					6362	296.3	301.3	5.0	.11	.001	
				MOD BXD @ APP. ALT 298.0 - 301.2							
300.0	310.0				6363	301.3	304.2	2.9	.33	.001	Not Wash Prep
				304.2-305.4 - BRN BANDED MOD GOR STRONG BXXN MINOR PY							
		1	.56	305.4-308.9 RHYOLITE BRECCIA + QSX MATRIX	6364	304.2	308.9	4.7	13.90	.926	0.525
				5% PY, MINOR AS, GL SL. MINOR YELLOW QUARTZ CMTS @ END OF BXXN							
				308.9 RHYOLITE ONLY SLIGHTLY BXXD. MINOR - 5% QSBX. BASE CONTC 20°	6365	308.9	312.3	3.4	.68	.096	0.102
310.0	320.0			FRACTS @ 30 & 60° TO C/A. MINOR YELLOWISH QZ. SX VFG.							
				312.3-315.3 QUARTZ SX BX & MINOR RHY CLASTS	6366 *	312.3	315.2	2.9	37.40	.754	0.590
				315.3-316.6 RHYOLITE AS AT 308.9 WITH 5% QSBX MATRIX.	6367	315.2	316.6	1.4	15.10	.184	0.110
				316.6-324.0 HIGH GRADE QZ SX BX. 30-35% SX. 35-40% RHY.	6368 *	316.6	321.6	5.0	46.50	1.924	2.166
				25-35% QZ. SX: 35% PY, 35% AS, 15% GL, 15% SL MINOR TRACE CP							
320.0	330.0				6369 *	321.6	324.0'	2.4	48.80	1.580	1.525
		100	.45	324.0-326.6 BXXD BANDED RHYOLITE. MINOR SX. CONTACT FRACT. 65+80°							
					6370	324.0	326.6	2.6	4.78	.154	0.167
				326.6-335.4 SILICIFIED RHYOLITE. ABUNDANT WHITE VEIN QZ WITH	6371	326.6	331.4	4.8	2.20	.297	0.282
				3-5% SX QZ FRACT FILLING & PY. VEINS N 30% GL 70%							
330.0	340.0			PY/AS. UNIDENTIFIED VFG GREY-BLACK SX IN QZ. MAY RUN WELL.	6372	331.4	335.4	1.0	1.31	.147	0.203
				335.4-338.0 RHYOLITE WITH YELLOWISH QUARTZ FRACT-FILLING	6373	335.4	338.0	2.6	.45	.004	

DIAMOND DRILL LOG

HOLE No. 87-4617 Page 4 of 4

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t	
				TRACE TO MINOR SX							
				338.0-339.3 RHY BXX & YELLOW QZ INFILLING & VFG SX IN SPACES.	6374	338.0	339.3	1.3	.58	.003	
340.0	350.0			339.3-348.6 CLEAN, COARSELY GRAINED RHYOLITE. MINOR BXXN	6375	339.3	344.3	5.0	.15	.001	(.002)
		100	.65	YELLOWISH QZ INFILLING SLKY CY LATER DRY FRACTURES. TRACE SX							
				FRACTS @ 60° TO C/A	6376	344.3	348.6	4.3	.05	.003	
				LOWER CONTACT FRACTURE @ 20° TO CA							
				348.6-353.6 BXD RHY & 5% SX incl PY, AS, GL SX.	6377 *	348.6	353.6	5.0	.96	.172	
350.0	360.0		.21	EGGS & ENDS IN BLACK VFG MATRIX BX.							
				353.6-369.3 RHYOLITE BRXXD, SILIC ALT. ARG ALT.	6378	353.6	358.6	5.0	.12	.024	
				IN SOME ZONES PARK OLIVE GREEN							
		100	.57	353.6-356.5 STRONG BXX. YELLOW QZ INFILLED. 2-3 BXXN EVENTS.							
				356.5-369.6 MINOR ANTH BX WITH V.LT GRN QZ IN TENSION	6379	358.6	363.6	5.0	.05	.001	(.001) .008
360.0	370.0			DASHES							
				BANDED CHLORITIC/CLAYEY, MORE BXXD ZONE FOR LAST 2 FT.	6380	363.6	368.6	5.0	.11	.001	
				BANDED/SHARED @ 60° TO C/A							
			.22	BXXD CONTACT & LOWER UNIT.							
				369.3-376.3 LT GRY TAN RHYOLITE MINOR SX IN BANDS &	6381	368.6	373.6	5.0	.51	.093	.229
370.0	380.0			FRACT FILLING MINOR CHLORITIZED ZONES @ 55° TO C/A							
				GRADATIONAL CONTACT & LOWER UNIT.	6382	373.6	376.3	2.7	.62	.023	.027
		100	.68	376.3-379.5 RHYOLITE AS ABOVE, BUT 5-7% SX							
				MINOR BXXD QZ SX BX MATRIX IN RHY BX. ABUNDANT	6393 *	376.3	379.5	3.2	4.85	.423	.554
				SL/GL. ENDS IN FG BX BAND @ 20° TO C/A. TOP CNTC @ 15°							
380.0	390.0			379.5-382.5 BANDED F.P. RHYOLITE. BANDS @ 15-20° PHENOS TO 3mm	6384	379.5	382.5	3.0	.11	.030	0.022
				382.5-385.5 QZ SXBX & MINOR SWIRLED RHY BANDS 35% SX	6385 *	382.5	385.5	3.0	28.50	.519	.595
			.23	385.5-391.5= BANDED, BXXD, SHARED, MINERALIZED ANDESITE.	6386	385.5	388.2	2.7	.48	.021	0.021
				STRONGLY ALTD. 1-2% SX, MOSTLY PY. CA HEMATITE & PY. @							
				386.2, 388.2 & 390.5	6387	388.2	391.5	3.3	.23	.006	
390.0	400.0			BX CNTC & TOP, SHARP @ BOTTOM							
				391.5-395.5: GRANODIORITE M.G. DK GRN-GRY. ABUNDANT CA.	6388	391.5	395.5		.15	.006	
		100	.60	MINOR SX. MOSTLY PY. SLIGHT ALTD BX							
				395.5-408.0: GRANODIORITE. CG. LT GRN-GRY.	6389	395.5	400.5		.04	.001	
				ABUNDANT EPIDOTE BANDS. NO MAFICS VISIBLE							
400.0	410.0										
				FRACTS @ 45-65° NO VIS SX.							
			.24	GRAD CONTACT @ TOP. SLIGHT ALTD BX.							
			.71	408.0 END OF HOLE							

[redacted] DIAMOND DRILL LOG HOLE No. 87-46A Page 1 of 2

Property SKUKUM CREEK	NTS 105D/3	Claim WH	Elevation 1306.93	Azimuth 312°311.3°	Length 202	Dip O
Coordinates 70855.66N 77758.91E	Dip Tests NONE TAKEN	Advance 197'	Depth O	Date Collared July 23, 1987	Date Completed July 24	
Purposes TO TEST KUHN ZONE 1300 M LEVEL EAST OF X-CUT #3	Drilled by CARON DIAMOND DRILLING	Assays by ACME ANALYTICAL	Logged by R.J. ROBINSON			

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0.0	20.0	0.0	18.0	0.0-146.0 COARSE-GRAINED GRANODIORITE (QTMZ)				
		100%	.95	QZ IS GREYISH PURPLE. FSPAR STAINED GREEN & SALMON RED/PINK				
		100%		VERY HARD. MOST FELDSPARS STILL QUITE HARD.				
		80%		FRACTURES @ 45, 60 & 90° TO C/A. BLOCKY FOR FIRST 20'.				
		18.0	37.6	MINOR CA VEINLETS & SMALL FRACT FILLING.				
20.0	40.0		.42	WEAK PROPYLITIC & POTASSIC ALT'N. MINOR TO TRACE SY				
				CHLORITE ON FRACT. SURFACES. STRONG SILICIC ALT'N &				
				GREYISH-GREEN QZ & EP VEINLETS CUT CORE @ ~80° TO C/A				
		80%		1/2-1½ CM ACROSS. AVERAGE OF 1 EVERY 7" FT				
		37.6	55.7	43-49 EP-RICH ZONE ABUNDANT STRINGERS.				
40.0	60.0	100%	.65					
				58-60: SLIGHTLY MORE K-ALT'D.				
		55.7	73.7					
60.0	80.0	100%	.75					
		73.7	91.5					
		95%	.65	78-85: BROKEN BLOCKY ZONE				
80.0	100.0			MORE ABUNDANT CL & EP 83-84'. FLOODED ZONE. SMALL HEALED FRACT.				
				95-97 EP-RICH ZONE.				
		91.5	110.0					
		100%	.80	BARREN QZ VEINS TO 2 CM.				
100.0	120.0							
		110.0	128.5					
		100%	.75	117 STRONGER PROP. ALT'N. FELDSPARS V. GREEN.				
120.0	140.0							
				126. QZ, CL, EP RICH ZONE. THIN QZ VEINLETS & MINOR PY				
		128	147.2	MINOR YELLOWISH-WHITE QZ VEINLETS.				
		100%	.95	MOD-STRONG PROP. ALT'N TREND OF ZONE.				

DIAMOND DRILL LOG

HOLE No. [redacted]18 Page 2 of 2

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width		Ag oz/t	Au oz/t	
				MINOR ANTO BYXN OVERPRINT								
140.0	150.0			M7.5 - 5MM MILLIONS OF CARB + EP+PY								
				MOPE MOD + BXO TOENDS. GRAD. OCCUR'S.								
		—		146.0-148.2: GRANODIORITE: LT GRN GRY STRONG PROP SILICIC, MINOR PY					148.0			
				148.2-157.8 MIXED BRECCIA. VERY STRONGLY ALT'D + BXD	6397	148.2 45.17	153.2 46.70	1.53 4.27		.27	.013	HW 45.17 Nat'l Prep
150.0	160.0	95	.35	UNIT WITH GDR, ANDESITE + RHY. PROP + SILICIC ALT'N. YELLOWS +								
				GRNITT GY STRINGERS. ABUNDANT EP CL STRINGERS (2 GENS)	6398	153.2 46.70	157.8 48.10	1.4 m		1.00	.078	0.071
				<1% SX - MOSTLY PY. PY PRE OR SYN 2 156'								
				FRACTS ● 40 - 55°								
				41.58m	6399	157.8 48.10	161.8 49.32	1.22		.09	.001	
				157.8-159.0 BRECCIATED + SHEARED AND. RUBBLE 65° TO CA CONT 60° TO CA ABUND. CLAY								
160.0	170.0			159.0-165.1: BXD + SHEARED PALE GRY GDR. V. CRUMBLY. ABUNDANT CLAY	6400	161.8 49.32	165.1 50.32	1.6		.04	.001	
				+ CHLORITE. HEMATITE STAINING. LOSE CORE GOOD.								FW 50.32
		100	43	165.1-170.1 MED. GRN. GRY GRANODIORITE AS AT TOP	6401	165.1 50.32	170.1 51.85			.13	.001	
				OF HOLE. FIRST 2' SHEARED + CRUMBLY.								
170.0	180.0			MOD. STRONG PROP. ALT'N.								
				TRACE TO NIL SX. ABUNDANT EP. CL. SE.								
				FRACTS MAINLY @ 70 + 65° TO CA								
180.0	190.0			STRONG SERICITIC + MINOR BYXN.								
				MORE EP + CL 179 - 187.								
		95	.33									
				STRONG K. ALT'N 187.0 - 189.0.								
190.0	200.0											
				FELDSPARS V. GREAT + SOFT.								
200.0	210.0		0	202.0 END OF HOLE @ 97-UG-18								

[redacted] DIAMOND DRILL LOG HOLE No. 87-UG-9 Page 1 of 3

Property SKUKUM CREEK | NTS 105D/3 | Claim WH | Elevation 1306.98 | Azimuth 021° 020° | Length 251' | Dip FLAT HOLE 0°63°

Coordinates 70886.81N 77762.98E | Dip Tests NONE TAKEN | Advance 251' | Depth 0 | Date Collared JUNE 24, 1987 | Date Completed JUNE 25

Purposes TO TEST KUIIN ZONE 300m LEVEL 30m EAST OF X-CUT #3 | Drilled by CARON DIAMOND DRILLING | Assays by ACME ANALYTICAL | Logged by RT PUBINCU

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
0.0	20.0	0.0	16.0	0.0 - 148.0: GRANODIORITE MED-COARSE-GRAINED.						
				MOD TO STRONG PROPYLITIC ALT'N OVERALL ? ZONES OF STRONG PHYLLIC,						
		100	.38	MOD. TO STRONG SILICIC, WEAK TO STRONG POTASSIC AND WEAK TO MOD- ARGILLIC						
				MANY QZ FLOODED ZONES AND STRINGERS, SOME MINERALIZED.						
		16.0	32.7	100: 6" BAND OF FG K-RICH INTRUSIVE ? ASSIMILATED CL + STRINGER OF PY AT 85°						
20.0	40.0			13'-14' Qtz Vein 1½" across - discontinuous 0° to Core Axis						
		100	.49	285-287 Fracture Zone with many fractures. 291-294 moderate Phyllic						
				Alt'n overprints 1% Py, bleached + ~1% Hematite green. 297-305 Potassic Alt'n						
		32.7	49.1	319-325 Core is [illegible] Phyllic Alt'n of fgr matrix						
				[illegible] 341-351 mod.						
40.0	60.0	100	.55	black stringers at 65° to C.A. 343-345 zone of Phyllic Alteration						
				403-420 Potassic Alt'n 417-418.5 Brecciated strong Propyllitic zone						
		49.1	67.0	main fracture 65° to Core Axis 1% Py. 50.2-50.7 Bleached green Phyllic						
				Alt'n zone at 50.1-54.6 Zone of weak-moderate						
		100	.53	Silicic Alt'n 56.6-59.0 Brecciated bleached moderately						
60.0	80.0			silicically Altered 60.0-60.2 Alt'n Epidote Zone 1% Py .5% Gn. 61.5	6415	59.0	61.0	2.0'	.68	.013
				qtz-Sx-Cpy Veinlets 2% Py over 1cm core 64.7-64.9, 66.3 CA						
		67.0	85.6	Alt'n Fractures 67.9-76.9 Strong Propyllitic / Weak Potassic						
				Alt'n to Py in wafers 72.8 " Andesite Xenolith 74.7-75.4						
		100	.72	moderate Silicic Alt'n + Brecciated Fracture zone 76.4						
80.0	100.0			Moderate-Strong Propyllitic with weak Potassic Alt'n - continuous to 148.0,						
		85.6	104.1	Sericitization of Phenocrysts 84.6-88.0 Moderate Silicic Alt'n zone						
				88.1-88.4 Qtz-Epidote Veins 3 mm wide 91.6-91.9 Phyllic						
		100	.69	Alt'n blended green with Qtz Veins outlined at 50° to C.A.						
				94.0 Andesite Xenolith 1" wide						
100.0	120.0			101.0-107.0 Phyllic Alt'n Granodiorite of phenocrysts in a						
		104.1	127.1	grey matrix Silicified. 104.8-105.4 as above 105.4-105.7						
				Zone of strong Phyllic Alt'n - dark green with a Qtz cut Vein 11° to						
		100	.62	Axis of contact 45° to C.A. 106.7-106.9 Crackle Br Zone.						
				107.0-107.3 Weak Phyllic Alt'n. 111.7-111.9 Bleached Silicic Patches / Zone						
120.0	140.0	127.1	138.5	116.2-116.4 Epidote Qtz Veinlets 70° to C.A. 116-136 Zone						
				have a strong Propyllitic and weak-moderate Potassic						
		100	.47	Alt'n. Plagioclase are limy green - 15% show sericitization = potassically						
				altered matrix are C.A. 137.0-137.6 Zones of Potassic Alt'n.						

DIAMOND DRILL LOG

HOLE No. 87-4619 Page 2 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t		Au oz/t	
		13[illegible]	155.3	140 VERY SHATTERED & BXX'd MINOR PY. TR CP. SILICIFIED & STRONGLY FRACTURED. CA ON FRACTS. FRACTS 40°, 60° & SMALL TO C/A	6427	143.6	148.0		.09		.007	
		95	.32	HEMATITE WITH SOME CA. BANDED @ 60°								
				148.0	6428	148.0	151.7	3.7	1.17		.060	
				150 CRUMBLED FRACTURAL ZONE GDR. 10% QUARTZ VEINS & 20% CG PY								
				151.7 = MINOR SL. TR GL. MINOR DISS PY. U. BROKEN UP: PC 3-6 cm @ LONG AXIS	6429	151.7 46-24	155.7 97-46	4.0	.73	HW	.037	151.7
		155.3	172.2	11.N SHEAR ZONE. CALCITIC. CLAY SHEAR. MOD HOLED AT DEPTH GRADES INTO MIL BXX & CLASTS OF 156.7 BXX'd RHY, ALT'D RHY, QTZ. GREEN RHY, SULFIDES, MATRIX BLACK & PY-RICH INTRUSIVE CNT. & RHYOLITE - SLT BANDED & ALTD BXX'd,	6430	155.7 97-46	160.7 48-28	5.0	.30		.003	
				< 1% PY IN FRACTS. VFG CLAY(?), LT GRN-TAN. MINOR CHLORITIZATION.								
		160	.49	160 BNDG @ 15° TO C/A FRACTS @ 15° TO C/A. SOME CA IN FILLING.	6431	160.7 98-98	164.2	3.5	.58		.009	
				FRACTS WELL-HEALED. SHARP, CA-LINED FAULT CONTACT @ 70° WITH:								
				163.5 SX-MATRIX RHY BX, SX-MATRIX QZ BX, ↑ ML BX & BLACK	6432 *	164.2 50-05	165.2	1.0	.33		.341	
				165.4 VFG MATRIX. PY IN RHY, AS IN QZ. DISS PY IN ML. INTRUSIVE CNT. @ BASE	6433	165.2	169.8	4.6	.14	Native Au Prep	.004	
				CLEAN, VFG, LT GRN-TAN RHYOLITE. BANDED (SLIGHT) V. MINOR DKGN QV								
				170 FRACTS, OTHERWISE SLIGHT ALTD BXX'd. MINOR PY @ CA FRACT FILLING	6434	169.8	174.8	5.0	.21		.006	
				172.7 BANDING @ 55° TO C/A WHERE VISIBLE. TR GL IN FRACTS. FRACTURED CONTACT @ BASE:								
		177.2	186.6	AS ABOVE BUT LESS FRACTURED, LESS SX & MORE MELLOW-ISH. FRACT. CNT @ END.	6435	174.8	179.9	4.6	.58	0.015	.026	
				175.0 BANDED, SWIRLED & BXX'd DK GRN RHY FOR 1.5' AND ANDESITE TO BASE.								
176 4'	180	100%	.30	176.4 FT. V SHEARED & SOFT. 1-2% VFG DISS PY IN AND. CA INFILLING.	6436 *	179.9 54-48	180.5 55-02	1.1	19.20	1.792	1.850	
				179.4 SHEAR CNT. @ 80° TO C/A.								
180 3.5'	183	100%	.32	180 180.5 QUARTZ SX BX. FROST HALF CRUSH, 2ND HALF GL RICH. 50% SX.	6437 *	180.5 55-02	183.5 55-16	2.5	4.28	0.291	.172	8.6
				FRACTURED, SHEARED - BXX'd DK RHYOLITE & CLASTS - FRAGS OF QSB. BNDG								
183 2.5'	186	83%	0	PARALLEL TO C/A. OVERALL 1-2% SX. GRAD. CNT. @ BASE.	6438 *	183.0 55-28	186.0 56-40	3.0	.145	0.041	.035	.406 8.58
				184.7								
				186.1 LIGHTER RHY BX & ONLY MINOR DISS PY. FRACTURED CONTACT @ END.	6439 *	186.0 56-40	188.0 57-20	2.0	19.45	0.435	.459	
186 1.6'	188 80%	186.6	205.2	QZ SX BX IN ? GNR ? (V. ALT'D). ABUNDANT LEAD OXIDE COATINGS.	6440 *	188.0 57-20	191.0 58-20	3.0	3.03	0.251	.217	11.60
188 1.0	191	30%	0	190 U. BROKEN UP CA ON FRACTS. ~30% SX. MOSTLY PY.							.357	
191 4.0'	195	100%	.16	191.0 MUDSLIP, MISLATCH, HIT WATER IN FAULT. SHEAR ZONE V. CLAYEY,	6441 *	191.0 58-20	195.0 59-44	4.0	1.24	0.060	.049	7.00
				SHEARED ALT'D ANDESITE. ABUND. CA, CL. CLASTS & FRAGS OF QZ SXBX								
195 2.5'	197	100%	.14	1% DISS PY. LOWER CNT @ 60° TO C/A, CLAY BAND.	6442 *	195.0 59-44	197.0 60-05	2.0	.92	0.073	.077	0.204
197.09'	198	100%	.10	196.9 RHYOLITE. SLT GR. DK GRN-GRY. SHEARED, BANDED, BXX'd.	6443	197.0 60-05	201.0 61-24	4.0	.73		.003	
198 2.7'	201	90%	.15	200 STRINGERS OF QZ CLEP. V STRONG PROP. ALT'D. BANDING								
				@ 70° TO C/A, FRACTS @ 20 & 60° TO C/A	6444	201.0 61-24	204.5 62-32	3.5	.09		.001	
201 4.2'	205	100%	0	204.4 LOWER CONTACT SOLID @ 65°								
		205.1	223.5	ANDESITE. DK SLT GRNISH-GREY. STRONG PROP. ALT	6445	204.5 63-36	209.5 64-96	5.0	1.11		.016	
				MINOR DISS. PY. ITCO CA STRINGERS, MOD BXX'd & QZ SX BX								
			.62	210 MATRIX INFILLING. <5% TOT. SX. SHARP CNT @ BAK	6446	209.5	213.5	5.0	.56	0.033	.050	
				210.7 M.G. GDR. STRONG PROP. ALT'N, BXX'd & SHATTERED. MOD CLAYEY								

DIAMOND DRILL LOG

HOLE No. 87-46-19 Page 3 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t	Natural Au oz/t
				213.8 MOD. CALCITIC OVERALL. NOT FRACTURED TRACE DISS PY SHARP CNT @ END	6447*	65.0 213.5	216.0	2.5	2.67	.252	0.685
				QZ-SX-BX IN ANDESITE. MOSTLY QS-U.WHITE AND. 15-20% SX	6448*	216.0	219.3	3.3	3.68	.199	0.134
				MOSTLY VEG PY+AS MINOR SL, GL, CP. MOD. CALCITIC. BASE CNT SHARP @ 45°	6449	219.3	227.0	2.7	.25	.035	0.039
				227.0 ANDESITE DIKE BND, SHEARED, FRAGS OF GDP WALL, SLT BXED. LOCALLY PART SILICIFIED. IRREGULAR @ 75° TO C/A MINOR VEG DISS. PY.	6450	227.0	226.1	4.1	.11	.014	
		235 241.8		SILICIFIED, BANDED, SLT BXED RHYOLITE + GDP. ABUNDANT LOCALLY PART SILICIFIED.							
				226.1 CA. DISS + IN VEINLETS + STRINGERS. CLASTS + FRAGS OF GDP IN PART.	6451	226.1	231.1	5.0	.01	↑ FW.001	68.92
				230 LT. GRY, M-F.G SILICIC ALT'D GRANODIORITE.							
		100	.82	MINOR BANDING @ 70° TO C/A							
				MINOR AUTO BX.							
				FRACTS @ 60-70° TO C/A.							
				MINOR DISS. PY							
				240 ABUNDANT QZ, CA, FP, CL.							
		241.8 251.0		CL COMMON ON FRACTS, MORE PY ON FRACTS.							
				FELDSPARS SLIGHTLY GREEN.							
		100	.80								
				250							
				251.0 END OF HOLE # 87-46-19.							

OMNI RESOURCES INC — DIAMOND DRILL LOG — HOLE No. 87-4420 — Page 1 of 3

Property SEYMOUR CREEK	NTS 105D/3	Claim WJ1	Elevation 1306.07	Azimuth 021°.8°	Length 252'	Dip -34° -30.7°
Coordinates 70856.44 N 77762.88 E	Dip Tests NONE TAKEN	Advance 208.9'	Depth 1409'	Date Collared JUNE 25, 1987	Date Completed JULY 20	
Purposes Test Kuhn 3/4 EAST of main x cut	Drilled by CARON DIAMOND DRILLING	Assays by ACME ANALYTICAL	Logged by VT / RTR.			

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width
0.0	17.5	100%	57	0.0 - 156.5' GRANODIORITE: MEDIUM-GRAINED				
				LT GRY TO DK GRN-GRY STRONGLY ALTERED ABUNDANT FG				
				K-RICH ZONES. HAS A PINK [illegible] IN MTX OF				
				ZONES. Plags light dark green, mafic sericitization and most slightly chlor				
17.5	35.6	100%	68	Black veinlet 2mm wide 20° to C.A				
				21.0-24.5' Small zone of Potassic Alth fg many small [illegible] veinlets				
				+ Qtz veinlets				
				30.7-32.0 - almost completely altered to a green grey colour Gdr				
				texture barely visible				
35.6	55.0	100%	65					
				44.1 ± 1" el Brecciated Gdr with Qtz fillings and 1% Py				
				+ Py for. Sil after 1/16" Qtz veinlet 2mm wide 70° to C.A				
				Slight Crackle Breccia Mtx 1/10.0-50.0				
55.0	72.7	100%	71	62.0-62.6 Crackle Breccia Gdr 62.6-66.0 [illegible]				
				with 1% Qtz veins				
				66.2 [illegible] 2% Py 20° to C.A				
				68.0 1" Porphyritic Veinlet 30% Qtz, 62.5 Gdr				
72.7	91.6	100%	66	Crackle Br [illegible] Calcite filling Dark green zone 71.8-73.7				
				73.6 - Numerous hairline Veinlets of Qtz, 76.1 Potassic Alth intensifies 79.0				
				Alth of [illegible] with more Qtz veinlets				
				89.0 Green Propyllitic - Weak Phyllic Alth with 3 inch zones of intense				
				Potassic Alth. Much of this core has a lighter weak Alth Potassic Silicic				
91.6	109.4	100%	88	92.9-93.7 - small zone of intense Potassic Alth also at 97.3-97.5.				
				97.1 Chert Xenolith.				
				102.0-104.2 Zone of intense Potassic Alth.				
				107.6 1" Xenolith fine grained Gdr				
109.4	127.8	100%	82	109-113.5 Zone of Strong Potassic Alth + Potassic				
				114-116.2 Abundant Qtz veins [illegible]				
				119.6-123.5 Gdr altered to [illegible] Propyllitic Alth				
				122.0 1" Aplite [illegible]				
				126.5 1" [illegible] Xenolith				
127.8	145.8	100%	87%	Propyllitic - Weak Phyllic Alth with more Silicic Potassic				
				Plags - dark green [illegible]				

OMNI RESOURCES INC — SKUKUM CREEK DIAMOND DRILL LOG HOLE No. 87-46Z0 Page 2 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
				140 144.6-144.8 Crackle Cgl with Sphalerite matrix as above						
145.8	164.4	100%	81							
147	152	100								
152	157 (5)	100		156.5 1"=10' Scale change (4.5') GRANODIORITE wk bleaching, silicification, ARG Alt'n, minor plag Alt, CHL & Occ. QTZ-SUL VLTS @ 60° to tc. (1) 1.5 cm QTZ-SUL VEIN 15° @ 45° to CA 160 START OF H.W. KUTH ZONE GRANODIORITE 49.07	6453	156.5	161.0	4.5	.06	.009
157	162 (5)	100		Mod GR str. Alt. GRANODIORITE, silicification, CHL Alt Occ pristine Qtz Eyeballs wk 10% QTZ-SUL VLTS 1 cm wide @ 45° PY, ASPY (?) 30% dark grey mottling for 1.5 m intensity of Qtz stockwork / calcite VLTS & SULPHIDES increasing 166.4-170.8 to 25% w/ disseminated PY, ASPY to 10% Calcite Fracture and Alt'n @ 50-55° to Core	6454	161.0	163.3	2.3	.08	.005
162	167 (5)	100			6455	163.3	166.4	3.1	.74	.007
167	172 (4.9)	100		170 SHARP 55° CNT 7.10% T.3 (3.6') QTZ-SUL-BX 6% PY, TR-SPH, TR ARSPY, MOST Filling fractures 5070 BX w/ Intermingled crackle BX, Cemented & Silicified, Intc 55° 174.8 FGT w/CAL. CONTACT SHP @ 55° w/ 4" Andesite BX 5-7% (2.7') MINOR L. BX of Andesite Phyolite Dike matl, QTZ Vein, 55° 177.0 cut by (2) late stage Hydro BX w/ QTZ-Calcite fillings 3% TS. BX is cemented to subangular	6456	166.4	170.8	4.4	1.71	.020
172	177 (5.1)	100		180 (5.0') STR ALT GRANODIORITE - cut by numerous QTZ/Calc/SUL Veinlets w/ overlapping halos of PY, Heavy fracture of chl & QTZ. Calc @ 30° to Core.	6457	170.8	174.5	3.5	.43	.003
						174.5	177.0	2.1		
177	182 (4.9)	98		182.0 SHP 60° CNT 3-5% T.2 183.9 (4.9') QTZ/SUL/BX w/ 60% Dk. matl. crossed and Brecciated, cut by chl late Calc CNT GRADATIONAL @ 50° 6-8% T.3-5% (4.1') Alt. str. QTZ-Fld, CHL GRANODIORITE cut by QTZ 188 late Calc 3-5%	6458	177	182.0	5.0	.29	.006
182	187 (4.9)	98			6459	182	183.9	1.9	1.01	.010
					6460	183.9	187.0	3.1	.29	.001
				190 (2.7') w/ GRANODIORITE w/ 25% QTZ/SUL/BX, str. CHL	6461	187	188	1.0	.06	.001
				192.8 192.0 (1.3') of FAULT CLAY (Core Loss) @ 40°		188	189	1.0	.35	.008
187	192 (5.0)	98		192.0 (1.3') of FAULT CLAY (Core Loss) @ 40° 68 T.3. 45° Clay seams normal to the main fault.	6462	189	190.7	1.7	.27	.001
					6463	190.7	192.0	1.3	.20	.004
192	197 (4.8)	98		197 Sheared BX GRANODIORITE, INT ARG-PROP ALT & FAULT CLAY @ 40° to Core w/ Pots Normal to Shear	6465	192.0	197.0	5.0	.05	.001
197	202	100		202 Crackle [illegible] SCALE CHANGE 1"=20' [illegible] up to 2mm wide Chl, [illegible] Veinlets Clear Qtz [illegible]	6466	197.0	202.0	5.0	.08	.001
					6467	202	207	5.0	.01	.001
					6468	207	212	5.0	.18	.001
				zone 209.2 [illegible]						
201.3	218.5	100	46	220 220.1-220.5 [illegible] Cgl. Intensive					w/ 3% Py [illegible]	
				225.0 5cm Qtz Vein 15° to CA [illegible] w/ 1% Py 224					3% Py [illegible]	
				230 Pink Clasts 2 [illegible] 230.2 with Qtz Veinlets						
				ANDESITE DYKE 233.8-235.4 crackled with Qtz						
218.5	236.2			238 Fillings & Veinlets upto 3cm wide tr Py.						

FW 58-73m

DIAMOND DRILL LOG

HOLE No. 87UG-20 Page 3 of 3

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	
238	252			Granite Breccia with fragments of Ch. Cat Alter					
				Fractures at 10's 70° to CA					
				248.0 - 249.2 Fractured and Qtz. By 10° to Core axis					1 Qtz.
				249.2 - 250.3 Band of Alter. Pk. green grey with Qtz. By					
				252.0 END OF HOLE					

AURUM GEOLOGICAL CONSULTANTS INC. — **DIAMOND DRILL LOG** — HOLE No. 87-062 — Page 1 of 3

Property SKUKUM CR.	NTS 105 D/3	Claim WH	Elevation 1306.0	Azimuth 021	Length 317'	Dip -54°
Coordinates 70856.9N 77762.9E	Dip Tests N/A	Advance	Depth	Date Collared JULY 27/87	Date Completed JULY 29/87	
Purposes TO TEST KULAN ZONE @ 1240m level below DDH 87-19		Drilled by CARON, D.D.		Assays by ACME	Logged by VT/JBR	

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	
				0-12.8 ALTERNATING GRANODIORITE+Quartz MONZONITE contacts not definite. Strong Propyllitic - Weak Phyllic Alt'n. Plag = Sur. - med grain					
		100	42	mafics - Chl where visible a/s tr. Py. Slight Potassic Alt'n in Plags of Gdr.					tr. Py from mafics.
				12.7-13.4 Zone of Intense Potassic Alt'n. in Med gr. Gdr. Med. gr. Gdr with					
				weak Phyllic Alt'n. extends to 20.2. 60° to CA. C. gr. QMn. Alt'n as					
				above					tr Py from mafics.
		95	40						
				32.6 - 39.5 Strong Propyllitic Alt'n with a later moderate Potassic					
				Alt'n stage. Plag + Sur - n° Secondary Mafics. 39.5 - Mafic rich GRANODIORITE					
				Chl Alt'n mafics. ¼" Qtz veinlet 90° to CA at 43.2, 43.3 Strong					
		95	42	Propyllitic Alt'n Rock very dark green due to chl Alt'n - rock very broken up					
				to 51.0 - continues to 53.7.					
				53.7 - 58.6 Moderate Potassic Alt'n. 57.2 Epi Alt'n					
				Chl Alt'n of a Mafic rich GRANODIORITE 61.4 - 61.8 Andesitic Xenolith.					
				white bands of Silicic - Alt'n upto ½" wide. Small Patches					
		100	85	of Potassic Alt'n continuous to 83.1.					
				83.1 - 88.5 Moderate - Strong Propyllitic Alt'n.					
		100	52	Chl + weak Ser. Alt'n.					
				88.5 - Moderate Potassic Alt'n - core bleached orange					
				89.6 - 90.1 Qtz veinlets 2mm wide 30° to 40°					
				1" 94.5 And. Xenolith. 94.6 - 97.0 Weak Propyllitic + Potassic Alt'n.					
				97.0 - 104.5 Moderate Propyllitic Alt'n Chl + Epi, some Ser with Potassic Alt'n					
		100	68	and Chl stringers at 40° to CA. 104.5 - W. - moderate Chl					
				Alt'n + Epi in small patches Potassic Alt'n in Feldspars along					
				small bands upto 2" wide in C. gr. Gdr mafic rich.					
				111.6 - 112.3 Weak Potassic Alt'n also 118.4 - 118.8					
		100	72	119.3 - 122.2 Epi Abundant 122.2 - 125.7 W. Potassic Alt'n					
				slight bleaching. 125.7 - Strong Epi Alt'n over first 2" with a Qtz					
				Veinlet 2.5mm wide followed by moderate Epi + Chl Alt'n.					
				127.1 - 127.6 Med gr. Gdr with a grey colour. 129.6 - 131.2 Moderate					
				Propyllitic Alt'n with Quartz flooding. Veinlets upto 1cm wide					
				at angles 20° - 70°					

DIAMOND DRILL LOG

HOLE No. 87-462L

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag oz/t	Au oz/t
		100	.84	132-137.8 W. Altn- both potassic & Propylitic with bands of intense Epi Altn up to 4 cm wide 143.7 Epi Altn with Cst 1cm wide 40° to CA. 147.0 - 149.2 Moderate Propylitic Altn (Chl. Epi minor Ser.) Also Potassic Altn. continuous with Chl Altn.						
		100	.78	162.2-162.4 1cm bands of intense Potassic 163.2-1" Banded of Epi-Chl 50° to CA with Cst veinlet 2mm, Bands of Epi Altn. 167.5-168.0, 170.3-170.5. 171.5-172.3 Rock bleached to a dark green.						
		100	.86	Weak Propylitic Altn. 184.0-196.0 Slight Potassic Altn. and Epi Altn.						
		100	.85	195-196.3 Intense Potassic Altn. zone bleached orange. 198.5 - Chl + Propylitic Altn. (Moderate Propylitic with 1cm bands of strong alteration 60° to CA. 209.5-209.5 bleached zone to a light						
		100	.90	Alteration from K to Chl mafic Rich Break Interchon of MAFICS 2 cx 40° to CORE						
2	232			232 SCALE CHANGE 1":10' Car MAFIC RICH GRANODIORITE AS ABOVE						
232	(5.0) 237	100		235 CONTACT DIP 40° AT 1.5cm CM SITE (26') Car. GRANODIORITE STR PROP-ARG ALT cut by 5mm QTZ+CARB VITS 2-4 mm. more in CONTACT ZN, 2-3% DISS PY	6469	230	235	5.0	.05	.001
					6470	235	237	2.0	.14	.001
				238 Car GRANODIORITE w/o BX. GRADATIONAL CNT	6471	237.0	238.5	1.5	.016	.001
237	(5.0) 242	100		238.5-245 (6.5') HIGHLY ALTERED F. Gr. GRANODIORITE AUTO BX TO CRACKLE BX. Numerous 5mm Qtz, Carb vits 1-5mm could be alteration destroying Fe bearing (Calcic + mafics) ID & dilute following contact. 240.5-245 strong limonite & vits N to 60°	6472	238.5	243.5	5.0	.07	.001
242	(4.5) 247	90		245 2MP 90° ENT W/ 4" OF MULTI LITHO FAULT BX (1.5') Qtz/SULFIDE BX, cut by Fe-Chl, Carb, Qtz Vnd Bx 2-5% TS/PY 246.8 FRT CNT 1.5" CLAYS @ 30° (1.4') mixed Multi Lithic Qtz/SULFIDE BX, cut by Fe-Chl, Qtz Vnd Bx 248.2-	6473	243.5	246	1.5'	.11	.001
					6474	245.0	246.8	1.8	.37	.036
					6476	246.8	248.2	1.4'	.26	.009
247	(5.0) 252	100		(2.8') Green Qtz Rhyolite BX, plus FAULT BX 40° Crush, subrounded Qtz Frags, w/clay, Fe, dark grey-black Fill filling. 250.0-252 STRONG FAULT @ 35° 2MP CLAYS Crush, Black Grains sulfides (2.2') Qtz/SULFIDE BX subrounded-sub angular, 2MP, Chl, 2x stockwk filling 252.1	6476	248.2	252.0	3.8'	.06	.001
					6477	252.0	253.0	1.0'	.01	.001
					6478	253.0	254.1	1.1'	.11	.001
252	(5.0) 257	100		Alt Car, Qtz Fld Granodiorite Bx cut by Qtz vits 1-3mm 257 258.1 (0.1') mafic dyke/sill BX's Granodiorite Bx w/	6479	254.1	257	2.9	.05	.001
					6480	257.0	258.1	1.1'	.04	.001

7468

DIAMOND DRILL LOG

HOLE No. 87-463A

Interval From	Interval To	Rec'y %	RQD	DESCRIPTION	Sample No.	Interval From	Interval To	Core Width	Ag g/t	Au g/t
	(5.0)	100			6481	258.1	261.0	2.9'	.01	.001
257	262			(2') ANDESITE DYKE Auto 2x plus 6" Hyd 3x as Matrix, Lt Grey 8x						
	(4.5)	98		10R 7/2, Gr8 vns 1-3mm w ±1/cm Alt Mt. 1-2% Pt	6482	261.0	263.0	2.0'	.20	.001
262	267			(3') ALTERED GRANODIORITE 8x Mt & Pt 25%	6483	263.0	266.0	3.0'	.04	.001
				266 (2') ANDESITE DIKE - Auto Brown, 4YR, 6/2, 1-3% Pt, 268 5YR 6/1, 30° to Fabric Pits	6484	266.0	268.0	2.0'	.07	.001
	(4.5)	98		6" int chill margin in Granodiorite at 20° ant						81-08
267	272				6485	268.0	272.0	4.0'	.13	.001
272	277 (6.0)	100		Contact Sharp at 30° Slightly Cracked						
277	282 (5.0)	100		At 277.1 1" Sulfide Veinlet at 30° to Axis						
	(5.0)			277.3-277.4 Donut Shaped Pyrite Veinlet						
282	287	100								
287	292									
292	297			Andesite Dyke 296.6-298.3 - Cracked with Many Cc Fillings Veinlets 2-3mm Int. Dissem Mt & Py.						
297	302									
302	307			302.2-305.7 Silicified Med gr Granodiorite Cut by Sev Cc Veinlets Contact at 305.7 60° to CA						
307	312			305.7-312 Calcite-Hematite Altered with Sulphide						
312	317			Small Carbonate Fillings in Fractures						
				EOH 317'						

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	SKUKUM CREEK	HOLE No.	87-UG22
COORDINATE N.	7095 4.67	DEPTH	211'
E.	77766.96	AZIMUTH	155° 156°
ELEVATION	1306.86	INCLINATION	+32° +35°
DATE STARTED	JULY 29, 1987	DRILLED BY	CARON DIAMOND DRILLING
COMPLETED	JULY 30, 1987	ASSAYED BY	ACME ANALYTICAL LABS.
HOLE SURVEY	SEPT 4/87	LOGGED BY	R.T. ROBINSON

Reason for Drilling: TO TEST KUHN ZONE ABOVE HOLE # UG-19.

Explanation of Results:

LEGEND

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
1					SCALE: 1" = 20' GRANODIORITE: Coarse gr. Mafic Rich. Strong Propyllitic Alt'n. Plags- light green-Sericite or Orange-Kspar Alt'n. Mafics—chlorite. Many zones strongly Potassic Altered bleached to an orange colour. 0-3.0 Gdr with Pot. Alt. Epi. 30-37.								
17.2			95	.17									
2					Gdr- Propyllitically Altered. Chl, Epi minor Ser. Aplite dykes. @17.3 20° to C.A. ½" wide. 19.0 45° to C.A. ½" wide. 21.0 40° to C.A. ½" wide. 21.8 40° to C.A. ½" wide. 31.1 50° to C.A. ½" wide. Cct Veining between 26.0-32.0 upto ½" at 40° to C.A. 32.9- Intense Potassic Alt. bleached orange Gdr texture barely visible very broken ground. 34.0-42.0			20					
34.1			100	.54									
3					Strong potassic Alt'n. 45.6-62.4. Epi on fractures.			40					
51.4			95	.16									
4					And 60.4-60.9 cm 70° to C.A. cct veinlets. 62.4-76.8 Intense Potassic Alt'n. with Qtz flooded zones.			60					
66.4			95	.42									
5					71.8-79.3 Strong Propyllitic Alt'n. Epi, Chl + some Ser. 79.3-82.0 Strong Potassic Alt'n. with Qtz flooding 81.0-81.8 82.0-90.3 Gdr with Strong Propyllitic Alt'n. Chl+Epi. Alt'n. with Cct. veinlets 90.3-102.0 Intense Silica Alt'n. Rock is bleached- light grey			80					
87.0			90	.41									
6					102.0- Quartz Monz. Chl+Epi minor Ser. Alt'n.			100					
103.0			95	.20									
7								120					

SCALE CHANGE

OMNI RESOURCES INC. PROJECT SKUKUM CREEK DIAMOND DRILL HOLE No. 87-11G22 Sheet 2 of 3

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE (SCALE 1"=10')	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T Ag	
1221	125			.08	GDR CONT'D.									
8	127	4.0	100	.67										
					HB PORPH ANDESITE. CA FRACT. FILLING. DK. GREENISH GRY. MOD. PROP ALT. PHENOS TO 2 mm. BROKEN CONTACT AT BASE.	TRACE VFG DISS PY.								
	132	5.0	100	.45	GDR. MOD. PROP. ALT'N. M-C.G. ABUNDANT CA VEINS. GREENISH QUARTZ + CALCITE VEINLETS. AT ALL ANGLES TO C/A. FRACTS. @ 90 + 55° TO C/A. WELL HEALED SHEAR @ 90° @ BASE.	TRACE F.G. DISS PY.		130						
	137	4.2	84	.62	GRANODIORITE. MOD-STRONG PROP ALT. MOD. BXXD. MED. GRAINED BANDED BXXD SHEAR AT BASE 65° TO C/A (BANDED @ 70° TO C/A)	135.0 TRACE DISS PY		135						
1384					BANDED, BRECCIATED GDR + RHYOLITE CLASTS IN EPIDOTE + CL MATRIX. MG OLIVE GRN. ANDESITE OR RHYOLITE DYKE ? TONGS 10° ALT'D GDR TO 2 mm. SHEARED. 0.4' BAND OF MINERALIZED QUARTZ. ABUNDANT CA. STRONG PROP. ALT'N. LAST FOOT STRONG SHEAR + CLAY + CRUMBLED AND. SHARP LOWER CONTACT	137.1 TRACE DISS PY		137.1	6539	137.1-141.9	4.8'	.029	.24	HW SHEAR 43.25m ↓↓
9	142	4.2	84	0		140.9 MINOR DISS PY OVERALL 0.1% TO 2% PY + 2% MAGNETITE DK GRY MINERAL		140						
					RHYOLITE. LT GRN-YELLOW INTERBANDED WITH DK. ANDESITE. AND MINOR MINERALIZED QZ. AFEW SMALL FRACTS. FILED WITH. GL and PY. CORE TOO BROKEN TO DETERMINE FRACT. ORIENTATION. BANDED GRADATIONAL CONTACT @ BASE. MOD. PROP. ALT. BANDING @ 35° TO C/A.	MINOR GL + PY FRACT FILLING		145.8	6540	141.9-145.8	3.9	.005	.08	
	147	2.9	58	0					6541	145.8-149.0	3.2	.001	.04	
					0.3' BANDED GDR. THEN DK GRY. ANDESITE DYKE ? XENOS OF STRONG PROP ALT'D GDR. ABUNDANT CA STRINGERS. SMALL (2mm) MINERALIZED QZ VEINLET NEAR BASE. BASE CONT. 90° TO C/A	149.0 DISS PY + MINOR PY+SL INVEIN.		150	6542	149.0-153.1	4.1	.001	.11	
					BANDED RHYOLITE. 4 cm STRONG ALT'D GDR CLASTS. (XENOS) BANDING N 90° TO C/A. INTRUSIVE CONT. @ BASE	153.1 TRACE DISS PY.		153.1	6543	153.1-155.9	2.8	.003	.43	
1570	157	3.3	66	.14	GRANODIORITE: STRONG PROP. ALT. ABUNDANT SECONDARY CL AROUND FS + IN FRACT. FILLING. ZONES OF SILICIC ALTERATION SLICKENSIDED FRACT. SURFACES ORIENTED PARALLEL TO C/A + 70° TO C/A.	155.9 TRACE DISS PY.		155.9	6544	155.9-160.8	4.9	.001	.04	
10	162	4.0	80	.25	GREENISH QZ + CA VEINLETS. MOSTLY N 70° LOWER CONTACT ABRUPT. SHEAR @ 90°			160	6545	160.8-164.5	3.7	.001	.04	
					MICRODIORITE: OLIVE GREEN, V.F.G. STRONG PROP. ALT'N. U. SHEARED AND CRUMBLED. ABUNDANT PRE. SHEAR CA. CLAY COATED + CA IN SHEARS. LOWER CONTACT LOST IN SHEAR ZONE. PARTLY CEMENTED.	164.5 MINOR DISS. PY. 169.1		164.5	6546	164.5-169.1	4.6	.001	.13	
	168	3.9	65	.12				169.1	6547	169.1-174.0	4.9	.001	.14	0.001, 0.123/47.7
	171	2.0	65	0	GRANODIORITE STRONG PROP. ALT. U. SHEARED + CRUMBLED. CLAY, CL + CA IN SHEAR ZONES. TOO SHEARED TO SEE STRUCTURE. PARTLY CEMENTED LOWER CONTACT LOST IN SHEAR	174.0		170						
1740	176	3.0	60	0	1 FOOT CORE LOST IN SHEAR, THEN 1 FT. MICRO-DIORITE OR ANDESITE, THEN RHYOLITE: FIRST 7 FT SHEARED, THEN BANDS OF SOLID, BXXD & SHEARED. 180.7-180.8: SHEARED + BXXD & BLK FG MATRIX. 181.8-181.9 MATRIX SUPPORTED VFG BLK MATRIX BX. ABUNDANT FG BLACK MINERAL, PY + CA IN FRACTS. ABUNDANT CL FRACTS MOSTLY 75-85°. MODERATE TO STRONG PROP. ALT'N. PERHAPS ARGILLIC IN SHEARED ZONES. SHARP, 5mm CA-FILLED FRACT @ END.	1-2 % PY DISS & IN FRACTS. UNKNOWN FG BLACK MINERAL MAY BE SL OR OTHER SX.		174.6	6548	174.0-179.0	5.0	.001	.12	
11	181	4.2	84	0				179						
								180	6549	179.0-184.0	5.0	.001	.25	
	186	3.9	78	.16				184						
						189.0		189	6550	184.0-189.0	5.0	.001	.08	
	191	4.1	82	.17	DIATREME OR PEBBLE DYKE. SUBANGULAR TO SUB-ROUNDED FRAGS OF RHY, GDR, QZ, FS, & FRESH + CHLORITIZED MAFICS IN LT. OLIVE GRN VFG MATRIX ? ALT'D AND? CA FRACT FILLING. CORE LOST (1') LOWER CONTACT GROUND.	TRACE PY. DISS + ON FRACT SURF.		190	6551	189.0-193.5	4.5'	.019	.65	
1935				1935	ANDESITE DYKE. DK OLIVE GREEN. SMALL HEMATITE VUG. MINOR	193.5 PY STRINGERS + FRACT. FILL.		193.5	6552	193.5-196.3	2.8			

OMNI RESOURCES INC. PROJECT DIAMOND DRILL HOLE No. 87-UG-22 Sheet 3 of 3

BOX	Run	Core	% R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T Ag	ANALYTICAL
12	196	3.5	70	0	QA STRINGERS FRACTS @ 45-60°. LOWER CONT. SHARP @ 60°	1963 OVERALL 1-2% PY.		196.3	6552		2B	.016	.37	Fw 59-83m
	201	4.3	86	.68	M-CG GRANODIORITE. V.HARD. ONLY MINOR FRTG ON QA STRINGERS. IS SLIGHTLY SER CHLORITE ALT'D OVERALL SLIGHT SILICIC ALT'N WITH ZONES SHOT THROUGH W QZ VEINLETS AND STRONG SILICIC ALT'N: QA/PY/QL CL ON FRACT. SURFACES. FRACTS @ 45 & 70°	MINOR DISS PY & QA FRACT. SURFACES		200	6553	1963-2013	5.0'	.001	.02	
	206	4.0	80	.16	2053-2060 3QZ VEINS & FLOODED ZONE WHITE QZ & SLIPPY VEINS @ 45° TO C/A	QZ VEINS & SL. PY			6554	2013-2063	5.0'	.002	.11	
	211	4.3	86	.15	MINOR PY IN 7mm GRNISH & WHITE QZ VEINLET @ 209' MODERATE CRACKLE OVER ALL.	MORE PY IN CL RICH ZONES		210	6555	2063-2110	4.7'	.001	.05	EOH.
		E.O.H			EOH									

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling: TO TEST KUHN ZONE ABOVE UG19 AT 1360 m LEVEL

Explanation of Results:

LEGEND

PROJECT	SKUKUM CREEK (WH claims)	HOLE No.	87-4623
COORDINATE N.	70854.7	DEPTH	202'
E.	77767.0	AZIMUTH	~~155°~~ 156°
ELEVATION	1308.2	INCLINATION	-54°
DATE STARTED	JULY 30, 1987	DRILLED BY	CARON DIAMOND DRILLING
COMPLETED	JULY 31, 1987	ASSAYED BY	ACME ANALYTICAL LABS
HOLE SURVEY	SEPT. 4/87	LOGGED BY	R.S.R.

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
								10					
								20					
								30					
								40					
								50					
								60					
								70					
								80					
								90					
								100					
								110					
								120					

OMNI RESOURCES INC. PROJECT SKUKUM CREEK DIAMOND DRILL HOLE No. 87-UG23 Sheet 2 of 3

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
					M-C-GR GRANODIORITE - SCALE CHANGED 1"=10'			120						
127	127				STRONG PROP. ALT. FSMRS GREEN & SOFT. ABUNDANT CA - STRONG CUBBLY FIZZ.	MINOR PY. (<1%)								
					LOCALIZED Fe STAIN ON FELDSPARS.									
	132	4.26	85	.12	MOD ABUNDANT CA STRINGERS MOST < 1mm. SEVERAL TO 2 mm. CUT CORE AT ALL ANGLES			130						
8					CORE QUITE BROKEN UP. FRACTURES MAINLY 65-75° TO C/A.									
	137	4.1	82	.37	OVERALL MED. GRN-GRY & LOCALIZED RED-ORANGE STAINING.				6507	133.2-138.2		0.001	0.01	
					MODERATE HEALED ALTO BX.									
	141	3.9	99	.17	SHARP CONTACT AT BASE @ 65° TO C/A.			140	6508	138.2-141.2		0.001	0.01	
137.1					141.2 GRANITE OR QUARTZ - ~ 25% QZ & K-SPAR RICH. FRACTS @ 80 & 60° ABUNDANT CL & EP IN FRACTS. FG GRANITE ON FRACT. SURF. SHARP 80° CNTCT			141.2						
	146	4.5	90	.55	143.9 4' MOD PROP ALT'N. THEN INT. PROP/MOD PHYL-MG GDR. LT GRN. QTZ VNS & CRUMS - GRNN. ON FRACTS. PSEUDO-BANDING 20° ABS. UND. CA/CL, EP. XTAL FABRIC OBLITERATED BY ALT'N. LOWER CNTC. GRD. & BROKEN	TRACE PY.		143.9	6509	141.2-144.9	3.7	0.001	0.01	* NOTE: THROUGH ZONE, CORE IS SO BATTERED, BROKEN, CRUSHED & GROUND THAT IT IS VERY DIFFICULT TO DETERMINE ACCURATE CONTACTS, RELATIONSHIPS, AND IN SOME CASES, EVEN LITHOLOGIES. 46-60 m HW.
9					147.9 VFG LT BRN-GRN GRANODIORITE IRON OR RED K-STAIN ON 30% OF FELDSPARS. XTALS << 1mm. INTENSE PROP. ALT'N.	MINOR VFG DISS. PY.		147.9	6510	144.9-147.9	3.0	0.001	0.02	
	161	4.1	92	.40	CA/QZ/CL VEINS. FRACTS @ 75 & 65° SHARP FRACT. CNTCT @ 60° TO C/A	~ 1% VFG DISS PY.		150	6511	147.9-152.9	5.0'	0.001	0.01	
	165	3.5	87	.35	VFG ALT'D PG DR AS ABOVE BUT BXD & BANDED. ABUNDANT CL. NO FEOR K STAINING ON FS. VERY BROKEN UP. BLACK CARBONACEOUS LINING ON SLIPS & SHEARS. CA-EPIDOTE VNS. MOD PHYL ALT. IN PATCHES ELSEWHERE.			152.9						
	167	1.9	95	.25	GRANODIORITE - MED. GR. MOD PROP. ALT. FEW CA STRINGERS MED-DK GRN-GRY. MOD CRACKLE. NUMEROUS X-CUTTING FRACTS @ 80-90° FILLED & CL/EP. & STRONG ALT. HALOS. MAFICS SOFT. NOT NOTICEABLY MAGNETIC. FRACTS @ 80° & PARALLEL TO C/A. LOWER CONT. SLIP @ 70°			157.7	6512	152.9-156.7	3.8	0.001	0.21	
159.1	171	3.2	66	.16		TRACE TO MINOR DISS. PY.		160	6513	156.7-161.0	4.3	0.001	0.01	
	166	4.6	92	.42	GRANODIORITE - MD. LT. GRN-GRY STRONG PHYLLIC ALT. GRAD. INC IN QZ UNTIL TOTAL QTZ-FLOODED. QZ: GRN-GRY & 3% YELLOW CA. FEW CLASTS GDR. LOWER CONT. 70°			163.4	6514	161.0-163.4	2.4	0.001	0.01	
10					HYDROTHERMAL BRX. STRONG BXD GDR & INFILLING OF YELLOW CA, EP, GRN-GRY DIATREME: (OLD MINE MUCK) OLIVE GRN & MASS. SURROUNDING FRAGS OF GDR. 2-10 cm. & SILT. GRANODIORITE INTENSE PHYLLIC ALT. PSEUDO-BND @ 60° STRONG GRNN BAND OF VFG DK GRY (SX?) MINERAL. MINOR GRN-GRY QZ. .4' DIATREME @ BASE 45°	SLIGHT TRACE PY		165.9	6515	163.4-165.9	2.5	0.001	0.02	
						SLIGHT TRACE PY.		167	6516	165.9-167.5	1.6	0.030	0.26	
						MINOR DISS VFG PY		168.3	6517	167.5-168.3	0.8	0.007	0.22	
	171	4.1	82	.40		V. MINOR DISS PY.		170	6518	168.3-171.0	2.7	0.004	0.21	
	175	3.3	83	.75	GRANODIORITE AS ABOVE. V. SOFT, ALT'D. STRONG PHYLLIC ALT'N. BANDED @ 65° TO CA. CL & GRAPHITE ON SHEARS. WEAKLY BXD. FRACTS & SHEARS @ ~65° TO CA.	MINOR DISS PY.		171.0	6519	171.0-176.0	5.0	0.001	0.11	
177	177	1.7	83	.26	176 FT. HEALED SHEAR & CLAY GOUGE @ 175.0 INCLINED @ 45° MINOR FRACTS @ 25° TO C/A. LOWER CONT. SHARP @ 60°			176.0						
					AMYGSITE DYKE. STRONG PROP. ALT. MINOR PHENOS. LT GREENISH GREY V. CALCITIC GDR. BAND @ 2° TO PY 3% SX, 2% WK PY 1% SX BXD. BASE 60°			177.7	6520	176.0-177.7	1.7	0.001	0.07	
	182	4.0	80	.07	GDR. INTENSE PROP. STRONG PHYLLIC ALT. XTAL STRUCTURE ALMOST TOTALLY MASKED. ZONES OF BXVN, FLOODING, HYDROTHERMAL ALT'N. F.G. VERY ALT'D. MINOR CLAY LOWER CONT. @ 70° TO C/A.	0.1' BAND HIGH GRADE SX.		180	6521	177.7-181.8	4.1	0.009	0.18	
11						(MINOR DISS PY.		181.8	6522	181.8-183.3	1.5	0.021	0.26	
	187	4.1	82	.09	INTENSELY PHYLLIC ALT VFG GDR OR APLITE OR C.G. RHYOLITE. LIGHT, BLEACHED APPLE GREEN. BANDS OF DIATREME @ 187 m & END OF ZONE. CRACCLED, MINOR BX. CLASTS, ZONES OF VEINS OR LESS ALT'D GDR. XTAL STRUCTURE TOTALLY BLEACHED AWAY.	TRACE DISS. PYRITE.		185.9	6523	183.3-185.9	2.6	0.001	0.02	
								188.8	6524	185.9-188.8	2.9'	0.015	0.18	
	192	2.9	58	0				190	6525	188.8-192.0	3.2	0.035	0.63	
196					GRANODIORITE. INTENSE PROP. ALT'N. STRONG HCL FIZZ ABUNDANT CA. CORE EXTREMELY BROKEN UP. MUCH LOST.	MINOR TO 2% PY.		192.0	6526	TOTAL CORE 192.0-197.0	5.0	0.005	0.14	

OMNI RESOURCES INC. PROJECT SKUKUM CREEK. DIAMOND DRILL HOLE No. 87-UG13 Sheet 3 of 3

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
195.5														
12	197	2.8	56	0	LIGHT, SLIGHT GREENISH-GREY, MEDIUM GRAINED. ABUNDANT CA ON SMEARS & FRACTURES. MUCH SECONDARY CA. ROCK QUITE CHALKY. SLIGHT CRACKLE. NO STRUCTURES VISIBLE AS CORE SO BROKEN AND CRUMBLED.	TRACE DISS PY.		197.0						
202	202	2.2	44	0				200.0	6527	1970-2020 TOTAL CORE	5.0'	0.002	0.06	TOTAL CORE SHIPPED. 61.57
E.O.H.								202.0						EOH

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	SKUKUM CREEK	HOLE No.	87-46Z-4
COORDINATE N.	70954.09	DEPTH	200'
E.	77753.30	AZIMUTH	UTT 289.2
ELEVATION	1307.04	INCLINATION	FLAT +2.3°
DATE STARTED	JULY 31, 1987	DRILLED BY	CARIBOU DIAMOND DRILLING
COMPLETED	AUGUST 2.	ASSAYED BY	ACME ANALYTICAL
HOLE SURVEY	SEPT. 4/87	LOGGED BY	R.J. ROBINSON

Reason for Drilling: TO TEST EXTENSION OF KUHN ZONE TO THE WEST ON 1300 LEVEL.

Explanation of Results:

LEGEND

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE			ANALYTICAL		
					SCALE: 1" = 20'				Sample No.	INTERCEPT	CORE LENGTH	O.P.T. Au	O.P.T. Ag	
								10						
								20						
								30						
								40						
								50						
								60						
								70						
								80						
								90						
								100						
								110						
								120						

OMNI RESOURCES INC. PROJECT SKUKUM CREEK DIAMOND DRILL HOLE No. 87-U624 Sheet 2 of 3

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag
					SCALE CHANGE 1"=10'			130					
						140		140					
						150		150					
9						160		160					
	163				LT MAUVISH GRY. QZ MONZ. K-SPAR + QZ INTIMATELY INTERGROWN. QZ LT GRY, K SPAR LT PINK. PLAG PARTLY ALT'D LT. GRN. MAFICS TO CL + LEUCOXENE. NO DETECTABLE MAGNETITE.	MINOR VFG PY DISS & ON FRACTS.							
10	168	3.6	72	.23	FRACTURES @ 70° TO C/A. MINOR CL & PY ON FRACTS								
	173	4.4	88	.69	THIN VEINS (<1cm) OF GREENISH QZ MORE COMMON W DEPTH	170 MINOR PY IN QZ VEINLETS.		170					
					SOME CLAY ON SHEARS. QZ VEINS @ 177.8, 174.2, 175.9, 176.8,								
	178	4.9	98	.65	177.9, 182.9, 183.1, 184.1, 186.2, 187.0, 189.3, 197.3.								
1982					SOME PLAG. POTASSIC STAINED + ALT'D. MINOR CRACKED.								
11	183	5.0	100	.69		180		180					
					187.4 SEGREGATED ZONE: 20cm NO MAFICS, THEREAFTER MOSTLY MAFICS. BANDS ORIENTED 40° TO C/A.								
	188	4.2	84	.34									
					189.4: 2 cm CA + CLAY-FILLED SHEAR. MINOR CL + PY.	190		190					
	193	3.3	66	40									
	197	2.6	65	0	195.5±0.7' CLAY-GOUGE FILLED SHEAR, ABUNDANT CL.								HW SHEAR. 59.59m ↓ ↓
1990						200		200					
	203	3.5	58	.17				203					
12					FELDSPARS GREENER + SOFTER T DEPTH. MORE STRONGLY SILICIFIED. SOME ZONES TO 50% QZ. SLIGHTLY MORE CRUMBLY TO LOWER CONTACT.				6528	203.0-208.0	5.0	0.001	0.01
	208	2.4	48	0	GRADATIONAL CHANGE @ BASE	208		208					
					GRANODIORITE. STRONG PHYLLIC & ARGILLIC ALT'N. RECESSIVE FRACTS. CLAY-FILLED ABUNDANT SMALL SUB-PARALLEL FRACTS, MOST PLAG → CLAY. ABUNDANT CL. MINOR CA. FRACTS @ 70 & 60°	210 MINOR PY. DISS, VFG.		210	6529	208.0-213.0	5.0	0.001	0.01
	213	2.5	50	0	QUITE CRUMBLY. MOD. INTERSTITIAL CPY. LOWER CONTACT NOT VISIBLE.	213		213					
					1 FOOT OF CORE FOR 5 FT. RUN.				6530	213.0-218.0	5.0	0.016	0.52
					ANDESITE DYKE. DK GRN. FRAGS OF STRONGLY ALT'D GDR AND QZ!	215							

OMNI RESOURCES INC. PROJECT DIAMOND DRILL HOLE No. 87-1624 Sheet 3 of 3

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
12					FS XTALS (SUB-ROUNDED + PREF. ORIENTED) CORE TOTALLY RUBBLED.	TRACE BL. MINOR PY DISS IN QTZ + ANDESITE								
	218	1.0	20	0	1 20cm. FRAG OF WHITE QTZ ± TRACE VFG SX. LAST 0.5' GRANODIORITE.			210	6530	TOTAL CORE SHIPPED FOR ASSAY		0.001	0.14	
	223	4.4	88	0	BANDED SHEAR ZONE CLAY, CL, EP. 20° TO C/A			220	6531	218.0-220.0	2.0'	0.001	0.14	
223.5					GRANODIORITE. STRONGLY PROPYLITIC ALTERED. ± WEAK TO MOD. ARGILLIC ALT. MUCH INTERSTITIAL CLAY. ABUNDANT CL + CA NUMEROUS CA-QTZ + CLAY-FILLED FRACTS. 0.2' CLAYEY BANDED SHEAR. DIFFICULT TO DETERMINE % OF PHASES OF BROKEN DUE TO INTENSITY OF LAST ONE - MORE COMPETENT - LESS FRACTURED ± DEPTH.			225	6532	220.0-225.0	5.0'	0.001	0.03	
13	228	4.3	86	.27	LESS CA + HARDER FSPAR ± DEPTH. LESS ALT'D. GRAD. CONTACT AT BASE.			230	6533	225.0-228.6	3.6'	0.001	0.04	
					DARK GREEN ALTERED GRANODIORITE. SWIRLS + BANDS OF LT + DK. GRN FRACTS MOSTLY HEALED, OPEN FRACTS @ 65° MINOR SHEARING. SHARP END IN 1CM CLAY SHEAR	1-7% PY IN BLEBS, STRINGERS & DISS.		228.6	6534	228.6-230.5	1.9'	0.001	0.21	0.001, 0.03
	233	4.9	98	.72	GRANODIORITE. MOD. STRONG PROP. ALT'N. DARK GRN-BLACK ZONES OR ZENOS. OF DIORITE / GABBRO. ABUNDANT MAFICS. @ 2 FT CLAY-FILLED SHEAR @ 233.7'. ABUND CL + MINOR BRXN AT BASE.	~1% DISS PY OVERALL. 1CM WEDGE OF VFG SX. AT BASE.		230	6535	230.5-235.2	4.7'	0.002	0.11	
					FRACTS MOSTLY 45 + 70° SHARP END IN SHEAR ± SX.			235.2	6536	235.2-240.2	5.0'	0.001	0.06	73.49m FNAA
238.6	238	4.7	94	.35	GRANODIORITE. WEAK TO MODERATE PROP. ALT'N. ABUNDANT QA AND GARNISH QTZ STRINGERS			240						SCALE CHANGE 1" = 20'
				.60	QA-LINED FRACTS. FG BAND ± QTZ + PY @ 236.5			240.2						
246			99		FRACTURE / SHEAR ZONE @ 241.0' MORE ALTERED AFTER THIS. SCALE 1" = 20'									
			98		FRACTS. MOSTLY 50+65° TO C/A. STRONG GYPSUM TO 243.5, THEN ONLY WEAK CRACKLE. XENOLITH OF FG BLACK ? AND ? @ 243.5									
14			100		MORE ABUNDANT EPIDOTE FLOODED ZONES ± DEPTH									
249			100	.70	LESS ALTERED FROM 243.5 DOWN. EPIDOTE ZONE FROM 265.0-239.9. GRAD. CONT. @ BASE.									
					QUARTZ MONZONITE. M-CG. LT. PINKISH GREY. ABUNDANT EPIDOTE FLOODED ZONES MINOR-WEAK POTASSIC + PROP. ALT'N. MINOR TO MOD CRACKLE.			260						
15								260						
258				.69	FRACTS @ 60 + 90° TO C/A.									
16					PALE GREEN EPIDOTE ZONE 284.0-286.0									
				.65				280						
EOH					EOH									EOH

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	SKUKUM CREEK WH CLAIMS	HOLE No.	87-UG25
COORDINATE N.	70853.12	DEPTH	419'
E.	77759.19	AZIMUTH	277° 278.25°
ELEVATION	1307.08	INCLINATION	FLAT + 0.2°
DATE STARTED	AUGUST 3, 1987	DRILLED BY	CARON D.D.
COMPLETED	AUGUST 4, 1987	ASSAYED BY	ACME ANALYTICAL LAB.
HOLE SURVEY	SEPT. 4/87	LOGGED BY	RJ ROBINSON

Reason for Drilling: TO TEST WEST EXTENSION OF KUHN ZONE ON 1300 M LEVEL.

Explanation of Results:

LEGEND

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE			ANALYTICAL		
									Sample No.	INTERCEPT	CORE LENGTH	O.P.T. Au	O.P.T. Ag	
								20.0						
								40.0						
								60.0						
								80.0						
								100.0						
								120.0						

OMNI RESOURCES INC. PROJECT SKUKUM CREEK W.H. CLAIMS DIAMOND DRILL HOLE No. 87-6625 Sheet 2 of 4

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE		CORE LENGTH	ANALYTICAL		
									Sample No.	INTERVAL		O.P.T. Au	O.P.T. Ag	
								140.0						
								160.0						
								180.0						
								200.0						
								220.0						
								240.0						
								260.0						
								270.0						

OMNI RESOURCES INC. PROJECT SKUKUM CREEK WH CLAIMS DIAMOND DRILL HOLE No. 87-WH25 Sheet 3 of 4

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T Ag	
								280.0						
18								300.0						
338.5					SCALE CHANGE: 1" = 10'			320.0						1" = 10'
19	322.0				GRANODIORITE: MED. GRAINED. V. DK GRN-GRY. ABUNDANT MAFICS PARTLY CHLORITIZED. WEAK - MOD. PROP. ALT. MINOR C/A LINING FRACTS. MORE STRONGLY ALTERED E DEPTH.	MINOR SECONDARY DISSEMINATED PY.		324.7						
	327	4.2	84	.22	FRACTS @ 45° 90° 70° C/A SHARP CONTACT @ BASE @ 40°				6591	324.7-329.4	4.7' 4.7'	.001	.28	
	328	9	90	0	BXXD GDR AS ABOVE AND AND AS BELOW. STRONG PHYLLIC ALT'N.	328.4		329.4						
					ANDESITE DYKE: MOD PHYLLIC ALT'N. ABUNDANT Q2/CA VEINLETS. BANDING. FRACTS & VEINLETS ORIENTED @ 40° TO C/A 1' ZONE OF PHYLLIC ALT. BXD AS ABOVE.	TRACE DISS. PY. MINOR DISS PY.		330.0						HW OF DYKE 329.4' = 100.4 m
	333	4.4	88	.40	STRONG TO INTENSE PHYLLIC ALTERATION OF MG. GRANODIORITE. BLEACHED APPLE GREEN. V. ABUNDANT Q2. VEINING. WEAK TO MOD. ARGILLIC ALT'N. V. SHRT. MINOR C/A STRINGERS. Q2 VEINS VARY TO GREENISH-GREY. LOWER CONT. SHARP @ 30°	332.5 BARE TRACE FG DISS. PY.		334.8						
339.0	338	5.0	100	.81	GRANODIORITE. M.G. V. LT BLEACHED APPLE GREEN.	336.7		336.7	6593	331.8-336.7	4.9'	.001	.05	
	342	3.0	75	0	INTENSE PHYLLIC AND STRONG ARGILLIC ALTERATION. ABUNDANT QUARTZ - CALCITE VEINS CUTTING ROCK AT ALL ANGLES. FELDSPARS VERY LIGHT, GREENISH - YELLOW. ~20% Q2 CA VEINS. MOSTLY WHITE.	MINOR DISS. PY.		340 342.0	6594	336.7-342.0	5.3' 1' ORE LOST FROM 338-342	.002	.03	
	347	4.7	84	31	MINOR CHLORITE. Q2 VEINS 1-5 mm ACROSS. MANY VEIN X-CUT OTHER VEINS. NETWORK VEINS. NO DOMINANT FRACTURE ORIENTATION. SHARP CONT. AT BASE			347.0	6595	342.0-347.0	5.0'	.001	.01	
20	352	4.9	98	88		351.5		350.0 351.5	6596	347.0-351.5	4.5'	.001	.01	
356.7	357	4.8	96	.68	GRANODIORITE: AS ABOVE, BUT SLIGHTLY HARDER, LESS CLAY, WEAKER ALTERATION AND MORE Q2 VEINING. GRADATIONAL CONTACT @ BASE. BECOMES BROKEN UP NEAR L CONT.	TRACE VFG DISS. PY 356.4		356.4	6597	351.5-356.4	4.9'	.002	.03	
21	362	4.8	96	.58	BRECCIA ZONE. BXD GDR. CLAST SUPPORTED WITH ~40° GREY - GREEN/GREY Q2 MATRIX. MINOR VEINS OF LT. GRN Q2. V. COMPETENT. NO DOMINANT FRACT. ORIENTATION. F.G. GDR. LT GREYISH - APPLE GREEN. MOD - STRONG PHYLLIC ALT'D. BROKEN CONTACT @ BASE.	TRACE FG DISS. PY. 361.7		360.0 361.4	6598	356.4-361.4	5.0'	.001	.10	
	367	4.3	86		GRANODIORITE: LT. GRY. V. SILICA-RICH. ZONES NOT SILICIC ALT'D ARE STRONGLY ARGILLIC ALT'D. LT. GREYISH-GREEN CLAY INTERSTITIAL TO QTZ EUHEDRAL FRACTS @ 45° 90°. SHARP 45° CONT. @ BASE.	MINOR DISS. PY. 369.3		364.7	6599	361.4-364.7	3.6'	.004	.04	
								369.3 370.0	6600	364.7-369.3	4.6'	.002	.11	

OMNI RESOURCES INC. PROJECT Skukum Creek WH claims DIAMOND DRILL HOLE No. 87-UG-25 Sheet 4 of 4

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T Ag	
21	372	4.8	96	.82	GRANODIORITE: INTENSE PHYLLIC ALT. MOD-STRONG ARGILLIC ALT'N. U. ABUNDANT CLAY, STILL QUITE SILICIC IN NON-CLAY ZONES. LT. GREY-GREEN. FINE GRAIN-SIZE INDISTINCT, PROBABLY M-C gr. FRACTS @ 30-45°. GRAD. CONT.	MINOR DISS PY		370.0						
3745								373.7	6601	369.3-373.7		.001	.02	
	377	5.0	100	75	GDR BX STRONGLY SILICIFIED GDR CLASTS IN MATRIX OF GREY QZ. THIS BX THEN BXED & BLACK MATRIX INFILLING. MOD. CLAY. CONT. SUB-PARALLEL @ 60°	377.7 1-3% VFG PY. DISS & IN BLACK MATRIX. 380.3 TRACE CP		377.7	6602	373.7-377.7		.001	.01	
92	382	5.0	100	90	AS ABOVE, BUT LESS CLAY AND MORE GREENISH BLACK, UFG MATRIX. LITTLE ROTATION ON SECOND BXN. OVERALL, MED GREY. SHARP 30° CONT. @ BASE, HEMATITIZED FAULT ± STRONG CLAY SHEAR ZONE. U. SOFT, PLASTIC - FORMS ON ABOVE UNITS. CLASTS & ABUNDANT SX. MINIMUM BANDING @ 70° LOWER CONT @ 70° TO C/A	381.3 1-2% PY IN BLACK MATRIX. TRACE CL IN QZ CLASTS. 385.5 1-2% PY MINOR SL/GL.		380.0	6603	377.7-380.0		.004	.31	
	382	4.7	94	70				383.3	6604	380.0-383.3		.005	.21	
								385.5	6605	383.3-385.5		.004	.23	
3928	392	5.0	100	87	STRONG TO INTENSE PHYLLIC ALT'D. ANDESITE. XENOS AND SMALL XTALLINE FRAGS OF U. ALT'D GDR. MINOR BXN @ TBP, AND BANDED THROUGHOUT. QZ + CA VEINLETS + STRINGERS. LT TAN TO BRNNISH OLIVE GREEN. FRACTS @ 20-40°	TRACE DISS. PY.		390.0	6606	385.5-390.0		.002	.06	
	393	1.0	100	45	LOWER CONTACT SHARP @ 15-20°			390.1	6607	390.0-392.8		.001	.01	↑ FW 119.73 ↑
	399	5.0	100	90	GRANODIORITE: STRONGLY SILICIC ALTERED. WEAKLY PROPYLITIZED. XTAL STRUCTURE HAZY AND INDISTINCT-MEDIUM TO COARSE-GRAINED. MED-DK GREY. MINOR CA STRINGERS.	MINOR DISS PY.		392.8	6608	392.8-397.8		.001	.06	
23	403	4.9	98	66	A FEW BANDS OF STRONGER SILICIFICATION. QUITE ABUNDANT EPIDOTE FROM 404.5' TO 407.0'			397.8	6609	397.8-402.8		.004	.07	
	408	5.0	100	83	LOOKS LIKE GRANODIORITE ABOVE ZONE. ABUNDANT MAFICS. CORE LIGHTER IN COLOR & LESS MAFICS ± DEPTH TO BOTTOM OF HOLE. FRACTS @ 40-70°.			402.8						
4096								410.0						
24	413	4.9	98	71										
	4165	3.5	100	75										
	419	2.5	100	83										
					END OF HOLE DDH UG-25			420.0						END OF HOLE 87-UG-25.

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling: Below SkR-27 — To test Kusha Zone at depth 1350m

Explanation of Results:

LEGEND

PROJECT	SKUKUM CREEK	HOLE No.	87-UG-26
COORDINATE N.	7085 5.38	DEPTH	284
E.	7775 9.28	AZIMUTH	312°
ELEVATION	1309.14	INCLINATION	-39°
DATE STARTED	AUG 4, 1987	DRILLED BY	CARON D.D.
COMPLETED	AUG 7, 1987	ASSAYED BY	ACME
HOLE SURVEY		LOGGED BY	TME

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE (SCALE 1":20')	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
1					QMz, Mafics chloritized and in a few places altered to Pyrite Meso-Cryst Plags. Light green medium green altered slight Potassic altn in small patches Weak-Mod. Propyllitic Altn								
1	18.1	18.1	17.2	95	.3								
					6.8-7.9 1mm Clr veinlets 10° to C.A.								
					11.5' Qtz-Cal Vein 1cm wide 50° to C.A.								
					17.9 .5" by .5" And. Xenolith.								
					22.6-23.3 zone of fine gr. QMz								
					24.5 Veinlets of Chl+Ep. along fractured shear 45° to C.A.								
					27.8-28.0 zone of fine gr. QMz								
					Fracture direction 0°+70°								
2													
34.0	34.0	14.5	90	.52									
					35.5-41.0 Qtz flooded zone veinlets upto 3cm wide running mostly 0° to C.A. also Ep, Chl in fractures as follows								
					40.0-40.7 Med-fine gr QMz.								
					49-51. Patches of stronger Altn Mafics less noticeable rock green-grey colour								
3													
51.5	51.5	17.5	100	.63									
					1" fine gr. Zone at 54.4 + 2" zone 55.4-55.6								
					56.0-57.8 Green-Grey zone with strong Propyllitic Altn.								
					62.5-63.0 fine grained zone.								
4													
69.0	69.0	17.5	100	.99	67.0-68.7 Epidote Altn - Qtz veinlet 3mm wide 45° to C.A								
					69.0-70.5 fine gr zone.								
					Hollite patches at 71.0 + 72.1-72.3 with Qtz vein (3mm)								
					81.2 Black Veinlet 4mm wide 30° to C.A.								
5													
87.4	87.1	15.1	100	.52									
					95.1-97.9 Pink fine gr Qtz/Monz								
					95.0-98.8 fracture Zone Ep.+Sericite on Pkg 10% Abundant								
					102.5 Aplite Zone.								
6													
104	104	16.9	100	.75									
					115.0-.3 Fracture with Cal Chl Altn.								
					118.9 3mm Qtz vein with .5% Py + Minor Cpy								
7													
								120					

OMNI RESOURCES INC. PROJECT SKUKUM CREEK DIAMOND DRILL HOLE No. 87-0626 Sheet 2 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
1409			100	.145	122.0-122.2 And. Olive Green with 5mm black phenocrysts. 45° Cat.			120						
8					123.0-125.4 Alteration intensities (Ep, Chl, +Ser) also cut Veinlets Grid 123.6 for 2" has .8cm Sz with Py+Gn. Zone in general 1% Py with tr. Gn.									
1417				.48	137.4 3mm Qtz Vein. 90° to C.A.									
9					Quartz veinlet 3mm @ 90° / Epidote Alter in cracks 1415			140						
1483				.71	Quartz veinlet 6mm @ 198.2									
10					Quartz Veinlet 2mm @ 1559			150						
1525		15	90	.38	165.0-166.4 Crackle Bx with Ser+Ep Alt'n 2mm Qtz veinlet & Cm. Silicified.			160						
					173.2-175 Fracture zone.			170						
11					178.2 Ep. dote Alt'n Qtz Vein 3mm wide									
					179.6 - 2" fine grained			180						
1582		15.3	90	.78	180.0 Qtz. Vein 85 to C.A.									
					190.9-109.7 Qtz Vein 70° to C.A. in Fracture Zone 186-192			190						
12					C.GR QUARTZ MONZONITE - propylitic alt'n: chl. mafics (5%) cores of plag. sericitized.									
1708		14.9	90	.68	194' = 4mm. gray felsite dyklet at 35° to core axis	Local Qvns as noted. From 207' = minor disseminated py.		200		63.14m Qtz-Sericite 5.41m				Native Au Prep HW 63.09m
					195.9' = 3mm. Qvn at 55° to c.a.									
					Fract. 60° to c.a.; a few fract at 20° & 45° to c.a.									
					206' = 1/2cm Qvn w. 3% py & minor gn (sl); 80° to c.a.									
					From 207' to rhyo. contact SCALE CHANGE 1"=10' Local silicification = bleaching of mafics			208						
					MINERALIZED RHYOLITE BRECCIA - varies from crackle bxa. to strong bxation. Broken contacts (?attitude?). 211.1' = 3mm. Qvn. at 45° to c.a. 212.5' = 1-3 mm. chlorite vns. at 45° to c.a.	2% py as C.gr. aggregates in matrix & disseminated. Minor cpy. 212.8-213.8 = strong mass of Q Sz Bxa, mixed w. rhyo. bx. w. ½-1% aspy. Minor galena		210	6556	205.3-210.7	5.4'	.001	.14	
	214	5.72	80	.15	Mineralized vns ca. 45° to c.a. Fracturing also commonly 45° to c.a.				6557	65.83m 210.7-216.0	5.3'	.182	.42	.089 NBZ
13	B155	1.3	88	0	MINERALIZED, WHITE QTZ.-SULPHIDE BRECCIA - Frags. 1mm to 2cm. From 219-219.5' = Rhyolite Bxa. Lower contact ca. 45° core. Fract. 25°, 45° & 60° to c.a.	3-5% Aspy & 2% Py in matrix. 0.1% Gn. and some sl ♦ cpy. C.gr. mineralization.			6558	216.0-219.5' 66.98 61.15	3.5' 67.81 (61.98)	.102	2.52	.124
	219	3.2	93	.13	MINERALIZED & ALTERED ANDESITE 221' = 4cm long frag. of rhyo. bxa. w. aspy at contact. Fract. 45° & 90° to c.a.	7-10% fine to blebby pyrite. As 221' = 5-7mm. Qvn w. coarse py blebs		220	6559	219.5 - 222.5' Fault zone recovery	3.0'	.015	1.51	.021 .197
	2213	1.6	64	0					6560	222.5(?) - 223.5'(?)	1.0'	.244	3.39	.197
2241	225	2.5	71	.14	STRONGLY MINERALIZED QTZ.-SULPHIDE BRECCIA 222.5-223.5' = only 30% core recovery. Contact 45° to c.a. Crude sulphide banding varies from 20°-45° to c.a.	5-7% Aspy; 5-7% Py 0.3% Cpy; 0.1-0.2% Gn. from 223.5-227.0'			6561	223.5(?)-227.0'	3.5'	.975	8.57	.624
	229	1.6	59	0	226' = shearing // core axis.				6562	227 - 230'	3'	4.320	21.58	2.168
	234	1.9	95	0	227'-230' = ca. 30-40% core recovery. Sulphides strong from 228.3-230'. From 227-228.3' only 2-3% total sulphides	4% Aspy; 2% Py; 0.2% Cpy; 0.1% Gn.								
14	232	1.8	90	0	230-230.7' = Strong (1%) cpy. Fract. 30°, 45° & 60° to c.a.				6563	230'-234'	4'	1.050	6.82	.996
	234	1.6	80	0	231.7'-231.8' = Weakly mineral. rhyolite bxa.	1% Aspy, 3% Py and 1% Cpy; <0.1% Gn.								
	2365	1.2	80	0	232.6'-232.9' = Strong (2-3%) cpy.				6564	72.84m 234 - 239' 66.58	5'	1.035	5.23	.726
					234.2-234.3' = 2% cpy.									
					Crude sulphide banding at 25° to c.axis.									
					* Smaller / ground pieces of core rich in sulphides ∴ sulphide loss!									
	239	2.0	57	0	Irreg. vns of Q-Carb at contact	3% Aspy; 2-3% Py; 0.3-0.5% Cpy; 0.1% Gn.								
					ALTERED (Carb) DARK BROWN ANDESITE									

Native Au Prep HW 63.09m

96 7, 5.9/28.3 cw

OMNI RESOURCES INC. PROJECT DIAMOND DRILL HOLE No 87 VG 26 Sheet 3 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
14	244	4.1	82	.30	Hairline to 1mm. calcite vnlts common; rock is carb. & calcite all'd. Lower contact ca. 10° to c.axis. ALTERED C.GR QUARTZ MONZONITE - 5-7% chl. matics, serecitized plag & dissem calcite plts. 245.9 - 246.3 = Brown Andesite dyke at 45° to c.a.	<0.1% Py	240	6565	239 - 244' (74.36m - 74.37m)	5'	.002	.05
	249	4.5	90	.21				6566	244' - 249'	5'	.003	.04
	253	4.0	100	.38	251' - 254' Epidote vnlts begin; also, dissem. epidote. Fract. mainly 45° & 20° to c.axis.	Minor Py.	250	6567	249' - 254'	5'	.001	.02
15	258	4.9	98	58	256 - 256.5' = 3 pink aplite dykelets at 70-80° to c.a. - cut by later ser-epid. vnlts. 78.73m - 79.67m 258.3 - 261.4' = GREEN, CARB(calcite) ALT'D ANDESITE 78.96 - 79.82m DYKE 257.4' = 5mm @ 70° SCALE CHANGE 1" = 20' Upper contact 45° to c.a. Lower contact 30° to c.a.			6568	254' - 258'	4'	.001	.06
16	263	4.4	88	50	Fract. 20°, 45° and 70° to c.axis. Epid. vnlts 20° & 45° to c.a. Occasional aplite dykelets at 60-80° to c.a. 282.5 - 284' = strong (5% of volume) epidote alteration.		260	6569	258 - 262'	4'	.001	.06
17							EOH.					

244.0' ↑↑ FW cont. 74.37 m

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling: TO TEST KVM ZONE AT 1330 LEVEL ABOVE HOLE 86-34

Explanation of Results:

LEGEND

PROJECT	SKUKUM CREEK	HOLE No.	87-UG27
COORDINATE N.	70854.63	DEPTH	320
E.	77758.95	AZIMUTH	~~293°~~ 289°
ELEVATION	1308.9	INCLINATION	+30°
DATE STARTED	AUGUST 7, 1987	DRILLED BY	CARON D.D.
COMPLETED	AUG 8, 1987	ASSAYED BY	ACME ANALYTICAL
HOLE SURVEY	SEPT. 4/87	LOGGED BY	RJ ROBINSON

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE (SCALE 1" = 20')	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
1					GRANODIORITE. C.G. LT.-MED. GREY - WEAK ABOP. ALT'N. ABUNDANT CA VEINLETS & STRINGERS. MINOR HEMATITE. 20cm. QZ VEIN OFFSET BY FAULT @ 6.0' FRACTS. @ 70° TO C/A CORE CONT. AT BASE								
183			95	.43	QUARTZ MONZONITE. C.G. LT MAUVISH-GREY. 25-30% HB. MOD. PROP. ALT'N. ZONES OF SEGREGATED ENRICHMENT OF VARIOUS PHASES. i.e. A FEW V. HB RICH ZONES, K-SPAR-RICH ZONES, VFG PINK & GREY BANDS.			10					
2					A FEW SMALL QUARTZ VEINS AND CA VEINLETS + STRINGERS			20					
336			100	.57	FAINT BANDING IN SOME AREAS. STRUCTURES INCLUDING BANDING, FRACTS & VEINING MOST COMMONLY ORIENTED @ 75-80° TO C/A.			30					
3					42.0-46.0 - MOD PROP. ALTN.	MINOR DISSEMINATED PYRITE. (SECONDARY)		40					
530			95	.33	54.0: 1 FT BAND STRONG GREY-GREEN QZ			50					
					57.5' 2cm QZ VEIN ± PY, SL & GL XTALS.								
4					MINOR SPECULAR HEMATITE			60					
					68-70 FG STRONG PROP ALT'N. DK GRN. BANDED.								
707			100	.40	MOD. ± POTASSIC ALT'N 63-88			70					
					88.8-89.6 ± VEINS OF GREEN/GREY QZ. AND VIS. MINS.								
5					MORE DISS. PY THROUGH THIS REGION			80					
786			100	.43	STOCKWORK OF SMALL BLACK VEINLETS. ORIENTATION CHANGES FROM 20-90° TO C/A OVER 1'. IN FAN PATTERN.	~1% DISS. PY.		90					
6								100					
1053				.62	MINOR QZ VEINS & THIN BLACK STRINGERS.			110					
7								120					

OMNI RESOURCES INC. PROJECT DIAMOND DRILL HOLE No. 87-UG-27 Sheet 2 of 3

BOX	Run	Core	% R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag
123			100	.54	TWO NARROW ANDESITE DYKES. ONE @ 129' FOR 0.3'; ONE @ 130' FOR 0.4'. BOTH CUT CORE CLOSE @ 45°.			120					
8								130					
140			100	.57	@ 138 IS MAGMATIC SEGREGATED ZONE OF POTASSIUM FELDSPAR-RICH UFG APLITE-LOOKING ROCK FOR 0.8'. @ 141.5 5 MM PY + SL STRINGER CUTTING CORE @ V. SHALLOW ANGLE. IN THIN FRACTS ± CA + QZ			140					
9						MINOR SL/PY IN QZ-CA VEINS.		150					
145.8			90	.44	STRONG PROP. ALT ZONE FROM 145 - 147. ± 2 ICM PERP. K-CUTTING WHITE QZ VEINS.								
10					149.0 MOD PHYLLIC ALT'N. MOD CLAY IN FRACTS. LT GRN. MORE ABUNDANT PY.	1-2% DISS PY.		160					
153.8			95	.45	153-157. QZ FLOODED STRONG ACID ZONE. NUMS SX. ALT STRONG PROP- MOD PHYLLIC FROM HERE DOWN.			170					
11					@ APLITE DYKE @ @ 176'								
169			100	.43	XENOLITHS OF UFG MAFIC INTRUSIVE ROCK TO 3 cm INC. ± DEPTH INCREASING W/ OC THIN GREEN-GREY QZ VEINS. ~ 8 VEINS/20' APLITIC ZONES MORE COMMON. MORE FRACTS. STILL @ 45° TO C/A	TRACE TO MINOR PY.		180					
12								190					
208			95	.43	ALTERATION INTENSITY INCREASING WITH DEPTH.			200					
13								210					
224.5			100	.32				220					
14	224							227.2					
					SCALE 1"=10'			230					
	234	3.0	100	.30	STRONGLY PHYLLIC ALTERED, M.G. GDR. MOD. FRACT. ABUNDANT GREY QZ VEINS.	232.2		232.2	6610	227.2-232.2	5.0'	0.001	0.03
	238	3.8	95	.27	V. BROKEN UP.	TRACE DISS PY		235.5	6611	232.2-235.5	3.0'	0.001	0.01
240.5						A FEW BLEBS OF PY.		239.0	6612	235.5-239.0	3.5'	0.001	0.02
	243	3.5	70	0	FRACTURES @ 45° TO C/A			240					
					LOWER CONTACT DISTINCT, GRADATIONAL.			243.0	6613	239.0-243.0	4.0'	0.001	0.17
15	248	4.8	96	.70				246.9	6614	243.0-246.9	3.9'	0.001	0.03
					GDR. STRONG PHYLLIC ALT. MOD. ARG ALT. ABUNDANT QZ + CA. BANDING @ 40° TO CA. RECESSIVE CLAY IN FRACTS.			249.0 250	6615	246.9-249.0	2.1'	0.001	0.01

OMNI. RESOURCES INC. PROJECT SKUKUMCREEK DIAMOND DRILL HOLE No 84-27 Sheet 3 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL Ag O.P.T. Au	ANALYTICAL Ag O.P.T. Au	
					249.0: SHEARED, ALT'D, BANDED QZ + CBX. U. CRUMBLY. SX IN CLAY + QTZ. QUARTZ MOD VUGGY. BANDING @ 45°. MINOR RHY.	251.8 BX, PY MINOR SL, GC Ag.		250						
15	263	5.0	100	.64	RHYOLITE. MOSTLY SOLID + VUGGY AT TOP WITH BLACK SX FRACT. FILLING. MORE STRONGLY ALT'D & DEPTH. BXXD + CLAY FILLED & GREY QZ FRAGS. (OR LESS ALT'D RHY)	MINOR FRACT-FILLING PY, SL, GC + BLACK FG SX.		251.5	6616	249.0 - 251.5	2.5'	0.69	0.002	* Note Ag fifty columns ↓ 75904 ↓
	268	5.0	100	.95	BANDED + FRACT @ 45°			256.5	6617	251.5-256.5	5.0'	0.16	0.003	
16	273	5.0	100	.44	GRANODIORITE. U. STRONG PHYLLIC + ARG ALT. EXTREMELY SOFT + CRUMBLY. ABUNDANT CA INFILLING. FRACTS + BANDS @ 45° ERRATIC BANDS. 1-2%	@ TRACE DISS PY.		260	6618	256.5-260.7	4.2'	0.10	0.001	
	276	3.0	100	100	EXTREMELY SOFT, CLAYEY ALT'D. GDR. (PRIMARILY) NO RTAL STRUCTURE VISIBLE. JUST LOOKS LIKE LT. GRN-TAN CLAY + CRUMBLED ROCK. BANDS + FRACTS @ 45 + 65°	MINOR PY IN QZ CLASTS		260.7	6619	260.7-263.0	2.3'	0.01	0.001	
	281	4.5	90	.53	GRANODIORITE.	269.0		263.0	6620	263.0-266.0	3.0'	0.02	0.001	
1084	287	5.4	90	.48				266.0	6621	266.0-269.0	3.0'	0.03	0.001	↑ FW. ↑ B1.99
								269.0	6622	269.0-273.5	4.5'	0.01	0.001	
17								270						
2928			95	.64				273.5				OPT Ag	OPT Au	
								290						
3104			100	.59				300						
								310						
3200			100	.40				320						
					END OF HOLE									EOH.

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	SKUKUM CREEK
COORDINATE N.	70854.83
E.	77761.37
ELEVATION	1305.85
DATE STARTED	AUG 9
COMPLETED	AUG 11
HOLE SURVEY	SEPT. 4/87
HOLE No.	87-UG28
DEPTH	243' 73.76
AZIMUTH	~~350°~~ 346.5°
INCLINATION	-35° -34.7°
DRILLED BY	CARON D.D.
ASSAYED BY	ACME
LOGGED BY	T.M. Elliott / RSR

Reason for Drilling: TO TEST KUHN ZONE 30m below X-CUT. (1230 LEVEL)

Explanation of Results:

LEGEND

SCALE 1:20

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
3.0					CASING IN BROKEN QMZ & MUCK.								
3.91					QUARTZ MONZONITE. BANDS & ZONES OF VARYING GRAIN SIZES. VARIES FROM FINE TO COARSE-GRAINED, & MAFIC POOR (~2%) TO MAFIC RICH (>20%) ZONES & SEGREGATIONS OF K-RICH ⇒ FELDSPARS. FRACTS @ 45° & 65° TO C/A. BANDING & HEALED FRACTS @ 75° TO C/A. MINOR CA VEINLETS & STRINGERS. WEAK PROP. ALT'N, WEAK TO MOD. POTASSIC ALT'N.	BARE TRACE DISS. PY OVERALL.		10					
20.7			95	.98				20					
23.71					8.23								
					27.0: 1.5' APLITIC ZONE. BUFF/TAN. ABUNDANT QZ. CONTINUOUS INTERGROWTHS OF QZ & K-SPAR.			30					
					10.97								
					36.0: 8cm QZ VEIN @ 25° TO C/A. (WHITE QZ)			40					
39.0			100	.35	12.35 – 12.72								
41.89					41.0-45.0 NUMEROUS BLACK-FILLED FRACTS. MOST @ 45°, BUT SOME ALMOST PERP. & SOME X-CUTTING @ 45° MINOR QZ INFILLING IN SOME FRACTS.			50					
					15.39								
					50.5': 2cm WHITE QZ VEIN IN 1 FT. MOD-STRONG PROP. ALT'D. ZONE.			60					
57.4			95	.59									
17.50					18.59 – 19.2,								
					61.0 – 63.0: POTASSIC ALT'D/K-SPAR RICH ZONE. FEW MAFICS. ORANGE-TAN. ALT'D.			70					
					19.5 – 20.27								
					63.0 – 68.0. STRONG MAFIC RICH ZONE, COARSE-GRAINED. ABUNDANT CL-FELD. GREEN & GREY BANDS @ 45° TO C/A. THEN BACK TO REGULAR QMZ-CUB.	MINOR PY		80					
79.4			100	.67	24.08								
22.69					79.0 ' MED.-GRY. F.G ZONE FOR 0.9'.			90					
					24.69								
					81.0' 3cm GREYISH WHITE QZ FLOODED ZONE, FOLLOWED BY 2' FRACT'D ZONE & BLACK INFILLING, THEN 2cm @ GREYISH GREY QZ VEIN. MOD-STRONG PROP. ALT'N. FELDS SMALLER & DEPTH TO M-G.			100					
93.1			100	.59	29.26								
28.38					96.0: 1.0' BAND OF X-CUTTING GREENISH QZ VEINLETS.			110					
					ABUNDANT GREYISH & GREENISH QZ VEINLETS. MOST CUT C/A @ 65°. BUT A FEW PERP. TO C/A. CA MORE ABUND. NOT & DEPTH.	STILL JUST TRACE DISS PY.							
					IN QZ VEINLET ZONE, ALT'N WEAK PROP. STILL MED. GR.			120					
111.2			100	.67	33.63 – 34.20								
33.57					110.0-112.2: STRONGLY FRACT'D ZONE & BLACK INFILLING. MOD. PROP. & MOD POTASSIC ALT'N.								

OMNI RESOURCES INC. · PROJECT OMNI: SKUKUM CK (WH Claims) DIAMOND DRILL HOLE No. 87-UG28 Sheet 2 of 3

BOX	Run	Core	%R	R.Q.D.
7				
1298			100	.72
1400			100	.85
8	1440	40	100	.95
WR1	1490	50	100	.78
9	1540	50	100	95
	1590	48	96	46
1640	1640	43	86	.20
	1690	46	92	.42
10	1740	48	96	.59
	1790	49	98	.59
WR2	1840	43	86	.35
	1890	49	98	.70
11	1940	47	94	62
	1990	50	100	.98
2042				
12				

LITHOLOGY, ALTERATION, STRUCTURE

37.47
153.0 VFG K-RICH ZONE. MOD-PERV. ALT. THEN GRADES INTO C.G. V. MAFIC RICH GRANODIORITE, MOD-WEAK PROP. ALT'N.
130 39.62
MAFIC-RICH (10%) C. GR. GRANODIORITE - hbde and biotite chloritized; plag. weakly sericitized; i.e. weak propylitic alteration. 134.1' = 3 mm. Q - Py vn. w. minor s/l gn. at 60° to the c.a.; 135.9' = 4 mm. Hem - Calcite vn at 30° to c.a.
41.17 - 43.57 SCALE CHANGE 1"=10'
135.4 - 143.7 = several Q - Carb - Ser wlts at 30° & 45° to c.a.
143.7' = Banded Qtz - Py and Q - calcite vnlts in green strongly propylitized Gd. Banding and veining ca. 30° to c.a.
145.1' to 145.9 - 146' = Q - Py vn.
Strong propy. alt'n & local bleaching w. silicification & thin (1-3 mm) Q - Carb. vns at 35° and 50° to c.a.
150.8
46.15
151.2' - 151.4' = 4 cm. wide Q - Py vn at 55° to c.a.
Overall strong propy. alt'n & local bleaching w. silicification
153.7' - bleaching becomes more intense.
154.5 - 155' = 2-3 mm Q vnlts cuts down core axis
155.1 = MOBILIZED GRANODIORITE BRECCIA W. SULPHIDE-BEARING QTZ. FRAGMENTS (2%) - Qtz. frags. carry sulphides. Gd frags strongly chloritized or silicified. Broken upper contact (? attitude.) Fabric 157' - 161.4' matrix may be a grey Rhyolite (?) Sulphide (mainly Py) bands 60° to & axis.
161.3 - Fabric 1/2" bands broken Silic. Rhyo? Brx?
FAULT ZONE (50%) IN C. GR. GRANODIORITE.
49.16
50.29
COARSE GRAINED GRANODIORITE
5-7% chl. mafics. Ser. plagioclases. Weak to mod. propylitic alt'n.
ABUNDANT QA STRINGERS, VEINS & FLOODED ZONES.
MOD. ABUNDANT EP. MOD. POTASSIC ALT. ZONES.
SEVERAL SMALL ANDESITE DIKES.
56.99
1870' 2CM WIDE WHITE QA VEIN PERP. TO C/A ± 1cm
57.61
C/A ± 1cm Q2 VEIN @ 50° TO C/A.
189.0-190.0 1' ZONE OF 1% PY IN GDR.
V. ABUNDANT CALCITE. MOD-STRONG PROP. ALT.
SCALE CHANGE 1"=20'
61.57
1950: 0.8' ANDESITE DYKE. CUTS CORE @ 50° TO C/A.
BOTH DYKES CUT BY ABUNDANT CA STRINGERS. ALSO BROKEN MARGIN AND DYKE @ 208.7-209.0'
64.01
2100: 0.4' ANDESITE DYKE. PERP TO C/A.
63.71 - 63.70

MINERALIZATION

Minor pyrite.
2-3% Py 0.1% Cu and minor Cpy
Minor pyrite
150.1'
151.2-154'= 20% py in 4 cm vn.; 1% Cu, and 0.5% Cpy.
Cpy and Py in Q. frags up to 1-1½ cm across. Overall 2% Py; 0.2% Cpy and minor sl.
Minor to 0.1% pyrite
MINOR PY.
1% PY.

GRAPHIC LOG

AH = Alteration, Min = Mineralization

FT.	
126	
130	
140	
150	
160	
170	
180	
190	
200	
210	

SAMPLE

Sample No.	INTERVAL	CORE LENGTH
6639	138.7'-143.7'	5'
6640	143.7'-145.1'	1.4'
6641	145.1'-150.1'	5'
6642	150.1-155.1'	5'
6643	155.1-160.1	5'
6644	160.1-165.1	5'
6645	165.1-170.1	5'

ANALYTICAL

O.P.T. Au	O.P.T Ag	
~~.001~~	0.53 ~~.555~~	
.037	.49	↓ HW. 43.80m ↓
.001	.10	
.053	.36	
.002	.67	
.001	.08	↑ 49.16 FW FAULT
.001	.13	

OMNI RESOURCES INC. PROJECT OMNI: SKUKUM CK (WH Claims). DIAMOND DRILL HOLE No. 87-UG-29 Sheet 3 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag	ANALYTICAL
233			100	41	66.75 – 68.29 219.3 – 224.0: MOD-STRONG @PROP. ALT. COARSE-GRAINED. DK. GREEN & ABUNDANT LT. YELLOW-GREEN EPIDOTE @ 220.6' IS SMALL SLICKENSIDED, CLAY + CHLORITE + CA FILLED SHEAR.	MINOR PY DISS THROUGHOUT.								
234			95	27	AFTER 224.0, JUST WEAK TO MOD. PROP. ALTERATION & A FEW CA + EP FILLED FRACTS + VEINS AND UNFILLED FRACTS @ 45 + 55° TO C/A.			230						
243			100	37	242.0' END OF HOLE. 73.76									END OF HOLE

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	OMNI: SKUKUM CK (WH CLAIMS)
HOLE No.	87-UG-29
COORDINATE N.	70857.5 N
E.	77761.0
DEPTH	233'
AZIMUTH	350°
ELEVATION	1309.0
INCLINATION	+37°
DATE STARTED	AUG 11, 1987
DRILLED BY	CARON
COMPLETED	AUG 13, 1987
ASSAYED BY	ACME
HOLE SURVEY	— SEPT 4/87
LOGGED BY	T.M. ELLIOTT

Reason for Drilling: To test min'z'n between ODH K-27 and the Kuba X-cut

Explanation of Results:

LEGEND

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	FT.	Sample No.	INTERCEPT	CORE LENGTH	O.P.T. Au	O.P.T. Ag
40					4.0' CASING							
1					MED. GR. QUARTZ MONZONITE PORPHYRY ~20% strongly ser. plag. 1% "pepper-sized" alt'd mafics ~several small dykes or inclusions of C. Gr. Q. Monz. 12.2' (est) At 7.9' C. Gr. Q. Monz. is 20° to core axis. At 12.1' = C. GR. QUARTZ MONZONITE at 30° to c.a. Weak to mod. propy. alt'm 13.2-15.5' = Pegmatite at 45° to c.a.							
22.4			95	.30	22.5'							
2					MED. GR. QUARTZ MONZONITE Contacts c.a. 45° to c.a. Fract. 10° and 30° to c.a.							
33.3			100	.57	Now. relatively Fresh w. 3% chl. mafics 37.4' = 2 cm. aplite dyke at 20° to c.a. Fract 15°, 45° and 80° to c.a.							
3					43.4-44.1' = dyke or inclusion of M.-gr. Q.M. Co. 45° to c.a.(?) Fract. at 45° & 80° to c.a.							
55.9			100	.70	54.7-54.9' = aplite dyke at 60° to c.a.							
4					59.5' = Q-Cal. vn. at ca. 45° to c.a. (3 mm thick). Fract. at 30°, 45° and 70° to c. axis. Rel. narrow zones of mod. propy. alt'n up to 8 cm across. 71.0' = 4 mm Qtz. vns(3) splaying off each other at 15° to c.a.							
75.0			95%	.78	77.9' = splaying Qtz. vn at 35° to c.a. (splays into 2 vns); ca. 4 mm. thick							
5					82.8' = 1 cm. Q-Py-Sl-Gn-Cpy vn at 75° to c.a. Weak prop. alt'm continues Fract. at 30° and 65° to c.a.	Vn. ctg. c.gr. Py-Gn-Sl-Cpy						
92.4			100	.73	92.5'-92.8' = Dyke of M. Gr. Q. Monz. at ca. 45° to c. axis. Strong fracturing from 92'-103' Fract. 30°, 45° and 75° to c. axis.							
6					102.4-102.7' = sheared Q. Monz. Shear ca. 45° to c.a. 106.8 = Q vn. 1-4 mm thick at 10-15° to core axis							
109.4			100	.31								
7					111-115' = Strong propy. alt'm. 116.6-116.8' = Andesite dyke at 45° to c.a. Fract. 20° & 45° to c. axis							

GRAPHIC LOG: Alt'n, Miner. — M.gr., C.gr., M.gr., C.gr., M.gr., M gr., And.

FT.: 10', 20', 30', 40', 50', 60', 70', 80', 90', 100', 110', 120'

OMNI RESOURCES INC. PROJECT DIAMOND DRILL HOLE No. 87-116-39 Sheet 2 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	ANALYTICAL
7			95	32	Weak propy. alt'n 128-129' = Strong fracturing w. gouge on fract. 132.4'-132.7' = Strongly fract'd & Qtz. veined M.gr. Q.M. dyke at 45° to c.a. Weak to mod. prop. alt'n.		130'						
8			93	24	Fract. 45° & 70° to c.a. 144.3 = 1-3 mm irreg. Q vn. w. Py-Cpy-Gn. (Vn. ca. 60° to c.a.)	Minor Py, Cpy, Gn in Q. vn.	140'						
9			88	20	C. GR. QUARTZ MONZONITE - mod. propy. alt'n. 5-7% chloritized mafics, lightly ser. plag, fresh K-spar; locally plag. are alt'd orange. SCALE CHANGE				44.35 45.5m				
9	162	14	70	0	From 151' - Q.M. is strongly fract'd and TO 1" = 10' ↓ ulte becomes strong propylitic from 158.5'		150'	6623	145.5-150.5'	5'	.001	.02	SCALE CHANGE 1"=10'
	167	3.4	68	0	Fractures at 30°, 45° and 65° to c.a.	Only minor pyrite		6624	150.5-155.5'	5'	.001	.07	
	160	1.3	60	0	159.8' = 2-3mm Q vn. at 30° to c.a. 48.97 49.04			6625	155.5'-160.5'	5'	.001	.05	
161.3							160'	6626	160.5-164'	3.5'	.082	1.48	HW 160.5' 48.92m ↓
10	164	2.1	53	0	MIXED RHYOLITE & QTZ-SULPHIDE BRECCIA - frags. 2mm-2cm; frags angular to subrounded; soft black matrix ca. 10-20% of rock; frags = 75% rhyo, 25% Qtz; Only 30%	Sulphides in matrix mainly a/w in frags 2% Py, 1-2% Aspy w/ minor Cpy and coarse Gn							
	168	4.4	88	53	RHYOLITE CRACKLE BRECCIA - tan; angular frags to 5 cm. long. 167' and 169' = 3 mm. Qtz. vns w/ 1-2% py ↓ 30° to core axis. Fract. mainly 45° to c.a.; 1 fract. 10° to c.a.	Fract-filling pyrite ca. 1-2% by vol.		6627	164-169'	5'	.002	.08	
	174	3.4	72	16	170 - 171.8' = Partly bleached green ANDESITE DYKE at 60-70° to c.a. Lower contact broken (? attitude ?)	169.3' = minor Cpy.	170'	6628	169-174'	5'	.001	.22	
179.9	179	3.6	72	0	PARTLY BLEACHED BUFF TO GREEN ANDESITE - cut by hairline to 2 mm Q-Carb-Py vnlts. = 2% by volume.	0.1-0.2% Pyrite.		6629	174-179'	5'	.001	.23	0.002, 0.14 177.4
11	184	2.8	56	7	183.3' 54.76 Lower contact ca. 45° to core axis.		180'	6630	179'-183.3'	4.3'	.001	.02	
	189	4.4	98	0	FAULT GOUGE of ground up Qtz. and Rhyolite (?) Occasional larger (6-8 mm) rounded Qtz. frags ctg. Py and aspy w/ minor Gn. Good core recovery.	Minor to 0.2% Py and Aspy Minor galena		6631	183.3-186.5'	3.2'	.001	.07	
					189.8' Contact 25° to core axis			6632	186.5'-189.8'	3.3'	.005	.18	
					191.0' BUFF RHYOLITE BRECCIA Lower contact ca. 50° to the core axis	Minor Pyrite		6633	189.8-191.4'	1.6'	.001	.15	
	194	4.4	88	57	MIXED QTZ-SULPHIDE BRECCIA (50%) w. ANDESITE (25%) & RHYOLITE BRECCIAS - Frags. up to 7 cm. long & commonly 20-30° to core axis. Sharp contact between each type. Lower contact irregular and 70° to c.axis. 3-5% Py-CARB veinlets	3-4% Py + 0.5%(?) Aspy		6634	191.4-195.7'	4.3'	.062	1.62	Native Au Prep
					VERY COARSE MULTILITHIC BRECCIA w. frags. of rhyo, and, & Gd(?) up to 7 cm long. Local infillings of Qtz. - Sulphide Breccia at 200.3-200.5', 201.3'-201.6' and 202.3'-203.0'. The latter is a vein of Q/Sx Bxa 1-1½ cm. wide running at 10° to the core axis. Banding of rock types ca. 30° to c.a.	1-2% Py, 0.1-0.2% Aspy.		6635	195.7-200'	4.3'	.024	.34	0.050
199.4	199	4.4	88	66			200	6636	200-205'	5'	.106	1.25	0.041
12	204	4.5	90	53	205' - Minz'd zone ends w. contact at 30° to core axis	205' END of MINZ'D ZONE							205' ↑ FW ↑ 62.48m
	209	4.5	90	68	ALTERED QUARTZ MONZONITE - coarse grained Strong propylitic alt'n to 212'. Local zones of brecciation. 209.2'-209.6' = Several Q py. lenses /cm by 2mm (max)	<0.1% Py.	210'	6637	205-210'	5'	.001	.08	

OMNI RESOURCES INC. PROJECT DIAMOND DRILL HOLE No. 87-HG-29 Sheet 3 of 3

BLK	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T Ag
	212	3.0	100	90						65.53			
12					215.9-216.2' = Frmd. pink aplite dyke at ca. 45° to the core axis				6638	210'-215'	5'	.001	.04
	217	14.5	90	62	1-3% dissem. & vnlt epidote Starting at 218.5 to E.O.H			220					
13					Main fracturing at 35-40° and 70-80° to core axis								
					Alteration only weak to mod. propylitic.								
233	233		95	40				230					
					E.O.H. = 233' (65.53								

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	SKUKUM CREEK WH. CLAIMS.	HOLE No.	87-UG-30
COORDINATE N.	10855.5	DEPTH	357'
E.	7776.40 E	AZIMUTH	350°
ELEVATION	1309.5 m	INCLINATION	-56½°
DATE STARTED	AUGUST 13, 1987	DRILLED BY	CABRON DIAMOND DRILLING
COMPLETED	AUGUST 18, 1987	ASSAYED BY	ACME ANALYTICAL LABS
HOLE SURVEY	87-09-04	LOGGED BY	R.J. ROBINSON / V.T.

Reason for Drilling: TO TEST KUHN ZONE ABOVE KUHN X-CUT ~60 m UP. (1360 m LEVEL)

Explanation of Results:

LEGEND

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T Ag
0.0					Quartz Monzonite: Crs.-Med. gr. Mafics altered to Chl. Plags Altered to a light green Ser. or an orange colour Potassic Alt'n. 6.5 Aplite Vein 2" across 70° to C.A. with Chl stringers. 12.3 And Xenolith 1cm x 1cm. 15.5-17.1 Many 1-4mm black stringers (chl?) 18.5-19.6 fine gr. Quartz Monzonite. 21.7 1" Aplite + Qtz. Vein. 21.8-24.2 Potassic Alt'n - Secondary Mafics + Plag + Kspar. 24.2 - altn as above.									
1													
18.4			95	.51									
2								20.0					
36.0			100	.60	35.0-35.6 Blacki stringers at 20° to C.A. 35.6 light Crackle with Chl as fillings in fractures.								
3					46.3 Qtz Vein 3mm wide/10° to C.A. 50.0-51.4 Mafics+Chl stringers 1mm wide 20° to C.A. 53.5-54.6 Slight increase in Potassic Alt'n.	tr Py.		40.0					
53.6			100	.57									
4					64.4 Black Vein let 1cm wide 50° to C.A. 65.1 ½" Qtz Vein	minor Py		60.0					
71.9			100	.76	72.9-73.1 Aplite Vein: 70° to C.A. Slight increase in Propyllitic Alt'n.								
5								80.0					
89.0			100	.54									
6					94.0-95.9 1cm Qtz Vein 0° to C.A. 96.5- 2" donut Shaped Qtz flooded zone.	2% Py minor Gn		100.0					
106.5			100	.69									
7					Main Fracture at 0°								
					119.5 Qtz Vein ½" ~70° to C.A. broken contacts			120.0					

OMNI RESOURCES INC. PROJECT SKUKUM CREEK W.H. DIAMOND DRILL HOLE No. 87-16 Sheet 2 of 4

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
123.9			95	.39	123.5-128.8 Med gr. Mafic-Rich - Quartz rich. Quartz Diorite Feldspars unaltered Mafics + Chl. rfy. Cpt Vein 1/2 mm wide 10° to CA.	1-2% Py tr. Cn		120.0					
8					128.8 Med-Cis gr. Quartz Monzonite.								
138.9			100	.71	151.0-133.2 Chl Stringers along Fractures as fracture fillings 0-10° to CA. Moderate Propylitic Alth with Slight Potassic Alth in patches.	tr. Py.		140.0					
9					138.5-139.7 Aplite dyke 50° to CA.								
149.2			100	.60	140.6 Cpt on Shear with 20° to CA								
10					153.2 Aplite Vein 1/2" 45° to CA.	Minor Py + tr Cn.		160.0					
159.4			100	.42	156.2 1/4" Wide Quartz Vein 65° to CA.								
					159.4 - 160.4 Strong Potassic Alth with Qtz vein 0°-10° to CA.	tr. Py.							
					164.0 - 167.0 Zone of Brecciation in places with flooding of And(?) Qtz Veinlets common @ 30° to CA. Epi + Chl Alth.								
					170.8 2mm Grey Qtz Vein 45° to CA.	tr. Py							
					173.0 2mm " " 40°								
11					174.4 3mm Grey Qtz Vein 60°/ Propyllitic Alth of Plags increase	tr. Py		180.0					
189.4			95	.62	Numerous Qtz. Veinlets up to 3mm wide cut CA. at 10°-60° increase in strength of Alth								
					199.7 Qtz Vein 4mm 60° to CA / 200.1-200.9 QUARTZ-DIORITE ASSOC	tr. Py.							
12					60.95 204.2 Increase in Alth. (Ser+Epi) Moderate Phyllic Many places Qtz flooded. Zone 207.9			200.0					
209.3			99	.40	210.4 - 217.0 Weak-Moderate Phyllic Alth. Dark flooding of Alth. with Qtz Veining 0°-20° to core QX15. 66.14 43.34								
					217.0 - 243.9 Continuation of Qtz flooding / Strong Propillitic Alth. Chl, Epi + Ser	tr Py		220.0					
13													
229.4			95	.45				240.0					
14													
249.0			95	.28	Alth. Weaker, less Epi + Ser.	?							
					QUITE SANDY IN A FEW ZONES TO 2.'	tr Py							
15	258		80	.25	SLIGHTLY POTASSIC ALT'D AT BASE. Q2 VEINS (GREY) @ 250, 251 & 256.5. STALE CHANGE 1" @ 10' 77.19			260.0					
15	261		83	.12	259.8 M.G. GDR OR QMZ - BLEACHED MED. GRN. ABUNDANT QZ VEINS AND SILICIC ALT'D. ZONES. INTENSE V.F.W.E CHLORITE FRACTURES AND PREDOMINANT VEINING @ 45° TO C/A	259.8 TRACE TO MINOR DISS. PY. (VFG)							
274.4	268		90	.15				264.0	6649	262.2-267.1	4.9'	0.001	0.03

OMNI RESOURCES INC. PROJECT SKUKUM CREEK 1-4142-1592653 DIAMOND DRILL HOLE No. 87-UG30 Sheet 3 of 4

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT	SAMPLE	INTERVAL	CORE LENGTH	ANALYTICAL O.P.T. Au	O.P.T Ag	
					QZ VEINS X-CUT TO FORM NETWORKS - MAFICS GONE TO CL. FELDSPARS LT-GREEN - AFEW STILL LT-TAN. LOWER CONTACT GRADATIONAL.			264				+	+	
	269	4.2	84	.58	GRANODIORITE: FINE TO MED. GRAINED; FEW TO NO MAFICS. 50% QZ. LT APPLE GREEN - TAN. QZ-FLOODED ZONE @ 268.0-269.0	267-1 61.41 1-2% PY IN A FEW BANDS OVERALL 0.5% PY MINOR GL.		269	6649	262.7 - 267.1	4.9'	0.001	0.03	
	273	3.2	80	.11	CLASTS = SWIRLS OF RHYOLITE. MOD-STRONG PHYLLIC ALT'N. 1-2%				6650	267.1 - 271.4	4.3'	0.001	0.03	
	279	.6	60	0	CLAYS. FEW MINOR CA VEINLETS. HEALED FRACTS. @ ALL ANGLES = OPEN, RUSTY FRACTS @ ALL ANGLES. SHARP LOWER CONTACT @ 80° TO C/A			274	6651	271.4 - 275.1	3.7'	0.001	0.01	
	279	2.9	72	.14	BRECCIA OF QZ, RHY, & DR & PEBBLE DIKE OR MATRIX. SHARP LOWER CONT. RHYOLITE: LT. GRN-GRY. SLT. ALT'D. BRECCIATED. CLAST SUPPORT. MATRIX OF MINERALIZED QZ. HACKLY FRACTS @ ALL ANGLES. RUSTY WEATH. ON FRACTS. SHARP LOWER CONTACT @ 45° TO C/A.	275.1 90.11 1-2% PY. 276.1 90.11 1-5% TOTAL SX. MOSTLY PY & MINOR SL.		275	6652	275.1 - 276.1	1.0'	0.001	0.04	HW SHEAR. ↓ 83.85 ↓
16	285	3.5	70	.44	DIATREME OR PEBBLE DYKE	285.1 90.63		279	6653	276.1 - 280.6	4.5'	0.001	0.15	
	287	2.3	57	.10	SILICEOUS, BLACK, GLASSY MATRIX WITH CLASTS OF GDR., ALT'D GDR, RHY, ALT'D RHY, QZ, FS, ± PY XTALS. CLASTS RANGE IN SIZE FROM <1MM TO 3CM.	TRACE DISS. PYRITE.		280.6	6654	280.6 - 283.0	2.4'	0.001	0.01	
	291	3.2	80	.47				284	6655	283.0 - 287.0	4.0'	0.001	0.01	
17	295	3.2	80	.49	MATRIX VARIES FROM BLACK TO DK GRY TO GREENISH.			287.0 289	6656	287.0 - 291.0	4.0'	0.001	0.02	
	300	3.9	78	.32	MOST COMMON FRACTURE ANGLE IS N20° TO C/A			291.0 294	6657	291.0 - 295.0	4.0'	0.001	0.02	0.001, 0.038/33.7
					ABUNDANT GREY-WHITE QZ VEINLETS (N1MM WIDE) CRISS-CROSSING THROUGHOUT ZONE. LOWER CONTACT			295.0 299	6658	295.0 - 300.0	5.0'	0.001	0.03	
18	304	2.2	55	0	LOST. IS CORE GROUND.			300.0	6659	300.0 - 304.0	4.0'	0.001	0.01	
	309	2.8	56	0	(IN NEXT SECTION, DUE TO CORE LOSS, CONTACTS + UNIT INTERVALS MUST BE ONLY APPROXIMATE.			304	6660	304.0 - 309.0	5.0'	0.001	0.03	
	314	2.9	58	0	DIATREME OR BRECCIA WITH QZ XTALS & SMALL ROCK FRAGS IN MATRIX OF APHANITIC, SOFT OLIVE GREEN (? ANDESITE?) LOWER CONT. @ 25° SOFT INTERVAL ALT. APHANITIC & RHY CLASTS. GREEN QUARTZ OR SILICIFIED GREEN RHY. CHUNKY - LIMONITE W. BRANCH UP. CORE LOST. RUSTY FRACTS. LOWER CONTACT FAULT @ 30° TO C/A	307 94.16 TRACE DISS PY. 310 96.16 TRACE DISS PY. 314.5 96.16		309	6661	309.0 - 310.7	1.7'	0.010	0.08	
	319	2.7	54	0	ZONE OF V. FROZ ZACHARY, CORE BRN, Ground, Rounded FRAGMENTS, mixture of RHY BX, Green QTZ, Grey QTZ sulfide occ QD fragment, overall appearance is olive grey Chorty Minerals related dike matrix BX. 3:1 ± CARBOD Contacts lost	1-2% T.S. as PY TR CPY, TZ Ga		314	6662	310.7 - 314	3.3	0.007	0.44	0.008, 0.32 /44.8
	320.5	0.7	45	0				319	6663	314-319	5.0	0.011	0.19	
	321.5	0.5	30	0					6664	319-320.5	1.5	0.007	0.81	Nat. Au Prep
	323	0.9	30	0					6665	320.5-321.5	1.0	0.007	0.25	
	324	0.2	50	0				324	6666	321.5-323	1.5	0.006	0.46	
	324.2	0.2	25						6667	323-325 (?)	2.0	0.024	3.58	0.017
19	324.5	25	100	0	325 CORE BLOCKS OFF LOG @ 323.10: QTZ/SULFIDE BX. multiple stage QZ, QTZ white, grey/tonal Rehealed & cracked, Silicified/Silicified T.S. 7-10% PY, ASPY, SPH, GA, TR CPY, Tetra Linear to QTZ, color shattered & BXL, NO CaCO3 & has MIN. Vugs w/ no open space fill. ag.	7-10% T.S. PY, AsPy SPH, GA: TR CPY, Tr Tetra		325		SINCE @ 323 Drag Core measures 85'				
	324.0	25	100	0				327	6668	325-329.5	5.5	0.294	9.86	0.348 m, 0.186, 6.90
	329.5				MIXED BX, GD, QZ Stockwk, brecciated RHY, cutby rehealed QTZ VITS & ¼ Stockwork, NO CaCO3	T.S. 2-3% diss PY. Tr CPY & FY mins			6669	329.5-333.5	4.0	0.001	0.05	
	334	3.7	74	16	334.5 FLT CNTC 40° grey FIG clay	333.5		334	6670	333.5-337.9	3.4	0.030	0.26	
					ZONE OF CRUSHED QTZ W/ clay gouge, Range to sandy clay to GOUGE, QTZ, GOLD RHY fragments, SEPARATE stage then 336.3 FLT CNTC40° grey clay to Sandy clay @ 20° w/ 60° intersect slip 337-342 FAULT CLAY & CRUSHED matrix & green ZAY; OD.	2.1% UF. diss PY NO VISIBLE SULFIDES		339	6671	337.9-342.0	5.1	0.001	0.32	
338.1	339	4.9	98	0										

OMNI RESOURCES INC. · PROJECT SKUKUM CREEK (WH) DIAMOND DRILL HOLE No. 87-W30 Sheet 4 of 4

BOX	Run	Core	% R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T Ag	
					MAJOR F.W. FAULT ZONE, grey to Sap Green, w/ minor CaCO3 remnant ~5% crush	NO VISIBLE SULPHIDES		337						↑ FW FAULT 104.24 ↑
	344	4.9	96	0	337.5-342 GRANO DIORITE STR. Qtz, Sap Alteration, cracked Hydrofrac's ADV. ALT.			344	6671	336.5-342	5.1	0.001	0.32	
									6672	342-345	3.0	0.001	0.01	
	349	4.4	88	.56	345-EOH mod to STR PHYLLIC, minor ARGILLIC Qtz Ser & clay alt plag ↑ and EP w/ chl on fract as later event, cracked & Qtz vns, CaCO3 ↓ to EOH.	TR-1% Disc'd bits of Py		349	6673	345-349	4.0	0.001	0.05	
20	352	2.6	87	.20					6674	349-353	4.0	0.001	0.02	
								354						
	357	3.8	76	.20	EOH 108.91				6675	353-357	3.0	0.001	0.03	
								357						

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling	To test Kishanzone to the West of Hole UG25.
Explanation of Results	HIT STRUCTURE BUT NOT MINERALIZED AT ALL.

LEGEND

PROJECT	SKUKUM CREEK.	HOLE No.	87-UG31
COORDINATE N.	70852.52	DEPTH	~~585~~ 590'
E.	77759.38	AZIMUTH	~~270°~~ 265° Surveyed
ELEVATION	1307.11	INCLINATION	0°
DATE STARTED	August 18, 1987	DRILLED BY	CARON DIAMOND DRILLING
COMPLETED	August 27, 1987	ASSAYED BY	ACME ANALYTICAL
HOLE SURVEY	SEPT. 4/87	LOGGED BY	RJR.

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag
1					QUARTZ MONZONITE. MED-COARSE-GRAINED. PALE TO DK. GREENISH-GREY. VARIOUS ALTERATION TYPES PRESENT IN WEAK TO MODERATE DEGREE. MOST CORE WEAK TO MOD. PROP. ALT. LT. GRN-GRY & MASSIVE CAST DUE TO K-SPAR. MOD. HARD. FAIRLY COMPETENT. WEAK TO MOD. POTASSIC ALT'N IN ZONES TO 7 m.	TRACE VFG DISS. PY ↓		10					
200			85	.30	16.0-18.0' POTASSIC ALT'D. ZONE. C.G. LT GRY & PINK/ORANGE FS.			20					
2					A FEW SMALL EPIDOTE + SERICITE-FILLED FRACTS + STRINGERS. A FEW MINOR HAIRLINE QTZ-CA VEINS. GREY/WHITE QTZ VEINS TO 6MM.			30					
339.7			95	.59	CG TO 29.0, THEN MED. GR TO 42.5'. MAFICS F.G. AND MORE SPARSE IN M.G. ZONE. FRACTS + VEINING @ 35 + 85° TO C/A. A FEW SMALL CA VEINLETS + STRINGERS. MINOR WEAK CRACKLE.			40					
3					52.8-58.3 DARKER GREEN MOD-STRONG PROP ALT. SLIGHT SILICIFIED. 1-2 SMALL QZ VEINS / FOOT. 2-3% PY OVERALL. ABUNDANT CL. SHARP 35° CONTACT AT END, WITH BRECCIATION.	52.8 PY STRINGERS + BLEBS + QTZ VEINS. ~ 2-3% PY.		50					
559			100	.53	PALE, PINKISH TAN FELSIC-POOR ZONE. MAY BE DYKE WITH SHD LOWER CONTACT. <5% MAFICS ALT'D TO CL. ±EPIDOTE MOSTLY PSEUDO + PLAG + SL + K-SPAR. LOWER CONTACT SHARP 70°	58.3 TRACE DISS PY		60					
4					GRANODIORITE: / BLACK + WHITE. COARSE-GRAINED. ALMOST TOTALLY UNALTERED. PLAG SLIGHTLY CHLORITIZED. A FEW HAIRLINE FRACTS + YELLOW BLEACHED HALOS. MINOR CRACKLE. 66.0 = 5 cm APLITE DYKE @ 65° TO C/A. FRACTS @ 35° TO C/A. 2 cm QZ VEIN @ T/C	67.5 SLIGHT TRACE DISS PY		70					
737			100	.54	73.0-80.0 MOD. PROP ALT'D. BASED 75.0-78.0' & STRONG POTASSIC ALT'N + ABUNDANT SE, CL, EP. HAIRLINE FRACT. & FS STRONGLY SERICITIZED.	80.8		80					
5					80.0 MOD. ALT'D GDR FOR 0.8', THEN QMZ. WEAKLY ALT'D. V. SLIGHT GREENISH-TAN. STRONG POTASSIC ALT'N IN NARROW HALOS AROUND HAIRLINE FRACTS. A FEW TO NARROW, CA-RICH ZONES & TRANS CA VEINS.	TRACE DISS PY.		90					
914			100	57	FRACTURES @ 35, 45 + 75° TO C/A. 91.0 GRADATIONAL LOWER CONTACT.	99.0		100					
6					VERY WEAKLY PROP. ALT'D. CG GDR. MOD. ALT'D. 96.0-97.5. ABUNDANT MAFIC-RICH XENOS TO 10 cm. (FG) WEAK CRACKLE, MINOR QZ VEINING & A FEW NARROW CA STRINGERS.	NO VIS SV.		110					
1089			100	67	HG V FG. (TO 9mm) YELLOW HALOS AROUND HAIRLINE FRACTS.			120					
7					111.0-113.0 PY + SL IN QZ-RICH ZONE. QZ VEINS CUTTING CORE @ 30° TO C/A MINOR CA STRINGERS IN MIN. ZONE.	111.0: @ 2.0' 3% PY & 2% SL. IN BLEBS, STRINGERS ~ DISS.							

OMNI RESOURCES INC. — PROJECT SKUKUM CREEK — DIAMOND DRILL HOLE No. 87463 Sheet 2 of 5

BOX	Run	Core	% R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
1275			95	49	C.G. WEAK TO MOD. PROP. ALT'N AS ABOVE. (GDR)	NO VIS SX.		120					
8					132.0' 1cm QZ-CA VEINLET- ± MOD-STRONG PHYLLITIZED HALO. LOWER CONTACT SHARP W/ FRACTURE @ 35-40° TO C/A.	134.4		130					
1455			100	60	C.G. QMZ ORANGISH-TAN. SLIGHTLY SMALLER GRAINS THAN MOD'E. FEWER + SMALLER H.B. XTALS. GREY & GREEN-GREY CALCEDONY QZ VEINLETS. WEAK CRACKLE TEXTURE. CHLORITE ON SOME FRACT. SURFACES. FRACTS. BTWN 45 & 75° TO C/A. MOSTLY ~50° HEMATITE STAINING ON SOME FRACTS. 148.0 - 149.6' ± PALE LT. APPLE GREEN - MINOR ALT'D ZONE. V. ABUNDANT SERICITE ON BIOT. FRACT. PLANES + DISPLACING PLAG.	TRACE DISS PY & BLOB OF PY IN QZ @ 150.6'.		140					
9					150.6 QZ-FLOODED ZONE WITH QZ BLOB + 2cm BLOB OF FG PY LESS K-SPAR DEPTH UNTIL BACK TO GDR T MOD. PROP ALT AT BASE.			150					
165			90	60	VERY GRADATIONAL CHANGE FROM ABOVE. CHANGES OVER ~5'. BACK TO V.C.G. GDR ± 30% HB XTALS TO 9mm. A FEW LARGE (8cm) DARK XENOS. SHARP LOWER CONTACT @ 70° TO C/A. CONTACT IS A MAGMATIC SEGREGATIONAL ONE. NO FAULT OR FAULT. JUST INCREASE IN K-SPAR.	160.0 NO VIS SX. 173.0		160					
10					M-C.G. QMZ. MOD POTASSIC ALT. OVERALL. ABUNDANT QZ / CA VEINLETS THROUGHOUT @ ALL ANGLES, MINOR GREY CALCEDONY VEINLET @ 177.6'	BARR TRACE DISS PY.		170					
1823			100	76	0.6' WITH 30% DARK SMALL XENOS (LIKE BXX) THEN GDR.	182.0		180					
11					C.G GDR ± LARGE HB XTALS. MOD. POTASSIC ALT'D TO 192' VFG BLACK VEINLETS & FRACT. FILLING ABUNDANT EP. STRINGERS, STRONGER ALT. 188.4-189.4: ZONE ± 40% DARK XENOS 2-3 CM ACROSS. ROUNDED. POTASSIC ALT'D HALOS AROUND HAIRLINE FRACS. & PHYLLIC	BARR TRACE DISS PY.		190					
2000			95	46	198.0 ± 0.8' F.G. SILICIC ALT'D BAND. ABUNDANT QZ + SS.			200					
12					CA STRINGERS MORE COMMON. MORE PERVASIVE CRACKLE ± DEPTH. CL, EP + SE VEINLETS. STRINGERS & FRACT. FILLING MORE COMMON ↑ DEPTH. FRACTS. STILL 45-70° ± CA & CL LINING.			210					
2192			95	56	212-213.5: 1cm QZ VEIN; CARBON ON SALBAND. WHITE ON WALLS. RUNNING ALMOST PARALLEL TO C/A. OFFSET BY LATER FRACTS. BANDS OF STRONGER PROP. ALT'N AROUND FRACTS + STRINGERS. STRONG CRACKLE AFTER 220'.			220					
13					1cm QZ VEIN (WHITE) @ 70° TO C/A @ 229.8' EARLIER STRINGER RUNS ALONG CORE FROM 231-233'. GRADATIONAL LOWER CONTACT.	233.0'		230					
2347			100	60	M-G. QMZ. MOD PROP. ALT'N OVERALL ± ZONES MORE & LESS ALT'D. MOD CRACKLE IN MORE ALT'D ZONES. SOME ZONES OF LESS K-SPAR CONTENT. VEINS & FRACTS MOSTLY 65-75° TO C/A, BUT MANY AT OTHER ANGLES. MANY YELLOWISH QZ VEINS FROM 222-232. 240-245 - MOD PHYLLIC ALT. A FEW XENOS - MOSTLY IN QBR ZONES. 247-249: GREY, YELLOW & WHITE QZ VEIN SWARM. SEVERAL CT BAN APLITE DYKES ~20cm.	TRACE TO MINOR DISS. PY.		240					
14								250					
2446			100	61	251-263: PHYLLIC ALT'D QZ FLOODED ZONE. ABUNDANT YELLOW - GREY QZ VEINS. MOD-STRONG POTASSIC & WEAK PHYLLIC ALTERATION TO 269.9'			260					
15					PYRITIC SHEAR @ 269.4' @ 45° TO C/A. XTALS TO 1cm.			270					
			100	45									

OMNI RESOURCES INC. · PROJECT SKUKUM CREEK · DIAMOND DRILL HOLE No. 87-1631 Sheet 2 of 5

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T Ag
16					MOD - STRONG PHYLLIC ALT. C.G. GDR.			270					
286			100	55	A FEW SMALL (1-2cm) XENOS. ABUNDANT (2-3/FT) SMALL GREY + GRNSH GRY QZ VEINS CUTTING CORE @ ALL ANGLES. BLEACHED LT. APPLE GREEN COLOR. MOD STRONG HEALED CRACKLE.	MINOR DISS PY.		280					
17					285-287. V. SOFT, STRONG PHYLLIC ALT'D / WEAK ARG. QUITE CLAYEY. QUITE CRUMBLY. CLAY ZONE @ 290'. 287 on: STRONG PHYLLIC ALTERATION, WITH NARROW ZONES OF WEAK TO MODERATE ARGILLIC ALT. NARROW ZONES OF MOD. POTASH AROUND FRACTS. MINOR FT. SILICIFIED ZONE @ 293'.	A FEW NARROW ZONES OF 1-2% V FG DISS PY.		290					
303			90	.46	V. CRUMBLED + BROKEN UP @ 299-300'. SILICIFIED PATCHES & INTERMITTENT CLAY @ 305'. MOD. ARGILLIC FROM 306.2-311.0.	INCREASING PY CONTENT W DEPTH		300					
18					2 cm APLITE DYKES @ 317 + 320.6. CUTTING CORE @ 45° ABUNDANT ~8% DK. GRN-GRY. HAIRLINE FRACTS. A FEW FRACTURES @ 15-20° TO C/A. SOME EVEN SHALLOWER. 1' ARG. ZONE @ 322.5'			310					
323			90	.80		~1% FG DISS PY.		320					
19					324.3-335.0 WEAK TO MOD. PROP. ALT'N. MOD. PHYLLIC ALT. ON FRACTS & BREAKS. ABUNDANT EPIDOTE, CA, QZ + CL VEINS & VEINLETS. MANY VEINS PARALLEL TO C/A, OTHERS 20-30°.			330					
334			90	.30	335.0 - CLAY BANDED SHEAR ZONE. STRONG PHYLLIC + ARG. ALT'N. 339.0-342.0. QZ VEIN SWARM. GREEN-GREY, GREY - WHITE QZ VEINS CUTTING CORE AT ALL ANGLES. CORE V. BROKEN UP + CRUMBLED SOME CLAY.			340					
20					342-382. GG GDR. 2 NARROW ALT'D ZONES AROUND FRACTS + VEINLETS. EP-FILLED FRACTS @ 75° TO C/A. CORE APPEARS BANDED @ 75° DUE TO LARGE # OF FRACTS & ALT'N ALL AT THIS ORIENTATION. LOWER CONTACT CHLORITIC, BRECCIATED.	SX.		350					
352					EXPLOSIVE, HYDROTHERMAL BRECCIATED GDR. AND CLAST MATRIX. CLASTS FROM 1-10mm TO 2.5cm. RUSTY CLAY MATRIX.	352 1-2% PY. MINOR cpy SL		352	6676	352.0-355.7	3.7'	0.001	0.08
356.7					C.G. GDR. PHYLLIC, PROPYLITIC, SILICIC ALT'D AROUND FRACTS + VEINS. AND REALLY STRONG ALT'N AFEW SMALL (2-3 cm) XENOS, INC. ALT & DEPTH			356.7					
361			95	.44	SCB = MOD - STRONG PHYLLIC ALT'N. PALE APPLE GREEN. MANY X-CUTTING GREY AND GREY-WHITE QZ VEINS TO 1cm. & INCREASING GLASS, VEINS AND FLOODED QZ ZONES. MOST VEINS @ 45 + 65° TO C/A			360					
370			95	50	1' DK GRN FLOODED ZONE @ 377.0'	MINOR TO TRACE UFG DISS. PY.		370					
22					383 50% CA VEINS FOR 0.5'. THEN CLAY ALT. ZONE FOR 1 FT. V. CRUMBLY.			380					
391			100	71	391-392 - ARG. ALT. ZONE. RECESSIVE CLAY IN FRACTS. V. CRUMBLY. MANY QZ VEINS ALMOST PARALLEL TO C/A. STRONG CRACKLE TEXTURE. FILLED C CA, CL, EP, SL + QZ			390					
23					404' QZ FLOODING FOR 1'. MORE STRONGLY ALT'D + BROKEN UP C DEPTH. MORE CRACKLED. V. BLEACHED.	minor PY.		400					
414			90	34	414.0': 1' CLAY-ALTERED ZONE. V. CRUMBLY STRONG PHYLLIC ALT'N FROM HERE DOWN.			410	6677	411.7-416.2	4.5'	0.001	0.09
								420	6678	416.2-421.3	5.1'	0.001	0.01

OMNI RESOURCES INC. · PROJECT SKUKUM CREEK · DIAMOND DRILL HOLE No. 87-4631 · Sheet 84 of 95

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT 420	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
					ALTERATION MORE INTENSE & DEEPER 421.6' GREEN QZ + EP VEINLETS. 5cm WIDE. 422.0-ZONE OF STRONG EPIDOTE VEINING + ALTERATION. 50-60 STRINGERS PER FOOT, DECREASED @ 15-20° TO C/A. ENDS @ 425.0'	TRACE VFG DISS PY.		421.3	6679	421.3-426.0	4.7'	0.001	0.01	
24		SCALE CHANGE				SCALE CHANGE 1":10'		426.0	6680	426.0-430.9	4.9'	0.001	0.01	SCALE CHANGE
	435		95	35	425.0-439.2: STILL C.G.GDR BUT WITH INTENSE PROP. / MOD. WEAK ARGILLIC ALT'N. ABUNDANT EP + GRN-GRY QZ VEINS. V. ABUNDANT CA. V. STRONG OVERALL FIZZ. MANY QZ-CA VEINS, and CA OR FRACS. 10cm QZ VEIN @ 20° TO C/A @ 437.5. MINOR MOD. POTASSIC ALT'N.	MINOR TO 1% PY. V.F.G. DISS.		430.9	6681	430.9-435.0	4.1'	0.001	0.01	
	440		92	46	439-440 ALL FEATURES ALT'D TO CALCITE and CLAY. Lower contact sharp	439.2		435.0	6682	435.0-440.0	5.0'	0.001	0.02	
	442		50	0	CG GDR INTENSE PHYLLIC ALT'D. & BANDS OF MOD-STRONG CLAY/CALCITE ALT'N. MAFICS V.BLACK, V.SOFT. WHITE STREAK. STRONG CRACKLE. MANY BLACK VEINLETS & FRACT FILLINGS. MUCH CORE LOST. V. BROKEN UP. Lower contact broken no visible fract. orient. often due to broken up core.	TRACE DISS. & EG PY.		440.0	6683	440.0-442.0	2.0'	0.001	0.06	
25	446		78	33		446.0		442.0	6684	442.0-446.0	4.0'	0.001	0.06	
	450		26	0	V. SOFT, CRUMBLY C.G.GDR. F.S. ALT'D TO CLAY + CALCITE? ABUNDANT RECESSIVE CLAY AND V. ABUNDANT CA. STRONG OVERALL FIZZ. PROP. + ARG. ALT'N. V. POOR RECOVERY IN SOME ZONES.			446.0	6685	446.0-450.0	4.0'	0.001	0.06	
	454		58	0	STRONG CRACKLE TEXTURE & CL, EP, SE. INFILLING ABUNDANT CA FRACT-FILLING + STRINGERS. - SOME & QZ.	RARE TRACE VFG DISS. PY.		450.0	6686	450.0-454.0	4.0'	0.001	0.02	
454.6	459.0		25	.12	BANDS OF MORE & LESS INTENSE PROP. ALT'N, & A FEW NARROW BANDS OF SOFT, GREEN, MOD. PROP PHYLLIC ALT'N. FRACTS + VEINS MOSTLY 65-85° TO C/A			454.0	6687	454.0-459.0	5.0'	0.001	0.02	
	462		90	48	Lower contact broken and indistinct.	462.7		459.0	6688	459.0-462.0	3.0'	0.001	0.03	
	467		88	32	GREEN-GRY QZ FRAGS BROKEN UP BY CA/CLAY IN GDR. ABUNDANT CA STRINGERS & AMYGDULES. STRONG CRACKLE. Lower cont. 35° TO C/A. LT. GRN. PHYLLIC ALT'D GDR & scattered & bands of GRN-GRY QZ. Lower cont. 35° TO C/A.	TRACE DISS PY 466.0 TRACE DISS PY.		462.0	6689	462.0-467.0	5.0'	0.001	0.03	
26	472		95	40	V. SOFT, LT. GREEN C.G.GDR. ALTERNATING THIN BANDS OF STRONG PROPYLITIC ALT'N & V. ABUNDANT CA AND MOD-STRONG PHYLLIC ALT'N. QUITE CRUMBLED. CA-RICH ZONES SOFTEST AND MOST CRUMBLY. CA MAY BE LATE, IE. AFTER CLAY ALT'N. FRACTS MOSTLY 45-55° TO C/A & A FEW SUB-PARALLEL FRACTS & VEINLETS.	474 MINOR EG. DISS. PY.		467.0	6690	467.0-472.0	5.0'	0.001	0.03	
472.2	477		73	46	Lower contact @ 50° TO C/A.	476.0		472.0	6691	472.0-477.0	5.0'	0.004	0.05	
					HARDER GDR, STILL LT. GRN & BLACK SOFT MAFICS. LESS CA. WEAK TO MOD. PHYLLIC ALT'N, 2 QZ VNS 3 SX + 15cm VEIN. 479.5 cont. 60° TO C/A	minor FRACT. FILLING + VNLT. 479.6, GL's + PY. + DISS PY.		477.0	6692	477.0-481.0	4.0'	0.002	0.07	
	481		51	.09	STRONG PHYLLIC ALTERED C.G.GDR. LT. GREEN. FAIRLY SOFT. NO DARK MINERALS PRESENT. ABUNDANT LT. GRN-GRY QZ VEINS CUTTING THROUGH CORE AT ALL ANGLES. RE (STOCKWORK)	RARE TRACE DISS PY + SL, GL, PY IN QZ VEINS + FG PY FRACT. FILLING.		480						
	483		48	0	STRONG CRACKLE (HEALED) OVERALL. STRONG CLAY ALT'N FROM 484.7 - 485.3. V. SOFT. FRACTS 45-50° TO C/A 2cm CA VEIN @ 487.6'.			481.0	6693	481.0-483.0	2.0'	0.001	0.01	
27	488		86	28	487.0 5mm QZ VEIN & 20% 5X GRAINS TO 4mm SL, GL, PY ~ = PROP. Lower contact SHARP ~ PERP TO C/A	488.0		483.0	6694	488.0-488.0	5.0'	0.001	0.11	HW SHEAR ZONE ↓ 148.74m ↓
	493		94	46	CLAY-GOUGE SHEAR ZONE. MAY WELL BE THE H.W. SHEAR. V. SOFT, LT. TO DK. GREEN, SHEAR BANDS ORIENTED @ ~50° TO C/A. ALMOST ALL FEATURES OVERPRINTED BY SHEAR STRUCTURE. JUST ONE LATE MINERALIZED QZ VEIN & PY + GL. GRADATIONAL CONTACTS AT BASE.	minor - 1% DISS FG PY. UNIDENTIFIED, V.F.G DARK MINERAL DISS THROUGHOUT. MINOR.		488.0	6695	488.0-493.0	5.0'	0.001	0.62	
494.4	496		76	30	494.3-500.7. VERY LT TAN ALT'D GDR WITH V.DK GREENISH BLACK FRACTURE-FILLING & STRINGERS. POOR RECOVERY AND VERY BROKEN UP & CRUMBLED & SHATTERED. QUITE HARD (SILICIFIED) IN LT. ZONES. DARK, CHLORITIC MATERIAL V. SOFT.	494.3 MINOR PY + GL IN QZ VEIN MINOR DISS PY & GL & SL. MED. GR (1mm) ALSO 5% IN VEINLETS.		493.0	6696	493.0-496.0	3.0'	0.001	0.38	
	500		58	0				496.0	6697	496.0-500.0	4.0'	0.001	0.25	
								500						

OMNI RESOURCES INC. PROJECT Skukum Creek DIAMOND DRILL HOLE No. 87-467A Sheet 5 of 5

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T Ag
	504		37	0	MOST VEINLETS & STRINGERS ORIENTED ~ 60-70°, BUT IS ALSO ABUNDANT VEIN MATERIAL FILLING CRACKLE STRUCTURE AT ALL ANGLES. NO ROTATION. ABUNDANT SERICITE ON SOME FRACT. SURFACES. SERICITIZED FRACTURES CUT CORE @ 20° TO AXIS. LESS ALT'D @ DEPTH UNTIL BACK TO PHYLLIC ALT'D GDR. PALE GRN.	AS ABOVE.		500	6698	500.0-504.0	4.0'	0.001	0.16
28	509		93	0				504.0					
	511		87	0	FINE-MED. GRAINED GDR. SERICITIZED, SILICIFIED, EPIDOTIZED. BANDS OF STRONG CLAY ALT'N. BANDING & VEINING @ 25-30° TO C/A. ABUNDANT CA OVERALL & IN STRINGERS & FRACTURES. MINOR CHLORITIZED. A FEW NARROW, GREEN-GREY QZ VEINS. LOWER CONTACT SHARP @ 45° TO C/A	SPEC.		509.0	6699	504.0-509.0	5.0'	0.001	0.08
516	515		92	15		TRACE VFG DISS. PY.		510	6700	509.0-511.0	2.0'	0.001	0.04
	519		84	0	CLAY GOUGE SHEAR ZONE. CLEAVE @ SILK ALT'D GDR. SOME RUBBLY BRECC. LOWER CONT.	515.0 SLIGHTLY ALTERED TR SL/GL.		515.0	6701	511.0-515.0	4.0'	0.001	0.08
29					BRECCIATED GRANODIORITE. M-C.GR. MATRIX SUPPORTED. MUCH ROTATION OF CLASTS. SOME CLASTS SUB-ANGULAR TO SUB-ROUNDED. MOST CLASTS GDR, BUT SOME ANDESITE AND A FEW QZ SX. BX. MATRIX MOSTLY GREEN-GREY QZ, EPIDOTE, CHLORITE & CALCITE.	MINOR PY DISS, ? IN QZ & QZ SX & BX. TRACE SL, GL IN QSB.		519.0	6702	515.0-519.0	4.0'	0.001	0.167
	524.5		67	07				520	6703	519.0-524.5	5.5'	0.001	0.13
530.7	529.5		98	58	A FEW NARROW, CLAY-RICH SHEARS. ABUNDANT CA. IN AREAS WHERE LARGE FRAGS OF GDR REMAIN, IS V. STRONGLY PHYLLIC ALT'D. A FEW SMALL OPEN-FILLED FRACTS. QZ SX BX LOOK AS THOUGH IT WOULD RUN WELL IF THERE WAS ENOUGH, HOWEVER THERE IS ONLY A TRACE TO MINOR COMBINED SA. PY, GL, SL.			524.5	6704	524.5-529.5	5.0'	0.001	0.10
	535.0	5.5	100	29				530	6705	529.5-535.0	5.5'	0.001	0.12
30	540.0	5.0	100	42	PROBABLY HYDROTHERMAL BRECCIA. FEW MEASURABLE FRACTS ORIENTED ~ 60-65° TO C/A. LOWER CONTACT INDISTINCT.			536	6706	535.0-540.0	5.0'	0.001	0.09
	545.0	4.4	88	39	SILICIFIED & CLAY ALT'D BRECCIA. SHEAR. ABUNDANT CLAY. LOWER CONT. SHARP @ 15°	540.0		540	6707	540.0-545.0	5.0'	0.001	0.14
548.1		2.5	50	80	HYDROTHERMAL BRECCIA: PALE GREY, SILICIFIED. ROUNDED TO SUB-ANGULAR CLASTS OF VARIOUSLY ALTERED GDR, RHY, QZ SX BX & ANDESITE. (CORE LOST FROM 550.0 - 552.0; ONLY GRAINED END OF A PEBBLE OR TWO OR SO BY) MOST CLASTS PALE GREY, SILICIFIED, PHYLLICALLY ALT'D. GDR. MOST CLASTS CRACKLED AND FILLED WITH MATRIX SOLUTION. CLAST. SUPPORTED. CLASTS RANGE IN SIZE FROM 0.5mm TO 4CM. MATRIX IS MED-GREY-GDN. V. SOFT IN PLACES & V. HARD IN OTHERS. APPEARS TO BE MIXTURE OF CHLORITE AND GREEN QZ. FROM 545.0-548.6 CORE LOST. JUST CUTTINGS FOUND.	SAME BARE TRACE DISS PY. TRACE VFG DISS PY. TRACE SL/GL IN ONE OR 2 CLASTS OF QSB.		545.0	6708	545.0-546.4	1.4'	0.001	0.30
	550.0							546.4	6709	546.4-548.6	2.2'	0.001	0.02
31	555.0	4.1	82	83				550	6710	548.6-553.1	4.5'	0.001	0.02
								553.1	6711	553.1-555.0	1.9'	0.001	0.01
	560.0	3.5	70	86	COARSE-GRAINED GRANODIORITE. STRONG PROP. TO MOD. PHYLLIC ALT. LESS ALTERED WITH DEPTH. MANY (STOCKWORK) SMALL CALCEDONY VEINS AT TOP OF UNIT - DECREASING & DEPTH. TOP 10' BRECCIATED & FILLED & SOFT, V.DK GRN MATRIX. GRADUALLY FADES OUT. SCALE CHANGE	TRACE TO NO DISS. PY. SCALE CHANGE 1"=20'		555.0	6712	555.0-560.0	5.0'	0.001	0.08
565.0	565.0	5.0	100	90	560.0' 1' SECTION V. STRONGLY SILICK ALT'D. V. PALE. ABUNDANT QZ, EP. GDR V.F.G. BANDS OF STRONG SILICIFICATION & SERICITIZATION TO 1'.			560	6713	560.0-565.0	5.0'	0.001	0.10
568.0	570.0	5.0	100	66				565.0	6714	565.0-569.1	4.1'	0.001	0.04
32	575.0	4.5	90	81	575-577.2 BLEACHED GREEN GREY STRONG SILICIFICATION, THEN JUST MINOR NARROW QZ VEINS. MINOR CRACKLE. FRACTS @ 65° TO C/A	AS ABOVE.		569.1	6715	569.1-574.1	5.0'	0.001	0.02
	580.0	5.0	100	96				570					
	585.0	5.0	100	92	MOD. ABUNDANT CA STRINGERS & FRACT FILLING TO END.			574.1	6716	574.1-577.2	3.1'	0.001	0.03
588.2		5.0	100	52				577.2					
33	590.0				EOH.			580					

590.0 END OF HOLE 590.0'

↑ SCALE CHANGE ↑
170.69 FW OF ZONE

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	SKUKUM CREEK (WH CLAIMS)
COORDINATE N.	70852.5
E.	77759.4
ELEVATION	1307.6
DATE STARTED	SEPTEMBER 3, 1987
COMPLETED	
HOLE SURVEY	
HOLE No.	87-4G32
DEPTH	349.0'
AZIMUTH	316
INCLINATION	-54
DRILLED BY	CARON DIAMOND DRILLING
ASSAYED BY	ACME ANALYTICAL LABS
LOGGED BY	RJR/TME

Reason for Drilling: TO TEST UPWARD EXTENSION OF HIGH GRADE SHOOT ABOVE HOLE 4G26

Explanation of Results:

LEGEND

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag
1	19.0	17.0	89	65	CG. PROP. ALT. GDR. FRACTS @ 45°-90° TO C/A MINOR QZ VEINING. DARK GREEN SERICITE ± CB. LOWER? CONTACT GRADATIONAL. CG. PROP ALT'D QMZ MALLOWISH-GREY. AMORPHOUS K-SPARS, LARGE PLAG ÷ QZ XTALS. SOME ZONE U.OK GREEN ALT'N. EP ± SE ON FRACTS ± IN SMALL STRINGERS. MINOR QZ VEINING. MINOR TO ABUNDANT CL. VFG SEGREGATED K-SPAR ZONE @ 12.5'.	5.0 NONE. TRACE TO MINOR DISS PY.		0.0					
2	17.1	17.1	100	59	21-23 SWIRRELED, BLEACHED ALT'D LT GRN-GRY ZONE. FRACTS @ 40-60° & 90° TO C/A. MINOR BLOBS, STRINGERS OR XENOS OF K-SPAR RICH, VFG - AMORPHOUS ROCK. MINOR ZONES OF POTASSIC ALTERATION. U. SLIGHT HEALED CRACKLE TEXTURE OVERALL			10.0					
3	17.4	17.4	100	58				20.0					
								30.0					
4	18.4	16.9	92	47	59.5-60.5: K-ALT'D ZONE SLIGHT CLAY. 63.0-64.0: QZ - FLOODED ZONE. ↑ SLIGHT INCREASE IN SX CONTENT. 64.6-70 cm QZ FLOODED ZONE. STRONG POTASSIC ALT'N 66.0-72.0' INCREASING CA. TOWARDS DEPTH. OVERALL ± FRACT-FILLING.	MINOR PY, SL, CL.		40.0					
								50.0					
5	18.5	16.8	91	76	74.0 1 cm QZ VEINLET 85° TO C/A MINOR SL, GL, PY. MED - STRONG POTASSIC ALT'N HERE DOWN ↓. 79.0-82 cm CA BRKN. WITH XTALLINE QZ. (LARGE XTALS. 86.6': 1-2% PY FOR 1 FOOT. CA STRINGERS. U. ABUNDANT CL ± CA. 3MM PY STRINGER @ 10° TO C/A.			60.0					
								70.0					
6	18.1	17.9	99	67	89.0': 6 cm CLAY ALT'D ZONE. FSPARS TO CLAY ± WASHED OUT. U. SOFT. STRONG POTASSIC ALT'N OVER 5 FT. VFG ROCK: APPARENTLY OF QMZ COMPOSITION. APPEARS TO BE AMORPHOUS RECRYSTALLIZATION OR EARLY INHIBITION (FROM STILL MAGMA). NO CHILL MARGINS, JUST GRADES INTO HOST ROCK. RHYOLITE-TRAN. ±	95.4 29.09m 27.42 MINOR DISS PY. 106.0 XTALS TO 1 mm. 30.78m		80.0					
								90.0					
7	14.4	16.2	99	43	7 cm PY BAND @ 60° TO C/A, THEN QMZ AS ABOVE. AFEW MAFIC XTALS AS LARGE AS 1 cm ACROSS. MOST ↓ 5 mm. ↓ 20% CHLORITE. ALL ALT'D TO CHLORITE. CLEAR FRAGMENTS.	TRACE VFG DISS PY		100.0					
								110.0					
					APHANITIC PORPHYRITION AS ABOVE 117.0'-121 cm BAND OF COARSE FSPARS ± QZ XTALS.	116.7 ↓1% DISS. PY.		120.0					

OMNI RESOURCES INC. · PROJECT SKUKUM CREEK · DIAMOND DRILL HOLE No. 87-463 Sheet 2 of 4

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG ALTN	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
					APHANITIC PINK-TAN SEGREGATION INTERSPACED ± ANG.	INT		1200						
8	19.5	18.3	94	55	C.G. QMZ AS ABOVE. ~40% HB. ALT'D TO CHLORITE. ABUNDANT CL, SE, EP. MINOR PY. MOD POTASSIC ALT'N IN NARROW ZONES. OVERALL STRONG PROPYLITK ALT'N ± ZONES OF WEAK TO MOD PHYLLIC- INCREASING ± DEPTH. ROCK GENERALLY COMPETENT WITH NARROW CRUMBLED ZONES - BARGASLY OLE TO DRILLERS. CL/CA VEINLETS QUITE COMMON. HEMATITE STAINING ON SOME FRACTS. NOT MAGNETIC AT ALL.	MINOR - TRACE DISS PY. USUALLY VFG.		1300						
9	16.5	16.2	98	41	APLN BLOBS OR ZONES OF APHANITIC, PINKISH-TAN TO 5 CM. IN THIS AREA- ROCK MORE FRACTURED WITH DEPTH. LESS-COMPLETELY HEALED.			1400						
10	19.9	17.5	88	57	162-165: ABUNDANT, DK, GREENISH-BLACK STRINGERS ± FRACT-FILLINGS. 1 CM QZ VEIN LINED ± GREEN-BLACK MINERAL MORE FRACTURES @ SHALLOWER ANGLES. (15-20° TO C/A.			1500						
11	17.2	16.9	98	71	185.5-188.5: M.G. BLEACHED ZONE ± MORE MAFICS, STRONG PHYLLIC ALT'N, AND SOME INTERSTITIAL CLAYS ± NARROW, CL-FILLED SHEARS. MINOR BRXN.			1600						
					200' SCALE CHANGES TO 1" = 10'			1700						
12	5	5.0		26	COARSE GRAINED QUARTZ MONZONITE. — moderate propylitic alteration; 5% chloritized mafics, partly sericitized plagioclase & fresh K-spar.	No sulphides		1800						
	4	4.0		56	→ 201' = 1 cm. of bleaching (now Q-K-spar) at 45° to c.a.			1900						
	6	5.0		50	208.8' → 1 cm. zone of green Q-Ser. melts each cm. mm. across Fract. 45° and 80° to c. axis. 211.5' = 5 mm. white Q. vn w. Py-Gn-Cpy → vn. ca. 70° to c.a.	3% Py, 1% Gn & ½% Cpy in 5 mm. Q. vn.		2000						SCALE CHANGE TO 1" = 10'
	5	4.6		92	214.2' = 2 mm. Q. vn. at 15° to c.a. 214.4' = 2 cm. zone of Q-Ser-Py at 45° to c.a. 216-219' = 5 one-3 mm. Q vns.; 30°, 50° and 70° to c.a.	Minor py ass'd w. Q vns.		2100						
13	5	3.7		74	Fract. ca. 20° and 50° to core axis.			2200						
	4	3.4		38										
	5	4.9		77	228-230' = Five 2-5 mm. Q. vns at 45° and 70° to c.a. 230.5-231' = Dyke of M.gr. Q.M. or Gd.(?) Contacts ca. 45° & 70° to c. axis.		Dyke	2300						
		1.0	100	80	234.3' = Well X-lized (cubes) pyrite on fract (1 mm xls).	Fract. plane pyrite.								

OMNI RESOURCES INC. PROJECT Skukum Creek DIAMOND DRILL HOLE No. 87-463 Sheet 3 of 4

BOX	Run	Core	% R	R.Q.D.
	5	4.7	94	36
	5	5	100	30
14	5	4.4	88	11
	4	3.3	83	15
	5	3.8	76	45
15	5	4.4	88	9
	6	5.3	88	62
	5	4.8	96	31
16	5	4.6	92	17
	5	4.3	86	49
	5	4.7	94	0
17	5	3.6	72	0
	7	2.4	34	0
	3	2.9	97	30
	5	0.2	4%	0

LITHOLOGY, ALTERATION, STRUCTURE

235.7' +/-2 cm. zone of Sericitization at 40° to c.a.
237.7' = 7 mm. Q vn. at 30° to c.a.
Fract. 10°, 45° and 60° to c.a.
241-242' = 2 x Q-Carb. veins (1-4 mm) at 50° to c.a.
242-242.6' = Gray aplite dyke; lwr. contact irreg. but ca 45° to ca
247' = 6 mm. Q. vn at ca. 45° to c.a.
247-252' = ½ doz. Q. vns up to 6 mm. across
Fract. 25°, 45° & 70° to c. axis.

78.99 m 74.43 m on X-Section 5+24N

259' M.Gr.-C.Gr. GRANODIORITE w. 1' of chilled margin(?) or rhyolite dyke(?) Looks like the former!
Abund. Q. vns to 267'
- Strong sericitic alteration.
Fract. 30°, 45° and 70° to c.a.
Qtz. vning continues at 45° to ca. } Zone of silicification.
83.69 m 78.91

274.6' TAN RHYOLITE BRECCIA. 80%-95% frags. - angular 1-3 cm. in 20% black, soft matrix which is locally silicified. Upper contact broken, but banding in Rhyo. is 45° to c.a.
278.9' = Speck of visible gold
279.7' = 1-1½ cm. broken Qtz. vn. in banded Rhyo. Bxa - banding ca. 35° to c.a. At contact = broken 5 mm. Q. vn at 45° to c.a.
281.4' = SILICIFIED DARK GREEN ANDESITE
85.77m 80.97
Upper contact ca. 15° to c.a. Fract. 80° & 25° to c.a.
283'-284.5' = BRECCIATED w. inclusions of granodiorite.
284.2' = 3 mm. Q. vn. at 30° to ca.
284.6-289.5' = Mod. pyrite (5%)
Fract. 0°, 60° & 90° to the core axis.

290.0' 88.39 m 83.34
MIXED, MINERALIZED ANDESITE and RHYOLITE BRECCIA (MULTILITHIC BRECCIA - some gd. frags.
89.61 84.49
Silicified w some tiny Qtz. veins.
294-299' - only 10% core recovery - mainly Rhyo. Bxa.
"Good ore zone from 294'-304'" From 294' = RHYOLITE BXA (MINERALIZED) - w. Qtz. vn matrix. 299-301' only 25% recovery → 92.65 87.36 96.50 91.74 m.
301-304' MAINLY QTZ-SULPHIDE BRECCIA w. some RHYOLITE BRECCIA.
304' STRONGLY-ALTERED GRANODIORITE FAULT ZONE.
- gd now bleached to white clay and quartz.
- very poor core recovery. (just pebbles).

MINERALIZATION

1% Py & ½% Gn in Q. vn.
Minor Py on margins of some vns.
Minor Py. in vns.
3% diss. py; minor cpy
Speck of Visible Gold at 278.9'
280-281' = 5% py.
284.5-289.5' = 5% 1 mm. cubes of pyrite
One 1" (2.5 cm) section of core w. 7% Galena ½% cpy and 10% Py.
299-301' = 2-3% Py
301-304' = 7-10% Py ½% Gn, ½% Sl., and minor cpy

GRAPHIC LOG (Mafic / Min.)

FT.: 2400, 2500, 2600, 2700, V.G.!, 2800, 2900, 3000, 3100

SAMPLE Sample No.	INTERVAL	CORE LENGTH	ANALYTICAL O.P.T. Au	O.P.T. Ag	
6717	274.6-279.6'	5'	0.006	0.21	Special Native Gold Prep. (RUSH)
6718	279.6-281.4'	1.8'	0.022	0.58	
6719	281.4'-286.4'	5'	0.026	0.28	0.017, 0.26/3.17m
6720	286.4'-290.0'	3.6'	0.003	0.06	
6721	290-294'	4'	0.005	0.13	0.006, 0.37/5.34
6722	294-299'	5'	0.009	0.85	
6723	299-301'	2'	0.003	0.27	
6724	301-304'	3'	0.034	1.61	
6725	304-309'	5	0.001	0.12	

Hw 274.6

OMNI RESOURCES INC. · PROJECT SKUKUM CREEK · DIAMOND DRILL HOLE No. 87-[illegible] Sheet 4 of 4

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag	ANALYTICAL
	5	0.5	10	0	Note: poor core recovery in Fault zone.	Minor py.								
17	5	0.8	16	0	ca. 318' = one piece of qtz. w. minor pyrite – ca. 4 cm. long. 97.84 92.25	Minor py.			6726	309-314'	5'	0.001	0.60	
	5	4.6	92	66	321' Fault ends at 30° to the core axis PROPYLITICALLY-ALTERED C. GR. GRANODIORITE 5% chl. mafics	No sulphides.		2100	6727	314-319'	5'	0.015	0.04	0.005, 0.21/6.10
18	5	5	100	42	324.2 – 325.2' = Strong chl-epid. alt^{n}. Fractures 30° and 45° to c.a.				6728	319-324'	5'	0.001	0.07	321' FW
	5	5	100	24	330.5' = 2-3 mm Qtz-Carb. vn at 45° to ca. Also 2mm Ser. vnlt at same orientation.			3300						
	5	5	100	84	Locally mod. Chl-Epid. alt^{n} (10% of rock over 6" to 1'.	No sulphides								
					Fract. 45° & 60° to c.axis.									
	5	5	100	66				3400						
19	2	2	100	0	344' – 345' = local brecciation and silicification; several 1/2-3 mm. Q-carb. vns at 70° to c.a.									
	1	1	100	35										
349.0	2	2	100	40	Fract at 35°, 50° & 70° to c.axis.	349.0								
					END OF HOLE 349.0' 106.37m 100.3 ↑ on X-section			3500						EOH

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling: TO TEST KUHN ZONE @ 1330 m LEVEL BETWEEN HOLES #26 & 27

Explanation of Results:

LEGEND

PROJECT	SKUKUM CREEK - WH.	HOLE No.	87-UG33
COORDINATE N.	70854.4	DEPTH	~~288~~ 298'
E.	77759.0	AZIMUTH	303
ELEVATION	1309.1	INCLINATION	+38
DATE STARTED	SEPT. 11, 1987	DRILLED BY	CARON DIAMOND DRILLING
COMPLETED	SEPT 15, 1987	ASSAYED BY	ACME ANALYTICAL
HOLE SURVEY	SEPT 24, 1987	LOGGED BY	R.SR. L.R.

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION
1			94	24	C.G. weak prop altd QMZ lt gry, fract. @ 30° & 65° to C.A., wkly silicified, abundant chlorite, crushed pyrite on some fractures, K-spars lt pink & amorphous, plag → sericite ± some epidote (mod. prop.) except at 34.7, wk rxn w/ acid, f-spars hard - crushed py on fract. at 120°	- py on fract
2			99	44	- 26.5 .8' ufg aplitic section (mag segn?) - 10.7 3" zone wk potassic altn - mod prop altn plag → sericite ± epi on fract. 37.3 lwr cnt sharp, marked by qtz enrichment & aplite & shear at 15° CA.	- 1" stockwork at 40° to C.A.
3			96	15	Mod to C.G. wk prop altd GDR lt. gry, silicified, abundant chloritized mafics, some mafics concentrated along X-cutting fractures 1-2 cm wide & at 50 & 65° to C.A., open fractures at 60 & 38° to C.A., - 44.2 crushed & cubic py on fract at 38° to C.A. - 50' stockwork for 5" ± calcite on fract, wk rxn w matrix - minor gry qtz veining at ~ 53'	- py on fract.
4			95	42 43	57.7' C.G. Mod Prop altd QMZ similar to 0 - 32.3 but stronger altn of plag 60.6 1" intermediate intermediate mod grey dyke w/ irregular cnts Mixed G.D.R. and QMZ drilled along contact ? sections of wk to mod altd (as above) G.D.R. and QMZ alternating w/ each other 62.7 C.G. mod prop QMZ 63.3 C.G. mod prop G.D.R. mafics → chlorite in 2-4 mm wisps, & fract 50/60° to C.A., silicified, f-spars still hard, lt gry colour	- cubic py << .5mm on fractures
5			94	42 [illegible]	70.9 1/2" gry qtz vein at ~ 60° cnt sharp lwr cnt 70.9 - 74.2 wk prop QMZ, C.g., f-spars white to greenish & still hard 74.2 - 84.7 wk prop GDR 84.7 - 87.7 C.g. QMZ; 81.7 - 83.0 wk prop GDR. 84.7 - 87.7 C.g. QMZ, wk - mod prop, f-spars → green colour & soft, rock lt grn-gry colour	
6			94	29	87.7 - 91.1 silicified G.D.R. mafics convey in 1-3mm fract, X-cutting but predominantly at 45° to C.A., & v strong chl altn 91.1 - 92.3 QMZ as above 92.3 - 96.3 Silicified GDR, mafics as blebs of chl & in hairline fract. at 50° to C.A. lt gry colour X-tals partially obscured & amorphous 96.3 4" section of QMZ then GDR as above 103.8 10" section of QMZ as at 96.3', then mod prop altd GDR, silicified w/ mafics in "crackle" fractures & strongly chl altd	
7			99	23	111.3' aplitic section to 114.3', creamy gry/grn colour, "bleached" look mafics in what fract. 114.3' mod prop G.D.R., silicified, lt gry to grn/gry colour, abundant mafics ± strongly altd to chl., f-spars cream coloured	

GRAPHIC LOG

FT.: 10, 20, 30, 40, 50, 60, 70, 80, 90, 100, 110, 120

SAMPLE			ANALYTICAL		
Sample No.	INTERCEPT	CORE LENGTH	O.P.T. Au	O.P.T. Ag	

OMNI RESOURCES INC. PROJECT SKUKUM CREEK DIAMOND DRILL HOLE No. 87-463 Sheet 2 of 3

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T Ag	
123.9					Aplitic section lt. tan-grn colour, same as at 111.3'-114.3'			120						
8			92	18	127.0 Wk Prop altd GDR, ø lt grey colour, silicified, amorphous f-spar cream coloured, abundant mafics ↓some in 18° & 50° 1mm fracts. 134.9 6" dk grey aphanitic intermed. to mafic dyke 136.7 Strong Prop to Phyllic altd Intrusive ↓strong foliation, bleached groundmass WK to Mod Prop altd GDR, med.-C.G., lt grey, abundant mafic blebs, Ca. in tiny fracts, f-spars soft & green 145.0 9" zone v. silicified section ↓ 2-3mm py blebs, grad-l cont	- 1cm band of grey crushed py - 1cm py band up to ½" qtz vein		130						
9			97	35	145.9 C.G. Prop altd QMZ, silicified, mod propaltd, f-spars from cream to lt grn, wk foliation, mafics ø partly altd to chl. ↓some in fine fracts at 50 to 60° to C.A., minor ½" qtz veins ø random orientation	- minor blebby py		140						
10			87	18	146.7 WK-Mod Prop Alt'd C.G. QMZ, lt grn/gry, f-spars soft & cream to green coloured, near fracts some stronger altn, abundant mafics altd to chl.) fracts at 40-60° to C.A., chl & Ca on fract. surfaces ↓a minor py; minor ¼" qtz veins 173.5 4" aplite dyke ↓ grn/gry qtz vein at 65° to C.A.	- ↓a minor cubic py on fract surfaces		150						
11			83	20				160						
12			99	16	STRONG PROP - ALT'D. C.G. QMZ. LT. GREENISH-GREY, FSPARS MED. SOFT 10-15% MAFICS - ALT'D TO ø CHLORITE. MOST FRACTS 40-50° TO C/A · CL, CA, ↓PY ON FRACT. SURFACES. MODERATE GREY, GREEN-GREY & WHITE QTZ STOCKWORK @ 197'-213' MINOR HEALED CRACKLE TEXTURE. 215.0': 5mm WIDE VEIN OF DIATREME - 1mm CLASTS, SUBROUND IN DARK SILICEOUS MATRIX - MATRIX SUPPORT. 45° TO C/A	TRACE DISS. PY. OCCASIONALLY TO 1% PY		170						
13					SCALE CHANGE 1" = 10'	SCALE CHANGE 1" = 10'		180						SCALE CHANGE: 1" = 10'
13	228.0				ALTERATION & FRACTURE INTENSITY INCREASING WITH DEPTH. AFTER ~222' IS STRONG PHYLLIC ALT'D. BLEACHED, PALE GREEN-GREY. ABUNDANT CL/EP/ø CA. MINOR BANDED QTZ VEINLETS. MORE FRACTURES PARALLEL TO C/A.	TRACE TO MINOR DISS. PY.		190						
	5		70	14	CRACKLE HEALED WITH BLACK OPAQUE MINERAL. PERHAPS VFG SX? MOST F.S. QUITE SOFT. V-CHLORITIC AT END.			200						
233.0					LOWER CONTACT LOST IN CRUMBLED SHEAR. - CORE LOST.	233.0		210						
	5		87 37	31 87	0.5' BXD GDR & RHY WITH DIATREME MATRIX. CLASTS IN DIATREME ø RARE QTZ IN BX. TREN GREY & GREEN-GREY VFG TO FG ø BXD RHY. NO ROTATION. VFG DARK MATRIX. ?WEAK HYDROTHERMAL ALTN? LOWER CONT. CLAY GOUGE SHEAR 238.0 SILICIFIED, CHLORITIZED, CALCIFIED, MED GRY, F.G. ALT'D. RHY OR INTERMEDIATE	TRACE TO MINOR DISS. PY OVERALL ? MINOR SX IN CLASTS IN DIATREME.		220						
14	5		95	79	FG DYKE. MINOR ROTATION. V. SOFT. LARGE FRAG. BXD BLACK SHEAR. 239.0 VDK GRN-BLACK, SANDY-MATRIX BANDED SHEAR 40° TO C/A. FOR 0.3', THEN MED. GRY A.G. DYKE - U. BXD. CLAY GOUGE STRIN CLASTS. V. SOFT. MAY BE GOUGE, MAY BE ALTN. PROBABLY GOUGE. LESS SHEARED WITH DEPTH. LOWER CONT. CURVED. INTERSECTS @ 70° TO C/A	MINOR CP IN PY FIRST FOOT OF ZONE. TRACE DISS. PY ↓ TO TRACE ↓PC DISS PY		230						
	239.0				SOFT, MED, GREY, C.G. ALT'D, SHEARED GDR. V. SOFT & CRUMBLY.	243.0		240	6730	228.0-228.0	5.0'	0.001	0.04	
								250	6731	228.0-233.0	5.0'	0.001	0.01	HW SHEAR
									6732	233.0-237.0	4.0'	0.005	0.14	
									6733	237.0-239.4	2.4'	0.004	0.31	
									6734	239.4-243.8	4.4'	0.001	0.02	
									6735	243.8-246.0	2.2'	0.001	0.18	

OMNI RESOURCES INC. PROJECT SHAKUM CREEK DIAMOND DRILL HOLE No. 87-6 Sheet 3 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
					MED-FINE-GRAINED SECTION FROM 246.0-247.6, THEN BACK TO STRONGLY CALCIFIED, CHLORITIC, SOFT, MED-COARSE-GRAINED GDR. FAINT GREENISH TINGE CHLORITE, CALCITE ? SERICITE HEALING CRACKLE TEXTURE.	TRACE TO MINOR DISSEMINATED PY.		245	6735	243.8-246.0	2.2'			
14	5		98	69				246.0	6736	246.0-247.6	1.6'	0.001	0.08	
254.4	5		95	58	OVERALL, FAINT ORIENTATION TO FRACTURES N 40-50° TO C/A. BANDED LOWER CONTACT SHARP-FLOW @ 45° TO C/A. ABUND CA IN CONTACT BANDS.	.5mm-2mm XTALS.		250	6737	247.6-252.0	4.4'	.001	.13	
	5		87	38	EITHER NEW UNIT OR ? CHANGES OF MG GDR, OR INCOMPLETELY ALT'D GDR. BANDED OR SLABBY GDR ? VFG MED-DK GRY V. SOFT ALT'N RICK. MAY BE BIOTITE ALT'D GDR, BUT NO REMNANT QZ. ABUNDANT CA STRINGERS, STRONG CHLORITIC LOWER CONT. GRAB	259.0 MINOR TO 1% PY DISS. & IN BANDS. 256.2		252.0	6738	252.0-256.2	4.2'	.001	.11	
15	5		98	51	VERY COARSE-GRAINED (UP TO 1cm) MED-DK GREENISH-GREY GDR ± QMZ. (MAY BE MINOR K-SPAR IN SOME ZONES) ABUNDANT SERICITE ALT'N OF PLAG, AND CHLORITE ALT'N OF MAFICS. STRONG PROP. ALT'N.			256.2	6739	256.2-261.3	5.1'	.001	.07	FW SHEAR
	5		97	67	261.3'-262.1': HEALED, BANDED SHEAR. BAND, QZ VEINS. CA. 80° TO C/A WEAK CRACKLE OVERALL.	FW?		261.3	6740	261.3-264.9	3.6'	.001	.01	
266.6	5		92	53	265.6'-268.0': A FEW BANDS + BLEBS OF FINE GRAINED MATERIAL OF SAME COMP. + ALT'N AS HOST. MAG. SEG. NO SPECIFIC ORIENTATION. 268.6: 1½' ZONE ± 2 cm. CA VEIN CURVING THROUGH CORE.	1-2% PY IN CA VEIN		264.9	6741	264.9-270.1	5.2'	.001	.03	
	5		98	31	273.0-283.9': BANDS ± STRINGERS OF CA + SX CUTTING CORE @ ~60°	CUBIC XTALS 1-2mm ø		270	6742	270.1-273.0	2.9'	.001	.02	
16	5		98	31	277.0: 2 x 1cm QZ VEINS ± PY XTALS CUT CORE @ 45°	SL. GL. PY. MOSTLY PY. ~5% SX OVER 0.9'.		273.0	6743	273.0-273.9	0.9'	.001	0.27	0.27 Ag
283.9	5		93	24	288.6: SLICKENSIDED FRACTURE @ 90° TO C/A. SLICKENSIDES ~ 35° TO C/A CRUMBLY, SHEARED ZONE. SOME CORE LOST.	2mm PY XTALS IN QZ VEIN.		273.9	6744	273.9-278.0	4.1'	.001	0.20	
	5		98	75	285-286 LT. TAN, FG. APLITIC-LOOKING ZONE. SEEMS TO MERGE INTO GDR AT TOP & BOTTOM. PROBABLY SEGREGATED ZONE.			278.0						
	4		100	79	QZ-Cb VEIN @ 20° TO C/A. 287.3: 1cm QZ VEIN ± PY @ 50° TO C/A.			280	6745	278.0-283.0	5.0'	.001	.09	
17	3		100	65	START OF MINOR POTASSIC ALTERATION & ABUNDANT, BRIGHT GREEN EPIDOTE STRINGERS, SWARMS & FLOODED ZONES.	PY CUBES 2mm ACROSS IN QZ VEIN.		283.0						
298.0	3		100	29	EOH 298.0	298.0		290						298.0 EOH
								300						

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling: To test extension of Kuhn zone to the east, on 1300 level.

Explanation of Results:

LEGEND

PROJECT: Skukum Creek (WH-Claims) | HOLE No.: 87-UG-34

COORDINATE N.: | DEPTH: 27'

E.: | AZIMUTH:

ELEVATION: | INCLINATION:

DATE STARTED: | DRILLED BY: Coron Diamond Drilling

COMPLETED: | ASSAYED BY: Acme Analytical Labs

HOLE SURVEY: | LOGGED BY: L. Rowan

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag	
1			84	31	C.G. Prop. altd. GDR fractures at 45 & 90° to C/A, med green Ab & minor epidote C.G Prop. altd QMZ pervasive pinkish-gray; large med. green Ab x-tals fractures at 45° to C/A, minor blebs of wht qtz; chlorite on fractures w/ minor clay 4" fig. "swirled" looking section, pink gray, QMZ becomes finer grained after this w wk fracturing chlorite filled	none trace to 1% dissem and fracture filling cubic PY		0.0						
187								10						
2			98	31				20						
270					E.O.H.		E.O.H.	30						E.O.H.

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling: TEST KUHN ZONE EAST OF HOLE 87-UG19

Explanation of Results:

LEGEND

PROJECT	SKUKUM CREEK	HOLE No.	87UG35
COORDINATE N.	70955.0	DEPTH	238'
E.	77768.0	AZIMUTH	132
ELEVATION	1304.8	INCLINATION	-43
DATE STARTED	SEPT. 16, 1987	DRILLED BY	CARON DIAMOND DRILLING
COMPLETED	SEPT. 19, 1987	ASSAYED BY	ACME ANALYTICAL LABS
HOLE SURVEY	✓	LOGGED BY	RJR, LR, TME

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
2.6					CORE LOST AT BEGINNING OF HOLE DOWN TO 2.6'								
1			98	42	C.G. GDR, med to dk gry, none to v. wkly alt'd, v. lg K-tals, mafics to ≅ 25-30% (Diorite ?), f-spars hard & white, minor Ca & chl on fracts @ 45° & 70° to C/A -11' shear w/ 1.6' pink (potassic alt'n ?) section, mafics become chloritized & strong rxn w acid down to lwr cnt, ca on fracts -18.6' 12' xeno of QMZ contact 45° & 20°			10					
2			98	16	-alt'n becomes mod to strong w/ intense chl & visible sericite & epidote -28.3' 1.3' xeno of QMZ, lwr cnt at 55° 29.1 Med. G. QMZ, pink-gry colour, x-tals 1-3 mm, wk prop. alt'n, minor cubic py on fract, rock mod soft, minor mafics (2-3%), major fract.s @ 60° to C/A, minor rxn w acid			20 30					
3			97	08	-39.5'-43.6' as silicified, u.f.g section, very few mafics, badly broken core -45.5'-46.4', med. g. section, mod prop alt'n, f-spars grn & soft alt'n increasing as you go down section			40 50					
4			95	10	-65.3' 6" dk gry, aphanitic andesite dyke, @ 30° to C/A			60					
5			98	30	-75.0' lwr cnt sharp & at 60° C.G. Prop Alt'd GDR, med gry colour, silicified, fracts at 40°/60°, 25% mafics altered to chl, f-spars cream-grn colour 80.4' F.G. Prop Alt'd QMZ, as at 39.5-43.6', alt'n increasing, wk fizz 84.9'	- minor py blebs - trace disseminated py and blebs at one fracture		70 80					
6	98.0		96	06	FG to Med.G. QMZ, as described below			90					
			72	0				100					
	104.0		72	0									
	106		100	0									
7	108		90	0	104' MEDIUM GRAINED QUARTZ MONZONITE continues: 1-3 mm grains: 2% chl mafics, Weak prop. alt'n as plag. is frsh to weakly-sericitized, Locally brecciated SCALE CHANGE 1" = 10'	Minor Py. SCALE CHANGE 1" = 20'							
7	113		96	36	Mod. silicification or sericitization j zones up to 7 cm. in crackle brecciated Q.M. One zone of silic. approx. 60° to c.a. 112.3-112.5 = Irregular dk gry (And.) Feldspar porphyry 113.8-114.5 = Sheared and [illegible] w/ sericite & locally chlorite	110.3 Minor Py		110.3 112.2 115	6746 6747	1103-112.2 112.2-116.3	1.9' 4.1	0.005 0.001	0.04 0.05
	100		100	55									

SCALE CHANGE 1" = 20'

OMNI RESOURCES INC. PROJECT Skukum Creek DIAMOND DRILL HOLE No. 87-4635 Sheet 2 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL G.P.T. Au	ANALYTICAL G.P.T. Ag
					113.2' = Healed shear at 20° to c.a.	Minor dissem. py on fract.		6747	112.2-116.3	4.1		
7	115		100	55	115.8' = Dissem. py. on fract. 10° to c.a.							
			93	43	To 120.5' = Semi. of seric. fract.; predominant set = 40° to c.a. Overall, mod. seric. alt'n.			6748	116.3-121.0	4.7'	0.001	0.01
120.0	120				120.5' = 1/2 cm Qtz. vn. at 60° to c.a.		120					
					120.5'-121.0' = Silicified section w. accompanying sericitization		121.0					
			98	50	STRONG SILICIFICATION and FRACT. SERICITE. Main fract. 45° and 70° to c.a. Massive & wall fract. sets alternate	Minor dissem. Py w. some 1cm³ pockets of 5-10% Py	124.1	6749	121.0-125.8	4.8'	0.001	0.04
					STRONG QTZ-SERIC. ALTERATION ALTERNATING W. STRONG SILICIFICATION							
8	130		98	76	-local irreg. veinlets of light brown Q.-carb. Fract. still 45° & 70° to c.a.	Minor dissem. Py.	130	6750	125.8-130.7	4.9'	0.001	0.03
							130.7					
			90	46	GRAY. to BLACK SHEARED AND REHEALED QTZ. MONZ. (Banding 50° to c.axis) POST RAINIRIAN	0.2% Py (dissem.)	132.1	6751	130.7-132.1	1.5'	0.011	<0.13
					MULTILITHIC BRECCIA w. mainly Q.M. clasts to 4 cm. (Qtz. veining 50° to c.axis) and fragments of Rhyolite & Andesite Frags.	0.5% Py; minor sphalerite	133.7	6752	132.1-134.7	2.6'	0.659	0.61
			100	80	Shear fabric (healed) at 35° to c.a.	Minor Cpy.	136.0	6753	134.7-136.6	1.9'	0.001	0.13
137.8	138		100	0	0.35' FRACTURED OR BROKEN ZONE	1% Py	136.6	6754	136.6-140.3	3.7'	0.006	0.30
			94	56	137.0-187.1 = 2cm of fault gouge contact. SOFT, GRAY (from 137') ANDESITE cut by 3% (of vol.) Q-CARB-PY-GN veins and veinlets. Vns randomly 45° to c.axis Fract. also 45° to c.axis	1-2% Py mainly in vns up to 1cm across 0.1% Gn and Sl.	140.3	6755	140.3-143.2	2.9'	0.001	0.18
	143						143.2					
					INCLUSION OF SILICIFIED QTZ. MONZONITE	0.5% diss. Py.	143.2	6756	143.2-147.4	4.2'	0.001	0.14
					PRE-MINERAL TAN RHYOLITE PORPHYRY Contact 70° to c.a.							
9			100	34	1-2% 3mm. Qtz. eyes. Banding 45° to c.a. Some Py vns. Fract 60° & 45° to c.axis Local strong sericitization Lower contact ca. 45° to c.a.	Some 1-2 mm. Py vns. Overall 1/2-1% Py	147.4	6757	147.4-152.2	4.8'	0.002	0.33
	148						150					
					COARSE, SHEARED & REHEALED Q. MONZ-RHYO BXA w. occas. AND. FRAGS. 0.5'-3' across. Healed shears at 50° to c.axis Fract. 45° to c.a.	0.1% Py Minor Gn.	152.2	6758	152.2-153.6	1.4'	0.005	0.37
	153		96	66			153.6	6759	153.6-159.1	5.5'	0.061	0.09
156.9												
	158		92	0		Minor dissem. Py.						
					157.5'-173.5' = FAULT ZONE - abundant gouge		159.1	6760	159.1-162.5	3.4'	0.001	0.31
			96	26	159.1' = GRAY ANDESITE DYKE cut by a myriad of Q=Carb. vnlts (Fill in cavities in and.); vnlts are white. Effer is FeO = calcite-fill		160.3					
10	163				- Aphanitic to f. grained; 162.5-163.5'(?) = RHYOLITE DYKE or INCLUSION IN SHEAR ZONE	Minor diss. Py.		6761	162.5-168.0	5.5'	0.001	0.13
	168	CORE LOST	30	0	Shearing ca. 30° to c.axis		168.0					
								6762	168.0-172.2	4.2'	0.002	0.26
			94	0	170.2-171.4' = PRE-MINERAL RHYO. DYKELET or INCLUSION. Upper contact 70° to c.axis.	2 mm. Py vn; w. Galena at 45°(?) to core axis.	172.2					
173.5								6763	172.2-177.2	5.0'	0.001	0.01
	178		100	30	Fract. mainly 45° to core axis. Qtz-calcite veining mainly 60°-80° to core axis		177.2					
								6764	177.2-181.0	3.8'	0.001	0.17
			98	91	180' = banding in Andesite ca. 40° to c.a.	Locally 1-2% py over 0.5'	181.0	6765	181.0-182.6	1.6'	0.001	0.14
11	183				CONTACT ZONE - Silic. and seric. alt'n; some rhyo. injection		182.6					
					MASSIVE, TAN RHYOLITE DYKE - Upper contact ca. 50° to c.axis. Banding ca. 45° to c.a. 1-3 mm. Q-carb. vnlts. ca. 50° to c.a. (1-2% of vol. of rhyo.)	Only minor dissem. Pyrite		6766	182.6-186.8	4.2'	0.001	0.01
	188		96	31			186.8					
								6767	186.8-191.0	4.2'	0.001	0.01
			100	33			190					

0.041, 0.47/4.1' (Hw ore zone)

0.001, 0.15/66.2'

OMNI RESOURCES INC. PROJECT Skukum Creek DIAMOND DRILL HOLE No. 87-46-35 Sheet 3 of 3

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
11	193		100	33	Contact cas 45° to core axis. MEDIUM GRAY, MATRIX-SUPPORTED, MULTILITHIC BRECCIA - CONTACT ZONE 191-193.7' ZONE SILICIFIED - only 20% of frags > 4 mm. Mainly subangular to subrounded rhyo. frags w. <5% Q.M. frags	Minor Py		190	6763	186.8-191.0	4.2'			
191.5			96	26				192	6768	191.0-192.7	1.7'	0.002	0.06	
	198					Minor Py		193.7	6769	192.7-193.7	1.0'	0.002	0.18	
12			94	15	Q-CARB Lower contact silicified w. 1.0' of shearing in the MONZONITE 200 SCALE CHANGE 1:20' D. Moore 1978	Variations in contact zone.		194	6770	193.7-197.3	3.6'	0.001	0.04	
	202		94	15	WEAKLY ALTERED QUARTZ MONZONITE AS BEFORE - now grain size is 1-4 mm. (Subporphyritic) 206.8' = Minor Q-Py-Gn vnlt at 45° to c.a. Fract. 45° & 70° to c.a. Lwr. contact 45° to c.a. M.gr.-C.gr. as WEAK PROPY.	Minor Py. 206.8' Q-Py-Gn vnlt at 45° to c.a.		197.3	6771	197.3-198.4	1.1'	0.001	0.23	FW SHEAR MM
	208		100	0				198.4	6772	198.4-199.8	1.4'	0.001	0.07	SCALE CHANGE 1:20'
215	216		100	60				200	6773	199.8-205.2	5.4'	0.001	0.07	
13			98	59				205.2	6774	205.2-209.4	4.2'	0.001	0.01	
219.7								210						
14			99	73	END OF HOLE MA-35	238. EOH.		220						
								230						
								240						E.O.H.

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	SKUKUM CREEK	HOLE No.	87-UG36
COORDINATE N.	70954.0	DEPTH	222'
E.	777660.9	AZIMUTH	147°
ELEVATION	1304.2	INCLINATION	-22
DATE STARTED	SEPT. 20, 1987	DRILLED BY	CARON DIAMOND DRILLING
COMPLETED	SEPT. 22, 1987	ASSAYED BY	ACME ANALYTICAL LABS
HOLE SURVEY		LOGGED BY	RJR.

Reason for Drilling: TO TEST FOR EXTENSION OF HIGH-GRADE ZONE BELOW AND TO THE EAST OF UG-19.

Explanation of Results:

LEGEND

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
1			97	7	Prop Altd QMZ, med g., pinkish-grn colour, altn intensity wk to mod. w/ strong at one shear, rock mod hard, f-spars cream to grn, ca on fracts, minor chl & epi. on some fract., minor rxn w/ acid, mod fract'd at 25, 65 & 80° to C/A			0.0					
2			97	22				10					
3			97	14				20					
4			97	21	33.6' 5" very strongly phyllic altd section at 80° to C/A, then intense propylitic w/ for 1.4', intense clay altn in last 5", "apple" grn colour, bleached appearance & rock is soft	- trace dissem cubic py		30					
5			99	66	62.4' Mixed Zone of Aplite, GDR. & QMZ, gradational change from QMZ, qtz enrichment and aplite dykelets in last 2', then mod. prop. altn w/ f-spars apple grn colour. C.A. filled fract at 25° to C/A, core is greenish-gray colour & no longer pinkish 73.6' lwr cnt arbitrary but marked by 2" aplite dyke			40					
6			94	43	Mod Prop Altd G.D.R., C.g., greenish-gray, f-spars cream coloured, "swirled" texture to matics, matics ≈ 25% of rock & are altd to chl, ca. & chl. on fracts, fracts are at 45° & 80-85° to C/A., mod. healed crackle	- V. minor visible py		50					
7			96	25	109.5' 6" aplite dyke 113.0' 8" aplite dyke			60					
								70					
								80					
								90					
								100					
								110					
								120					
	1104	80	99	60									

OMNI RESOURCES INC. · PROJECT SKUKUM CREEK · DIAMOND DRILL HOLE No. 87-4636 Sheet 2 of 3

BOX	Run	Core	% R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	INTERCEPT	CORE LENGTH	ANALYTICAL O.P.T. Au	O.P.T. Ag	
					MOD. PROP. ALT'D @ GDR. COARSE-GRAINED. MED. GRN-GRY.	TRACE DISS VFG PY.		120						
8	5.0	4.8	96	52	FRACTS @ ~45° & 80-85° TO C/A	MINOR PY WHERE DESCRIBED								
	5.0	5.0	100	72	122.5-123.5 BXID, BANDED QZ-CA-FLOODED ZONE. (2% SX) MINOR HEM. IN CA.	MINOR MG.								
					ABUNDANT CA IN STRINGERS & THROUGHOUT ROCK. MOD. BOILED CAKCLE.									
					129.0-129.9 AND DYKE & QZ CO_2 VEIN. MINOR PY & HC			130						
					SHARP CONTACT - NO MELTING OR DISCOLORATION	135.7								
9					ANDESITE DYKE. V.DK. GRY TO MED. GREENISH-GRY. ~1% SERICITE (GROUND). V. ABUNDANT CL STRINGERS. SCALE CHANGE 1"=50' HEADS OF COUNTRY ROCK. LOWER CONT. SHARP-UNDULATING	TRACE DISS PY. 5% PY FOR 1 CM AT LOWER (~1/10') CONTACT.		135.7						
					SHARP CONTACT - NO MELTING OR DISCOLORATION			140						
					STGL BRECCIA. SCALE CHANGE. ALT CONTACT. CA IN LOWER CONT.	141.3		141.3	6775	135.7-141.3	5.6'	.001	0.05	FW. ANDES. SCALE CHANGE TO 1"=1'
	5.0	2.6	87	18	GDR AS ABOVE BUT MORE STRONGLY CRACKLED. ABUNDANT CHLORITE-CALCITE-EPIDOTE-SERICITE. STRONG PROP ALTN. SLIGHTLY DARKER GREEN. LOWER CONTACT SHARP-50° CHILL MARG. IN ANDES.	TRACE DISS PY.		144.6	6775					
9					ANDESITE AS ABOVE.	TRACE DISS PY.		149.1	6776	141.3-144.6	3.3'	0.001	.011	
	5.0	5.0	100	60	LOWER CONTACT BRECCIATED GDR & ANDESITE MATRIX				6777	144.6-148.1	3.5'	0.009	0.07	2.003, 0.07/4.51m
					GDR. AS ABOVE BUT & MORE STRONGLY ALTERED & FRACTURED. 40°-45° SOME ORTHOQZ & CA & CA INFILLING. LOWER CONT. BXXD AGN & DISTRUSIVE CONTACT	TRACE DISS PY.		150.5	6778	148.1-150.5	2.4'	0.001	0.06	
					DISTRUSIVE BRECCIA: VFG GREEN MATRIX & SMALL QZ+ RHY CLASTS FORM MOSTLY FOR FRGS OF AND. GDR & RHY. BANDED QZ CLASTS TO 2 cm. SOME CLASTS OF QSX BX BANDED @ 45° TO C/A. SOME LOWE CA. LOWER CONT. SHARP & 80° TO C/A	PY, SL, GL, CP IN QSX & CLASTS		153.0	6779	150.5-153.0	2.5'	0.016	0.25	FOOTWALL 45.87m OCT 21
					QZ SX BX: WHITE QZ WITH VFG GREY SX THROUGHOUT & SX MATRIX.	DISS PY THROUGHOUT								
	4.0	4.1	100	0	SX FG TO VFG. OVERALL 25-30% TOTAL SX.				6780 *	153.0-157.2	4.2'	0.336	5.16	
					MOST FRACTURES LATER THAN MINERALIZATION ORIENTED	*50% PY, 30% AS, 10% SL, 5% GL, MINOR CP REMAINDER UNKNOWN.								
	5.5	5.3	96	41	40° TO C/A. FRACTURES LINED WITH CA & GROUND SX.	*PERCENTAGES ARE OF SULFIDES. 25-30% OF ROCK IN ZONE IS SX.		157.2	6781 *	157.2-162.8	5.6'	0.535	8.25	0.816, 6.60 / 14.3'
								160						
	1.5	0.7	47	23				162.8	6782 *	162.8-167.3	4.5'	1.614	5.88	
	6.5	6.3	97	12	LOWER CONTACT SHARP @ 45° TO C/A			167.3						
	1.5	1.3	87	0	MED GR, MED GRN-GRY ALT'D, BXID, SHEARED, BANDED GDR. CLASTS OF QSXBX. SEVERAL SOFT, CLAY-COATED ZONES.	TRACE DISS PY THROUGHOUT.		170	6783	167.3-171.0	3.7'	0.013	0.49	
	1.0	1.0	100	0	SOFT CLAY COATED SHEAR @ 168-169.5'			171.0	6784	171.0-172.0	1.0	0.088	1.95	
					SOME CORE LOST IN THE SOFT SHEARS, BUT NOT MUCH.	ALL SX MENTIONED ABOVE IN CLASTS OF QZ SX BX IN BXX. OVERALL V. MUAR.		172.0						
	5.0	4.2	84	32	OVERALL CARBONATE OVERPRINT - LATE CO_2 FLOODING.				6785	172.0-177.0	5.0'	0.011	0.97	
					177.0-178.0 CLASTS OF RHYOLITE TO 2cm, V. ANGULAR IN GDR BX. & SHEAR.			177.0						
11					BANDING AT ~70° TO C/A. CL, EP, CLAY, SE, CA IN BANDS OF WEAKNESS IN GDR.			180	6786	177.0-182.0	5.0'	0.016	0.47	0.010, 0.45 / 23'
	5.0	4.8	96	72				182.0						
					LOWER CONTACT SHARP, BX AGAINST BXXE. @ 60° TO C/A	184.8			6787	182.0-187.0	5.0'	0.001	0.21	
					INTERMEDIATE, F.G. MED GRN-GRY. DIKE. ALT'D. CRACKLED. MOD. CA. BASE SHARP 60°	TRACE PY.		187.0						
	5.0	5.0	100	50	BACK INTO MG. MED. GRY GDR. V. PHYLLIC ALT'D. BXID & SHEARED.				6788	187.0-192.0	5.0'	0.007	0.31	
					AS ABOVE, BUT GENERALLY LESS DEFORMED.	TRACE DISS PY.		190						
					BRECCIA & SHEAR @ 187.5'. V. CLAYEY SHEAR 0.7' WIDE., THEN 2 FT V. BROKEN ROCK.			192.0						
1930	5.0	4.8	96	7	LOWER CONTACT CRUMBLED & BROKEN BY SHEAR - GRADUAL.	193.1			6789	192.0-196.1	4.1'	0.015	0.63	75-97 23
					SHEAR ZONE. MOSTLY GDR CRUMBS & SAND, BUT SOME QZ SX BX FRAGS C/1cm.	BARITE, PY & SLIGHT SX IN QZ SX BX CLASTS.		196.1						
					SHEARED, ALT'D, BXID M-C-G GDR. AS DESCRIBED ABOVE	197.3			6790	196.1-201.0	4.9'	0.010	0.140	
	5.0	5.0	100	31	BUT WITH 1-2% SULFIDE BANDS, BLEBS & FG. DISSEMINATIONS THROUGHOUT. SOME SILICIFICATION.	MINOR ~1-2% SX BANDED THROUGH GDR. MOSTLY PY, BUT ALSO GL, SL, CP, AS.		200						
12					MOST FRACTS ORIENTED @ 50-60° TO C/A.	201.0		201.0	6791 *	201.0-202.1	1.1'	0.131	3.69	0.146, 4.27 / 4.8
	5.0	4.9	98	51	LOWER CONTACT UNCLEAR - BRECCIA GRADING INTO BRECCIA.									
					BRECCIA ZONE. GDR, QZ+SX, QZ & SX GRAINS TOGETHER. BANDED @ 30° TO C/A. LOWER CONT.	202.1		202.1	6792 *	202.1-205.8	3.7'	0.151	4.44	
	5.0	4.9	98	34	QZ-SX BX. ~30% SX IN GREY-WHITE QZ CLASTS. DK. GRY MINOR EP, CL, SE BANDING. MINOR CLASTS OF GDR. MOD. CRACKLE	PY, AS, SL, GL, CP TRACE AREA F.G.								

OMNI. RESOURCES INC. PROJECT SKUKUM CREEK DIAMOND DRILL HOLE No. 87-UG-36 Sheet 3 of 3

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
13	50 207.0	4.9	98	34	LOWER CONTACT GRADATIONAL, GOOD. BMD GDR ? CLASTS OF ASBX. GRADATIONAL LOWER CONTACT.	196.8 minor py sx @. 205.8		205.8	6793	205.8 - 207.0	1.2	.039	.36	
	50 222.0	5.0	100	63	ALT'D, BANDED, STRONGLY CRACKLED MED. GRN-GRY C.G. GDR. 210.0'-216.8'. XENOLS OF F.G. INTERMEDIATE DYKE & ABUNDANT FRACT-FILLING SX. CL, SE, CA, IN STRINGERS, BANDS & DISS THROUGHOUT. BANDS & STRINGERS OF PY=AS	BANDS + STRINGERS OF PY & AS. & SX MINOR CP + GL. DISS. PY DECREASING WITH DEPTH		210	6794	207.0-212.0	5.0	.002	.19	
	50 227.0	5.0	100	36	212': 1cm QZ VEIN @ 50° TO C/A ? 20% PY, SL, GL, AS. SX BANDS @ 213'. 213.3' HW SHEAR. 2 FRACTURE SETS @ 45° TO C/A, 90° TO EACH OTHER.			212.0	6795	212.0-216.1	4.1	.043	.43	213.3 HW. SHEAR 0.015, 0.21 /16.2
	50 232.0	5.0	100	44	214-219.6 MORE XENOLS TO 8mm OF INTERMEDIATE F.G. MED GRY DYKE ROCK. THEN 2' BAND OF F-M.G INTRUSIVE OF GDR COMPOSITION & 1cm BAND OF @ C.G. GDR THROUGH IT @ 20° TO C/A. THEN JUST C.G.			216.1 219.2 220	6796	216.1-219.2	3.1	.001	.04	
					MOD. PROP ALT'D MED GRN-GRY GDR.	222.0		222.0	6797	219.2-222.0	2.8	.005	.04	222.0 EOH
					END OF HOLE B7-UG-36	EOH								

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT SKUKUM CREEK (WH-claims)
COORDINATE N. 70954.8
E. 77767.6
ELEVATION 1304.2
DATE STARTED Sept. 22, 1987
COMPLETED Sept. 24, 1987
HOLE SURVEY

HOLE No. 87-UG-37
DEPTH 328'
AZIMUTH 123
INCLINATION -34°
DRILLED BY Caron Diamond Drilling
ASSAYED BY Acme Analytical Labs
LOGGED BY R.J.R., TME

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION
1			88	14	Med. G. Prop. Alt'd QMZ, pinkish-green, amorphous k-spar, plag x-tals often indistinct & in some zones are strongly alt'd to Se, minor matics (2-5%) & are v. alt'd minor to complete chl. fracts @ 40, 55 & 80° to C/A w occasional ca healing minor silicified zones	trace of dissem py
2			92	23		
					37.6 strongly chloritized fract at 50° to C/A	
3			100	15		
					very slight overall healed crackle texture	
4			99	11	63.0 Sharp lwr cnt Matic Chloritized zone, >50% matics, alt'd to chl, cubic Py zone is mashed 1-2% py Med to C.G. Prop Alt'd QMZ, as at 0-63.0', cnt's sharp & marked by qtz enrichment, aplite dyke at 68.0'	
5			100	12	C.G. Prop Alt'd GDR., med gry to med grn-gry colour, matics mod. abundant (15%), ~~large chloritized areas~~, matics partially alt'd to chl. on fracts, overall wk silicification w some small sections v. strongly silic'd, fracts at 20, 50 & 80°, some rehealed by ca. or conc'd matics - overall wk propylitic alt'n	- blebby py at some fract.'s
6			100	25	93.0' 6" v. silicified section	
7			96	63		

GRAPHIC LOG

FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag
10					
20					
30					
40					
50					
60					
70					
80					
90					
100					
110					
120					

OMNI RESOURCES INC. · PROJECT Skukum Creek · DIAMOND DRILL HOLE No. 87-46-37 Sheet 2 of 4

BOX	Run	Core	% R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	FT.
123.0							120
8			99	82			
131.0					-137' 5" andesite dyke		130
9			99	45			140
139.5					-157 ± 1" aplite dykelets		150
10			98	53	-1" qtz-carb vein at 167'		160
178.1							170
11			94	37	- v. strong prop alt'n from 180-193'		180
196.3					-5" andesite dyke at 192'		190
12			99	73	C. GR. GRANODIORITE - weak propy alt'n - Q-carb. vns 30-70° to c.a. 203.6'-204.8' = DARK GREEN ANDESITE DYKE. Lwr. contact ca. 50° to c.a. Scale change 1"=10'	Minor Py 1" = 10'	200
214.4					Fract. mainly 75° to c.a.; some fract. 35° & 45° to c.a.	Minor Py	210
	4		90	75	-217.4'		
219.0					DARK GREEN ANDESITE DYKE w. Gd. inclusions 2-3% Q-Cal. vns and irregular fillings. Upper contact 60° to c.a. Fract. 45° & 70° to c.a. Lower contact 30° to c.a.	Minor Py	
13	4		98	87			
223.0					223.1 SILICIFIED C. GR. GRANODIORITE. Irregular lower contact; 1/2-1% by vol. Q-carb. vns. 227.2 Fract. 70° to c.a.	Minor Py	220
	5		100	80			
228.0					COARSE MULTILITHIC BXA - mainly Gd frags; also Rhyo.; And; and mineralized Q.Sx.. Mainly 1-2cm clasts; occas. 0.5' clast; matrix supported, 2-3% Q-Sx frags. STRONGLY MNZD. QUARTZ-SULPHIDE BRECCIA - black, pyritic matrix. Mineralized cm. white; barren Q frags common. 235.8'-245.6' = ALTERED C. GR. GRANODIORITE	1-2% Py w. minor galena. * 2% Py, 1% Cpy from 233-233.8' * Quartz 7% Py, 0.2% Asp to 240'	
232.5	5		94	64			230
233.0							
14	5		100	64			
238.0							
	2		70	Ø	Mod to strong propylitic alt'n. Strong chlorite locally along fractures	0.1% Py	240
240.0							

SAMPLE			ANALYTICAL		
Sample No.	INTERVAL	CORE LENGTH	O.P.T. Au	O.P.T. Ag	
223.1					
T 6798	223.1'-227.2'	4.1'	0.001	0.02	
227.2					
T 6799	227.2 - 231.6'	4.4'	0.001	0.32	
T 6800	231.6-235.8	4.2	0.036	2.68	RUSH Special prep.
T 6801	235.8 - 240.8'	5.0	0.001	0.10	

1" = 10'

JL @ Fou. 217.4

OMNI RESOURCES INC. ** PROJECT Skukum Creek DIAMOND DRILL HOLE No. 87-UG-37 Sheet 3 of 4

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION
	5		96	61	Fract. mainly 35° & 60° to c.a.	0.1% Py.
	246.0				Zone ends in shear ca. 45° to c.a.	
14	5		70	21	245.8 - 268.2' = SHEARED, TAN RHYOLITE IN FAULT ZONE.	
	250.0				- abundant fault gouge.	
	251.0		40	0	Strongly sheared to 252' (Poor recovery)	Minor Gn and Py
253.0	253.0		25	0		
	5					
	258.0		8	0		
	3		90	17	258.5' - 260' = minor Gn and Py on fracts (black)	
	261.0				Fract. 30° & 50° to c. axis.	
	2		75	0		
	263.0				263 - 267' = Occas. Q - Cal. vns	
15	3		87	13	264.5 = Cal - Fluorite infilling around frags.	
	266.0				267' = 2 x 1 cm. Q-Sx (Py) frags in brx?.. Rhyo = Post Mineral	
	2		90	60		
	268.0				Delete!	
	6		96	58	COARSE MULTILITHIC BRECCIA as from 221.2 - 234.6' Clast supported; mainly Gd. frags.	
	273.0				272' = healed shear at 20° to c.axis	
276.0					Mod. propylitic alt'n; local silicification	
	5		96	40	Pyrite in frags. and in matrix.	1-2% Py
	278.0				½% Q - Cal. vns.	Minor Gn
	5		96	51	Fractures mainly 45° to c.a.; some are 20° or 70° to c.a.	
	283.0				282.9' = 5mm. Q vn w. 5-7% Py & minor Gn at 40° to core axis	
16	5		94	20	285.5 - 286' = 5 x Q - cal. vns at 45° to c.axis Vary from ½ - 3 mm.	
	288.0				287.1 = ALTERED C. GR. GRANODIORITE	
	5		98	9	- moderate propylitic alt'n / irregular upper contact. Mafics strongly chloritized and plag. sericitized.	Minor Py
293.2	293.0				Fract. mainly at 45° to c.a.; some at 30° to c.a.	
	6		98	34	293.5 - 296.9' = MIXED MULTI-LITHIC BXA of Q SX BXA Mainly Rhyo. & Q. Fragsw Q Sx Bxa from 295 - 295.5' C GR GRANODIORITE Contacts 45° (upper) & 30° (lwr.) to c.a.	2% Py w. 0.2% Cpy in Q Sx Bxa Section = 5-7% Py, Cpy
	298.0				Moderate propylitic alt'n.	
	5		98	35		
17	303.0				Chlorite along fract.	Minor Py.
	5		100	44		
	308.0				Fract. mainly 45° to c.a.; some fract. 60° to c.a.	
310.1	5		98	26		
	313.0					

GRAPHIC LOG

FT

SAMPLE			ANALYTICAL		
Sample No.	INTERVAL	CORE LENGTH	O.P.T. Au	O.P.T Ag	
T 6802	240.8 - 245.6	4.8'	0.001	0.17	
T6803	245.6 - 250'	4.4'	0.001	0.25	
T6804	250 - 253'	3.0'	0.001	0.05	
T6805	253 - 258'	5.0'	0.002	0.16	
T6806	258 - 263'	5.0'	0.007	0.02	
T6807	263 - 268.2'	5.2'	0.008	0.16	Delete.
T6808	268.2 - 273.2'	5.0'	0.016	0.23	
T6809	273.2' - 278.2'	5.0.	0.001	0.06	
T6810	278.2' - 283.2'	5.0'	0.001	0.05	
T6811	283.2' - 287.1'	3.9'	0.002	0.10	
T6812	287.1 - 292.1'	5.0'	0.001	0.08	
T6813	292.1' - 293.5'	1.4'	0.002	0.11	
T6814	293.5 - 296.9'	3.4'	0.009	1.33	HW contact @ 296.9
T6815	296.9 - 301.9'	5'	0.001	0.05	
					0.004, 0.19 C.I.

OMNI RESOURCES INC. · PROJECT Skukum Creek DIAMOND DRILL HOLE No. 87-46-37 Sheet 4 of 4

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag	ANALYTICAL
	5 318.0		100	46	315.5' = 2 cm. brated white Qtz. vn at 30° to c.a.	Minor Py								
18	5 327.0		100	41	317.5' = 3mm. Q-Py vn at 55° to c.a. Weak to Mod. propylitic alt'n. Fract. mainly 45° to c.a.; some fract 30° & 70° to c.a.			320						
326.8 19	5 328.0		100	42			EOH	330						

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT Skukum Creek (Wh) | HOLE No. 87-UG-38
COORDINATE N. 71257.9 | DEPTH 275'
E. 77999.4 | AZIMUTH 122.3
ELEVATION 1300 | INCLINATION -46.5
DATE STARTED | DRILLED BY Caron Diamond Drilling
COMPLETED | ASSAYED BY Acme Analytical Labs
HOLE SURVEY | LOGGED BY T. M. Elliot

T.W. Multiplier 0.5225

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION
1			99	20	Core loss at beginning 1.8' **Bi-Modal Diorite** - wkly Prop. alt'd, med gry colour, # plag x'ls 2-5mm in f.gr. grndmass of qtz & minor hornblende, mafics occasionally concentrated in anastomosing lines & are chl. alt'd - ca. reheeling some fract's at 32°, fract. sets of 70°, 25° & 80°	
2			84	24	- 19.7' 1.6' f.gr. And. dyke at 60° to CA, wkly visible f-spars @ 1-2mm - 29.6' 1.0' And. dyke at 26° to CA - 32' section qtz enrichment & ½" qtz vein w/py at 35° to CA - Diorite finer grained & more strongly Alt'd from 33' to 37.5' 37.5' - 38.9' finegr. And dyke @ 85° to CA	- ≤ 2% blebby py w qtz vein
3			97	31	- 44.9' ½" [illegible] xenolith of BMZ	
4			84	56	- 52.5' epi in veins & bands at 50° to CA offset by fracts at 25° 66.3' to 68.6' section of wkly prop alt'd GDR	
5			84	19		
6			92	4		
7			97	19	- 108' 1' section qtz flooding w/ brown & epi(?) clasts 5mm - 1cm - 110.8' lwr cnt sharp & at 35° C. Gr. Silicified Prop Alt'd GDR, cnt marked by qtz flooding wk bryn & epi in stge to 113.5, then increasing silic'n of GDR to 122, 5" str prop alon then a brecd completely silica replaced to w/ epi in cracks	

GRAPHIC LOG

FT. 1" = 20'	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag
0					
10					
20					
30					
40					
50					
60					
70					
80					
90					
100					
110					
120					

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	FT.	Sample No.	Interval	Core Length	O.P.T. Au	O.P.T. Ag	
128.5					Intensely altered ash tuff w/ strong schistosity & qtz. stringers								
8			99	62	C.Gr. Prop Altd Matic Rich G.DR. matics ≤ 50% total → chl, med-dk grn clr, matrix of qtz clasts fracts at 18, 35, 60 & 80°, wk pervasive silic'n 131.6 lwr cnt gradual C.Gr. Mod Prop Altd GDR lt grey clr, matics 15% → chl, minor epi along one fract., matics wkly conc in some fract.'s, fract at 35, 60 & 80°		120						
140.4					139.6' sharp cnt at 45°		130						
9			99	15	Mod Gr. Prop Altd QMZ pinkish grey clr, pervasive silic'n, matics minor % → chl, minor rehealing of fract by chl & kspl(?) & epi in one fract., fract at 40° & 75°		140						
157.7					157' sharp cnt C.Gr. Prop Altd GDR. mod matics (15%) → chl, lt grey clr, fract at 35°, 60° & 80°		150						
10			100	4	-168-169, silic'd section		160						
173.9					173' sharp cnt		170						
11			81	0	Mod Gr. Prop Altd QMZ as at 164.5'; minor kspl on fract, wk prop altn 180.6'	- minor blob py along qtz veinlet	180						
					main change 1" = 10'	main change 1" = 10'	190						main change 1" = 10'
192.3			99	10	WEAK TO MOD. ALT'D C. GR. GRANODIORITE - propylitic alt'n; chl. matics and partly ser. plags - Fract. mainly 30° and 60° to c.axis.	Minor Py							
	1&1+	3.96											
	3 199	2.97	99	0	196.5-196.6' = DARK GRAY MULTILITHIC BRECCIA Sharp contacts 50° to c.a. Manly Gd frags.; 1% Qtz. frags.; Matric supported; 1% Pyrite	1% Py (196.5-196.6')							
12	4.5 202.5	4.45	99	0	197.5' = 1½ cm. fault gouge at 45° to c.a. 200.3' = 3 mm Q vn. at 50° to c.a. 203' = chl. and ser. on fract.		200						
	2.5 205	2.5	100	0	205.2' = 2mm - 7mm Q-Cal vn w. minor Py at 40° to c.a.	Minor Py							
208.9	5 210	5	100	20	208' = Bleb (5 mm x 4 mm) of MoS_2 in C. gr. Gd. Patchy; weak to mod. silicification begins.	Bleb of MoS_2							
	3 213	2.31	77	0	Fract. mainly 45° to c.axis.		210						
	3.5 216.5	2.69	77	0	215.5' = 4 mm Q-Py-Aspy vn. at 45° to c.a.	Vein of Q-Py-Aspy							
13	1.5 218	1.31	87	0	216' = Patchy strong sericitization = Q-Py vn (2mm) at 50° to c.a.	2-3% Py on fract from 216-218.3		T6816	214.1-218.6'	4.5'	0.004	0.12	
	4 222	1.6	40	0	218.3-218.6 = ANDESITE at 45° to c.a. PEBBLES of QTZ-SX BRECCIA and MNZ'D RHYO. 50% Q Sx Bxa and 50% Rhyo	Pebbles of Q Sx Bxa ctg. 10% Aspy, 1-2% Py and Py(?) in fgr. Gd	220	T6817	218.6-221.7	3.1'	0.082	4.97	* Only 15% Fine recovery. Whole sample taken.
	4 226	4	100	46	RHYO. BXA FAULT GOUGE. MIXED QTZ-SX BXA & C.GR. GD. BXA Both clast and matrix supported sections; clasts up to 2-3 cm. across; 2.5' is Q Sx Bxa	1% Py (?) 3-4% Py overall Some (?½%) Aspy? Fine grained		T6818	221.7-223.6	1.9'	0.006	1.05	
								T6819	223.6-227.8	4.2'	0.180	5.41	
230.1	5.6 231.5	5.23	95	40	SHEARED GRANODIORITE BXA - 30% light brown carb. infilling	2% Py (disseminated)	230	T6820	227.8-231.1	3.3'	0.004	0.27	

OMNI. RESOURCES INC. ** PROJECT _____ DIAMOND DRILL HOLE No. 87-46-39 Sheet 3 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag	ANALYTICAL
								230	231.8'					
	5	5	100	34	FAULT ZONE of GD. BXA (85%) and Q. Ser. BXA FRAGS (10-15%) - Lwr. contact 40° to c.axis	2-3% disem. Py			T6821	231.8-234.9'	3.1'	0.059	4.34	
14	234.5				MAINLY RHYOLITE BRECCIA - both frag & matrix supported. Black matrix = 30-40% 5-10% Qtz. frags. over last 0.5' Lwr. contact 35° to c.a. Partly silicified	1-2% Py			T6822	234.9-238.9	4.0'	0.022	0.38	M contact
	5	5	100	34										
	239.5								T6823	238.9-243.9'	5.0'	0.008	0.09	
	5.5	4.92	93	9	ALTERED C. GR GRANODIORITE - Crackle brated to 240' Silicified to 248' Fractures mainly 60° to c.a.; some are 45° to c.a. Chl. on fractures.	Up to ½% Py locally.								
	245								T6824	243.9-248.9'	5.0'	0.001	0.01	
	5	5	100	8										
	252				251.8' - 5mm Q-Carb vn at 50° to c.a. Vein is offset twice by shear fract.									
	3	3	100	0	252.5-253' = Py on shear fract down core axis									
	256				255' = Mod. propylitic alt'n. Fractures 60° and 45° to core axis.			250						
15	5	4.90	98	10										
	260				260.8' Lwr contact ca 45° to c.a.									
	5	5	100	10 (83)	DARK GRAYISH-GREEN M. GR GRANODIORITE PORPHYRY DYKE									
	265				30% 3mm. plag. phenos in a finer granular matrix. Wk to mod. propy alt'n. Fract. 45° & 70° to c.a. Lower contact irregular at 45° to c.a.	Minor Py		260						
	5	4.90	98	33										
16	270				272'									
	5	5	100	30	C. GR GRANODIORITE - weak to mod. prop. alt'n. end of hole at 275'	Minor Py		270						
	275						E.o.H.	275						E.o.H.

0.46, 1.53, 10.4

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT	Skukum Creek (W/h)	HOLE No.	87-UG-39
COORDINATE N.	71257.3	DEPTH	279'
E.	77998.3	AZIMUTH	155
ELEVATION	1300.0	INCLINATION	-53
DATE STARTED		DRILLED BY	Caron Diamond Drilling
COMPLETED		ASSAYED BY	Acme Analytical Labs
HOLE SURVEY		LOGGED BY	T M Elliot

T.W Multiplier 0.4924

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
1			100	11	Med Gr. GRANODIORITE Porphyry ≈ 15% 2-5mm plag phenos in fine to med. gn matrix, med. gry colour, pleg's white, v.wk propylitic alt'n, v. slight tr'n of plag w/ acid, calcite filled fractures at 40° to C/A, fract. at 40° & 70° to C/A, general subporphyritic texture - section of @ GDR continues to 219.7'			0					
17.0					19.0' sharp cnt			10					
					21.7' Andesite DyKe, black aphanitic, m.s.v. texture								
2			92	24	GDR as @ at 0 - 19.0'			20					
					26.4 minor brn'n w/ rustiness on fractures, clasts in calcite matrix	- minor rustiness on fractures							
33.7					31.7' 33.7' Andesite DyKe, as at 19.0 - 21.7'			30					
					36.1' fract at 25° to C/A, cream coloured reheal'ng (qtz w/ kaol?) 38.6' increase in matrix								
3			98	42	GDR. as above 43.1' Andesite DyKe dkgry-black, aphanitic, <<.5mm fract w/ ca			40					
51.3					Med Gr. GRANODIORITE Porphyry as described above			50					
4			99	27	61.9 1' section strong sericite & clay alt'n & w/ ca, in bands at ∠ 30° to C/A			60					
68.6					69.4 1cm band of sericite			70					
5			93	21				80					
86.2								90					
6			92	6	- some broken core, slightly stronger alt'n & ca. on fractures			100					
102.1					103.6' 1cm ca. vein at 32° to C/A increase in pervasive silic'n								
7			100	26				110					
118.8								120					

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-UG-38 Sheet 2 of 3

RQX	Run	Core	% R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag	ANALYTICAL
8			91	23	131.3' 3 cm networking & banded qz. & c. cor. veinlet at 45° to C/A			130						
136.1														
9			99	10	142.3' shear for 2", gry gouge, shear at 45° to C/A			140						
149.4														
10			100	48				160						
167.7														
11			89	26	179.0' 1 cm calcite vein at 20° to C/A			170						
186.3														
12			96	36	scale change 1" = 10'	1" = 10'		190						scale change 1" = 10'
202.5								200						
	5	5	100	17	DARK GRAY M. GR GRANODIORITE PORPHYRY as from 260.8 – 272.2' in hole UG 38. ~15% 2-3 mm. plag phenos in a f.gr. matrix. rock is subporphyritic. Ca. 10% chl. (M) shratty mafics. Abund. (2/ft) hairline to 1 mm calcite veinlets at 30° to 60° to core axis. Fract. mainly 50° to c.a. some fract. at 25° to c.a. Weak propy. alt'n; some plag. phenos. sericitized.									
	5	5	100	32										
13	212.5													
	214	1.5	100	Ø										
	4	3.52	88	34				210						
	218													
	218.1	1	100	Ø	218.7'									
220.7	5	4.9	98	34	ANDESITE PORPHYRY DYKE – contact zone very f.gr.; very dark gray. After 3' of contact zone and ~1% porph. w. spotty, shratty chl mafics (5%) and ~5% fresh plag. phenos, 2% by vol. calite vns at 25 & 45° to c.a. Fract. 45° to c.a. j occas. 0° along c.a. Silicified & bleached from 224' to contact.									
	224													
	5	4.8	96	Ø										
14	229				228.4'									
	5	4.8	96	Ø	STRONGLY MINZ'D QUARTZ-SX BRECCIA 20-25 ERMS 2/cm. Contacts 20° (upper) & 25° (lwr) to c.a. CLAST-SUPPORTED CREME to TAN RHYOLITE BRECCIA 5% light brown carb. vnlts & irreg. fract. fillings to 233'. Max. frag. size = 2-3 cm. Locally white vein Qtz which is also brecciated.	15% Apy in matrix 2-3% Py; <½% f.gr Gn		230	T 6825	223.4-228.4'	5'	0.014	0.17	
	234					2-3% matrix Py on healed black shears.			T 6826	228.4-230.5'	2.1'	0.194	5.53	
									T 6827	230.5-235.5'	5.0	0.025	1.28	

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-UG-39 Sheet 3 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag	
238.2	5 239	5	100	36	PRE-MINERAL RHYO. BXA. continues.	2-3% Py Minor Gn.			T6828	235.5-241.3'	5.8'	0.028	1.85	
	5 248	5	100	56	239' ± minor Gn in matrix Lower contact 40° to c.a. Approx 0.6' at fault gouge COARSE GRAINED GRANODIORITE - 5-7% mafics (chloritized) - Crackle brecciated w. patchy silicification to 244'			240						Contact ##
15	5 249	5	100	42	- weak to mod. propy. alt'n	Minor Py. delete!			T6829	241.3'-246.3'	5.0'	0.001	0.05	
	5 254	4.9	98	35	M.GR. to C.GR. QUARTZ DIORITE - 20-25% chl. matrix Mod. propylitic alt'n. - 10-15% Qtz.; Contact 45-50° to c.axis. 252'			250						
256.2	5 259	5	100	42	Qtz-Cal. vns ca 45° to c.a. / per foot ave.									
16	5 264	5	100	48	Fract. mainly 70° to c.a.; some fract = 45° to c.a.	Minor Py		260						
	5 269	5	100	70	Fracture intensity increases over last 2.5' Lwr. contact ca 20° to core axis									
274	5 274	5	100	65	COARSE GRAINED GRANODIORITE as from 241.3-252'	Occas. Q-Py vnlt.		270						
17 279	5 279	4.4	88	75	Fract. 70° & 45° to c.a. Moderate propylitic alt'n. End of Hole UG-39 at 279'		E.o.H.							End of Hole

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT Skukum Creek (Wh)
COORDINATE N. 71257.1
E. 77298.4
ELEVATION 1300.4
DATE STARTED
COMPLETED
HOLE SURVEY

HOLE No. 87-UG-40
DEPTH 204'
AZIMUTH 156
INCLINATION ~~ABOV~~ -35°
DRILLED BY Coron Diamond Drilling
ASSAYED BY Acme Analytical Labs
LOGGED BY TM Elliot

T.W = 0.7295

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION
1			95	45	Med. Gr. Sub-Porphyritic Granodiorite 10-15%, 2-5mm plag phenos in fine to med gr. matrix, med grey colour, plag phenos white w/ w/k rx'n to acid, v. wk propylitn some ca. filled fractures at 40° to C/A, fract. at 30° & 70° -GDR continues to 134.7' 12.8' Andesite dyke dk grey w/ 1-2mm plag phenocrysts	
17.9					GDR. as above 20.3' andesite dyke	
2			94	41	24.9' GDR. as above 27.5' Andesite dyke, black & aphanitic GDR., as described for 0 to 12.5'	
35.7					-34.8' 15 mm wide band of ca & qtz at 46° to C/A	
3			90	31	39.4' 3cm inclusion of QMZ	
57.8						
4			99	37	64.5' 0.a' section w/ 1cm ca. vein at 45° to C/A, ≤ 10% Cn & Zn	-ca vein w/ 10% Zn & Cn
71.0						
5			97	24	90.6' v. broken & fractured core, ca veins & clots 92.4'	
6			87	28		
104.6						
7			100	55	109.5' 2x3cm xeno. of QMz	

GRAPHIC LOG

FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag
0					
10					
20					
30					
40					
50					
60					
70					
80					
90					
100					
110					
120					

OMNI RESOURCES INC. PROJECT DIAMOND DRILL HOLE No. 87-46-40 Sheet 2 of 2

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.R.T Ag
122.6					122.6' .7' med grey, f.gr. dyke, prob. GDR equivalent – percentage of mafics increasing along ψ silic'n			120					
8			96	33	131' 2.5 x 3cm xena of QMZ ∥ to CA 139.7' Andesite, med-dk gry, f.gr. to aphanitic 137.3' ≤ 7% ryas blebs in veins scale change 1" = 10'	cubic py as blebs along veins scale change	55°	130					
136.4	6 144	4.3	86	50	ANDESITE w. INCLUSIONS OF C.GR GDR Local, patchy silicification Fract. mainly 45° to c.a., along some fract. 60° & 30° to c.a.. And. dark grayish green. GDR. inclusions from 156-151' and 152.5-154'	Minor Py		140					scale change 1" = 10' CONTACT
9	5 149	4.8	96	38									
	5 154	4.6	96	54				150	151.4'				
	5 159	3.7	74	18	BLEACHED ANDESITE CONTACT ZONE ca. 50° to c.a. FAULT GOUGE of RHYOLITE BRECCIA - banding near upper contact = 50° to c.axis trends E-W SHEAR	(?) Only minor Py at contact. 2-3% Py; 0.1-0.2% Aspy (fracs)			T6830	151.4-156.4'	5.0	0.001	0.02
161.0	5 164	4.9	98	68	MAINLY GRANODIORITE BRECCIA w. 1-7' of RHYOLITE BxA. 161.9' RHYO BxA – 15% blk matrix in gdr. bxa. Some min'd Q frags in matrix	2-3% Py mainly in matrix.			156.4'				
	166 2	1.9	95	25	163.4' GDR BxA Lwr. contact 45° to c.axis.				T6831	156.4'-159'	2.6'	0.016	0.59
10	3 169	2.5	83	Ø	ANDESITE w. INCLUSIONS of GDR. 1-2% by vol. white calcite vns 45° and 60° to the core axis.	0.1-0.2% Py		160	T6832	159-164.3'	5.3'	0.008	0.22
	5 174	4.7	94	44	Weak propylitic (?) alt'n.								
	5 179	4.7	94	26	Fract. mainly 45° & 60° to c.a.; a few fract = 25° to c.a.				T6833	164.3-169.3	5.0'	0.003	0.17
179.0					Contact irreg. and roughly 35° to core axis			170					
	5 184	4.7	94	Ø	COARSE GRAINED GRANODIORITE 5-7% chl. mafics Moderate propylitic alt'n.	Py at contact.							
11	5 189	4.9	98	36		0.1-0.2% Py							
	5 194	4.8	96	54	191.6/192.0 Pyritized zone in gdr. 60° to c.a.	191.6/192.0 7% Py, w. minor cpy and gl.		180					
197.1	5 199	4.8	96	86	196' = 0.1' of Q-Py along shear 60° to c.axis								
12	5	5.0	100	32	Fract. mainly 20°, 45° & 60° to c.axis.	0.1-0.2% Py.		190					
204.0	204												
								200					

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	Skukum Creek (Wh)
COORDINATE N.	71256.9
E.	77997.1
ELEVATION	1303.6
DATE STARTED	
COMPLETED	
HOLE SURVEY	
HOLE No.	87-46-41
DEPTH	233
AZIMUTH	189
INCLINATION	-45°
DRILLED BY	Ceron Diamond Drilling
ASSAYED BY	Acme Analytical Labs
LOGGED BY	T M Elliot

Reason for Drilling

Explanation of Results

LEGEND

T.W. Multiplier 0.5668

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION
1			95	11	C.Gr. Sub-Porphyritic Diorite 15', 2-5mm plag phenos in med.gr. matrix, med gry colour, plag phenos white, hard & donot react w acid, Ca. on some fractures but does not re-heal, fractures at 90°, 60° & minor set at 80°, groundmass of qtz & hornblende (?), some fractures & anastomosing veinlets filled by hard bright grn mineral (clinozoisite ?) 15.6' — GDR continues to 126.6' 17.7' Andesite Dyke, black, aphanitic	
2			96	19	Diorite as above 22.6' Andesite Dyke 25.0' Andesite Dyke 27.3' 1.5' section of c.gr. QMZ w clino. filled tract. at 60° to C/A 28.5' 5" section of c.gr. QMz 29.7' Andesite Dyke - xenolith of QMz	
3			98	7	40.2' 42.7' C.Gr. Prop Altd QMZ, cream coloured plag; wk prop alt'n 46.1' 1.5' section of f.gr. Diorite, few plag phenos, veinlets of clino.	
4			95	46		
5			88	33	73.6' 1.5' section of silicified Diorite, crackle fractured & reheeled by Clino(?) 76.5' 1.0' section v. silic'd & strongly crackled to brec'd, clasts not rotated 84.7' 6" section of c.gr. QMZ, wk prop alt'n 87.5' sharp contact	
6			98	44	91.2' C.Gr. silicified QMZ, wk prop alt'n, plag cream coloured, matics → chl.; clino(?) in fractures - 1" band of clino. at 80° to C/A - 2" band of clino. at 60° to C/A - increasing pervasive silication	
7			98	4	111.5' 1" band of clino., broken & slightly offset about C/A, at 45° to C/A	

GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
37° 60° 80° 45° 60°	0, 10, 20, 30, 40, 50, 60, 70, 80, 90, 100, 110, 120					

OMNI RESOURCES INC. · PROJECT Skukum Creek (Wh) · DIAMOND DRILL HOLE No. 87-UG-41 Sheet 2 of 3

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag	ANALYTICAL
1725					Andesite dk grey clr, fgr., silic'd		120						
1765					Silicified C.Gr. Diorite								
8			99	12	Andesite w/ Diorite Inclusions		130			2			
					scale change 1" = 10'	scale change							scale change 1" = 10'
1912	5 143	5	100	34	ANDESITE w. M.Gr. GRANODIORITE INCLUSIONS		140						
	5 149	4.3	96	53	Patchy mod. silicification Occasional calcite veins (½ - 2mm) at 10-20° to c.a. A few veins are 45-50° to c.a.								
9	5 153	5	100	44	Fract. mainly 55-70° to c.a.; some fract. are 30° and 45° to c.a.	Minor Py							
	5 158	4.9	98	43	Crackle brecciation from 154' to contact. Lower contact is irregular but banding in underlying 159.9' rhyo. is 45° to c.a.		150						6.09 3.95
1582	5 163	5	100	16	RHYOLITE BRECCIA FAULT ZONE - shear banding in tan to grey rhyo. = 45° to c.a.; 2% scrag carb. infilling	Minor Py (very low contact)	154.9'	T6834	154.9' - 159.9'	5'	0.004	0.01	FOOTWALL
	5 168	4.7	94	40	BANDED (40° to c.a.) QUARTZ - SULPHIDE BRECCIA TAN RHYOLITE BRECCIA FAULT ZONE. Banding mainly 60° to c.a. Occas. ang. or Qtz. frag.	7% Py, 2% Aspy, 2% Sl. 2% Py, vis. Galena		T6835	159.9 - 162.8	2.9'	0.001	0.16	
10	5 173	3.2	64	Ø	164.1 - 167.6 = 2% Py & visible galena. Clast-supported bxa. 167.9 - 168.7 = fault gouge. Patchy gray silicification in rhyo frags	1% Py	160	T6836	162.8 - 164.1	1.3'	0.304	21.89	
	5 178	2.8	56	Ø	173' → fract. commonly 30° to c.a. 172.6 - 177' = Carb (creme) and carb - py veins (1mm) 177'	1% Py.		T6837	164.1 - 167.6	3.5'	0.013	0.50	
1796	5 183	3.7	74	Ø	Section w. strong Py - Sl± Aspy as impregnations along fract. Carb - py veins common. 182'	3-4% Py, 1% Sl. <½% Aspy.		T6838	167.6 - 172.6	5.0'	0.008	0.34	0.022, 1.15 / 12.5'
					184' Banded Rhyo. Bxa w. 10-15% black sulphide matrix	2-3% Py	170	T6839	172.6 - 177'	4.4'	0.026	0.48	
11	5 188	4.8	96	29	MIXED QTZ - SX BXA & RHYOLITE BXA FAULT ZONE - both clast & matrix supported - equal amts. of rhyo & Qtz. frags; w. an occasional GDR. frag. 189.2' = some Gn on fract	7% Py, 2-3% Aspy 1% Sl. Minor Gn		T6840	177 - 182'	5.0'	0.046	3.04	33.10 .080 9.52 (.254) 10.09
	5 193	4.2	84	Ø	Fract. at 60° to c.a. 191.5 - 192.5' = Strong fault gouge. Contacts ca. 45° to c.a. 193' - FAULT ZONE ENDS			T6841	182' - 184'	2.0'	0.019	1.06	
1988	5 198	4.3	86	Ø	STRONGLY ALTERED M. GR GRANODIORITE - bleached light gray; clay & creme carb. altered. - local silicification Fract. 45°+60° to c.a. - local crackle brecciation. - blocky irreg. Inc. contact w. some AND. frags	½% Py.	180	T6842	184 - 189'	5.0'	0.167	25.05	RUSH Spec. Native Gold Prop
12	5 203	4.5	90	13	WEAKLY ALTERED M. to C. GR. QTZ. DIORITE - 20% chl. matics; rel. fresh plag.; ie. wk. propy. alt'n	Minor py & cpy.		T6843	189 - 193'	4.0'	0.247	34.55	CONTACT
							190	T6844	193' - 198'	5.0'	0.001	0.04	0.203, 29.27 / 9.0
								T6845	198 - 201'	3.0'	0.001	0.06	
							200	T6846	201 - 206'	5.0'	0.001	0.06	

OMNI RESOURCES INC. · PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-UG-41 Sheet 3 of 3

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.R.T Ag	ANALYTICAL
	5 209	4.6	92	Ø	Fract. 30° ¼ 45° to c.a. 4 some rehealed by calcite strong rsʰn in matrix, near contact fractures have oxide staining	Minor Py.			7 6894					
12	5 213	4.4	88	Ø				210						
218.9	5 218	4.9	98	8										
	5 223	4.8	96	Ø				220						
					223 Inr Cpt V. sharp at 80° to C.A.									
13	4 227	2.2	55	Ø	C.G. Prop to Altrd QMZ v.fractured and broken, plag v. soft & bleached, mod rsʰn w/acid, plag x-tals up to 10mm, ltgry & gry/grn colour, open x-cutting fractures, abundant mafics → chlorite as blebs 1-5mm									
	4 231	3.0	75	Ø	224.7 & 230.0 f.g. aphanitic intermediate(?) dykes 1'85" wide			233						
	2 233	1.7	85	Ø	87-UG-41 End of Hole at 233'		E.o.H							end of hole

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT	Skukum Creek (Wh)	HOLE No.	87-46-42
COORDINATE N.	71257.9	DEPTH	194
E.	77997.8	AZIMUTH	165
ELEVATION	1304.1	INCLINATION	-55°
DATE STARTED		DRILLED BY	Caron Diamond Drilling
COMPLETED		ASSAYED BY	Acme Analytical Labs
HOLE SURVEY		LOGGED BY	TM Elliott

T.W Multiplier 0.6528

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	ANALYTICAL
1			95	25	C.Gr. Sub-Porphyritic Granodiorite Over 15% 2-5mm white plag. x's in med gr. matrix of qtz, s hornblende, general med. gry colour, fractures at 40°, 60°, 80° f.gr. groundmass of qtz & hornblende, ca in some fractures, & some traces of networking veins filled by hard green mineral 157' poss. clinozoisite (?) - Section of Granodiorite continues to 129.4'			0						
19.0								10						
					19.7' sharp contact 21.2' 4" f.gr. hornblende dyke, strong prop altd Andesite			20						
2			95	15	GDR as above			30						
35.9					35.2' sharp contact 37.4' 4" Prop Altd Andesite									
3			96	36	GDR as above			40						
59.0								50						
4			92	27	68.1' 4" 8" section fract at 30° to CA filled w/ clinozoisite (?)			60						
71.4								70						
5			97	26	85.2' 7" section of anastomosing clino. (?) veinlets			80						
89.6					DARK GRAY M.GR SUBPORPHYRITIC GRANODIORITE - 7% f.gr. mafics ; local crackle brecciation - fresh to weakly propylitized ; plag. is relatively fresh. scale change 1" = 10'	scale change		90						
6			98	18	Occas. yellowish - creme rhyo. dyklets. (ag) at 106' 1/cm dyklet at 60° to c.a.			100						scale change 1" = 10'
106.9	5 109	5	100	16	104.4 - 104.7 = Dark green andesite dyke at ca. 30° to core axis. Fract. mainly 45-60° to c.a. Core is strongly fractured	No Py.		110						

OMNI RESOURCES INC. · PROJECT Skukum Creek (Wh) · DIAMOND DRILL HOLE No. 87-UG-42 Sheet 2 of 3

BGA	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
	4 113	4	100	23				110						
	2 116	2	100	Ø	Weak calcite alteration. Strong fracturing — see low R.Q.D.'s	No Py. (TE)								
7	4 119	3.8	95	Ø		TRACE DISS PY. (TE)								
	2 121	2	100	Ø				120						
123.7	3 124	2.7	90	Ø										
	3.5 127.5	2.0	57	Ø										True Width MuHole 0.641
	1240	1.	73	Ø	Bleaching of gd. 0.5' before contact.									
					129.4' Contact ca. 45° to c.a.	129.4		129.4						
8	5	4.5	90	13	ANDESITE: F.G. DK GREENISH-BLACK. STRONGLY PROP. ALT. STRONG OVERALL CALCITE WASH. (FIZZES STRONGLY) MINOR EPIDOTE IN FRACTS & DISS. RUST ON FRACT. SURFACES. 2 FRACT. SETS. 1@ 60-65° & 1@ ~90° TO C/A	BARE TRACE UFG DISS. PY (SECONDARY)		130						
	134													
	135	.7	70	Ø				131.5						
	136	1.0	100	Ø	LOWER CONTACT GRADATIONAL + GRADES INTO COARSER GROUND	135.7		135.7	6848	134.2-135.7	1.5'	0.001	0.01	
	137	.9	80	Ø										
	138	.5	100	Ø					6849	135.7-140.0	4.3'	0.001	0.01	
	1390	10	67	Ø	FINE-M.G GDR & APHANITIC GROUNDMASS. DK-GRN-GRY AT TOP TO LT-GRN-GRY AT BASE. WASHED OUT. KTAL STRUCTURE V. INDISTINCT. STRONG PROPYLITIC ALT. AT TOP WITH MOD PHYLLIC @ BASE. LAST @ 60 cm STRONGLY SILICIFIED. LIMONITE ON FRACT. SURFACES. FRACTS @ 20, 50 & 85-90° TO C/A. MOD. HEALED CRACKLE. MINOR CA IN LAST 60 cm, MORE AT TOP OF UNIT. 1cm CA VEINLET AT BASE OF UNIT - V. RUSTY. LOWER CONTACT SHARP @ 70° TO C/A.	1Ho' CA STRINGER & FLOODED ZONE @ 5% PY OVER 2cm.		140						
	140	.4	40	Ø					6850	140.0-143.0	3.0'	0.001	0.01	
	141	.4	40	Ø										
143.0	2 143	10	50	Ø				143.0						
	144	.7	70	Ø					6851	143.0-146.3	3.3'	0.011	0.09	
	145	4	40	Ø										
	4 149	2.5	63	Ø		146.3		146.3						
	2 151	9	45	Ø	GDR. med-c.GR. LT GRN-GRY. LESS SILICIFIED & ALT'D. JUST WEAK TO MOD PROP & CA + SOFT, GREEN, SERICITIZED F-SPARS. GRADES INTO LOWER UNIT OVER ~1 FOOT INTERVAL.	TRACE DISS PY.			6852	146.3-150.0	3.7'	0.003	0.03	
	152	.7	70	Ø				150						
9	153	.6	60	Ø	ANDESITE AS @ 129.4. V.DK GREENISH-BLACK. STRONG PROP. ALT. ABUNDANTCA. . WEAK, HEALED CRACKLE. MINOR EPIDOTE IN BLEBS & FRACT-FILLING. MOST FRACTS N 50-60° TO C/A.	150.0 MINOR DISS PY.			6853	150.0-155.0	5.0'	0.001	0.01	FW CONT. @
	155	.8	40	Ø	GRADD INTO LOWER UNIT OVER ~15 Cm. NO SHARP CONTACT.	156.0		155.0						
	156	.6	60	Ø	RHYOLITE: UFG. WEATHERED RUSTY BROWN-ORANGE LIMONITE ON FRACT. SURFACES. SOME CLAY & MnO2 IN FRACTS & SHEARS. STRONG, HEALED CRACKLE. FRACTS @ 85-90° TO C/A. GROUND CORE @ CONTACT.	MINOR PY IN BANDS & DISS. MINOR SL/GL.			6854	155.0-158.0	3.0'	0.019	0.07	
158	1.3	65	Ø		158.0 BANDS TO 2mm.		158.0	6855 ✱	158.0-159.0	1.0'	0.288	10.76	0.209, 7.71/5.0'	
	159	.7	70	Ø				160	6856 ✱	159.0-160.0	1.0'	0.398	10.37	TOTAL CORE BARREL MUCH LOST
	160	.5	50	Ø	QZ SX BX: WHITE QZ & PY, SL, GL, AS, AM. V. RUSTY & WEATHERED. MUCH CORE LOST. MANY AREAS GROUND TO ROUND PEBBLES. FROM 160-166 VERY POOR RECOVERY - JUST PEBBLES. @ 158.6 1cm WIDE CA VEIN CUTTING CORE @ 65° TO AXIS. LOWER CONTACT: CORE GROUND.	PY, SL, GL, AS, Sb AS MATRIX IN QZ BX. DIFFICULT TO ACCURATELY DETERMINE PERCENTAGES.			6857 ✱	160.0-163.0	3.0'	0.120	5.82	
	3 163	.2	7	Ø					6858 ✱	163.0-165.0	2.0'	0.035	1.17	MUCH CORE SHIPPED MUCH LOST 0.143, 5.39/8'
	3 166	.3	10	Ø		166.0		165	6859 ✱	165.0-166.0 SOLD	1.0'	0.031	1.47	TOTAL CORE SHIPPED.
166								160						
	2 168	1.9	95	47	BRECCIATED, SHEARED, GREENISH TAN RHYOLITE. ABUNDANT CLAY - FAULT GOUGE. QUITE RUSTY & WEATHERED. DIFFICULT TO SEE. MAY HAVE SMALL ZONES OF OTHER LITHOLOGIES. IS DIATREME OR GDR. LOWER CONTACT RUSTY MIXED SHEAR @ 75° TO C/A.	NO VIS. SX.			6860	166.0-170.2	4.2'	0.006	0.32	
	3 171	3.0	100	27		170.2		170						
	173	2	10	Ø	RHYOLITE AS ABOVE, BUT LESS FRACTURED LOWER CONTACT DISTINCT, BROKEN	1-2% M.gr. ? 174.5		170.2	6861	170.2-174.5	1.3'	0.029	3.36	
10	5	3.2	64	Ø	MIXED ZONE OF BROKEN RHY, GDR, FRAGS OF QSXBX MASHED TOGETHER AND POORLY CEMENTED. V. BROKEN UP. RUSTY-WEATHERED. LOWER CONTACT GRADATIONAL BUT CALLED MULTI-LITHOLOGIC BX. NO FRACTS MEASURABLE	1-2% VIS PY, SL, GL MOSTLY IN QSXBX FRAGS			6862	174.5-176.5	5.0'	0.056	2.11	
	178					176.5		174.5						
	179	.6	60	Ø	MORE MULTI-LITHOLOGIC BRECCIA, BUT FEW TO NO CLASTS OF QZSXBX. JUST LARGER (1-3cm) CLASTS OF RHY IN GROUND GDR. V. RUSTY & BROWN VERY NEAR SURFACE. NO CLEAR CONTACT.	1-2% DISS PY			6863	176.5-180.7	4.2'	0.004	0.37	
	5 184	4.3	86	Ø	PROBABLY GRANODIORITE. VERY GROUND UP AND CLAYEY. ORANGE-BROWN AND GREY CLAYS IN V. SHEARED, WEATHERED GDR. ABUNDANT Mn STAINING ON FRACTS. NO DISCERNABLE LOWER CONTACT.	180.8 ± GL+SL. TRACE DISS PY. 184.9		180	6864	180.7-184.7	4.0'	0.001	0.36'	HW CONTACT ↑

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-UG-42 Sheet 3 of 3

BO.I	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERSECT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T Ag	
184.3	5	4.5	90	Ø	MORE COMPETENT, LESS ALTERED, LESS SHEARED, GRANODIORITE	TRACE TO NO			6865	184.7-187.7	3.0'	0.012	2.24	
	189				STILL QUITE FRACTURED, POTHOLOW, & SOME SHEAR ZONES.			187.7						
11	5	9	18	Ø	MAY HAVE SOME RHYOLITE AT TOP BUT APPEARS TO BE STRAIGHT GOR	DISS Py								
194.0	MH				AT BASE. TOO BROKEN TO GET FRACT. ORIENTATIONS. SEDIMENT-MAFIC XENOS			190						
					87-UG-42 End of Hole at 194' V. RUSTY.		E.oH.							FOR (JW SHEAR NEAR E.oH) 194' end of hole

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT Skukum Creek (WH) | HOLE No. 87-16G-43
COORDINATE N. 71,256.8 | DEPTH 136'
E. 77,998.4 | AZIMUTH 164.5
ELEVATION 1301.3 | INCLINATION Flat. 0°
DATE STARTED | DRILLED BY Caron Diamond Drilling
COMPLETED | ASSAYED BY Acme Analytical Labs
HOLE SURVEY | LOGGED BY LR/RJR

True Width Multiplier 0.931

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	ANALYTICAL
1			81	10	C.Gr. Bimodal or Sub-Porphyritic Granodiorite - 2-4mm white plag x'ls in f.gr. qtz/horn blende matrix, fract at 25°, 70°-80°, v.minor ca. in matrix 95' 5" xeno of C. gr. QMZ WK Prop Alt'd Andesite DYKE, f.gr. - aphanitic, dk grey/black 140' G.D.R. as above, xeno of c.gr. QMZ at 110 146' WK Prop Alt'd Andesite DYKE, 45° to core, fract at top of section, v. fractured	- minor bornonite in cracks		0						
19.4								10						
2			99	33	181' Andesite DYKE, black, aphanitic 224' Andesite DYKE, black, aphanitic 247' 2" section of anastomosing veinlets (clinozoisite?) 249' 1" section of clino.? 260' f.gr. section of GDR, poss. magmatic segregation			20						
36.7								30						
3			92	15		- minor cubic py along fract.		40						
58.9								50						
4			95	48	A FEW BLEBS OF CA TO 7mm. EPIDOTE STRINGERS MORE ABUNDANT ↓ DEPTH. A FEW NARROW ZONES SLIGHTLY COARSE-GRAINED. OVERALL V. HARD. MINOR CA FRACT. FILLING. INCREASING SILICIFICATION ↓ DEPTH - STARTING @ 75°. VERY FEW FRACTURES, MOST @ 75° TO C/A Scale change 1" = 10'	Scale change		60						
73.5								70						Scale change
	4 76	4	100	45	SLIGHT FIZZ ON ALL CORE = CA VEIN OR OVERPRINT. XTAL STRUCTURE GHOSTED - PROBABLY SLIGHT SILICIFIED ∴ HARD. @ 76.0 @ 77.5' ARE 2, 5cm WIDE VEINS. ⅓ @ 5mm WIDE CA LINING WITH WHITE QZ CENTERS. @ 5-7% C.G SX XTALS IN QZ. VEINS CUT CORE @ 20-25° TO C/A.	1% BS 3-4% PY IN XTALS TO 1 cm. 2-3% SL ABD IN LARGE XTALS.		75.6						
5	6 84	5.5	95	7	MORE BROKEN UP AND FRACTURED ↓ DEPTH SEVERAL QZ. CA & CLAY-FILLED SHEARS. FRACTS COATED ↓ LIMONITE. YELLOW-ORANGE.			77.9	6866			0.033	0.22	
	4 88	2.9	73	Ø	FRACTS & SHEARS @ 40 & 60° TO C/A CA-FILLED CRACKLE MORE INTENSE ↓ DEPTH			80						
91.0	6 94	4.8	80	27	LOWER CONTACT MISSING - LOST BY DRILLERS AS ABOVE BUT MORE STRONGLY ALTERED. SOFTER, MED. GRN-GRY. V. INDISTINCT XTAL STRUCTURE. V. GHOSTY. DRAWER = HARDER ↓ DEPTH & UNTIL AT BASE, IT IS THE SAME AS THE ROCK ABOVE. STILL CALCITIC & MANY FRACTS @ 40 & 65°	91.6		90						

OMNI RESOURCES INC. · PROJECT Skukum Creek (WH) DIAMOND DRILL HOLE No. 87-UG-43 Sheet 2 of 2

b/x	Run	Core	%R	RQD
6	4 98	3.7	93	11
	5 107	5.0	100	42
	5 108	4.9	98	Ø
109.7	4 112	4	100	13
	113	9	90	66
7	5 118	3.7	74	Ø
	3 121	1.7	67	Ø
	123.5	2.9	100+	Ø
126.9	4.5 128	3.9	87	Ø
8	5 133	4.3	86	21
136	3 136	2.6	87	15

LITHOLOGY, ALTERATION, STRUCTURE

MOD TO STRONG PROP ALTN LAST 15 cm BEARS CONTACT. CNT. BROKEN-UP.
F.G. SHEAR Zone. V RUSTY SHEAR, NONFOLIATED, & SHEAR PARALLEL QZ VEINS @ 28° TO C/A. SHEAR ALSO @ 75° TO C/A THE LATTER SHEAR- SURFACE BROKEN.
CRUSHED CNT, GHOSTED, F.G. GDR & NUMEROUS QZ-CA VEINS TO 3 cm RUNNING ~20° TO C/A. VEINS MIXED. WEAK CRACKLE. CA-HEALED. RUSTY FRACTS @ ~40° TO C/A.
MOD. LT-GRN GRY. LOWER CONTACT SHARP FRACTURE @ 45° TO C/A
PROBABLY FG. GDR. STRONG PROP. ALT'N. V. ABUNDANT SERICITE, CL, EP.
MED. GRN-GRY. QUITE SOFT. SOME CLAY ON FRACTS. MOST FRACTS RUSTY ORANGE-BROWN. FRACTS 20 & 60° TO C/A. MOD. CA-HEALED CRACKLE.
ONE 5mm QZ VEIN SUB-PARALLEL TO C/A. MINOR PY/GL. INCREASING CA & DEPTH.
LAST 15 cm V. CALCITIC & BRECCIATED. LOWER CONTACT SHARP, SHEAR.
BRECCIA. GDR MATRIX - V. SHEARED ; CLASTS OF LT GRN-TAN RHY & MINERALIZED QZ SX-BX. LOWER CNT. SHARP, BROKEN.
FIRST 17 cm SHEARED RHY, THEN STRONG PROP. ALT. FG GDR. SOFT. CRACKLED (MOD) ABUNDANT CL, SER, EP, XTAL CHLORITE MASS BUT BEDDED. 60° CNT BROKEN UP
LT TAN TO LT. GREENISH-TAN RHY. BRECCIATED VARIOUSLY FROM WEAK CRACKLE TO STRONG. MATRIX SUPPORT. MATRIX IS DK GRY TO BLACK, CONTAINS GROUND UP SX, AND STRONGLY RESEMBLES MATRIX FROM DIATREME. CRACKLE FOR 90 cm. THEN BX FOR 20 cm. THEN REMAINDER JUST CRACKLED. LOWER CONT. SHARP SHEAR @ 60° TO C/A.
15 cm DIATREME BRECCIA, THEN QZ SX BX & MINOR CRUSHED GDR
STUNG PIECES OF QZ. FRAGS OF QZ FROM 1mm TO 8 cm.
22 cm DIATREME BX & FRAGS OF QZ-CRYSTAL RHY-GDR. V. SHEARED. MUCH CLAY.
33 cm STRONGLY-SHEARED GDR & CA & CLAY CEMENT.
22 cm CRUSHED QZ SX BX IN BLACK MATRIX. LOWER CONT. SHARP SHEAR 75°
MOD-STRONG PROP. ALT'D. M-F.G GDR. SOFT AT TOP, BECOMING HARDER & DEPTH. A FEW LIMONITE-COATED FRACTS, & SOME & CA.
MOST FRACTS @ 45 or 90° TO C/A. MOD. CRACKLE HEALED & CA @ TOP, WEAKENING & DEPTH

87-UG-43 End of Hole at 136'

MINERALIZATION

1% DISS PY minor SL, AS.
98.0 minor PY STRINGERS
3-4% SL, 2-3% PY, minor AS, GL in QZ VNS.
TRACE DISS VFG PY.
PY + GL IN NARROW QZ VEIN.
15-20% BX QZ IN RECK OVERALL <5% COMB.
TRACE DISS PY. GOOD
2-3% COMBINED SX. MOSTLY DISS PY. SOME SL/GL IN MATRIX OF BX
3% PY 2-3% SL/GL/AS
22 cm 3% PY 3% SL/GL
33 cm TR DISS SX
TRACE TO 1% DISS. PY.
end of hole

GRAPHIC LOG

FT.

100 · 110 · 120 · 130

SAMPLE

Sample No.	INTERVAL	CORE LENGTH
6867	96.3 - 100.0	3.7
6868	100.0 - 101.3	1.3
6869	101.3 - 106.0	4.7
6870	106.0 - 108.4	2.4
6872 *	108.8 - 110.9	2.1'
6873	1109 - 113.2	2.3'
6874	113.2 - 118.0	4.8'
6875	118.0 - 120.3	2.3'
6876 *	120.3 - 123.1	2.8'
6877 *	123.1 - 124.0	0.9'
6878	124.0 - 125.1	1.1'
[illegible]	125.1 - 125.9	0.8'
6880	125.9 - 130.0	4.1'

ANALYTICAL

O.P.T. Au	O.P.T. Ag
0.014	0.85
0.007	0.87
0.001	0.05
0.001	0.15
0.159	0.14
0.001	0.23
0.031	0.44
0.001	0.08
0.218	24.19
0.048	1.92
0.036	0.65
0.099	3.65
0.001	0.06

FW SHEAR

.006, 0.40 / 5.69

6871 0.036Au 1.86Ag

0.014, 0.30 / 9.7

0.138, 13.05 / 5.6'

HW SHEAR 125.9

end of hole at 136'

True Width Multiplier 0.9356

.2868

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT	Skukum Creek (Wh)	HOLE No.	87-UG-44
COORDINATE N.	71160.4	DEPTH	208'
E.	77,988.7	AZIMUTH	1.2°
ELEVATION	1301.9	INCLINATION	FLAT 1.8°
DATE STARTED		DRILLED BY	Caron Diamond Drilling
COMPLETED		ASSAYED BY	Acme Analytical
HOLE SURVEY		LOGGED BY	

TRUE WIDTH MULTIPLIER 0.7964

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: G.P.T. Au	ANALYTICAL: G.P.T. Ag
1			93	27	C. Gr. Propylitic Alt'd Granodiorite - lt gry colour, V. Wk mauve/pink tint, qtz & f-spar x'ls ≤ 5mm often w/ ghosted outline due to pervasive ~~silication~~ silicication, minor calcite in fractures, matics ≤ 15 avg but patches of 30-40%, matics → chl., some blebs of str. altn of plag → ser., general weak prop. altn fractures at 30, 45 & 80°			0					
19.3								10					
2			100	32				20					
38.0								30					
3			92	36				40					
56.0					51.1' gradational lower contact			45					
4			92	48	Propylitic Alt'd Granodiorite - similar to above unit but plag more strongly alt'd to calcite and ser., general lt grn tint, V. minor dissem py, matics ~~to~~ completely → chl., epidote on fractures intense prop. to phyllic altn at 54.5' fractures at 45, 70 & 80° 58.7 – 62.9 increase in matics to ≥ 40% of total, complete chl altn	minor dissem. cubic pyrite		50					
75.1								60					
5			95	18				70					
92.5					97.6'			80					
6			100	17	C. Gr. Propylitic Alt'd Granodiorite similar to section from 0-51.1', but w/ some bi-modal plag sub-porphyritic sections, mag' segreg'n (?)			90					
					102.5'			100					
					104.9' Strong Prop. Alt'd Andesite Dyke, dk gry grn, V. strong ~~ri~~ py, ca in matrix & fract			110					
110.2								120					
7			97	28	C. Gr. Prop Alt'd GDR as above								

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-46-44 Sheet 2 of 3

BOX	Run	Core	%R	RQD
128.0				
8			92	25
146.5	146.5			
	5	5	100	38
	151.5			
	5	5	100	80
9	156.5			
	5	4.7	94	21
	162			
	4	3.5	88	Ø
165.2	166			
	2	1.8	90	Ø
	168			
	2.5	2.2	88	Ø
	170.5			
	172	1.2	80	Ø
10	174	1.7	85	Ø
	2.5			
	176.3	2.2	88	32
		6.5	100	42
	183			
183.5	5	5	100	8
	188			
	5	5	100	8
11	193			
	5	5	100	28
	198			
	5	5	100	20
201.8	203			
12				

LITHOLOGY, ALTERATION, STRUCTURE

122.0 6" strongly prop Altd Andesite dyke

- C.Gr. GDR but mafic content & silicif silicification increasing altn slightly stronger & ca. now in blebs & stringers appears finer grained, possibly due to silicn

Scale change 1" = 10'

MODERATE TO STRONG CRACKLE - HEALED BY CA STRINGERS.
~1% CA IN STRINGERS & BLEBS.
DARK & LIGHT GREY & GREENISH TINTED C.G. GDR. MAFICS => CHLORITE.
F.SPARS HARD, WHITE. MINOR CL & EP STRINGERS FRACT. FILLING.
LOWER CONTACT IS AT INTERSECTION OF STRONGLY RUSTY-WEATHERED SHEAR (PARALLEL TO VA, AND CRUMBLY FOOTWALL SHEAR ZONE (RECLINED) 40° TO C/A.

FW SHEAR ZONE. CRUMBLY, BLACK MATRIX, BRKD C.GR FOLIATED 40° TO C/A. MATRIX LOOKS LIKE GROUND SX & RB. MAY BE CLASTS OF BLEACHED WHITE RHY. ALSO.
LOWER CONTACT CRUMBLED & BROKEN.
BRECCIATED GRN-TAN RHY & QZSXBX MATRIX. CLAST SUPPORT. BASE CONT. 30°
GRN-TAN RHY, WEAK TO MOD. CRACKLE. V. HARD. BASE CONT. SHARP 20° TO C/A
QZ SXBX. 25-30% SX. FG QZ XTALS. SHARP LOWER CONTACT
RHYOLITE BRECCIA. (GREEN-TAN GY) HARD. RANGING FROM MOD. CRACKLE TO MATRIX SUPPORTED BRECCIA. MATRIX IS QSXBX AS ABOVE.
LOCAL ZONES TO 5cm OF QZ SXBX, WITH ZONES TO 45 cm OF RHY & LITE CRACKLE. SOME RUSTY-WEATHERED SURFACES. CRUMBLY CLAY - SHEAR FOR 8cm @ 174.4, TOO BROKEN TO MEASURE FRACTURE ORIENTATION.
LOWER CONTACT BRECCIATED. N2Cm WIDE.
QZ SX BX 25-30 % SX. QZ & F.G. (4.5 mm) LOWER CONT. BRKN OVER 10 cm.
BRIGHT LIMEY APPLE GREEN ALT'D M-C.G GDR. BASE CONT. SHARP @ 70°
DARK GREENISH-GREY VF-M.G PORPH. GRANODIORITE. ZONES APHANITIC TO 3 mm XTALS. 3 FRACTURE SETS. MOST COMMON 60-65° MORE THAN ½ Q 60-65°. REMAINDER EQUALLY DIVIDED BTWN. 40-45 & 75-80 TO C/A. MANY FRACTS HEALED WITH CA OR EPIDOTE. A FEW CA OR & EPIDOTE STRINGERS TO 3cm WIDE - MOSTLY FRACT-FILLING.
A FEW BLEBS OF CA & / OR EP.
WEAK PROP. ALT'D, QUITE SOFT. WHERE MAFICS CHANGE TO CHLORITE, ALT'D TO CHLORITE. F.SPARS STILL HARD, WHITE.
XTAL. SIZE INCREASES AND INTENSITY OF ALTERATION DECREASES & DEPTH. XTAL STRUCTURE LESS WASHED OUT - MORE DISTINCT & DEPTH. CA CONTENT DECREASES, EPIDOTE MORE OR LESS CONSTANT. & DEPTH
WEAK CRACKLE DECREASING & DEPTH.

MINERALIZATION

1" = 10'

TRACE VFG DISS PY.

161.0
GROUND SX (BLACK) IN MATRIX OF BX.
164.4 @ PROBABLY <5% OVERALL
WEAK VF.FG BLACK SX IN MATRIX
NIL TO VIS SX
~30% TOTAL SX BY SX/CL/AS
167.6
N3-5% TOTAL SX AS MATRIX OF BX. MOSTLY PY, THEN AS, SL, CL DECREASING.
176.0
176.4 25-30 % TOTAL SX
TRACE DISS PY. VFG.
179.9
BARE TRACE TO NO VIS. SX. V.V.FG. PY.

GRAPHIC LOG



FT.

120, 130, 140, 150, 160, 161.0, 165, 167, 170, 172.0, 176, 177, 177.9, 180, 182.5, 190, 200

SAMPLE

Sample No.	Interval	Core Length
6910	157.0 - 161.0	
6911	161.0 - 164.4	3.4
6912 *	164.4 - 166.1	1.3
6913	166.9 - 166.6	0.9
6914 *	166.6 - 167.6	1.0
6915	167.6 - 172.0	4.4
6916	172.0 - 176.0	4.0
6917 *	176.0 - 176.9	0.9
6918	176.9 - 177.9	1.0
6919	177.9 - 182.5	4.6

ANALYTICAL

Sample No.	O.P.T. Au	O.P.T. Ag
6910	0.001	0.08
6911	0.012	0.55
6912 *	0.282	1.95
6913	0.001	0.49
6914 *	0.416	17.87
6915	0.018	0.85
6916	0.019	0.93
6917 *	0.070	1.93
6918	0.012	1.16
6919	0.001	0.02

1" = 10'

161.0 FW SHEAR

0.125, 3.41/6.6'

0.245, 6.46/3.2'

(0.022; 1.00 / 10.3

176.9 HW CONTACT

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-UG-44 Sheet 3 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.R.T Ag	
208	5 208	5	100	68	87-UG-44 End of Hole at 208'	end of hole	E.o.H.							end of hole at 208'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	Skukum Creek (Wh)
COORDINATE N.	71,159.8
E.	77,988.8
ELEVATION	1300.6
DATE STARTED	
COMPLETED	
HOLE SURVEY	✓
HOLE No.	87-UG-45
DEPTH	208
AZIMUTH	6.6
INCLINATION	-28.6
DRILLED BY	Caron Diamond Drilling
ASSAYED BY	Acme Analytical Labs
LOGGED BY	RJR/LR

Reason for Drilling

Explanation of Results

LEGEND

T.W Multiplier 0.6955

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T Ag
1			100	.85	Coarse Grained Propylitic Altered Quartz Monzonite - plag & qtz x'ls ≤ 4 mm, kspar to 2mm, mafics ≅ 10% ↓ zones of 30-40%, general lt. pink-gry colour sometimes ↓ green tint from chloritized mafics, wk rxn of f-spars & minor ca. in matrix & cracks, general wk to mod propylitic alteration fractures at 30, 45 & 80° to C/A V. minor << .5mm py & cal on fractures	v. minor << .5mm py on fractures		0					
17.8								10					
2			91	.21				20					
37.1								30					
3			99	.22	49.5' 5" section of f.gr. & mafic ~~dyke~~ rich			40					
53.9								50					
4			98	.08	— 58' general increase of alt'n, plag becoming green to cream coloured, minor epi in fractures	≤ 1mm cubic py trace dissem.		60					
71.1								70					
5			92	.09				80					
88.9					— 91.0 anastomosing green veinlets, clinozoisite(?)			90					
6			100	.46	100.1' Propylitic Altered Andesite Dyke, f.gr. to aphanitic, general med gry. coloured, strong rxn ↓ acid & Ca. in stgs & veinlets 106.4' strong prop alt'n 106.2 - 106.0 ↓ cubic py	≤ 2% cubic py in .8' alt'n section	22° 30° 50° 60°	100					
107.1								110					
7			99	.19	— 108.0 1' strongly prop altrd And. dyke, small sheared on lwr cnt & abundant ca. C. gr. QMZ as above, but increasing mafics & chl.			120					
115.5					Prop Altrd Andesite Dyke, v. fractrd core								

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-UG-45 Sheet 2 of 2

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION
124.5					122.0' Mod Prop Altd Andesite DykE, med gry clr ca in matrix stgs & veins 127.0'	
8			97	.14	- C.gr. QMz, altn, slightly stronger	- trace dissem py
143.0					- silic'n increasing	
9			99	.14	scale change 1" = 10'	
					BLACK ANDESITE DYKE From 152.8-153.8' APHANITIC & V. SMALL HB PHENOS. W. CALCITE.	NO VIS. PY
160.7	5 163.0	5	100	.08	F-SPARS GREENER & SOFTER ALTERATION INCREASING WITH DEPTH. FRACTURES GENERALLY 50-55° & N 20° TO C/A	
	5 168	5.5	100	Ø	167.4-167.7 - ANDESITE DYKE AS ABOVE.	
10	5 173	4.8	96	.33	MAFICS COMPLETELY ALT'D TO CHLORITE, MORE CALCITE IN BLEBS & STRINGERS. HEALING CRACKLE.	TRACE DISS PY & FEW SMALL BLEBS.
177.5	5 178	4.8	96	.10	GDR SLIGHTLY FINER-GRAINED. w 2-3mm XTALS. & DARKER. SOME CA STRINGERS CONTAIN REDDISH HEMATITE. @ 176.6 IS A 1cm BLEB OF PY.	TRACE TO MINOR DISS PY OVERALL.
	5 183	4.8	96	Ø	SOME GREENISH QZ WITH CA STRINGERS & VEINLETS. XTAL STRUCTURE MORE WASHED-OUT & INDISTINCT NEARER ZONE. FRACTURE SURFACES WEATHERED ORANGE BROWN RUSTY.	MORE P/T DEPTH
185.5	187	2.0 / 1.5	80 / 100	Ø / Ø	CORE MORE FRACTURED & BROKEN UP & DEPTH.	
	188	1.0	100	Ø	MOD. LINEAR ZONE, ALMOST/NEARLY HEALED GOUGE CRUSHED GDR TURNED GRN-TAN RUS. BANDED @ 5x2 TO C/A. V. CLAYEY. SOME BRECCIA W. RUSTY YELLOW-ORANGE STAINED. LINEAR CUT SHARP BREAK 57° TO C/A	188.0 TRACE TO MINOR PY, DISS & BLEBS.
	190	1.3	65	Ø	HARD, VFG GRNY-TAN RHY. WITH CHLORITE & PCK WEATHERING. V. RUSTY, ORANGE-BRN WEATHERED PARTS. BAND CUT SHARP BREAK @ 55° TO C/A.	188.8 NO VIS SX
	192	1.8	90	Ø	CRUMBLED, SUGARED MINERALIZED ZONE. V. SOFT & GOUGY. ABUNDANT CLAY. SOME RUSTY ZONES. TO BROKEN UP TO GOUGE ABUNDANT. SOME CUT. SHARP, SHEARED @ 55° TO C/A	V.V. FG GREY & MOD 5% PY. ? = MoS2? 192.0
194.6	195	3.2	100	.28	DARK GREENISH-GREY STRONGLY PROP. ALT'D C-C. GDR. MOD. CRACKLE, HEALED & CA. & GRN-GRY QZ. MOD ROTATION.	TRACE TO NO VIS PY.
	198	2.5	83	.36	FRACTS RUSTY ON SURFACES, ORIENTED N 65° TO C/A.	
12	5 203	4.4	88	.09	XTAL STRUCTURE V. GHOSTED & INDISTINCT AT TOP, BECOMING MORE DISTINCT & LESS ALTERED AT DEPTH. QUITE SOFT.	
208	5 208	4.3	86	.39	87-UG-45 End of Hole at 208'	

SAMPLE				ANALYTICAL		
Sample No.	INTERCEPT	CORE LENGTH	O.P.T. Au	O.P.T. Ag	
6920	182.0-187.0	5.0'	0.001	0.06	187.0 ↓ HW.
6921	187.0-188.5	1.5'	0.001	0.26	
6922	188.5-192.0	3.5'	0.012	0.48	192.0 ↑ F.W
6923	192.0-194.6	2.6'	0.001	0.09	
					End of hole at 208'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	Skukum Creek (Wh)
COORDINATE N.	71,159.8
E.	77,988.8
ELEVATION	1300.6
DATE STARTED	
COMPLETED	
HOLE SURVEY	
HOLE No.	87-UG-46
DEPTH	294'
AZIMUTH	8.0
INCLINATION	-54
DRILLED BY	Caron Diamond Drilling
ASSAYED BY	Acme Analytical Labs
LOGGED BY	R.J.R.

Reason for Drilling: To test mineralization in Rowena Zone at 1250 level 30 m East of E-cut #1

Explanation of Results: Hit well-mineralized zone.

LEGEND

T.W Multiplier = 0.5261

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
1			94	.20	Coarse Grained Propylitic Altered Granodiorite plag & qtz x'ls 2-5mm w/ obscured nearly amorphous crystal form, matics avg 15% w/ zones of 30-40%, matics completely chl altr'd general lt gry colour w/ grn tint f-spars soft & react w/ acid fractures at 30, 40 & 70° general mod. propylitic alteration			0					
17.0								10					
2			98	.34				20					
35.3								30					
3			100	.47				40					
53.1								50					
4			97	.09				60					
70.6								70					
5			95	.49	—BLS: strong prop altr'n w/ minor ser. & epi. for 16'			80					
89.0								90					
6			100	.41				100					
106.9								110					
7			96	.27				120					

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-UG-46 Sheet 2 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag	
8			93	.25	– 131.7' 4" propaltd And. dyke			120						
142.1					– 144' 3" prop altrd And dyke			130						
9			96	.17	– 150' 8" prop altrd And dyke – 152' 10" propaltrd And dyke – 156' 4' prop altrd And dyke			140						
159.0								150						
10			99	.19	- alteration of GDR increasing, more ca. in Stgs & veinlets			160						
176.9								170						
11			90	.32	MOST FRACTS @ 40, 85+65° TO C/A.			180						
195.1					MINOR CALCITE ALTERATION. A FEW VEINLETS & FRACT-FILLING.			190						
12					INCREASING AMOUNTS OF HEMATITE WITH DEPTH IN BLEBS & FRACT-FILLING.	TRACE PY, MINOR HEMATITE		200						
					CRACKLE INTENSITY INCREASES W DEPTH.									
					205-206 - WEAK [redacted] POTASSIC ALT'N. BRIGHT RED STAINING ON FSMRS.									
					Scale change 1" = 10'			210						scale change
212.5	6 214	6	100	.27										
13	5 219	4.8	96	.22	U-BROKEN UP & FRACTURED FROM 215-217. ABUNDANT HEMATITE STAINING ON FRACTS.									
	2 221	3.2	160	Ø	MORE BROKEN UP WITH INCREASING DEPTH.			220						
	5 226	4.5	90	Ø	226-227. BAND OF FINER-GRAINED MATERIAL. NO CONTACTS, MUST BE MERELY MAGMATIC SEGREGATED ZONE.									
227.5	227	.8	80	Ø	ALTERATION INTENSITY INCREASING SLIGHTLY W DEPTH.	TRACE DISS PY. (U/FG)								
14	5 232	4.7	94	.16				230						
	234	1.9	95	.18				231.6						
	5 239	4.4	88	Ø	LOWER CONTACT SHEARED @ 50° TO C/A.	235.9			6924	231.5-235.9	4.4'	0.001	0.04	
					HW SHEAR ZONE: CLAYEY, CRUMBLED LT. GREENISH-TANNISH-GREY. GDR. APPEARS TO BE INCLINED @ 50° TO C/A. WAS PARTIALLY CA-CEMENTED, BUT W. CRUMBLED BY DRILLING.	MINOR - TRACE TO NO VIS SV		235.9						HW SHEAR 235.9'
					LOWER CONTACT SHEARED, ADVD @ 50° TO C/A.	239.3		240	6925	235.9-239.3	3.4'	0.002	0.04	

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-UG-46 Sheet 3 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	INTERCEPT	CORE LENGTH	ANALYTICAL O.P.T. Au	O.P.T. Ag	
	5 244	4.7	94	.55	QUARTZ-SERICITE BRECCIA IN ALTERED UP GDR. MOTTLED LT + DARK GREY, CLASTS ANITE SMALL, MOST < 5mm. SX MATRIX UFG GROUND BLACK MATERIAL - PERHAPS SPHALERITE. LOWER CONTACT @ 45° TO C/A. SHARP ASSOCIATED	1.5-2% TOTAL SX. MOSTLY PY + SPH? BLACK UFG MATERIAL PY?		240						
245.4	5 249	4.8	96	.52	5% CHLORITE ALT'D C.A. GDR - CLOSELY SHEARED AND BRECCIATED. LIME GREEN - THEN BACK TO BLACK, FG. QZ SX BRECCIATED GDR. MOSTLY QZSXBX. WITH JUST A FEW GRAINS OF QZ, FELDSPAR & HORNBLENDE FROM GDR. A FEW LARGER CLASTS OF PHYLLIC ALT'D GDR TO 3CM.	DIFFICULT TO DETERMINE DUE TO VERY FINE XTAL SIZE OF SX.		245	6927 *	240.7 - 243.3	2.6'	0.158	3.89	.52 .03	.10 .05
15	5 254	4.7	94	.07	QZ CLASTS IN QZSXBX ROUNDED TO SUB-ROUNDED. A FEW YELLOW QZ CLASTS IN ADDITION TO NORMAL, WHITE TO BLUE-WHITE QZ. MOD MOST COMMON FRACT. ORIENTATION = 50° TO C/A	5-10% PY, 1-2% UIS GL		250	6929 *	244.0 - 248.5	4.5'	0.066	2.15	.20	.22
	4.5 258.5	4.4	98	.20	MORE SHEARED, ALT'D, BWD GDR & DEPTH. LOWER CONTACT SHEARED @ 50° TO C/A.				6930 *	248.5 - 253.4	4.9'	0.102	2.18	.31	.41
263.7	5.5 264	5.5	100	.62	DIATREME BRECCIA. CLASTS OF PHYLLIC ALT'D GDR AND QZSXBX TO 50mm IN COARSE, APHANITIC DARK GREEN GROUNDMASS MATRIX. BWD 50° DARK GREEN, STRONGLY CHLORITE, SERICITE + EPIDOTE ALTERED FG GDR OR ANDESITE. MODERATE HEALED CRACKLE WITH PREDOMINANT FRACTURE ORIENTATION N 40° TO C/A. MINOR CA STRINGERS. LOWER CONT. SHARP, @ 50° TO C/A	OVERALL <5% TOTAL SX. 35-40% SX IN QTSX BX CLASTS		260	6931 *	253.4 - 258.3	4.9'	0.120	11.14	1.38	0.93
	5 269	5.1	100	.33	COARSE GRAINED LIGHT GREY GRANODIORITE. WEAK BANDING @ 60° TO C/A. FRACTS @ 50-55-60° TO C/A. HEALED CRACKLE BRECCIA-FILLED + GREY QUARTZ. FRACTS TO 1mm WIDE WITH NO ROTATION. SHARP DYKE (INTRUSIVE) CONTACT @ 35° TO C/A.	NO UIS SX.			6933 *	258.8 - 260.9	1.9'	0.250	11.32	2.32	1.40
16	5 274	5	100	.58	COARSE APHANITIC ANDESITE DYKE. DARK GREENISH, @ BROWNISH BLACK ABUNDANT EPIDOTE ? CHLORITE STRINGERS. WEAK, CHLORITE-HEALED @ CRACKLE TEXTURE. ALL FRACTURES @ 85-90° TO C/A - MAY BE DRILL INDUCED. LOWER CONTACT SHARP (INTRUSIVE) @ 50° TO C/A.	NO UIS SX.			6934	260.6 - 264.0	3.4'	.006	.14		
	5 279	5	100	.18	COARSE-GRAINED LIGHT GREY MOD PROP. ALTERED GDR AS @ 264 ABOVE. FRACTS @ 45°. INCREASING EPIDOTIZATION + DEPTH. LOWER CONTACT GRADATIONAL. GRAIN SIZE DECREASE + DEPTH + FSPARS DISAPPEAR.	TRACE U.F.G. DISS PY.			6935	264.0 - 268.9	4.9'	.001	0.02	0.002, 20%	4.18
283.3	5 284	4.7	94	.83	PROBABLY SAME UNIT AS ABOVE BUT SLIGHTLY FINER GRAIN SIZE. DARK GREENISH GREY DUE TO STRONG CHLORITE/SERICITE OVERPRINT - NO VISIBLE FELDSPARS OR MAFICS. ONLY GHOSTY REMNANT QZ XTALS. ABUNDANT EPIDOTE STRINGERS + VEINLETS. MOD. ABUNDANT CA. ALTERATION DECREASES + DEPTH TO END OF HOLE. FRACTS @ 50° TO C/A.			270	6936	268.9 - 274.3	5.4'	0.001	0.01		
17	5 289	4.8	96	.79		TRACE U.F.G. DISS PY.								
294	5 294	4.4	88	.34	AT END IS LIGHTER GREEN + VISIBLE HB + FSPAR XTALS. 87-UG-46 End of Hole at 294'	end of hole	E.O.H.	290						end of hole at 294'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT Skukum Creek (WN) | HOLE No. 87-UG-47
COORDINATE N. 71,158.8 | DEPTH 424'
E. 77,989.2 | AZIMUTH 010
ELEVATION 1300.5 | INCLINATION -67.7
DATE STARTED | DRILLED BY Caron Diamond Drilling
COMPLETED | ASSAYED BY Acme Analytical Labs
HOLE SURVEY | LOGGED BY V. Thornsberry

True Width Mult. ~.3243

BOX	Run	Core	%R	R.Q.D.
1			99	.15
18.4				
2			99	.07
34.7				
3			89	.03
52.0				
4			98	.22
70.9				
5			96	.29
87.0				
6			93	.36
105.1				
7			100	.33

LITHOLOGY, ALTERATION, STRUCTURE

C.Gr. Propylitic Altered Quartz Monzonite

f-spar & K-spar to 70% of total rock, 15-20% qtz, 10-15% mafics
lt pink-grey colour, ~~occasional~~ occasional green or ~~pink~~ stronger pink due to chlor potassic altn
- X'ls 3-5 mm up good to nearly amorphous form, mafics v. blurred in outline
fractures at 30, 60 & 80°
- ~~no~~ wk to mod. propylitic altn

46.4' sharp cnt
Sub-Porphyritic Granodiorite
50% 2-3 mm plag x'ls in matrix of ~~dk~~ mafics, mafics → chl, dk grn grey colour, ~~mafics white~~ plag white & reacts w/acid
35% fracts at 30, 45° & 80°, moderately fract'd core

Strongly Prop Altrd C.Gr. Quartz Monzonite

lt apple grn colour, overprint on pink grey, strong sericite & epi altn of plag, ca. in matrix & hairline stgs.
- 68'-69' chloritized mafics > 50% of rock
- unit same as for 0-46.4' from 69.0', but propaltn slightly stronger

- wk pervasive silic'n

- from 112 to 121.6 increasing percentage of mafics

MINERALIZATION

GRAPHIC LOG

60°
80°

FT.

0, 10, 20, 30, 40, 50, 60, 70, 80, 90, 100, 110, 120

SAMPLE			ANALYTICAL	
Sample No.	INTERCEPT	CORE LENGTH	O.P.T. Au	O.P.T. Ag

OMNI RESOURCES INC. | PROJECT Skukum Creek (Wh) | DIAMOND DRILL HOLE No. 87-46-97B Sheet 2 of 4

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
123.1					123.6 sharp cont Strongly Prop Altrd Andesite Dyke dk grn-gry colour, aphanitic, soft 125.4 sharp cont ca. in matrix & wavy stgs			120					
8			97	.28	- C. Gr. prop altrd QMZ, wk pervasive ~~silicific~~ silic'n			130					
140.6								140					
9			95	.26				150					
159.0					- wk potassic altn 155-159'			160					
10			96	.44	167.0 Shear at 60° to CA, 13' section of strong prop & argillic altn, core v. broken up 168.3		65°	170					
176.9								180					
11			99	.50				190					
194.9								200					
12			98	.12	- stronger prop altn, v. strong rx'n w acid and .5mm dissem. cubic py	trace dissem cubic py		210					
211.9					213.2'		65°						
13			98	.24	Plag-Porphyry Andesite Dyke 8 10% 2-4 mm plag phenots, minor qtz v'ls in aphanitic med grn-gry matrix plag & matrix reacts w acid, ca. in stgs 221.4' sharp cont fractures at 30, 50 & 70°		60°	220					
227.0					Shear Breccia, rotated clasts of And. dyke in black shear matrix 224.0 sharp cont & minor fine crushed py Prop Altrd Andesite Dyke, mod to strongly altrd, med. grn gry And. dyke 224.4' matrix reacts w acid, ca. & epi. in stgs	v fine crushed py	?	230					
14			100	.16	c. gr. prop altrd QMZ, slight increase in mafic percent.			240					
254.0					249-259' mis-numbered and this 10' of core does not exist			250					
15			94	.28	- 262.8' 6" prop altrd And. dyke minor potassic altn			260					
								270					

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-46-47R Sheet 3 of 4

BOX	Run	Core	% R	RQD
274.2				
16			99	.31
290.7				
17			95	.30
18				
324.2				
	5	5	100	.52
19	334			
	5	5	100	.54
	339			
	3	3	100	.12
342.4	342			
	5	5	100	.23
	347			
	5	5	100	.40
20	352			
	5	4.8	96	.50
	357			
	2	2.0	100	.38
360.8	359			
	5	5	100	.58
	364			
	5	5	100	.64
21	369			
	5	5	100	.68
	374			

LITHOLOGY, ALTERATION, STRUCTURE

- matic percentage increasing to ≅ 20 or 25%, matics + chl. wk pervasive silicn

306.4' 5" shear strong argillic alt'n & shear gouge

matics ≅ 25%, altd to chl. and have a "swirly" texture ca. in stgs & small veinlets

Scale change 1" = 10'

333.6 SHP INT CNT @ 18° 6" Fg-sect Rhyolite Dike
N.W. RAINBOW ZONE @ 15-20° TO CORE

[Alt. GRANODIORITE BX w/ Bx clasts of Bx clasts of RHYOLITE]
335.6-378.5 ZONE OF INTENSE Bx. w/ 20° Lineation of QTZ, Pyrite

337.5
N.W. SHEAR ZONE in GRANODIORITE Bx 337.5-339 & 341-342
w/ wedge of GRANODIORITE Bx between Shears

342
GRANODIORITE Bx. Rehealed & cracked 3 stage Bx
Qtz-Calcite last stage.

346
RHYOLITE Bx contains dismembered dikes CNT SHP @ 60°
348 SHEARED ON N.W.

GRANODIORITE Bx

351.1 SHP 60° CNT
Brown-d. grey Aph. felsic RHYOLITE probably a large Bx Frag.
Sharp CNT Brecciated - subrounded-subangular ± cm. Rhyolite Bx
343.7 CNT Bx QTZ-CCTE vits as clasts in Bx

GRANODIORITE Bx w/ most Stockwork Frags (LIKE)
Bx filling stg-1 & 2 dark grey smkish mineral, most of Qtz-Calcite Cracks Bx filling and/or Selective Replacement Bx

360.2 Subhorizontal CNT
Mixed RHYOLITE & GRANODIORITE Bx
70% RHYOLITE @ 30% GRANODIORITE, clasts range from several inches to 1 cm. Bx stage Bx leaf-ex Qtz-Calcite cracks Bx
364.0 minor 2" Qtz-Calc vein Bx

GRANODIORITE Bx
Cracked & Rehealed Frags w/ late stage in-filling of Qtz-Calcite-Sulfides & minor chl ± EP in fill
Mod Sericite altered mafics

371.1 REHEALED SHEAR ZONE @ 20° in GRANODIORITE Bx

374 SHP CNT @ 20°
375 1' MOLY MICTIC Bx

MINERALIZATION

Scale change

333.6

SMA Py as disseminations (1) TR. 324

347.6

1-5% ground subhedral in Cracks & Bx

± 2% diss Py

2-5% subhedral ground in cracks

± 2% diss Py

6"-4 in wk % diss Py

2-5% Disseminated Py

MINOR Py, TR Cpy, TR Sph

± 1% fn diss Py

353.7-374.8

± 3% diss Py

occ hairline veins of Py w/ Qtz/Calcite filling

371.1-374
soft fg ground in cracks
± 5% Py

1" 65-70 Mtl, Mod ± 60 Fe

GRAPHIC LOG

FT.: 270, 280, 290, 300, 310, 320, 330, 340, 350, 360, 370

SAMPLE Sample No.	INTERCEPT	CORE LENGTH	ANALYTICAL O.P.T. Au	O.P.T. Ag	
6881	329.0-332.6	3.6	0.001	0.04	Scale change
6882	332.6-335.6	1.0	0.001	0.03	333.6 HW.
6883	335.6-357.5	3.9'	0.003	0.10	
6884	357.5-359.0	1.5'	0.001	0.04	
6885	339-342	3.0	0.001	0.04	0.002, 0.11 / 14.4'
6886	342-346	4.0	0.001	0.18	
6887	346-348	2.0	0.002	0.16	
6888	348-349.3	1.3	0.030	0.36	0.032, 0.88/3.1
6889	349.3-351.1	1.2	0.036	1.71	
6890	351.1-353.7	2.6	0.001	0.04	
6891	353.7-357.0	3.3	0.001	0.20	
6892	357.0-360.2	3.2	0.001	0.03	
6893	360.2-364	3.8	0.001	0.01	0.001, 0.08 / 22.9'
6894	364-367.5'	3.5	0.001	0.08	
6895	367.5-371.1	3.6	0.001	0.04	
6896	371-374	2.9	0.001	0.16	
6897	374-375	1.0	0.060	1.71	

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-46-47R Sheet 4 of 4

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T Ag	Native Gold Prep
379.0	5 379	4.6	92	.17	376-378.1 SOFT, dominantly rubbly to Breccia fill comp'd of ss, siltstone & minor chert @ 20° to c.a. Probably Caprock Formation	1-5% blebby-stringer (Py)-sphalerite			6898	114.30 3760-3781	3.1	0.043	0.98	
					378.1 CONTACT LOST AT ~230°				6899 *	378.1-379.6	1.5	0.520	73.76	0.232, 20.02 / 14.7
22	5 384	4.9	98	.46	QUARTZ-SULFIDE-BRECCIA 2-4 stage Br. QFP sub rounded-subangular some bodies over 2m Lithics black, strongly QSP w/ 1-10% Sulfides in Br 40-50° to c.a. of Br. Foot stage is cracked, loaf is rehealed	1-2% Py, Sph, Gn, Tr Sph, Mo Py 1-10% T.S. over zone anastomosing veinlets (Py, Sph, Gn?) w/ silicification	390		6900 *	379.6-383.0	3.4	0.145	22.88	0.283, 25.11 / 11.6
	5 389	4.8	96	.15	SILICIFIED CNT Brecciated QSP-Sulfide as above w/ QFP Block Br matrix-comp'd Andesite fr. of dev. sericite Bandings @ 40° to c.a.				6901 *	383.0-387.1	4.1	0.386	20.87	
	4 393	3.5	88	.23	389.7 SHP 30° CNT Tan-green fuzzy QFP Rich Rhyolite cut by chert Br fill w/ chert fragments & minor QFP, Br crosscuts rhyolite	2-5% disseminated PY			6902 *	118.78 387.1-389.7	2.6	0.163	6.65	
					392.5 SHP 40° CNT	2-5% disseminated PY		390	6903	389.7-391.2	1.5	0.022	0.36	
397.1	5 398	4.9	98	.19	STR PROP-WK ARG ALT, GRANODIORITE BX Br is strongly silicified, crackled & rehealed fmgs grained, retained, str chl, fmgs clay. No calcite	2-3% disseminated PY, 1% Cpy, Sph, Gn, Mo in Qtz veinlets & Br matrix			6904	391.2-392.5	1.3	0.001	0.08	
					398.0 FLT CNT @ 20° F.W. RAINBOW ZONE				6905	392.5-397.0	4.5	0.001	0.08	0.005, 0.16/E 3
	5 403	4.8	96	.14	STR Prop → WK Arg. Alt'd GDR C.Gr, ltgry, abundant cc. in matrix, str chl, plag → clay, espm fract. fract at 21°, 50°, no Ca. reheals some fract. & forms veins < ¼"; occasional v. strong epi altn as anastomosing fine veinlets overall wk-mod silic'n	1gn xl << 1mm			6906	397-398	1.0	0.001	0.01	398.0 → FW.
23	5 408	4.9	98	.58				400	6907	398-403	5.0'	0.001	0.04	
	5 413	4.5	90	.41	404.5' Sharp lower cut marked by 6" of qtz clasts in dk matrix									
	5 418	5	100	.48	Intensely Epidote Alt'd G.D.R. matrix → epi & kaol w/ silicification only qtz clasts remain, 1st 6" v str chl, then complete kaol & epi in str phyllic altn & lt apple grn colour, silicified	minor cubic PY on fract								Multiplier 0.346
					Epidote Alt'd G.D.R. Brx, matrix → epi & kaol as network btwn 418.9 qtz clasts, clasts are rotated				6908	414.3-416.9	2.6'	0.001	0.01	
24	6 424	5.6	93	.14	Mod Prop Alt'd G.D.R. ltgry, C.Gr, mod Ca. in matrix, str chl, ~2% pl plag → kaol, epi in anastomo'g veinlets, Ca. reheals some fractns fractns at 80°, 70°, & 35° 87-46-47 EOH End of Hole at 424'	end of hole		420	6909	416.9-418.4	1.5'	0.001	0.03	
							E.o.H.							end of hole at 424'

SUMMARY

336.6 N.W. Rainbow zone strong shearing

336.6-374 GRANODIORITE BX w/ incl & Br dikes of Rhy's AND

374-378.1 polymictic Br mostly Altered Br fill

378.1-389.7 QUARTZ SULFIDE BX

389.7-392.5 mineralized Rhy Br

392.5-398.0 F.W. GRANODIORITE of Rainbow Zone

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT	Skukum Creek (Wh)	HOLE No.	87-UG-48R
COORDINATE N.	71,156.8	DEPTH	328'
E.	77985.7	AZIMUTH	275
ELEVATION	1300.5	INCLINATION	-51.8
DATE STARTED		DRILLED BY	Caron Diamond Drilling
COMPLETED		ASSAYED BY	Acme Analytical Labs
HOLE SURVEY	T.W. Multifolen 0.1866	LOGGED BY	L. Rowan, L. Robinson

BOX	Run	Core	% R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION
1			98	.12	Coarse Grained Propylitic Altd Quartz Monzonite 60-70% k-spar & f-spar, x'ls 2-5mm in size, qtz 20-30% as amorphous x'ls, mafics ≤ 10% as blobs & fracture fillings, mafics altd to chl. general pink-gray colour, occasional grn tint due to chl. fractures at 30, 50 & 80° to C/A wk rx'n on fractures & mod rx'n on matrix overall wk prop altn	
18.1						
2			97	.15		trace crushed & cubic py at 1cm wide shear
35.7						
3			92	.21		
53.1						
4			91	.05		
70.1						
5			99	9	- slight rustiness on fracture surfaces 84'-87' f.gr. & wkly silicified section	
87.1						
6			93	17		
103.7						
7			99	13		
118.0					Prop Altd Plag Porphyry Andesite Dike, dk grey-grey matrix w/ 15% 5mm white reactive plag x'ls, Ca in strgly altd, veins & matrix, strong prop altn	1% minor trace 2C-5mm cubic py

GRAPHIC LOG

FT.: 0, 10, 20, 30, 40, 50, 60, 70, 80, 90, 100, 110, 120

SAMPLE			ANALYTICAL	
Sample No.	INTERCEPT	CORE LENGTH	O.P.T. Au	O.P.T. Ag

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-UG-48P Sheet 2 of 3

BG	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag
8			97	.11	- alteration increasing, rock becoming a bleached greenish colour, occasional 1.5mm PY cube increasing ca. & clay on fractures			120					
9			98	.08	- 145.1' 5cm section of strong altn w/ chl, ca, ser. & epi.			130					
10			100	.29	160.8' increasing mafics & darker green colour from chl. also more ca. in veinlets	- trace dissem cubic PY		140					
11			98	.30	170 – 174 section of potassic altn			150					
12			100	.29	-186' 1' sheared section strong prop w/ argillic altn 187' 1' strongly prop altd And. dyke, 2nd shear at 188 w/ ca & 5% blebby PY - 195-197 a mafic rich, fine plag subporphyritic section	- 5% blebby PY in ca. filled shear		160					
13			99	.40	211-214.5 subporphyritic texture, 10% 2-6mm plag phenos x'l structure becoming unclear & "ghosty", propylitic alteration increasing in strength • ca. in stgs & veinlets			170					
14			100	.44				180					
					Scale change 1" = 10'			190					
	5 244	5	100	.38	ATAL STRUCTURE V. GHOSTY & INDISTINCT. V. STRONG PROPYLITIC OVERPRINT. ONLY QTZ & SOME F. SPAR ATALS VISIBLE. BRAK CRACKLE WELL-HEALED BY CA & MINERALS. 244.7: WEAK, WELL HEALED BANDED SHEAR ZONE FOR 15cm.	TRACE DISS. PY		200					
15	5 249	5	100	.66	MOST FRACTS. & STRINGERS @ 70 TO 45° TO C/A			210					
	5 254	4.7	94	.62	CONTACT V. WAVY & INDISTINCT. LIGHTER GREY. VERY GOOEY = HARZY. MAY BE SAME UNIT AS ABOVE BUT STRONGER ALTERED, BUT MAY HAVE CLASTS OF LIGHTER UNIT ENCLOSED. MAY BE BRECCIA. 70 CONTACT SHEAR @ 60° TO C/A. BRECCIATED Q. PHENOCRYST. DK GRN-GRY BANDED ½" PC/a. MAG, F.G. MATRIX. CLAST SUPPORTED. ABUNDANT CA STRINGERS. CLASTS OF RHYOLITE. 70/cm. LOWER CONTACT SHARP @ 75° TO C/A	249.5 MINOR PY DISS & IN VEINLETS & BLEBS. MINOR TO 2% PY IN Q & ANKER VEINS. MAY BE 254.6 3% IN MATRIX.		220					
								230					
								240					
								246.7					
								249.3	6937	249.7-249.3	4.6'	0.001	0.06
								250.3	6938	249.3-251.3	2.0'	0.001	0.07
								251.3	6939	251.3-254.6	3.2'	0.009	2.42
								254.6					

Zn Pb

HW ↓ 251.3'

OMNI RESOURCES INC. PROJECT Skukum Creek (WL) DIAMOND DRILL HOLE No. 87-UG-48R Sheet 3 of 3

BC's	Run	Core	% R	RQD
257.2	5 259	5	100	.62
16	5 264	5	100	.52
	5 269	5	100	.14
274.8	5 274	5	100	.52
	5 279	5	100	.40
17	5 284	4.6	92	.76
	5 289	5	100	.41
293.0	4 293	3.7	93	.19
	5 298	5	100	.76
	300	13	65	.85
18	5 305	5	100	.41
	4 309	3.7	93	.54
311.5	5 314	5	100	.59
19	5 319	5	100	.57
	4 323	4	100	.42
328	5 328	4.4	88	.36

LITHOLOGY, ALTERATION, STRUCTURE

SILICIFICATION SO STRONG IT IS V. DIFFICULT TO SEE STRUCTURE, LITHOLOGY OR ANYTHING ELSE. BANDED @ 40° TO C/A. LOWER CONT. SHARP, INTRUSIVE @ 40° TO C/A

RHYOLITE BRECCIA DIKE. AS ABOVE. BANDED @ 40° TO C/A. LOWER CONT. SHARP, INTRUSIVE @ 40° TO C/A

SILICIFIED, BRECCIATED LIGHT GRN-GRY GOR. FAINT BANDING @ 40° TO C/A. ABUNDANT CA + CLAY CEMENT. MINOR BLAKISH-GREEN BANDS. MAY BE CHLORITE AND/OR SX. LOWER CONT. SHARP 35-40° TO C/A.

SHEARED, BRECCIATED SX MATRIX. OLIVE GRN/ARGILLIC ALTERED CHERTY CLAST-SHARP TO CONTACT GRADATIONAL FROM GOR AT TO DECREASING SYNTHETIC BRECCIA AT 289.3, BUT MATRIX IS DARK GREY-GREEN NOT AS CLEARLY BANDED. CLASTS OF DK GREEN/BLACK CHL/ARG. LOWER CONT. INTRUSIVE @ 40° TO C/A.

BANDED, BXD GOR. LT-MED GRY. ABUNDANT LATE CA STRINGERS. GOR IS MED-F.G. MODERATE CLAY/SE - WEAK ARGILLIC ALT'D. GRADATIONAL LOWER CONT.

BANDED, BXD, ALTERED, SHEARED, HEALED MIXED UNIT OF FG GOR TAN RHY (COARSE & FINE GRAINED) MAY ALSO BE FRAGS & BANDS OF ARGILLIC OR MAY BE BANDED RHY & GOR. BANDS @ 40° TO C/A. SHARP LOWER CONTACT AT 30° TO CORE AXIS. INTRUSIVE CONTACT, NOT SHEARED.

CRACKLE BRECCIATED LT GRN-TAN, HARD VFG RHY. DYKE. CRACKLE WELL HEALED BY CA INFILLING. A FEW ZONES OF FLOODING BY DK GREEN CHLORITE AND WHITE, MINERALIZED QZ CAUSING MINOR ROTATION OF RHY CLASTS. ABUNDANT OVERALL CHLORITE.

LOWER CONTACT SHARP, INTRUSIVE 40° TO CORE AXIS.

BRECCIATED, SWIRLED, CRACKLED, HEALED, LT-MED. GREEN-GREY F-MED-GRAINED GRANODIORITE, ALMOST NO CALCITE. PROBABLY WEAK TO MED PHYLLIC ALT'D. SOME BLACK, VFG MATRIX CAUSING ROTATION FOR LAST 20cm. LOWER CONT. SHARP, BXD 50° TO C/A.

QUARTZ SULFIDE BRECCIA ZONE WITH JUST A FEW CLASTS? FRAGS OF M.G. GOR. BANDED @ 40° TO C/A. QZ FRAGS VARY IN SIZE FROM <10cm TO 5cm ACROSS. SOME OF THE LARGER FRAGS HAVE BLUISH TINGE. LOWER CONTACT SHARP, INTRUSIVE @ 45° TO C/A.

BANDED, BXD RHY & QZ SX MATRIX. BANDED @ 40° TO C/A. MED. GRN-GRY. ABUNDANT CA WITH OVERALL & STRINGERS & VEINLETS.

LOWER CONTACT SHARP, INTRUSIVE @ 40° TO C/A.

RHYOLITE DYKE. AS ABOVE @ 281.9'. WEAK, HEALED CRACKLE OVERALL, WITH CA HEALING, AND SOME QZ-SX BX FLOODED BRECCIATED ZONES. ABUNDANT CHLORITE IN FRACTS. SOME QZ SX LOOKS LIKE IT INCLUDED RHY, SOME LOOKS LIKE XENOS. MAY BE 2 PHASES OF MINERALIZATION - LOWER CONT. BANDED, ORIENTATION @ 55° TO C/A.

MED. GRN-GRY, MED GRAINED STRONG PROP. ALT'D. GOR. ABUNDANT CA, EP, SF, CL. WEAK CRACKLE. V. FEW REMNANT MAFICS. FSPARS SDST + GREEN. SLIGHT FIZZ. USD 20/C

LOWER CONTACT SHARP, INTRUSIVE. SOME PHASES OF LOWER UNIT INCLUDED IN UPPER.

ANDESITE DYKE. V. DK GRN-GRY. MINOR CA STR. FEW SMALL QZ PHENOS. UPPER CONT. SHARP @ 25° TO C/A. DK. GRN-GRY M-FINE-GRAINED GOR. WEAK, CA HEALED CRACKLE. F.G. GROUNDMASS. V. DARK (PORPH GOR) XENO OF ANDESITE OR OTHER BLACK ROCK. SOME MORE NEAR END. LOWER CONT. 40° TO C/A

ANDESITE DYKE AS ABOVE. V. DK. GRN-GRY, MED. GR. APHANITIC (<.1mm XTALS) ABUNDANT CA VEINLETS, STRINGERS & CRACKLE HEALING. V. ABUNDANT EPIDOTE IN FRACTS, VEINLETS & FLOODED ZONES. FRACTS @ 60-65° TO C/A.

87-UG-48R End of Hole at 328'

MINERALIZATION

257.2	BANDS + BLEBS OF CPY, PY, MAY BE SX IN PLACES.
259.3	TRACE TO MINOR PY MAINLY IN MATRIX.
264.3	SX/GL/PY/AS/ IN CLASTS OF QZSX BX. ABUNDANT PY + PROBABLY OTHER GROUND UP. VFG SX IN GROUNDMASS.
265.7	
268.3	NO VIS SX.
274.8	TRACE VFG DISS PY
278.9	5% PY/AS
279.6	NO REALLY VIS. SX, BUT MAY BE GROUND IN MATRIX.
284.3	TRACE TO NIL VIS PY
289.6	
289.9	TRACE TO NIL VIS PY.
293.0	TRACE TO NIL SX IN RHY, 5-10% SX: GL, PY, AS WITH QZ IN MATRIX OF BXD ZONES.
298.0	OVERALL <1% SX.
298.3	TRACE TO NO VIS SX.
299.3	
300.1	20-25% COMBINED SX MOSTLY PY/PO.
301.6	<1% SL/GL.
304.6	3-5% COMB. SX.
309.2	NO DISS SX, BUT QZ-SX BX ZONES WITH ABUNDANT GL/SL LOCALLY.
311.5	MINOR PY, DISS & IN BLEBS.
314.4	
314.9	NO VIS SX
319.5	NO VIS SX
323.5	NO VIS SX.
328.0	End of hole

GRAPHIC LOG: E.o.H.

FT.
260
265.7
270
274.8
280
284.0
289.0
293.0
298.1
300
301.6
304.6
310
314.4
315.9
320
324.3

SAMPLE

Sample No.	Interval	Core Length
6940 *	254.0-256.8	2.2'
6941	256.8-259.3	2.5'
6942	259.3-262.6	3.3'
6943	262.6-265.7 (80-99)	3.1'
6944	265.7-268.3	2.6'
6945	268.3-271.9	3.6'
6946	271.9-275.6	3.7'
6947	275.6-277.6	2.0'
6948	277.6-281.9	4.3'
6949	281.9-285.0	3.1'
6950	285.0-288.0	3.0
6951	288.0-289.8	1.8
6952	289.8-293.3	3.5
6953 *	293.3-298.1	4.8
6954	298.1-301.6	3.5
6955	301.6-304.6	
6956	304.6-309.2	
6957	309.2-314.4	
6958	314.4-315.9	
6959	315.9-319.5	
6960	319.5-324.3	
6961	324.3-328.0	

ANALYTICAL

Sample No.	O.P.T. Au	O.P.T. Ag	Pb%	Zn%
6940 *	0.243	12.55	1.01	2.14
6941	0.108	2.47		
6942	0.128	2.79		0.123, 4.58/11.1'
6943	0.043	2.52		5.483' in 7'
6944	0.005	0.28		
6945	0.032	0.69		
6946	0.022	0.38		
6947	0.004	0.19		
6948	0.032	0.67		
6949	0.011	0.46		
6950	0.032	1.23		
6951	0.002	0.29		
6952	0.011	0.41	Pb%	Zn%
6953 *	0.266	13.43	1.30	1.76
6954	0.029	0.01		
6955	0.037	1.39		
6956	0.007	0.36		
6957	0.002	0.02		
6958	0.001	0.02		
6959	0.001	0.01		
6960	0.001	0.01		
6961	0.001	0.35		

309.2' → FW CONT.

end of hole at 328'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling: TO TEST MINERALIZATION @ ~~1200~~ 1200 m LEVEL EITHER 87-46 R - 87-46 RE.

Explanation of Results:

LEGEND

PROJECT: Skukum Creek (Wh)
COORDINATE N. 71156.7
E. 77986.1
ELEVATION: 1300.4
DATE STARTED: OCT. 18, 1987
COMPLETED: OCT. 19, 1987
HOLE SURVEY:

HOLE No.: 87-46-49R
DEPTH: 364
AZIMUTH: ~~090°~~ 279.5
INCLINATION: ~~090°~~ -61.5
DRILLED BY: Caron Diamond Drilling
ASSAYED BY: Acme Analytical Labs
LOGGED BY: L. Rowan, R.J. Robinson

T.W. Multiplier 0.4690

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	F.T.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
					Coarse Grained Propylitic Altered Quartz Monzonite.			0					
1			93	.06	- pinkish gry-grn colour, ≈ 60% K-spar & fspar ↓ 25% qtz & 10-15% chl. alt'd mafics			10					
17.0					- qtz amorphous in matrix, f-spar & K-spar ~~appear~~ appear alt'd & ghosty but remain hard due to pervasive silicication, minor Ca. in matrix			20					
2			100	.24	- strongly silic'd & alt'd from 23' to 33.6' - fracture sets at 30, 50, 70 & 80° to C/A v. minor ser., epi & clay on some fractures	- 23' to 33.6' v. minor dissem. cubic PY		30					
34.4													
3			100	.30	- 41' 5" sheared section at 70° to C/a, strong prop ↓ argillic alteration			40					
51.4								50					
4			99	.21				60					
69.4								70					
5			100	.33	- 71 - 82' ~~silica~~ silicication & potessic alt'n ↓ a decrease in percent matics, ~~& is ghosty~~ f-spar's "ghosty"			80					
87.2								90					
6			99	.37				100					
103					104.3 interfingered sharp contact Prop Alt'd Sub-Porphyritic Granodiorite(?)			110					
7			99	.46	- 10% 2-5mm white, mod soft, & reactive plag pheno's ca. in matrix, stgs & blebs, med grn-gry colour chl. visible on fractures fractures at 30, 60 & 70° to C/A			120					
					116.1 - no diamonds, rubies or emeralds								

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-UG-49R Sheet 2 of 4

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL Q.P.T. Au	ANALYTICAL Q.R.T. Ag
8			98	.36			120					
129.3					-136' 6" f.gr. dkgry And. dyke		130					
					-137.3' 42' section of strong prop altn w/ argillic on fractures							
9			100	.35			140					
157.5							150					
					-158.6 3" And dyke							
10			100	.24	-165.1' increasing mafic content, patches of ≤ 46%, strongly prop altn also & modest increase in fractures		160					
175.5					169-171 silicin w/ ≤ 1% dissem py	- ≤ 1% .6mm cubic py	170					
					-177.5' 2" diatreme dyke at 25° to C/A							
11			100	.41	-185.3' to 186.5 Strong prop altd, small shear at 185.3, ≤ 15% Cn, 5% Sol, 10% py & 1" band of QSB	- 15% Cn, 5% Spl, 10% py & 1" QSB	180					
192.0					-194' to 196' phyllic altn of QMZ, small shear at 196' at 20° to C/A		190					
12			100	.30			200					
209.0												
					-210.4' 1" wavy & irregular diatreme band at 20° to C/A		210					
213.5			97	.66	Strongly Prop Altd Sub-Porphyritic Dyke, ≈ 60% mafics altd to chl., ≈ 15% bsm plag x'ls	locally ≤ 1% py as blebs & stgs						
13					218.2' to 215' 3" qtz ca. vein		220					
227.5					- V. strong prop altn, Ser & epi in anastomosing stgs & pervasive silicin							
14			97	.45			230					
					-238 1' silic'd & v. prop altd And. dyke at 35° to C/A							
246.1					WEAK, CA-FILLED COARSE. INCREASING ± DEPTH-		240					
	5	5	100	.57	87-UG-49R scale change 1" = 10'	scale change						
					-251.3: 15cm CLAYEY SHEAR ZONE.		250					Scale change
15	254				STRONG PROP. ALT.	251.3	251.3					— HW SHEAR (PROBABLY)
					-254.7: SMALL (1cm) QZ VEIN ± SL/CL/PY /RS/CA.	BARREN TO 1% DISS PY		6962	251.3-255.3	4.0'	0.002	0.06
	5	5	100	.67	SOMEWHAT BANDED + BRECCIATED MINOR ROTATION after 261'		260	6963	255.3-259.3	4.0'	0.001	0.07
	259				ABUNDANT PY 259-261	3-5% PY 259-261						

OMNI RESOURCES INC. ** PROJECT SKUKUM CREEK (WK) DIAMOND DRILL HOLE No. 87-16 Sheet 3 of 4

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	ANALYTICAL Pb %	ANALYTICAL Zn %
259.4	5 264	4.5	90	.58	BANDED @ ~30° TO C/A BRECCIATION INCREASES TO 270'			260	6964	259.3-264.8	5.5'	0.001	0.07		
	5 269	4.7	94	.61	FEW FRACTURES. MOST @ 50-60° TO C/A SOME FRACTS HAVE CLAY ON SURFACES.			265	6965	264.8-269.9	5.1'	0.001	0.04	0.102, 7.2/17.9,	
16	5 274	4.9	98	.60	CLAST SUPPORTED BRECCIA WITH ROTATION FROM 270' DOWNWARDS. STRONG PROP ALTERATION. MATRIX APPEARS TO BE JUST PARTLY MELTED OR CRUSHED GDR. LOWER CONTACT SHARP, BXD. 35° TO C/A.	274?		270	6966	269.9-274.7	4.6'	0.001	0.12		
	5 279	4.9	98	.35	BANDED, SHATTERED, MATRIX SUPPORTED QZSXBX IN BXD. GDR. MUCH OF MATRIX IS GREENISH-BLACK F.G. CHLORITIC ± GROUND SX. BANDING ORIENTED 35 TO 40° TO C/A. SOME QZ FORMS SUB-ROUNDED. LOWER CONTACT SHARP, INTRUSIVE @ 50° TO C/A	279.4		275	6967*	274.7-279.1 83-73	4.4'	0.134	6.29	0.61	2.10
282.1	5 284	5.0	100	.39	MINERALIZED RHYOLITE BRECCIA. HARD, VFG LT GRN-TAN BUT CLEARLY SHOWS QZSXBX MATRIX. LAST 2 FT POLYMICTIC BRECCIA COMPOSED OF CRUSHED GDR, GROUND, CHLORITIC SULFIDES, AND CLASTS OF REMOBILIZED QZ SXBX. LOWER CONTACT SHARP, INTRUSIVE @ 35° TO C/A	5-10% SX OUTSIDE IN QZSXBX & MATRIX 283.3 MOSTLY PY		280	6968*	279.1-283.3	4.2'	0.073	2.35	0.42	0.59
	5 289	5.0	100	.31	POLYMICTIC BRECCIA OF LT TAN RHY, GDR & QZ-SX CLASTS IN MATRIX OF CHLORITE, GROUND SX - MOSTLY PY, AND ROUNDED QZ OR QZ EYES. FRACTURES @ 35, 55 & 70° TO C/A. LOWER CONT. SHARP, INTRUSIVE @ 36° TO C/A.	UP TO 20% SX AS MATRIX. PROBABLY MOSTLY PY 288.0		285	6969*	283.3-285.8	2.5'	0.005	0.29	0.11	0.16
17	5 294	4.9	98	.24	SHEARED, CRUSHED, GROUND RHY & QZSXBX. V. LATE SHEAR. ALL BUT QZSXBX TOTALLY PULVERIZED & EVEN QZ MOSTLY CRUSHED. POORLY CEMENTED BY CA. LATE FRACTS @ 20, 40 & 70° TO C/A. SHEAR LOWER CONT. @ 50° TO C/A.	PROBABLY 20-25% TOTAL SX GROUND IN SHEAR 291.5		290	6970*	285.8-288.0	2.2'	0.153	1.28	0.23	0.80
	5 299	4.9	98	.49	QZ SXBX AS ABOVE BUT NOT SHEARED. MINOR CA. LOWER CONT. SHARP, INT. 35° MED. GRN-GRY GDR. STRONG PROP. ALT'N. V. ABUNDANT CL & CA VEINLETS. 10 CM CLAST UPWARD OF MED GRY TUFF. LOWER CONT. SHARP, INT. 60° TO/A 292.6	292.6 - MOSTLY QL + QS, DISS PY		291.5	6971*	288.0-291.5	3.5'	0.122	15.79	2.01	1.19
291.0	5 304	5.0	100	.60	VEINLETS & BANDS OF QZ IN THE LT GRN-TAN RHYO. DYKE. STRONG PROP. ALT'N. BASE CONTACT SHARP, INTRUSIVE @ 45° TO C/A. DK GRN-GRY M-F.G. GDR. STRONG PROP ALT'D. ABUNDANT CL/CA. XTAL SCRUBBAR SALTEARED. LOWER CONT. SHARP, INT. 60° TO C/A.	294.9 TRACE DISS PY. 295.2 NO VIS SX.		293.5	6972*	291.5-292.6 293.8	1.1'	0.144	29.62	2.49	1.85
	5 309	4.4	88	.43	MINERALIZED. BRECCIATED RHYOLITE. LT GRN-TAN. V.F.G. HARD. ABUNDANT CL STRINGERS & CRACKLE HEALING. MINERALIZATION MOSTLY IN QZ VEINS AND STRINGERS BLASTED INTO RHY. VERY LITTLE ROTATION - MOSTLY JUST CRACKLE, BUT THERE ARE A FEW ZONES WITH ENOUGH QZ VEINS TO BE CONSIDERED TRUE, ROTATED BRECCIA. ABUNDANT LATE CA & GREY & YELLOW QZ STRINGERS. RHYOLITE SOMEWHAT MOTTLED LIGHT & DARK. DARK ZONES SLIGHTLY COARSER-GRAINED. SOME LATE CHLORITE ALONG FRACTURES.	3-5% SX OVERALL. MOSTLY PY. 2 ~1%-2% COMB. SL, GL, ANT.		296	6973	292.6-294.9	2.3'	0.003	0.48		
18	5 314	4.6	96	.56				297	6974	294.9-296.7	1.8'	0.003	0.31		
	5 319	5.0	100	.50				298	6975	296.7-298.2	1.5'	0.001	0.49		
317.4	5 324	4.7	94	.54	MOST VEINS & BANDS OF QZ & SX TEND TO CUT CORE @ ~35-45°.			299	6976*	298.2-303.0	4.8'	0.038	0.25	0.05	0.13
19	5 329	5.0	100	.76				302	6977*	303.0-308.0	5.0'	0.117	0.62	0.14	1.34
	5 334	5.0	100	.49	LOWER CONTACT ~ 35° TO C/A. SHARP, INTRUSIVE. POLYMICTIC BRECCIA OF GDR, LT TAN RHY. MED GRY RHY & SULFIDES IN SUPPORTING MATRIX OF DARK GREENISH-GREY GROUND SX. GDR MOSTLY CRUSHED TO XTALS, AND SOME FS. & MAFICS ACT'D UPON. THEY PROBABLY FORM PART OF PRE-MINERALIZING MATRIX	334		305	6978*	308.0-313.0	5.0'	0.200	6.04	0.95	1.21
								314	6979*	313.0-317.7	4.7'	0.064	1.33	0.22	0.23
								317	6980*	317.7-322.0	4.3'	0.021	0.51	0.08	0.16
								320	6981*	322.0-326.9	4.9'	0.013	0.30	0.06	0.20
								326.9	6982*	326.9-330.8	3.9'	0.024	1.24	0.22	0.50
								329	6983	330.8-335.3	4.5'	0.037	1.32	0.037, 1.32/7.31	

0.102 0.329 /22.3

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-UG-48R Sheet 4 of 4

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag	
335.3						336.3								
	5 339	5.0	100	.46	SUB-PORPHYRITIC GRANODIORITE. VERY FINE-GRAINED BLACK GROUNDMASS WITH QUARTZ & FELDSPAR (PLAG) XTALS. ABUNDANT CALCITE BLEBS & STRINGERS. WEAK, HEALED CRACKLE TEXTURE. NO FRACTURES. LOWER 2 FT FELDS ALT'D TO BRIGHT EPIDOTE.	BARREN TRACE DISS. PY. & VFG.			6984	335.3-339.0	3.7'	0.001	0.01	335.3 FW CONTACT.
20	5 344	5.0	100	.84	LOWER CONTACT HAZEY, INDISTINCT, MELTED. INTENSE PROP ALT'N. INTRUSIVE CONTACT.	343.2			6985	339.0-343.2	4.2'	0.001	0.01	
	5 349	5.0	100	.80	ANDESITE DYKE. NUMEROUS XENOLITHS OF GRANODIORITE. DARK GREENISH BLACK, V.F.G. INTENSE PROP ALT'N. ABUNDANT EP, CL, SE. MAIN FRACTURE ORIENTATION N 65° TO C/A.	TRACE PY - ALL VISIBLE PY IN OR ALONG CA VEINLETS & BLEBS.		340	6986	343.2-348.0	4.8'	0.001	0.04	
354	5 354	4.9	98	.73	LOWER CONTACT GRADATIONAL, INDISTINCT, INTRUSIVE.	353.7		350	6987	348.0-353.7	5.7'	0.001	0.01	
	5 359	5.0	100	.52	MEDIUM GREENISH, GREY, F-M.G GRANODIORITE. INTENSE PROP ALT'N DECREASING ↓ DEPTH. ABUNDANT CA VEP DEC. ↓ DEPTH. WEAK HEALED CRACKLE. MOST FRACS 80-90° TO C/A.	TRACE DISS VFG PY.			6988	353.7-358.8	5.1'	0.001	0.01	
21	5 364	4.5	90	.18	87-UG-48R End of Hole at 364'		364 E.o.H.	360						end of hole at 364'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT	Skukum Creek (Wh)	HOLE No.	87-UG-50R
COORDINATE N.	71190.7	DEPTH	169'
E.	77899.4	AZIMUTH	156.3
ELEVATION	1301.2	INCLINATION	-21.2
DATE STARTED	Oct 21, 1987	DRILLED BY	Caron Diamond Drilling
COMPLETED	Oct 22, 1987 (casing not in)	ASSAYED BY	Acme Analytical Labs
HOLE SURVEY	✓	LOGGED BY	L. Rowan, R.T. Robinson

TW Multiplier 0.811

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
1			98	.40	Propylitic Altered Sub-Porphyritic Granodiorite 15-20%, 1-5mm white subhedral plag x'ls in f.gr. qtz & hornblende matrix, med grn-gry colour, mod. prop. alt'n, ca. & epi in fractures & as anastomosing networks - fractures at 30, 46, 70 & 80° - inclusions of QMz at 12.5' & 14.2'			0						
110								10						
2			97	.44	sharp cnt at 50° Strongly Prop Altd C.Gr. Granodiorite - bleached white amorphous plag x'ls in matrix of 20-40% mafics & ≅ 15% qtz, mafics completely altd to			20						
126					29.4' chrome grn chl as blebs & fine streaks 32.5' strong propaltn w/ ca. stgs, for 6" 4" shear band, strongly prop & argillic altn - pervasive silic'n - ser. & epi. in ~~crackle textures & fractures~~ wavy fractures - fracture sets at 30, 45, 70 & 80° ca. & clay on some fractures			30						
3			100	.20				40						TW multiplier = 0.811
154.0								50						
4			97	.30	- increased silicification from 71-74'			60						
171.7								70						
5			100	.18	- 81' epi band at 60° to C/A			80						
189.3					Scale change 1" = 10'			90						scale change
6	5.5 93	5.2	95	Ø	HEMATITE IN SOME CA VEINS.	NO TO TRACE DISS. PY		93.0	1					
	5 98	2.0	40	Ø	YELLOW & BLACK OXIDIZED COATINGS ON FRACTS. NEAR CONTACT. SHARP, 50° TO C/A	98.5		98.5	69.89	93.0-98.5	5.5'	0.001	0.02	POOR RECOVERY 98.5' ↓ FW
	5 103	5.0	100	51	MED. DK GRN STRONG PROP. ALT'D C.G. GDR. STRONG CRACKLE. 2CM DIATREME W/ CLASTS: LOWER CONT. SHARP, PLANAR @ 40° TO C/A.	100.9	TRACE VFG DISS PY.	100	69 90	98.5-100.9	2.4'	0.006	0.21	
					HEALED, BANDED, BRCD SHEAR IN GDR. BANDED @ 55° TO C/A. ABUNDANT CA + CHLORITIC. FRACTS @ 25-55° TO C/A SOME BANDS BURRELED UP. LOWER CONTACT GRADATIONAL	104.9	TRACE VFG DISS PY.	104.5	69 91	100.9-104.9	4.0'	0.003	0.36	

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-UG-50R Sheet 2 of 2

Box	Run	Core	%R	R.Q.D.
108.8	5 108	5	100	.46
	5 113	5.1	100	.55
7	5 118	5.5	100	.25
	2.5 120.5	2.4	96	.63
	4.5 125	4.3	96	.41
126.0	2.5 128.5	2.7	100	.52
	4.0 131.5	3.7	93	Ø
8	5.0 136.6	4.8	96	.42
	5 141.5	5.0		.17
143.5	5 146.6	5.0	100	.43
	3.5 150	2.2	63	Ø
9	5 155	4.8	96	.15
	4 159	3.7	93	.11
164	5 164	5.0	100	Ø
10 169'	5 169	5.2	100	Ø

LITHOLOGY, ALTERATION, STRUCTURE

BXXD, PROP ALT'D GD RHY. MOSTLY CLEAN, HARD, SLIGHTLY CHLORITIC RHY, WITH ZONES OF STRONG BXXN & ROTATION. ABUNDANT CALCITE (YELLOW) + YELLOW QZ. V. THIN STRINGERS OF BX INFILLING. FRACTS MOSTLY 45° & 80° TO C/A. Mn OXIDE COATING ON FRACT. SURFACES. BLEB OF QSBX @ 111.0'. ~2cm WIDE. LOWER CONTACT GRADATIONAL, BXXD.

GDR BX & QSBX MATRIX. STRONG PROP. ALT GDR, M.G. LT GRN-GRY WITH BANDS & SWIRLS OF QSBX approx 20% QSBX. GDR MASHED & V. BROKEN UP CHALKY GREEN WHERE NO QSBX. BANDS @ 45° TO C/A. FRACTS @ 45 & 70°. BASALT DIKE.

QUARTZ SULFIDE BRECCIA. WITH A FEW FRAGS. BANDS AND GRAINS OF GDR. ABUNDANT GALENA. FRACTURES AT 45 & 75° TO C/A. V. ABUNDANT PY IN REMNANT GDR. GDR IS STRONGLY PROP ALT'D. SOME PLACES COMPLETELY QSBX - SOME ZONES TO 10% GDR OVER 30cm.
LOWER CONTACT GRADATIONAL. LESS QSBX.

QSBX & GDR SIMILAR TO ABOVE, BUT NOT SO WELL MIXED. HERE WE HAVE SHEARED GDR SEPARATE FROM SOLID @ 35°. ONLY ~ 10% QSBX. LESS OF PROPORTIONALLY TO ABOVE. WEAK BANDING @ 25° TO C/A.

EXACTLY AS ABOVE NO SEPARATE UNIT. MASHED GDR HAS V. ABUND. PY DISS THROUGHOUT. LOWER CONTACT: SHARP, INTRUSIVE. 90° TO C/A

CLEAN, HARD LT GRN-TAN RHY. MOD. HEALED CRACKLE. WEAK BANDING @ 30° TO C/A. MINOR QZ VEINLETS. LOWER CONTACT SHARP, BROKEN.

MIXED, BANDED, SHATTERED, LT GRN-TAN RHY AND DK GRN PROP. ALT'D M-G GDR. BANDS @ 30° TO C/A. BASE CONTACT SHARP SHEAR 10°TO C/A.

HANGING WALL SHEAR ZONE. SHATTERED, CRUMBLED, POORLY-HEALED & SILICIFIED M-CG GDR. WEAK BANDING @ 55° TO C/A. ABUNDANT CL/CA. SOME LATE, YELLOW QUARTZ. LOWER CONT NOT SHARP, SHEAR @ 80° TO C/A.

V. HARD, LT. TAN-GREY STRONGLY SILICIFIED M-G. GDR. XTAL STRUCTURE V. HAZEY & INDISTINCT. MOD HEALED CRACKLE. MINOR, LATE YELLOW QZ STRINGERS. LOWER CONTACT GRADATIONAL.

PHYLLIC ALT. M-G LT. GRN-GRY GDR. STRONGLY CRACKLE TO WEAK ROTATION. WELL-HEALED. MnOXIDES ON FRACT. SURFACES. GRAIN SIZE INCREASING WITH DEPTH. FRACTS @ 45 & 70° TO C/A. NARROW GALENA VEIN @ 156'. (NOT SIGNIFICANT.)

ONLY QZ VEIN XTALS DISTINCT - OTHERS V. INDISTINCT.

ABUNDANT CL, EP, SERICITE

ALTERATION DECREASES WITH DEPTH.

87-UG-50R End of Hole at 169'

MINERALIZATION

TRACE TO MINOR SL, GL, PY, AS. IN SMALL STRINGERS & FRACT FILLING.
112.8

5-7% COMB. SY. MINOR PY, TRACE GL, SL, AS.
116.2

17-20% COMBINED SY. 90% OF THAT PY, 30% GL REST IS SL, AS & SB.
122.9

8-10 % TOTAL SF. MAINLY PY, THAN GL, SL, AS, SB.
126.0 LESS GL THAN ABOVE.

4-5 DISS PY IN GDR
129.0 AND QSBX AS ABOVE

130.8 MINOR DISS & BAND SF. - MAINLY PY.

TRACE DISS PY.
132.9

1-2 % PY BLEBS & DISS.
136.9

TRACE DISS PY

TRACE TO MINOR DISS PY.

end of hole

GRAPHIC LOG



E.o.H.

FT.
108.8
110
112.8
116.2
120
122.9
126.0
129.0
130
132.9
136.9
140
145.0
150
160

SAMPLE

Sample No.	INTERVAL	CORE LENGTH
6992	104.9 - 108.6	3.7'
6993	108.6 - 112.8	4.2'
6994 *	112.8 - 116.2 (3438)	3.4'
6995 *	116.2 - 119.1	2.9'
6996 *	119.1 - 122.7	3.6'
6997 *	122.7 - 126.0	3.3'
6998 *	126.0 - 129.0 (3931)	3.0'
6999	129.0 - 130.8	1.8'
87000	130.8 - 132.9	2.1'
3001	132.9 - 136.9	4.0'
3002	136.9 - 140.5	3.6'
3003	140.5 - 145.0	4.5'

ANALYTICAL

O.P.T. Au	O.P.T. Ag
0.001	0.30
0.012	0.56
0.084	8.54
0.221	29.84
0.236	64.96
0.118	13.57
0.126	10.16
0.001	0.11
0.001	0.03
0.007	0.21
0.001	0.05
0.010	0.24

0.006, 0.38 /14.3

1288.8 .

0.157, 26.3/6.2

(4.07) TW

1287.0

HW SHEAR.

Tw multiplier 0.811

end of hole at 164'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT	Stukum Creek (Wh)	HOLE No.	87-UG-51 R
COORDINATE N.	71,190.8	DEPTH	144'
E.	77898.9	AZIMUTH	174.9
ELEVATION	1303.8	INCLINATION	29.6
DATE STARTED	OCT 22, 1987	DRILLED BY	Caron Diamond Drilling
COMPLETED	OCT 23, 1987 LOGGED BY TW	ASSAYED BY	Acme Analytical Labs
HOLE SURVEY	T.W Multiplier 0.8308	LOGGED BY	L. Rowan, P.J. Robieson

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
1			98	.35	Prop Alt'd Subporphyritic Quartz Monzonite Prop Alt'd Sub-Porphyritic Granodiorite - med grn-gry, 10-15% 2-5mm mod alt'd white plag phenocrysts in f.gr. gtte. hornblende matrix 9.2 – 10.8 f.gr. GDR w/ wk brx'n, non rotated clasts of GDR - Ca rehealing fractures & as hairline stgs, matrix moderately reactive - mod. intensity of prop alt'n, epi. & ser. on some fractures, mafics completely altered to chlorite - fracture sets at 15, 25, 60 & 80° to C/A - 33-34' strong alt'n w/ shearing & brx'n									
2			100	.22		-24.7' 1cm ca. band w/ 5mm py blebs -28.0' 3mm py blebs								
3			100	.29										
4			100	.14	- increasing pervasive silic'n									
5			100	.36	74.0 1' prop alt'd f.gr. And. dyke 75.2' sharp cnt Prop Alt'd Andesite Dyke, dk gry to gry-grn, aphanitic matrix w/ 1mm plag laths faintly visible, ca. cnt. & fgr. on fractures, mod prop alt'n, fract. at 30 & 45°	TRACE VFG DISS PY								
	5 99	4.7	94	.64	M.G. GDR: STRONG PROP. ALT'N. ASSIMILATED CA + YELLOW QZ XENOLITHS AND FRACT. HEALING. STRONG CRACKLE - WEAK ROTATION. @ 81.7 IS 4 CM SHEAR ZONE. HEMBOT. YELLOW QZ. LT-MED. YELLOW GRN-GRY. FGR GTE @ 20+40 TO C/A. BACK CNT SHARP SHEAR/FLT? @ 80° TO C/A.	TRACE VFG DISS FY 0 TO TRACE PY								
6	5 94	5.1	100	.39	BANDED, SWIRLED, ALT'D GDR AS AT 87.3 ABOVE. STRONG PROP. + SILICIC ALT'N. LT-TO MED. GREYISH-GREEN, MED GRAINED. SOME WEAK BANDING @ 65° TO C/A. VERY ASSIMILATED YELLOW QUARTZ. VERY FEW FRACTURES, MOST @ 65° TO C/A.	TRACE DISS PY.								
	5 99	4.9	98	.94	LOWER CONTACT BXED @ 40° TO CORE/AXIS DIATREME BRECCIA. SOFT BLACK, WHITE-STREAK MATRIX WITH ROUND TO SUB-ROUND CLASTS OF RHYOLITE. NO FRACT. ORIENTATION. BASE CONTACT BROKEN.	NO VIS SX.								
	5 104	4.9	98	.78	BRECCIATED, CRACKLED, SLIGHTLY ROTATED, AND HARD, FINE GRAINED RHYOLITE. A FEW NARROW BANDS OF DIATREME MATERIAL AND A FEW NARROW BANDS OF BLACK MATRIX BRECCIA. SOME FRACTURES SLIGHTLY RUSTY-WEATHERED. FRACTURES @ 20 & 40° TO C/A. SOME CLAY & GROUND CA ON FRACES.	RARE TRACE DISS PY.								

	SOLID	80.9-83.3	2.4'	0.001	0.01		80.9' W.F.W CONTACT
	3028	83.3-87.3	4.0'	0.001	0.06		.003, 0.12 / 9.1
	3029	87.3-90.0	2.7'	0.0006	0.30		Scale change 1":10'
	3030	90.0-90.8	0.8'	0.076	1.99		
	3031	90.8-95.9	5.1	0.002	0.04		
	3032	95.9-98.0	2.1	0.080	1.46		
	3033	98.0-102.7	4.7	0.001	0.16		
	3034	102.7-107.0	4.3	0.005	0.81		

OMNI. RESOURCES INC. * PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-46-51R Sheet 2 of 2

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
	5 109	5.0	100	.30	BOTTOM CONTACT SHARP, INTRUSIVE @ 35° TO CORE AXIS STRONGLY ALT'D, SHEARED GDR AS ABOVE. FRACTS @ 40° TO C/A, BANDING. DARKER GREEN, SLIGHTLY COARSER. CHAINED @ RHY. ABUNDANT CA.	107.0 TRACE PY		107.0						
7	5 114	5.0	100	.08	V. SOFT. STRONG PROP. ALT. BASE INTRUSIVE, BKD @ 40° TO C/A. DIATREME ? BRECCIATED, ION SHEARED GDR. BASE SHARP @ 25° TO C/A	108.4 NO VIS SX		108.4 110	3036	108.4-111.4	2.0	0.001	0.01	
					ALT'D, SHEARED SILICIFIED MAG. GDR. FRACTURES, BANDING & SHEARING @ 65-70° TO C/A. BASE CONTACT GRADATIONAL - INCREASING FRACTS.	111.4 NO VIS SX 112.7 NO U.S.S.X EXCEPT FOR 10cm BAND AT TOP OF 1% V.F.G. CHLORITE		111.4 112.7	3038	111.4-112.7	1.3'	1.13	0.007	
	5 119	5.0	100	.16	10 cm BAND OF SHEARED, V.F.G. BLACK CHLORITE & SULFIDES IN GDR, THEN JUST MORE ALT. SHEARED SILICIFIED MAG. GDR. FRACTURES, BANDING & SHEARING @ 65-70° TO C/A. BASE CONTACT GRADATIONAL - INCREASING FRACTS.	116.3 2-3% PY DISS & IN 119.0 3 LENS.		116.3	3039	112.7-116.3	3.6'	1.34	0.023	.015, .034'/7.6'
	5 124	3.3		Ø	SOFT, CRUMBLED, SHEARED STRONGLY-ALT'D GDR. ABUNDANT CL, CA POORLY HEALED. MINOR YELLOW QZ STRINGERS. BASE CNT. SHARP, SHEARED 45°	MINOR DISS PY IN GDR 7-10% SX IN ASBX - MOSTLY PY.		119.0	3040	116.3-119.0	2.7'	0.04	0.009	1321.7
1229					BANDS & BLEBS of MINERALIZED GDR SX BX IN SHEARED, STRONGLY PROP. ALT'D GDR MED GRN-GRY, MG. STRONG SHEAR/CRACKLE TEXTURE. ABUNDANT CL, CA, QZ - YELLOW & WHITE, MOST FRACTURES & BANDING AT 65 & 85° TO CORE AXIS. BASE CONTACT GRADATIONAL, BROKEN.			120	3041	3622 119.0-123.0	4.0'	29.89	0.139	
8	5 129	5.0	100	Ø	SHEARED, BROKEN-UP, STRONGLY ALTERED, SOFT, CRUMBLY. HW. SHEAR ZONE. LT YELLOWISH-GREEN-GREY. STRONG PROP & SILICIC ALT'N. ABUNDANT CA/CL. BASE CNT SHARP, SHEAR, 45°	1260 BARE TRACE DISS. 1290 VFG PY		123.0 1260	3042	123.0-126.0 38.40	3.0'	0.075	1.81	0,112,178 / 7' 1322.8 (1.77 m TW ↑ H.W CONTACT
	5 134	5.0	100	.15	GDR AS ABOVE BUT NOT SHEARED JUST STRONG CRACKLE FRACTS & BANDS @ 60° TO C/A. YELLOW QZ LESS ABUNDANT AT THAN ABOVE. BASE CONTACT SHARP, ON CA HEALED FRACTURE @ 80° TO C/A.	0 TO TRACE DISS. VFG PY.		126.0	3043	126.0-129.0	3.0'	0.006	0.46	
	5 139	5.0	100	.62	DARK GRN-GRY, MOD. PROP. ALT'D M.G. GDR. MODERATE CRACKLE TEXTURE, WELL HEALED - PROBABLY BY CHLORITE. MAIN FRACT ORIENTATION ~ 60-65° TO C/A. CRACKLE & ALT'N DECREASING & DEATH.	TRACE DISS. VFG PYRITE		129.0 130 133.7	3044	129.0-133.7	4.7'	0.001	0.03	
9 144	5 144	5.0	100	.08				139.0 140 144 EOH	5-3 3045	133.7-139.0	5.3'	0.001	0.01	end of hole at 144'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT Skukum Cr (Wh) | HOLE No. 87-UG-52R
COORDINATE N. 71,192.0 | DEPTH 161'
E. 77900.7 | AZIMUTH 102.7
ELEVATION 1304.0 | INCLINATION 38.8
DATE STARTED Oct 23, 1987 | DRILLED BY Caron Diamond Drilling
COMPLETED Oct 24, 1987 Logged Wgt | ASSAYED BY Acme Analytical Labs
HOLE SURVEY T.W Multidex 0.6602 | LOGGED BY L. Rowen, R.J. Robinson

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag
1			94	.44	Propylitic Altered Sub-Porphyritic Granodiorite - medium to dark K gray colour - 15% 2-5mm w/ minor 10mm white, hard & non-reactive plag phenos - matrix of quartz, hornblende & minor calcite - minor anastomosing veinlets of calcite & sericite - fracture sets at 30, 55 & 70° to C/A			0					
18.6								10					
2			100	.38				20					
35.3								30					
3			98	.45				40					
52.9								50					
4			93	.19	- 65.9' xenolith of c. gr. GDR.			60					
69.9					~~Silicif~~ Silicification & alt'n increasing w/ depth			70					
5			87	.05				80					
87.0					93.5' contact lost in very broken core 95.5' C. Gr., wkly Prop alt'd, Granodiorite			3/4					
6			100	.13	Coarse Grained Mod-Strong Prop Alt'd Granodiorite - pinkish w/ lt. gry colour, ≤ 10% chl. alt'd mafics, amorphous qtz & plag. matrix w/ minor to moderate calcite, calcite & kaol. on fractures - fracture sets at 30, 70 & 80° to C/A			90					
102.0								100					
7			87	.11	107.6 sharp cnt & broken core Prop Alt'd Andesite Dyke, dk gry, aphanitic, minor crackle fracturing, mod prop alt'n 111.0 C. Gr. Prop Alt'd Granodiorite, same as at 85.5' to 107.0 116.0' Prop Alt'd Andesite, same as at 107' but alt'n increasing in intensity down hole			60					
119.9					118.7	118.7		70					
								110					
								120					119.7 FW

OMNI RESOURCES INC. · PROJECT Skukum Creek (Wh) · DIAMOND DRILL HOLE No. 87-UG-52R Sheet 2 of 2

scale change 1" = 10'

FOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag	
	3	3.0	100	.33	RHYOLITE - FIRST 30 cm SOFT, ALT'D. COARSER-GRAINED, MOD. CALCITIC. MOD. PROP. ALTN. AFTER 30 cm IS MOSTLY CLEAN, HARD, U-FG. LT. GRN-TAN. ABUNDANT CRACKLE-HEALING YELLOW QZ + WHITISH-YELLOW CALCITE. MOD-STRONG CRACKLE, MINOR ROTATION WITH MATRIX OF MASHED RHY. SLIGHT BANDING + V. BROKEN + CORE LOSS @ 129'. MINOR SULFIDE MINERALIZATION IN BANDS & GLEBS.			120					
	123													
	5	4.1	82	.08		MINOR SX OVERALL								
	128													
8	5	1.4	28	Ø		BANDS + GLEBS OF FG SX. MOSTLY PY. SOME SL/CL/AS/SB		130	3021	128.0 - 133.0	5.0'	0.024	1.99	CORE LOST. 0.028, 1.84/18'
	133													
	3	2.6	87	.29	AFGN FRACS SHOWN @ 20-25° TO C/A.									
	136							136.0	3022	133.0 - 136.0	3.0'	0.047	3.54	
	5	4.9	98	Ø					3023	136.0 - 141.0	5.0	0.011	1.46	
140H	141				V. BROKEN FOR 25 cm @ 141'.			140						
	5	3.5	70	Ø	MORE ALTERED + SOFTER FOR LAST 50 cm. BASE CONTACT, SHARP, INTRUSIVE & CHILL MARGINS @ 20° TO C/A			141.0	3024	141.0 - 146.5	5.5	0.001	0.36 oz/t	
	146					146.5		146.5						
9	2	1.7	85	Ø	NW SHEAR ZONE: SHEARED, GROUND, STRONGLY PROP. ALT'D GDR. ABUNDANT CALCITE AND CLAY. BOTTOM 40 cm BANDED GRITTY CLAY, MOSTLY V. BROKEN UP. SOME BANDING @ 40° TO C/A. LOWER CONTACT BANDED HEALED SHEAR @ 40°	TRACE DISS. PY.								
	148													
	4	2.4	60	Ø					3025	146.5 - 151.6	5.1	0.078	3.54	↑↑ HW 151.6
	152					151.6		150						
	4.5	4.2	93	.09	MED-C.G. MED-DK GRN-GRY MOD. PROP ALT'D GDR. ABUNDANT CA. FAIRLY SOFT. MOST FRACTURES @ 35-40° TO C/A. SOME RUSTY WEATHERING ON FRACS.	Ø TO TRACE DISS. PY.		151.6						
	156.5								3026	151.6 - 156.5	4.9	0.001	0.02	
	4.5	4.1	91	.18	WEAK CRACKLE TEXTURE W/ HEALED WITH CA INFILLING.			156.5		NO SAMPLE TAKEN				
TD	161				87-UG-52R End of Hole at 161'		E.O.H. @ 161'	160						end of hole at 161
161														

-259

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT Skukum Creek (Wh) — HOLE No. 87-UG-53R
COORDINATE N. — DEPTH 169.5'
E. — AZIMUTH
ELEVATION — INCLINATION
DATE STARTED October 26, 1987 — DRILLED BY Caron Diamond Drilling
COMPLETED Oct. 27, 1987 (loosed Oct 30) — ASSAYED BY Acme Analytical Labs
HOLE SURVEY — LOGGED BY L. Rowen, R.T. Robinson

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
1			92	.09	Coarse Grained Propylitic Altered Quartz Monzonite - greenish-gry colour, f-spars soft & v. reactive, mafics in "marbled" swirl texture and completely alt'd to chl., plag & K-spar & qtz x'ls blurred but visible in matrix, sor. & epi on fracs 18.9' shear, c.a. 19.0' strongly prop alt'd Andesite dyke, lwr cnt strongly silic'd	.5mm py cubes in ¼" ca. vein	70°	0					
18.9					- C. gr. Granodiorite as above fracture sets at 45, 60, 70 & 80° to C/A			10					
2			100	.29				20					
35.8					- 33.5' 1.5' section of strong prop alt'n	30' wk trace dissem py		30					
3			96	.10				40					
52.4					- 52' a 1' w strongly prop. alt'd Andesite dyke			50					
4			96	.15				60					
68.8													
74.4					74.4' gradational contact Potassic Altered C. Gr. Granodiorite		70°	70					
5			94	.24	- Similar to above unit, pinkish grn-gry colour, K-spars v. strong red-orange colour, mafics ⇒ chl. in blebs & swirled texture minor ca. & kaol on fractures 86.7' fracture sets at 30, 60 & 70°			80					
85.9					91.4' silicified P.Gr. Potassic Altered Granodiorite, amorphous texture		60°						
6			100	.15	Propylitic Altered Granodiorite - med grn colour, x'ls in matrix ~~which~~ have amorphous texture, mafics ⇒ chl as blebs & blurred indistinct boundaries, ca. on fractures, in stgs & as blebs in matrix plag ⇒ sericite & minor epi. fractures at 30, 60 & 70°			90					
101.4								100					
7			99	.11	- 111.0' - shear at 20° to C/A marking boundary of increasing prop alt'n, change from mod to strong, rock soft & bleached grn-gry colour, ca. & kaol on fractures			110					
118.4								120					

OMNI RESOURCES INC.

PROJECT Skukum Creek (Wh)

DIAMOND DRILL HOLE No. 97-UG-53R Sheet 2 of 2

BOX	Run	Core	%R	RQD
8	5 (122)	4.8	96	.09
	3.5 (125.5)	3.5	100	.10
	5.0 (130.5)	5.0	100	.31
135.2	5.0 (135.5)	5.0	100	.52
	5.0 (140.5)	5.0	100	.12
	5.0 (145.5)	5.0	100	.17
	5.0 (150.5)	5.0	100	.56
	5.0 (155.5)	5.0	100	.50
	4.0 (159.5)	4.0	100	.54
	5.0 (164.5)	4.9	98	.57
169.5'	5.0 (169.5)	5.0	100	.18

LITHOLOGY, ALTERATION, STRUCTURE

scale change 1" = 10'

STRONG PROP. ALT'N WITH Qz FLOODED ZONES.
BRECCIATION INCREASING WITH DEPTH. MINOR CLAY + CRUSHED CHLORITE IN SOME FRACTURES MOST FRACTS ~65° TO C/A

LOWER CONTACT GRADATIONAL.

SILICIFIED, Qz-FLOODED STRONG PROP. ALT'D C.G. GDR. PALE, LIGHT GREENISH-GREY. SOME GROUND CRUSH + CA ON FRACT SURFACES. STRONG CRACKLE TEXTURE SOME MINOR ROTATION OF CLASTS. MOST FRACTURES 55-65° TO C/A

LOWER CONTACT SHARP, PLANAR 35° TO C/A

BRECCIATED, & INTENSELY PROP. ALT'D. m.C.G. GDR. LT. GRN. GRY. ABUNDANT CL, EP, SE, CA. Some Qz FLOODING. SOME SWIRLING & BANDING. FRACTS @ 40° TO C/A.

LOWER CONTACT SHARP, PLANAR 80° TO C/A

SHEAR ZONE: CRUSHED, UNCEMENTED, GROUND-UP GDR AS ABOVE FOR 20cm. THEN JUST GRITTY CLAY & some minor Qz GRAINS. SLIGHTLY RUSTY IN THIN BANDS.

LOWER CONT AT SHARP, PLANAR @ 90° TO C/A.

FRACTS @ 60-65° + MINOR CA STRINGERS. MINOR COMPACT GRADATIONAL - INCR. MINS.

GDR IS PHYLLIC ASS'D. Qz IS MORE VIS. XTNS. BANDED 70-90° TO C/A. BASECUT CHANGES

BRECCIATED RHYOLITE. OVERALL WEAK - MOD BX'N - USUALLY NO FOREIGN MATRIX. CLAST SUPPORTED. MOST MATRIX JUST CRUSHED RHY. SOME MATRIX VFG SILICIC SULFIDES.

RHY MOSTLY CLEAN, HARD, LT GRN-TAN. SLIGHTLY PROP. ALT'D.

FRACTS @ 35+75° TO C/A.

LOWER CONTACT SHARP, PLANAR-IRREGULAR / ROLL. 45° TO C/A

QUARTZ SX BX IN RHYOLITE, AND THEN IN GDR. RHY/GDR CONTACT NOT VISIBLE DUE TO INTENSITY OF ALT'N AND WEAK BANDING + MOST FRACTURES @ 70° TO C/A.

LOWER CONTACT VERY ABRUPT ON RUSTY FAULT @ 20° TO C/A. FRACTURE IS SLICKENSIDED WITH SEVERAL RUSTY FRACTS FOR 20cm.

BLOTCHY LIGHT TO MEDIUM GREEN ALT'D GDR. COARSE GRAINED. LIGHT IS PHYLLIC, DARK IS INTENSE PROPYLITIC ALT'N. CA STRINGERS. FRACTS @ 65° BASECUT SHALLOW @ 65° TO C/A.

DK GRN, C.G. STRONG - MOD. PROPYLITIC ALT'D. GRANODIORITE. V. WEAK CRACKLE. CA - NEALED. ALT'N DECREASING WITH DEPTH.

97-UG-53R End of Hole at 169.5'

MINERALIZATION

MINOR DISS. PY. @ FC

@ 126.4

MINOR DISS PY

@ 130.5

3-5% DISS. PY.

@ 134.4

NO VIS SX.

@ 137.5 2-3% DISS SL, GL, PY.

@ 139.1 MOSTLY PY.

@ 140.8 5-7% DISS SX.

1-2% VFG SL, GL, PY, AS IN SILICIC PARTS AS MATRIX TO BX.

@ 150.4


15-20% SX MOSTLY PY, THEN GL, SL + AS. ± SB.

@ 161.6 TRACE DISS. PY.

@ 163.7

TRACE DISS. PY.

GRAPHIC LOG



FT.

120
126.4
130
130.5
134.4
137.5
139.1
140
140.8
143.9
146.9
150
150.4
152.9
155.5
158.8
160
161.6
163.7
167.2
170

SAMPLE

Sample No.	INTERVAL	CORE LENGTH
3004	126.4-130.5	
3005	130.5-134.4	3.9
3006	134.4-137.5	3.1
3007	137.5-139.1	1.6
3008	139.1-140.8	1.7
3009	140.8-143.9	3.1
3010	143.9-146.9	3.0
3011	146.9-150.4	3.5
3012 *	150.4-152.9	2.5'
3013 *	152.9-155.5	2.6'
3014 *	155.5-158.8	3.3'
3015 *	158.8-161.6	2.8'
3016	161.6-163.7	
3017	163.7-167.2	
3018	167.2-169.5	

ANALYTICAL

Q.P.T. Au	Q.P.T Ag	
0.017	0.24	130.5 SV — HW SHEAR
0.013	0.07	0.41, 3.17/8.6
0.013	8.70	
0.001	0.02	
0.149	19.74	
.004	0.29	0.203
0.007	0.39	
0.016	0.90	
0.334	12.40	
0.124	2.58	0.217, 10.37/11.20
0.140	6.99	
0.289	19.77	3.23 m TW
0.004	0.34	FW SHEAR
0.001	0.04	
0.001	0.10	end of hole at 169.5'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT Skukum Creek (Wh) — HOLE No. 87-UG-54R

COORDINATE N. — DEPTH 222'

E. — AZIMUTH

ELEVATION — INCLINATION

DATE STARTED OCT 28 1987 — DRILLED BY Caron Diamond Drilling

COMPLETED OCT 29, 1987 — ASSAYED BY Acme Analytical Lab

HOLE SURVEY — LOGGED BY L. Rowan, R.T. Robinson

BOX	Run	Core	% R	R.Q.D.
1			99	.51
18.5				
2			100	.38
36.8				
3			99	.21
54.3				
4			98	.21
71.2				
5			99	.51
89.2				
6			96	.46
107.6				
7			102	.41

LITHOLOGY, ALTERATION, STRUCTURE

Coarse Grained Propylitic & Potassic Altered Granodiorite

- bleached appearing pinkish-green colour
- 70-80% 3-6 mm qtz & plag x'ls ψ textures from distinct to amorphous, plag varies from mod to strongly altered, 2ndary K-spar where rock is potassic altered
- matics altered to chl as blebs or swirl texture stgs, esp in crackle fractures as revealing
- chl, ca. & fe-oxide on fracture surfaces
- fracture sets at 30, 50, & 66° to C/A, dominant set at 66°

71.5' 6" strongly prop altd And. dyke

82.6' 1' section v. strongly prop alt'd & matic enriched (>60%)

- increase in silicification down length of drill hole

112.6' Sharp contact

Silicified Propylitic Altered Subporphyritic Granodiorite

- 10% ≥5mm plag phenos in aphanitic dk gry matrix

MINERALIZATION

- minor dissem. py

GRAPHIC LOG

70°

70°

FT.
0
10
20
30
40
50
60
70
80
90
100
110
120

SAMPLE			ANALYTICAL	
Sample No.	INTERCEPT	CORE LENGTH	O.P.T. Au	O.P.T. Ag

OMNI RESOURCES INC. PROJECT Skukum Creek (wh) DIAMOND DRILL HOLE No. 87-146-SR Sheet 2 of

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
1259					- Ca in matrix, & as fracture fillings stgs & blebs plag fizz w/ acid; mafics → chl. scale change 1" = 10'	BARE TRACE VFG	120						
8	5 135	4.8	96	.38	- fractures at 30, 60, & 80° to C/A. Sharp contact @ 60° TO C/A.	DISS. PY	130						scale change 1"=10'
	4 139	4.0	100	.23	INTENSELY PROP. ALT'D M-CG, PALE Greenish-GREY GDR. STRONG FIZZ. ABUNDANT CHLORITE FRACTS @ 40 & 60° TO C/A. STRONG CA-HEALED CRACKLE TEXTURE. LOWER CONTACT GRADATIONAL - DECREASING ALTN	TRACE DISS PY.	135.0	3046	130.0-135.0	5.0'	0.001	0.01	
1449	5 142	2.1	70	.19		141.7	139.5	3047	135.0-139.5	4.5'	0.001	0.01	
	5 147	5.0	100	.46	MED. GRN-GRY STRONG PROP. ALT'D GDR. SIMILAR TO ABOVE UNIT, BUT DARKER. ABUNDANT CA IN .1 EINS TO 5 MM. STRONG CRACKLE. MINOR WEAK ROTATION. CA & QZ MATRIX	TRACE DISS. PY. (VFG)	140	3048	139.5-144.0	4.5'	0.001	0.01	
9	5 152	4.3	86	.51	1' SILICIC ALT'D YELLOWISH ZONE @ 147'. SOME CLASTS & FRAGS OF QZ TO 2Cm. PREDOMINANT FRACT. ORIENTATION 60° TO C/A. LOWER CONTACT GRADATIONAL - ROCK JUST BECOMES LIGHTER	153.0	144.0	3049	144.0-149.0	5.0'	0.001	0.07 0.06	
	5 157	4.6	92	.17	LT. GRN-GRY F-M.G. STRONG PHYLLIC ALT'D GDR. INTENSE CRACKLE TO WEAK BXXN. MATRIX OF CL & GREY QZ. VERY CHEWEDUP & QZ HEALED. NO REAL DOMINANT FRACT ORIENTATION. SOME 50°, SOME 60°, SOME 90°. BASE CONTACT GRAD. BRXXD.	ALMOST NO SX MIN. JUST A FEW VFG PY XTALS.	149.0	3050	149.0-153.0	4.0'	0.001	0.27 0.02	
1599	5 162	5.0	100	.27	V. HARD VFG WEAKLY BANDED, LT GREENISH-TAN RHYOLITE. BANDS ARE OF CHLORITIZATION - SILICIFICATION. QZ IS GREYISH. FROM 162.0 - 164.5 IS A 1-2 cm WIDE CALCIFIED SHEAR DOWN CORE AXIS. MOD. CRACKLE TEXTURE WITH SMALL OFFSET ON FRACTS. MINOR TO MOD. ROTATION IN NARROW BANDS WITH LIGHTER, GROUND RHY MATRIX. BANDING FROM 90-0° TO C/A. BASE SHARP, CALCITIC 20° TO C/A.	153.0	153.0	3051	153.0-158.6	5.6'	0.001	0.07 0.28	
	5 167	4.8	96	.55		BARE TRACE DISS UFG PY & VR BLACK MATERIAL IN VERY FEW THIN FRACTS.	158.6	3052	158.6-163.8	5.2'	0.001	0.05	4W
10	5 172	5.0	100	.44	2 PT DK GRN-GRY, COARSER-GRAIN TO MODERATE WITH STRONG CRACKLE & V. ABUNDANT CA INFILLING, THEN FRAGS OF V. ALT'D GDR & RHY AS ABOVE, THEN FRAG OF DK GRN-GRY. BROADLY LARGE-CLAST BXX. BASE 60°, 6mm LTR OVER 5cm.	168.2	163.8	3053	163.8-168.2	4.4'	0.001	0.62	0.001, 0.04 / 17.1'
	5 177	4.8	96	.56	LT GRN-GRY RHY AS ABOVE BUT SOFTER, LO TH LESS QZ & MORE CA & CL. STRONG CRACKLE WITH SOME ROTATION. CA & LT. GROUND RHY MATRIX. FRACTS @ 45-50° TO C/A. BASE CONTACT GRADATIONAL, SHATTERED BX. BLACK DIATREME BX INTRUDES BASE OF RHY FOR 30 cm.	BARE, RARE TRACE PY - DISS-1 IN CA BLEBS. 171.3	168.2	3054	168.2 -171.3	3.1'	0.001	0.01	
1725						TRACE VFG DISS PY. 175.7	171.3	3055	171.3-175.7	4.4'	0.002	0.06	
	5 182	4.8	96	.38	RHYOLITE AS ABOVE BUT BRECCIATED WITH BANDS OF DIATREME BRECCIA TO 40 Cm. ~ 50% RHY, 50 % DIATREME. DIATREME IS V FG GROUND BLACK MATRIX WITH CLASTS OF ROUND-SUB-ROUND GDR, QZ & RHY. MAY BE SMALL AMT OF SX IN DIATREME. BANDED & FRACTURED @ 40° TO C/A. BASE CNT BROKEN, BXD, GRADATIONAL.	TRACE TO MINOR DISS PY 183.5	175.7	3056	175.7 - 180.0	4.3'	0.022	1.36	
	5 187	5.0	100	.32	Zone similar to above, but totally sheared. Appears to exhibit remnant banding. May have GDR. V. soft, crumbled, partly ground to clay. Base bxd, broken	TRACE TO NO DISS. PY. 186.0	180	3057	180.0-183.5	3.5'	0.116	7.02	0.004, 5.06 / 6.0'
11	5 192	5.0	100	.60	RHYOLITE BRECCIA WITH QZ SX MATRIX. CLEAN, FG. HARD LT GRN-TAN @ TOP GRADING TO COARSE GR. SOFTER. MORE ALT'D, DARKER @ BASE. WEAK CRACKLE HEALED BY QSBX & CA & YELLOW QZ. WEAK BANDING @ 40-45° TO C/A. MOST FRACTURES ALSO 40 TO 45° TO C/A. WEAK TO MOD. PROP. ALT'N. BASE CNT. FRACT. & BROKEN.	3-4% SL, GL, PY, AS WITH QZ AS MATRIX TO BXD. RHY. 195.0	183.5	3058	183.5-186.0	2.5'	0.064	2.73	
1958	5 197	5.0	100	.16			186.0	3059	186.0-190.3	4.3'	0.033	0.28	
	5	5.0	100	.49	STRONGLY SHEARED, BROKEN, BXYD, SOFT; ALT'D COARSER-GRAINED MED. GRN RHYO. FIRST 25 cm CLAYEY, CRUMBLE SHEAR, THEN SHEARED & BXD & ABUNDANT CL. CLAY, CA & YELLOW WAXY QZ. FRAGS OF GDR, LT TAN RHY & QZ SBXX. FRACTS @ 30, 60 & 90° TO C/A.	BARE TRACE DISS PY, & MINOR SX IN QSBX CLASTS.	190.3	3060	190.3-195.0	4.7	0.003	0.11	
							195.0	3061	195.0-198.7	3.7	0.002	0.20	
							198.7	3062	198.7-202.8		0.001	0.03	

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-UG-55R Sheet 3 of 3

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERVAL	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag	
	202				WEAK BANDING IS 0° TO C/A. BASE CONTACT SHARP, BANDED @ 40° TO CORE AXIS.			200						
	5					202.8		202.8						
12		5.0	100	.54	TEXTURALLY SIMILAR TO ABOVE UNIT; BUT COMPOSED MOSTLY OF STRONGLY PROP ALT'D F-M.G MED-LT.GRN-GREY GDR. A FEW CLASTS + BLEBS OF QZ, RUT, + ASPY AT TOP DECREASING IN DEPTH. BANDED + FRACTURED @ 40-45° TO C/A. BASE CONTACT BROKEN, GRAD. ABUNDANT CHLORITE INFILLING + FLOODING.	TRACE VFG DISS-PY + MINOR SX, CL, PY, AS IN QZ BX FRAGS.			3062	198.7-202.8	4.1'	0.001	0.03	0.008, 18 /P.S
	207					208.8			3063	202.8-208.8	6.0'	0.005	0.33	FW
	5				LT GRN-GREY, MED GR. INTENSELY PROP ALT'D GDR. STRONG FIZZ, ABUND. SE, EP, CL, CA. STRONG CRACKLE FILLED + HEALED BY ABOVE MINERALS. MINOR ROTATION OF FEW CLASTS. FEW FRACTS. NO PREFERRED ORIENTATION. BASE CAT. GRAD. COLOR CHANGE.	TRACE TO NO DISS. PY.		210						
	212	5.0	100	.62		212.9		212.9	3064	208.8-212.9	4.1'	0.001	0.05	
213	5				DK GRN-GRY M.G. GDR. STRONG PROP ALT'N. MOD CRACKLE + CA HEALING. INTENSE ALT'N AROUND & WITHIN FRACTS. NO OXIDE, THEN 30 cm AS ABOVE UNIT. 0° FRACTS @ 40° TO C/A. BASE CAT. SHARP, ALTN OF THIS UNIT	TRACE TO NO DISS. PY			3065	212.9-215.2	2.3'	0.002	0.34	
	217	5.0	100	.60		215.2		215.2						
13	5				VFG - MED. GRAINED MED. GREEN-GREY GDR. WEAK CRACKLE - WELL-HEALED. FAIRLY ABUNDANT CA + QZ STRINGERS. FRACTURES AT 20, 45 + 90° TO C/A. QZ-FLOODED ZONE @ 216.0'. COARSER GRAINED AT END OF HOLE.	TRACE TO NO DISS PY.			3066	215.2-219.7	4.5'	0.001	0.01	
222	222	4.7	94	.40	87-UG-55R End of Hole at 222'			220						
							Eo.H							End of hole at 222'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT Skukum Creek (Wh) | HOLE No. 87-46-55R
COORDINATE N. | DEPTH 368'
E. | AZIMUTH
ELEVATION | INCLINATION
DATE STARTED OCT 29, 1987 | DRILLED BY Caron Diamond Drilling
COMPLETED NOV 2, 1987 LOGGED NOV 12/87 | ASSAYED BY Acme Analytical Labs
HOLE SURVEY | LOGGED BY R.J. Robinson, L.R.

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag
1			96	.30	Propylitic, Silicified, Potassic Altered Quartz Monzonite - colour varys from pinkish grn-gry to pinkish gry to lt gry depending on strength and type of alteration - coarse grained, crystal size 2-5 mm for plag, k-spar and quartz; mafics 10-15% w/ occasional 1-2' sections of 35-50%, mafics altrd to swirl texture chlorite; plag, k-sper & qtz vary from clearly crystalline to amorphous in texture - fractures at 40, 60 & 80° to C/A minor calcite, chlorite, sericite & occasional epidote on fractures	wk trace dissem cubic py		0					
17.9								10					
2			91	.28				20					
35.4								30					
3			99	.23				40					
52.9								50					
4			92	.17				60					
69.0								70					
5			91	.13				80					
86.5								90					
6			89	.09	- increasing silicification, potassic alteration and amorphous texture to rx			100					
103.2								110					
7			96	.10	115.5' gradational contact Potassic Altered Silicified Quartz Monzonite			120					
119.5													

OMNI RESOURCES INC. · PROJECT Skukum Creek (Wh) · DIAMOND DRILL HOLE No. 87-##55-S Sheet 2 of 4

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
8			73	.11	C.gr. & strongly potassic altered, w/ wk prop. pinkish gry colour moderately to strongly fractured fracture sets at 30, 40, 70, ~~80~~ & 80°			120 130					
9			89	.14	149.6' gradational contact Fine Grained, Potassic Altered Quartz Monzonite u.f. gr. to aphanitic, pinkish gry, no matics fractures at 30, 50, 70 & 80° to C/A			140 150					
165					154-164 does not exist, core blocks mis-labeled, error was not discovered by company clerk until it was too late			160					
10			81	.18	166.6' gradational contact Coarse Grained Propylitic & Potassic Altered Quartz Monzonite - Pinkish gry colour from alteration Crystal size 2-5mm plag & qtz & K-spar, some K-spar appears to be 2ndary; matics ≯ 15% w/ ≤ 20-25% in patches, matics altered to blebs of chlorite			170 180					
184.6					- Calcite, chlorite, sericite w/ minor epidote on fractures								
11			90	15	- fracture sets at 15, 45, 70 & 90° to C/A			190					
203.6								200					
12			79	.03				210					
216.9													
13			90	.04				220					
231.6					- 230 1" calcite band at 30° to C/A			230					
14			83	.04				240					
247.0					- Very badly fractured core			250					
15			86	.03				260					
263.0					~~decreasing~~ - decreasing matics and texture becoming amorphous			270					

OMNI RESOURCES INC. PROJECT Skukum Creek (Wh) DIAMOND DRILL HOLE No. 87-U606R Sheet 3 of 4

BOX	Run	Core	% R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
16			81	.27	-279' 1' section w/ strong propylitic alteration chlorite in fine anastomosing stringers Scale change 1" = 10'	TRACE UF.G.		270						
289								280						
						DISS PY		290						Scale change at 290'
17	5	4.8	96	.50	AS ABOVE WITH INCREASING CRACKLE TEXTURE AT DEPTH. (FAIRLY WELL-HEALED)									
	297				GRADATIONAL LOWER CONTACT.	297.0		297.0						
299.0	5	4.8	96	.42	STRONGLY PROP. ALT'D LT. GRN-GRY M-FG GDR. SWIRLED AND WEAKLY BRECCIATED IN NARROW ZONES @ 301' IS 25 cm BAND STRONGLY RUSTY WEATHERED HEALED SHEAR. ABUNDANT CL, SE, EP, CA. MINOR YELLOW + GREYISH QZ.	TRACE VFG DISS PY.								
	302				BANDS w RUSTY CALCITIC FRACTS @ 40° TO C/A. BASE: SHEAR @ 65° TO C/A.	304.8		300	3115	297.0-302.0	5.0'	0.001	0.01	
	5	4.5	90	.22				302.0	3116	302.0-304.8	2.8'	0.001	0.01	
18	307				GDR AS ABOVE, BUT EXTREMELY SHEARED AND CRUMBLY. TOTALLY SHEARED + MOSTLY CA-INFILLED TO 307. THEN U-CRUMBLY — NOT CEMENTED. MUCH CORE LOST BTWN 307 + 311'. Some GRITTY GREY CLAY, BUT MOSTLY JUST U-BROKEN, CRUMBLED EXTREMELY PROP GDR. BASE IS END OF MAIN SHEAR, NO ANGLE, LIGHT MORE SOLID.	MINOR TO 1% DISS PY on OTHER, DARK VFG SX.		304.8	3117	304.8-307.0	2.2'	0.148	5.48	
	4	1.1	28	Ø				307.0						HW SHEAR ZONE. CORE LOST.
	311					310.0		310	3118	307.0-311.0	4.0'	0.060	1.95	
	2 313	1.1	55	Ø	LT GRN-GRY MG GDR AS ABOVE. VERY STRONGLY PROP. ALT'D. MODERATELY CRUMBLED UP & SHEARED, BUT NOT AS MUCH AS UNIT ABOVE. TO BROKEN UP TO GET SPECIFIC FRACT ORIENTATION. UNIT IS CM TO 2 FAMILIES OF QSBX-FRACS ARE BADLY GROUND. BASE CONTACT IS GROUND.			313.0	3119	311.0-313.0	2.0'	0.001	0.03	
	5	4.0	80	Ø		TRACE DISS PY OVERALL 15 cm HYSKER 2 30% SX		316.5	3120	313.0-316.5	3.5'	0.057	6.83	
	318					318.5 Py, GL, SL, AS, SB.			3121	316.5-317.5	1.0'			missing assay
319.3	5	4.7	94	.38	LT-GRN-GRY MG GDR LESS PROP. ALT'D THAN UNITS ABOVE. MORE COMPETENT AND LESS SHEARED, SWIRLED AND FRACTURED. FRACTS @ 30, 50 + 90° TO C/A. SOME FRACTS CA LINED AND RUSTY-WEATHERED. ABUNDANT CA + SERICITE. BASE CONTACT COARSE BRECCIATED	TRACE DISS PY.		317.5	3122	317.5-320.8	3.3' @	0.006	0.31	
	323					323.7		320	3123	320.8-323.7	2.9'	0.001	0.12	
	2 325	1.3	65	.54	RELATIVELY COARSE GRAINED, MED. GRN-GRY - TO DK GRY RHYOLITE. @ 325 IS NARROW (6 cm) RUSTY-WEATHERED, SANDY ZONE.			323.7						
	3 328	3.0	100	.33	FRACTS @ 45 + 60° TO C/A. BASE SHEAR @ 60° TO C/A	MINOR DISS PY. 326.9		326.9	3124	323.7-326.9	3.2'	0.001	0.20	
19	5	5.0	100	.33	CLEAN, HARD, UFG, LT GRN-TAN RHYOLITE. RUSTY FRACTURES THROUGHOUT - WEAKLY PROP. ALT'D. WEAK CRACKLE OVERALL WITH ZONES TO 50 cm OF ACID BRXN. SLIGHT ROTATION WITH CRUSHED RHY MATRIX. A FEW MINOR, NARROW CLAYEY SHEAR ZONES. NARROW BAND OF PY @ 335.5'.			330	3125	326.9-332.0	5.1'	0.001	0.15	
	333							332.0						
	5	5.0	100	.30		1.2mm BAND PY cutting CORE @ 30° TO C/A, OTHERWISE JUST BARREN TRACE UFG DISS PY.			3126	332.0-337.0	5.0'	0.002	0.29	
338	338							337.0						
	5	4.9	98	.58				340	3127	337.0-342.0	5.0'	0.003	0.24	
	343				FRACTS @ 30, 45, 60 + 80° TO C/A. SOME X-CUTTING.			342.0						
20	5	5.0	100	.38	MORE WEATHERED @ DEPTH MN + Fe OXIDES ON FRACTS + THROUGH CORE.				3128	342.0-347.0	5.0'	0.024	0.37	
	348							347.0						
	4	3.4	85	.25	GENERALLY MORE CRACKLED @ DEPTH. MORE CA INFILLING.			350	3129	347.0-352.0	5.0'	0.003	0.20	
	352				BASE CONTACT & GRADATIONAL. DECREASING ALT'N.	352.0		352.0						
	5	6.0	100	.58	MED. GRY RHY + WEAK PROP ALT'N. MOD. CRACKLE OVERALL. FG BLACK INFILLING, MAY BE SX. MANY FRACTS V. RUSTY WEATHERED. 2 BANDS VFG SX CUTTING CORE @ 70°. BROKEN 5 cm WIDE.	2 x 5 cm WIDE BROKEN VFG BK GRN SX.			3130	352.0-356.0	4.0'	0.012	6.16	

OMNI RESOURCES INC. PROJECT Skukum Creek (WH) DIAMOND DRILL HOLE No. 87-46-56R Sheet 4 of 4

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
356	357				BASE CONTACT BROKEN UP.	AS ABOVE		356.0	3130	352.0 - 356.0	4.0'			
	5				LT. TAN RHYOLITE. FAIRLY HARD, UFG. V. WEAKLY ALTERED, BUT STRONGLY WEATHERED. DENDRITIC Mn OXIDES THROUGHOUT.	TRACE DISS PY			3131	356.0-359.2	3.2'	0.039	2.80	
21		4.9	98	.28	ORANGE & BROWN RUSTY FRACTURES. 45 @ 90° TO C/A.			360	3132	359.2-362.0	2.8'	0.008	1.03	↑
	362				WEAK - MOD. CRACKLE BRECCIA. SOME RUSTY-WEATHERED SEAMS. BASE CONTACT U-STRONGLY WEATHERED FRACT.	362.0		362.0						
	6				SUB-PORPHYRITIC GDR. - QZ + FS XTALS TO 6 mm IN DARK GRY, APHANITIC GROUNDMASS. WEAK, CA-HEALED CRACKLE. FRACTS RUSTY WEATHERED @ 30, 45, 60 + 90° TO C/A.	TRACE DISS PY.			3133	362.0-368.0	6.0'	0.001	0.07	
368	368				LAST 30 cm REGULAR COARSE GRAINED, WEAKLY ALTD GDR. 87-46-56R End of Hole at 368'			368' E.o.H						end of hole at 368'

0.009 Lab / 44.5

OMNI RESOURCES INC
DIAMOND DRILL HOLE LOG

Reason for Drilling: _____

Explanation of Results: _____

LEGEND

PROJECT: Skukum Creek — HOLE No.: 87-46 SGR.
COORDINATE N. _____ — DEPTH: 231.5'
E. _____ — AZIMUTH: _____
ELEVATION: _____ — INCLINATION: _____
DATE STARTED: _____ — DRILLED BY: Caron Diamond Drilling
COMPLETED: _____ — ASSAYED BY: Acme Analytical
HOLE SURVEY: Longshot 25/26 — LOGGED BY: RSR

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	SAMPLE: INTERCEPT	SAMPLE: CORE LENGTH	ANALYTICAL: O.P.T. Au	ANALYTICAL: O.P.T. Ag
1	20.6	16.6	81	40	COARSE-GRAINED GDR: MED. GRN-GRY. MOD PROP. ALT. MOD POTASSIC ALT'D. V. BROKEN. UP. MUCH CORE LOST AT TOP OF UNIT. ABUNDANT CA VEINING & FRACT. FILLING. MOD. TO ABUNDANT HEMATITE IN CA. WEAK TO MOD. CA-HEALED CRACKLE. FRACTURES AT 20, 45, 55, ~90° TO C/A.			0.0					
20.6								10.0					
2	18.8	17.8	95	37	MANY FRACTURES CA-LINED. MUCH RUSTY WEATHERING. BROKEN UP @ 25-26', 12-14', 45-46' DARKER, GREENISH BLACK FROM 39-48. JUST MORE MAFICS.	TRACE DISS PY		20.0					
39.4								30.0					
3	18.3	17.8	97	34	GRADATIONAL LOWER CONTACT.	55.4		40.0					
57.7								50.0					
4	22.7	17.5	77	22	COARSE-GRAINED GDR. BROWNISH-GREENISH-GREY. STRONGLY PROP. ± POTASSIC ALTERED. ALL FELDSPARS EITHER REDDISH BROWN OR GREEN. STILL RUSTY-WEATHERED FRACTURES. STILL QUITE BROKEN UP OVERALL. OLDER CRACKLE HEALED WITH BLACK UNIDENTIFIED MATERIAL. SOME ZONES BRIGHT RED POTASSIC ALT'D. MINT FRACTS @ 40-45° - BASE CONTACT GRADATIONAL.	TRACE DISS UFG PY.		60.0					
80.4						78.0		70.0					
					M-G GDR. VERY DARK. ~50% MAFICS. & WEAK PROP POTASSIC ALT'N. FRACTS @ 40 & 75° TO C/A. WEAK, DARK-HEALED CRACKLE. BASE CONTACT SHARP, GRADUAL.	BARE TRACE DISS PY.		80.0					
						85.5		90.0					
5	17.1	17.1	100	49	MG. QMZ. MED. GRN-TAN. MOD-STRONG PROP ± POTASSIC ALTERATION. WEAK CHLORITE, CALCITE AND BLACK HEALED MOD CRACKLE OVERALL. ALMOST ALL FRACTURES BROWN OR ORANGE RUSTY-WEATHERED.			100.0					
97.5								110.0					
6	17.3	17.3	100	28	MOST FRACTS @ 25, 30, 45 & 75 & ~90° TO C/A. SOME FRACTS SLIGHTLY CRUMBLY & CLAYEY. FROM 115-128 IS MORE GREEN, LESS POTASSIC ALT'D. JUST STRONG PROP. ALT'D. AND WITH MORE MAFICS — UP TO 40-50% IN			120.0					
114.8													

YUKON RESOURCES INC. PROJECT Skukum Creek (WH) DIAMOND DRILL HOLE No. BZ-96-16R Sheet 2 of 3

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag
7	17.0	17.0	100	26	A FIVE FOOT SECTION FROM 115-120'	JUST BARE TRACE UFG DISS PY		120.0					
					AFTER DARK ZONE JUST BACK TO BRN, GRN-GRY MG. GME. SOME BANDS & ZONES OF V. STRONG, RED POTASSIC ALT'N.			130.0					
8	16.7	16.7	100	33	VERY LITTLE CALCITE			140.0					
					BASE GRADATIONAL	141.8		150.0					
9	17.4	17.4	100	29	MED-DK GRN-GRY M-CG GDR, MOSTLY GREY, WITH JUST LIGHT GREEN CALCITE / SERICITE / CHLORITE ALT'N. SOME CLAY ON FRACTS & SHEARS. STILL STRONGLY BROKEN UP. MINOR GREY CALCEDONY QUARTZ VEINS. MOD-STRONG PROP ALT'N. FRACS @ 50, 70 & 90° TO C/A	TRACE DISS. PY		162.0					SCALE CHANGE 1" = 20'
	163.0				SCALE CHANGE: 1" = 20'			162.0					
TBSA	5	5	100	38	STRONG, CA-HEALED CRACKLE OVERALL.	(UFG)		166.9	3187	162.0-166.9	4.9'	0.003	0.27
	168.0				BASE CONTACT SHARP, FLOW @ 30° TO C/A	166.9		169.9	3188	166.9-170.2	3.3'	0.008	0.52
	5	5	100	56	LT GREEN RHY & M-G-GDR IN MATRIX OF DIATREME BRXG. CLASTS V. SMALL AT TOP - BASE MOSTLY WEAKLY BXXD GDR & BANDS OF DK GREY HEALED DIATREME. BASE BROKEN UP	BARE TRACE DISS. PY.		170.0 170.2					
	173				LIGHT TAN, SILICIFIED, V.F-G. RHYOLITE U. HARD, STRONG, WELL-HEALED CRACKLE. MINOR ROTATION IN AUTO BX. NO SULFIDE MATRIX.	170.2		174.2	3189	170.2-174.2	4.0'	0.001	0.10
10	5	5	100	64	MINOR FLOW BANDING AT TOP. BASE CONTACT MT. 50° FRACTS 50° TO C/A	TRACE DISSPY		174.2	3190	174.2-176.6	2.4'	0.001	0.06
	178				AUTO BXXD MG GDR. STRONG PROP & SMX ALT'N. 8% QTZ & CLAY @ 176.2' AB. CHLORITE & SERICITE. FRACS @ 20 & 45° SHEAR 75° BASE 20°	TRACE DISS PY.		176.6	3191	176.6-181.1	4.5'	0.001	0.03
	5	5	100	92	ANDESITE: MED TO DARK GRN-GREY AT TOP, LIGHTENING W DEPTH. BECOMING MED. GRN @ DEPTH.			180.0 181.1	3192	181.1-186.1	5.0'	0.001	0.03
1830	183				WEAK BANDING & TEXTURE @ 45° TO C/A. TOP CONTACT FAULT, NOT FLOW. MEDIUM HARD. BARELY SCRATCHED BY KNIFE.	JUST BARE TRACE VFG DISS PY.		186.0	3193	186.1-190.9	4.8'	0.001	0.04
	5	5	100	32	MINOR CA STRINGERS & COATING ON FRACT. SURFACES. V. STRONG FIZZ-CA OVERPRINT. MOST FRACTS @ 45° TO C/A.			190.0 190.9	3194	190.9-194.1	3.8'	0.001	0.06
	188				RUSTY WEATHER ON SOME FRACTS.			191.7	3195	194.1-195.8	1.7'	0.069	0.34
11	5	5	100	86	FLOW BANDING @ 40° AT BASE. ABUNDANT YELLOW QZ IN THIN CLEAVAGES.			MSB 195.8	3196	195.8-199.8	4.0'	0.005	0.29
	193				BASE CONTACT BXXD, GRADATIONAL	194.1		200.0	3197	199.8-204.3	4.5'	0.001	0.35
	5	5	100	70	MINOR BRECCIA: ANG. RHY. FRAGS OF OAR IN BLACK MATRIX. STRONG & RANDOM 40° TO C/A. CONTACT CHLORITE RICH FOR 20 CM @ BASE. CONTACT BROKEN UP.	MINOR TO 2% DISS PY		204.3	3198	204.3-209.0	4.7'	0.002	0.10
	198				RHYOLITE: CLEAN, HARD, LT. FAINTLY CARBONISH TAN. SLIGHTLY MINERALIZED. STRONGLY AUTO BXXD. WEAK HEALED CRACKLE. CRUSHED UP SHEAR FOR 30 CM @ 197'. BANDING & ABUNDANT FRACTS @ 45° TO C/A. MINOR CHLORITIZATION. MOST FRACTS RUSTY WEATHERED. BASE UNEVEN BROKEN BRECCIA.	MINOR SX MINERALIZATION IN GREY QZ		209.0	3199	209.0-213.7	4.7'	0.004	0.01
TBSS	5	5	100	24	MINOR MINZD GREY CALCEDONIC QZ.	MOSTLY PY, MINOR SL, AS CL & SB.		210.0 213.7	3200	213.7-218.0	4.3'		
	203				DARKER GREEN, SOFTER, MORE ALT'D RHYOLITE: VERY CHLORITIZED UP AND SHEARED. VERY, VERY SOFT. V. ABUNDANT CA.	204.3		215.0					
12	5	5	100	88	INTENSE PROP. ALT'N. FRAGS OF LT & DK GRN RHY IN MATRIX OF V. MASSIVE CRYPTO RHY. & CA. FRAGS & WEAK BANDING @ 20-40° TO C/A. GRN-DIA. BX IN BASE SHEAR. BASE CONTACT CLEARLY SHEARED 45° TO C/A.	0 TO BARE TRACE DISS PY.							
	208				FINE TO MED. GRAINED, LT GREY PORPH. GDR.	213.3							
	5	5	100	74									
	213												

GIANI RESOURCES INC. PROJECT SKUKUM CREEK DIAMOND DRILL HOLE No. 87-UG-16R Sheet 3 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERVAL	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
	5 218	5	80	52	FSPARS + MINOR QTZ + MAFICS TO 2 mm IN MATRIX OF VFG TO APHANITIC GROUNDMASS. MINOR CA STRINGERS + FRACT-HALOS. WEAK, WELL-HEALED PERV CRACKLE - FRACTS @ N 60° TO C/A. A FEW BANDS OF GREENISH-GREY QTZ + A FEW FRAGS OF WHITE QTZ.			215.0						
200	4 224	4	100	65	BANDS @ 40° TO C/A. BASE CONTACT SHARP FLOW @ 45° TO C/A.			218.0	3200	213.7 - 218.0	4.3'	0.001	0.03	
	4.5 227.5	4.5	100	80	DARK, GREENISH, BROWNISH BLACK ANDESITE. VFG. BLACK SPECKS + GREENISH-GREY STRINGERS. FRACTS ± HALOS 30° BASE IMBRICATE FLOW 30° TO C/A	222.6		218.0						
					FINE-GRAINED, MEDIUM GREY PORPHYRITIC GDR AS ABOVE.	No VIS SX.		220.0	3201	218.0 - 222.6	4.6'	0.003	0.05	
	5 232.5	5	100	48	MINOR BANDING ± @ FLATTENED BLACK XENOS ALIGNED 40° TO C/A - MINOR, WELL HEALED CRACKLE. MINOR CA STRINGERS + FRACT-FILLING MOST FRACTS 30 OR 40 ° TO C/A.	224.4		222.6	3202	222.6 - 224.4	1.8'	0.001	0.01	
					231.5 END OF HOLE.			224.4	3203	224.4 - 228.5	4.1'	0.001	0.02	
								228.5						
								230.0	3204	228.5 - 231.5	3.0'	0.001	0.03	
								231.5						231.5 END OF HOLE
								240.0						

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling

Explanation of Results

LEGEND

PROJECT	SKUKUM CREEK.	HOLE No.	87-UG-57-K
COORDINATE N.		DEPTH	282'
E.		AZIMUTH	
ELEVATION		INCLINATION	
DATE STARTED	NOV. 5, 1987	DRILLED BY	CARON DIAMOND DRILLING
COMPLETED	NOV. 9, 1987 LOGGED NOV 14, 1987	ASSAYED BY	ACME ANALYTICAL
HOLE SURVEY		LOGGED BY	R.T. ROBINSON

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag
1 16.5	16.5	16.5	100	43	MG. WEAKLY POTASSIC ALT'D. PINKISH-TAN QZ MONZONITE. WEAK CRACKLE, ABUNDANT CA FRACT-FILLING. FRACTS @ 30 & 55° TO C/A. QUITE BROKEN UP. NS-7% MAFICS	BARE TRACE DISS VFG PY		100					
					BASE CONTACT GRADATIONAL.	13.4							
2 24.0	17.5	17.5	100	40	M.G. GDR ± BANDS OF QMZ AS ABOVE. WEAK TO MOD CRACKLE, ABUNDANT CA INFILLING. WEAK PROP ALT. FRACTS @ 65 & 90° TO C/A. QUITE BROKEN UP. BASE SHARP FRACT @ 85° TO C/A.	0 TO TRACE DISS PY.		200					
						26.0							
3 49.8	15.8	15.8	100	30	QMZ AS AT TOP OF HOLE. WEAK TO MOD. CRACKLE OVERALL. ABUNDANT CA FRACT-FILLING & BANDS & STRINGERS. SOME RED HEMATITE IN CA BANDS. WEAK PROP & POTASSIC ALT'N AT TOP, INCREASING PROP ALT'N & DEPTH.	BARE TRACE DISS VFG PY.		300					
4 70.0	20.2	19.5	97	33	ONLY ~7-10 % MAFICS OVERALL, WITH BANDS TO 20 cm WITH VFG & NO MAFICS. MAGMATIC SEGREGATION AS NO REAL CONTACTS? REG. QMZ. FRACTS @ 65 & 85° TO C/A.			400					
								500					
5 89.7	16.7	16.7	100	41	CONTACT BTWN QMZ & GDR BELOW IS SHARP, FLAT @ 45° 82-84.0: BLACK, VFG ANDESITE DYKE IN GRANODIORITE BAND. GDR GRADES BACK INTO PINK QMZ.			600					
					BASE CONTACT GRADATIONAL.	91.4		700					
6 108.9	18.2	18.2	100	59	MED-COARSE-GRAINED, MOD. PROP. ALT'D MED GRN-GRY GRANODIORITE. MOD. WELL (CA) HEALED CRACKLE. ABUNDANT CA FRACT-FILLING & BANDING & STRINGERS. COARSER-GRAINED & DEPTH	0 TO TRACE DIS DISS VFG PY		800					
								900					
7 128.8	18.8	18.8	100	52	BANDS & BLOCKS OF QMZ AS ABOVE, BUT ± MORE MAFICS (TO 20cm). FRACTS @ 55 & 80-85° TO C/A. INCREASING INTENSE SILICIC ALT'N STARTING @ 113.0' FEW NARROW ZONES OF FIRST; THEN COMPLETELY INT. SILIC. ALT'D BY BASE			1000					
					BASE CONTACT ABRUPT	119.3		1100					
								1200					

OMNI RESOURCES INC. PROJECT Skukum Creek (ext. claims) DIAMOND DRILL HOLE No. 87-465K Sheet 2 of 3

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	INTERVAL	CORE LENGTH	ANALYTICAL O.P.T. Au	O.P.T. Ag	
					QUARTZ MONZONITE - MOD-STRONG PROP ALT'N, INTENSE SILICIFICATION. SOME ZONE ALMOST COMPLETELY QUARTZ-FLOODED.	TRACE DISS PY. TRACE SL IN QZ BANDS.		130						
8	17.7	17.7	100	61	WEAK CRACKLE, ABUNDANT BLACK, HAIRLINE FRACTURES ORIENTED 30-40° TO C/A - MINOR CA IN FRACTS + AFEW STRINGERS/BANDS. SOME ZONES QUAR BROWN UP, FRACTS @ 30, 60 + 85° TO C/A. ABUNDANT CL/SE/EPI INCREASING WITH DEPTH			140						
9	18.6	18.6	100	46	FRACTURES @ 45 + 90° TO C/A. MORE CALCITE WITH DEPTH. CRACKLE TEXTURE INCREASING. SOME CHANGE 1" = 10'			150						
								160						SCALE CHANGE 1"=10'
	5	5	100	76		TRACE DISS PY		170	3159	170.3-175.3	5.0'	0.001	0.06	FW CONTACT 175.3'
					BASE CONTACT GRADATIONAL.									
	5	5	100	90	BANDED, SHEARED, BXXD, WEAK PROP. ALT'N, STRONG SILICIC ALT'N. MED. GRY C.G. C.DR. BANDING VFG GRN-GRN. WELL-HEALED SHEARS. MINOR CA OVERALL. V. WEAK LATE CRACKLE. BANDS ? FRACTS @ 45° TO C/A. BASE CNT. RAGGED BRECCIA. BANDED ~ 30°	TRACE DISS PY		180	3160	175.3-180.3	5.0'	0.017	0.51	
	5	5	100	70	QSBXBX IN DK GRN - COARSE GRAINED RHYOLITE. BRECCIATED. BANDED BROKEN UP RHY., ± N 30° % QSBX. BASE CONTACT CLAYEY GREENISH SHEAR @ 45° TCA	8-10% SX SL, GL PY, AS, SB.		190	3161	180.3-184.3	4.0'	0.242	11.57	
	5	5	100	52	BANDED, SHEARED, INTENSE PROP. ALT'D M.G. GDR. ABUNDANT CL, CA, SE, EP. BANDED @ 45° TO C/A. SEVERAL CLAYEY SHEARS @ 45° TO C/A. BASE SHR 45°				3162	184.3-187.0	2.7'	0.001	0.13	
	5	5	100	50	BXXD, SHEARED. MT'D GDR. V. ABUNDANT CA STRINGERS, BANDS + FRACT. FILLING. A FEW FRACTS OF QSBX IN GDR. WELL-HEALED, 15 cm SHEAR @ 188'; CRUMBLED SILTY SHEAR @ AN. FRACTURE @ 45°. BASE MOD. FLOW BANDED. VERY BROKEN UP - CRUMBLED + SHATTERED - LT GRN-TAN VFG RHY. ABUNDANT CA STRINGERS. MOD. PROP ALT'N. BANDING @ 40° TO C/A. NO PREFERRED FRACTURE ORIENTATION. BASE CNT BROKEN UP.	MINOR DISS PY + 190.0 4% MOD SX IN QZ VEINS. BARR TRACE DISS. PY.			3163	187.0-190.0	3.0'	0.001	0.36	
									3164	190.0-194.5	4.5'	0.001	0.25	
	2.5	2.5	100	0	INTENSELY SHEARED, DARKER GRN- TO COARSER GRAINED RHY. COMPLETELY BROKEN UP - CRUMBLED. MINOR CLAY + NO INDICATION OF FRACTURE ORIENTATION. BASE CONTACT SHARP SHEAR 45° TO C/A	194.5 NO VIS SX			3165	194.5-197.5	3.0	0.001	0.28	
	2.5	2.5	100	0	V. DK GRN RHY. V. BROKEN UP, SOME TEXTURE AS ABOVE, BRAC. SOME SHEARING. BOX BROKEN UP	NO VIS SX			3166	197.5-198.5	1.0	0.021	0.42	
	5	5	100	52	HARD, VFG, LT GRN-TAN, BARELY ALT'D RHY. ABUNDANT E-CUTTING SHEARS. V. CLAYEY + CHLORITIC. STRONG CL-HEALED CRACKLE. FRACTS @ 15, 40, 55 + 90° TO C/A. BASE CNT. SHARP - QZ VN @ 45° TO C/A	NO VIS SX		200	3167	198.5-202.3	3.8'	0.001	0.14	
	5	5	100	44	3cm QSX VEIN, THEN JUST RHY - SLT CHARGE CA, BANDED - GREEN. ABUND. CA, STRONG WELL-HEALED CRACKLE. MINOR, CHLORITE SHEARING. MOST FRACTS N 90° TO C/A. BAS + CONT. 70° TO C/A. SHARP. BRECCIA OF RHYOLITE IN GDR. HARD, LT GRN-TAN RHY + DK. GRN-GRY STRONG PROP ALT'D GDR. NO FRACT SET. AN CRACKLE. BASE CNT. BROKEN	30% SX IN QZ, MINERALIZE TRACE DISS SX. NO VIS SX.			3168	202.3-205.3	3.0'	0.001	0.07	
									3169	205.3-207.0	1.7	0.001	0.13	
	5	5	100	64	GRANODIORITE: INTENSELY PROP. / WEAK PHYLLIC ALT'D, CHLORITIC, SERICITIC, V. CALCITIC. BANDED, WEAKLY SHEARED IN PLACES. V. SOFT + CRUMBLY. MOST BANDING @ ! FRACTURES @ 40-45° TO C/A.	TRACE DISS PY + AS.		210	3170	207.0-211.5	4.5'	0.001	0.07	
	5	5	100	44	STRONG, CA-HEALED CRACKLE OVERALL. LT-MED GRN-GRY.				3171	211.5-215.2	3.7'	0.001	0.06	
									3172	215.2-219.2	4.0	0.001	0.06	
										219.2-222.4				

OMNI RESOURCES INC. · PROJECT Skukum Creek (QH claims) · DIAMOND DRILL HOLE No. 87-165K Sheet 3 of 3

BQX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.
	5 224	5	100	34	BASE CONTACT BROKEN UP. BRECCIA OF QSBX IN GRANODIORITE. ROUGHLY 40% QSBX, 60% GDR. WEAK BANDING. FRACTS + BANDS @ 40-45° TO C/A. GDR U. BROKEN UP. AND HEALED U. ABUNDANT CALCITE. MODERATE LATE FINE CRACKLE (HEALED) OVERALL. BASE SHEAR @ 45°	222.4 ~12-15% SX. MOSTLY PY, THEN SL, GL AS + SB. 229.5		220 222.4
229.0	5 229	5	100	54				226.0
	5 234	5	100	20	INTENSE PROP. ALT'D CG., M. GRN-GRY RHY. U.V. SOFT + CRUMBLY BUT NOT CRUMBLED. U. ABUNDANT CA OVERPRINT. WEAK BANDING & SHEARING @ 40-45° TO C/A. A FEW BLEBS OF QSBX. BASE CONTACT HEALED BRECCIA FLOW? GDR:	TRACE DISS PY + MINOR SX IN FEW BLEBS OF QSBX. (<1%) 236.7		230 232.9
	5 239	5	100	36	STRONG PROP. ALT'D, COARSE GRAINED, MED. GRN-GRY. CRUMBLY, MINOR CLAYEY SHEARING. ABUNDANT CA. WEAK CA-HEALED CRACKLE. FRACTS @ 40-45° TO C/A. BASE CONTACT BROKEN UP	TRACE UFG DISS PY. 238.0		236.2 239.0
	5 244	5	100	32	BANDED, BXD, WEAK ROTATED DK GRN, CG BDY. MINOR FRACS OF F-MG. GDR. FRACTS @ 45 + 90° TO C/A BASE CONT. SHARP @ 45° TO C/A	241.0 TRACE DISS PY.		240 241.0
248.0	3 247	3	100	8	F-M.G, DK GRN STRONG PROP. ALT'D GDR. MOD. SHATTERED & AUTO BXD. ROTATED BUT NO REAL MATRIX. FRACS @ 45+ 90° TO C/A. MOD, CA-HEALED CRACKLE. BASE CONTACT BROKEN UP.	TRACE DISS PY. 245.1		245.1
	5 252	5	100	38	LT. TAN RHYOLITE. U. HARD, UFG. SHATTERED FOR FIRST 40 cm. SOME CRUMBLY, CLAYEY, CHLORITIC SHEARS FRACS @ 0, 45+90° TO CORE AXIS. - SOME SHEARED. WEAK, CA-HEALED CRACKLE-LATE. WEAK ALT'N ON SOME FRACTURES.	MINOR - TRACE DISS PY.		248.0 250
	5 257	5	100	40	BASE IS FLOW CONTACT @ 45° TO CORE AXIS WEAKLY BANDED, M-G. LT-MED GRN-GRY, INTENSE PROP. ALT'D GDR. WEAKLY BXD - MINOR ROTATION - ABUNDANT SL, EP, SE, CA. WEAK CA-HEALED FRACS. 8cm @ 45° CONT. @ 60°, LOW SHEAR. BASE CONTACT BROKEN SHEAR	255.0		251.7 255.0
	5 262	5	100	48	DK GRN, STRONG PROP ALT'D GDR. ABUNDANT QZ + QZ FLOODED ZONE + SX. ABUND. CA. V. WEAK CRACKLE BASE CONTACT HAZY + INDISTINCT	TRACE DISS PY. MINOR SX IN CLAST OF GDR. 259.0 260.9 + SL IN QZ. MINOR DISS PY.		260 260.9
	5 267	5	100	90	GDR: M-CG. MED GRN-GRY, V. COMPETENT, FEW FRACTS, NO SHEARS. U. WEAK CRACKLE MOD-WEAK PROP ALT'N, FRACTS @ 45+85° TO C/A. ALT'N DECREASING ↓ DEPTH.	TRACE DISS PY (VFG).		264.8
	5 272	5	100	78	COARSER- GRAINED ↓ DEPTH. MINOR GREY + WHITE QZ VEINS (UN MINERALIZED)			270
	5 277	5	100	76	MORE QZ-MONZONITIC ↓ DEPTH, MORE K-SPAR.			
					END OF HOLE 277.0'			280

SAMPLE Sample No.	INTERVAL	CORE LENGTH	ANALYTICAL O.P.T. Au	O.P.T. Ag	Pb %	Zn %	Cu %	As %	Sb
3173	219.7-222.4	3.2'	0.001	0.04					
3174 *	222.4-226.0	3.6	0.170	2.00	0.89	1.92	0.07	2.63	0.09
3175 *	226.0-229.5	3.5'	0.158	1.59	0.74	2.22	.05	3.59	.03
3176	229.5-232.9	3.4'	0.057	0.84					
3177	232.9-236.7	4.0'	0.001	0.39					
3178	236.7-239.0	2.8	0.001	0.17					
3179	239.0-241.0	2.0	0.001	0.14					
3180	241.0-245.1	4.1	0.001	0.32					
3181	245.1-248.0	2.9	0.001	0.04					
3182	248.0-251.7	3.7'	0.001	0.08					
3183	251.7-255.0	3.3'	0.001	0.05					
3184	255.0-259.0	4.0'	0.001	0.29					
3185	259.0-260.9	1.9'	0.001	0.79					
3186	260.9-264.8		0.001	0.12					

HW CONTACT.

EOH - 277 ft.

0.164, 1.80 /71'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	Skukum Creek (Wh)
COORDINATE N.	
E.	
ELEVATION	
DATE STARTED	OCT 13, 1987
COMPLETED	OCT 14, 1987 LOGGED NOV. 4, 1987
HOLE SURVEY	
HOLE No.	87-40-Test hole #1
DEPTH	31'
AZIMUTH	
INCLINATION	
DRILLED BY	Coron Diamond Drilling
ASSAYED BY	Acme Analytical Labs
LOGGED BY	R.J. Robinson

Reason for Drilling: X-CUT #1 West wall lower HW-FW

Explanation of Results:

LEGEND

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
	7	6.4	91	.13	GDR. M.G. MED. GRN-GRY. MOD PROP. ALTD. FAIRLY ABUNDANT CA, SE, EP, CL. MOST FRACTS 40-45° TO C/A. MAFICS ALT'D TO CHLORITE. ROCK FAIRLY SOFT. CORE LOST BTWN 7 & 12' DUE TO DRILLING THROUGH BACK OF SAFETY BAY.	TRACE DISS. PY. V.F.G.		0						
1	5	2.5	50	Ø				10	3067	7.0-12.0	15.0'	0.001	0.01	
	5	3.2	64	.19	BASE CONTACT BROKEN UP. BANDED, SHEARED GDR + ASH. MOSTLY BRECC. QUITE BROKEN UP. SOME BLACK, BRECCIATED DIATREME MATERIAL. AT BASE, GRADES INTO LOWER UNIT.	7-10% SX IN QZ. MOSTLY PY, THEN SL, GL, AS.		12.0	3068 *	12.0-14.5	2.5'	0.282	5.30	
	5	6.0	100	.21	BRECCIATED RHYOLITE WITH ~30% QZ SX BX INFILLING. MINOR DIATREME BRECCIA MATERIAL. RHYOLITE NOT BRECCIATED WITH QZ SX HAS STRONG CRACKLE TO MOD BRKN WITH GROUND RMX AS MATRIX. BANDING at ~60° TO C/A. MINOR CA + WHITE QZ FRACT-FILLING STRINGERS. FRACTS ALONG BANDS @ ~60° TO C/A. HEALED, DIATREME-FILLED SHEAR @ 30-60° TO C/A IS BASE CONTACT. CORE LOST @ 15-17 FT.	15-15% SX IN QZ MOSTLY PY, THEN GL, SL, AS, SB.		14.5	3069 *	14.5-27.0	12.5'	0.083	4.20	0.127, 6.59/15.7'
2	5	4.9	98	.94				20	3070 *	22.0-27.7	5.7	0.116	10.30	
	4	4.0	100	.10	DARK GREENISH-GREY M.G. GDR. MOD-STRONG PROP. ALT'N. ABUNDANT CA. QUITE BROKEN UP. SOME FRACTS WEATHERED, MOST CA-LINED. MOST FRACTS @ 60-70° TO C/A.	TRACE DISS UFG PY.		27.7	3071	27.7-31.0	3.3'	0.004	0.02	
31	31				END OF HOLE: 31.0			30						END OF HOLE 31'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	Skukum Creek (Wh)
COORDINATE N.	
E.	
ELEVATION	
DATE STARTED	OCT 20, 1987
COMPLETED	OCT 20, 1987 LOGGED ON NOV 4, 1987
HOLE SURVEY	
HOLE No.	87-UG-Testhole #2
DEPTH	35'
AZIMUTH	
INCLINATION	
DRILLED BY	Caron Diamond Drilling
ASSAYED BY	Acme Analytical Labs
LOGGED BY	R.I. Robinson

Reason for Drilling: X-cut #1 west wall upper HW-FW

Explanation of Results:

LEGEND

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T. Ag	
1	18	6.9	38	Ø	MED-COARSE-GRAINED MED. GREEN-GREY MOD. PROP. ALT'D GDR. MOD. & ABUNDANT CA FLOODING & FRACT-FILLING. VERY BROKEN UP-SHATTERED. NO SPECIAL OBSERVABLE FRACTURE ORIENTATION DUE TO OVERALL BREAKAGE. BASE CONTACT BROKEN UP, GRADATIONAL. MOD-WEAK CRACKLE TEXTURE - WELL-HEALED.	TRACE VFG DISS PY.		0						
								10						MUCH CORE LOST
	18					16.0		11.0	3072	11.0-16.0	5.0'	0.001	0.01	
1&2	4	3.1	78	Ø	OX STAIN IN GDR. OVERALL 5-10% QSBX IN GDR AS ABOVE. ABUNDANT CA. CORE STILL V. BROKEN & CRUMBLED = SHATTERED AND AREA ALT'D. BASE CONTACT CORE LOST.	OVERALL 3-5% SL, GL, PY, AS, SB.		16.0	3073	16.0-18.8	2.8'	0.053	2.18	
	22				STRONGLY PROP ALT'D MED-DK GRN, SLIGHT COARSE-GRAINED RHYOLITE. V. SOFT; V. ABUNDANT CA STRINGERS & VEINS. WEAK-MOD CA-HEALED CRACKLE. LOWER CONTACT CORE LOST:	18.8 MORE DISS PY. & SOME BLEBS & STRINGERS		18.8	3074	18.8-21.7	2.9'	0.034	0.12	
	23	1.0	100	.80		21.7		21.9						
2	5	5.0	100	.38	HARDER, F.G. LT-GRN-TAN MINERALIZED, BXXD RHY. SOME YELLOW & WHITE CA VEINS, STRINGERS & VEINS. MOST MATRIX IS VFG SX, BUT SOME IS INTRUSIVE BRECCIA MATRIX CONTAINING 3% & SUB-ROUNDED QTZ. ONLY SLIGHT ROTATION OF CLASTS. BASE CONTACT SHARP HEALED SHEAR @ 75° TO C/A.	3-4% VFG GL, SL, PY, AS, SB AS MATRIX IN BX.		28.4	3075	21.7-28.4	6.7'	0.087	9.78	
	28					28.4		30						
	5	5.0	100	.39	STRONGLY CRACKLED, STRONG PROP ALT'D. M-C MOD GDR-GREY GDR. FRACTS MOSTLY WITH QL. ALONG CA STRINGS. NO DOMINANT FRACT. ORIENTATION. BASE CONT. SHARP SHEAR. 75° TO C/A	MINOR DISS PY.		31.3	3076	28.4-31.3	2.9'	0.032	0.53	
	33				DARKER GREEN, STRONG PROP ALT'D GDR. STILL MED GRAINED, JUST LESS ALT'D. MOD. HEALED CRACKLE TEXTURE.			31.3	3077	31.3-35.0	3.7'			
3&5	35	2.0	100	.85	FRACTS @ 45° TO C/A.	TRACE DISS PY.		35.0						EOH - 35.0'
					EOH 35.0'	35.0								

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling: X-CUT #1 EAST WALL LOWER HW-FW

Explanation of Results:

LEGEND

PROJECT: Skukum Creek (Wh) — HOLE No.: 87-KG-Testhole #3

COORDINATE N. — DEPTH: 35'

E. — AZIMUTH

ELEVATION — INCLINATION

DATE STARTED: OCT 20, 1987 — DRILLED BY: Coren Diamond Drilling

COMPLETED: OCT 20, 1987 LOGGED NOV 5 1987 — ASSAYED BY: Acme Analytical Labs

HOLE SURVEY — LOGGED BY: R.J. Robinson

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE AZIMUTH	ANALYTICAL O.P.T. Au	O.P.T. Ag	Cu	Pb	Zn	As	Sb
	7	6.8	97	.11	BRECCIATED, SHEARED, MOD - STRONG PROP. ALT'D MED. GRAINED GDR. CORE QUITE BROKEN UP, BUT MOST FRACTS 80-90° TO C/A. Abundant CA. BASE CONT ACT SHARP BUT BROKEN UP.	MINOR PY - DISS + IN BLEBS + STRINGERS		0	3078	0.0-4.0	40'	0.049	1.02					
1	7.0				FAIRLY HARD, MOD. PROP. ALT'D, MOD CRACKLED, WELL-HEALED, WEAKLY BXD, FINE GRAINED, LT. GRN-GRY RHYOLITE.	TRACE DISS PY.		4.0										
	3 10.0	2.6	87	.13	FRACTS @ 40+ 80° TO C/A. SOME CA INFILLING SOME CLAYEY SHEARING. BASE CONTACT GRADATIONAL.	10.5' DISS PY THRU.		10	3079	4.0-10.8	6.8'	0.011	0.33					
	5 16.0	5.0	100	.11	RHYOLITE AS ABOVE FLOODED WITH QSBT. OVERALL ~ 50% QZ SHEET + 50% CLEAR HARD RHY. FRACTS MOSTLY 80-90° TO C/A. BASE SHARP @ 80° TO C/A	13.0 5-7% GLSL PY AS ± SB		10.8	3080 *	10.8-13.0	2.2'	0.249	11.77	.08	1.62	2.48	4.70	.05
					INTENSE MOD. ALT'D F.G. GDR LT. GRN-GRY. ABUNDANT CA INFILLING + STRINGERS. STRONG SILICIFICATION + MINOR BXN + ROTATION. FRACTS = BANDING @ 75+85° TO CA.	TRACE DISS PY.		13.0										
17.9	5 20.0	5.0	100	.40	BASE CONTACT SHARP, BANDED INTRUSIVE. @ 85° TO C/A. MIXED ANDESITE AND PORPHYRITIC GRANODIORITE. OVERALL FAIRLY EVEN DARK GRAY WITH ZONES OF GHOSTY 40% FS XTALS IN DK GRY F.G. GROUNDMASS. SOME CLAYEY	16.7 TRACE DISS VEG PY.		16.7	3081	13.0-16.7	3.7'	0.003	0.15					
								20	3082	16.7-20.0	3.3'	0.001	0.01					
2	5 25.0	6.0	100	.25	SHEARS MOD CRACKLE FAIRLY WELL HEALED WITH CA. MOD. PROP. ALT'N. STRONG SILICIFICATION IN GRANODIORITIC ZONES													
	5 30.0	5.0	100	.21	SOME SLICKENSIDES ON FRACTS. MOST FRACTS. ORIENTED @ 40 50° TO C/A. BASE CONTACT SHARP, INTRUSIVE @ 45° TO CA.													
					LT. GRY, COARSE-GRAINED GDR. WEAK PROP. ALT'D FRACTS @ 75-90° TO C/A. BASE CONTACT SHARP, INTRUSIVE @ 80°	TRACE TO NO VIS PY		30									
35	5 35.0	5.0	100	.39	DK, GREYISH BLACK, FAINTLY GREENISH TINGED ANDESITE. V. WEAK CRACKLE - CA HEALED. STRONG CLAY + RUSTY WEATHERING ON SOME FRACTS. FRACTS @ 40+50° TO C/A	TRACE TO NO VIS PY												

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling: K-CUT #1 EAST WALL UPPER HW-FW

Explanation of Results:

LEGEND

PROJECT: Skukum Creek (Wh) | HOLE No.: 87-UG-Test hole #4

COORDINATE N. | DEPTH: 35'

E. | AZIMUTH

ELEVATION | INCLINATION

DATE STARTED: OCT. 20, 1987 | DRILLED BY: Coron Diamond Drilling

COMPLETED: OCT. 20, 1987 Logged Nov 5, 1987 | ASSAYED BY: Acme Analytical Labs

HOLE SURVEY | LOGGED BY: R.J. Robinson

BOX	Run	Core	% R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE: Sample No.	INTERCEPT	CORE LENGTH	ANALYTICAL: O.P.T. Au	O.P.T. Ag	Cu | Pb | Zn | As | Sb
	4 4.0	4.0	100	Ø	MG. MED GRN-GRY. STRONGLY BROKEN UP. CRUMBLY + SHEARED GDR. MOD. PROP. ALT'N. FRACTS + BASE CNT NOT MEASURABLE.	TRACE DISS PY. 7.8'		0						
					CRUMBLED, CLAYEY SHEAR ZONE, YELL GDR. BANDED @ 80° TO C/A. BASE CNT BROKEN.			2.0'	3083	0.0-2.8	2.8'	0.001	0.01	
1	5 9.0	4.9	98	.21	SILICIFIED, MINERALIZED, BRECCIATED GDR. ABUNDANT CA. MINOR ROTATED QZ, CA + PY MATRIX. SOME CLAY ON SHEARS + FRACTS. BASE CNT SHEAR @ 80° TO C/A			4.0'	3084	2.8-4.0	1.2'	0.041	1.08	
					BAND. ALT'D RHY WITH QZ, CA, PY MINOR FRACTS BANDS. SAME COND. AS ABOVE.	4.6' 1-2% PY, MINOR SL GL AS.		5.5'	3085	4.0-5.5	1.5'	0.006	0.50	
					CLEAN, HARD LT GRN-TAN RHY + YELLOW QZ + CA STRINGERS. MINOR BLACK, FG SX FRACT-FILLING. @ 8.5' IS 3cm ZONE OF QSBX + MINOR SL AS, SL GAL. BASE 75°.	MINOR SX OVERALL <1% EACH SL GL AS PY. 9.1'		6.8'	3086	5.5-6.8	1.3'	0.011	1.34	
	5 14.0	5.6	100	.06	UFG DK GRY ANDESITE. ABUNDANT YELLOW QZ VEINS. MOD, WELL-HEALED CRACKLE. LIGHT PINK INDEX ARGILLIZATION. BASE GRADATIONAL.	11.0' MINOR DISS PY.		9.2' 10'	3087	6.8-9.2	2.4'	0.018	1.39	
					SLEAM/HARD, LT GRN-TAN RHYOLITE. SLIGHTLY PROP. ALT'D. MOD ABUNDANT YELLOW QZ + CA STRINGERS. MODERATE CRACKLE, WELL-HEALED SOME FRACTS CRUMBLED + CLAYEY. TRANSITIONAL FOR FRACT. ALTERATION. BASE SHARP, MOD. DIPPA	TRACE UFG DISS PY 14.1		11.0	3088	9.2-11.0	1.8'	0.001	0.11	
16-5	5 19.0	5.1	100	.17	3% SX AS IN RHY. MOSTLY QZ + SX WEAK BANDING @ 60° TO C/A. BASE CNT. LIGHT PINK AS @ 11' BUT 2 BANDED ZONES OF QSBX + QUITE BLEB OF AMS. BASE SHARP ANDESITE: V. DK GRN-GRY. ABUNDANT YELLOW QZ + CA STRINGERS V. SOFT. WEAK BANDING, + CRACKLE + FRACTS @ 80-85° TO C/A. STRONG PROP-ALT'N. SOME PINK WEATHERING ON FRACT. SURFACES. BASE CONTACT - GRADATIONAL - GRAIN SIZE INCREASES	15.1' 3% SX AS, PY, GL, SL 15.6' 15.0	3089	11.0-14.1	3.1'	0.010	0.45	
						17.0 MINOR SX AS AS PY		17.0	3090 ★	14.1-15.6	1.5'	0.725	16.55	607 | 2.23 | 2.82 | 8.29 | .08
						TRACE TO NO DISS. PY. 21.3		19.0	3091 ★	15.6-17.0	1.4'	0.073	2.70	291 | .33 | .53 | 1.91 | .01
2	6 26.0	6.3	100	.50	SUB-PORPHYRITIC GRANODIORITE. DARK, APHANITIC GROUNDMASS WITH SMALL PHENOS OF QZ, FS + HB. STRONG PROP ALT'N + U. ABUNDANT CA + QZ BLEBS + STRINGERS. LARGE, CA-FILLED, RUSTY FRACTURE 20° TO C/A @ 22.3'. STRONG, HEALED CRACKLE. FRACTS @ 30 + 80° TO C/A. BASE CONTACT SHARP, SHEAR @ 80° TO C/A.	TRACE UFG DISS PY. 29.1		20	3092	17.0-21.3	4.3'	0.001	0.01	0.242, 5.91/5.0'
	5 30.0	5.0	100	.54				21.3						
33B	5	5.2	100	.52	LT GREY; V. CLEAN, ALMOST UNALTERED GDR. WEAK TO MOD. HEALED CRACKLE. FAIRLY ABUNDANT CA. MOST FRACTS @ 80° TO C/A. BASE CNT BROKEN.	33.3		30						
35	35				ANDESITE @ 21.3									
					END OF HOLE @ 35-0'									END OF HOLE @ 35-0'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	Skukum Creek (Wh)
COORDINATE N.	
E.	
ELEVATION	
DATE STARTED	OCT. 26, 1987
COMPLETED	OCT. 26, 1987 LOGGED NOV. 13, 1987
HOLE SURVEY	
HOLE No.	87-UG-test hole #5
DEPTH	51'
AZIMUTH	
INCLINATION	
DRILLED BY	Coeur Diamond Drilling
ASSAYED BY	Acme Analytical Labs
LOGGED BY	R.J. Robinson

Reason for Drilling: X-CUT 7 FOOT WALL LOWER HW-FW

Explanation of Results:

LEGEND

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.
	10	9.3	93	.12	STRONGLY PROP. ALT'D. MED GRN-GRY MG GDR. SEVERAL LATE GRITTY, CLAYEY SHEARS. WEAK BANDING, SHEARS & FRACTS @ 50° TO C/A. ABUNDANT CL/CA. BASE CUT. SHEAR @ 70° TO C/A.	TRACE UFG DISS PY.		0
1								4.0
	10				H.W. SHEAR ZONE. STRONG-INTENSELY PROP. ALT'D. M-CGR LT-MED GRN-GRY GDR. SHEARS NOT HEALED. V. CRUMBLY. ABUNDANT GRITTY CLAY ON SHEARS. FRACTS & SHEARS AT ALL ANGLES BTWN 0 & 90° TO C/A. SOME X-CUTTING FRACTS. BASE CUT SHEAR @ 65° TO C/A.	TRACE UFG DISS PY.		10
						16.3		
	11	9.8	89	.32	BAND OF QSBX IN GDR. V. BROKEN UP. BASE CUT @ 2-HEALED SHEAR ZONE. INTENSELY PROP & MOD. SILICIC ALT'D M-G. MED GRN-GRY GDR. QUITE CRUMBLY. SEVERAL GRITTY CLAY-FILLED SHEAR ZONES TO 15 cm WIDE. FRACTS @ 75 & 90° TO C/A. BASE CONTACT	15-20% TOTAL SX		
						TRACE DISS PY. MINOR SX IN CLAYS OR QSBX VEINS.		
19.3						18.8		18.5
	21				BRCKIA, HEALED BRECCIA. GRADES INTO LOWER ZONE	BARE TRACE PY. (1 mm)		20
					DK GRN-COARSE GRAINED, HARD, WEAKLY PROP ALT'D RHYOLITE. BXXD. BLACK WISPS & YELLOW QTZ MATRIX. BASE IS GRAPHITIC SHEAR @ 30° TO CA	20.4		20.4
	10	10.0	100	.54	QTZ-SX BX IN LT GRN RHY. >90% QTZ-SX BX. INTENSE CRACKLE, HEALED & BLACK SX & CHLORITE. ONLY MINOR ROTATION OF QTZ CLASTS. CLAST SUPPORTED. X-CUTTING FRACTS @ 20 & 60°. 2 FRACT SETS @ 20° TO C/A OPPOSITE TO EACH OTHER (<) FAIRLY ABUNDANT CALCITE. BASE CONT BXXD.	~20% SX. UFG IN QTZ & FRACT & CRACKLE HEALING - MOSTLY PY, THEN CL, SL, AS, SB.		
2						23.9		23.9
	31				V. HARD, LT GRN-TAN VFG, WEAK PROP ALT'D RHY. STRONG CRACKLE. ABUNDANT MINERALIZED GREY-WHITE QTZ STRINGER CRACKLE HEALED BY WK VFG BLACK MATERIAL. BASE @ CONTACT SHEAR, 70° TO C/A.	2-3% SX OVERALL. MOSTLY PY, THEN SL, CL.		30
						30.8		30.8
	5	6.0	100	.77	INTENSELY SILICIFIED LT GRN-TAN RHY. ALMOST TOTALLY WHITE, ALTERED AROUND STRONG CRACKLE. ABUNDANT QTZ FLOODING. GRAD TO BASE CUT.	MINOR DISS SL & PY.		
	36				V. HARD, COMPETENT, LT GRN-TAN, VFG RHY. FAIRLY STRONG CRACKLE HEALED WITH QTZ (WHITE) AND SX - MOSTLY PY & SL. 25 cm XENOLITH OF DARK, VERY CHLORITIC QTZ-SX BX. CORE DRILLED THROUGH CURVED EDGE - ABUNDANT XENOLITHS. MOST FRACTS BTWN 70 & 90° TO C/A. BASE BXXD.	32.6		32.6
37.1						3% PY, 2% SL JUST TRACE OTHER SX.		
	5	4.7	94	.47				
	41					40.5		40
								40.5
	5	4.9	98	.65	COARSER-GRAINED, DARKER GREEN, STRONGER PROP. ALT'D., SOFTER, V. CALCITIC RHY. STRONG TO INTENSE CRACKLE, HEALED & WHITE QTZ, PY & SL & CA. ~5% CA OVERALL IN CRACKLE, STRINGERS & FLOODED ZONES. BASE CONT. SLICKENSIDED SHEAR 35° TO C/A.	~5% PY, MINOR SL TRACE GL.		
3	46					45.0		45.0
					INTERBDD BX OF QTZ RHY. GDR & SL & BRN-BLK MATRIX (L-ALT'N). BASE CA SHEARED.	~5% MINOR SX.		45.9
	5	5.0	100	.80	DK GRN, SOFT, C.G. RHY. V. SOFT, V. CALCITIC, WEAK CRACKLE - CA HEALED. FRACTS & BANDING @ 55-60° TO C/A. BASE GRADATIONAL.	MINOR DISS PY.		48.0
51.0	51				COARSE GRAINED, DARK GRN-BLACK GDR. STRONG PROP. ALT. U. LARGE QTZ XTALS. (TO 1 cm) ABUNDANT CL/SE/CA	TRACE DISS. PY.		50
					END OF HOLE @ 51' HOLE 87-UG TH #5		51 cm H.	

Sample No.	INTERCEPT	CORE LENGTH	ANALYTICAL Y. O.P.T. Au	O.P.T. Ag	Cu	Pb	Zn	As	Sb
									HW SHEAR
3134	4.0-10.3	6.3'	0.010	0.31					
3135 X	10.3-11.4	1.1'	0.171	17.84	.003	1.03	.44	1.52	.02
3136	11.4-18.5	7.1	0.047	16.08					
3137	18.5-20.4	1.9'	0.004	0.62					
3138 A	20.4-27.9	7.5'	0.147	9.71	.05	1.55	2.03	MER 0.11	.01
3139	27.9-30.8	2.9'	0.046	3.30					
3140	30.8-32.6	1.8'	0.115	5.82					
3141	32.6-40.5	7.9'	0.095	4.94					
3142	40.5-45.0	4.5'	0.027	0.54					
3143	45.0-45.9	0.9'	0.034	1.17					
3144	45.9-48.0	2.1'	0.003	0.14					
3145	48.0-51.0	3.0'	0.004	0.09					end of hole at 51'
									0.090, 8.83 /30.2'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

PROJECT	Skukum Creek (Wh)	HOLE No.	87-UG-Testhole #6
COORDINATE N.		DEPTH	60'
E.		AZIMUTH	
ELEVATION		INCLINATION	
DATE STARTED	Oct 26, 1987	DRILLED BY	Caron Diamond Drilling
COMPLETED	Oct 26, 1987 (Cosaco Mon 12)	ASSAYED BY	Acme Analytical Labs
HOLE SURVEY		LOGGED BY	R.J. Robinson

Reason for Drilling: X-CUT #7 WEST WALL UPPER (HW-FW)

Explanation of Results:

LEGEND

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.
	3/3	3.0	110	Ø	INTENSLY PROP ALT'D, SHEARED, F.G., LT. GRN-GRY GDR.			0
	3/6	2.8	93	Ø	VERY CRUMBLY & BROKENUP. H.W. SHEAR ZONE.	TRACE TO MINOR DISSEMINATED V.F.G. PY.		
1	3/9	2.6	87	Ø	SOME SILICIFICATION. VERY STRONG CRACKLE TEXTURE - SOME ROTATION OF CLASTS IN GROUND GDR MATRIX. MANY FRACTS + SHEARS CLAY-FILLED.			6.8
	5/14	4.5	90	Ø	FRACTS + SHEARS AT ALL ANGLES. BASE CONTACT BROKEN SHEAR - INCORPORING QZ.	11.9		10
	4/18	4.0	100	.09	QZ VEINS & QSBX IN SHEARED, ALT'D GDR. ~20% SX IN WHITE + GREY-WHITE MINERALIZED QZ. STILL V. SHEARED UP WITH SOME SHEARS AFTER MINERALIZATION. V. BROKEN UP. MINOR RHYOLITE AT END OF (INSTEAD OF GDR) BASE CONTACT GRADATIONAL.	~20% TOTAL SX MOSTLY PY+SL WITH 1-2% GL, AS+SB		11.9
18.0	4/22	4.0	100	Ø	V.DK BRownish-GREYISH-BLACK QSBX. MAX CLAST SIZE 10cm. MINOR RHY. SX MATRIX AND RARE QZ CLASTS. FRACS @ 0, 45°, 90°. BASE CAT SHEAR @ 90° TO C/A POLYMICTIC, DIATREME BRECCIA. CLASTS 1 MM TO 2 cm IN ARGILLITE, SLTST, GRN-BLACK GRNDMASS. CLASTS OF RHY, GDR, QZ + QSBX. FRACTS @ 0-5° TO C/A. BASE INT. 40°	19.9 30-40% SX. MSL, GL, AS, SB TRACE-MINOR SX 21.8 IN ASSOC CLASTS		18.2
	3/25	2.5	83	.94	BRECCIATED QUARTZ WITH SULFIDE MATRIX: NOT NORMAL QSBX AS QZ IS MOSTLY CLEAN + MORE, WITH NO INCLUDED DFG SX. ONLY MINOR ROTATION OF CLASTS. INCLINED SX STRIS (LOWER PRESENT) 2-5 mm. FRACT-FILLING + MATRIX ~ 50% MIXED SX + 50% CHLORITE, SERICITE, GP. NO DOMINANT FRACTURE OR BANDING. ORIENTATION. BASE GRADATIONAL.	~7-9% TOTAL SX. MOSTLY PY+SL with 1-2% comp GL, AS, SB		19.9
2	5/30	5.0	100	.56	CLEAN, HARD, SLIGHTLY PROP ALT'D LT. GRN-TAN VFG-RHY WITH GREY QZ + SX FRACT-FILLING. MINOR ROTATION OF CLASTS. V. STRONG CRACKLE WELL-HEALED. NO DOMINANT FRACTURE ORIENTATION. V. FEW FRACTS:			21.8
35.0	5/35	5.0	100	.71	BASE CONTACT BROKEN FRACTURE.	3-5% TOTAL SX. MOSTLY PY, THEN MINOR SL, GL, AS, SB.		28.0
	5/40	4.8	96	.79	AS ABOVE, BUT RHYOLITE IS SOFTER, SLIGHTLY COARSER-GRAINED, MORE STRONGLY ALTERED AND DARKER GREEN. STILL CRACKLED AND HEALED WITH SX + GREY QZ FRACT-FILLING.			30
3	5/45	5.0	100	.40	BASE SHARP, CLEAN SHEAR OR FRACTURE @ 75° TO C/A	3-5% TOTAL SX. MOSTLY PY, THEN MINOR SL, GL, AS + SB.		33.4
	5/50	4.5	90	.78	ALT. GRY AS ABOVE WITH V. ABUNDANT YELLOW QZ INFILLING & FRACTURE-FILLING. SOME GREY QZ + SX INFILLING. MINOR BX. BASE SHEAR ZONE 90° TO C/A	44.4 MINOR SX IN GREY QZ.		37.6
					MED. GRAINED, MED GRN MOD PROP. ALT'D RHY. QZ + CA (WHITE) STRINGERS + FRACTURE-FILLING. BASE CAT: GRADATIONAL FLOW CONTACT.	46.7 BARE TRACE DISS PY. 49.0		40
529	5/55	5.0	100	.58	STRONG PROP. ALT'D, CG DK GRN-GRY GDR. ABUNDANT QZ, SE, EP + CA. QZ XTALS V. LARGE - UP TO 15 mm - RESEMBLE CLASTS, BUT PROBABLY JUST XTALS. MOD CRACKLE, WELL-HEALED. CA-LINED FRACTS @ 40-45° TO C/A. BASE EP-FLOODED 1ST ZONE.	TRACE DISS PY 55.3		44.4
4	5/60	4.9	98	.25	MED GRAINED, MOD. PROP. ALT'D MED GRN-GRY GDR. FRACTS @ 45-50° TO C/A. STRONG, WELL-HEALED (CA) CRACKLE. 87-UG-Testhole #6 end of hole at 60'	TRACE DISS PY.	E.O.H.	46.7 49.0 50 55.3 60

SAMPLE				ANALYTICAL						
Sample No.	INTERCEPT	CORE LENGTH	O.P.T. Au	O.P.T. Ag	Cu	Pb	Zn	As	Sb	
3104	6.8-11.9	5.1'	0.003	0.05						
3105	11.9-18.2	6.3'	0.048	4.71						
3106 *	18.2-19.9	1.7'	0.155	23.64	.08	1.64	1.47	1.48	.04	
3107 *	19.9-21.8	1.9'	0.009	1.56	.01	.34	.36	.03	.01	
3108 *	21.8-28.0	6.2'	0.161	12.69	.05	1.65	.82	.06	.02	
3109 *	28.0-33.1	5.1'	0.319	7.73	.03	.77	.77	.29	.01	
3110 *	33.1-37.6	4.5'	0.059	5.25	.03	.53	.67	.04	.01	
3111 *	37.6-44.4	6.8'	0.168	3.29	.04	.79	1.37	.08	0.8	
3112	44.4-46.7	2.3'	0.023	0.71						
3113	46.7-49.0	2.3'	0.029	0.43						
3114	49.0-55.3	6.3	0.011	0.14						

0.165, 7.91/26.2

end of hole at 60'

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling: X-CUT #7 EAST WALL LOWER HW-FW

Explanation of Results:

LEGEND

PROJECT: Skukum Creek (Wh) — HOLE No.: 87-UG-test hole #7

COORDINATE N. — DEPTH: 62'

E. — AZIMUTH

ELEVATION — INCLINATION

DATE STARTED: OCT-26,1987 — DRILLED BY: Coron Diamond Drilling

COMPLETED: OCT 26,1987 LOGGED NOV-13,1987 — ASSAYED BY: Acme Analytical Labs

HOLE SURVEY — LOGGED BY: R.J. Robinson

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.
	3 3.0	2.0	.66	Ø	INTENSELY PROP. ALT'D, LT. GRN-GREY, V. SOFT, MOD. SHEARED ≡ C-G-GDR. V. ABUNDANT CA. FRACTS @ 45°&70° TO C/A. V-STRONG, WEAKLY-HEALED CRACKLE. SEVERAL GRITTY CLAY-FILLED SHEAR ZONES TO 5cm WIDE. BASE CONTACT GRADATIONAL. JUST INCREASING AMOUNTS OF SHEARING.	TRACE TO MINOR FG DISS PY.		0
1	5 8.0	4.8	96	.27				8.0
	5 13.0	5.0	100	.10				10.4
	4 17.0	4.0	100	.19	HW SHEAR ZONE. ALT'D GDR AS ABOVE, BUT ALMOST TOTALLY SHEARED & GROUND UP. ABUNDANT GRITTY CLAY IN FRACTS. AT ~16', GDR @ CONTACTS WITH DK GRN, CG RHYOLITE. STRONG PROP. ALT-STILL V. SHEARED. UNIT END AT SHEAR ORIENTED 90° TO C/A	MINOR DISS PY.		12.4
-18.6	5 22	5.0	100	.07	BRECCIA OF QSBX IN DK GRN ALT'D RHY. V. BROKEN UP STRONG SHEAR ZONE 20 cm WIDE @ 21'. FRACTS & BANDING AT ALL ANGLES ~ 50% RHY, 50% QSBX. BASE CONT. GRADATIONAL.	10-12% TOTAL SX. MOSTLY PY, THEN GL, AS=38.		17.5
	5 27	5.0	100	.26	BRECCIA AS ABOVE, BUT QSBX IN LT GRN-TAN, HARD, LESS ALT'D RHY. SOME RUSTY-WEATHERED FRACTS. BASE CONT. HEALED SHEAR @ 70° TO C/A.	10-12% TOTAL SX. AS ABOVE		22.0
2					HARD, WEAKLY-ALT'D, VFG, LT. GRN-TAN RHYOLITE. MOD.-STRONG CRACKLE. HEALED WITH VFG UNKNOWN BLACK MATERIAL. SOMEWHAT GRAINED. FRACTS @ 90° TO C/A. BASE CONT. BLACK-LINED FAULT @ 155° TO C/A.	TRACE VFG DISS PY.		23.7
	5 32	5.0	100	.71	MINERALIZED QUARTZ, PARTLY BLEBBY, UNIT OF QZ WITH FRACTURE FILLING AND FLOODED ZONES OF SULFIDES - MOSTLY GL. MOD. CRACKLE WITH QZ & SX FILLING. BASE CONT. BLACK-LINED SHEAR @ 40° TO C/A	4% GL, 2% PY		26.6
					HARD, WEAKLY ALTERED, VFG, LT-TAN-GREEN RHYOLITE. MOD. BXXD & MINERALIZED WHITE QZ MATRIX. ~70% RHY, 30% QZ. CLAST SUPPORTED. PROBABLY MORE OF A QZ VEIN SWARM THAN A BX. LATE CRACKLE CUTTING ALL ROCK TYPES HEALED BY GREENISH-BLACK FG MATRIX. FRACTS @ 45-50°. BASE CONT. GRAD.	MINOR BLK AS.		28.7
-34.2	5 37	4.8	96	.67		3-5% TOTAL SX MOSTLY PY, + SL. THEN GL, AS, SB.		30
	5 42	5.0	100	.71	QUARTZ SX-BX IN DARKER GREEN RHYOLITE. QZ BANDS & STRINGERS SHOT THROUGH RHY. LATER MASS-FILLING CHLORITE SX. BASE CONTACT SHARP, IRREGULAR. MOD. ALT'D. MOD. COARSE-GRAINED MED GRN RHYOLITE. ABUNDANT CALCITE & YELLOW QZ INFILLING & STRINGERS. FIRST 15 cm MINERALIZED, THEN NOT. WEAK CRACKLE. FRACTS @ 50 & 90° TO C/A. BASE CONTACT SHARP @ 70° TO C/A.	4% PY, 2% GL. TRACE ~ 5% SAMBORNITE SX.		33.5
3					ALL DIFFERENT BX: BXH (ALT-HOST), QSBX & GDR IN BLACK FG MATRIX. BASE CONT. SHARP, IRREGULAR	7% PY FOR FIRST 15 cm, THEN TRACE VFG DISS PY.		36.6
	5 47	5.0	100	.13	BRECCIA OF 1ST. ALT. GDR & CLEAR, MED RHY. BASE CONT. SHARP, IRREGULAR	TRACE DISS PY		38.4
	5 52	4.9	98	.74	DARK, STRONGLY PROP. ALT'D CG GDR. BANDED & SWIRLED. SOME QZ & FS XTALS TO 1cm, MOST ~ 2-3mm. BLACK, FAIRLY FINE-GRAINED GROUNDMASS. ABUNDANT CA/CL/EP/SE BLEBS & MEANDS. WEAK CALCITIC CRACKLE. FEW FRACTURES @ 75° TO C/A. BASE CONT. @ 65°	TRACE DISS PY		41.4
	5 57	5.0	100	.50	MOD. PROP. ALT'D MED. GRN-GRY, MED-GRAINED GRANODIORITE. FRACTURES @ 45° TO CORE AXIS. VERY WEAK CRACKLE TEXTURE. SOME CALCITE STRINGERS & FRACT-FILLING: CHLOR STRINGERS & BLEBS. SOME WEAK BANDING & SWIRLING.	BARE TRACE DISS PY.		43.9
-54.7								48.9
4	5 62	5.0	100	.40	87-UG-test hole - #7			50
62'								60

E.O.Hat Bdy 62'

SAMPLE Sample No.	INTERCEPT	CORE LENGTH	ANALYTICAL O.P.T. Au	O.P.T. Ag	Cu	Pb	Zn	As	Sb
3146	8.0-12.4	4.4'	0.002	0.01					
3147	12.4-17.5	5.1'	0.012	0.37	HW SHEAR.				
3148 *	17.5-22.0	4.5'	0.177	17.50	0.05	2.26	2.82	.31	.01
3149 *	22.0-23.7	1.7'	0.248	45.00	.12	3.40	3.56	.28	.03
3150	23.7-26.6	2.9'	.002	0.27					
3151	26.6-28.7	2.1'	0.307	41.85					
3152	28.7-33.5	4.8'	0.171	8.61	0.152, 13.84/24.9'				
3153	33.5-36.6	3.1'	0.062	2.25					
3154	36.6-38.4	1.8'	0.258	14.88					
3155	38.4-41.4	3.0'	0.062	1.45					
3156	41.4-42.4	1.0'	0.263	21.14					
3157	42.4-43.9	1.5'	0.053	0.70					
3158	43.9-48.9	5.0'	0.004	0.13					
					end of hole at 62'				

OMNI RESOURCES INC.

DIAMOND DRILL HOLE LOG

Reason for Drilling: X-CUT #7 EAST WALL UPPER HW-FW

Exploration of Results:

LEGEND

PROJECT: Skukum Creek (Wh)
COORDINATE N.
E.
ELEVATION
DATE STARTED: Oct 28, 1987 Logged Nov 16, 1987
COMPLETED: 09:36, 1987
HOLE SURVEY

HOLE No.: 87-UG-test hole # 8
DEPTH: 54'
AZIMUTH
INCLINATION
DRILLED BY: Caron Diamond Drilling
ASSAYED BY: Acme Analytical Labs
LOGGED BY: R.J. Robinson

BOX	Run	Core	%R	RQD	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	CORE AZIMUTH	ANALYTICAL O.P.T. Au	O.P.T. Ag	Pb	Zn	Cu
1	9	8.0	89	.05	STRONGLY PROP. ALT'D., STRONGLY SHEARED AND FAULTED. FINE TO MED. GRAINED, MED-GRY GRANODIORITE. ABUNDANT CA, AND CLAY ZONES. VERY FAULTED AND SHEARED. @ HANGING WALL SHEAR ZONE. IN SOME PLACES ONLY GRITTY CLAY REMAINS. (MIXTURE OF CLAY + QZ GRAINS) MINOR, LATE, YELLOW QZ VEINING.	MINOR DISS PY THROUGHOUT		0								
	9															
	5	5.0	100	Ø	@ 12.0' IS 20 cm BAND QZ SX BX. @ ~ 65° TO C/A. MOSTLY PY.	QZ SX BX ~ 20% SX, MOSTLY PY, THEN MINOR GL, SL, AS.		10	3093	9.0-14.0	50°	0.034	1.84			
	14							14.0								
	5	4.5	90	.26	WEAK BANDING + FRACTURING @ 75-80° TO C/A. IN PLACES TOTALLY CRUMBLED ZONES @ IS U-STRONG CRACKLE TEXTURE.				3094	14.0-19.7	5.7'	0.035	1.21			
17.6	19				BASE CONTACT SHEAR @ ~ 90° TO C/A.			19.7								
	5	4.7	94	.16	1-2' OF QZ + SX (MOSTLY PY) CLASTS IN CRUMBLED GOR MATRIX CEMENTED TO ALL CLEAVAGE OR QZ. THEN SHARP SHEAR CUTS 2 0.4' DIAMETER SUBANGULAR CLEAN, HARD, WEAKLY-CRACKLED LT GREEN/TAN RHY. TOP CONTACT GRAD. BRECCIA OVER 1cm. BLACK, UFG MATERIAL FILLING FRACTS + CRACKLE. FRACTS @ ~ 5, 20, 45 + 75° TO C/A BASE CONTACT GRAD ALT'N.	1-2' OF QZ + SX (MOSTLY PY) CLASTS IN CRUMBLED GOR MATRIX CEMENTED TO ALL CLEAVAGE OR QZ. THEN SHARP SHEAR CUTS 2 0.4' DIAMETER SUBANGULAR CLEAN, HARD, WEAKLY-CRACKLED LT GREEN/TAN RHY. TOP CONTACT GRAD. BRECCIA OVER 1cm. BLACK, UFG MATERIAL FILLING FRACTS + CRACKLE. FRACTS @ ~ 5, 20, 45 + 75° TO C/A BASE CONTACT GRAD ALT'N.			3095	19.7-21.4	1.7'	0.162	15.50			
	24					MINOR PY + SL-GL IN QZ.		21.4								
	4	4.0	100	Ø	STRONGLY PROP. ALT'D., COARSER GRAINED. DARKER GREEN RHY. SILICIFIED, INTENSE CRACKLE, MINOR ROTATION. + BRITTLE + CRUMBLY. BASE BROKEN QZ.	BARE TRACE DISS. PY PERHAPS UFG GRAINED QZ			3096	21.4-25.8	4.4'	0.001	0.16	0.079	7.62	24.5
2	28					FRACT-FILLING		25.8								
	5	5.0	100	.55	V. HARD, FINE-GRAINED LT TAN RHY. WITH V. ABUNDANT QZ VEIN SWARM. ~ 40% QZ IN VEINS, STRINGERS + FRACT-FILLING. THE QZ IS CLEAN + WHITE WITH XTALS OF GL, SL, AS + PY. NOT AS DARK AS REGULAR QSBX, AND QZ IS NOT VERY BRECCIATED. 5% XTALS RANGE FROM .1mm TO 2mm. A FEW SUCCESSIONED FRACTURES @ 40 + 70°. BASE CUT @ 90° TO C/A	TRACE DISS PY.		27.8									
	33					~ 2-3% GL, PY. MINOR SL, AS, CP IN QZ.			3098	27.8-35.4	7.6'	0.055	4.73			
35.5	6	6.0	100	.68	VERY ALTERED + BRD PACK RHY WITH FG GOR WITH QZ + SX. ~ 15% GOR IRRY AND 15% QZ + 10% SX. STRONG CRACKLE, NOT MUCH ROTATION. NO UNHEALED FRACTURES. BASE CUT. SHARP CONTACT @ 60° TO C/A.			35.4								
	39					~ 5% GL, minor SL, PY, AS + CP.		39.2	3099	35.4-39.2	3.8'	0.210	26.00	5.48	2.73	0.10
	5	4.9	98	.82	SILICIFIED, BRD, WEAK PROP. F-MG MED. GRN RHYOLITE. V. ABUNDANT YELLOW QZ. SOME BLACK, DIAMOND MATERIAL AS MATRIX. CLAYEY SHEAR @ CUT. 5% QZ IN ANDESOME. ~ 40% SX, 35% QZ + 25% GOR. 2 FRACTS, BOTH GRAY, CLAY LINED @ 75° TO C/A. GOR IS STRONG PROP. ALT'D. WEAK FRT OVERALL, LATE QZ STRINGERS. BASE BRXD. GABBRO.			40	3100	39.2-41.3	2.1'	0.001	0.18			
3	44					TRACE DISS. PY.		41.3								
	5	5.0	100	.54	MOD-STRONG PROP. ALT'D GOR. F-MGR. MODERATE SCHIRLING. WEAK BXN AT TOP DECREASING WITH DEPTH. SOFT, GREENISH-GREY BANDS - PERHAPS CALCITE, CRUSHED GOR - CUTTING + CORE AT ALL ANGLES AND HEALING SOME SHEARS. MOD. SE, EP, CL, CA.	40% SX. MOSTLY SL-GL		44.0	3101*	41.3-44.0	2.7'	0.150	7.44	1.99	0.81	0.05
	49					TRACE DISS PY.			3102	44.0-49.0	5.0'	0.001	0.07			
	5	5.0	100	.70				49.0								
57	54				87-UG-test hole end. End of hole at 54'		E.o.H	54.0	3103	49.0-54.0	5.0'	0.001	0.01	end of hole at 54'		

OMNI RESOURCES INC
DIAMOND DRILL HOLE LOG

Reason for Drilling: TO TEST ZONE IN WEST WALL X-CUT #7 FAN-HN BTWN HOLES TH 5 + TH 6

Explanation of Results:

LEGEND

PROJECT: SKUKUM CREEK (WH) — HOLE No. 87-WC TH 9
COORDINATE N. — DEPTH 66'
E. — AZIMUTH
ELEVATION — INCLINATION
DATE STARTED NOV. 9, 1987 Logged DEC 13, 1987 — DRILLED BY CARON DIAMOND DRILLING
COMPLETED NOV. 10, 1987 — ASSAYED BY ACME ANALYTICAL
HOLE SURVEY — LOGGED BY RJR

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE Sample No.	SAMPLE INTERCEPT	SAMPLE CORE LENGTH	ANALYTICAL O.P.T. Au	ANALYTICAL O.P.T Ag	ANALYTICAL Pb	ANALYTICAL Zn	ANALYTICAL As	ANALYTICAL Sb
1	7	7	100	44	SUB-PORPHYRITIC GRANODIORITE. U. DARK GREENISH BLACK WITH QZ PHENOS TO 7 mm. STRONG PROP ALT'N. ABUNDANT SERICITE. MINOR LATE CALCITE VEINLETS + STRINGERS. WEAK, WELL HEALED CRACKLE. MOST FRACTS 20-70°. BASE CONTACT GRADATIONAL.	TRACE DISS PY		8.2						0.253	6.14	29.4	
	11 5	5	100	78	M.G. GDR. INTENSE PROP ALT. INTENSE CRACKLE - ALMOST BRECCIA. WELL-HEALED. FRACTS 35+90° TO C/A. BASE SHARP INT. 70°	TRACE DISS PY.		11.8									
2	17 5	5	100	90	RHYOLITE BX & BXXD RHY. M.G. LT GRN RHY AT TOP ± CM YELLOW QZ STRINGERS, THEN TOTALLY BXXD WITH QZ SX BX MATRIX FROM 13.0-15.0', THEN CRACKLED MG RHY AGAIN. FRACTS 0, 45+90° TO C/A. BASE SHARP INTRUSIVE. 50° TO C/A	OVERALL 5-7% SX PY, SL, GL, AS, SB. MOSTLY BTWN 13'-15'.		18.8	3215	8.2-11.8	3.6'	0.029	0.59				
	22 5	5	100	88	QUARTZ SULFIDE BRECCIA. 93% WHITE, HARD, SOLID QZ WITH ~7% SULFIDE MATRIX. STRONG, WELL-HEALED LATE CRACKLE. FRACTS @ 45, 70° + 90° TO C/A BASE SHARP, INT. 45°	~7% SX DISS + MATRIX BX.		24.7	3216	11.8-18.8	7.0'	0.164	6.92	.91	.98	.05	.01
	27 5	5	100	96	MINERALIZED, CRACKLED RHYOLITE TO 31.0', THEN QSBX. RHY IS HARD, SOLID, LT-GRN. ± 2-3% VFG DK GRY SX IN CRACKLE. QSBX IS AS IN ABOVE UNIT - FRACTS 50, 70° + 90°	2-3% DK GRY VFG SX IN RHY + 5-7% DISS + MATRIX QZ.		33.1	3217	18.8-24.7	5.9'	0.224	6.75	.86	.95	.36	.01
	32 5	5	[illegible]	90	BASE CNT SHARP SHEAR @ 75° TO C/A.				3218	24.7-33.1	8.4'	.532	6.66	1.46	.98	.74	.01
3	37 5	5	100	44	SHEARS FOR 3', THEN MINERALIZED, BXXD GDR. V. STRONGLY PROP. ALT. GDR WASHED OUT, DIFFICULT TO SEE GRAIN SIZE. QZ-FLOODED SX MOSTLY PY. FRACTS N 80° TO C/A. DK GREY OVERALL WITH SOME LIGHTER QZ ZONES. BASE SHARP, HEALED SHEAR @ 80° TO C/A.	3-5% PY DISS + MATRIX TO BX. MINOR SL, GL.		41.2	3219	33.1-41.2	8.1'	.061	4.47	.63	.82	.34	.01
	42 5	5	100	68	LT. GREEN. INTENSELY PROP / WEAK PHYL ALT. GRANODIORITE. ALL PLAG. → LT. GRN. SERICITE. SLIGHT QZ-SX MINERALIZATION - MOSTLY PYRITE. QUITE SOFT-CRUMBLY. POORLY HEALED. FRACTS MOSTLY N 80° TO C/A. BASE CONTACT. GRAD. SHEAR FOR 10 cm.	3-5% PY DISS + IN QZ - MINOR TO 1% SL-GL. MAY BE TRACE AS, SB.		49.2	3220	41.2-49.2	8.0'	.024	.99	.20	.29	.61	.01
	47 5	5	100	52													
4	52 5	5	100	60	INTENSE PROP - WEAK PHYLLIC ALT'D GDR AS ABOVE, BXXT NOT MINERALIZED. U. SOFT + CRUMBLY, CALCITIC CRUSHED ZONES FRACTS 45+80°. BASE CNT SHEAR @ 90° TO C/A.	TRACE DISS PY.		53.4	3221	49.2-53.4	4.2	0.001	0.05				
	57 5	5	100	72	INT. PROP GDR.							[illegible]					
	62 5	5	120	34	AS ABOVE, BUT MORE COMP. + LESS ALT'D. LT-GRN. BASE CNT. SHARP, ROUGH @ 10° TO C/A.	TRACE DISS PY		59.5	3222	53.4-59.5	6.1	0.001	0.06				
	64 4	4	100	45	DARKER GREEN, STRONG PROP ALT. C.G. GDR. V. BROKEN UP. FRACTS MOSTLY @ 70° TO C/A.	TRACE DISS PY		65									

SCALE CHANGE 1" = 20'

OMNI RESOURCES INC
DIAMOND DRILL HOLE LOG

PROJECT	SKUKUM CREEK (WH)	HOLE No.	87-46 TH10
COORDINATE N.		DEPTH	58'
E.		AZIMUTH	
ELEVATION		INCLINATION	
DATE STARTED	NOV. 10, 1987 LOGGED DEC 13, 1987	DRILLED BY	SARON DIAMOND DRILLING
COMPLETED	NOV. 10, 1987	ASSAYED BY	ACME ANALYTICAL LABS
HOLE SURVEY		LOGGED BY	RJR

Reason for Drilling: TO TEST ZONE IN EAST WALL X-CUT #2 EN-HW BTWN HOLES TH 7 + TH8

Explanation of Results:

LEGEND

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE No.	SAMPLE INTERCEPT	CORE LENGTH	ANALYTICAL O.P.T. Au	O.P.T. Ag	Pb	Zn	As	Sb
					BXXD GDR. DK-GREEN, STRONG PROP. ALT'D. V. BROKEN UP. BASE CONTACT SHARP, FLOW / INTRUSIVE. 90° TO C/A	MINOR DISS PY.		0									
1	8 8	8	100	15	RHYOLITE, MED GRAINED, MED-LT. GREEN. MOD. INFILLING YELLOW QZ STRINGERS. WEAK, WELL HEALED CRACKLE. NARROW BLOB OF QSBX @ 4.0'. PROBABLY XENOLITH. ALSO XENOLITH OF GDR BX @ 9.5-11'. QUITE BROKEN-UP MOST FRACTS APPEAR TO BE PERP TO C/A. BASE INT. SHARP, 40°	TRACE DISS PY OVERALL.											
	5 5	5	100	26		15 %PY IN QTZ SX & FRAG 1-2 % SI-GL.		12.4									
17.3	5 5	5	100	80	QUARTZ SULFIDE BRECCIA IN RHYOLITE AND GDR. MOSTLY (>80%) QZ SX BX. DIFFICULT TO DETERMINE WHEN RHY ENDS + GDR BEGINS.	MINOR AS, SB. 15 % TOTAL SX.			3225 *	12.4-17.5	5.1'	.302	67.55	3.54	2.43	.10	.0
	5 5	5	100	80	WELL-MINERALIZED. STRONG, WELL-HEALED LATE CRACKLE. SOME ZONES ALMOST BLACK WITH SI/GL, SOME ALMOST BARREN QZ. FRACTS 45, 70+90° TO C/A	~50:50 PY-AS / SI-GL		17.5									
2	5 5	5	100	56	BASE CONTACT SHARP, INTRUSIVE, SLIGHT BXXD. 40°			20	3226 *	17.5-25.7	8.2'	.567	12.46	1.32	.86	.06	.0
	4 4	4	100	0	BXXD GDR + UP TO 50 % QSXBX. SOME FRAGS RHY. SO ACTUALLY ML BX. V.U. BROKEN-UP. S. PROP. ALT'N.	2.5.7 5% CL/SL 5% PY/AS, SB.		25.7									
	6 6	6	100	0	M-S PHYLLIC GDR BX. FRAGS OF QSBX + MINZD ZONES. V. SOFT + CRUMBLY. ABUNDANT CLAY	MINOR DISS PY		30.3	3227 *	25.7-30.3	4.6'	.176	34.56	3.25	2.95	.82	.02
3	4 4	4	100	43	AND LATE CA. LT GREEN, LESS MINERALIZED WITH DEPTH. FRACTS + SHEARS N 75 W 90° TO C/A	QTZ FRAGS + VFG DISS SX.		35.0	3228	30.3-35.0	4.7'	0.058	14.66				
	4 4	4	100	0	BASE CONTACT GRADATIONAL			40 40.4	3229	35.0-40.4	5.4'	0.017	0.52				
	5 5	5	100	18	AS ABOVE BUT LESS MINZD + LESS STRONGLY ALT'D — ONLY WEAK PHYLLIC — STRONG PROP. STILL QUITE SHEARED. FRACTS+SHEARS 45, 75 +90° BASE GDR	MINOR DISS PY.		45.6	3230	40.4-45.6	5.2'	0.003	0.05				
4	7 7	7	100	9	DK GRN 5-1. PROP ALT'D GDR. V. BROKEN UP. SLIGHT CA-HEALED CRACKLE. SOME V. THIN, LATE QZ + CA VEINLETS. WEAK SHEARING FRACTS+SHEARS 45, 75 +90° TO C/A.	TRACE DISS VFG PY.		50									
58.0	6.8				END OF HOLE - 58.0	EOH		60									EOH

OMNI RESOURCES INC
DIAMOND DRILL HOLE LOG

PROJECT	SKUKUM CREEK (WH)
COORDINATE N.	
E.	
ELEVATION	
DATE STARTED	NOV 11, 1987 LOGGED DEC 11, 1987
COMPLETED	NOV 11, 1987
HOLE SURVEY	
HOLE No.	87-UGTH 11
DEPTH	28'
AZIMUTH	
INCLINATION	
DRILLED BY	CARON DIAMOND DRILLING
ASSAYED BY	ACME ANALYTICAL LABS
LOGGED BY	R.T.R.

Reason for Drilling: TO TEST WEST WALL #1 X-CUT FW-HW BTWN TH 3-TH4

Explanation of Results:

LEGEND

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE No.	SAMPLE INTERCEPT	CORE LENGTH	ANALYTICAL O.P.T. Au	O.P.T. Ag	Pb	Zn	As	Sb
					SDR: DK GRN - STRONG PROP ALT - V. BROKEN UP. ABUNDANT CA. FRACTS AT ALL ANGLES WELL-HEALED CRACKLE. BASE CAT: GDRN	TRACE DISS PY 3.2		0		~~0.0-3.2~~							
	8.0				BANDED, BXXD I. PROP / W. PHYLLIC ALT'D. LT. GRN-GRY GDR. SOME FRACTS CLAY LINED / SHEARED. SOME LATE CA VEINING. STRONG CA-HEALED CRACKLE. FRACTS 50-65° TO C/A. BASE FLUI - BXXD @ 70° TO C/A	TRACE DISS PY 7.7		3.2	3205	3.2-7.7	4.5'	0.002	0.14				
1		8.0	100	33				7.7									
	13.0	5.0	100	44	HYDROTHERMAL BRECCIA: V. HARD, VFG, LT GRN - RHY. BXXD & SX MATRIX. SOME ZONES MATRIX SUPPORT, SOME CLAST SUPPORTED. NOT VERY MUCH QZ IN BX. ONLY ~ 1-2% MORE QZ & DEPTH. SOME ZONES V. STRONGLY BXXD & CLASTS 1-3 mm IN BLACK VFG MATRIX, OTHER ZONES UN-BX RHY OR JUST TWIN SX STRINGERS. FRACTS 70-80° TO C/A. BASE GRADATIONAL.	20-25% TOTAL SX. SL > GL, PY, AS, SB IN THAT ORDER. ~ ½ SX ARE SL/GL. 18.6		10	3206 *	7.7-13.7	6.0'	0.196	8.25	.83	.92	2.49	.05
2	18.0	5.0	100	50				13.7									
	23.0	5.0	100	44	BRECCIATED GRANODIORITE: U. ABUNDANT QZ + PY MATRIX IN GDR. MORE QZ-FLOODED THAN PROPER BX. V. ABUNDANT LATE CA STRINGERS. MOST FRACTS 70-80° TO C/A. BASE SHARP SHEAR @ 85° TO C/A. HW SHEAR TO 23.2 THEN MG GDR. WEAR PROP. ALT'D. SHEAR SOFT, CRUMBLY. ~ 30% MAFICS. MOD. CA-HEALED CRACKLE, SOME HEMATITE CA VEINS TO 4 mm. FRACTS @ 55 + 85° TO C/A.	3-5% DISS PY IN QZ. 23.2		18.6	3207 *	13.7-18.6	4.9'	0.114	6.58	.79	.96	.96	.02
	28.0	5.0	100	40	28.0' END OF HOLE	TRACE TO MINOR DISS & BLEBS PY. DECREASING & LENGTH		20	3208	18.6-23.2	4.6'	0.102	1.32				
								23.2	3209	23.2-28.0	4.8'	0.001	0.09				
								30									
								40									
								50									
								60									

EOH. 28.0'

OMNI RESOURCES INC
DIAMOND DRILL HOLE LOG

Reason for Drilling: TO TEST ZONE IN & ABT WALL OF X-CUT @ FW-HW CONTACT TH 1 & TH 2

Explanation of Results:

LEGEND

PROJECT: SKUKUM CREEK (WH)
COORDINATE N.
E.
ELEVATION
DATE STARTED: NOV 11, 1987 - LOGGED DEC 7, 1987
COMPLETED: NOV. 11, 1987
HOLE SURVEY

HOLE No.: 87-4GTH 12
DEPTH: 28'
AZIMUTH
INCLINATION
DRILLED BY: CARON DIAMOND DRILLING
ASSAYED BY: ACME ANALYTICAL LABS LTD
LOGGED BY: RTR.

BOX	Run	Core	%R	R.Q.D.	LITHOLOGY, ALTERATION, STRUCTURE	MINERALIZATION	GRAPHIC LOG	FT.	SAMPLE No.	INTERCEPT	CORE LENGTH	ANALYTICAL O.P.T. Au	O.P.T. Ag	Pb	Zn	As	Sb
	8 (0-8)	8	100	40	GDR. LT GRN-GRY · AR. QZ. U. BRKTN UP. BXX OA SHEAR @ 70°/70 C/A - MED-DK GRN-GRY GDR. F-M-GRAINED. WEAK, WELL-HEALED CRACKLE. FRACTS @ 65-75° TO C/A. STRONG PROP. ALT, INCREASING WITH DEPTH. BASE CONTACT GRAD. BXD FLOW.	TRACE DISS PY		1.6									
1	5 (13)	5	100	60	QUARTZ SULFIDE BRECCIA IN RHYOLITE. U. HARD. UFG WEAK PROP ALT'D LT GRN RHY. BRXXN VARIES FROM RHY WITH SPARSE STRINGERS TO ALMOST TOTAL BXXD QZ ± NO RHY. IN BETWEEN IS CLAST SUPP RHY BX, MATRIX SUPPT RHY ± QTZ SX. AND EQUAL PARTS FAIRLY FINE-GRAINED QTZ-RHY ± CLASTS ± SX MATRIX. FRACTS MOSTLY PERP TO C/A. MINOR LATE CA. BASE CNT GRAD INTO GDR.	TRACE DISS PY		8.0								
	5 (18)	5	100	78		APPROX 20-25% SULFIDES: SL, GL, PY AS, Sb. AS MATRIX IN QZ BXXA. MORE AS THAN THII.		13.6	3211 *	8.0-13.6	5.6'	0.127	21.74	2.72	3.50	1.13	0.04
	5 (23)	5	100	60	WEAKLY MINERALIZED BXXD GDR - QZ FLOODED WITH 5-7% SX, MOSTLY PY. U. BROKEN. UP. ABUNDANT LATE CA STRINGERS ± FRACT-FILLING. FRACTS 65-70° TO C/A. BASE SHARP SHEAR PERP. TO C/A.	7% SX IN QZ BXXA IN SAME PROPORTIONS AS 23.7 MORE PY. ABUN.		19.1	3212 *	13.6-19.1	5.5'	0.286	8.61	1.11	1.02	1.66	0.03
2	5 (28)	5	100	36	STRONG PROP. GDK. SLIGHTLY BANDED & COMPRESSED PERP. TO C/A. FRACTS @ 45° TO C/A. AB. CHLORITE. NO CRACKLE. TOP 20 cm HW. SHEAR ZONE.	TRACE TO MINOR DISS PY.		23.7	3213	19.1-23.7	4.6'	0.088	3.54				
					END OF HOLE. 28.0'	EOH.		28.0	3214	23.7-28.0	4.3'	0.003	0.24				
																	28.0' END OF HOLE

APPENDIX 6

ASSAY RESULTS

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE:251-1011

DATE RECEIVED JUNE 23 1987

DATE REPORTS MAILED July 29/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.
AG** & AU** BY FIRE ASSAY

ASSAYER D Toye DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SKUKUM CREEK FILE# 87-1940 PAGE# 1

SAMPLE	Ag** oz/t	Au** oz/t	WIDTH
9696	.06	.003	3.1'
9697	7.79	.316	5.4'
9698	1.11	.022	0.9'
9699	5.76	.060	1.9'
9700	49.91	.177	1.6'
9701	1.86	.052	2.5'
9702	.43	.005	4.8'
9703	.08	.002	6.6'

VG2

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: JUNE 24 1987
DATE REPORT MAILED: June 26/87

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-1972

SAMPLE#	AG** OZ/T	AU** OZ/T	
9704	.07	.005	3.9'
9705	.86	.013	6.1'
9706	53.99	.300	.58 1.9' 2
9707	7.11	.118	2.8' 3
9708	.77	.009	5.0'
9709	2.36	.047	4.6'
9710	.12	.002	3.9'
9711	.45	.016	4.2'
9712	1.55	.045	5.1'
9713	.08	.001	5.8'
9714	.98	.010	4.0'
9715	.14	.003	3.8'

/

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: JULY 1 19E

DATE REPORT MAILED: July 3/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-2110

SAMPLE#	AG** OZ/T	AU** OZ/T
9727	1.59	.009
9728	.03	.001
9729	.01	.001
9730	.20	.001
9731	.08	.005
9732	.27	.006
9733	.59	.021
9734	3.10	.072
9735	.39	.009
9736	.64	.056
9737	.26	.007
9738	7.14	.138
9739	2.24	.070
9740	9.44	.182
9741	2.89	.075
9742	.95	.014
9743	10.91	.148
9744	.26	.002
9745	.22	.003
9746	.33	.021
9747	18.20	.180
9748	.23	.006
9749	.93	.042
9750	.13	.001
9751	.11	.002
9752	.10	.004
9753	.03	.002
9754	.04	.004
9755	.06	.001

UG-3 (4

11/08

U65

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: JUL 2 1987

DATE REPORT MAILED: July 6/87...

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-2166

SAMPLE#	AG** OZ/T	AU** OZ/T
9756	.03	.001
9757	58.92	.093
9758	.10	.001
9759	.84	.001
9760	1.02	.001
9761	.63	.003
9762	3.22	.023
9763	12.99	.054
9764	.10	.001
9765	.16	.001
9766	.15	.001
9767	63.86	.109

UG 6+7 SENT JULY 3

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: JULY 9 1987
DATE REPORT MAILED: July 16/87
RECEIVED JULY 20

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-2332

SAMPLE#	AG** OZ/T	AU** OZ/T
9768	.11	.001
9769	.03	.001
9770	.05	.001
9771	.03	.001
9772	.04	.001
9773	.16	.002
9774	9.66	.077
9775	.18	.002
9776	.01	.001
9777	.01	.001
9778	.23	.001
9779	.03	.001
9780	20.44	.690
9781	2.02	.039
9782	.12	.006
9783	.01	.001

UG6

UG7

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: JULY 8 1987
DATE REPORT MAILED: July 10/87

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-2280
87-R4 AND 87-UG8

SAMPLE#	AG** OZ/T	AU** OZ/T
6151	.12	.001
6152	.09	.001
6153	.28	.009
6154	.67	.031
6155	.04	.001
6156	1.66	.182
6157	.16	.003
6158	1.43	.037
6159	.42	.056
6160	.01	.001
END R-4 9784	.11	.001
9785	.08	.003
UG-8 9786	.10	.001
9787	.01	.001
START. R-4 9788	.32	.005
9789	.18	.007
9790	.37	.021
9791	.69	.026
9792	.53	.031
9793	.36	.012
9794	.54	.013
9795	1.21	.022
9796	35.52	.284
9797	.68	.085
9798	.68	.019
9799	.08	.003
9800	.01	.001

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: JUL 9 1987
DATE REPORT MAILED: July 14/87.
RECEIVED July 15/87

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D.A.Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES File # 87-2327 Page 1

UG-8

SAMPLE#	AG** OZ/T	AU** OZ/T
6161	.02	.001
6162	.06	.001
6163	.01	.001
6164	.07	.001
6167	.02	.001
6168	.01	.001
6169	.04	.001
6170	.02	.001
6171	.01	.001
6172	.01	.001
6173	.09	.001
6174	.02	.001
6175	.02	.001
6176	.01	.001
6177	.01	.001
6178	.03	.001
6179	.01	.001
6180	.08	.001
6181	.03	.001
6182	.20	.017
6183	.30	.016
6184	.06	.002
6185	.07	.001
6186	.09	.001
6191	.04	.001
6192	.13	.009
6193	.07	.001
6194	.01	.001
6195	.02	.001
6196	.06	.001
6197	.10	.001
6198	.06	.001
6199	.10	.001
6200	.03	.001
6201	.06	.005
6202	.07	.001

SAMPLE#	AG** OZ/T	AU** OZ/T
	87-UG8	
6203	.10	.008
6204	.35	.007
6205	.76	.013
6206	.08	.005
6207	.06	.001
6208	.07	.001

BONDAR-CLEGG & COMPANY LTD.

136B INDUSTRIAL RD, WHITEHORSE, YUKON Y1A 2V1 PHONE: (403) 667-6523

Certificate of Analysis

TO Omni Resources

87-UG8

REPORT NO. 47-4342

DATE July 8, 1987
Received July 15

I hereby certify that the following are the results of analyses made by us upon the herein described rock samples

MARKED	oz/ton Au	oz/ton Ag
6165	0.01	0.09
6166	0.01	0.36
6187	L0.01	0.05
6188	0.01	0.19
6189	L0.01	0.12
6190	0.04	0.29

BONDAR-CLEGG & COMPANY LTD.

John R

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE:251-1011

DATE RECEIVED JULY 18 1987

DATE REPORTS MAILED July 29/87

Received July 31st Expressmail

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.
AG** & AU** BY FIRE ASSAY

ASSAYER D Toye DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SKUKUM CREEK FILE# 87-2531 PAGE# 1

SAMPLE	Ag** oz/t	Au** oz/t
T 6209	.04	.001
T 6210	.01	.001
T 6211	.11	.001
T 6212	.18	.006
T 6213	1.67	.059
T 6214	.26	.046
T 6215	1.74	.022
T 6216	.02	.001
T 6217	.03	.001
T 6218	.01	.004
T 6219	.10	.001
T 6220	.03	.001
T 6221	.17	.001
T 6222	.05	.001
T 6223	.05	.001
T 6224	.03	.001
T 6225	.06	.001
T 6226	.08	.006
T 6227	.30	.008
T 6228	.10	.004
T 6229	.39	.048
T 6230	.01	.002
T 6231	.01	.003
T 6232	1.21	.007
T 6233	.11	.001
T 6234	.18	.002
T 6235	.70	.012
T 6236	.24	.003
T 6237	3.39	.058
T 6239	13.20	.133
T 6240	1.88	.048
T 6241	1.84	.099
T 6242	2.90	.043
T 6243	.11	.004
T 6244	.07	.002
T 6245	.04	.001
T 6246	.06	.002

87 46-9 POSTED 7/31/87

86 46-10 POSTED 7/31/87

86 46-11 POSTED 7/31/87

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE:251-1011

DATE RECEIVED JUL 18 1987

DATE REPORTS MAILED July 24/87
Received July 31st

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.
AG** & AU** BY FIRE ASSAY

ASSAYER D. Toye DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES INC. PROJECT SKUKUM CREEK FILE# 87-2525 PAGE# 1

SAMPLE	Ag** oz/t	Au** oz/t
~~T 6247~~	.01	.001
T 6248	.28	.002
T 6249	.13	.001
T 6250	.05	.006
T 6251	.74	.039
T 6252	.58	.016
T 6253	7.24	.232
T 6254	.22	.012
T 6255	4.02	.272
T 6256	.34	.022
T 6257	1.22	.112
T 6258	.26	.013
T 6259	.30	.010
T 6260	.11	.011
T 6261	.24	.009
T 6262	.02	.001
T 6273	.12	.001
T 6274	.01	.001
T 6275	.01	.001
T 6276	.01	.001
T 6277	.10	.002
T 6278	1.50	.035
T 6279	1.28	.032
T 6280	.39	.015
T 6281	2.25	.039
T 6282	.19	.003
T 6283	.14	.001
T 6284	.22	.001
T 6285	.24	.007
T 6286	4.85	.229
T 6287	.10	.002
T 6288	.06	.001

87-UG12 posted 7/31/87

87-UG13 posted 7/31/87

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

K-2 DATE RECEIVED: JULY 22 1987

DATE REPORT MAILED: July 29/87.
Received July 31st

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK-CR File # 87-2617

SAMPLE#	AG** OZ/T	AU** OZ/T
T-6263	.01	.001
K-2 T-6264	.02	.001
T-6265	.04	.001
T-6266	.02	.001
T-6267	.01	.001
T-6268	.02	.001
T-6269	.04	.001
T-6270	.01	.001
T-6271	.02	.001
T-6289	.16	.002
T-6290	.48	.044
T-6291	.44	.017
T-6292	.11	.016
T-6293	.18	.011
T-6294	9.19	.342
UG-4		
T-6295	.31	.007
T-6296	.21	.002
T-6297	.12	.001
T-6298	.16	.001
T-6299	.60	.012
T-6300	.05	.001
T-6301	.01	.001
T-6302	.01	.001
T-6303	.15	.005
T-6304	.04	.001
6A		
T-6305	.03	.002
T-6306	.01	.001

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
V6A 1R6 (604)253-3158 COMPUTER LINE:251-1011

DATE RECEIVED JULY 25 1987

DATE REPORTS MAILED Aug 3/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.

ASSAYER D. Toye DEAN TOYE . CERTIFIED B.C. ASSAYER

OMNI RESOURCES FILE# 87-2721

UG 15

SAMPLE	Ag** oz/t	Au** oz/t
T 6307	.01	.001
T 6308	.02	.002
T 6309	7.35	.055
T 6310	53.70	.480
T 6311	40.10	.145
T 6312	3.66	.132
T 6313	.94	.038
T 6314	.47	.025
T 6315	.38	.055
T 6316	.55	.015
T 6317	.42	.058
T 6318	1.34	.057
T 6319	4.43	.266
T 6320	.10	.008
T 6321	.04	.002
T 6322	.01	.001
T 6323	.02	.005
T 6324	.01	.004
T 6325	.01	.002
T 6326	.01	.001
T 6327	.01	.002
T 6328	.01	.001
T 6329	.04	.001

87-GIA

UG-16

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE:251-1011

DATE RECEIVED JUL 27 1987

DATE REPORTS MAILED Aug 3/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.
AG** & AU** BY FIRE ASSAY

ASSAYER D Toye DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SK FILE# 87-2755 PAGE# 1

SAMPLE	Ag** oz/t	Au** oz/t	
T 6330	.16	.001	
T 6331	.03	.001	
T 6332	.03	.001	
T 6333	.09	.001	
T 6334	.21	.001	
T 6335	.01	.001	
T 6336	.05	.001	
T 6337	.01	.001	
T 6338	.04	.001	
T 6339	.04	.001	
T 6340	.02	.001	
T 6341	.18	.006	
T 6342	.71	.021	
T 6343	.21	.006	
T 6344	1.53	.023	↑
T 6345	8.73	.182	3.2
T 6346	2.79	.075	1.7
T 6347	.31	.012	↓
T 6348	1.19	.059	1.8
T 6349	.18	.009	
T 6350	.08	.002	
T 6351	.17	.001	
T 6352	.01	.001	

P1 UG 17
P2 G 1H (RS)

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE: 251-1011

DATE RECEIVED JUL 29 1987

DATE REPORTS MAILED Aug 6/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.
AG** & AU** BY FIRE ASSAY

ASSAYER D Toye DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SKUKUM CREEK FILE# 87-2829 PAGE# 1

SAMPLE	Ag** oz/t	Au** oz/t
T 6353	.20	.003
T 6354	.17	.003
T 6355	.01	.001
T 6356	.15	.001
T 6357	.03	.001
T 6358	.08	.001
T 6359	.04	.001
T 6360	.07	.001
T 6361	.10	.001
T 6362	.11	.001
T 6363	.33	.001
T 6364	13.90	.926
T 6365	.68	.096
T 6366	37.40	.754
T 6367	15.10	.184
T 6368	46.50	1.924
T 6369	48.80	1.580
T 6370	4.78	.154
T 6371	2.20	.297
T 6372	1.31	.147
T 6373	.45	.004
T 6374	.58	.003
T 6375	.15	.001
T 6376	.05	.003
T 6377	.96	.172
T 6378	.12	.024
T 6379	.05	.001
T 6380	.11	.001
T 6381	.51	.093
T 6382	.62	.023
T 6383	4.85	.423
T 6384	.11	.030
T 6385	28.50	.519
T 6386	.48	.021
T 6387	.23	.006
T 6388	.15	.006

SAMPLE#	AG** OZ/T	AU** OZ/T
T 6389	.04	.001
T 6390	.05	.001
T 6391	.04	.001
T 6392	.01	.001
T 6393	.03	.001
T 6394	.01	.001
T 6395	.01	.001
T 6396	.03	.001

UG 18+R6

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE: 251-1011

DATE RECEIVED AUG 1 1987

DATE REPORTS MAILED Aug 12/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.
AG** & AU** BY FIRE ASSAY

ASSAYER D. Toye DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SKUKUM CREEK FILE# 87-2908 PAGE# 1

SAMPLE	Ag** oz/t	Au** oz/t
T 6397	.27	.013
T 6398	1.00	.078
T 6399	.09	.001
T 6400	.04	.001
T 6401	.13	.001
T 6402	.13	.002
T 6403	.78	.009
T 6404	.27	.001
T 6405	1.63	.019
T 6406	25.85	.265
T 6407	1.93	.052
T 6408	.78	.011
T 6409	7.97	.093
T 6410	4.93	.310
T 6411	.16	.006
T 6412	2.17	.250
T 6413	.11	.007
T 6414	.01	.002

R7 / UG19 / UG20

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE: 251-1011

DATE RECEIVED AUG 8 1987

DATE REPORTS MAILED Aug 17/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.
AG** & AU** BY FIRE ASSAY

ASSAYER D. Toye DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SK. FILE# 87-3095 PAGE# 1

SAMPLE	Ag** oz/t	Au** oz/t	
T 6415	.68	.013	
T 6416	.01	.001	
T 6417	.01	.001	
T 6418	.08	.006	
T 6419	1.12	.075	
T 6420	.59	.008	
T 6421	.63	.004	R7
T 6422	1.45	.005	
T 6423	.66	.031	
T 6424	.12	.029	
T 6425	1.55	.061	
T 6426	.10	.002	
T 6427	.09	.007	
T 6428	1.17	.060	
T 6429	.73	.037	
T 6430	.30	.003	
T 6431	.58	.009	
T 6432	.33	.341	
T 6433	.14	.004	
T 6434	.21	.006	
T 6435	.58	.026	
T 6436	19.20	1.850	UG19
T 6437	4.28	.172	
T 6438	.45	.035	
T 6439	19.45	.459	
T 6440	3.03	.217	
T 6441	1.24	.049	
T 6442	.92	.071	
T 6443	.73	.003	
T 6444	.09	.001	
T 6445	1.11	.016	
T 6446	.56	.050	
T 6447	2.57	.252	
T 6448	3.68	.199	
T 6449	.25	.035	
T 6450	.11	.014	

SAMPLE	Ag** oz/t	Au** oz/t
T 6451	.01	.001
T 6452	.25	.026
T 6453	.06	.009
T 6454	.08	.005
T 6455	.74	.007
T 6456	1.71	.020
T 6457	.43	.003
T 6458	.29	.006
T 6459	1.01	.010
T 6460	.29	.001
T 6461	.06	.001
T 6462	.85	.008
T 6463	.27	.001
T 6464	.20	.004
T 6465	.05	.001
T 6466	.08	.001
T 6467	.01	.001
T 6468	.18	.001

UG20

UG21/K8

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE: 251-1011

DATE RECEIVED AUG 10 1987

DATE REPORTS MAILED Aug 15/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.
AG** & AU** BY FIRE ASSAY

ASSAYER _____ DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SK FILE# 87-3142

SAMPLE	Ag** oz/t	Au** oz/t
T-6469	.05	.001
T-6470	.14	.001
T-6471	.04	.001
T-6472	.07	.001
T-6473	.11	.001
T-6474	.37	.036
T-6475	.26	.009
T-6476	.06	.001
T-6477	.01	.001
T-6478	.11	.001
T-6479	.05	.001
T-6480	.04	.001
T-6481	.01	.001
T-6482	.20	.001
T-6483	.04	.001
T-6484	.02	.001
T-6485	.13	.001
T-6486	.01	.001
T-6487	.02	.001
T-6488	1.64	.001
T-6489	.31	.001
T-6490	.13	.001
T-6491	11.75	.213
T-6492	7.09	.179
T-6493	3.12	.131
T-6494	.05	.002
T-6495	1.56	.035
T-6496	10.04	.136
T-6497	1.16	.015
T-6498	11.86	.151
T-6499	.33	.008
T-6500	1.31	.123
T-6501	.17	.026
T-6502	.36	.050
T-6503	.11	.026
T-6504	.02	.001
T-6505	.11	.004

UG 22+26

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604) 253-3158 COMPUTER LINE: 251-1011

DATE RECEIVED AUG 13 1987

DATE REPORTS MAILED Aug 21/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.
AG** & AU** BY FIRE ASSAY

ASSAYER D Toye DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SKUKUM CREEK FILE# 87-3235 PAGE# 1

SAMPLE	Ag** oz/t	Au** oz/t	
T 6537	.06	.001	
T 6538	.05	.008	
T 6539	.29	.024	
T 6540	.08	.005	
T 6541	.04	.001	
T 6542	.11	.001	
T 6543	.43	.003	
T 6544	.04	.001	
T 6545	.04	.001	22
T 6546	.13	.001	
T 6547	.14	.001	
T 6548	.12	.001	
T 6549	.25	.005	
T 6550	.08	.005	
T 6551	.65	.019	
T 6552	.37	.016	
T 6553	.02	.001	
T 6554	.11	.002	
T 6555	.05	.001	
T 6556	.14	.001	
T 6557	.42	.182	
T 6558	2.52	.102	
T 6559	1.15	.015	
T 6560	3.39	.244	
T 6561	8.57	.975	
T 6562	21.58	4.320	
T 6563	6.82	1.050	
T 6564	5.23	1.035	
T 6565	.05	.002	
T 6566	.04	.003	
T 6567	.02	.001	
T 6568	.06	.001	
T 6569	.06	.001	

Posted

Posted

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE:251-1011

DATE RECEIVED AUG 13 1987

DATE REPORTS MAILED Aug 21/87

Received Nov 18/87

ASSAY CERTIFICATE

SAMPLE TYPE : ROCK/CORE
AG## & AU## BY FIRE ASSAY

ASSAYER _____ DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SK. FILE# 87-3229 PAGE# 1

SAMPLE	Ag** oz/t	Au** oz/t	
X 3829	18.75	.610	Kohn X-cut muck samples
X 3830	.25	.027	
X 3831	.11	.052	
T 6506	.28	.015	
T 6507	.01	.001	
T 6508	.01	.001	
T 6509	.01	.001	
T 6510	.02	.001	
T 6511	.01	.001	
T 6512	.01	.001	
T 6513	.01	.001	
T 6514	.01	.001	
T 6515	.02	.001	
T 6516	.26	.030	
T 6517	.22	.007	
T 6518	.21	.004	87-0623K
T 6519	.11	.001	
T 6520	.07	.001	
T 6521	.18	.009	
T 6522	.26	.021	
T 6523	.02	.001	
T 6524	.18	.015	
T 6525	.63	.035	
T 6526	.14	.005	
T 6527	.06	.002	
T 6528	.01	.001	
T 6529	.01	.001	
T 6530	.52	.016	
T 6531	.14	.001	87-0624K
T 6532	.03	.001	
T 6533	.04	.001	
T 6534	.21	.001	
T 6535	.11	.002	
T 6536	.06	.001	

entered on logs Nov 19/87 BR.

87-UG-25 Sent Aug 11
Received Aug 28

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: AUG 15 1987
DATE REPORT MAILED: Aug. 24/87...

ASSAY CERTIFICATE

- SAMPLE TYPE: CORE AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-3339

POSTED AUG 30

SAMPLE#	AG** OZ/T	AU** OZ/T
T-6591	.28	.001
T-6592	.11	.001
T-6593	.05	.001
T-6594	.03	.002
T-6595	.01	.001
T-6596	.01	.001
T-6597	.03	.002
T-6598	.10	.001
T-6599	.04	.004
T-6600	.11	.002
T-6601	.02	.001
T-6602	.01	.001
T-6603	.31	.004
T-6604	.21	.005
T-6605	.23	.004
T-6606	.06	.002
T-6607	.01	.001
T-6608	.06	.001
T-6609	.07	.004

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: AUG 20 1987
DATE REPORT MAILED: Aug. 26/87...

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye.. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK File # 87-3467

Received 8/21/87

UG-27

Posted to log

SAMPLE#	AG** OZ/T	AU** OZ/T
T-6610	.03	.001
T-6611	.01	.001
T-6612	.02	.001
T-6613	.17	.001
T-6614	.03	.001
T-6615	.01	.001
T-6616	.69	.002
T-6617	.16	.003
T-6618	.10	.001
T-6619	.01	.001
T-6620	.02	.001
T-6621	.03	.001
T-6622	.01	.001

AG-28 - UG29

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: AUG 21 1987
DATE REPORT MAILED: Aug 31/87

Received Sept 3.

POSTED

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK. File # 87-3516

SAMPLE#	AG** OZ/T	AU** OZ/T
T 6623	.02	.001 5
T 6624	.07	.001 5
T 6625	.05	.001 5
T 6626	1.18	.089 3 5
T 6627	.08	.002 5
T 6628	.22	.001 5
T 6629	.23	.001 5
T 6630	.02	.001 4.5 UG29
T 6631	.07	.001 3.2
T 6632	.18	.005 3.3
T 6633	.15	.001 1.6
T 6634	1.62	.062 4.3
T 6635	.34	.024 4.3
T 6636	1.25	.106 5.0
T 6637	.08	.001 5.0
T 6638	.04	.001 5.0
T 6639	.35	.001 5
T 6640	.49	.037 UG28
T 6641	.10	.001 5
T 6642	.36	.053 5
T 6643	.67	.002 5
T 6644	.08	.001 5
T 6645	.13	.001 5

R9 - 4G30

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: AUG 31 1987
DATE REPORT MAILED: Sept 7/87....

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye.. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK File # 87-3787

SAMPLE#	AG** OZ/T	AU** OZ/T	
X-3063	1.91	.115	R8
T-6646	.27	.001	
T-6647	.03	.001	R9
T-6648	.01	.001	
T-6649	.03	.001	
T-6650	.03	.001	
T-6651	.01	.001	
T-6652	.04	.001	
T-6653	.15	.001	
T-6654	.01	.001	
T-6655	.01	.001	
T-6656	.02	.001	
T-6657	.02	.001	
T-6658	.03	.001	
T-6659	.01	.001	
T-6660	.03	.001	4G-30
T-6661	.08	.010	
T-6662	.44	.007	
T-6663	.14	.011	
T-6664	.81	.007	
T-6665	.25	.002	
T-6666	.46	.006	
T-6667	3.58	.024	
T-6668	9.86	.294	
T-6669	.05	.001	
T-6670	.26	.030	
T-6671	.32	.001	
T-6672	.01	.001	
T-6673	.05	.001	
T-6674	.02	.001	
T-6675	.03	.001	

Received 9/11/87

Posted to log 9/11/87 mt

87-4631

Received Sept 18, 1987

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: SEPT 8 1987
DATE REPORT MAILED: Sept. 16/87

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-4000 Page 1

SAMPLE#	AG** OZ/T	AU** OZ/T
T 6676	.08	.001
T 6677	.09	.001
T 6678	.01	.001
T 6679	.01	.001
T 6680	.01	.001
T 6681	.01	.001
T 6682	.02	.001
T 6683	.06	.001
T 6684	.06	.001
T 6685	.06	.001
T 6686	.02	.001
T 6687	.02	.001
T 6688	.03	.001
T 6689	.02	.001
T 6690	.03	.001
T 6691	.05	.004
T 6692	.07	.002
T 6693	.01	.001
T 6694	.11	.001
T 6695	.62	.001
T 6696	.38	.001
T 6697	.25	.001
T 6698	.16	.001
T 6699	.08	.001
T 6700	.04	.001
T 6701	.08	.001
T 6702	.17	.001
T 6703	.13	.001
T 6704	.10	.001
T 6705	.12	.001
T 6706	.09	.001
T 6707	.14	.001
T 6708	.30	.004
T 6709	.02	.001
T 6710	.02	.001

POSTED
SEPT 21, 1987

SAMPLE#	AG** OZ/T	AU** OZ/T
T 6712	.08	.001
T 6713	.10	.001
T 6714	.04	.001
T 6715	.02	.001
T 6716	.03	.001

OT-UG 52

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604) 253-3158 COMPUTER LINE: 251-1011

DATE RECEIVED SEPT 14 1987

DATE REPORTS MAILED Sept 23/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE
AG & AU BY FIRE ASSAY

ASSAYER D Toye DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SKUKUM CREEK FILE# 87-4179 PAGE# 1

SAMPLE	Ag** oz/t	Sample wt. gm	Au-100 oz/t	Native Au mg	Average oz/t
T 6717	.21	780	.006	ND	.006
T 6718	.58	480	.022	ND	.022
T 6719	.28	850	.026	ND	.026
T 6720	.06	590	.003	ND	.003
T 6721	.13	500	.005	ND	.005
T 6722	.85	420	.009	ND	.009
T 6723	.27	290	.003	ND	.003
T 6724	1.61	650	.034	ND	.034

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: SEPT 14 1987
DATE REPORT MAILED: Sept 23/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-4179 Page 2

SAMPLE#	AG** OZ/T	AU** OZ/T
T 6725	.12	.001
T 6726	.10	.001
T 6727	.60	.015
T 6728	.04	.001
T 6729	.07	.001

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: SEPT 29 1987
DATE REPORT MAILED: Oct 9/87

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-4550 Page 1

Holes 33 & 36 entered on logs

SAMPLE#	AG** OZ/T	AU** OZ/T	
T 6730	.04	.001	
T 6731	.01	.001	
T 6732	.14	.005	
T 6733	.31	.004	
T 6734	.02	.001	
T 6735	.18	.001	
T 6736	.08	.001	
T 6737	.13	.001	33
T 6738	.11	.001	
T 6739	.07	.001	
T 6740	.01	.001	
T 6741	.03	.001	
T 6742	.02	.001	
T 6744	.20	.001	
T 6745	.09	.001	
T 6775	.05	.001	
T 6776	.11	.001	34
T 6777	.07	.009	
T 6778	.06	.001	
T 6779	.25	.016	
	5.12	.336	
	3.25	.213	
	8.88	1.675	
T 6783	.49	.013	
T 6784	1.95	.088	
T 6785	.97	.011	
T 6786	.47	.016	
T 6787	.21	.001	
T 6788	.31	.007	
T 6789	.63	.015	
T 6790	.14	.010	
T 6791	3.69	.131	
T 6793	4.44	.151	
	.36	.039	
T 6794	.19	.002	
T 6795	.43	.043	
T 6796	.04	.001	
T 6797	.04	.005	

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011 DATE RECEIVED: SEPT. 29 1987
DATE REPORT MAILED: Oct 9/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Rock Chips AG & AU BY FIRE ASSAY

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-4550

SAMPLE#	AG** oz/t	SAMPLE wt. gm	AU-100 oz/t	NATIVE Au mg	AVG. oz/t
T 6743	.27	430	.001	ND	.001
T 6780	5.16	870	.319	.52	.336
T 6781	8.25	760	.398	3.57	.535
T 6782	5.88	680	1.540	1.73	1.614
T 6792	4.44	660	.151	ND	.151

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE(604)253-3158 FAX(604)253-1716

DATE RECEIVED: OCT 14 1987
DATE REPORT MAILED: Oct 26/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Core
AU** AND AG** BY FIRE ASSAY FROM 1/2 A.T.

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-4836 Page 1

SAMPLE#	AG** OZ/T	AU** OZ/T	
T 6746	.04	.005	
T 6747	.05	.001	
T 6748	.01	.001	
T 6749	.04	.001	
T 6750	.03	.001	
T 6751	.13	.011	
T 6752	.61	.059	
T 6753	.13	.001	
T 6754	.30	.006	
T 6755	.18	.001	
T 6756	.14	.001	
T 6757	.33	.002	
T 6758	.31	.005	
T 6759	.09	.001	
T 6760	.31	.001	4635
T 6761	.13	.001	
T 6762	.26	.002	
T 6763	.01	.001	
T 6764	.17	.001	
T 6765	.14	.001	
T 6766	.01	.001	
T 6767	.01	.001	
T 6768	.06	.002	
T 6769	.18	.002	
T 6770	.04	.001	
T 6771	.25	.001	
T 6772	.07	.001	
T 6773	.07	.001	
T 6774	.01	.001	
T 6798	.02	.001	
T 6799	.32	.001	
T 6801	.10	.001	
T 6802	.17	.001	4637
T 6803	.25	.001	
T 6804	.05	.001	
T 6805	.16	.002	

SAMPLE#	AG** OZ/T	AU** OZ/T	
T 6806	.02	.007	
T 6807	.16	.008	
T 6808	.23	.016	
T 6809	.06	.001	
T 6810	.05	.001	UG37
T 6811	.10	.002	
T 6812	.08	.001	
T 6813	.11	.002	
T 6814	1.33	.009	
T 6815	.05	.001	
T 6816	.12	.004	
T 6817	4.97	.082	UG38
T 6818	1.05	.006	
T 6819	5.41	.180	
T 6820	.27	.064	
T 6821	4.34	.059	
T 6822	.38	.022	
T 6823	.09	.008	
T 6824	.01	.001	
T 6825	.17	.014	
T 6826	5.53	.194	
T 6827	1.28	.025	UG39
T 6828	1.85	.028	
T 6829	.05	.001	
T 6830	.02	.001	
T 6831	.59	.016	UG40
T 6832	.22	.008	
T 6833	.17	.003	
T 6834	.01	.004	
T 6835	.16	.001	
T 6836	21.89	.304	
T 6837	.50	.013	UG41
T 6838	.34	.008	
T 6839	.48	.020	
T 6840	3.04	.046	
T 6841	1.06	.019	

SAMPLE#	AG** OZ/T	AU** OZ/T
T 6844	.04	.001
T 6845	.06	.001
T 6846	.06	.001

u641

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE(604)253-3158 FAX(604)253-1716

DATE RECEIVED: OCT. 14 1987
DATE REPORT MAILED: Oct. 26/87

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AG** & AU BY FIRE ASSAY

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-4836 P.4

SAMPLE#	AG** oz/t	SAMPLE wt. gm	AU-100 oz/t	NATIVE Au mg	AVG. oz/t
T 6800	2.68	650	.036	ND	.036
T 6842	25.05	500	.167	ND	.167
T 6843	34.55	480	.237	.16	.247

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE(604)253-3158 FAX(604)253-1716

DATE RECEIVED: OCT 21 1987
DATE REPORT MAILED: Oct 26/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Core
AU** AND AG** BY FIRE ASSAY FROM 1/2 A.T.

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES File # 87-5034 Page 1

SAMPLE#	AG** OZ/T	AU** OZ/T	
T 6847	.01	.003	
T 6848	.01	.001	
T 6849	.01	.001	
T 6850	.01	.001	
T 6851	.09	.011	
T 6852	.03	.003	
T 6853	.01	.001	
T 6854	.07	.019	
T 6855	10.74	.288	U642R
T 6856	10.37	.398	
T 6857	5.82	.120	
T 6858	1.17	.035	
T 6859	1.47	.031	
T 6860	.32	.006	
T 6861	3.36	.029	
T 6862	2.11	.056	
T 6863	.37	.004	
T 6864	.36	.001	
T 6865	2.24	.012	
T 6866	.22	.033	
T 6867	.85	.014	
T 6868	.87	.007	
T 6869	.05	.001	
T 6870	.15	.001	
T 6871	1.86	.036	
T 6872	6.14	.159	U643R
T 6873	.23	.001	
T 6874	.44	.031	
T 6875	.08	.001	
T 6876	24.19	.218	
T 6877	1.92	.048	
T 6878	.65	.036	
T 6879	3.65	.099	
T 6880	.06	.001	
T 6881	.04	.001	
T 6882	.03	.001	U647R
T 6883	.10	.003	

SAMPLE#	AG** OZ/T	AU** OZ/T	
T 6884	.04	.001	
T 6885	.04	.001	
T 6886	.18	.001	
T 6887	.16	.002	
T 6888	.36	.030	
T 6889	1.71	.036	
T 6890	.04	.001	
T 6891	.20	.001	
T 6892	.03	.001	
T 6893	.01	.001	
T 6894	.08	.001	
T 6895	.04	.001	
T 6896	.16	.001	
T 6897	1.71	.060	
T 6898	.98	.043	
T 6899	73.76	.520	
T 6900	22.88	.145	
T 6901	20.87	.386	
T 6902	6.65	.163	UG47R
T 6903	.56	.022	
T 6904	.08	.001	
T 6905	.08	.001	
T 6906	.01	.001	
T 6907	.04	.001	
T 6908	.01	.001	
T 6909	.03	.001	
T 6910	.08	.001	
T 6911	.55	.012	
T 6912	1.95	.282	
T 6913	.29	.001	
T 6914	17.87	.416	
T 6915	.85	.018	UG44R
T 6916	.93	.019	
T 6917	1.93	.070	
T 6918	1.16	.012	
T 6919	.02	.001	

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE(604)253-3158 FAX(604)253-1716

DATE RECEIVED: OCT 21 1987
DATE REPORT MAILED: Nov. 3/87..

ASSAY CERTIFICATE

Received Nov 6/87

- SAMPLE TYPE: Core
AU** AND AG** BY FIRE ASSAY FROM 1/2 A.T.

ASSAYER: ..D. Toye../DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK. File # 87-5093 Page 1

Entered on logs BR.

SAMPLE#	AG** OZ/T	AU** OZ/T	
T 6920	.06	.001	} UG 45 R
T 6921	.26	.001	
T 6922	.48	.012	
T 6923	.09	.001	
T 6924	.04	.001	} 87 UG 46 R
T 6925	.04	.002	
T 6926	1.53	.044	
T 6934	.14	.006	
T 6935	.02	.001	
T 6936	.01	.001	
T 6937	.06	.001	} 87 UG 48 R
T 6938	.07	.001	
T 6939	2.42	.009	
T 6941	2.47	.108	needs native gold prep.
T 6942	2.79	.128	needs native gold prep.
T 6943	2.52	.043	
T 6944	.28	.005	
T 6945	.69	.032	
T 6946	.38	.022	
T 6947	.19	.004	
T 6948	.67	.032	
T 6949	.46	.011	
T 6950	1.23	.032	
T 6951	.29	.002	
T 6952	.41	.011	
T 6954	.01	.029	
T 6955	1.39	.037	
T 6956	.36	.007	
T 6957	.02	.002	
T 6958	.02	.001	
T 6959	.01	.001	
T 6960	.01	.001	
T 6961	.35	.001	

Received Nov 6/87

OMNI RESOURCES PROJECT-SK. FILE # 87-5093 Page 2

SAMPLE#	PB %	ZN %	AG** OZ/T	SAMPLE WT.GM	AU-100 OZ/T	NATIVE AU MG	AVG. OZ/T	
T 6927	.52	.70	3.83	500	.137	.36	.158	87 UG46 R
T 6928	.03	.05	.29	370	.008	ND	.008	
T 6929	.20	.22	2.15	470	.061	.08	.066	
T 6930	.31	.41	2.18	490	.075	.46	.102	
T 6931	1.38	.93	11.14	460	.119	.02	.120	
T 6932	.26	.27	2.35	400	.080	ND	.080	
T 6933	2.32	1.40	11.32	450	.249	.02	.250	
T 6940	1.01	2.14	12.55	450	.243	ND	.243	87 UG 48 R
T 6953	1.30	1.76	13.43	470	.265	.02	.266	

entered on 109 BJH.

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE(604)253-3158 FAX(604)253-1716

DATE RECEIVED: OCT 27 1987
DATE REPORT MAILED: Nov. 9/87

ASSAY CERTIFICATE

Received Nov 13/87

AG** AND AU** BY FIRE ASSAY.
- SAMPLE TYPE: Core

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK. File # 87-5235 Page 1

SAMPLE#	PB %	ZN %	AG** OZ/T	SAMPLE WT.	AU-100 OZ/T	NATIVE AU. MT	AVG OZ/T
T 6967	.61	2.10	6.29	530	.134	ND	.134
T 6968	.42	.59	2.35	550	.073	ND	.073
T 6969	.11	.10	.29	320	.005	ND	.005
T 6970	.23	.80	1.28	430	.149	.06	.153
T 6971	2.01	1.19	15.79	440	.118	.06	.122
T 6972	2.49	1.85	29.62	480	.142	.04	.144
T 6976	.05	.13	.25	560	.031	.14	.038
T 6977	.14	1.34	.62	470	.091	.42	.117
T 6978	.95	1.21	6.04	550	.197	.06	.200
T 6979	.22	.23	1.33	550	.064	ND	.064
T 6980	.08	.16	.51	580	.021	ND	.021
T 6981	.06	.20	.30	580	.013	ND	.013
T 6982	.22	.50	1.24	450	.024	ND	.024

UG 49 R
entered on logs - Nov 15/87

SAMPLE#	AG** OZ/T	AU** OZ/T
T 6962	.06	.002
T 6963	.07	.001
T 6964	.07	.001
T 6965	.04	.001
T 6966	.12	.001
T 6973	.48	.003
T 6974	.31	.003
T 6975	.49	.001
T 6983	1.32	.037
T 6984	.01	.001
T 6985	.01	.001
T 6986	.04	.001
T 6987	.01	.001
T 6988	.01	.001

VE 49 R
entered on log

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE(604)253-3158 FAX(604)253-1716

DATE RECEIVED: NOV 5 1987
DATE REPORT MAILED: Nov. 17/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Core
AU** AND AG** BY FIRE ASSAY FROM 1/2 A.T.

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK File # 87-5494 Page 1

ENTERED DEC 1 3 1987

SAMPLE#	AG** OZ/T	AU** OZ/T	
T 3001	.21	.007	87-UG-50R
T 3002	.05	.001	
T 3003	.24	.010	
T 3004	.24	.017	
T 3005	.07	.013	
T 3006	8.70	.013	87UG53R
T 3007	.02	.001	
T 3008	19.74	.149 *	
T 3009	.29	.004	
T 3010	1.39	.007	
T 3011	.90	.016	
T 3016	.34	.004	
T 3017	.04	.001	
T 3018	.10	.001	
T 3019	.11	.001	
T 3020	1.04	.037	87UG52R
T 3021	1.99	.024	
T 3022	3.54	.047	
T 3023	1.46	.011	
T 3024	.30	.001	
T 3025	3.54	.078	
T 3026	.02	.001	
T 3027	.01	.001	
T 3028	.06	.001	
T 3029	.30	.006	
T 3030	1.99	.076	87UG51R
T 3031	.04	.002	
T 3032	1.46	.080	
T 3033	.16	.001	
T 3034	.81	.005	
T 3035	.08	.001	
T 3036	.01	.001	
T 3037	4.76	.065	
T 3038	1.13	.007	
T 3039	1.34	.023	
T 3040	.04	.009	
T 3041	29.89	.139 *	

* should do native Au prep

SAMPLE#	AG** OZ/T	AU** OZ/T	
T 3042	1.81	.075	87UG51R
T 3043	.46	.006	
T 3044	.03	.001	
T 3045	.01	.001	
T 3046	.01	.001	
T 3047	.01	.001	87UG54R
T 3048	.06	.001	
T 3049	.02	.001	
T 3050	.27	.001	
T 3051	.07	.001	
T 3052	.05	.001	
T 3053	.02	.001	
T 3054	.01	.001	
T 3055	.06	.002	
T 3056	1.36	.022	
T 3057	7.02	.116	
T 3058	2.33	.064	
T 3059	.28	.033	
T 3060	.11	.003	
T 3061	.20	.002	
T 3062	.03	.001	
T 3063	.33	.005	
T 3064	.05	.001	
T 3065	.34	.002	
T 3066	.01	.001	
T 3067	.01	.001	TH# 1
T 3071	.02	.004	
T 3072	.01	.001	TH #2
T 3076	.53	.032	
T 6989	.02	.001	
T 6990	.21	.006	87UG50R
T 6991	.36	.003	
T 6992	.30	.001	
T 6993	.56	.012	
T 6999	.11	.001	
T 7000	.03	.001	

ACME ANALY[illegible]AL LABORATORIES LTD. 852 E. HASTINGS ST. VANCOUV[illegible]3.C. V6A 1R6 PHONE(604)253-3158 FAX(604)253-17

ASSAY CERTIFICATE

- SAMPLE TYPE: Core

DATE RECEIVED: NOV 5 1987 DATE REPORT MAILED: Nov 25/87 ASSAYER..D. Toye..DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK File # 87-5495

	SAMPLE#	CU %	PB %	ZN %	AG** OZ/T	AS %	SB %	SAMPLE WT.GM	AU-100 OZ/T	NATIVE AU.MG	AVG. OZ/T
UG53R	T 3012	.06	1.95	3.47	12.40	.11	.01	610	.322	.24	.334
	T 3013	.02	.61	.97	2.58	.25	.01	500	.122	.03	.124
	T 3014	.06	1.36	3.20	6.99	2.87	.05	620	.140	ND	.140
	T 3015	.12	2.79	3.49	19.77	6.84	.11	570	.289	ND	.289
UGTH1	T 3068	.03	.70	1.10	5.30	.44	.01	750	.242	1.02	.282
	T 3069	.02	.46	.49	4.20	.56	.01	800	.081	.06	.083
	T 3070	.06	1.75	1.48	10.30	1.18	.03	560	.116	ND	.116
UGTH2	T 3073	.02	.32	.69	2.18	.41	.01	520	.049	.08	.053
	T 3074	.01	.02	.07	.12	.13	.01	590	.034	ND	.034
	T 3075	.04	1.03	.80	9.78	1.70	.03	600	.085	.03	.087
87-UG50R	T 6994	.04	.66	1.13	8.54	1.16	.03	490	.084	ND	.084
	T 6995	.07	1.52	1.72	29.84	3.75	.09	550	.221	ND	.221
	T 6996	.23	5.44	2.73	64.96	2.36	.25	460	.236	ND	.236
	T 6997	.05	.67	2.04	13.57	1.67	.04	500	.117	.02	.118
	T 6998	.06	.71	4.02	10.16	1.70	.02	540	.120	.11	.126

entered on logs

*

see

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE(604)253-3158 FAX(604)253-1716

DATE RECEIVED: NOV 20 1987
DATE REPORT MAILED: Nov. 30/87

Recieved Dec 4/87

ASSAY CERTIFICATE

- SAMPLE TYPE: Core
AU** AND AG** BY FIRE ASSAY FROM 1/2 A.T.

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK. File # 87-5803 Page 1

SAMPLE#	AG** OZ/T	AU** OZ/T
T 3093	1.84	.034
T 3094	1.21	.035
T 3095	15.50	.162
T 3096	.16	.001
T 3097	1.44	.004
T 3098	4.73	.055
T 3100	.18	.001
T 3102	.07	.001
T 3103	.01	.001
X 3159	.06	.001
X 3160	.51	.017
X 3161	11.57	.242
X 3162	.13	.001
X 3163	.36	.001
X 3164	.25	.001
X 3165	.28	.001
X 3166	.42	.021
X 3167	.14	.001
X 3168	.07	.001
X 3169	.13	.001
X 3170	.07	.001
X 3171	.06	.001
X 3172	.06	.001
X 3173	.04	.001
X 3176	.84	.057
X 3177	.39	.001
X 3178	.17	.001
X 3179	.14	.001
X 3180	.32	.001
X 3181	.04	.001
X 3182	.08	.001
X 3183	.05	.001
X 3184	.29	.001
X 3185	.79	.001
X 3186	.12	.001

Testhole #8 entered Nov 4 on 1095 RB

87-0657K

OMNI RESOURCES PROJECT-SK FILE # 87-5803

SAMPLE#	CU %	PB %	ZN %	AG** OZ/T	AS %	SB %	SAMPLE WT.GM	AU-100 OZ/T	NATIVE AU.MG	AVG OZ/T	
T 3099	.10	5.48	2.73	26.00	.20	.02	620	.210	ND	.210	} Test Hole #8
T 3101	.05	1.99	.81	7.44	2.55	.02	400	.150	ND	.150	
T 3174	.07	.89	1.92	2.00	2.63	.01	600	.170	ND	.170	3.6
T 3175	.05	.74	2.22	1.59	3.59	.01	550	.158	ND	.158	3.5 } 87-UG57K

entered on logs

Received Dec 4/87

entered on logs

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE(604)253-3158 FAX(604)253-1716

DATE RECEIVED: DEC 11 1987
DATE REPORT MAILED: Dec. 15/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Core
AU** AND AG** BY FIRE ASSAY FROM 1/2 A.T.

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK. File # 87-6138 Page 1

SAMPLE#	AG** OZ/T	AU** OZ/T	
T 3078	1.02	.049	Test Hole #3
T 3079	.33	.011	
T 3081	.15	.003	
T 3082	.01	.001	
T 3083	.01	.001	
T 3084	1.08	.041	Test Hole #4
T 3085	.50	.006	
T 3086	1.34	.017	
T 3087	1.39	.018	
T 3088	.11	.001	
T 3089	.45	.010	
T 3092	.01	.001	
X 3115	.01	.001	B7U655R entered on 1/95
X 3116	.01	.001	
X 3117	5.48	.148	
X 3118	1.95	.060	
X 3119	.03	.001	
X 3120	6.83	.057	
X 3122	.31	.006	
X 3123	.12	.001	
X 3124	.20	.001	
X 3125	.15	.001	
X 3126	.29	.002	
X 3127	.24	.003	
X 3128	.37	.024	
X 3129	.20	.003	
X 3130	6.16	.012	
X 3131	2.80	.039	
X 3132	1.03	.008	
X 3133	.07	.001	
X 3134	.31	.010	Test Hole #5
X 3136	16.08	.047	
X 3137	.62	.004	
X 3139	3.30	.046	
X 3140	5.82	.115	
X 3141	4.94	.095	

entered B2

SAMPLE#	AG** OZ/T	AU** OZ/T
X 3142	.54	.027
X 3143	1.17	.034
X 3144	.14	.003
X 3145	.09	.004
X 3146	.01	.002
X 3147	.37	.012
X 3150	.27	.002
X 3151	41.85	.307
X 3152	8.61	.171
X 3153	2.25	.062
X 3154	14.88	.258
X 3155	1.45	.062
X 3156	21.14	.263
X 3157	.70	.053
X 3158	.13	.004

Test Hole 7
entered on logs
BZ

OMNI RESOURCES PROJECT-' FILE # 87-6138

SAMPLE#	CU %	PB %	ZN %	AG** OZ/T	AS %	SB %	SAMPLE WT. GM	AU-100 OZ/T	NATIVE AU. MG	AVG. OZ/T	
T 3080	.08	1.62	2.48	11.77	4.70	.05	650	.247	.03	.249	TH3
T 3090	.07	2.23	2.82	16.55	8.49	.08	500	.649	1.30	.725	TH4
T 3091	.01	.33	.53	2.70	1.81	.01	550	.072	.02	.073	
T 3135	.03	1.03	.44	17.84	1.52	.02	530	.171	ND	.171	TH5
X 3138	.05	1.55	2.03	9.71	.11	.01	590	.137	.20	.147	
X 3148	.05	2.26	2.82	17.50	.31	.01	520	.122	.99	.177	TH7
X 3149	.12	3.40	3.56	45.00	.28	.03	620	.244	.09	.248	

entered BZ

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE(604)253-3158 FAX(604)253-1716

DATE RECEIVED: DEC 7 1987
DATE REPORT MAILED: Dec 9/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Core
AU** AND AG** BY FIRE ASSAY FROM 1/2 A.T.

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK. File # 87-6056

SAMPLE#	AG** OZ/T	AU** OZ/T
X 3187	.27	.003
X 3188	.52	.008
X 3189	.10	.001
X 3190	.06	.001
X 3191	.03	.001
X 3192	.03	.001
X 3193	.04	.001
X 3194	.06	.001
X 3195	.34	.019
X 3196	.29	.005
X 3197	.36	.001
X 3198	.10	.002
X 3199	.01	.004
X 3200	.03	.001
X 3201	.05	.003
X 3202	.01	.001
X 3203	.02	.001
X 3204	.03	.001

87 V0 56 R
entered on log's
BZ

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE(604)253-3158 FAX(604)253-1716 DATE RECEIVED: DEC 14 1987
DATE REPORT MAILED: Dec. 21/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Core
AU** AND AG** BY FIRE ASSAY FROM 1/2 A.T.

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK. File # 87-6166 Page 1

SAMPLE#	AG** OZ/T	AU** OZ/T
X 3104	.05	.003
X 3105	4.71	.048
X 3112	.71	.023
X 3113	.43	.020
X 3114	.14	.011

Test Hole #6 entered on log BZ

SAMPLE#	CU %	PB %	ZN %	AG** OZ/T	AS %	SB %	SAMPLE WT. GM	AU-100 OZ/T	NATIVE AU. MG	AVG OZ/T
X 3106	.08	1.64	1.47	23.64	1.48	.01	510	.154	.02	.155
X 3107	.01	.34	.36	1.56	.03	.01	520	.009	ND	.009
X 3108	.05	1.65	.82	12.69	.06	.02	600	.161	ND	.161
X 3109	.03	.77	.77	7.73	.29	.01	600	.303	.33	.319
X 3110	.03	.53	.67	5.25	.04	.01	600	.059	ND	.059
X 3111	.04	.79	1.37	3.29	.08	.01	670	.163	.11	.168

Test Hole 6 entered on log BZ

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE(604)253-3158 FAX(604)253-1716 DATE RECEIVED: DEC 18 1987
DATE REPORT MAILED: JAN. 5, 1988.

ASSAY CERTIFICATE

- SAMPLE TYPE: Core
AU** AND AG** BY FIRE ASSAY FROM 1/2 A.T.

ASSAYER: ..... DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES SK File # 87-6249 Page 1

SAMPLE#	AG** OZ/T	AU** OZ/T
T 3205	.14	.002
T 3208	1.32	.102
T 3209	.09	.001
T 3210	.01	.001
T 3213	3.54	.088
T 3214	.24	.003
T 3215	.59	.029
T 3221	.05	.001
T 3222	.06	.001
T 3223	.49	.007
T 3224	.83	.021
T 3228	14.66	.058
T 3229	.52	.017
T 3230	.05	.003

ENTERED JAN U 9 1988

Test holes 9-12 entered on logs BG

ENTERED JAN U 9 1988

OMNI RESOURCES PROJECT - SK. FILE # 87-6249

SAMPLE#	PB %	ZN %	AG** OZ/T	AS %	SB %	SAMPLE WT.GM	AU-100 OZ/T	NATIVE AU.MG	AVG OZ/T
T 3206	.83	.92	8.25	2.49	.03	600	.196	ND	.196
T 3207	.79	.96	6.58	.96	.02	530	.114	ND	.114
T 3211	2.72	3.50	21.74	1.13	.04	520	.127	ND	.127
T 3212	1.11	1.02	8.61	1.66	.03	600	.267	.40	.286
T 3216	.91	.98	6.92	.05	.01	550	.159	.09	.164
T 3217	.86	.95	6.75	.36	.01	500	.216	.14	.224
T 3218	1.46	.98	6.66	.74	.01	560	.530	.05	.532
T 3219	.63	.82	4.47	.34	.01	600	.058	.05	.061
T 3220	.20	.29	.99	.61	.01	600	.024	ND	.024
T 3225	3.54	2.43	67.55	.10	.03	550	.272	.56	.302
T 3226	1.32	.86	12.46	.06	.01	600	.440	2.62	.567
T 3227	3.25	2.95	34.56	.82	.02	500	.171	.09	.176

Test Holes
9 - 12
entered on log's

ENTERED JAN 9 1988

87-D1

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: JUNE 3 1987

DATE REPORT MAILED: June 10/87

GEOCHEMICAL ICP ANALYSIS

.500 GRAM SAMPLE IS DIGESTED WITH 3ML 3-1-2 HCL-HNO3-H2O AT 95 DEG.C FOR ONE HOUR AND IS DILUTED TO 10 ML WITH WATER. THIS LEACH IS PARTIAL FOR MN FE CA P LA CR MG BA TI B W AND LIMITED FOR NA AND K. AU DETECTION LIMIT BY ICP IS 3 PPM.
- SAMPLE TYPE: Core AU* ANALYSIS BY AA FROM 10 GRAM SAMPLE.

ASSAYER: ..... DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES INC PROJECT-SK File # 87-1569

SAMPLE#	AG PPM	AU* PPB
9602	18.3	560
9603	.6	1
9604	.7	5
9605	3.1	36
9606	1.3	1
9607	1.4	8
9608	5.6	47
9609	2.0	7
9610	.5	5
9611	.8	7
9616	.5	1
9620	1.7	33
STD C/AU-R	7.0	495

86-D1

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE: 251-1011

DATE RECEIVED JUN 03 1987

DATE REPORTS MAILED June 9/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE & ROCK

ASSAYER D Toye DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES INC PROJECT SK FILE# 87-1570 PAGE# 1

SAMPLE	Ag oz/t	Au oz/t	
9601	1.69	.008	1.5'
9612	2.18	.098	0.7
9613	.13	.006	1.5'
9614	1.05	.062	1.1
9615	1.73	.037	4.6'
9617	1.36	.068	3.6 } .31 opt. Au over 4.5'
9618	3.96	1.180	1.0 }
9619	.16	.002	2m'
~~6074~~ Rock Phaleuto Vein	17.63	.526	

core length
? true length

87-92

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: JUNE 10 1987
DATE REPORT MAILED: June 19/87.

GEOCHEMICAL ICP ANALYSIS

.500 GRAM SAMPLE IS DIGESTED WITH 3ML 3-1-2 HCL-HNO3-H2O AT 95 DEG.C FOR ONE HOUR AND IS DILUTED TO 10 ML WITH WATER. THIS LEACH IS PARTIAL FOR MN FE CA P LA CR MG BA TI B W AND LIMITED FOR NA AND K. AU DETECTION LIMIT BY ICP IS 3 PPM.
- SAMPLE TYPE: Core AU* ANALYSIS BY AA FROM 10 GRAM SAMPLE.

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT - SKUKUM File # 87-1696 Page 1

SAMPLE#	AG PPM	AU* PPB			
87-91 9622	.8	10	.02	.001	
9623	3.0	785	.09	.023	
9624	1.0	14	.03	.001	
9625	16.2	61	.47	.002	
9626	10.9	42	.32	.001	
9627	8.3	32	.24	.001	
9628	8.4	295	.21	.008	
9629	5.9	285	.13	.008	
9630	15.4	1060	.45	.031	
9631	10.8	295	.31	.009	
9638	10.7	545	.31	.016	
9639	41.3	1360	1.26	.04	
9640	4.2	33	.12	.001	
9641	1.2	21	.06	.001	
9642	3.1	15	.09	.000	3.4
MLBX 9643	101.9	5660	2.97	.17	3.7'
9644	59.6	2100	1.74	.06	3.7'
9645	12.0	52	.35	.002	2.9'
9646	2.9	31	.08	.001	
9647	2.2	42	.06	.001	
9648	.5	7	.01	.001	
9649	.7	3	.02	.001	
9650	2.6	10	.05	.001	
9651	1.1	4	.03	.001	
9652	.9	7	.03	.001	
9653	1.1	3	.03	.001	
9654	1.3	1	.04	.000	
9655	1.1	1	.03	.000	
9656	3.0	37	.09	.001	
9657	.4	7	.01	.001	
9658	.8	8	.02	.001	
9659	.7	1	.02	.000	
RUN DOR 9660	63.4	2020	1.85	.059	
9661	2.6	14	.08	.000	
9662	19.9	595	.58	.018	
9663	12.6	295	.37	.009	
STD C/AU-R	6.7	500			

87-D2

OMNI RESOURCES PROJECT - SKUKUM FILE # 87-1696

SAMPLE#	AG PPM	AU* PPB	Ag	Au
9664	227.1	2890	6.67	.084
9665	13.5	310	.39	.009
9666	40.1	695	1.17	.020
9667	298.4	2060	8.70	.060
9668	2.7	73	.08	.002
9669	12.1	495	.35	.014
9670	88.1	3250	2.57	.095
9671	26.6	660	.78	.019
9672	1.7	140	.05	.004
6075	3.6	102	.10	.003

- ASSAY REQUIRED FOR CORRECT RESULT - for Ag > 35 ppm

D2
Bn

87-D2 SILVER ASSAY

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: JUN 10 1987
DATE REPORT MAILED: June 19/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Core Ag** by Fire Assay

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT - SKUKUM File # 87-1696A Page 2

SAMPLE#	AG** OZ/T	
6076	.34	WIDTH
9632	.98	1.0
9633	2.22	4.2
9634	10.13	2.2
9635	10.69	1.7
9636	55.53	1.7
9637	7.86	4.8

87-D2 GOLD ASSAYS

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604) 253-3158 COMPUTER LINE: 251-1011

DATE RECEIVED JUNE 10 1987

DATE REPORTS MAILED June 19/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.
AU BY FIRE ASSAY
ND=None Detected

ASSAYER _____ DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SKUKUM FILE# 87-1696A

SAMPLE	Sample wt. gm	Au-100 oz/t	Native Au mg	Average oz/t	
6076	300	.014	ND	.014	WIDTH
9632	300	.015	ND	.015	1.0
9633	270	.099	ND	.099	4.2
9634	300	.292	ND	.292	2.2
9635	270	.081	ND	.081	1.7
9636	350	.269	ND	.269	1.7
9637	300	.178	ND	.178	4.8

87-D3

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: JUNE 18 1987
DATE REPORT MAILED: June 22/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT - SKUKUM CREEK File # 87-1842

SAMPLE#	AG** OZ/T	AU** OZ/T	WIDTH
9673	.02	.001	5.7'
9674	.01	.001	4.8',
9675	.05	.001	4.6',
9676	.22	.001	4.7'
9677	.10	.001	4.6
9678	.28	.005	3.1
9679	.27	.012	4.6
9680	.41	.006	4.8
9681	.22	.005	5.2
9682	.56	.012	4.6
9683	22.47	.239	1.8
9684	2.79	.045	3.0
9685	1.91	.047	4.3
9686	1.55	.032	5.1
9687	4.59	.048	4.6
9688	1.54	.035	5.1
9689	3.11	.050	3.4
9690	.47	.015	1.5
9691	.01	.001	4.6
9692	.01	.001	5.2
9693	.01	.001	4.3
9694	.09	.001	3.9
9695	.44	.005	4.9

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: JUNE 26 1987

DATE REPORT MAILED: June 30/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT - SKUKUM CREEK File # 87-2024

87-41

SAMPLE#	AG** OZ/T	AU** OZ/T
9716	.01	.001
9717	.02	.001
9718	.01	.001
9719	.01	.001
9720	.01	.001
9721	.03	.004
9722	.02	.001
9723	.01	.001
9724	.02	.001
9725	.02	.001
9726	.03	.001

ACME ANALYTICAL LABORATORIES
352 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: JULY 8 1987

DATE REPORT MAILED: July 10/87.
Received July 14/87

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-2280

SAMPLE#	AG** OZ/T	AU** OZ/T
6151	.12	.001
6152	.09	.001
6153	.28	.009
6154	.67	.031
6155	.04	.001
6156	1.66	.182
6157	.16	.003
6158	1.43	.037
6159	.42	.056
end R-4 — 6160	.01	.001
9784	.11	.001
UG8 9785	.08	.003
9786	.10	.001
9787	.01	.001
Start R-4 — 9788	.32	.005
9789	.18	.007
9790	.37	.021
9791	.69	.026
9792	.53	.031
9793	.36	.012
9794	.54	.013
9795	1.21	.022
9796	35.52	.284
9797	.68	.085
9798	.68	.019
9799	.08	.003
9800	.01	.001

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

K-2

DATE RECEIVED: JULY 22 1987

DATE REPORT MAILED: July 29/87.

Received July 31st

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK-CR File # 87-2617

SAMPLE#	AG** OZ/T	AU** OZ/T
T-6263	.01	.001
K-2 T-6264	.02	.001
T-6265	.04	.001
T-6266	.02	.001
T-6267	.01	.001
T-6268	.02	.001
T-6269	.04	.001
T-6270	.01	.001
T-6271	.02	.001
T-6289	.16	.002
T-6290	.48	.044
T-6291	.44	.017
T-6292	.11	.016
T-6293	.18	.011
T-6294	9.19	.342
UG-4		
T-6295	.31	.007
T-6296	.21	.002
T-6297	.12	.001
T-6298	.16	.001
T-6299	.60	.012
T-6300	.05	.001
T-6301	.01	.001
T-6302	.01	.001
T-6303	.15	.005
T-6304	.04	.001
61A		
T-6305	.03	.002
T-6306	.01	.001

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
V6A 1R6 (604)253-3158 COMPUTER LINE:251-1011

DATE RECEIVED JULY 25 1987

DATE REPORTS MAILED Aug 3/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.

ASSAYER D. Toye DEAN TOYE . CERTIFIED B.C. ASSAYER

OMNI RESOURCES FILE# 87-2721

UG 15

SAMPLE	Ag** oz/t	Au** oz/t
T 6307	.01	.001
T 6308	.02	.002
T 6309	7.35	.055
T 6310	53.70	.480
T 6311	40.10	.145
T 6312	3.66	.132
T 6313	.94	.038
T 6314	.47	.025
T 6315	.38	.055
T 6316	.55	.015
T 6317	.42	.058
T 6318	1.34	.057
T 6319	4.43	.266
T 6320	.10	.008
T 6321	.04	.002
T 6322	.01	.001
T 6323	.02	.005
T 6324	.01	.004
T 6325	.01	.002
T 6326	.01	.001
T 6327	.01	.002
T 6328	.01	.001
T 6329	.04	.001

87-G1A

SAMPLE#	AG** OZ/T	AU** OZ/T
T 6389	.04	.001
T 6390	.05	.001
T 6391	.04	.001
T 6392	.01	.001
T 6393	.03	.001
T 6394	.01	.001
T 6395	.01	.001
T 6396	.03	.001

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE: 251-1011

DATE RECEIVED AUG 1 1987

DATE REPORTS MAILED Aug 12/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.
AG** & AU** BY FIRE ASSAY

ASSAYER D. Toye DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SKUKUM CREEK FILE# 87-2908 PAGE# 1

SAMPLE	Ag** oz/t	Au** oz/t	
T 6397	.27	.013	
T 6398	1.00	.078	U/G 18
T 6399	.09	.001	
T 6400	.04	.001	
T 6401	.13	.001	
T 6402	.13	.002	
T 6403	.78	.009	
T 6404	.27	.001	
T 6405	1.63	.019	
T 6406	25.85	.265	4.2'
T 6407	1.93	.052	
T 6408	.78	.011	
T 6409	7.97	.093	
T 6410	4.93	.310	
T 6411	.16	.006	
T 6412	2.17	.250	2.2' Sheared Gt
T 6413	.11	.007	
T 6414	.01	.002	

R7 / UG19 / UG20

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE: 251-1011

DATE RECEIVED AUG 8 1987

DATE REPORTS MAILED Aug 17/87

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.
AG** & AU** BY FIRE ASSAY

ASSAYER D. Toye DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SK. FILE# 87-3095

SAMPLE	Ag** oz/t	Au** oz/t	
T 6415	.68	.013	
T 6416	.01	.001	
T 6417	.01	.001	
T 6418	.08	.006	
T 6419	1.12	.075	
T 6420	.59	.008	
T 6421	.63	.004	R7
T 6422	1.45	.005	
T 6423	.66	.031	
T 6424	.12	.029	
T 6425	1.55	.061	
T 6426	.10	.002	
T 6427	.09	.007	
T 6428	1.17	.060	
T 6429	.73	.037	
T 6430	.30	.003	
T 6431	.58	.009	
T 6432	.33	.341	
T 6433	.14	.004	
T 6434	.21	.006	
T 6435	.58	.026	
T 6436	19.20	1.850	UG19
T 6437	4.28	.172	
T 6438	.45	.035	
T 6439	19.45	.459	
T 6440	3.03	.217	
T 6441	1.24	.049	
T 6442	.92	.071	
T 6443	.73	.003	
T 6444	.09	.001	
T 6445	1.11	.016	
T 6446	.56	.050	
T 6447	2.57	.252	
T 6448	3.68	.199	
T 6449	.25	.035	
T 6450	.11	.014	

UG 21 + R8

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE: 251-1011

DATE RECEIVED AUG 10 1987

DATE REPORTS MAILED Aug 15/87
Received Aug 18

ASSAY CERTIFICATE

SAMPLE TYPE : CORE - CRUSHED AND PULVERIZED TO -100 MESH.
AG** & AU** BY FIRE ASSAY

ASSAYER _____ DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SK FILE# 87-3142 PAGE# 1

SAMPLE	Ag** oz/t	Au** oz/t	
T-6469	.05	.001	
T-6470	.14	.001	
T-6471	.04	.001	
T-6472	.07	.001	
T-6473	.11	.001	
T-6474	.37	.036	
T-6475	.26	.009	
T-6476	.06	.001	
T-6477	.01	.001	
T-6478	.11	.001	
T-6479	.05	.001	
T-6480	.04	.001	
T-6481	.01	.001	
T-6482	.20	.001	
T-6483	.04	.001	
T-6484	.02	.001	UG-21
T-6485	.13	.001	
T-6486	.01	.001	R-8
T-6487	.02	.001	
T-6488	1.64	.001	
T-6489	.31	.001	
T-6490	.13	.001	
T-6491	11.75	.213	
T-6492	7.09	.179	
T-6493	3.12	.131	
T-6494	.05	.002	
T-6495	1.56	.035	
T-6496	10.04	.136	
T-6497	1.16	.015	
T-6498	11.86	.151	
T-6499	.33	.008	
T-6500	1.31	.123	
T-6501	.17	.026	
T-6502	.36	.050	
T-6503	.11	.026	
T-6504	.02	.001	
T-6505	.11	.004	

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: AUG 14 1987

DATE REPORT MAILED: Aug 27/87

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye.. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SKUKUM CREEK File # 87-3277

Received 9/2/87
87-R9

Posted to log

SAMPLE#	AG** OZ/T	AU** OZ/T	
T 6570	.02	.002	
T 6571	.02	.001	
T 6572	.06	.001	
T 6573	2.54	.063	1.5'
T 6574	13.22	.235	1.3'
T 6575	.01	.002	
T 6576	.03	.001	
T 6577	.01	.001	
T 6578	.05	.001	
T 6579	.57	.032	4.2'
T 6580	10.51	.210	2.1'
T 6581	10.28	.160	1.1'
T 6582	.07	.004	4.7'
T 6583	.04	.001	5.0'
T 6584	.58	.018	5.1'
T 6585	9.38	.138	3.3'
T 6586	10.46	.260	2.0'
T 6587	.25	.016	4.2'
T 6588	.20	.003	5.8'
T 6589	.44	.042	1.6'
T 6590	.21	.008	4.7'

R9 - 4G30

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: AUG 31 1987
DATE REPORT MAILED: Sept 7/87....

ASSAY CERTIFICATE

- SAMPLE TYPE: Core AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye.. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT-SK File # 87-3787

SAMPLE#	AG** OZ/T	AU** OZ/T	
X-3063	1.91	.115	R8
T-6646	.27	.001	
T-6647	.03	.001	R9
T-6648	.01	.001	
T-6649	.03	.001	
T-6650	.03	.001	
T-6651	.01	.001	
T-6652	.04	.001	
T-6653	.15	.001	
T-6654	.01	.001	
T-6655	.01	.001	
T-6656	.02	.001	
T-6657	.02	.001	
T-6658	.03	.001	
T-6659	.01	.001	
T-6660	.03	.001	
T-6661	.08	.010	
T-6662	.44	.007	
T-6663	.14	.011	
T-6664	.81	.007	
T-6665	.25	.002	
T-6666	.46	.006	
T-6667	3.58	.024	
T-6668	9.86	.294	
T-6669	.05	.001	
T-6670	.26	.030	
T-6671	.32	.001	
T-6672	.01	.001	
T-6673	.05	.001	
T-6674	.02	.001	
T-6675	.03	.001	

Received 9/11/87
Posted R9 log 9/11/87 MT

46 - 50

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE:251-1011

DATE RECEIVED AUGUST 30 1987

DATE REPORTS MAILED Sept 9/87

ASSAY CERTIFICATE

Received Sept 14/87

87-R9

SAMPLE TYPE : REJECT
AU BY FIRE ASSAY

ASSAYER ____D. Toye____ DEAN TOYE . CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT SKUKUM CREEK FILE# 87-3277 R PAGE# 1

SAMPLE	Sample wt. gm	Au-100 oz/t	Native Au mg	Average oz/t	LAST ASSAY
T 6574	270	.254	ND	.254	(0.235)
T 6580	290	.193	.02	.195	(0.210)
T 6584	140	.021	ND	.021	(0.018)
T 6585	310	.172	ND	.172	(0.138)

POSTED Sept 15

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE(604)253-3158 FAX(604)253-1716

DATE RECEIVED: SEPT 28 1987
DATE REPORT MAILED: Oct 27/87

ASSAY CERTIFICATE

- SAMPLE TYPE: REJECT Au by Fire Assay.

ASSAYER: DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES File # 87-4809 R Page 1

1987 Native Au Preps

Original Fire Assay

SAMPLE#	SAMPLE wt. gm	AU-100 oz/t	NATIVE Au mg	AVG. oz/t	
9617	340	.056	ND	.056	.068
9618	260	1.642	1.03	1.757	1.180
9643	400	.157	.09	.164	0.165
9644	420	.046	ND	.046	0.061
9683	270	.258	.01	.259	0.239
9684	280	.051	ND	.051	.045
9685	230	.040	ND	.040	0.047
9686	230	.031	ND	.031	0.032
9687	250	.046	ND	.046	0.048
9688	300	.040	.01	.041	0.035
9689	290	.041	ND	.041	0.050
9697	250	.361	.88	.464	0.316
9698	210	.027	.03	.031	0.022
9699	290	.058	ND	.058	0.060
9700	240	.179	.04	.184	0.177
9701	280	.078	.01	.079	0.052
9706	280	.294	.03	.297	0.300
9708	290	.010	ND	.010	0.009
9738	340	.177	.04	.181	0.138
9739	200	.073	ND	.073	0.070
9740	320	.197	ND	.197	0.182
9741	270	.078	ND	.078	0.075
9742	320	.019	ND	.019	0.014
9743	290	.208	.02	.210	0.148
9746	270	.009	ND	.009	0.021
9747	370	.172	.05	.176	0.180
9757	170	.125	ND	.125	0.093
9762	250	.021	ND	.021	0.023
9763	310	.053	ND	.053	0.054
9767	270	.127	.03	.130	0.109
6156	370	.126	.03	.128	0.182
6158	340	.042	ND	.042	0.037
6159	330	.024	.12	.035	0.056
9795	350	.018	.01	.019	0.022
9796	260	.288	.34	.327	0.284
9797	270	.028	ND	.028	0.035

Please send to Brenda

Entered on log ?

* Duplicate set 10/11/87 TOT

SAMPLE#	SAMPLE wt. gm	AU-100 oz/t	NATIVE Au mg	AVG. oz/t	
9774	270	.085	ND	.085	0.077
9780	370	.642	ND	.642	0.690
9781	290	.065	ND	.065	0.039
T 6253	400	.483	ND	.483	0.232
T 6254	400	.015	ND	.015	0.012
T 6255	260	.306	ND	.306	0.272
T 6256	170	.011	ND	.011	0.022
T 6257	400	.130	ND	.130	0.112
T 6286	250	.140	.08	.149	0.229
T 6293	250	.006	ND	.006	0.011
T 6294	230	.325	ND	.325	0.342
T 6295	250	.015	.02	.017	0.007
T 6309	300	.058	ND	.058	0.055
T 6310	250	.450	.04	.455	0.480
T 6311	150	.138	ND	.138	0.138
T 6312	250	.166	ND	.166	0.166
T 6317	300	.020	.02	.022	0.058
T 6318	320	.039	ND	.039	0.057
T 6319	300	.148	.14	.161	0.256
T 6344	260	.012	ND	.012	0.023
T 6345	300	.183	ND	.183	0.182
T 6346	290	.055	ND	.055	0.075
T 6364	400	.389	1.84	.523	0.926
T 6365	300	.102	ND	.102	.096
T 6366	350	.586	.04	.590	.754
T 6367	300	.110	ND	.110	.184
T 6368	420	2.115	.73	2.166	1.924
T 6369	420	1.506	.27	1.525	1.580
T 6370	260	.167	ND	.167	.154
T 6371	350	.281	.02	.282	.297
T 6372	300	.201	.02	.203	.147
T 6381	250	.220	.08	.229	.093
T 6382	300	.027	ND	.027	.023
T 6383	370	.354	ND	.354	.423
T 6384	310	.022	ND	.022	.030
T 6385	300	.592	.03	.595	0.519
T 6386	300	.021	ND	.021	0.021

OMNI RESOURCES FILE # 87-4809 R

SAMPLE#	SAMPLE wt. gm	AU-100 oz/t	NATIVE Au mg	AVG. oz/t	Original Fire Assay
T 6398	300	.071	ND	.071	0.078
T 6405	350	.013	ND	.013	0.019
T 6406	400	.236	.03	.238	0.265
T 6407	340	.051	ND	.051	0.052
T 6408	360	.010	ND	.010	0.011
T 6409	350	.106	ND	.106	0.093
T 6410	250	.259	ND	.259	0.310
T 6411	320	.010	ND	.010	0.006
T 6412	260	.197	ND	.197	0.250
T 6435	330	.015	ND	.015	0.026
T 6436	350	1.756	.43	1.792	1.850
T 6437	370	.291	ND	.291	0.172
T 6438	195	.041	ND	.041	0.035
T 6439	320	.435	ND	.435	0.459
T 6440	250	.251	ND	.251	0.217
T 6441	270	.060	ND	.060	0.049
T 6442	240	.073	ND	.073	0.071
T 6446	310	.031	.02	.033	0.050
T 6447	260	.570	1.01	.683	0.252
T 6448	310	.134	ND	.134	.199
T 6449	300	.039	ND	.039	.035
T 6491	280	.204	ND	.204	0.213
T 6492	350	.211	.04	.214	0.179
T 6493	300	.117	.05	.122	0.131
T 6494	290	.001	ND	.001	.002
T 6495	270	.084	ND	.084	0.035
T 6496	320	.143	ND	.143	0.135
T 6497	250	.028	ND	.028	0.015
T 6498	380	.117	ND	.117	0.151
T 6499	310	.008	.02	.010	.008
T 6500	280	.072	ND	.072	.123

SAMPLE#	SAMPLE wt. gm	AU-100 oz/t	NATIVE Au mg	AVG. oz/t	
T 6557	350	.083	.07	.089	.182
T 6558	400	.122	.03	.124	.102
T 6559	340	.021	ND	.021	.015
T 6560	340	.197	ND	.197	.244
T 6561	280	.614	.10	.624	.975
T 6562	240	2.310	2.95	2.668	4.320
T 6563	300	.962	.35	.996	1.050
T 6564	290	.710	.16	.726	1.035
T 6573	300	.071	.03	.074	0.063
T 6579	300	.035	ND	.035	0.032
T 6581	300	.115	.02	.117	0.160
T 6586	370	.238	ND	.238	0.260
T 6635	290	.050	ND	.050	0.024
~~T 6636~~	~~290~~	~~.041~~	ND	~~.041~~	0.106
X 3063	270	.158	~~.29~~	~~.189~~	
T 6667	260	.017	ND	.017	0.024
T 6668	300	.334	.08	.342	0.294

where from

X-Cut #1 MUCK PILE SAMPLES

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: MAY 25 1987
DATE REPORT MAILED: May 29/87

ASSAY CERTIFICATE

- SAMPLE TYPE: Rock Chips AU** AND AG** BY FIRE ASSAY.

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT - OMNI SKUKUM File # 87-1401 Page 1

	SAMPLE#	AG** OZ/T	AU** OZ/T
Burnt rhy	6053	.02	.003
Alt GOR	6054	.12	.001
Alt Soft ~~Quartz~~ RHY	6057	1.34	.015
RHY ~~Eudesma~~ Bx	6058	.78	.012
Alt GOR	6059	.25	.026
ML BX	6061	1.29	.031

1ST X-cut muck samples

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: MAY 25 1987

DATE REPORT MAILED: May 29/87

GEOCHEMICAL/ASSAY CERTIFICATE

.500 GRAM SAMPLE IS DIGESTED WITH 3ML 3-1-2 HCL-HNO3-H2O AT 95 DEG.C FOR ONE HOUR AND IS DILUTED TO 10 ML WITH WATER. THIS LEACH IS PARTIAL FOR MN FE CA P LA CR MG BA TI B W AND LIMITED FOR NA AND K. AU DETECTION LIMIT BY ICP IS 3 PPM.
- SAMPLE TYPE: Rock Chips AU** BY FIRE ASSAY

ASSAYER: D. Toye. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT - OMNI SKUKUM File # 87-1401 Page 2

	SAMPLE#	PB PPM	ZN PPM	AG PPM	AS PPM	SB PPM	AU** OZ/T
Soft alt'd vny	6052	251	508	7.2	354	4	.003

#1 X-cut muck pile

X-cut #1 muck pile samples

ACME ANALYTICAL LABORATORIES LTD.
852 E. HASTINGS, VANCOUVER B.C.
PH: (604)253-3158 COMPUTER LINE: 251-1011

DATE RECEIVED MAY 25 1987

DATE REPORTS MAILED May 29/87

ASSAY CERTIFICATE

SAMPLE TYPE : ROCK - CRUSHED AND PULVERIZED TO -100 MESH.
AU BY FIRE ASSAY
ND = NONE DETECTED

ASSAYER D Toye DEAN TOYE , CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT OMNI SKUKUM FILE# 87-1401 PAGE# 3A

SAMPLE		Sample wt. gm	Au-100 oz/t	Native Au mg	Average oz/t
6051	MINERALIZED QTZ RHY	500	.038	ND	.038
6055	QZ SX BX	510	.299	ND	.299
6056	GALENA	500	.144	ND	.144
6060	QZ SX BX	520	.439	.48	.466

#1 X-cut 1 of 2 pile muck spls

SAMPLE#	PB PPM	ZN PPM	AG PPM	AS PPM	SB PPM
6051	2412	2913	48.3	2413	37
6055	12761	11637	309.5	42191	457
6056	15086	45346	255.1	18946	761
6060	16417	24444	289.3	49071	860

ASSAY REQUIRED FOR CORRECT RESULT -

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: JUNE 10 1987
DATE REPORT MAILED: June 19/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Rock Chips Ag** Au** by Fire Assay.

ASSAYER: D. Toye DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT - SKUKUM File # 87-1696A Page 1

		SAMPLE#	AG ** OZ/T	AU** OZ/T
		3062	8.05	.115
SECOND X-CUT	MUCK #1	6077	2.27	.036
"	MUCK #2	6078	7.71	.149
"	MUCK #3	6079	8.47	.172
"	MUCK #4	6080	13.41	.205
FIRST X-CUT	MUCK #1	6081	2.19	.041
" "	MUCK #2	6082	4.32	.092
	5'	6083	4.46	.144
	5'	6084	3.25	.267
	5'	6085	9.14	.536
	5'	6086	6.37	.103
	7'	6087	22.54	.214
	5'	6088	3.59	.032
	5'	6089	28.54	.228
	3'	6090	10.77	.096
	5'	6091	37.00	.169
	5'	6092	3.14	.037
	4'	6093	2.12	.025
SECOND X-CUT FOOTWALL WASTE	5'	6094	.69	.009
	5'	6095	1.53	.004

Bondar-Clegg & Company Ltd.

136 Industrial Road
Whitehorse, Yukon Territory Y1A 2V1
Phone: (403) 667-6523
Telex: 036-8-460

BONDAR-CLEGG

Geochemical Lab Report

REPORT: 427-3566 (COMPLETE)

REFERENCE INFO: X-cut #2 PANELS

CLIENT: OMNI RESOURCES
PROJECT: NONE GIVEN

SUBMITTED BY: RUSS DAVIS
DATE PRINTED: 28-AUG-87

ORDER		ELEMENT	NUMBER OF ANALYSES	LOWER DETECTION LIMIT	EXTRACTION	METHOD
1	AU	GOLD - FIRE ASSAY	13	0.001 OPT		
2	AG	SILVER	13	0.01 OPT		

SAMPLE TYPES		NUMBER
R	ROCK OR BED ROCK	13

SIZE FRACTIONS		NUMBER
2	-150	13

SAMPLE PREPARATIONS	NUMBER
ASSAY PREP	13
OVERWEIGHT SAMPLE/LB	2640
PULVERIZING	26

REPORT COPIES TO: OMNI RESOURCES

INVOICE TO: OMNI RESOURCES

Bondar-Clegg & Company Ltd.

136 Industrial Road
Whitehorse, Yukon Territory Y1A 2V1
Phone: (403) 667-6523
Telex: 036-8-460

BONDAR-CLEGG

Geochemical Lab Report

REPORT: 427-3566

PROJECT: NONE GIVEN PAGE 1

SAMPLE NUMBER	ELEMENT UNITS	AU OPT	AG OPT
R2 I		0.077	1.37
R2 II		0.164	3.19
R2 III		0.202	4.43
R2 IV		0.114	6.14
R2 V		0.115	11.11
R2 VI		0.081	9.32
R2 VII		0.143	24.82
R2 VIII		0.145	16.38
R2 IX		0.074	7.41
R2 X		0.046	4.63
R2 XI		0.022	0.65
R2 XII		0.014	0.57
R2 XIII		0.006	0.07

X-cut #1 Channels.

ACME ANALYTICAL LABORATORIES
852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6
PHONE 253-3158 DATA LINE 251-1011

DATE RECEIVED: MAY 29 1987
DATE REPORT MAILED: June 4/87.

ASSAY CERTIFICATE

- SAMPLE TYPE: Rock Chips

ASSAYER: D. Toye.. DEAN TOYE, CERTIFIED B.C. ASSAYER

OMNI RESOURCES PROJECT - SKUKUM CREEK File # 87-1489

SAMPLE#	PB %	ZN %	AG OZ/T	AU OZ/T	AS %	SB %
6062	.10	.19	.97	.026	.22	.01
6063	.47	1.55	2.64	.106	1.72	.01
6064	.16	1.55	1.45	.033	.45	.01
6065	.08	.34	.87	.016	.15	.01
6066	.10	.27	.73	.013	.17	.01
6067	.06	.18	.37	.012	.09	.01
6068	.63	.64	6.51	.312	.04	.03
6069	.65	.47	3.68	.108	1.10	.01
6070	.01	.09	.11	.001	.02	.01
6071	.11	.24	.77	.028	.19	.01
6072	2.49	1.41	39.30	.146	1.54	.10
6073	.73	.56	3.09	.065	1.26	.01

BONDAR-CLEGG & COMPANY LTD.

136B INDUSTRIAL RD, WHITEHORSE, YUKON Y1A 2V1 PHONE: (403) 667-6523

Certificate of Analysis

TO Omni Resources

REPORT NO. 47-4346

DATE July 10, 1987 Received July 15

grab samples from Kuhn zone in main drift

I hereby certify that the following are the results of analyses made by us upon the herein described rock samples

MARKED	oz/ton Au	oz/ton Ag
A	0.79	9.33
B	0.39	0.64

Note*: Somewhat erratic silver values were noted on repeat analyses of A.

BONDAR-CLEGG & COMPANY LTD.

John Rose