MAP No. 115 H 4

ASSESSMENT REPORT [x]
PROSPECTUS
CONFIDENTIAL
OPEN FILE [x]

DOCUMENT NO.: 092581
MINING DISTRICT: Whitehorse
TYPE OF WORK: ~~Geochemical~~

REPORT FILED UNDER: J.P. Ross

DATE PERFORMED: July 28-Aug 14, 1988 DATE FILED: 27 October, 1988

LOCATION		AREA:	
LAT.	61°13'N	Ruby Range	
LONG.	137°40'W	VALUE $	1100

CLAIM NAME & NO. ARC 10-20 YB07835-07845

WORK DONE BY: J.P. Ross

WORK DONE FOR: J.P. Ross

DATE TO GOOD STANDING	

REMARKS:

30. SPRUCE

21 geochemical samples were taken from fault zones in Ruby Range granodiorite.

092581

Indian and Northern Affairs Canada | Affaires indiennes et du Nord Canada

M.R. file no.	
R.M.M.R. file no.	
Date forwarded	28 October 1988

TRANSMITTAL FORM

From ▶ Mining Recorder at: Whitehorse

To ▶ Regional Manager, Mineral Rights at Whitehorse, Y.T.

For action are:

- ☐ NEW APPLICATION FOR PLACER LEASE TO PROSPECT — Name
- ☐ RENEWAL APPLICATION PLACER LEASE TO PROSPECT — Name — Lease no.
- ☐ AFFIDAVIT OF EXPENDITURE ON PLACER LEASE — Name — Lease no.
- ☐ SECURITY DEPOSIT
- ☐ FINANCIAL ABILITY
- ☐ ASSIGNMENT OF PLACER LEASE NO. — From — To
- ☐ GROUPING APPLICATION UNDER SEC. 52(2) PLACER MINING ACT. — Owner
- ☐ DIAMOND DRILL LOGS — Claims — Claim sheet no.
- ☑ QUARTZ ASSESSMENT REPORT — Claims: ARC 10-20 YB07835-YB07845 — Claim sheet no.

Type of report: Grock Report

Submitted by: T. P. Ross

Cls. work performed on:

$ req. for ren. application: 1100

Signature

092581

REPLY ACTION

Date returned: 21 Nov 88

OFFICE OF THE REGIONAL MANAGER MINERAL RIGHTS OCT 27 1988 WHITEHORSE YUKON TERRITORY

Approved for amount required

Signature

802-6027-26 (6-86)

092581

GEOCHEMICAL REPORT

ARC (10-20) CLAIMS
(YB07835 - YB07845)

CLAIM SHEET 115 A/4

LAT. 61°13 LONG. 137°40'

REPORT by

J. PETER ROSS
BOX 4842
WHITEHORSE
YUKON TERRITORY
CANADA Y1A 4N8

092581

WORK DONE: JULY; 28(½), 29(½)
AUG; 1, 2(½), 3, 4, 5, 7, 8, 9, 12, 13, 14(½)
1988

This report has been examined by the Geological Evaluation Unit under Section 53 (4) Yukon Quartz Mining Act and is allowed as representation work in the amount of $ 1100.00 .

P. J. Bremner

for Regional Manager, Exploration and Geological Services for Commissioner of Yukon Territory.

ARC PROPERTY

INTRODUCTION

STAKED IN 1987 BY J. PETER ROSS ON BASIS OF A GEOCHEM SURVEY RELEASED BY GOVT. IN AUGUST 1986.

PROPERTY, LOCATION, ACCESS

THE 20 ARC CLAIMS ARE BROKEN INTO 2 GROUPS. RECORDED BY J. PETER ROSS AND REGISTERED IN THE WHITEHORSE MINING DISTRICT

CLAIM NAME	RECORD NUMBERS	EXPIRY DATE
ARC (10-20)	YB07835 - YB07845	SEPT. 3, 1988,

LOCATION	CLAIM MAP
LAT. 61°13' LONG 137°40'	115 H 4

ACCESS IN 1988 WAS BY HELICOPTER AND 42 MILES NORTH OF HAINES JUNCTION

PREVIOUS WORK

NO HISTORY OF FORMER WORK OR OLD POSTS WERE FOUND.

PHYSIOLOGY AND GLACIATION

THE AREA HAS BEEN RECENTLY GLACIATED. MANY BEDROCK EXPOSURES ARE PRESENT. EVEN AT LOW ELEVATION. TREELINE IS PLUS OR MINUS 4500' DEPENDING ON NORTH OR SOUTH EXPOSURES.

GEOLOGY AND MINERALIZATION

THE PROPERTY LIES WITHIN THE COAST PLUTONIC COMPLEX. THE ROCK TYPE (PAPER 73-41) IS RUBY RANGE GRANODIORITE OF THE MESOZOIC AGE. MANY LARGE AND SMALL FAULTS ARE PRESENT. MANY MINERALIZED FLOAT WERE FOUND.

GEOCHEMISTRY

SOIL SAMPLES WERE TAKEN ON FAULTS AND IN FLOAT AREAS. MANY WERE ANOMOLOUS FOR GOLD, ARSENIC, AND SILVER. ROCK SAMPLES WERE ALSO.

DISCUSSION

THE CLAIMS SHOULD BE KEPT.

TECHNIQUES OF GEOCHEMICAL ANALYSIS

SILTS SCREENED TO -80 MESH. GOLD SAMPLES WERE 30 GMS. AND DONE BY FIRE ASSAY (5 PPB DET). 31 ELEMENTS DONE BY (HNO_3-HCl HOT EXTRACION AND PLASMA EMISSION SPEC). Hg DONE BY FLAMELESS AA.

QUALIFICATIONS

I, J. PETER ROSS, DECLARE

1. I GRADUATED McGILL UNIV. 1970 B Sc (GENERAL)
2. I HAVE TAKEN 3 PROSPECTING ~~EX~~ COURSES
   - 1974 BC-YUKON CHAMBER MINES
   - 1978 UKHM STAFF COURSE
   - 1987 YUKON CHAMBER MINES (ADVANCED)
3. I HAVE PRACTICAL EXPERIENCE AS A PROSPECTOR

J. PETER ROSS B.Sc.

STATEMENT OF EXPENDITURES (ARC 10-20)

GEOCHEMICAL SAMPLES		~~1~~
LABOUR JUNE ~~27~~	11 X 50	550
JULY 28(½), 29(½)		
AUG 1, 2(½), 3, 4, 5, 7, 8, 9, 12, 13, 14(½)		
PREPARATION OF REPORT		110
CAMP + MISC	11 X 35	385
TRANSPORT HI MILEAGE	$60 X ½	30
HELICOPTER	$854 X ½	427
		1502



ALASKA
YUKON
Elsa
Keno City
Minto Bridge
Mayo
Gordon Landing
Sulphur
Dominion
TINTINA
THE SILVER TRAIL
Moose Creek Lodge
Stewart
Thistle Creek
Kirkman Creek
Coffe Creek
Isaac Creek
Donjek
Canada Customs - Beaver Creek
Beaver Creek
Pelly Crossing
Fort Selkirk
Minto
Midway Lodge
Yukon Crossing
TRENCH
CLARKE HILLS
RUSSELL RANGE
McARTHUR GAME SANCTUARY
WILKINSON
ANVIL RANGE
GLENLYON RANGE
DAWSON RANGE
TATCHUN HILLS
Carmacks
Little Salmon
Faro
Ross River
Big Salmon
PELLY
BIG SALMON RANGE
Hootalinqua
Lower Laberge
Braeburn Lodge
MINERS RANGE
White River Lodge
Bear Flats Lodge at Koidern
Koidern River Fishing Lodge
Pine Valley Motel
Kluane Wilderness Village
NISLING RANGE
KLUANE GAME SANCTUARY
Aishihik
Burwash Landing
Destruction Bay
Bayshore Motel
Silver City
Cottonwood Park
Kluane Lake Lodge
Macintosh Lodge
Canyon Creek
Haines Junction
Champagne
Takhini Crossing
Whitehorse
Kathleen Lake Lodge
Sourdough Country R.V. Park
Dezadeash Lodge
Klukshu
Dalton Post
Carcross
Tagish
Teslin
YUKON
BRITISH COLUMBIA
Chilkat Pass
Bennett
White Pass
Yakutat
MT LOGAN
MT VANCOUVER
MT QUEEN MARY
ST. CYR MOUNTAINS
SIMPSON RANGE
CASSIAR
Frances Lake
Tuchitua
Upper Liard
Macmillan Pass
MACKENZIE MOUNTAINS
SELWYN
MOUNTAINS
HESS
NADALEEN RANGE
LOGAN
MT CHRISTIE
Halsteads
Rancheria Hotel/Motel
Junction 37 Services
BEAVER CREEK
BURWASH


ARC
STROKER
ACE
BETH
TOP GUN
LIB
4500
5000
5500
6000
6500
4000
YB21591
YB21592
YB21598
YB21597
YB21595
YB21593
YB21596
YB21590
YB21589
YB21588
YB21587
YB21594
YB07826
YB07827
YB07828
YB07829
YB07830
YB07831
YB07832
YB07833
YB07834
YB07835
YB07836
YB07837
YB07838
YB07839
YB07840
YB07841
YB07842
YB07843
YB07844
YB07845
YB20427
YB20428
YB20429
YB20430
YB20431
YB20432
YB20433
YB20434
YB20436
YB20437
YB20438
YB20439
YB20440
YB20441
YB20442
YB20444
YB20445
YB21794
YB21795
YB21796
YB21797
YB21798
YB21799
YB21800
YB21801
YB21802
YB21803
YB21804
YB20408
YB20409
YB20410
YB20411
YB20412
YB20413
YB20414
YB20415
YB20416
YB20417
YB06101
YB06102
YB06119
YB06120
YB06121
YB06122
YB06311
YB06312
YB06313
YB06315
YB06316
YB06317
YB06318
YB06322

,rton Ave.
ancouver, B.C.
X5
,985-0681 Telex 04-352667

BONDAR-CLEGG

Lab Report

REPORT: V88-05693.0 | PROJECT: NONE GIVEN | PAGE 1A

SAMPLE NUMBER	ELEMENT UNITS	Au 30g PPB	Ag PPM	As PPM	B PPM	Ba PPM	Be PPM	Bi PPM	Cd PPM	Ce PPM	Co PPM	Cr PPM
R2 R1		1405	1.5	>2000	<2	265	<4.0	30	<126	13	5	51
R2 R2		2605	7.5	>2000	<2	162	<4.0	25	<156	6	<2	21
R2 R7		2180	>50.0	>2000	<2	34	<4.0	201	<595	<5	9	21
R2 R8		8070	>50.0	>2000	<2	36	<4.0	369	<438	<5	6	55
R2 R9		1844	30.1	>2000	<2	22	<4.0	60	<347	<5	<2	62
R2 R11A		1501	25.5	>2000	<2	56	<4.0	<5	25	31	<2	39
R2 R11B		1722	>50.0	>2000	<2	88	<4.0	114	<1109	7	<2	100
R2 R14		630	2.7	>2000	<2	34	<4.0	8	<143	14	4	33
R2 R18		418	16.6	>2000	<2	121	<4.0	22	61	<5	<2	84
(E) R2 R19		267	0.7	>2000	<2	22	<4.0	8	<177	<5	23	67
(E) R2 R25A		297	0.6	>2000	<2	11	<4.0	<5	45	<5	3	57
R2 R27		5221	>50.0	>2000	<2	99	<4.0	65	<550	<5	<2	18
R2 R35A		3909	29.7	>2000	<2	47	<4.0	72	<553	<5	<2	18
R2 R35B		3883	>50.0	>2000	<2	39	<4.0	97	<745	<5	<2	45
R2 R36		594	23.5	>2000	<2	106	<4.0	51	107	<5	3	48
R2 R38		946	5.8	>2000	<2	174	<4.0	15	22	7	<2	40
R2 R39		1377	7.7	>2000	<2	403	<4.0	21	<93	10	3	52
R2 R40		1551	3.6	>2000	<2	135	<4.0	13	<28	<5	<2	80
R2 R43		236	<0.5	>2000	<2	126	<4.0	<5	20	<5	2	70
R2 R44		1826	>50.0	>2000	<2	295	<4.0	15	66	<5	2	69
R2 R45		675	9.6	>2000	<2	87	<4.0	8	30	<5	3	136
R2 R46		3569	>50.0	>2000	<2	38	<4.0	78	<512	8	11	38
R2 R48		455	7.4	>2000	<2	95	<4.0	11	33	<5	<2	85
R2 R49		541	1.8	>2000	<2	96	<4.0	6	76	6	4	63
R2 R52		434	5.2	>2000	<2	41	<4.0	16	<66	<5	<2	107

REPORT: V88-05693.6

SAMPLE NUMBER	ELEMENT UNITS	Ag GMT	Cu PCT
R2 R7	5.5	171.4	
R2 R8	9.0	122.4	
R2 R11B	13.4	110.7	
R2 R27	6.5	202.6	1.79
R2 R35B	3.0	68.9	
R2 R44	1.0	30.9	
R2 R46	2.5	88.1	

J.P. Ros (K.G)

ACME ANALYTICAL LABORATORIES LTD. 852 E. HASTINGS ST. VANCOUVER B.C. V6A 1R6 PHONE(604)253-3158 FAX(604)253-1716

GEOCHEMICAL ANALYSIS CERTIFICATE

ICP - .500 GRAM SAMPLE IS DIGISTED WITH 3ML 3-1-2 HCL-HNO3-H2O AT 95 DEG. C FOR ONE HOUR AND IS DILUTED TO 10 ML WITH WATER. THIS LEACH IS PARTIAL FOR MN FE SR CA P LA CR MG BA TI B W AND LIMITED FOR NA K AND AL. AU DETECTION LIMIT BY ICP IS 3 PPM.
- SAMPLE TYPE: P1 SOIL P2 ROCK AU* ANALYSIS BY ACID LEACH/AA FROM 10 GM SAMPLE., HG ANALYSIS BY FLAMLESS AA.

DATE RECEIVED: AUG 30 1988 DATE REPORT MAILED: Sept 8/88 ASSAYER. C. Leong ..D.TOYE OR C.LEONG, CERTIFIED B.C. ASSAYERS

NORANDA EXPLORATION PROJECT 8809-002 312 File # 88-4064 Page 1

SAMPLE#	Mo PPM	Cu PPM	Pb PPM	Zn PPM	Ag PPM	Ni PPM	Co PPM	Mn PPM	Fe %	As PPM	U PPM	Au PPM	Th PPM	Sr PPM	Cd PPM	Sb PPM	Bi PPM	V PPM	Ca %	P %	La PPM	Cr PPM	Mg %	Ba PPM	Ti %	B PPM	Al %	Na %	K %	W PPM	Au* PPB	Hg PPB
Q1	1	103	33	136	1.3	23	20	1094	5.04	1955	5	ND	3	54	1	7	3	70	.39	.074	15	33	1.04	209	.14	6	2.40	.02	.34	2	210	120
Q1 D	1	113	38	203	1.3	20	20	1118	5.05	1899	5	ND	3	55	2	7	2	70	.43	.077	15	31	1.01	208	.14	9	2.26	.02	.36	2	230	20
Q2	1	22	3	115	.1	15	12	411	2.96	56	5	ND	2	39	1	2	2	52	.60	.095	11	25	.82	201	.17	4	1.77	.03	.30	1	4	30
Q3	1	111	55	689	3.8	20	17	763	5.95	3670	5	ND	2	28	13	10	7	51	.29	.054	14	25	.80	188	.10	16	1.98	.02	.19	1	98	80
Q3 (8,9)	1	66	21	534	1.5	20	16	748	4.44	1354	5	ND	2	31	6	7	2	53	.34	.042	13	26	.84	164	.12	5	2.05	.03	.17	1	330	50
Q4	1	150	153	1267	3.8	20	18	727	5.07	5252	5	ND	2	52	29	11	2	62	.48	.091	11	22	1.13	296	.17	2	2.62	.03	.34	3	112	80
Q4 B	1	219	208	1628	5.3	17	19	748	5.59	9732	5	ND	2	55	41	17	5	60	.49	.097	11	20	1.11	339	.17	2	2.54	.03	.38	5	220	100
Q5	1	462	497	1466	33.1	11	14	633	9.23	10864	7	4	4	108	29	47	42	66	.44	.117	17	25	.97	303	.12	5	2.08	.03	.55	1	2680	300
Q5 A1	1	356	496	2194	14.7	14	20	1122	7.45	9421	5	16	2	70	49	32	20	80	.57	.137	16	30	1.27	658	.16	10	2.26	.02	.61	1	9780	150
Q6	1	49	412	1126	2.1	16	26	2375	7.20	3794	5	ND	3	59	9	18	4	48	.61	.086	14	29	1.00	240	.08	8	1.94	.02	.16	1	370	50
Q6 A6	1	47	304	851	1.6	15	30	2476	7.32	3449	5	ND	2	60	7	15	2	41	.61	.100	13	22	.92	208	.07	9	1.65	.02	.17	1	320	30
Q7	1	107	266	1573	1.6	10	24	1557	6.00	2593	5	ND	3	42	20	10	5	44	.53	.130	21	23	.82	204	.06	7	1.64	.01	.17	1	171	50
Q8	1	23	23	136	.3	20	13	391	3.25	179	5	ND	1	25	1	3	2	58	.30	.039	9	28	.91	159	.17	7	2.05	.02	.26	1	33	30
Q9	1	375	1114	5783	12.9	8	39	1911	16.44	11369	5	3	3	276	138	192	11	33	1.86	.096	10	11	.66	115	.02	15	1.15	.01	.12	63	1070	260
Q10	2	88	99	747	1.7	50	22	1042	6.93	6781	5	ND	2	256	7	63	4	30	2.47	.078	14	24	.93	167	.03	10	1.40	.01	.18	1	215	30
Q11	1	35	15	159	.2	21	13	452	3.77	147	5	ND	3	29	1	2	2	73	.50	.110	14	27	.85	127	.16	6	1.61	.02	.26	1	41	100
Q12	1	49	42	370	.3	22	18	765	4.33	827	5	ND	4	29	3	4	2	65	.39	.074	20	34	1.09	231	.16	5	2.32	.02	.34	1	25	30
STD C/AU-S	16	56	35	124	6.7	68	28	1051	4.06	42	18	8	37	48	18	17	18	56	.46	.087	40	55	.91	178	.06	34	1.93	.06	.13	11	48	1400

SAMPLE#	Mo PPM	Cu PPM	Pb PPM	Zn PPM	Ag PPM	Ni PPM	Co PPM	Mn PPM	Fe %	As PPM	U PPM	Au PPM	Th PPM	Sr PPM	Cd PPM	Sb PPM	Bi PPM	V PPM	Ca %	P %	La PPM	Cr PPM	Mg %	Ba PPM	Ti %	B PPM	Al %	Na %	K %	W PPM	Au* PPB	Hg PPB
ARCC	1	2329	384	580	77.8	7	46	55	16.70	11516	6	15	1	47	39	92	269	14	.11	.025	2	16	.15	19	.01	11	.35	.01	.30	1	11320	10
R-5	1	119	169	106	5.2	1	2	103	4.18	11199	5	2	1	97	2	29	17	3	.66	.034	3	3	.02	238	.01	4	.16	.01	.10	1	2050	20
R-10	1	229	85	2040	4.6	5	6	533	3.88	10644	5	ND	1	57	35	17	20	10	1.16	.018	2	24	.38	61	.01	6	.43	.01	.07	1	285	120
R-12	1	395	239	576	31.7	3	4	73	8.49	10966	5	ND	4	29	31	49	101	2	.04	.023	4	3	.03	48	.01	20	.26	.01	.22	1	475	520
R-15	1	9	8	287	.3	3	5	644	1.69	427	5	ND	1	154	1	2	2	16	1.60	.043	3	3	.34	423	.03	3	2.18	.09	.08	28	9	10
R-16	1	44	182	466	3.4	4	7	763	2.88	1442	5	ND	1	9	5	6	3	19	.21	.058	4	14	.68	84	.01	4	1.00	.01	.20	2	49	20
R-20	1	65	21	309	.9	14	15	1142	5.03	202	5	ND	2	154	2	7	2	93	1.35	.093	16	96	3.50	44	.01	30	3.67	.01	.19	1	2	20
R-25	1	52	691	5662	2.8	6	12	1308	5.78	11380	5	2	2	303	101	393	8	1	4.00	.033	3	3	1.04	54	.01	7	.22	.01	.13	16	1060	220
R-28	1	29	2289	2795	15.3	1	2	14932	1.35	10864	18	ND	3	496	24	31	18	1	30.68	.001	8	1	.24	7	.01	11	.02	.01	.01	1	805	190
R-51	51	41	35	60	.8	2	3	203	1.24	615	5	ND	15	8	1	13	2	1	.11	.001	9	1	.01	53	.01	16	.20	.01	.12	1	42	5
R-54	1	60	96	60	11.4	3	1	55	1.90	10996	5	ND	1	9	4	28	3	1	.02	.005	2	6	.02	137	.01	6	.11	.01	.08	5	505	10
R-55	1	85	497	1300	12.0	4	9	381	5.26	11060	5	2	1	132	54	31	20	32	.18	.039	5	22	.78	158	.05	5	1.32	.01	.21	1	1685	30
STD C/AU-R	18	58	35	124	6.7	68	28	1051	4.06	42	18	8	37	48	18	17	18	56	.46	.087	40	55	.91	178	.06	34	1.93	.06	.13	11	520	1300

Sampler WENE	Location, Target (words) PROSPECT 'ARC' CLAIMS W/ PETER photo no. RUSS	Sample Nos NONE
Date June 26th		Cert. Nos A1 - A25

ADA - SLIGHTLY OX VUGGY VN QTZ [BLOCKY WHT] TRACE CHALCO PYRITE - 20% AS PYRITE STRINGERS
A(2) - ... OX/LIMONITIC QTZ ... NO VISIBLE MZN
A(3) - ... OX VN QTZ - SLIGHT MN STAINING - CORE OF MATRIX HAS ... XSTAL GROWTH W/ 15% SEMI-MASSIVE PATCHES AS PYRITE & TRACE PYRITE
A(4) - BLOCKY WHT VN QTZ, - 5% PYRITE LEACHING (SLIGHTLY OX) - 10-20% SI XSTAL GROWTH
A(5) - MODERATELY OX VN QTZ - STRONGLY VUGGY & TEXTURE & LIMONITIC - 5% GREY QTZ IN WHT QTZ
A6 - STRONGLY OX & FOLIATED VN QTZ - 5% PYRITE, 10% AS PYRITE - 2% GALENA - 20% ... MATRIX ... SCORODITE ALTN. MZN IS BANDED.
A(7) - SLIGHTLY PHYLLITIC QTZ VNING W/ ~15% AS PYRITE FINELY DISSEM.
A(8) - MODERATELY OX VN QTZ W/ ~ 7% DISSEM AS PYRITE
A(9) - SLIGHTLY OX BLOCKY WHT VN QTZ W/ TRACE DISSEM AS PYRITE
A(10) - STRONGLY OX VN QTZ - 20% PYRITE, 15% ARSENO, 5% SULFOSALTS ; 50% OF FLOAT IS WHT QTZ, 50% GREY QTZ W/ SULFOSALTS.
A(11) - STRONGLY OX SILICEOUS LIMONITE - MODERATE MN STAINING W/ NO VISIBLE MZN
A(12) - STRONGLY OX VN QTZ W/ MN STAINING (VUGGY) ; 3-4% BLEBBY AS PYRITE
A(13) - BLOCKY WHT VN QTZ W/ SLIGHT MN STAINING & TRACE AS PYRITE.
A(14) - SLIGHTLY PHYLLITIC QTZ VNING ; SLIGHTLY OX W/ MINOR MN, 2% ARSENO IN BLEBS & TRACE GALENA.
A(13) - MODERATELY OX, VUGGY QTZ BRECCIA [QTZ & CALCITE] TRACE AS PYRITE.
A(14) - STRONGLY OX & SLIGHTLY LIMONITIC GRANO DIORITE - NO VISIBLE MZN.
A(15) - MODERATELY OX BLOCKY WHT QTZ. W/ 40% CALCITE IN MATRIX - TRACE AS PYRITE
A(16) - SLIGHTLY OX QTZ VNING W/ 20% SI XSTAL GROWTH & 5% ARSENO PYRITE - APPEARS SLIGHTLY FOLIATED - ~10% KAOLINITE FELDSPARS IN 1 PART OF ROCK.
A(17) - FINE GRAINED [DARK] APPALITE DYKE. 2-3% PYRRHOTITE. [NOT FOR ASSAY]
A(18) - MODERATELY OX QTZ VN W/ MODERATE MN STAINING 5-10% MUSCOVITE IN MATRIX TRACE AS PYRITE.
A(19) - BLOCKY WHT VN QTZ - 5% LIMONITIC - 50% YELLOW STAINED
A(20) - BROWN/RED SOIL
A(21) - BLOCKY WHT QTZ VNING W/ CHLORITIC ALTN, 3-5mm BAND OF AS PYRITE ON 1 EDGE
A(22) - LIMONITIC QTZ VNING W/ MODERATE MN STAINING - CORE OF MATRIX IS MASSIVE AS PYRITE [30%] W/ 10% SULFOSALTS.
A(23) - BLOCKY WHT QTZ VNING W/ CHLORITIC ALTN & ~3-5% DISSEM AS PYRITE
A(24) - STRONGLY OX QTZ VN (10cm WIDTH) FOUND IN PLACE [STRIKE 020°, DIP 60°] ; 30-40% AS PYRITE & 10-15% SULFOSALTS - 5% GREY-BLUE QTZ IN CORE OF MATRIX
A(25). AS PYRITE STRINGERS IN GRANO DIORITE FRACTURES. STRONG CHLORITIC ALTERATION STRINGERS ARE 1-2mm WIDTH. 5% AS HAS MIGRATED TO WALL ROCK.

NOTE: ALL SAMPLE ARE FLOAT FROM FLOAT TRAINS ~ 1 METER WIDE EXCEPT FOR A24,25.

DON'T FORGET CONTOURS, DRAINAGE, NORTH ARROW, LAT/LONG, SAMPLE SITES, WORKINGS, TRAILS, GOSSANS, OBSERVED GEOLOGY: DEFINED —— INFERRED - - - ASSUMED .....

SPECIMEN SITE A.B.... ; DO NOT WRITE ON OTHER SIDE OR USE COLOURS

MINERALS · INTRUSIVE · LIMESTONE DOLOMITE · VOLCANIC · CONGLOMERATE · SANDSTONE SILTSTONE · SHALE · CHERT

SILT x SOIL • ROCK • PAN Δ WATER O

Chemex Labs Ltd.
Analytical Chemists * Geochemists * Registered Assayers
212 BROOKSBANK AVE. NORTH VANCOUVER,
BRITISH COLUMBIA CANADA V7J-2C1
PHONE (604) 984-0221

T. ...HER CATHRO & ASSOC. (1981) LTD.
BOX 4127, 3125 3RD AVE.
WHITEHORSE, Y.T.
Y1A 3S9
Project: SHUT
Comments:

Page N. :1
Tot. Pages: 1
Date : 7-JUL-88
Invoice # : I-8818142
P.O. # : NONE

CERTIFICATE OF ANALYSIS A8818142

SAMPLE DESCRIPTION	PREP CODE	Au oz/T RUSH
6501 A1-A	236 —	0.106
6502 — B	236 —	0.206
6503 — C	236 —	0.160
6504 A2	236 —	0.002
6505 3	236 —	0.022
6506 4	236 —	0.046
6507 5	236 —	0.319
6508 6	236 —	0.046
6509 7	236 —	0.002
6510 8	236 —	0.012
6511 9	236 —	0.026
6512 10	236 —	0.008
6513 11	236 —	0.012
6514 12	236 —	0.006
6515 13	236 —	< 0.002
6516 14	236 —	0.004
6517 15	236 —	0.002
6518 16	236 —	0.002
6519 17	236 —	< 0.002
6520 18	236 —	0.002
6521 19	236 —	0.016
6523 21	236 —	0.018
6524 22	236 —	0.024
6525 23	236 —	0.004
6526 24	236 —	0.138
6527 24.25	236 —	0.004

ALL ASSAY DETERMINATIONS ARE PERFORMED OR SUPERVISED BY BC CERTIFIED ASSAYERS

CERTIFICATION: _____