2009 DIAMOND DRILLING REPORT
ON THE
CANYON GOLD GREW CREEK PROJECT

Whitehorse Mining District, Yukon Territory

Project Centre
Latitude 62° 03' N, Longitude 132° 50' W

NTS Map Sheets: 105 F15, 105 K2, 105K3

Kaolin 1 (YC18762), Kaolin 3 (YC18764),
Maverick 10 (YC19371), Canyon 66 (YA81185)
and Canyon 10 (YA75726)

for

095232

EMERICK RESOURCES

830 – 355 Burrard Street
Vancouver, BC V6C 2G8

Owner of Claims: A. Carlos

By: Shane A. Carlos
March 10, 2010.

Costs associated with this report have been approved in the amount of $ 138,100.00 for assessment credit under Certificate of Work No. Q02847

Mining Recorder
Whitehorse Mining District

Table of Contents

	Page
Introduction	1
2009 Program	1-5
Drill Hole Summaries	6-7
Discussion/Conclusions	7-11
Recommendations	11-12
References	13

Table

Table 1	Summary of Drill Hole Data	1

Figures

Figure 1	Project Location Map	2
Figure 2	Overview Drill Hole Location Map	5
Figure 3	Rat Creek Grid Mercury Contour, Greg. T. Hill	9
Figure 4	Rat Creek Enzyme Leach Mercury Contour and drill hole locations	10
Figure 5	Orthophoto: Rat Creek Grids, drill hole locations and claim location	14
Figure 6	Orthophoto: Maverick Grid, drill hole locations and claim location	15
Figure 7	Orthophoto: Km 410 Grid, drill hole locations and claim location	16

Appendices

Appendix 1	Drill Hole Logs
Appendix 2	Drill Hole Cross Sections and Corresponding Plan Maps
Appendix 3	Assay Results-ALS Chemex
Appendix 4	Work History-Yukon Minfile
Appendix 5	Active Claim List
Appendix 6	Statement of Qualifications

Introduction

A total of 1592.3 meters of drilling on three target areas was completed through July and September, 2009. Geochemical results were in general disappointing, however a strong mercury anomaly in D.D.H. 08 is an encouraging sign that the geochemical approach is working and warrants follow up. A large portion of this report will focus on the results in the Rat Creek area and secondly the Km 410 target area. Some speculative statements are made with exploration in mind and compilation of other work is considered especially in light of the Rat Creek drilling results.

An overview map of the drilling locations is given in Figure 2 and Figures 5, 6 and 7 with drill hole locations, claim and topography maps. A detailed work history is provided in Appendix 4.

2009 Program

The primary purpose of the drilling was to test Enzyme Leach soil geochemistry targets at the Rat Creek, Maverick and Km 410 target areas. Drill locations were chosen primarily on the recommendations of Gregory T. Hill, who provided interpretation of the Enzyme Leach data. The drill holes were successfully completed except for the first attempts at drill holes D.D.H. 01 and D.D.H. 08 which were lost in the overburden and D.D.H. 05 which was abandoned in overburden. A summary of the drilling program is presented in Table 1.

Hole ID	NAD83 GPS coordinates		Local grid coordinates		Claim	Elevation	Total Length	Azimuth	Dip
	Easting	Northing				m a.s.l.	m		
CG-01-09	596709	6891549	21+470W	10+050N	Kaolin 1	794	18.3	78	-50
CG-01-09R	596709	6891549	21+470W	10+050N	Kaolin 1	794	186.6	78	-50
CG-02-09	596892	6891602	21+330W	10+195N	Kaolin 1	776	157	258	-50
CG-03-09	595939	6892083	22+400W	10+155N	Kaolin 3	777	181.4	215	-60
CG-04-09	595857	6891936	22+400W	9+975N	Kaolin 3	777	207.3	35	-60
CG-05-09	606546	6886500	9+700W	10+260N	Canyon 66	784	35.05	230	-50
CG-06-09	605264	6887031	11+030W	9+740N	Maverick 10	823	189	60	-50
CG-07-09	605401	6887178	11+030W	9+942N	Maverick 10	819	199.6	230	-70
CG-08-09	612036	6881087	11+035E	9+635N	Canyon 10	795	37	93	-45
CG-08R-09	612036	6881087	11+035E	9+635N	Canyon 10	795	205.7	93	-50
CG-09-09	611951	6880832	11+035E	9+350N	Canyon 10	805	175.3	93	-50

Table 1



Emerick Resources Corp.

Grew Creek Project
Location Map

Figure 1

Date: January 30, 2008
Drawn By: Scott Turton

The following insert in italics is taken directly from Sarah Publicover (geologist) who was responsible for this portion of the program:

Drilling

The drilling contractor was Kluane Drilling Ltd. (Kluane) of Whitehorse, Yukon. Drill core size was NW although several holes were reduced shortly after casing to BW size. The drill was a KDHT-1000 (Kluanes version) and was moved between drill sites with a D8 CAT.

A total of 1592.3 m of drilling was completed in nine holes. The length of casing in each hole varied between 1.5 and 94.5 meters. Core recovery was excellent, with only rare, short intervals returning less than 100 percent of the core.

Core Logging

All drill core from the 2009 program was logged and split on site at the core shack in Faro by a contract geologist hired by Emerick. Detailed geologic descriptions were recorded by hand on geologic logs and were subsequently transcribed [onto computer]. A complete set of geologic logs is attached as Appendix [1].

Core is stored on site in a small clearing off main road at UTM 0607319, 6886096 (NAD 83).

Sampling

Almost all core was split by hand with a heavy duty, crank-type splitter and sampled with one half the core sample submitted for assay and the remainder retained for future reference. Occasionally, sections with little geologic interest were skipped in the sampling process. The sample intervals were generally at 1.5 meters and normally defined by changes in geology and or mineralogy.

Samples, including blank and standard duplicate samples, were shipped to Vancouver to be analyzed by ALS Chemex. All samples were analyzed for 28 elements. Gold analyzes were by fire assay followed by atomic absorption finish and Ag, Al, As, Ba, Be, Bi, Ca, Cd, Co, Cr, Cu, Fe, K, Mg, Mn, Mo, Na, Ni, P, Pb, S, Sb, Sr, Ti and V were analyzed by the Induce Couple Plasma (ICP) method.

Data Verification

Samples from the 2009 drilling program were subjected to a Quality Control (QC) program designed by the author. The QC program consisted of:

***Sequentially numbered sample tickets:** to identify each sample with a unique number to minimize the possibility of sample numbering errors and to ensure uniform collection of sample data.*

Securely tied sample bags: *to secure individual sample bags to reduce the possibility of sample contamination, spilling or tampering.*

Chain of custody: *samples were stored in secure preparation area and delivered to the laboratory directly by commercial freight carrier.*

Sample blanks: *Geochemical blanks of un-mineralized rock material taken from nearby gravel pit were inserted into the sample sequence at a frequency of approximately 1 in 20. All blank samples yielded background values, including samples inserted directly following a "standard" value to test for "smear effect" during the sampling process, indicating no observable contamination. Thus, the analytical techniques employed by ALS Chemex can be considered highly reliable. These blanks were assigned unique sample numbers within the sample sequence so as to be "blind" to the laboratory.*

Reference standard samples: *Three commercially produced gold reference standards were purchased from CDN Resource Laboratories Ltd. The standards values were 1.05 +/- 0.10 g/t, 9.71 +/- 0.65 g/t, and 21.12 +/- 1.54 g/t respectively. The highest value standard was not necessary in this program as there were no samples nearing that range. The lowest grade standard was used most frequently at a rate of 1 in 20 samples, however occasionally was substituted for the mid-range standard. Standards were assigned unique and sequential sample numbers and were inserted randomly so as to be "blind" to the laboratory. Assay results were almost identical to the known values again indicating high reliability of results provided by ALS Chemex.*


595000
600000
605000
610000
615000
620000
6900000
6895000
6890000
6885000
6880000
6875000
6870000
6865000
N
CG-03-09
CG-04-09
CG-02-09
CG-01-09
CG-01-09R
CG-06-09
CG-07-09
CG-05-09
CG-08-09
CG-09-09
CG-08-09R
Legend
Drill Holes
0 2 4 6
Kilometers
Emerick Resource Corp.
Grew Creek
Drill Hole Location Map
Figure 2

Diamond Drill Hole Summaries

Km 410 Grid

Two Enzyme Leach targets were tested with a fence of two drill holes each.

D.D.H. 01 returned carbonaceous breccia, grey breccia with qtz./carbonate stockwork, pegmatitic granitoid dyke and brecciated graben sediments with interbedded green lapilli tuffs down-hole. The grey qtz./carb. stockwork zones which were originally probably siltstone layers assayed around 1ppm silvers. The nearby pegmatitic dyke assayed 2.4 ppm silver and anomalous Pb, Cu and Bi.

D.D.H. 02 intersected a 35m interval of felsic quartz breccia that was pyritized, sericitized, quartz veined, argillized and returned anomalous gold from 11-44 ppb, a course grained felsic intrusion and carbonaceous breccia grading into brecciated but cleaner graben sediments down-hole.

D.D.H. 03 returned dominantly carbonaceous breccia incorporating sections of recognizable graben sediments and bleached basalt dyke, and at the end of the hole brecciated, cleaner sediments. The only mineralization was a 70 cm apparent clast of magnetic, sheared cataclasite, with high nickel, chrome, cobalt.

D.D.H. 04 started in meta-siltstones, to carbonaceous breccia and ending in less altered graben sediments. No mineralization was detected.

Maverick Grid

D.D.H. 05 encountered gas pressure and was abandoned at 115m in the overburden. Part of the reason the hole was lost was due to the lack of bentonite to maintain the hole from eroding. When pulling the casing, mud, boulders and chunks of clay were shot 15-20 feet out of the hole for about ten minutes.

D.D.H. 06 and 07 drilled to test Enzyme Leach target 'B' returned no anomalous zones of elements, leaving this target unexplained. Brecciated graben sediments and a short section of volcaniclastic rich unit were intersected.

Rat Creek Grid

D.D.H. 08 and 09 were drilled to test a joint Enzyme Leach, resistivity, magnetics and structural setting target in the Rat Creek area. Sericitization of rhyolites and clay alteration are pervasive throughout these holes.

D.D.H. 08 intersected sections of hydrothermal breccia (previously called heterolithic volcanic, or volcanic conglomerate), gabbroic dykes, quartz feldspar rhyolite porphry, various tuffs and hematized welded tuff. Only low levels of gold were detected, occuring in the hydrothermal breccia, gabbroic dyke and rhyolite porphry. The hematized welded tuff returned a strong mercury anomaly near the bottom of the hole in immediate proximity to a fault zone to the North. The up hole side of the gabbroic dyke had abundant chalcedony permeating the overlying breccia, while the underside was a clay matrix with broken white vein fragments throughout.

D.D.H. 09 intersected hydrothermal breccias, various tuffs, portions of altered gabbroic dyke, a long section of pyritized green rhyolite porphry, and ending the hole in hematized, pyritic lapilli tuffs. Only low levels of gold were detected in the hydrothermal breccias, and pyritized rhyolite porphry.

Discussion

Rat Creek Target

The coinciding mercury and hematized welded tuff below an in-soil mercury anomaly is the best result out of the Rat Creek drilling this past fall.

The mercury anomaly in D.D.H. 08-2009, is the most significant intersection of mercury outside the Main Zone deposit from all drilling completed on the property to date. I personally conducted a survey for mercury and encountered only two other occurrences (with mercury's consistently over 1 ppm) outside the Grew Creek deposit:

1. D.D.H. 81-1988, from 36m-49m (13m interval) in sediments, mercury from 1-3 ppm, at 9800N, 12000E (same Noranda grid).

2. RC-23-1988, from 87m-91m in reddish-brown stained rock chips, mercury from 1-2 ppm, at 9310N, 11400E (same Noranda grid).

These occurrences are minor contrasted to D.D.H. 08 with consistent mercury from 2-4 ppm, (averaging 3 ppm) over 34m with a 15 ppm outlier . These values and length of interval are comparable to the Main Zone hanging wall mercury's. For example, D.D.H. 30-1988, with hanging wall mercury from 1-5 ppm, (averaging 4 ppm) over 27m is a typical example from the Grew Creek Deposit, though in most cases there was a 5 ppm upper detection limit. Of interest, the highest recorded Main Zone mercury's are 12.8 and 12.4 ppm over 1/2 m intervals, while D.D.H. 08 had a 15 ppm over 1.5m.

The rock unit is a welded tuff/pseudo porphry which is present at the Main Zone and has been encountered East of Grew Creek. Robert Stroshein describes these welded tuffs as 'hematized, mottled red and green,' (see drill logs and lithological descriptions, Stroshein, 1993) which compares to D.D.H. 08 logs with 'bright green and red speckled' core. Also, fine white crystal laths are seen to overprint the rock texture which suggests melting of the rock and that indeed the rock is welded tuff. See, Christie et al., 1992 on the importance of these welded tuffs as aquicludes as a control to gold mineralization at Grew Creek.

Drill holes 170-178 on the Rat Creek Grid were only assayed for gold and silver and in some rare instances assay sheets are missing from provided data from previous operators. This leaves open the possibility of undetected or unreported mercury anomalies. However, other welded tuffs, for example D.D.H. 143 between Grew and Rat Creeks returned no mercury. Of all the drilling outside the Main Zone, only D.D.H. 170-178 and 182-184, 186 were tested for gold and silver alone, R.C. Holes 9-15 in the area were not assayed for mercury and D.D.H. 237-240 are missing the multi-element sheets. To restate: In the Rat Creek area there are a total of 19 holes that have no mercury analysis out of a total of approximately 72 drill holes.

The intersection of the strong mercury anomaly must be considered a very encouraging confirmation of the geochemical approach on the Rat Creek target. The Enzyme Leach data indicated a strong mercury presence at the Northern edge of the survey and has been confirmed by drilling. It should be noted that over the Grew Creek deposit no Enzyme Leach mercury anomalies were detected, which is not easily explainable other than to say this inconsistency is simply a limitation in the mobile element geochemical approach. Regardless, the Enzyme Leach mercury over the Rat Creek target has been confirmed to be working locally and is therefore a useful tool in the immediate target area.

Finally, the fault that D.D.H. 08 came close to crossing (see Plan Map, Figure 4) was drawn in by Noranda based off of an I.P. Survey (Fig. 62, Duke, 1988). Noranda draws this fault directly into or just North of the Main Zone deposit (see Figure 5). In Gregory T. Hill's 2006 report on the Enzyme Leach survey over the Main Zone he refers to two parallel faults that flank the gold mineralization at 20 degrees to the Grew Creek Fault. The Northern of these faults lines up with the same Noranda interpreted fault that strikes to Rat Creek. With the high mercury zone in D.D.H. 08, the importance of this fault for controlling mineralization is becoming clear.

Special note on D.D.H. 09-2009:

Compilation of drill data on plan (see Appendix 2, D.D.H. 09-2009) reveals a possible local target centered on an Enzyme Leach mercury anomaly and fault zone. D.D.H. 09, amongst other ideas was also supposed to cross this fault but due to concern over sanding the hole was stopped short. RC-31 intersected an 18 meter zone of consistent gold from 207-730 ppb and when plotted comes out on the Western strike of the Enzyme Leach fault trace. All the drill holes centered around this 100m strike, local target have managed to not follow up on the original 1988 R.C.-31 gold intercept but have entirely missed this possible trend. These holes have picked up anomalous golds all around and D.D.H. 03-2006 intersected a 3m interval averaging 71 g/t silver in breccia. This target has a North trending extensional fault (not shown) that trends up line 11+100E, making a favourable fault intersection. Drill holes 02-2006, 03-2006 and 09-2009 all intersected a zone of accretionary lapilli balls, that has a dip to the North into the fault zone. These balls are known to occur in vertical pipes. I suggest a possible mineralized structural setting and breccia pipe at the intersection of two extensional faults and roughly outlined by the mercury contour on the plan map.

The breccia with 71 g/t silver had large fragments of highly altered and mineralized (sulfides) gabbroic dyke. This mineralized breccia occurs at the top of hole D.D.H. 3-2006 and D.D.H. 09 did not return this silver mineralized breccia. There is a bend in the magnetics (see Figure 3) on the fault trace which could represent the alteration and mineralization of the dyke fragments encountered. A brecciating source coming to surface at a fault intersection would help explain why we weren't able to intersect the mineralized dyke fragments in D.D.H. 09.

Finally, an unusual occurrence of 'coal' in D.D.H. 176 (see Appendix 2, plan of D.D.H. 09) may be of importance. There are several about one meter thick carbon sections with carbonate veining in them. These 'coal' sections occur in heterolithic volcanic breccia (hydrothermal), so are apparently re-mobilized. An example of re-mobilized carbon occurring immediately peripheral to a gold deposit is the Carlin in Nevada (Radtke, 1980), and there are other examples.

Km 410 Target



FIG. 4

Drawn by: Shane Carlos



Figure 3. Distribution of mercury by enzyme leach overlaid on 400 nT contours showing magnetic high (from Noranda, 1988). Grey large dashed lines represent faults interpreted by Noranda. Black short dashes are interpreted faults from soil geochemistry. Enzyme leach gold shown in symbol plot.

Zoned geochemical responses in the area had suggested an intrusion related target. A pegmatitic dyke and dyke fragments in D.D.H. 01-2009 are indeed portions of an intrusion. The D.D.H. 01 and D.D.H. 02 fence have a carbonaceous and clay-rich breccia section that dies off with depth. It appears that this carbonaceous breccia is locally an alteration envelope around a pegmatitic dyke intrusion and to the felsic igneous rocks by the road and in D.D.H. 02 (see Appendix 2, plan and section for D.D.H. 02, 03). In the area these carbonaceous breccias can be quite extensive as in D.D.H. 03 and D.D.H. 04 and the source of this carbon and breccia alteration may have much to do with fault movement and a larger, as yet unseen intrusion to the south.

In the D.D.H. 01 and D.D.H. 02 fence, the quartz/carbonate stockworks with anomalous silvers and 35m section of pyrite alteration with gold, respectively, occur near the surface. The grey breccia stockwork zones are apparently altered siltsones with core angles of 45 degrees. If these units are indeed flat lying they would lay just below the till cover and above the pyritic zone in D.D.H. 02. Optimistically, these units may be hosting gold mineralization and the fence of drill holes effectively drilled underneath and missed the favourable horizons. The gold could be dropped out between the drill holes and at the distance of D.D.H. 01 only qtz./carbonate stockwork and anomalous silvers have penetrated along these units. The other option is that the gold anomaly is only related to the low levels of gold in D.D.H. 02. In favour of the later option, D.D.H. 02 has the 35m interval of consistent gold values albeit low, whereas in D.D.H. 134 which crosses and in a direction away from the gold anomaly the gold values are not continuous. Perhaps D.D.H. 02 is getting closer to where the gold is dropped out.

Maverick Target

The role of gas has been theorized as a carrier for mobile elements to the B-horizon soil, therefore the possibility that target 'D' was caused in part/or by gas emanations should be considered.

Maverick target 'B' drilled by the D.D.H. 06 and D.D.H. 07 fence was simply not explained by the geology and rock geochemistry.

Recommendations

1. Follow up drilling on the Rat Creek target should be undertaken, specifically, to follow up on the mercury encountered. The mercury could be considered as either a hanging wall, lateral zone or both to gold mineralization.

The area is free from any drilling to the North of the mercury anomaly except for R.C.-33 that ended in overburden (see Figure 3, Plan Map). D.D.H. 08-2009 only went about 15m beyond the mercury zone so the possibility of a mineralized zone to the North has not been tested. For example, at the Main Zone, there is sometimes 30 meter long gaps in Hg, and only weakly anomalous Au after the hanging wall mercury before economic gold values appear. R.C.-28, immediately to the West (see Appendix 2, plan and section for D.D.H. 08-2009) almost penetrated the elevation where the mercury was encountered in D.D.H. 08-2009 but the assay sheet for this section is not included in the original Noranda report where we would be most interested. The written report for the R.C. holes makes no mention of what was encountered down-hole in R.C.-28, however in the logs the rock chips are all hematite stained, which suggests a mercury anomaly may have been encountered but was unfortunately

not recorded. The soil geochemistry shows the mercury zone does trend over R.C.-28 (see Appendix 2, plan for D.D.H. 08-2009).

Drilling to the immediate South may still be warranted as one of the Enzyme Leach targets has not been tested and is peripheral to the mercury anomaly. See Figure 4, where an Enzyme Leach arsenic anomaly sits immediately up ice of R.C.-9 with 3540 ppm As and 10400 ppb Au, in concentrates at bedrock.

2. A drill hole to cross the Enzyme Leach fault trace and soil mercury anomaly beside D.D.H. 09-2009, as mentioned in the discussion section.

3. If any more work is undertaken at the Km 410 target, exploratory drilling along trend to test geochemical zonation patterns should be completed. Optimistically, a mineralized zone might exist between D.D.H. 01 and D.D.H. 02 and could be tested with a shallow, steeply dipping drill hole.

4. Follow up drilling on the Maverick target 'B' is not recommended at this time because of the lack of geochemical results and the high expenses of drilling through the deep overburden.

5. Bentonite must be used in the overburden. The first attempt at D.D.H. 08 was lost because a driller used only a weak water polymer in the overburden. The rock alteration is also very intense in the Rat Creek area, so any deep drilling that is undertaken would preferably use bentonite throughout, as sanding down-hole will invariably become a problem.

References

Christie, Anthony B., Duke, Jesse L., Rushton, Ralph, 1992. Grew Creek epithermal gold-silver deposit, Tintina Trench, Yukon. In: Yukon Geology, Vol. 3; Exploration and Geological Services Division, . Indian and Northern Affairs, Canada, p.223-259

Duke, Jesse L., 1988. Summary Report of the 1988 Exploration Activities on the Canyon and Grand Claims, Grew Creek Development Project. Unpublished report, Noranda Exploration Company Limited, Fig. 62

Hill, Gregory T., 2006. Interpretation of Enzyme Leach Orientation Soil Survey Data Above the Grew Creek Main Zone Gold Deposit. Unpublished report.

Radtke, A.S., Rye, R.O, Dickson, F.W., 1980. Geology and Stable Isotope Studies of the Carlin Gold Deposit, Nevada: Economic Geology, v. 75, p. 645, Fig. 3.

Stroshein, Robert W., 1993. Diamond Drilling Report on the Carlos Gold Project, Grew Creek Area. Unpublished Report for YGC Resources Limited.




GRID EXTENSION (2003)
SEE FIG. 4
DANGER CK. FAULT
Possible Mineralized Fault
see Gregory T. Hill (22 Nov. 2000)
ENZYME LEACH "Sb" APICAL ANOMALY C
A, B and D OCCUR AS Sb OXIDATION HALOS
B.L. 10+000N 135° az.
OUTCROP (Au to 2110 PPB)
ENZYME LEACH ANOMALY "E" (APICAL)
SCALE: 1:10,000
GREW CREEK DEPOSIT
RAT CREEK TARGET AREA
KEY CUT LINES
DIAMOND DRILL HOLES
ANGLE O.D.H.-HOLES — 2003
GREW CREEK FAULT
LINE 11100E
9+600N B.L.
PI CANYON 11+12
A
B
C
D
E

FIG. 5


Maverick prospect — Canyon Gold Property
Enzyme Leach survey grid
Grid extension and sample points (2004)
Diamond Drilling : 2003 - 2004
053991 OUTCROPS (ASSAY NO'S)
Diamond Drilling: 2009
PYROBITUMEN - RICH BRECCIA (float)
POST & MAVERICK 11 and 12
D.D.H.-07
D.D.H.-08
D.D.H.-09
GREW CREEK FLT.
10+450N
10+500N
B.L. 135°
94400N
94550N
11950W
11900W
11850W
11800W
8700W
8600W
FIG. 6



FIG. 7

KM. 410— Canyon Gold Property (ENZYME LEACH SURVEY GRID)

LEGEND:

D.D.H. 2003 ●

B — Carles Till Conc. : Au= 9320 ppb (1992)

A — Plouffe Till Conc. : Au= 4790 ppb / As= 289 ppm (1988)

Altered Silicic Volc.: Au To 325 ppb

South Bounding Graben Fault: Tertiary igneous + sed. units north ; Permian chert south of fault

Aerodat Int. Faults

SCALE: 1:10,000

APPENDIX 1

DRILL HOLE LOGS

Arg	argillic	Hm	red hematite
Sil	silicification	Ser	sericite
Py	pyrite	Car	carbonate
Mag	magnetics	Cpy	chalcopyrite
Bx	breccia		
Stw	stockwork		
QFP	qtz feldspar porphry		

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Km 410 Grid

DDH No. **CG-01-2009** Azimuth 078 Started on: 10/08/2009
Northing: 10049 Dip -50 Completed on: 13/08/2009
Westing: 21471 Core Size NTW Logged by: Sara P./Shane C.
Collar Elev. 812m Final Depth 186.6m

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
0	19.8	OVERBURDEN glacial till, boulders, pebbles, sand	
19.8	21.6	CARBONACEOUS FAULT BRECCIA, black, carbon and clay matrix with occasional subangular qtz clasts	Arg-4, Bx
21.6	22.1	GREY BRECCIA, silicified, grey very fine grained angular fragments (1mm-2cm), highly fractured, qtz/carbonate veined, stockwork	Car-3, Stw, Bx Sil-3
22.1	30.5	CARBONACEOUS FAULT BRECCIA, black, carbon and clay matrix with occasional qtz clasts 24.5m-24.8m silicified, grey/green, trace pyrite coarse grained/pegmatitic, 50% qtz, 15% pinkish K-spar, 20% plagioclase, 15% chlorite/unaltered biotite upper contact @ 35 degrees to core angle, probably just a fragment @27.4m 10cm same rock, trace fluorite, trace pyrite @27.8m 4cm piece with py floating in black clay @28m 5cm same rock, less silicious/more argillic	Arg-3, Bx Fluorite-trace Py-trace
30.5	36	GREY BRECCIA, silicified, grey/black very fine grained angular fragments (1mm-2cm), with variable black clay alteration throughout, fragments are veined and vein filling surrounds fragments, qtz/carbonate stockwork Contacts are blurry and gradational.	Car-3, Stw, Bx Sil-3
36	41.2	CARBONACEOUS FAULT BRECCIA, black, carbon and clay matrix with gritty subrounded qtz grains (1-2mm) scattered throughout, occasional clasts of grey breccia unit @36.8m 10cm fragment of the grey/green, coarse crystal grained unit	Arg-5, Bx
41.2	47	GREY BRECCIA, silicified, grey/black very fine grained angular fragments (1mm-2cm), with variable black clay alteration throughout, fragments are veined and vein filling surrounds fragments, qtz/carbonate stockwork Contacts are blurry and gradational. Bottom grades into gritty black clay.	Car-3, Stw Bx
47	55.4	CARBONACEOUS FAULT BRECCIA, black, same as above @48.2m, 5cm of beige/pink clay @49.5m, 30cm white/grey clay 50.9m-55.4m abundant flow textures, colour is grey/green clay altered gouge of underlying unit, intersperced with the black clay	Arg-5, Bx
55.4	59.5	PEGMATITIC, coarse grained/crystals average 2cm, 50% qtz, 15% pinkish K-spar, 20% plagioclase, 15% chlorite, silmilar to above sections but more coarse grained light grey/green colour, white/grey argillic alteration, minor carbonate	Arg-4, Car-2

Arg	argillic	Hm	red hematite
Sil	silicification	Ser	sericite
Py	pyrite	Car	carbonate
Mag	magnetics	Cpy	chalcopyrite
Bx	breccia		
Stw	stockwork		
QFP	qtz feldspar porphry		

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Km 410 Grid

DDH No. **CG-01-2009** Azimuth 078 Started on: 10/08/2009
Northing: 10049 Dip -50 Completed on: 13/08/20
Westing: 21471 Core Size NTW Logged by: Sara P./Shane C.
Collar Elev. 812m Final Depth 186.6m

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
		@57.5m large blebs and stringers of chalcopyrite and chalcocite? ('silver/lead' grey sulphide) upper contact @ 45 degrees, lower contact @ 35 degrees to core angle	Cpy-trace
59.5	81.3	CARBONACEOUS FAULT BRECCIA, black, carbon and clay matrix with gritty fragments throughout, very similar to above CFB, however more competent, less clay and not quite as black, large altered qtz clasts (up to 8cm) subrounded throughout section	Arg-4, Bx
		59.5m-62.6m gradation from green gritty clay, flow textured. (An altered and ground up version of the above pegmatitic rock.) into the black breccia	Arg-4, Car-2
81.3	121.9	SILTSTONE/SANDSTONE BRECCIA, medium to dark grey/light brownish siltstone with occasional gritty beds, heavily interbedded with black bituminous material, bedding planes @ 40 degrees to core angle, clay alteration is variably weak to moderate throughout 98.4m-106.5m increasingly coarse/sandier section 106.5m-115m interbedded siltstone and sandstone 115m-119.7m siltstone, flow textures/banding parallel to c.a., fractures healed with black bitumen	Arg-3, Bx
		119.7m-121.9m highly fractured, lots of black bitumen, coarsens downward, bottom of section has several clasts >1cm	Arg-3.5
121.9	128.5	CONGLOMERATE, bitumen throughout, strong clay alteration, flow textures, brecciated pieces of original conglomerate Bottom 30cm completely black clay and broken pieces <4cm	Arg-4
128.5	129.5	LAPILLI TUFF, light grey, clay altered, qtz eyes to 2mm,contacts are both altered and fractured, lower contact very shallow (ie semiparallel) to core angle	Arg-3-4
129.5	136.8	SANDSTONE TO CONGLOMERATE, 129.5-132.6m dominantly altered medium sandstone, occasional gritty beds, fractured throughout with pyrobitumen on surfaces @131.5m, large 5cm clast of tuff 132.6m-136.8m clay altered conglomerate, with black pyrobitumen common in matrix, large qtz and clay clasts (2mm-3.5cm, rarely larger) rounded to subrounded, some thin sandy sections as well @136.6m flow textures are evident	
136.8	137.2	LAPILLI TUFF, light grey, upper contact @ 30 degrees, lower @ 30 degrees to core angle	
137.2	141.6	SANDSTONE TO CONGLOMERATE, extensively fractured, healed with pyrobitumen, large (>2cm) chunks of pyrobitumen usually along fractures	

Arg	argillic	Hm	red hematite
Sil	silicification	Ser	sericite
Py	pyrite	Car	carbonate
Mag	magnetics	Cpy	chalcopyrite
Bx	breccia	Ble	bleaching
Stw	stockwork		
QFP	qtz feldspar porphry		

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Km 410 Grid

DDH No. **CG-01-2009** Azimuth 078 Started on: 10/08/2009
Northing: 10049 Dip -50 Completed on: 13/08/2009
Westing: 21471 Core Size NTW Logged by: Sara P./Shane C.
Collar Elev. 812m Final Depth 186.6m

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
141.6	144.8	LAPILLI TUFF, grading denser at bottom upper contact @ 45 degrees to core angle with black carbonaceous clay hairline fractures throughout, black pyrobitumen common on larger fracture surfaces lower contact @ 75 degrees t.c.a., with 2cm of black pyrobitumen	Arg-3, Ble
144.8	148.2	SANDSTONE, with occasional gritty/coarser beds, highly fractured, coarse grained, siliceous, in places appears almost granitic in texture, long vertical fracture with pyrobitumen on surface	Sil-2-3
148.2	149.7	LAPILLI TUFF, same as above tuff unit	
149.7	152.3	SANDSTONE TO CONGLOMERATE, coarsening downward, bedding variably 20-40 degrees t.c.a, generally less clay altered and less fractured than previous seds, clay common on fracture surfaces @151.3m, 5cm of black pyrobitumen and clay in fractures at 15 degrees t.c.a 152.2m-152.3m pyrobitumen and clay in fracture	
152.3	152.7	LAPILLI TUFF	
152.7	153.5	COARSE SANDSTONE, with occasional large qtz clasts	
153.5	157.4	CONGLOMERATE, fresh, little to no clay alteration	
157.4	160.4	COARSE SANDSTONE, coarsening downward, several parallel t.c.a fractures with black carbonaceous clay	Arg-1-2
160.4	160.5	TUFF	
160.5	186.6	SANDSTONE TO CONGLOMERATE, variably fine to medium grained sandstone coarsens downward, occasionally very coarse and silicious grades into conglomerate fractures with clay infilling common **End of Hole**	Sil-4

Grew Creek Project

Recovery and RQD

Hole # CG-01-09R Page 1

core size NTW

RADIUS GOLD INC.

logged by: Spublicover

Date:

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
20.0	21.3	1.3	1.3	100	0.7	50
21.3	23.0	1.7	1.6	94	1.4	82
23.0	26.0	3.0	3.0	100	1.7	57
26.0	29.0	3.0	3.0	100	1.6	53
29.0	32.0	3.0	3.0	100	1.5	50
32.0	35.1	3.1	3.0	97	1.9	61
35.1	38.1	3.0	2.8	93	2.6	87
38.1	41.1	3.0	2.9	97	2.8	93
41.1	44.2	3.1	3.1	100	2.8	90
44.2	47.2	3.0	2.9	97	2.8	93
47.2	50.3	3.1	3.1	100	3.1	100
50.3	53.3	3.0	3.0	100	3.0	100
53.3	56.4	3.1	3.1	100	3.0	97
56.4	59.4	3.0	3.0	100	3.0	100
59.4	62.5	3.1	3.0	97	2.9	94
62.5	65.5	3.0	3.0	100	3.0	100
65.5	68.6	3.1	3.1	100	3.1	100
68.6	71.6	3.0	2.9	97	2.9	97
71.6	74.7	3.1	3.0	97	2.7	87
74.7	77.7	3.0	3.0	100	2.7	90
77.7	80.8	3.1	3.0	97	3.0	97
80.8	83.8	3.0	3.0	100	2.5	83
83.8	86.9	3.1	3.1	100	2.3	74
86.9	89.9	3.0	2.9	97	1.7	57
89.9	93.0	3.1	3.1	100	2.5	81
93.0	96.0	3.0	3.0	100	2.6	87
96.0	99.0	3.0	3.0	100	2.6	87
99.0	102.1	3.1	3.0	97	2.7	87
102.1	105.2	3.1	3.0	97	2.7	87
105.2	108.2	3.0	3.0	100	2.0	67
108.2	111.3	3.1	3.0	97	1.5	48
111.3	114.3	3.0	3.0	100	2.9	97
114.3	117.3	3.0	3.0	100	2.8	93
117.3	120.4	3.1	3.0	97	2.1	68
120.4	123.4	3.0	3.0	100	2.7	90
123.4	126.5	3.1	3.0	97	3.0	97
126.5	129.5	3.0	3.0	100	2.0	67
129.5	132.6	3.1	3.0	97	1.5	48
132.6	135.6	3.0	3.0	100	2.9	97
135.6	138.7	3.1	3.0	97	2.8	90

Grew Creek Project

Recovery and RQD

Hole # CG-01-09R Page 2

core size NTW

RADIUS GOLD INC.

logged by: Spublicover

Date:

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
138.7	141.7	3.0	3.0	100	0.8	27
141.7	144.8	3.1	3.0	97	2.5	81
144.8	147.8	3.0	3.0	100	1.4	47
147.8	150.9	3.1	3.1	100	2.3	74
150.9	153.9	3.0	3.0	100	2.7	90
153.9	157.0	3.1	3.1	100	2.9	94
157.0	160.0	3.0	3.0	100	2.7	90
160.0	161.5	1.5	1.5	100	0.7	47
161.5	164.6	3.1	3.1	100	2.6	84
164.6	167.6	3.0	3.0	100	2.7	90
167.6	170.7	3.1	3.0	97	2.6	84
170.7	173.7	3.0	3.0	100	2.9	97
173.7	176.8	3.1	3.1	100	2.7	87
176.8	179.8	3.0	3.0	100	2.8	93
179.8	182.9	3.1	3.1	100	3.0	97
182.9	185.9	3.0	3.0	100	2.7	90
185.9	186.6	0.7	0.7	100	0.5	71

Emerick Resources Ltd

Drill Core Sample Record

Type of sampling:	Selective	Hole-id:	CG-01-09R
		Date:	13-Aug-'09

Sample No.	Sample interval		
	From	To	Length (m)
25501	19.8	21.3	1.5
25502	21.3	22.8	1.5
25503	22.8	24.7	1.9
25504	24.7	24.9	0.2
25505	24.9	26.4	1.5
25506	26.4	27.4	1
25507	27.4	28.25	0.85
25508	28.25	29.8	1.55
25509	29.8	31.3	1.5
25510	31.3	32.8	1.5
25511	STD	GS-1D	
25512	32.8	34.3	1.5
25513	34.3	35.8	1.5
25514	35.8	37.2	1.4
25515	51	52.5	1.5
25516	52.5	54	1.5
25517	54	55.5	1.5
25518	BLANK		
25519	55.5	57	1.5
25520	57	58.5	1.5
25521	58.5	59.5	1
25522	59.5	61	1.5
25523	61	62.5	1.5
25524	STD	GS-1D	
25525	71.5	73	1.5
25526	73	74.5	1.5
25527	74.5	76	1.5
25528	76	77.5	1.5
25529	80.4	81.9	1.5
25530	86.9	88.4	1.5
25531	88.4	89.9	1.5
25532	89.9	91.4	1.5
25533	98.2	99.7	1.5
25534	99.7	101.2	1.5
25535	BLANK		
25536	113.9	115.4	1.5
25537	120	121.5	1.5
25538	121.5	123	1.5
25539	123	124.5	1.5
25540	124.5	126	1.5
25541	126	127.5	1.5
25542	127.5	128.5	1
25543	STD	GS-10C	
25544	128.5	129.5	1
25545	129.5	131	1.5
25546	137.3	138.8	1.5
25547	138.8	140.2	1.4
25548	140.2	141.6	1.4

Sample No.	Sample interval		
	From	To	Length (m)
25549	141.6	143.1	1.5
25550	143.1	144.8	1.7
25551	144.8	146.3	1.5
25552	160.5	162	1.5
25553	162	163.5	1.5
25554	STD	GS-1D	
25555	163.5	165	1.5
25556	177.3	178.8	1.5
25557	178.8	180.3	1.5
25558	BLANK		
25559	180.3	181.8	1.5
25560	181.8	183.3	1.5

25791	45.5	45.8	0.3

Arg	argillic	Hm	red hematite
Sil	silicification	Ser	sericite
Py	pyrite	Car	carbonate
Mag	magnetics		
Bx	breccia		
Stw	stockwork		
QFP	qtz feldspar porphry		

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Km 410 Grid

DDH No. **CG-02-2009** Azimuth 258 Started on: 14/08/2009
Northing: 10195 Dip -50 Completed on: 16/08/2009
Westing: 21329 Core Size NTW Logged by: Sara P./Shane C.
Collar Elev. 794m Final Depth 157m

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
0	9.1	OVERBURDEN	
9.1	13	CARBON, very black, carbon rich, soft, flaky, very consistent texture carbonaceous alteration	
13	21.3	ALTERED SEDIMENTS grey, seal fractured, dense/fine-grained, quartz/carbonate stockwork, pyrobitumen on fracture surfaces	Car-2, Stw
		16.8m-17.7m extensively brecciated	Bx
		18.3m-18.7m Conglomerate, moderate to strong black clay with sub-rounded clasts up to 3cm, qtz/car clasts with occassional green sericite tint	
21.3	24.5	Light greenish, crumbled, strong clay altered, patchy silicification, minor pyrite dark qtz eyes throughout, lower contact @30 degrees to core angle	Arg-4
		Apparently an extremely clay altered version of the underlying altered rhyolites? based predominantly on presence of qtz eyes and the greenish colour.	
24.5	36.4	SILICIFIED CAP?, light green/grey	Sil-5
		intense silicification (difficult to split, 'rings' when hit, sharp fragments when fractured), disseminated pyrite, qtz stockwork, occassional black carbon on fractures, The silicification destroys most of the original features that would help in the rock identification, though probably a highly altered rhyolite.	Py-1-3%
36.4	71.6	FELSIC QUARTZ BRECCIA, argillization, pyritization, sericitization, qtz breccia are the predominate features of this likely rhyolitic package	Arg-4, Ser-2, Bx Py-3%, Ble
		Generally qtz fragments set in green sericite+quartz flooding+pyrite+clay.	
		Light green/grey, softer rock, clay altered, more intense pyritization, qtz veining up to 1-2cm wide, veins are broken., light green sericite and bleaching	Stw
		38.5m-42m possibly a tuff, greyish, brecciated, qtz stockwork, lower contact @ 30 degrees to core angle, pyritization	Py-3%
		42m-71.6m increase in pyritization (disseminated and veinlets)	Py-5%
		@47.5m massive granular pyrite vein about 2cm wide	
		@53.3m still 1cm py bands and 1-2cm + 1/2cm qtz veins x-cut and parallel the core, soft, argillic, qtz breccia, core is 'sparkling' from the pyrite	Bx
		56.3m-57.6m begins more silicification for a short section, less argillic, more solid/less crumbly	Sil-4
		57.6m-66.4m back to more argillic alteration, patchy sections up to 5cm long of massive silicification	
71.6	71.8	CARBON, very black, carbon rich, soft, flaky, very consistent texture	
71.8	73	GREY TUFF, fine-grained, qtz/carbonate stockwork, several clay clasts	Car-2, Stw
73	73.8	CARBONACEOUS FAULT GOUGE, black, carbon + clay matrix with 2cm angular clasts of grey tuff, fragments have qtz/carbonate stockwork	Car-1, Stw

Arg	argillic	Hm	red hematite
Sil	silicification	Ser	sericite
Py	pyrite	Car	carbonate
Mag	magnetics		
Bx	breccia		
Stw	stockwork		
QFP	qtz feldspar porphry		

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Km 410 Grid

DDH No. **CG-02-2009** Azimuth 258 Started on: 14/08/2009
Northing: 10195 Dip -50 Completed on: 16/08/200
Westing: 21329 Core Size NTW Logged by: Sara P./Shane C.
Collar Elev. 794m Final Depth 157m

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
73.8	74.4	GREY TUFF	
74.4	74.5	CARBON, very black, carbon rich, soft, flaky, very consistent textured, carbonaceous alteration	
74.5	83.4	FELSIC QUARTZ BRECCIA, upper contact @ 40 degrees t.c.a. 74.5m-75.4m green, crushed, argillic + quartz breccia 75.4m-80m grey, argillic + quartz breccia 80m-83.4m intense silicification, trace pyrite, lower contact very broken	Bx Arg-4 Arg-3 Sil-5, Py-trace
83.4	99.3	COARSE GRAINED FELSIC BRECCIA, dark grey/green, silicified, highly fractured with white clay throughout the fractures and surrounding fragments flow textures throughout, disseminated cubic pyrite also, very course grained crystals throughout, quartz	Py-1-2% Bx
99.3	99.6	CARBONACEOUS FAULT BRECCIA, black, clay + carbon rich	Arg-4, Bx
99.6	103.1	grey/green, crushed argillic gouge with flow textures large qtz/carbonate clasts	Arg-4
103.1	124.9	CARBONACEOUS FAULT BRECCIA, dark brown/black, clay+carbon rich matrix with generally rounded clasts of felsic breccia, siltstones 117.3m-118.4m conglomerate, clean/relatively unaltered reddish qtz clasts, fines down to sandstone	Arg-4, Bx
124.9	157	SEDIMENTARY PACKAGE, still mainly carbonaceous fault breccia but with well defined sediment sections 124.9m-126.2m coarse sandstone with conglomerate beds black pulses throughout, white clay in sandy matrix 126.2m-126.7m siltstone weakly brecciated with moderate quartz stockwork black bitumen/coal @ upper contact 126.7m-128.4m coarse sandstone, qtz has been recrystallized 128.4m-157m occasional short sections (<30-40cm) of similar sandstone, siltstone and conglomerate occasional flow textures throughout clay, bitumen/carbon common **End of Hole**	 Arg-3 Stw, Bx Sil-3

Grew Creek Project

Recovery and RQD

Hole # CG-02-09 page: 1

core size:NTW

RADIUS GOLD INC

logged by: Spublicover

Date:Aug 13/09

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
0.0	9.1	9.1		0		0
9.1	12.2	3.1	2.1	68	0 3	10
12.2	15.2	3.0	2.6	87	1.0	33
15.2	18.3	3.1	3.1	100	1.1	35
18.3	21.3	3.0	3.0	100	1.5	50
21.3	24.4	3.1	2.5	81	0.3	10
24.4	25.9	1.5	1.5	100	0.2	13
25.9	29.0	3.1	3.1	100	0.0	0
29.0	32.0	3.0	3.0	100	0.9	30
32.0	35.1	3.1	3.1	100	0.3	10
35.1	38.1	3.0	3.0	100	1.7	57
38.1	41.1	3.0	2.7	90	2.1	70
41.1	44.2	3.1	3.1	100	2.5	81
44.2	47.2	3.0	3.4	113	2.3	77
47.2	50.3	3.1	1.7	55	0.6	19
50.3	53.3	3.0	2.7	90	2.0	67
53.3	56.4	3.1	3.0	97	2.5	81
56.4	59.4	3.0	2.9	97	2 1	70
59.4	62.5	3.1	2.6	84	2.0	65
62.5	65.5	3.0	3.0	100	1.9	63
65.5	68.6	3.1	3.0	97	2 7	87
68.6	71.6	3.0	2.9	97	2.9	97
71.6	74.7	3.1	3.1	100	2.8	90
74.7	77.7	3.0	3.0	100	2.9	97
77.7	80.8	3.1	3.0	97	2.0	65
80.8	83.8	3.0	3.0	100	0.4	13
83.8	86.9	3.1	2.7	87	2 1	68
86.9	89.9	3.0	2.9	97	1.1	37
89.9	93.0	3.1	3.1	100	0.0	0
93.0	96.0	3.0	3.0	100	0 4	13
96.0	99.1	3.1	3.0	97	2 7	87
99.1	102.1	3.0	3.0	100	2.8	93
102.1	105.2	3.1	2.9	94	2 6	84
105.2	108.2	3.0	3.0	100	2.3	77
108.2	113.3	5.1	3.0	59	2.9	57
113.3	114.3	1.0	1.0	100	1.0	100
114.3	117.3	3.0	2.9	97	2.6	87
117.3	120.4	3.1	3.0	97	2.4	77
120.4	123.4	3.0	3.0	100	2.5	83
123.4	126 5	3.1	3.1	100	2 7	87

Grew Creek Project

RADIUS GOLD INC.

Recovery and RQD

Hole # CG-02-09 page: 2 logged by: Spublicover

core size:NTW Date: Aug 15/09

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
126.5	128.0	1.5	1.3	87	1.0	67
128.0	131.1	3.1	3.1	100	2.8	90
131.1	134.1	3.0	3.0	100	2.7	90
134.1	137.2	3.1	3.0	97	2.6	84
137.2	140.2	3.0	3.0	100	3.0	100
140.2	143.3	3.1	2.8	90	1.6	52
143.3	144.8	1.5	1.5	100	0.0	0
144.8	147.8	3.0	2.1	70	0.8	27
147.8	150.9	3.1	3.0	97	2.7	87
150.9	153.9	3.0	3.0	100	2.7	90
153.9	157.0	3.1	3.1	100	2.8	90

Emerick Resources Ltd

Drill Core Sample Record

Type of sampling:	Selective	Hole-id:	CG-02-09
		Date:	15-Aug-'09

Sample No.	Sample interval			Sample No.	Sample interval		
	From	To	Length (m)		From	To	Length (m)
25561	9.1	10.6	1.5	25606	68.3	69.8	1.5
25562	10.6	13	2.4	25607	69.8	71.3	1.5
25563	13	14.5	1.5	25608	71.3	71.8	0.5
25564	14.5	16	1.5	25609	BLANK		
25565	16	17.5	1.5	25610	71.8	73.2	1.4
25566	17.5	18.3	0.8	25611	73.2	74	0.8
25567	18.3	18.7	0.4	25612	74	74.5	0.5
25568	18.7	20.2	1.5	25613	74.5	76	1.5
25569	20.2	21.7	1.5	25614	76	77.5	1.5
25570	STD	GS-1D		25615	77.5	79	1.5
25571	21.7	23.2	1.5	25616	79	80.5	1.5
25572	23.2	24.5	1.3	25617	80.5	82	1.5
25573	24.5	26	1.5	25618	82	83.5	1.5
25574	26	27.5	1.5	25619	83.5	85	1.5
25575	27.5	29	1.5	25620	85	86.5	1.5
25576	29	30.5	1.5	25621	86.5	88	1.5
25577	BLANK			25622	88	89.5	1.5
25578	30.5	32	1.5	25623	89.5	91	1.5
25579	32	33.5	1.5	25624	91	92.5	1.5
25580	33.5	35	1.5	25625	92.5	94	1.5
25581	35	36.5	1.5	25626	94	95.5	1.5
25582	36.5	38	1.5	25627	STD	GS-1D	
25583	38	38.5	0.5	25628	95.5	97	1.5
25584	38.5	40.2	1.7	25629	97	98.5	1.5
25585	40.2	41.7	1.5	25630	98.5	99.2	0.7
25586	41.7	43.2	1.5	25631	99.2	99.6	0.4
25587	STD	GS-10C		25632	BLANK		
25588	43.2	44.7	1.5	25633	99.6	101.1	1.5
25589	BLANK			25634	101.1	103.2	2.1
25590	44.7	46.2	1.5	25635	103.2	104.7	1.5
25591	46.2	47.7	1.5	25636	104.7	106.2	1.5
25592	47.7	50.3	2.6	25637	106.2	107.7	1.5
25593	50.3	51.8	1.5	25638	107.7	109.2	1.5
25594	51.8	53.3	1.5	25639	109.2	110.7	1.5
25595	53.3	54.8	1.5	25640	110.7	112.2	1.5
25596	54.8	56.3	1.5	25641	112.2	113.7	1.5
25597	56.3	57.8	1.5	25642	138.1	139.6	1.5
25598	57.8	59.3	1.5	25643	139.6	141.1	1.5
25599	59.3	60.8	1.5	25644	141.1	142.6	1.5
25600	60.8	62.3	1.5	25645	142.6	144.1	1.5
25601	62.3	63.8	1.5	25646	144.1	145.6	1.5
25602	63.8	65.3	1.5	25647	145.6	147.1	1.5
25603	65.3	66.8	1.5	25648	147.1	148.6	1.5
25604	66.8	68.3	1.5	25649	148.6	150.1	1.5
25605	STD	GS-10C		25650	150.1	151.6	1.5

Arg	argillic	Hm	red hematite
Sil	silicification	Ser	sericite
Py	pyrite	Ble	bleaching
Mag	magnetics		
Bx	breccia		
Stw	stockwork		
QFP	qtz feldspar porphry		

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Km 410 Grid

DDH No. **CG-03-2009** Azimuth 215 Started on: 16/08/2009
Northing: 10165 Dip -60 Completed on: 17/08/2009
Westing: 22400 Core Size NTW Logged by: S.P/S.C.
Collar Elev. 775m Final Depth 181.4m

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
0	1.5	OVERBURBEN	
1.5	30.5	CARBONACEOUS FAULT BRECCIA, black, clay rich, carbon rich frequently interbedded with conglomerate and sandstone	Bx, Arg-3
30.5	30.7	COAL, seam, or pyrobitumen associated with the fault generated, prevalent carbon and clay alteration	
30.7	73.2	FAULT BRECCIATED SILTSTONE, brown to black, shiny black on fractures @38m, 50cm white clay seam @42.3m, 50cm light grey clay seam @46.4m, 30cm highly fractured 48.8m-49.1m bedding at 30 degrees to core angle 63.3m-67.1m fracture zone, no pieces >5cm, shiny, polished looking surfaces @73.2m fracture zone, clay gouge, black carbon	Bx Arg-4
73.2	84.6	BRECCIATED SILTSTONE + CARBONACEOUS FAULT BRECCIA, mixed zone of these units, highly fractured throughout, lots of bituminous/coal material	Bx
84.6	105.7	CARBONACEOUS FAULT BRECCIA, SANDSTONE, CONGLOMERATE, mixed zone of the black sticky clay and carbon with areas of sandstone and conglomerate that have been less affected by this pervasive black clay and carbon alteration 95.2m-95.9m carbonate cataclasite, sheared, reddish and black bands	Bx Mag-3
105.7	106.2	BASALT DYKE, medium grey (bleached) with slight green tint, qtz/carbonate veins, dark qtz eyes, somewhat chloritic, both contacts very broken/brecciated	Ser-2, Ble-2 Stw-4, Bx
106.2	107.4	CARBONACEOUS FAULT BRECCIA, black, clay and carbon matrix	
107.4	114.85	BASALT DYKE, same as above	Ser-2, Ble-2 Stw-2
114.85	161.4	CARBONACEOUS FAULT BRECCIA, occasional sandy/conglomerate sections @141.5, 10cm weak red hematite	
161.4	162.7	light grey/green, locally red hematized, generally bleached, very granular large brecciated quartz fragments (possibly broken veining?)	Ser-2, Ble-3 Arg-3
162.7	181.4	CARBONACEOUS FAULT BRECCIA, black sticky clay and carbon rich, pulls out of the core box as long (several feet) flexible pieces, can split with a spatula @164.5m, 20cm brick red tint, qtz veining, occasional black pulses	Bx Hm-3

Arg	argillic	Hm	red hematite
Sil	silicification	Ser	sericite
Py	pyrite	Ble	bleaching
Mag	magnetics		
Bx	breccia		
Stw	stockwork		
QFP	qtz feldspar porphry		

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Km 410 Grid

DDH No. **CG-03-2009** Azimuth 215 Started on: 16/08/2009
Northing: 10165 Dip -60 Completed on: 17/08/2
Westing: 22400 Core Size NTW Logged by: S.P/S.C.
Collar Elev. 775m Final Depth 181.4m

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
		@164.9m, 5cm of brick red tint, qtz veining	Hm-2
		171.8m-172.1m light-grey, bleached and brecciated qtz veining	Ble-5, Arg-4
		@175.3m, 30cm of completely silicious yellow/green sericite tinted rock	Sil-5
		qtz stockwork within silicious piece	Ser-3, Stw
		lower contact @ 30 degrees to core angle	
		End of Hole	

Grew Creek Project

Recovery and RQD

Hole # CG-03-09 page: 1

core size:NTW

RADIUS GOLD INC

logged by: Spublicover

Date:Aug 16/09

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
1.5	6.1	4.6	3.7	80	0.0	0
6.1	9.1	3.0	3.0	100	1.5	50
9.1	10.7	1.6	1.4	88	1.3	81
10.7	13.7	3.0	3.0	100	3.0	100
13.7	16.8	3.1	3.1	100	2.9	94
16.8	19.8	3.0	2.9	97	2.0	67
19.8	22.9	3.1	3.1	100	2.8	90
22.9	24.4	1.5	1.5	100	1.5	100
24.4	27.4	3.0	3.0	100	3.0	100
27.4	33.5	6.1	6.1	100	5.7	93
33.5	36.6	3.1	2.8	90	2.5	81
36.6	39.6	3.0	3.0	100	3.0	100
39.6	42.7	3.1	3.1	100	3.1	100
42.7	45.7	3.0	3.0	100	2.5	83
45.7	48.8	3.1	3.1	100	2.8	90
48.8	51.8	3.0	3.0	100	2.6	87
51.8	54.9	3.1	3.1	100	2.7	87
54.9	57.9	3.0	2.9	97	2.7	90
57.9	61.0	3.1	3.0	97	2.4	77
61.0	64.0	3.0	3.0	100	2.8	93
64.0	67.1	3.1	3.0	97	0.9	29
67.1	70.1	3.0	3.0	100	2.9	97
70.1	73.2	3.1	2.7	87	2.0	65
73.2	76.2	3.0	3.0	100	0.0	0
76.2	77.7	1.5	1.6	107	1.4	93
77.7	80.8	3.1	3.1	100	1.6	52
80.8	83.8	3.0	3.0	100	0.8	27
83.8	86.9	3.1	3.1	100	1.6	52
86.9	89.9	3.0	2.9	97	1.3	43
89.9	93.0	3.1	3.1	100	2.7	87
93.0	96.0	3.0	2.7	90	2.7	90
96.0	99.1	3.1	3.1	100	3.1	100
99.1	102.1	3.0	2.8	93	2.5	83
102.1	105.2	3.1	3.1	100	2.9	94
105.2	106.7	1.5	1.5	100	1.4	93
106.7	109.7	3.0	3.0	100	2.4	80
109.7	112.8	3.1	3.1	100	3.0	97
112.8	115.8	3.0	3.0	100	2.4	80
115.8	118.9	3.1	3.1	100	3.0	97
118.9	121.9	3.0	3.0	100	2.0	67

Grew Creek Project

Recovery and RQD

Hole # CG-03-09 page: 2

core size:NTW

RADIUS GOLD INC.

logged by: Spublicover

Date: Aug 17/09

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
121.9	125.0	3.1	3.1	100	2.8	90
125.0	128.0	3.0	3.0	100	2.6	87
128.0	129.5	1.5	1.5	100	1.7	113
129.5	132.6	3.1	3.1	100	2.8	90
132.6	135.6	3.0	3.0	100	2.8	93
135.6	138.7	3.1	3.1	100	2.9	94
138.7	141.7	3.0	3.0	100	3.1	103
141.7	144.8	3.1	3.1	100	3.0	97
144.8	147.8	3.0	3.0	100	3.0	100
147.8	150.9	3.1	3.1	100	2.8	90
150.9	153.9	3.0	3.0	100	2.7	90
153.9	157.0	3.1	3.0	97	3.0	97
157.0	160.0	3.0	3.0	100	2.8	93
160.0	163.1	3.1	3.1	100	3.0	97
163.1	166.1	3.0	3.0	100	3.0	100
166.1	169.2	3.1	2.9	94	2.8	90
169.2	172.2	3.0	3.0	100	2.7	90
172.2	175.3	3.1	3.1	100	3.0	97
175.3	178.3	3.0	3.0	100	3.1	103
178.3	181.4	3.1	3.1	100	3.1	100

Emerick Resources Ltd

Drill Core Sample Record

Type of sampling:	Selective	Hole-id:	CG-03-09
		Date:	16-Aug-'09

Sample No.	Sample interval		
	From	To	Length (m)
25651	24	25.5	1.5
25652	STD	GS-1D	
25653	25.5	27	1.5
25654	27	28.5	1.5
25655	28.5	30	1.5
25656	30	30.7	0.7
25657	30.7	32.2	1.5
25658	32.2	33.7	1.5
25659	BLANK		
25660	42.3	42.9	0.6
25661	42.9	44.4	1.5
25662	44.4	45.9	1.5
25663	45.9	47.4	1.5
25664	STD	GS-10C	
25665	47.4	48.9	1.5
25666	64	65.5	1.5
25667	65.5	67	1.5
25668	67	68.5	1.5
25669	70.1	71.1	1
25670	71.1	71.6	0.5
25671	71.6	73.1	1.5
25672	73.1	74.6	1.5
25673	74.6	76.1	1.5
25674	BLANK		
25675	76.1	77.6	1.5
25676	77.6	79.1	1.5
25677	79.1	80.6	1.5
25678	80.6	82.1	1.5
25679	82.1	83.6	1.5
25680	83.6	85.1	1.5
25681	104.2	105.7	1.5
25682	105.7	106.2	0.5
25683	106.2	107.4	1.2
25684	107.4	108.9	1.5
25685	BLANK		
25686	108.9	110.4	1.5
25687	110.4	111.9	1.5
25688	111.9	113.4	1.5
25689	113.4	114.85	1.45
25690	114.85	116.4	1.55
25691	STD	GS-1D	
25692	116.4	117.9	1.5
25693	148	149.5	1.5
25694	149.5	151	1.5
25695	151	152.5	1.5
25696	152.5	154	1.5
25697	154	155.5	1.5
25698	155.5	157	1.5
25699	157	158.5	1.5
25700	158.5	160.3	1.8
25701	160.3	160.6	0.3
25702	160.6	161.4	0.8
25703	161.4	162.7	1.3
25704	162.7	164.2	1.5
25705	164.2	165.7	1.5
25706	165.7	167.2	1.5
25707	167.2	168.7	1.5
25708	168.7	170.2	1.5
25709	STD	GS-1D	
25710	170.2	171.7	1.5
25711	171.7	173.2	1.5
25712	173.2	174.7	1.5
25713	174.7	175.3	0.6
25714	175.3	175.6	0.3
25715	175.6	177.1	1.5
25716	177.1	178.6	1.5
25717	178.6	180.1	1.5
25718	180.1	181.1	1
25719	BLANK		
25720	95.2	95.9	0.7
25790	2	3.5	1.5

Arg	argillic	Hm	red hematite
Sil	silicification	Ser	sericite
Py	pyrite	Ble	bleaching
Mag	magnetics	Chl	chlorite
Bx	breccia		
Stw	stockwork		
QFP	qtz feldspar porphry		

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Km 410 Grid

DDH No. **CG-04-2009** Azimuth 035 Started on: 19/08/2009
Northing: 9975 Dip -60 Completed on: 22/08/2009
Westing: 22400 Core Size NTW Logged by:Sara P./Shane C.
Collar Elev. 775m Final Depth 207.3m Page 1 of 1

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
0	8.4	OVERBURDEN, Glacial till: sand, pebbles, boulders	
8.4	12.4	4m or so of a clay, pebble conglomerate	
12.4	43.2	META-SILTSTONE, medium to dark grey, upper contact @ 80 degrees t,c.a.,	Chl-3, Stw-3
		moderate brecciation with fine qtz stockwork, S1 @ 65-70 degrees t.c.a.	Bx
		12.4m-24m four along hole fractures, often with white clay infilling,	Py-1%, Sil-4
		disseminated cubic pyrite and abundant py on fractures, highly silicified	
		25.5m-27.4m highly fractured, intense argillic, up to 10cm sections bleached,	Arg-3, Ble-4
		pyritic, silicified	
		28.4m-31.8m highly fractured, patches of 10cm intense white clay	Arg-3
		Don't see as much py on fractures.	
		31.8m-40m silicified, thin (<1/2cm) qtz veins abundant, tiny (1mm wide) elongate	Sil-3, Veining
		cavities, occasional clay crushed zone 15cm wide	
		40m-40.9m carbonaceous, clay-rich and very black	Arg-3
		@42.7m brick red hematite fractures	Hm-1
43.2	55.5	META-SILTSTONE, increasingly siliceous, light green sericite tint in places,	Sil-4, Py-1%
		brecciated with fine qtz stockwork, highly fractured, pyrite common on fracture	Ser-2, Stw-3
		surfaces (generally small cubic crystals)	
		48m-48.8m bleached zone, clay altered	Arg-4, Ble-4
55.5	67	META-SILTSTONE, darker grey in colour, strongly fractured, clay common on	
		fracture surfaces	
67	88.5	MEDIUM GREY META-SILTSTONE, similar to 12.4m-43.2m	
		75m-77m moderate bleaching	Ble-3
		77m-88.5m increasingly dark grey, quartz stockwork more intense than	Stw, Bx
		previous section, pyrite often follows qtz as stringers and disseminated	Py-3%
88.5	170	CARBONACEOUS FAULT BRECCIA, extremely black, clay-rich with few clasts,	
		upper contact is ground but appears to be @ 90 degrees t.c.a.	
		lower contact has 50cm of very dark siltstone with up to 5% pyrite	Py-5%
		114.7m-115.3m bleached	Ble
		117m-117.6m bleached	Ble
		149m-149.1m calcitic brecciated clasts	
		@185.7m 20cm of blue green clay, bleached at either end	
170	207.3	CARBONACEOUS FAULT BRECCIA, siltier and lighter-brown colour,	
		occasional coal seam	
		Apparently grading into the Tertiary graben sediments.	
		198.4m-199m sandier section	
		End of Hole	

Grew Creek Project

Recovery and RQD

Hole # CG-04-09 page: 1

core size:NTW

RADIUS GOLD INC.

logged by: Spublicover

Date:Aug 20/09

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
3.0	6.1	3.1	2.0	65	0.0	0
6.1	9.1	3.0	2.0	67	0.0	0
9.1	12.2	3.1	2.6	84	0.6	23
12.2	15.2	3.0	3.0	100	1.2	40
15.2	18.3	3.1	3.1	100	1.3	42
18.3	21.3	3.0	3.0	100	1.8	60
21.3	24.4	3.1	3.0	97	2.6	87
24.4	27.4	3.0	3.0	100	0.3	10
27.4	29.0	1.6	1.4	88	0.3	21
29.0	32.0	3.0	3.0	100	0.5	17
32.0	35.1	3.1	3.1	100	1.5	48
35.1	38.1	3.0	3.0	100	1.2	40
38.1	41.1	3.0	3.0	100	0.7	23
41.1	44.2	3.1	3.0	97	0.4	13
44.2	47.2	3.0	3.0	100	1.3	43
47.2	50.3	3.1	3.1	100	1.2	39
50.3	53.3	3.0	2.8	93	1.2	43
53.3	56.4	3.1	3.1	100	2.0	65
56.4	59.4	3.0	3.0	100	0.8	27
59.4	62.5	3.1	2.8	90	0.5	18
62.5	64.0	1.5	1.5	100	0.9	60
64.0	65.5	1.5	1.5	100	0.1	7
65.5	68.6	3.1	3.0	97	1.8	60
68.6	71.6	3.0	3.0	100	2.7	90
71.6	74.7	3.1	3.1	100	2.9	94
74.7	77.7	3.0	3.0	100	0.7	23
77.7	80.8	3.1	3.1	100	1.7	55
80.8	83.8	3.0	3.0	100	2.1	70
83.8	86.9	3.1	2.9	94	0.2	7
86.9	88.4	1.5	1.5	100	1.2	80
88.4	91.4	3.0	3.0	100	2.8	93
91.4	94.5	3.1	3.1	100	3.0	97
94.5	97.5	3.0	3.0	100	3.0	100
97.5	100.6	3.1	3.0	97	2.6	87
100.6	103.6	3.0	3.0	100	2.9	97
103.6	106.7	3.1	3.1	100	3.1	100
106.7	109.7	3.0	3.0	100	3.0	100
109.7	112.8	3.1	3.1	100	2.9	94
112.8	115.8	3.0	3.0	100	2.9	97
115.8	118.9	3.1	3.1	100	3.1	100

Grew Creek Project

Recovery and RQD

Hole # CG-04-09 page: 2

core size:NTW

RADIUS

logged by: Spublicover

Date: Aug 21/09

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
118.9	121.9	3.0	3.0	100	3.0	100
121.9	125.0	3.1	3.1	100	3.1	100
125.0	128.0	3.0	3.0	100	2.8	93
128.0	131.1	3.1	3.1	100	3.1	100
131.1	134.1	3.0	3.0	100	2.9	97
134.1	137.2	3.1	3.1	100	3.0	97
137.2	140.2	3.0	3.0	100	3.0	100
140.2	143.3	3.1	3.1	100	3.1	100
143.3	146.3	3.0	3.0	100	3.0	100
146.3	147.8	1.5	1.5	100	1.5	100
147.8	150.9	3.1	3.1	100	3.0	97
150.9	153.9	3.0	3.0	100	2.9	97
153.9	157.0	3.1	3.1	100	3.1	100
157.0	160.0	3.0	3.0	100	3.0	100
160.0	163.1	3.1	3.1	100	3.1	100
163.1	166.1	3.0	3.0	100	3.0	100
166.1	169.2	3.1	3.1	100	3.0	97
169.2	172.2	3.0	3.0	100	3.0	100
172.2	175.3	3.1	3.1	100	2.9	94
175.3	178.3	3.0	3.0	100	3.0	100
178.3	181.4	3.1	3.1	100	3.0	97
181.4	184.5	3.1	3.1	100	3.0	97
184.5	185.9	1.4	1.4	100	1.6	114
185.9	189.0	3.1	3.1	100	2.7	87
189.0	192.0	3.0	3.0	100	3.0	100
192.0	195.1	3.1	3.1	100	3.1	100
195.1	198.1	3.0	3.0	100	2.9	97
198.1	201.2	3.1	3.1	100	2.8	90
201.2	204.2	3.0	3.0	100	2.4	80
204.2	207.3	3.1	3.1	100	3.0	97

Emerick Resources Ltd

Drill Core Sample Record

Type of sampling:	Selective	Hole-id:	CG-04-09
		Date:	20-Aug-'09

Sample No.	Sample interval		
	From	To	Length (m)
25721	12.4	13.9	1.5
25722	13.9	15.4	1.5
25723	15.4	16.9	1.5
25724	16.9	18.4	1.5
25725	18.4	19.9	1.5
25726	19.9	21.4	1.5
25727	21.4	22.9	1.5
25728	STD	GS-1D	
25729	22.9	24.4	1.5
25730	24.4	25.9	1.5
25731	25.9	27.4	1.5
25732	27.4	28.9	1.5
25733	28.9	30.4	1.5
25734	30.4	31.9	1.5
25735	31.9	33.4	1.5
25736	33.4	34.9	1.5
25737	BLANK		
25738	34.9	36.4	1.5
25739	36.4	37.9	1.5
25740	37.9	39.4	1.5
25741	39.4	40.9	1.5
25742	40.9	42.4	1.5
25743	42.4	43.9	1.5
25744	43.9	45.4	1.5
25745	45.4	46.9	1.5
25746	46.9	48.4	1.5
25747	48.4	49.9	1.5
25748	49.9	51.4	1.5
25749	57.5	59	1.5
25750	BLANK		
25751	59	60.5	1.5
25752	60.5	62	1.5
25753	STD	GS-1D	
25754	62	63.5	1.5
25755	63.5	65	1.5
25756	65	66.5	1.5
25757	66.5	68	1.5
25758	68	69.5	1.5
25759	69.5	71	1.5
25760	71	72.5	1.5
25761	72.5	74	1.5
25762	74	75.5	1.5
25763	75.5	77	1.5
25764	77	78.5	1.5
25765	78.5	80	1.5
25766	80	81.5	1.5
25767	STD	GS-10C	
25768	81.5	83	1.5
25769	83	84.5	1.5
25770	84.5	86	1.5
25771	86	87.5	1.5
25772	87.5	88.5	1
25773	88.5	90	1.5
25774	90	91.5	1.5
25775	93.3	94.8	1.5
25776	97.3	98.8	1.5
25777	114.6	116.1	1.5
25778	123.3	124.8	1.5
25779	132.2	133.7	1.5
25780	BLANK		
25781	141	142.5	1.5
25782	149.6	151.1	1.5
25783	158.3	159.8	1.5
25784	167	168.5	1.5
25785	171.4	172.9	1.5
25786	179.9	181.4	1.5
25787	188.8	190.3	1.5
25788	197.3	198.8	1.5
25789	STD	GS-1D	

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Maverick Grid

DDH No. **CG-05-2009** Azimuth 225 Started on: 23/08/2009
Northing: 10260 Dip -50 Completed on: 23/08/2009
Westing: 9700 Core Size BTW Logged by:SaraP./Shane C.
Collar Elev. 780m Final Depth 35m Page 1 of 1

Footage		Description	Notables-
From (m)	To (m)		Intensity (1-5)
0	35	Overburden and several clay-rich unconsolidated horizons several meters thick. CG-05-09 was abandoned after 35m of very troublesome overburden and overpressured fluids. The drill hole became too costly and dangerous to continue. Before giving up we tried reducing to BQ and triconing. A lack of bentonite from the start compounded the problem of the sandy and pressurized ground. While pulling the rods, high pressure from methane(?) gas shot rocks and debris 10ft out of the hole for about a ten minute duration. Methane was positively identified (by burning) in a previous hole in the area.	

Arg argillic
Sil silicification
Py pyrite
Mag magnetics
Bx breccia
Stw stockwork
QFP qtz feldspar porphry

Hm red hematite
Ser sericite

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Maverick Grid

DDH No. **CG-06-2009** Azimuth 050 Started on: 25/08/2009
Northing: 9740 Dip -50 Completed on: 30/08/2009
Easting: 11030 Core Size BTW Logged by: Sara Publicove
Collar Elev. 820m Final Depth 188.6m Page 1 of 1

Footage		Description	Notables-
From (m)	To (m)		Intensity (1-5)
0	94.5	OVERBURDEN, extremely sandy till, mix of sand, rounded pebbles and greyish clay sections, reduced to BQ at 42.7m @94.5m pyrite encrusted pebbles and coarse sand, some 3cm pieces are sand to pebbles lithified together by the fine pyrite pebbles are black, cherty and grey indistinct lithics, well to subrounded	Py-trace
94.5	106.7	SILTSTONE, coarsens downward to sandy conglomerate by 101.0m several intermediate to vertical fractures, white clay on fracture surfaces weakly brecciated 103.2m healed vertical fracture with bitumen on surface 105.7m-106.7m very dark siltstone coarsens down to coarse, light colored sandstone, several healed fractures/weak brecciation	Arg-2-3 Bx-1
106.7	127.9	SILTSTONE, with occasional sandier sections, weakly brecciated sandier sections generally more clay altered	Arg-2
127.9	139.9	CONGLOMERATE, clast supported and aligned in one direction, with occasional sandy to silty sections 139.1m-140m moderately silicified conglomerate, some qtz flooding and veining with minor vug upper contact @25 degrees t.c.a., with 1cm brownish/grey silicified siltstone	Arg-3 Qtz flooding
139	146.6	SILTSTONE, coarsens down section	Arg-2, Bx-2
146.6	152.4	CONGLOMERATE	Arg-4
152.4	168	SILTSTONE, dark-grey, bottom 1m coarsens to sandstone	Arg-2
168	172.5	COARSE SANDSTONE TO CONGLOMERATE, grades into conglomerate, high biotite content, relatively fresh/unaltered	
172.5	180.5	SILTSTONE TO CONGLOMERATE, grades downhole into sandstone then to conglomerate, weak clay alteration in places	Arg-1-2
180.5	188.5	SILTSTONE TO CONGLOMERATE, grades into sandstone, then to conglomerate, bedding @ 45 degrees t.c.a., occasional clay clasts in conglomerate **End of Hole**	

Grew Creek Project

Recovery and RQD

Hole # CG-06-09

core size:B

page: 1

RADIUS GOLD INC.

logged by: Spublicover

Date:Aug 30/09

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
0.0	94.5	94.5			0.0	
94.5	97.5	3.0	2.8	93	0.2	7
97.5	99.1	1.6	1.4	88	0.2	13
99.1	102.1	3.0	2.6	87	0.6	20
102.1	105.2	3.1	3.0	97	1.5	48
105.2	106.7	1.5	1.5	100	0.9	60
106.7	109.7	3.0	3.0	100	0.3	10
109.7	112.8	3.1	3.1	100	2.2	71
112.8	115.8	3.0	2.7	90	1.8	60
115.8	118.9	3.1	3.1	100	2.9	94
118.9	121.9	3.0	2.8	93	2.4	80
121.9	125.0	3.1	3.1	100	0.7	23
125.0	128.0	3.0	3.0	100	0.9	30
128.0	131.1	3.1	3.0	97	2.4	77
131.1	132.6	1.5	1.5	100	1.1	73
132.6	135.6	3.0	3.0	100	2.8	93
135.6	138.7	3.1	3.1	100	1.6	52
138.7	141.7	3.0	3.0	100	2.0	67
141.7	144.8	3.1	3.1	100	0.5	16
144.8	147.8	3.0	3.0	100	1.2	40
147.8	150.9	3.1	3.1	100	2.6	84
150.9	152.4	1.5	0.4	27	0.0	0
152.4	153.9	1.5	1.5	100	0.4	27
153.9	155.4	1.5	1.5	100	1.3	87
155.4	158.5	3.1	3.1	100	0.9	29
158.5	161.5	3.0	3.0	100	1.2	40
161.5	164.6	3.1	3.1	100	2.7	87
164.6	167.6	3.0	2.9	97	0.3	10
167.6	170.7	3.1	2.5	81	0.3	10
170.7	173.7	3.0	3.0	100	1.8	60
173.7	175.3	1.6	1.5	94	0.4	25
175.3	178.3	3.0	3.0	100	1.6	53
178.3	181.4	3.1	3.1	100	2.4	77
181.4	184.4	3.0	3.0	100	2.6	87
184.4	187.5	3.1	2.7	87	1.9	61
187.5	188.6	1.1	1.1	100	1.5	136



Emerick Resources Ltd					
Drill Core Sample Record					
Type of sampling:		Selective		Hole-id:	CG-06-09
				Date:	30-Aug-'09

Sample No.	Sample interval		
	From	To	Length (m)
25792	94.50	96.00	1.5
25793	96.00	97.50	1.5
25794	99.00	100.50	1.5
25795	100.50	102.00	1.5
25796	102.00	103.50	1.5
25797	114.00	115.50	1.5
25798	118.40	119.90	1.6
25799	128.00	129.50	1.5
25800	129.50	131.00	1.5
25801	131.70	133.20	1.5
25802	135.60	137.10	1.5
25803	137.10	138.20	1.1
25804	138.20	139.10	0.9
25805	139.10	140.00	0.9
25806	140.00	141.50	1.5
25807	146.50	148.00	1.5
25808	STD	GS-1D	
25809	148.00	149.50	1.5
25810	149.50	151.00	1.5
25811	155.40	156.90	1.5
25812	168.00	169.50	1.5
25813	BLANK		
25814	169.50	171.00	1.5
25815	171.00	172.50	1.5
25816	184.80	186.30	1.5
25817	186.30	187.80	1.5

Arg argillic
Sil silicification
Py pyrite
Mag magnetics
Bx breccia
Stw stockwork
QFP qtz feldspar porphry

Hm red hematite
Ser sericite

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Maverick Grid

DDH No. **CG-07-2009** Azimuth 225 Started on: 31/08/2009
Northing: 9942 Dip -70 Completed on: 07/09/2009
Easting: 11030 Core Size BTW Logged by:S.P./S.C.
Collar Elev. 820m Final Depth 199.6m

Footage		Description	Notables-
From (m)	To (m)		Intensity (1-5)
0	79.6	OVERBURBEN sand, pebbles, boulders	
79.6	83.6	SANDSTONES/SILTSTONES/CONGLOMERATE-Breccia, alternating layers, Box 6 was dumped in truck crash	
83.6	108.3	DARK-GREY SILTSTONE, interbedded with lighter, greyish-brown sandstone, highly fractured throughout, occasionally silty sections are wkly brecciated (healed fractured), white/light grey clay on several fractures, greasy black fractures common in siltstone, high white mica content, bedding commonly At ~30 degrees t.c.a., occasional fine py	Arg-3
108.3	113	CONGLOMERATE-Breccia, strongly clay altered crumbles clastic sand supported with white mica content 20% of clasts are subangular, <2cm, black and white banded qtz with disseminated sulfides, some oblong irregular clasts mostly at 3cm by ½ cm which are volcanics and seds 15% is about 1cm clear qtz pebbles + 15% finer sand (fines may be finer portion of the banded sulfide qtz clasts) @108.9m 3cm of soft, greasy, light-green mineral associated with black 0.5mm disseminated mineral (or bitumen?) lower contact with siltstone is sharp at ~75 degrees t.c.a.	Arg-4 Py-1%
113	116.8	SILTSTONE to SANDSTONE, grey, abundant white mica in the sandstone sediment load structures: very fine black silt 'flaming' up into sand layers, features are about 2cm wide and thin	
116.8	125	SANDY CONGLOMERATE, coarsening + fining in sections with clasts ranging from a few mm to 3cm 120.4m-121.3m coarse sst mod-strong arg alt, dark-grey, bedding at 75 deg tca 124.7m-125m very coarse, 50% 2cm black/white banded qtz clasts, subangular @125m 2cm of green soapy mineral, chrysocolla? Serpentine?	Arg-3
125	137.6	SILTSTONES + SANDSTONES, very fine-grained sandstones, medium to Dark-grey in colour, highly brecciated and fractured	Arg-3
137.6	142.7	VOLCANICLASTIC BRECCIA, clasts include: large 7cm by 3cm hydrothermal breccia clasts, subrounded and mosaic texture, other clasts from 4cm to 2cm include, arcuate volcanic lithic shards, rounded green qtz with fine granular sulfides, flat/elongate pumice and crystal-rich wispy shaped non-flattened pumice, mostly at 2cm or less is the same subangular black/white banded qtz clasts as seen in the other conglomerates Fine-grained matrix: pumiceous, crystal shards, other black/white fines reworking has occurred, epiclastic?	Bx

Arg argillic
Sil silicification
Py pyrite
Mag magnetics
Bx breccia
Stw stockwork
QFP qtz feldspar porphry

Hm red hematite
Ser sericite

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Maverick Grid

DDH No. **CG-07-2009** Azimuth 225 Started on: 31/08/2009
Northing: 9942 Dip -70 Completed on: 07/09/2
Easting: 11030 Core Size BTW Logged by: S.P/S.C.
Collar Elev. 820m Final Depth 199.6m

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
		139.1m-139.5m grey siltstone	
142.7	146.9	CONGLOMERATE, an initial 20cm of clay altered siltstone, then coarse sandy subangular conglomerate with sandstone sections 20% larger 2cm clasts, 80% matrix and clay about half the clasts are banded black/white qtz, and half are green qtz with fine foliations, brown clasts matrix <3mm clasts of equal amounts of black qtz lithics and clear qtz, so if large clasts and matrix are same material then 80% rock has same origin	Arg-3
146.9	149.8	CONGLOMERATE, clay altered, crumbly, sandy, same black/white clasts and fines as previously noted @146.9m 20cm of argillic shear/crushed rock	Arg-4 Bx
149.8	150.5	SILTSTONE, grey, muddy, fractured	
150.5	154.8	SANDY CONGLOMERATE, clay altered, crumbly/granular, same black/white appearance and composition as noted	
154.8	156	SILTSTONE, grey, clay altered, brecciated	Bx
156	159.3	CONGLOMERATE, clay altered, some 20cm sections more competent, harder, less altered	
159.3	166	FINE SANDSTONE, strongly lithified, grey/brown, mica rich 40% @160m 20cm of siltstone with flaky, brown/white, soapy bands, seems to be shears @164.7m 20cm strong grey clay alteration of a silt band	 Arg-4
166	170.5	SILTSTONES/SANDSTONES, alternating layers, some of the siltstones are brecciated/sheared @169m 15cm of siltsone with minor qtz veining, 1mm wide, 6 veins	
170.5	175.2	FINE SANDSTONE, grey/brown, mica rich 20%	
175.2	178.4	CONLOMERATE TO SANDSTONE, grading from the conglomerate to a coarse sandstone to fine sandstone	
178.4	180.2	SILTSTONE, grey	
180.2	190.3	FINE SANDSTONE, strongly lithified in 40cm sections, short 20cm sections of very coarse sandstone 180.2m-182.2m about 40% white mica	

Arg argillic
Sil silicification
Py pyrite
Mag magnetics
Bx breccia
Stw stockwork
QFP qtz feldspar porphry

Hm red hematite
Ser sericite

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Maverick Grid

DDH No. **CG-07-2009** Azimuth 225 Started on: 31/08/2009
Northing: 9942 Dip -70 Completed on: 07/09/2009
Easting: 11030 Core Size BTW Logged by: S.P/S.C.
Collar Elev. 820m Final Depth 199.6m

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
190.3	191	TUFF, white/grey, fine crystal and shard-rich, banded qtz veining <1.5cm 190.1m-190.3m pyrite disseminations and 1mm py bands in the overlying sandstone 2% py. 15-20 degrees to core angle at bottom of section bottom 3mm of tuff is darker/purplish	Arg-4 Py-2%
191	192.6	SILTSTONE, dark-grey with dark bands parallel t.c.a., possibly fine sulfides grades into sandstone, highly fractured	Arg-2
192.6	198.6	SANDSTONE to CONGLOMERATE, coarse, brown sandstone grading into conglomerate as seen above, fractured	Py-trace
198.6	199.6	SILTSTONE, dark-grey, with dark bands parallel t.c.a., possibly fine sulfides, fractured	
		End of Hole	

Grew Creek Project

Recovery and RQD

Hole # CG-07-09

core size:B

page: 1

RADIUS GOLD INC.

logged by: Spublicover

Date:Sept 5/09

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
0.0	83.8	83.8	4.0	5	0.4	0
83.8	86.9	3.1	3.1	100	0.5	16
86.9	89.9	3.0	2.8	93	0.6	20
89.9	93.0	3.1	3.1	100	0.2	6
93.0	96.0	3.0	3.0	100	1.2	40
96.0	99.1	3.1	3.0	97	1.5	48
99.1	102.1	3.0	3.0	100	0.3	10
102.1	105.2	3.1	3.1	100	2.7	87
105.2	108.2	3.0	3.0	100	0.8	27
108.2	111.3	3.1	3.1	100	0.0	0
111.3	114.3	3.0	3.0	100	1.0	33
114.3	117.3	3.0	3.0	100	0.4	13
117.3	120.4	3.1	3.1	100	0.7	23
120.4	123.4	3.0	3.0	100	2.5	83
123.4	126.5	3.1	3.0	97	1.8	58
126.5	129.5	3.0	3.0	100	1.1	37
129.5	132.6	3.1	2.8	90	2.0	65
132.6	135.6	3.0	3.0	100	1.2	40
135.6	138.7	3.1	3.1	100	2.1	68
138.7	141.7	3.0	3.0	100	2.0	67
141.7	144.8	3.1	3.1	100	2.8	90
144.8	147.8	3.0	3.0	100	1.6	53
147.8	150.9	3.1	3.1	100	0.9	29
150.9	153.9	3.0	2.7	90	0.4	13
153.9	155.4	1.5	1.4	93	0.0	0
155.4	158.5	3.1	2.1	68	0.0	0
158.5	160.0	1.5	1.5	100	0.3	20
160.0	163.1	3.1	3.0	97	1.5	48
163.1	164.6	1.5	1.5	100	1.0	67
164.6	166.1	1.5	1.5	100	0.4	27
166.1	169.2	3.1	3.1	100	2.3	74
169.2	172.2	3.0	3.0	100	2.5	83
172.2	175.3	3.1	3.0	97	1.0	32
175.3	178.3	3.0	3.0	100	2.6	87
178.3	181.4	3.1	3.0	97	1.0	32
181.4	184.4	3.0	2.8	93	2.5	83
184.4	187.5	3.1	3.1	100	0.2	6
187.5	190.5	3.0	3.0	100	0.9	30
190.5	192.0	1.5	1.5	100	0.4	27

Emerick Resources Ltd

Drill Core Sample Record

Type of sampling:	Inclusive	Hole-id:	CG-07-09
		Date:	06-Sept-'09

Sample No.	Sample interval			Sample No.	Sample interval		
	From	To	Length (m)		From	To	Length (m)
25818	79.60	83.60	4.00	25862	142.7	144.20	1.50
25819	83.60	85.10	1.50	25863	144.20	145.70	1.50
25820	85.10	86.60	1.50	25864	145.70	147.20	1.50
25821	86.60	88.10	1.50	25865	147.20	148.7	1.50
25822	88.10	89.60	1.50	25866	148.70	150.2	1.50
25823	89.60	91.10	1.50	25867	150.20	151.7	1.50
25824	91.10	92.60	1.50	25868	STD	GS-1D	
25825	STD	GS-1D		25869	151.70	153.2	1.50
25826	92.60	94.10	1.50	25870	153.20	154.7	1.50
25827	94.10	95.60	1.50	25871	154.70	156.2	1.50
25828	95.60	97.10	1.50	25872	156.20	157.7	1.50
25829	97.10	98.60	1.50	25873	157.70	159.2	1.50
25830	98.60	100.10	1.50	25874	159.20	160.7	1.50
25831	100.10	101.60	1.50	25875	BLANK		
25832	101.60	103.10	1.50	25876	160.70	162.2	1.50
25833	103.10	104.60	1.50	25877	162.20	163.7	1.50
25834	104.60	106.10	1.50	25878	163.70	165.2	1.50
25835	106.10	107.60	1.50	25879	165.20	166.7	1.50
25836	107.60	108.30	0.70	25880	166.70	168.2	1.50
25837	108.30	109.80	1.50	25881	168.20	169.7	1.50
25838	BLANK			25882	169.70	171.2	1.50
25839	109.80	111.30	1.50	25883	171.20	172.7	1.50
25840	111.30	112.90	1.60	25884	172.70	174.2	1.50
25841	112.90	114.40	1.50	25885	174.20	175.7	1.50
25842	114.40	115.90	1.50	25886	175.70	177.2	1.50
25843	115.90	117.40	1.50	25887	BLANK		
25844	117.40	118.90	1.50	25888	177.20	178.7	1.50
25845	118.90	120.40	1.50	25889	178.70	180.2	1.50
25846	120.40	121.90	1.50	25890	180.20	181.7	1.50
25847	BLANK			25891	181.70	183.2	1.50
25848	121.90	123.40	1.50	25892	183.20	184.7	1.50
25849	123.40	125.00	1.60	25893	184.70	186.2	1.50
25850	125.00	126.50	1.50	25894	186.20	187.7	1.50
25851	126.50	128.00	1.50	25895	187.70	189.2	1.50
25852	128.00	129.50	1.50	25896	STD	GS-10C	
25853	129.50	131.00	1.50	25897	189.20	190.3	1.10
25854	131.00	132.50	1.50	25898	190.30	191	0.70
25855	132.50	134.00	1.50	25899	191.00	192.5	1.50
25856	134.00	135.50	1.50	25900	192.50	194	1.50
25857	135.50	137.60	2.10	25901	194.00	195.5	1.50
25858	137.60	139.10	1.50	25902	195.50	197	1.50
25859	STD	GS-1D		25903	197.00	198.5	1.50
25860	139.10	140.60	1.50	25904	198.50	199.6	1.10
25861	140.60	142.70	2.10				

Arg argillic
Sil silicification
Py pyrite
Mag magnetics
Bx breccia
Stw stockwork
QFP qtz feldspar porphry

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Rat Creek Grid

DDH No. **CG-08R-09** Azimuth 093 Started on: 10/09/2009
Northing: 9635 Dip -50 Completed on: 15/09/2009
Easting: 11035 Core Size NTW Logged by: Shane Carlos
Collar Elev. 795M Final Depth 205.7m

Footage		Description	Notables-
From (m)	To (m)		Intensity (1-5)
0	19.5	OVERBURDEN, glacial till, abundant boulders and pebbles	
19.5	27.9	HETEROLITHIC BRECCIA/HYDROTHERMAL, dark grey/black fine to <1cm (subangular) breccia matrix supported, various lithologies: rounded grey pebbles, with larger 15cm by 7cm pyroclasts of QFP rhy, ragged-wispy	Arg-4
		surficial alteration and bleaching to 25.5m	
		27m-27.1m entirely qtz flooded, trace pyrite	
		referred to elsewhere as heterolithic volc. Bx, epiclastite, volc. conglomerate	Py-trace
27.9	30	OVERBURDEN, alternating sections of surficially altered bedrock (volcanic breccia) and glacial till-boulders and pebbles	
		27.9m-28.4m frozen sand	
30	31.2	WELDED LAPILLI TUFF, surficially altered, bleached grey/white	Py-2%
		several QFP clasts with about 2% pyrite	
31.2	52.1	HETEROLITHIC BRECCIA/HYD., matrix dark grey/black with QFP fragments	Arg-3 + Py-trace
		larger porphry clasts with ragged, wispy shapes suspended sporadicaly throughout matrix, various clast types	
		@33m weak magnetic fragment	Mag-1
		34.1m-38.7m mosaic breccia	
		50m-51.1m intense clay alteration	Arg-4
52.1	58.9	HETEROLITHIC BRECCIA/HYDROTHERMAL, clasts include altered mafic dyke rock, 12cm by 5cm QFP clasts ragged, wispy shaped	
		matrix is grey/black, various clast types	
		58.7m-58.9m complete chalcedony replacement	Sil-5
58.9	60.5	SILICIFIED BRECCIA, patchy clay alteration + bounded by intense silicification grey chalcedony stringers, open spaced 2mm qtz crystal growth (vugs)	
		60.3m-60.5m complete chalcedony replacement with 2mm feldspars?	Sil-5
		section dark-grey, fractures reveal disseminated py and py on fractures	Py-1%
60.5	75.2	MAFIC DYKE, mostly bleached, hard to split, silicified, gabbro?	Sil-5 + stw
		agglomeroporphyritic 2mm blobs of crystal laths	
		banded creamy chalcedony veins up to 1.5cm thick	
		66.3m-73.4m patchy, moderate magnetism, rock is darker grey/green	Mag-3
		(ie. less altered) @72.6m wavy alteration pattern; fluid infiltration, where the	
		light-green is non-mag. and dark-green is mag. Disseminated py. 3%	Py-3%
		73.6m-75.2m clay altered, soft, chalcedony veins + light-brown veining filling	Arg-5
		around fractured + clastic dyke rock, ie. Vein breccia	Bx
		(brecciation has occurred in place/hydrothermal breccia)	

Arg argillic
Sil silicification
Py pyrite
Mag magnetics
Bx breccia
Stw stockwork
QFP qtz feldspar porphry

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Rat Creek Grid

DDH No. **CG-08R-09** Azimuth 093 Started on: 10/09/2009
Northing: 9635 Dip -50 Completed on: 15/09/2009
Easting: 11035 Core Size NTW Logged by: Shane C[illegible]s
Collar Elev. 795M Final Depth 205.7m

Footage		Description	Notables-
From (m)	To (m)		Intensity (1-5)
75.2	77.6	PYROCLASTIC, greenish ½ cm-1.5cm white subhedral feldspars, squarish;not elongate matrix composed of round 1mm qtz eyes, 2mm crystal + crystal shards, and a finer indistinct portion occasional wispy >4cm porphyritic pyroclasts, 1 large 30cm flow banded coarse QFP clast	
77.6	86.6	HETEROLITHIC BRECCIA/HYDROTHERMAL, typical grey/black matrix, various clast types wispy, flow banded, 1.5cm thin and distorted clasts no preferred clast orientation Matrix, <½ cm angular + wispy clasts, of 2 components: grey qtz lithic, and wispy white pyroclasts fining to indistinct black matrix 79.1m-80.6m moderate argillic 82.1m-84.1m more clastic-rich, various clasts, clast-rich, clast supported, grey qtz clasts with qtz stockwork in them 80.6m-86.6m intense argillic alteration, fine gritty clay, relict clasts and pyroclasts	 Arg-3 Stw Arg-5
86.6	89.1	MAFIC DYKE, grey, intensely clay alt., rare remnant agglomeroporphyritic texture, abundant grey/white clay, brecciated with brecciated creamy chalcedony banded veins, with brown bands (qtz?) , gabbro? 30% of rock is vein material, 70% is grey clay and clay alt. dyke also, black + white qtz vein fragments are banded 88.9m-89.1m intense silicification of broken banded vein and vein clasts up to 4cm	Arg-5 Bx, veining Sil-5
89.1	92.4	HETEROLITHIC BRECCIA/HYD, grey/black matrix, then short section of Coarse 1cm light crystals and laminar texture, last 50cm of section is clay 'slop'	
92.4	101.8	MAFIC DYKE, grey, intensely clay alt., rare remnant agglomeroporphyritic texture, brecciated, soft, crumbles, gabbro? brecciated banded qtz veining up to 1.5cm thick, abundant, regularly occurring veining. @99.1m-10cm thick pure grey/white clay	Arg-5 Bx, veining
101.8	110.6	HETEROLITHIC BRECCIA/HYD., qtz., QFP 6cm clasts, 1 large 30cm QFP clast, black matrix with fine clasts to 106.1m very clay altered both framents and matrix 106.1m-110.6m silicified, some clay alt. + brecciated	Arg-4 Sil-3, Bx
110.6	113.6	WELDED TUFF, grey-brown colour, 70% matrix, 30% pumice lapilli clasts 3cm by 5mm, planar alignment of wispy qtz. porphyritic fiamme from 3cm down and thin, matrix is wispy elongate clasts and granular (1mm mostly, 90%) crystals very granular, compacted rock, compressed pumice	

Arg	argillic	Hm	red hematite
Sil	silicification	Ser	sericite
Py	pyrite	Car	carbonate
Mag	magnetics		
Bx	breccia		
Stw	stockwork		
QFP	qtz feldspar porphry		

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Rat Creek Grid

DDH No. **CG-08R-09** Azimuth 093 Started on: 10/09/2009
Northing: 9635 Dip -50 Completed on: 15/09/2009
Easting: 11035 Core Size NTW Logged by: Shane Carlos
Collar Elev. 795M Final Depth 205.7m

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
113.6	116.2	QUARTZ BRECCIA, very fine, white/grey/brown, brecciated, with picture puzzle (mosaic) breccia, some 1mm quartz eyes, and hairline clay seams	
116.2	134.4	HETEROLITHIC BRECCIA/HYD., black matrix, black bituminous 10cm sections/clasts, most clasts are volcanic, amygdule basalt and QFP possibly hydrothermally brecciated 120.3-121.8m white/grey granular 1mm clay breccia, very little matrix <10% crumbles 123.4m-124.1m grey very fine grained clast?, somewhat schistose @128.6m 2cm banded qtz vein cutting through the volcanic breccia 130.1m-131.6m hematite red clay alt zone, max fragment size is 1mm of gritty lithics	Arg-4 Hm-3
134.4	144.5	RHYOLITE PORPHRY, (QFP), red + green, clay and sericite altered, hematite breccia pulses throughout/hydrothermal breccia? soft, soapy, green sericite on fractures and throughout rock patchy sections of fine granular pyrite accumulations with hematite stringers at least 1% scattered 2cm wide accumulations throughout section 139m-141.1m 2-3% pyrite as massive 5cm accumulations of fine grained py., intimately associated with hematite stringers, about 33% Hem+py veinlets 141.1m-144.3m picture puzzle hematite matrix breccia pulses/hydrothermal breccia	Hm-3 Ser-3 Bx Py-1% Py-2-3%
144.3	150.5	HETEROLITHIC BRECCIA/HYD, various lithologies, black matrix, QFP rhy lapilli, 30cm bituminous, 30cm of rounded 2cm qtz+black rounded lithics in a sandy, clay alt. matrix	
150.5	159.9	WELDED TUFF/PSEUDOPORPHRY, Qtz + bright green (chlorite?) + red hematite speckled <2mm blobs, milky qtz flooding and 3mm vugs with a browny white crystal and overall hematite matrix @152m breccia texture and false breccia texture due to hematite alt leaving behind unaltered cores, also development of fine 1mm long crystal laths as porphry texture in patchy sections @157m some clasts are rhyolite porphry, lacking the 1mm laths breccia pulses/hydrothermal breccia? Several black 1cm wide breccia 'veinlets' with ½ cm light QFP clasts within	Hm-3
159.9	161.5	HEMATITE BRECCIA, silicified, healed breccia texture, intense red hematite 80% fine-grained matrix with abundant 1mm long, light-coloured crystal laths	Hm-5
161.5	167.4	WELDED TUFF/PSEUDOPORPHRY, Qtz + green + red hematite speckled <2mm blobs with hematite breccia pulses. Soft, clay altered and green soapy (sericite) mineral on fractures @163.6m 4cm banded milky qtz vein @166.8m false breccia texture, hematite alt leaving cores of green altered QFP also, some true brecciation, disseminated pyrite	Hm-3 Bx Py-1%

Hg 3-15 ppm
Hg 1ppm
Hg 2 ppm

Arg argillic
Sil silicification
Py pyrite
Mag magnetics
Bx breccia
Stw stockwork
QFP qtz feldspar porphry
Hm red hematite
Ser sericite

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Rat Creek Grid

DDH No. **CG-08R-09** Azimuth 093 Started on: 10/09/2009
Northing: 9635 Dip -50 Completed on: 15/09/[illegible]
Easting: 11035 Core Size NTW Logged by: Shane Ca[illegible]os
Collar Elev. 795M Final Depth 205.7m

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
167.4	174.1	HETEROLITHIC BRECCIA/HYD., black matrix, various lithologies, QFP pumice clasts, some minor qtz veining	
174.1	191.4	CRYSTAL LITHIC ASH TUFF, grey brecciated, argillic alteration	Hm-3
		broken milky qtz vein frags + some stockwork	Bx
		banded colloform milky qtz + red hematite nodules up to 2cm by 1cm and scattered 5% <1cm banded nodules	
		8% disseminated <2mm red hematite blobs with a preferred planar orientation, somewhat squashed. Implied: compaction or possible minor welding	
		sections of mostly grey/white clay and fine <5mm frags of grey lithic and qtz hematite throughout	
		@178.7m large 6cm by 6cm banded colloform spherical nodule, growth appears to be inward with bands of clear qtz, red hematite, brown calcite	Car-1
		186.4m-189.1m granular bands of pyrite, 2mm and 1cm thick	Py-2%
		2% py, patchy silicification	Sil-2
191.4	199.1	HETEROLITHIC BRECCIA/HYD.,various lithologies, black matrix, angular QFP rhyolite clasts (no wispy edges), bottom of section has increasingly, up to 4% white/brown frags <1cm wide. This unit has torn up the underlying white ash tuff clay altered and extremely broken up, incompetent rock	Bx
199.1	204.2	ASH TUFF, white, very fine-grained sealed breccia, monolithic, 1cm frags but themselves have fine grain	
		Qtz-calcite veining minor	
		clay altered and extremely broken up, incompetent	
204.2	205.3	HETEROLITHIC BRECCIA/HYDROTHERMAL various lithologies black matrix, QFP rhyolite clasts 30cm section, black fine-grained, no other discernable texture, possibly fine sulfides	
205.3	205.7	WELDED LAPILLI TUFF, ½ cm crystals as a granular matrix with lapilli size fiamme pyroclasts, ie. flattened pumice	
		End of Hole	

Hg 2-3 ppm

Grew Creek Project

Recovery and RQD

Hole # CG-08-09R

core size: N

RADIUS GOLD INC.

logged by: Spublicover

Date: Sept 10, 2009

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
9.1	19.8	10.7	0.9	8	0.1	1
19.8	21.3	1.5	0.5	33	0.0	0
21.3	24.4	3.1	3.1	100	0.6	19
24.4	27.4	3.0	2.6	87	1.9	63
27.4	30.5	3.1	1.9	61	0.3	10
30.5	32.0	1.5	0.8	53	0.1	7
32.0	33.5	1.5	1.3	87	0.4	27
33.5	35.1	1.6	1.6	100	0.5	31
35.1	38.1	3.0	3.0	100	2.2	73
38.1	41.1	3.0	3.0	100	2.8	93
41.1	44.2	3.1	3.1	100	2.9	94
44.2	47.2	3.0	2.9	97	2.0	67
47.2	50.3	3.1	3.1	100	2.8	90
50.3	53.3	3.0	2.9	97	2.8	93
53.3	56.4	3.1	3.1	100	2.2	71
56.4	59.4	3.0	3.0	100	2.8	93
59.4	62.5	3.1	3.0	97	2.8	90
62.5	65.5	3.0	3.0	100	2.6	87
65.5	68.6	3.1	3.0	97	2.8	90
68.6	71.6	3.0	3.0	100	2.6	87
71.6	74.7	3.1	3.1	100	3.0	97
74.7	77.7	3.0	2.9	97	2.7	90
77.7	80.8	3.1	3.1	100	2.9	94
80.8	82.3	1.5	1.5	100	0.4	27
82.3	85.3	3.0	3.0	100	3.0	100
85.3	88.4	3.1	3.1	100	2.9	94
88.4	91.4	3.0	2.5	83	2.0	67
91.4	94.5	3.1	3.1	100	2.2	71
94.5	96.0	1.5	1.5	100	1.5	100
96.0	99.1	3.1	3.1	100	2.8	90
99.1	102.1	3.0	3.0	100	2.6	87
102.1	105.2	3.1	3.0	97	2.8	90
105.2	108.2	3.0	3.0	100	2.7	90
108.2	111.3	3.1	3.1	100	2.6	84
111.3	114.3	3.0	3.0	100	1.1	37
114.3	117.3	3.0	3.0	100		0
117.3	120.4	3.1	3.1	100	2.2	71
120.4	123.4	3.0	3.0	100	2.6	87
123.4	126.5	3.1	3.1	100	2.2	71
126.5	129.5	3.0	3.0	100	2.7	90

Grew Creek Project

Recovery and RQD

Hole # CG-08-09R

core size: N

RADIUS GOLD INC.

logged by: Spublicover

Date: Sept 10, 2009

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
135.6	138.7	3.1	3.1	100	2.8	90
138.7	141.7	3.0	3.0	100	2.7	90
141.7	144.8	3.1	3.1	100	2.8	90
144.8	147.8	3.0	3.0	100	3.0	100
147.8	150.9	3.1	3.1	100	2.9	94
150.9	153.9	3.0	3.0	100	2.9	97
153.9	155.4	1.5	1.5	100	1.4	93
155.4	158.5	3.1	3.1	100	2.9	94
158.5	161.5	3.0	3.0	100	2.6	87
161.5	164.6	3.1	3.1	100	2.9	94
164.6	167.6	3.0	3.0	100	2.9	97
167.6	170.7	3.1	3.1	100	2.5	81
170.7	173.7	3.0	3.0	100	18.0	600
173.7	176.8	3.1	3.1	100	3.0	97
176.8	179.8	3.0	3.0	100	3.0	100
179.8	182.9	3.1	3.1	100	2.8	90
182.9	185.9	3.0	3.0	100	2.5	83
185.9	189.0	3.1	3.1	100	2.0	65
189.0	192.0	3.0	3.0	100	2.6	87
192.0	195.1	3.1	3.1	100	2.5	81
195.1	198.1	3.0	3.0	100	0.3	10
198.1	201.2	3.1	3.1	100	2.3	74
201.2	204.2	3.0	3.0	100	0.9	30
204.2	205.7	1.5	1.5	100	0.2	13

Emerick Resources Ltd

Drill Core Sample Record

Type of sampling:		Inclusive			Hole-id:	CG-08-09R
					Date:	15-Sept-'09

Sample No.	Sample interval			Sample No.	Sample interval		
	From	To	Length (m)		From	To	Length (m)
25905	21.30	22.80	1.50	25953	85.10	86.60	1.50
25906	22.80	24.30	1.50	25954	86.60	88.10	1.50
25907	24.30	25.80	1.50	25955	88.10	89.60	1.50
25908	25.80	27.30	1.50	25956	89.6	91.10	1.50
25909	27.30	28.80	1.50	25957	91.10	92.60	1.50
25910	BLANK			25958	BLANK		
25911	28.80	30.30	1.50	25959	92.60	94.1	1.50
25912	skipped			25960	94.10	95.6	1.50
25913	30.30	33.30	3.00	25961	95.60	97.1	1.50
25914	33.30	34.80	1.50	25962	97.10	98.6	1.50
25915	34.80	36.30	1.50	25963	98.60	100.1	1.50
25916	STD	GS-1D		25964	100.10	101.6	1.50
25917	36.30	37.80	1.50	25965	101.60	103.1	1.50
25918	37.80	39.30	1.50	25966	103.10	104.6	1.50
25919	39.30	40.80	1.50	25967	104.60	106.1	1.50
25920	40.80	42.30	1.50	25968	106.10	107.6	1.50
25921	42.30	43.80	1.50	25969	BLANK		
25922	43.80	45.30	1.50	25970	107.60	109.1	1.50
25923	STD	GS-10C		25971	STD	GS-1D	
25924	45.30	46.80	1.50	25972	109.10	110.6	1.50
25925	46.80	48.30	1.50	25973	110.60	112.1	1.50
25926	48.30	49.80	1.50	25974	112.10	113.6	1.50
25927	49.80	51.30	1.50	25975	113.60	115.1	1.50
25928	51.30	52.80	1.50	25976	115.10	116.2	1.10
25929	52.80	54.30	1.50	25977	116.20	117.7	1.50
25930	54.30	55.80	1.50	25978	117.70	119.2	1.50
25931	55.80	57.30	1.50	25979	119.20	120.3	1.10
25932	57.30	58.80	1.50	25980	120.30	121.8	1.50
25933	58.80	60.30	1.50	25981	121.80	122.5	0.70
25934	60.30	61.80	1.50	25982	122.50	123.4	0.90
25935	61.80	63.30	1.50	25983	123.40	124.1	0.70
25936	BLANK			25984	124.10	125.6	1.50
25937	63.30	64.80	1.50	25985	125.60	127.1	1.50
25938	64.80	66.30	1.50	25986	127.10	128.6	1.50
25939	66.30	67.80	1.50	25987	128.60	130.1	1.50
25940	67.80	69.30	1.50	25988	130.10	131.6	1.50
25941	69.30	70.80	1.50	25989	131.60	133	1.40
25942	70.80	72.30	1.50	25990	133.00	134.4	1.40
25943	72.30	73.80	1.50	25991	STD	GS-10C	
25944	73.80	75.30	1.50	25992	134.40	135.9	1.50
25945	75.30	76.80	1.50	25993	135.90	137.4	1.50
25946	76.80	77.60	0.80	25994	137.40	138.9	1.50
25947	77.60	79.10	1.50	25995	138.90	140.4	1.50
25948	79.10	80.60	1.50	25996	140.40	141.9	1.50
25949	80.60	82.10	1.50	25997	141.90	143.4	1.50
25950	82.10	83.60	1.50	25998	143.40	144.9	1.50
25951	STD	GS-10C		25999	BLANK		
25952	83.60	85.10	1.50	26000	144.90	146.4	1.50

Emerick Resources Ltd

Drill Core Sample Record

Type of sampling:	Inclusive	Hole-id:	CG-08-09R
		Date:	15-Sept-'09

Sample No.	Sample interval		
	From	To	Length (m)
26001	146.40	147.9	1.50
26002	147.90	149.4	1.50
26003	149.40	150.9	1.50
26004	150.90	152.4	1.50
26005	152.40	153.9	1.50
26006	153.90	155.4	1.50
26007	155.40	156.90	1.50
26008	156.90	158.40	1.50
26009	158.40	159.90	1.50
26010	STD	GS-1D	
26011	159.90	161.40	1.50
26012	161.40	162.90	1.50
26013	162.90	164.40	1.50
26014	164.40	165.90	1.50
26015	165.90	167.40	1.50
26016	167.40	168.90	1.50
26017	168.90	170.40	1.50
26018	170.40	171.90	1.50
26019	171.90	173.70	1.80
26020	BLANK		
26021	173.70	175.20	1.50
26022	175.20	176.70	1.50
26023	176.70	178.20	1.50
26024	178.20	179.70	1.50
26025	179.70	181.20	1.50
26026	181.20	182.70	1.50
26027	182.70	184.20	1.50
26028	184.20	185.70	1.50
26029	STD		
26030	185.70	187.20	1.50
26031	187.20	188.70	1.50
26032	BLANK		
26033	188.70	190.20	1.50
26034	190.20	191.70	1.50
26035	191.70	192.50	0.80
26036	192.50	194.00	1.50
26037	194.00	195.50	1.50
26038	195.50	197.00	1.50
26039	197.00	198.50	1.50
26040	198.50	200.20	1.70
26041	200.20	201.70	1.50
26042	201.70	203.20	1.50
26043	203.20	204.20	1.00
26044	204.20	205.70	1.50

Arg argillic
Sil silicification
Py pyrite
Mag magnetics
Bx breccia
Stw stockwork
QFP qtz feldspar porphry
Hm red hematite
Ser sericite

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Rat Creek Grid

DDH No. **CG-09-2009** Azimuth 093 Started on: 15/09/2009
Northing: 9350 Dip -50 Completed on: 21/09/2009
Easting: 11035 Core Size NTW Logged by: Shane Carlos
Collar Elev. 805M Final Depth 175.3m

Footage		Description	Notables-
From (m)	To (m)		Intensity (1-5)
0	19.8	OVERBURDEN glacial till, boulders, pebbles, sand	
19.8	52.1	HEMATITE CLAY ZONE, intense clay alteration, dark-red colour, brecciated-granular 1mm pieces, qtz eye + feldspar porphyritic 19.8m-22.8m green clay + green lithic breccia pieces suspended in the clay 25.5m-28.9m clay rich breccia, with green clay + green lithics, then 20cm black carbonaceous clay, then fine equigranular salt + pepper (sandstone texture) tuff? 30.5m-32m black + green clay-rich breccia, possibly alt rhyolite porphry clasts	Arg-5
52.1	63	HETEROLITHIC BRECCIA/HYD., black matrix supported, various clasts abundant QFP clasts 5cm by 2cm: some blocky/angular and some with wispy flowing shapes-pumice? , rounded 1cm qtz clasts, angular black lithics, large QFP blocks (40cm long), black bituminous zones 10cm long, flow banded QFP, brown clasts with ½ cm white amygdules *generally clay alt and incompetent with 10cm granular breccia gouge sections @59.4m 20cm long qtz feldspar porphry tuff, looks like a rhyolite but for the rare 1% rounded 1cm black clastics 61.7m-63m milky qtz veining + vein fragments, vugs 1mm wide in veins	Arg-3
63	65.3	QFP TUFF, light-green breccia, hairline flow banding within 2mm clasts round/grey concentrically banded ½ cm accretionary lapilli? or spherulites? Very rare. Possibly larger 5cm by 2cm clasts of green QFP rhyolite but edges are indistinct and grade into surroundings	Arg-2
65.3	68.4	SULFIDE QTZ VEIN ZONE 65.3m-66.6m Grey Granular Breccia, disseminated fine sulfides, grey clay, crushed milky qtz veining 66.6m-68.4m white, medium sandy unit with 2% disseminated py very fine About 80% qtz	Arg-3
68.4	70.5	HETEROLITHIC BRECCIA/HYD., black matrix breccia, matrix supported, various lithics, wispy QFP rhyolite pyroclasts	
70.5	72	WELDED TUFF, eutaxitic texture-wispy flattened black pyroclasts 3cm by 2mm Light-green matrix supported and predominantly qtz eye porphocrysts, few feldspars	
72	76.2	HETEROLITHIC BRECCIA/HYDROTHERMAL, matrix supported, various lithics, wispy QFP clasts are altered light-green	
76.2	79.6	CRYSTAL LITHIC TUFF/QFP TUFF, green, with larger 1cm feldspars + qtz eyes feldspars are broken and angular also black angular to rounded lithics about 2%	

Arg argillic
Sil silicification
Py pyrite
Mag magnetics
Bx breccia
Stw stockwork
QFP qtz feldspar porphry
Hm red hematite
Ser sericite

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Rat Creek Grid

DDH No. **CG-09-2009** Azimuth 093 Started on: 15/09/2009
Northing: 9350 Dip -50 Completed on: 21/09/2009
Easting: 11035 Core Size NTW Logged by: Shane Cullis
Collar Elev. 805M Final Depth 175.3m

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
79.6	85.2	ACCRETIONARY LAPILLI TUFF, light-green 20% 1.5cm diameter, grey/white concentrically banded spheroids, silicified interiors, 1mm qtz clasts incorporated, bread crust ragged outer edges (1mm thick outer soft rim), balls are in places alligned in a plane @ 20% to core 80% matrix: 1mm qtz eyes, <2mm green hairline concentrically banded spheroids lower contact @ 45% to core with some balls cut off by underlying breccia *this provides some support for the Volcanic breccia to be hydrothermal in places	
85.2	86.5	HETEROLITHIC BRECCIA/HYD., possibly a hydrothermal breccia 40% black matrix, 60% clastic from 1cm to 5cm, wispy QFP clasts+various incorporating some of the accretions and some fragments from above	
86.5	87.2	Mica-rich qtz vein or fragment, white/grey mica-rich with pink feldspars	
87.2	89.1	WELDED TUFF, 50% black matrix with 3mm long dark crystal fragments 50% light-green 4cm by ½ cm flattened porphry clasts alligned in one direction	
89.1	93.5	LITHIC CRYSTAL TUFF, breccia, black matrix, wispy QFP clasts, most clasts ½ cm square, some 10% 3cm by 3cm	
93.5	94.8	ASH TUFF, very fine-grained, grey and bleached white along fractures + one 2mm wide qtz vein	
94.8	98.5	HETEROLITHIC BRECCIA/HYD., typical smaller fragment dark-grey matrix incorporating Qtz porphry rhyolite and tuff fragments, some qtz flooding	
98.5	105.2	TUFF, grey/black 1mm thick, elongate wisps clay altered, gray wisps sometimes replaced by fine granular sulfide last 20cm, clay seam/granular + muscovite rich 1cm seam along core angle	
105.2	107.9	MAFIC DYKE, highly altered, essentially grey clay, brecciated, relict green alt agglomeroporphyritic texture as seen in CG-08-2009, ie. 2mm blobs of laths within 1cm grey breccia clasts , gabbro? Milky qtz veining and crushed ½ cm brecciated veins, in places 20cm long sections with 30% vein fragments	Arg-5 Bx
107.9	117.1	HETEROLITHIC BRECCIA/HYDROTHERMAL, matrix supported, various lithics, wispy QFP rhyolite to pumice clasts 3cm 109.1m-110.3m mildly brecciated, silicified QFP rhyolite 110.3m-114m highly fractured/blocky, clay-rich, abundant 5cm bleached fine-grained dyke clasts and other rounded unidentified lithics, @113.3m 1cm wide Milky-white qtz vein 114m-117.1m less fractured than previous, clay-rich reduced to BTW due to sanding	Arg-4, Py-trace Bx

Arg argillic
Sil silicification
Py pyrite
Mag magnetics
Bx breccia
Stw stockwork
QFP qtz feldspar porphry

Hm red hematite
Ser sericite

Diamond Drill Log
Project: Canyon Gold/Grew Creek/Rat Creek Grid

DDH No. **CG-09-2009** Azimuth 093 Started on: 15/09/2009
Northing: 9350 Dip -50 Completed on: 21/09/2009
Easting: 11035 Core Size BTW Logged by: Shane Carlos
Collar Elev. 805M Final Depth 175.3m

Footage		Description	Notables- Intensity (1-5)
From (m)	To (m)		
117.1	167.3	QFP RHYOLITE, to 127.7m extremely fragmented/blocky, variable clay alteration, distinct grey colour 127.7m-167.3m less fractured than previous, fine millimeter grey flow banding throughout, about 2% pyrite	Bx, Arg-3 Py-2%
167.3	169.7	LAPILLI TUFF, mostly 5cm by 2cm clasts of QFP rhyolite and black finely banded scoria? Spotted with white ½ cm qtz eyes, ie. Porphyritic scoria? highly fractured, possibly a fault zone	Fault
169.7	175.3	LAPILLI TUFF?, red hematite-rich clastic, clay altered, fractured, thin ½ cm qtz veinlets throughout, protolith uncertain 171.2m-175.3m banded + vuggy ½ cm wide qtz. Veining parallel to core angle, pyrite along vein trends and on fractures **End of Hole**	Hm-4 Py-2%

Grew Creek Project

Recovery and RQD

Hole # CG-09-09 page: 1

core size: N

RADIUS GOLD INC.

logged by: Spublicover

Date: Sept 18, 09

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
0.0	10.7	10.7	0.3	3	0.0	0
10.7	18.3	7.6	0.4	5	0.0	0
18.3	22.9	4.6	1.2	26	0.7	15
22.9	25.9	3.0	3.0	100	2.1	70
25.9	27.4	1.5	1.0	67	0.8	53
27.4	29.0	1.6	1.5	94	0.3	19
29.0	30.5	1.5	1.5	100	1.1	73
30.5	33.5	3.0	2.5	83	1.4	47
33.5	35.1	1.6	1.6	100	1.3	81
35.1	38.1	3.0	3.0	100	2.6	87
38.1	39.6	1.5	1.5	100	1.4	93
39.6	42.7	3.1	3.1	100	2.8	90
42.7	45.7	3.0	3.0	100	2.5	83
45.7	48.8	3.1	2.5	81	2.2	71
48.8	51.8	3.0	1.9	63	1.4	47
51.8	54.9	3.1	3.1	100	2.9	94
54.9	57.9	3.0	3.0	100	0.6	20
57.9	61.0	3.1	3.1	100	0.2	6
61.0	64.0	3.0	3.0	100	2.9	97
64.0	65.5	1.5	1.5	100	1.5	100
65.5	68.6	3.1	3.1	100	3.1	100
68.6	71.6	3.0	3.0	100	2.8	93
71.6	74.7	3.1	3.0	97	2.8	90
74.7	77.7	3.0	2.8	93	2.6	87
77.7	79.2	1.5	0.8	53	0.5	33
79.2	80.8	1.6	1.3	81	1.3	81
80.8	83.8	3.0	2.9	97	2.8	93
83.8	86.9	3.1	2.8	90	1.3	42
86.9	89.9	3.0	3.0	100	2.7	90
89.9	93.0	3.1	3.1	100	2.9	94
93.0	96.0	3.0	3.0	100	2.7	90
96.0	99.1	3.1	3.1	100	2.0	65
99.1	102.1	3.0	3.0	100	2.3	77
102.1	105.2	3.1	3.1	100	2.7	87
105.2	106.7	1.5	1.5	100	1.3	87
106.7	109.7	3.0	3.0	100	1.2	40
109.7	111.3	1.6	1.4	88	0.1	6
111.3	114.3	3.0	2.5	83	0.5	17
114.3	115.8	1.5	1.5	100	0.6	40
115.8	117.3	1.5	0.6	40	0.0	0

Grew Creek Project

Recovery and RQD

Hole # CG-09-09

core size: N

RADIUS GOLD INC.

logged by: Spublicover

Date: Sept 21, 09

from (m)	to (m)	interval (m)	core recovery (m)	core recovery %	Sum Core Lengths =/> 10cm	RQD %
117.3	118.9	1.6	0.9	56	0.0	0
118.9	120.4	1.5	0.5	33	0.0	0
120.4	121.9	1.5	1.5	100	0.4	27
121.9	125.0	3.1	2.0	65	0.4	13
125.0	128.0	3.0	2.7	90	0.6	20
128.0	129.5	1.5	1.5	100	0.3	20
129.5	131.1	1.6	1.2	75	0.7	44
131.1	132.6	1.5	1.3	87	0.0	0
132.6	135.6	3.0	2.7	90	0.5	17
135.6	138.7	3.1	2.9	94	0.2	6
138.7	140.2	1.5	1.5	100	0.0	0
140.2	141.7	1.5	1.5	100	1.0	67
141.7	144.8	3.1	2.9	94	0.3	10
144.8	147.8	3.0	3.0	100	0.0	0
147.8	149.4	1.6	1.2	75	0.0	0
149.4	152.4	3.0	2.7	90	0.5	17
152.4	155.4	3.0	3.0	100	0.4	13
155.4	158.5	3.1	3.1	100	1.4	45
158.5	160.0	1.5	1.5	100	0.6	40
160.0	163.1	3.1	2.9	94	2.0	65
163.1	166.1	3.0	3.0	100	2.5	83
166.1	169.2	3.1	3.1	100	0.9	29
169.2	172.2	3.0	3.0	100	2.1	70
172.2	175.3	3.1	2.6	84	1.9	61
	EOH					

Emerick Resources Ltd

Drill Core Sample Record

Type of sampling:		Inclusive		Hole-id:	CG-09-09
				Date:	19-Sept-'09

Sample No.	Sample interval			Sample No.	Sample interval		
	From	To	Length (m)		From	To	Length (m)
26045	23.00	24.50	1.50	26093	86.40	86.60	0.20
26046	24.50	26.00	1.50	26094	86.60	87.30	0.70
26047	26.00	27.50	1.50	26095	87.30	88.50	1.20
26048	27.50	29.10	1.60	26096	88.50	90.00	1.50
26049	29.10	30.50	1.40	26097	90.00	91.50	1.50
26050	30.50	32.00	1.50	26098	91.50	93.60	2.10
26051	32.00	33.50	1.50	26099	93.60	95.00	1.40
26052	33.50	35.00	1.50	26100	BLANK		
26053	35.00	36.50	1.50	26101	95.00	96.50	1.50
26054	36.50	38.00	1.50	26102	96.50	98.10	1.60
26055	STD	GS-10C		26103	98.10	99.10	1.00
26056	38.00	39.50	1.50	26104	99.10	100.60	1.50
26057	39.50	41.00	1.50	26105	100.60	102.10	1.50
26058	41.00	42.50	1.50	26106	BLANK		
26059	BLANK			26107	102.10	103.60	1.50
26060	42.50	44.00	1.50	26108	103.60	105.00	1.40
26061	44.00	45.50	1.50	26109	105.00	106.50	1.50
26062	45.50	47.00	1.50	26110	106.50	107.70	1.20
26063	47.00	48.50	1.50	26111	107.70	109.20	1.50
26064	48.50	50.00	1.50	26112	109.20	110.70	1.50
26065	50.00	52.10	2.10	26113	BLANK		
26066	52.10	53.60	1.50	26114	110.70	112.20	1.50
26067	53.60	55.10	1.50	26115	112.20	113.70	1.50
26068	55.10	56.60	1.50	26116	113.70	115.2	1.50
26069	BLANK			26117	115.20	116.7	1.50
26070	56.60	57.20	0.60	26118	116.70	118.2	1.50
26071	57.20	58.70	1.50	26119	118.20	119.7	1.50
26072	58.70	59.40	0.70	26120	119.70	121.2	1.50
26073	59.40	60.90	1.50	26121	121.20	122.7	1.50
26074	60.90	63.10	2.20	26122	122.70	124.2	1.50
26075	63.10	64.60	1.50	26123	124.20	125.7	1.50
26076	STD	GS-1D		26124	125.70	127.2	1.50
26077	64.60	65.00	0.40	26125	127.20	128.7	1.50
26078	65.00	66.70	1.70	26126	128.70	130.2	1.50
26079	66.70	68.20	1.50	26127	130.20	131.7	1.50
26080	68.20	69.70	1.50	26128	131.70	133.2	1.50
26081	69.70	70.40	0.70	26129	133.20	134.7	1.50
26082	70.40	71.90	1.50	26130	BLANK		
26083	71.90	73.40	1.50	26131	134.70	136.2	1.50
26084	73.40	74.90	1.50	26132	136.20	137.7	1.50
26085	74.90	76.40	1.50	26133	137.70	139.2	1.50
26086	76.40	79.20	2.80	26134	139.20	140.7	1.50
26087	79.20	80.70	1.50	26135	140.70	142.2	1.50
26088	80.70	82.20	1.50	26136	BLANK		
26089	82.20	83.70	1.50	26137	142.20	143.7	1.50
26090	83.70	85.10	1.40	26138	143.70	145.2	1.50
26091	STD	GS-1D		26139	145.20	146.7	1.50
26092	85.10	86.40	1.30	26140	146.70	148.2	1.50

Emerick Resources Ltd					
Drill Core Sample Record					
Type of sampling:		Inclusive		Hole-id:	CG-09-09
				Date:	19-Sept-'09

Sample No.	Sample interval		
	From	To	Length (m)
26141	148.20	149.7	1.50
26142	149.70	151.2	1.50
26143	151.20	152.7	1.50
26144	152.70	154.2	1.50
26145	154.20	155.7	1.50
26146	155.70	157.2	1.50
26147	157.20	158.7	1.50
26148	158.70	160.2	1.50
26149	160.20	161.7	1.50
26150	161.70	163.2	1.50
26151	163.20	164.7	1.50
26152	164.70	166.2	1.50
26153	166.20	167.3	1.10
26154	STD		
26155	167.30	168.8	1.50
26156	168.80	170	1.20
26157	170.00	171.5	1.50
26158	171.50	172	0.50
26159	BLANK		
26160	172.00	173	1.00
26161	173.00	175.30	2.30

APPENDIX 2

DRILL HOLE CROSS SECTIONS AND PLAN MAPS



PLAN Scale: 1:5000



LEGEND

- Carbon + Clay rich Breccia
- + + + Coarse Grained Intrusions
- Felsic Tuffs
- Quarte/Carbonate Stockwork
- Pyrite (disseminated, 1-5%)
- Anomalous Au 11-55 ppb
- all other assays in ppm
- Trench (70-380 ppb Au)
- * only 30cm section assayed from this interval @ 0.5 ppm Ag

Quarte Veining

SECTION Scale: 1:1000

KM 410 GRID Looking: North

CG-01, CG-01-2009

Drawn by: Shane Carlos



PLAN Scale: 1:5000



LEGEND

Pyrite (disseminated 1-3%)

bb Bleaching

Carbon + Clay rich Breccia

* assay values in ppm *

SECTION Scale: 1:1000

KM 410 GRID Looking: North West

CG-03, CG-04-2009

Drawn by: Shane Carlos



PLAN Scale: 1:5000

LEGEND

Sulphides (disseminated)

ΔΔΔ Brecciation



SECTION Scale: 1:1000

MAVERICK GRID Looking: North West

CG-06, CG-07-2009

Drawn by: Shane Carlos


?? Assay Sheet Missing (Noranda)
N
08
08R
Hg Zone
RC-08
178
239
9+600N
11+100E
177
PLAN
RC-36
08
08R
795 M
Rat Creek
750 M
Hydrothermal Breccia
151 ppb Au
chalcedony
Mafic Dyke
Hydrothermal Breccia
Mafic Dyke
Hydrothermal Breccia
Welded Tuff
Quartz Breccia
bottom of 177 projected
700 M
Hydrothermal Breccia
Hg 3-15 ppm
Hg 2ppm
Rhyolite porphyry
Hydrothermal Breccia
Welded Tuff/Pseudo Porphyry
Hg 2-3ppm
Hydrothermal Breccia
Crystal Lithic Ash Tuff
Hydrothermal Breccia
Welded Tuff
650 M
Meters Above Sea Level
LEGEND
Pyrite (diss.+stringers)
Interpreted Fault (Noranda)
Red Hematite Alteration (speckled + stringers)
Au Anomalies
12-39 ppb
Enzyme Leach soil Mercury Contour
Sample Points
Enzyme Leach soil Gold Plots
SECTION
Scale: 1:1000
RAT CREEK GRID
Looking: North
CG-08, CG-08R-2009
Drawn by: Shane Carlos



LEGEND

- Pyrite (disseminated)
- Interpreted Fault (Enzyme Leach)
- Red Hematite Alteration
- Enzyme Leach soil Mercury Contour
- Sample Points
- Au Anomalies
  - 19-94 ppb
  - 68-210 ppb
- Enzyme Leach soil Gold Plots

Meters Above Sea Level

SECTION

RAT CREEK GRID

CG-09-2009

Scale: 1:1000

Looking: North

Drawn by: Shane Carlos

APPENDIX 3

ASSAY RESULTS-ALS CHEMEX

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: **EMERICK RESOURCES LTD.**
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

Finalized Date: 10-SEP-2009
This copy reported on 25-SEP-2009
Account: EMERES

CERTIFICATE VA09094233

Project: Canyon Gold

P.O. No.:

This report is for 150 Drill Core samples submitted to our lab in Vancouver, BC, Canada on 28-AUG-2009.

The following have access to data associated with this certificate:

SARA PUBLICOVER	SIMON RIDGWAY	

SAMPLE PREPARATION

ALS CODE	DESCRIPTION
WEI-21	Received Sample Weight
LOG-22	Sample login - Rcd w/o BarCode
CRU-QC	Crushing QC Test
PUL-QC	Pulverizing QC Test
CRU-31	Fine crushing - 70% <2mm
SPL-21	Split sample - riffle splitter
PUL-31	Pulverize split to 85% <75 um
LOG-24	Pulp Login - Rcd w/o Barcode

ANALYTICAL PROCEDURES

ALS CODE	DESCRIPTION	INSTRUMENT
ME-ICP41	35 Element Aqua Regia ICP-AES	ICP-AES
Au-AA23	Au 30g FA-AA finish	AAS

To: **EMERICK RESOURCES LTD.**
ATTN: SIMON RIDGWAY
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

This is the Final Report and supersedes any preliminary report with this certificate number. Results apply to samples as submitted. All pages of this report have been checked and approved for release.

Signature:

Colin Ramshaw, Vancouver Laboratory Manager

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd.
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

Finalized Date: 10-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094233

Sample Description	Method	WEI-21	Au-AA23	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu	Fe
	Units	kg	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	%
	LOR	0.02	0.005	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1	0.01
25501		3.10	<0.005	0.8	0.72	18	10	440	1.0	2	1.31	1.2	10	10	37	2.35
25502		3.56	<0.005	0.8	0.74	20	10	190	0.8	2	7.91	1.3	6	16	27	2.58
25503		4.30	<0.005	0.3	0.90	12	10	290	1.3	2	1.91	1.2	10	12	33	3.40
25504		0.50	<0.005	<0.2	1.76	3	<10	290	0.6	<2	3.07	<0.5	9	15	8	3.46
25505		3.10	<0.005	0.4	0.98	16	10	180	1.1	2	1.96	1.3	11	17	28	2.56
25506		2.42	<0.005	0.2	1.17	11	10	160	1.1	<2	1.84	0.8	12	21	25	2.92
25507		2.24	<0.005	0.2	1.10	9	10	170	0.9	2	2.22	<0.5	10	23	18	2.44
25508		4.00	<0.005	0.2	1.32	10	10	220	1.4	<2	1.79	0.5	11	24	24	2.70
25509		4.50	<0.005	1.1	0.99	17	10	250	0.9	<2	11.45	4.0	7	31	35	1.94
25510		4.34	0.005	1.4	0.54	11	10	200	<0.5	<2	21.0	5.3	3	39	23	0.87
25511		0.10	0.975	13.2	1.82	450	<10	110	<0.5	<2	0.90	1.3	10	40	278	3.43
25512		4.76	<0.005	1.2	0.58	11	10	180	0.5	<2	18.2	3.6	3	31	28	0.98
25513		3.50	<0.005	0.8	0.52	7	10	170	<0.5	<2	17.4	3.1	2	29	16	0.90
25514		2.94	<0.005	0.5	1.28	10	10	550	1.1	<2	3.00	0.7	10	21	30	2.66
25515		4.96	<0.005	<0.2	1.45	9	<10	320	0.8	<2	2.04	<0.5	11	17	18	2.72
25516		4.36	0.005	<0.2	1.65	28	<10	250	0.7	<2	2.34	<0.5	12	19	15	2.98
25517		3.96	<0.005	0.2	1.54	11	<10	340	0.9	<2	2.58	<0.5	11	21	21	3.01
25518		0.78	<0.005	<0.2	1.10	2	<10	380	<0.5	<2	4.77	0.6	7	21	14	1.95
25519		4.74	<0.005	<0.2	1.76	<2	<10	100	<0.5	<2	2.37	<0.5	10	11	2	3.11
25520		4.82	<0.005	2.4	1.65	<2	<10	60	<0.5	6	2.12	<0.5	8	8	85	2.79
25521		3.10	<0.005	<0.2	1.77	<2	<10	80	<0.5	<2	2.07	<0.5	10	9	9	2.86
25522		4.46	0.005	0.2	1.16	5	<10	360	0.6	2	3.21	<0.5	10	24	27	2.85
25523		3.86	<0.005	0.3	0.91	4	<10	210	0.7	<2	1.75	<0.5	6	12	11	3.05
25524		0.12	1.120	9.9	1.77	452	<10	110	<0.5	<2	0.87	1.4	9	38	281	3.32
25525		4.34	<0.005	<0.2	0.95	10	<10	400	0.5	<2	1.43	<0.5	7	55	11	1.81
25526		4.64	<0.005	0.2	1.32	12	<10	610	1.2	<2	2.45	0.6	9	24	25	2.31
25527		4.24	<0.005	0.3	0.70	10	<10	410	0.8	<2	8.00	0.7	4	9	21	1.50
25528		4.12	<0.005	<0.2	1.10	18	<10	640	0.7	<2	3.48	<0.5	8	39	14	1.95
25529		3.90	<0.005	0.2	1.34	12	10	360	1.4	<2	0.76	0.8	13	28	31	2.87
25530		4.04	<0.005	0.2	1.54	6	<10	240	1.2	<2	0.21	0.5	12	37	34	2.80
25531		3.56	<0.005	<0.2	1.50	42	<10	220	1.4	<2	0.19	<0.5	13	34	29	2.79
25532		4.30	<0.005	0.2	1.60	4	<10	300	1.4	<2	0.19	0.6	11	35	39	2.32
25533		3.56	<0.005	0.2	0.86	16	<10	250	1.1	<2	0.18	0.8	9	18	13	2.73
25534		3.60	<0.005	0.3	1.08	7	<10	330	1.3	<2	0.17	0.9	12	20	21	2.41
25535		0.76	<0.005	<0.2	1.22	6	<10	470	<0.5	<2	3.53	0.6	7	47	15	1.87
25536		4.38	<0.005	0.2	1.47	4	<10	430	1.8	<2	0.75	1.1	11	24	24	3.33
25537		3.50	<0.005	0.3	1.21	8	<10	430	1.6	<2	0.36	1.1	12	26	32	3.44
25538		5.20	<0.005	<0.2	1.45	17	<10	250	0.9	<2	1.89	<0.5	14	49	32	3.74
25539		3.96	<0.005	<0.2	1.20	12	<10	350	0.7	<2	2.31	<0.5	12	38	29	3.91
25540		3.52	<0.005	0.2	1.75	14	<10	300	1.1	<2	1.83	<0.5	13	46	32	3.38

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

Finalized Date: 10-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094233

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc	Sr
	Units	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm	ppm
	LOR	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1	1
25501		<10	1	0.30	<10	0.46	269	3	0.10	39	770	22	0.33	4	4	97
25502		<10	1	0.28	10	1.22	325	4	0.08	25	1790	11	0.81	4	5	263
25503		<10	<1	0.34	10	0.71	425	4	0.15	33	790	22	0.38	4	5	143
25504		<10	<1	0.19	20	1.06	713	1	0.09	13	470	8	0.12	<2	8	239
25505		<10	<1	0.30	10	0.77	400	5	0.15	41	630	30	0.33	2	5	132
25506		<10	<1	0.30	10	0.91	433	3	0.16	41	570	23	0.21	2	5	122
25507		10	<1	0.27	10	0.84	368	1	0.14	32	520	12	0.14	<2	4	122
25508		10	<1	0.33	10	0.80	470	2	0.20	36	650	19	0.22	<2	5	136
25509		<10	<1	0.32	10	1.41	411	6	0.12	34	3840	9	0.81	3	6	444
25510		<10	1	0.21	10	1.03	207	5	0.05	26	5660	2	0.9	2	3	692
25511		10	<1	0.14	10	0.88	520	85	0.09	39	570	95	0.27	8	5	47
25512		<10	1	0.24	10	1.06	177	5	0.05	28	4620	3	1.0	3	4	616
25513		<10	<1	0.22	10	1.23	191	3	0.04	22	3650	3	0.9	2	3	562
25514		<10	1	0.30	10	0.95	608	2	0.22	26	640	17	0.32	<2	6	221
25515		<10	<1	0.31	20	0.83	530	1	0.20	17	490	15	0.20	<2	5	145
25516		10	<1	0.29	20	0.96	611	1	0.17	15	460	9	0.16	<2	6	145
25517		10	1	0.35	20	0.91	634	1	0.22	21	490	21	0.22	<2	6	166
25518		<10	<1	0.15	10	0.88	473	1	0.04	21	660	9	0.05	<2	4	145
25519		10	<1	0.23	30	0.91	718	<1	0.10	2	460	4	0.02	<2	5	120
25520		10	<1	0.17	30	1.09	753	1	0.08	<1	400	114	0.06	<2	6	106
25521		10	<1	0.17	30	1.15	743	<1	0.09	1	420	4	0.09	<2	5	109
25522		<10	<1	0.31	20	0.91	609	<1	0.17	17	380	12	0.23	2	6	176
25523		<10	1	0.29	40	0.49	788	2	0.15	8	370	20	0.14	<2	5	128
25524		10	<1	0.13	<10	0.84	507	87	0.09	37	570	98	0.25	8	5	43
25525		<10	<1	0.16	20	0.50	274	<1	0.10	45	520	11	0.09	<2	3	93
25526		<10	<1	0.29	10	0.60	392	2	0.21	35	750	19	0.19	<2	4	162
25527		<10	<1	0.28	<10	0.46	335	4	0.15	18	900	14	0.26	<2	4	428
25528		<10	<1	0.20	10	0.75	449	1	0.13	39	630	11	0.19	<2	4	224
25529		<10	<1	0.29	20	0.58	521	2	0.24	43	710	19	0.15	<2	5	101
25530		10	<1	0.26	20	0.67	333	1	0.13	38	380	17	0.05	<2	6	45
25531		10	<1	0.30	20	0.69	335	1	0.12	33	370	14	0.26	<2	8	35
25532		10	<1	0.28	30	0.61	271	1	0.14	37	560	20	0.07	<2	7	56
25533		<10	<1	0.18	20	0.29	361	1	0.09	28	430	14	0.03	<2	5	44
25534		<10	<1	0.21	20	0.29	318	1	0.13	38	580	21	0.03	<2	5	67
25535		<10	<1	0.13	20	1.38	457	1	0.05	29	910	14	0.06	<2	4	121
25536		<10	<1	0.24	30	0.38	374	1	0.15	39	2900	20	0.03	<2	6	99
25537		<10	<1	0.23	30	0.41	626	2	0.18	44	1020	24	0.06	2	7	97
25538		10	<1	0.24	10	1.35	792	1	0.18	60	950	13	0.13	<2	7	146
25539		<10	<1	0.23	10	1.47	952	1	0.15	60	700	16	0.10	<2	6	173
25540		10	<1	0.27	10	1.21	695	1	0.20	60	690	16	0.08	<2	7	108

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

Finalized Date: 10-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094233

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Th	Ti	Tl	U	V	W	Zn
	Units	ppm	%	ppm	ppm	ppm	ppm	ppm
	LOR	20	0.01	10	10	1	10	2
25501		<20	<0.01	<10	<10	27	<10	209
25502		<20	<0.01	<10	<10	24	<10	111
25503		<20	<0.01	<10	<10	35	<10	207
25504		<20	<0.01	<10	<10	50	<10	61
25505		<20	<0.01	<10	<10	29	<10	204
25506		<20	<0.01	<10	<10	28	<10	158
25507		<20	<0.01	<10	<10	22	<10	92
25508		<20	<0.01	<10	<10	26	<10	130
25509		<20	<0.01	<10	<10	35	<10	156
25510		<20	<0.01	<10	<10	30	<10	142
25511		<20	0.14	<10	<10	63	10	200
25512		<20	<0.01	<10	<10	22	<10	163
25513		<20	<0.01	<10	<10	17	<10	167
25514		<20	<0.01	<10	<10	24	<10	100
25515		<20	<0.01	<10	<10	25	<10	74
25516		<20	<0.01	<10	<10	33	<10	57
25517		<20	<0.01	<10	<10	25	<10	72
25518		<20	0.03	<10	<10	41	<10	67
25519		<20	<0.01	<10	<10	46	<10	55
25520		<20	<0.01	<10	<10	43	<10	52
25521		<20	<0.01	<10	<10	43	<10	57
25522		<20	<0.01	<10	<10	21	<10	60
25523		<20	<0.01	<10	<10	13	<10	129
25524		<20	0.13	<10	<10	63	10	198
25525		<20	<0.01	<10	<10	17	<10	45
25526		<20	<0.01	<10	<10	26	<10	114
25527		<20	<0.01	<10	<10	22	<10	85
25528		<20	<0.01	<10	<10	23	<10	51
25529		<20	0.01	<10	<10	39	<10	130
25530		<20	0.03	<10	<10	44	<10	108
25531		<20	0.06	<10	<10	49	<10	94
25532		<20	0.03	<10	<10	47	<10	107
25533		<20	0.02	<10	<10	29	<10	113
25534		<20	0.01	<10	<10	32	<10	146
25535		<20	0.06	<10	<10	63	<10	65
25536		<20	0.02	<10	<10	42	<10	144
25537		<20	0.01	<10	<10	40	<10	154
25538		<20	<0.01	<10	<10	45	<10	87
25539		<20	<0.01	<10	<10	31	<10	84
25540		<20	<0.01	<10	<10	39	<10	90

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

Finalized Date: 10-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094233

Sample Description	Method	WEI-21	Au-AA23	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu	Fe
	Units	kg	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	%
	LOR	0.02	0.005	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1	0.01
25541		4.44	<0.005	<0.2	1.29	13	<10	250	0.8	<2	2.05	<0.5	11	35	24	2.90
25542		2.00	<0.005	0.2	1.46	13	<10	280	0.8	<2	2.02	<0.5	13	50	30	3.08
25543		0.10	9.29	0.6	1.54	4150	<10	60	0.5	<2	0.84	<0.5	14	70	69	3.62
25544		3.22	0.005	<0.2	1.19	9	<10	350	1.3	2	1.68	<0.5	19	27	25	5.82
25545		3.68	<0.005	<0.2	1.31	14	<10	260	0.9	<2	1.51	0.5	15	42	39	3.87
25546		4.28	0.006	<0.2	1.43	15	<10	280	1.0	<2	1.23	0.5	16	43	40	3.97
25547		3.94	0.006	0.2	1.38	11	<10	250	0.8	<2	1.55	<0.5	15	45	35	3.37
25548		3.42	<0.005	<0.2	1.11	15	<10	270	0.8	<2	2.10	<0.5	12	34	31	3.51
25549		4.56	<0.005	<0.2	0.82	9	<10	330	1.4	<2	2.34	<0.5	20	28	22	5.90
25550		5.88	0.019	0.2	0.78	12	<10	280	1.4	<2	2.88	<0.5	21	24	22	5.73
25551		3.88	0.005	<0.2	0.65	8	<10	340	1.1	<2	2.28	<0.5	16	19	27	3.93
25552		3.98	0.005	0.2	0.53	14	<10	210	0.5	<2	1.40	<0.5	8	12	25	2.85
25553		4.38	<0.005	0.2	0.72	5	<10	220	0.5	<2	0.75	<0.5	10	16	26	2.64
25554		0.10	0.988	10.9	1.74	475	<10	110	<0.5	<2	0.85	1.4	9	39	280	3.30
25555		2.88	<0.005	0.2	0.94	12	<10	190	0.5	<2	0.98	<0.5	10	34	29	2.77
25556		4.64	<0.005	<0.2	0.80	10	<10	350	1.2	<2	0.67	<0.5	9	14	23	3.39
25557		3.70	<0.005	<0.2	0.60	5	<10	310	1.0	<2	0.51	<0.5	10	11	23	2.93
25558		0.50	<0.005	<0.2	1.45	7	<10	280	<0.5	<2	2.78	0.7	10	47	26	2.43
25559		4.04	<0.005	<0.2	0.48	7	<10	300	0.6	<2	0.70	<0.5	8	9	17	1.95
25560		4.16	0.005	<0.2	0.56	10	<10	320	1.0	<2	0.42	<0.5	11	10	27	2.40
25561		3.76	<0.005	<0.2	2.22	9	<10	250	1.8	<2	1.26	1.3	20	20	29	6.61
25562		2.82	0.006	<0.2	1.85	12	<10	190	1.4	<2	0.75	0.6	16	14	24	4.26
25563		4.36	<0.005	<0.2	2.17	33	<10	230	1.8	<2	0.93	0.6	33	13	24	4.25
25564		3.24	<0.005	<0.2	2.91	12	<10	200	1.5	<2	3.23	<0.5	30	96	31	5.77
25565		2.86	<0.005	<0.2	2.79	12	<10	210	1.2	<2	5.28	<0.5	24	85	27	5.56
25566		2.38	<0.005	<0.2	2.88	15	<10	130	1.2	<2	3.70	<0.5	25	79	27	6.16
25567		2.00	<0.005	<0.2	2.50	5	<10	80	1.7	<2	2.27	0.5	14	49	25	3.78
25568		3.60	<0.005	0.3	2.89	11	<10	140	1.5	<2	4.73	<0.5	25	84	35	6.66
25569		4.84	<0.005	<0.2	0.83	12	<10	60	0.6	<2	1.07	<0.5	2	7	4	2.70
25570		0.10	1.170	9.3	1.68	448	<10	110	<0.5	<2	0.84	1.4	9	38	268	3.25
25571		2.46	<0.005	<0.2	0.80	13	<10	50	0.5	<2	1.04	<0.5	2	5	5	2.48
25572		2.68	<0.005	<0.2	1.03	3	<10	60	0.7	<2	0.56	<0.5	2	4	4	2.95
25573		5.02	<0.005	<0.2	0.84	5	<10	60	0.6	2	0.65	<0.5	2	7	5	2.37
25574		4.34	<0.005	<0.2	1.01	8	<10	60	1.1	<2	0.71	<0.5	4	12	3	2.70
25575		3.32	<0.005	<0.2	0.64	7	<10	50	0.7	<2	1.31	<0.5	1	4	4	2.46
25576		3.30	<0.005	<0.2	0.50	10	<10	40	0.6	<2	0.97	<0.5	2	3	4	2.34
25577		0.88	<0.005	0.3	1.17	11	<10	540	<0.5	<2	2.96	0.9	8	29	33	2.28
25578		5.12	<0.005	<0.2	0.72	6	<10	40	0.7	<2	1.16	<0.5	1	4	3	2.52
25579		3.48	0.009	<0.2	0.83	7	<10	50	1.1	<2	0.93	<0.5	1	3	4	2.63
25580		4.30	<0.005	0.2	0.77	11	<10	50	0.9	<2	0.89	<0.5	1	2	3	2.48

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

Finalized Date: 10-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094233

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc	Sr
	Units	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm	ppm
	LOR	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1	1
25541		<10	<1	0.23	10	1.11	749	1	0.15	46	580	13	0.09	<2	6	120
25542		<10	<1	0.26	10	1.19	669	1	0.16	62	620	15	0.08	<2	6	118
25543		10	<1	0.16	10	0.87	398	6	0.07	63	490	7	0.88	36	5	40
25544		<10	<1	0.27	30	1.30	1210	2	0.28	36	1780	9	0.04	<2	9	146
25545		<10	<1	0.24	10	1.16	729	2	0.18	64	1040	13	0.11	<2	7	109
25546		<10	<1	0.28	10	1.21	642	1	0.18	73	840	17	0.10	<2	7	92
25547		<10	<1	0.26	10	1.26	676	1	0.17	68	600	16	0.08	<2	7	109
25548		<10	<1	0.26	10	1.29	778	1	0.18	59	700	16	0.09	<2	7	126
25549		<10	<1	0.22	20	1.59	938	2	0.21	31	1800	7	0.08	<2	9	161
25550		<10	<1	0.21	20	1.88	1050	2	0.22	30	1570	8	0.07	<2	9	183
25551		<10	<1	0.25	10	1.33	646	1	0.19	43	830	13	0.04	<2	7	187
25552		<10	<1	0.20	10	0.89	613	1	0.12	33	560	11	0.17	<2	5	122
25553		<10	<1	0.20	10	0.69	389	1	0.15	39	430	12	0.06	<2	4	75
25554		10	<1	0.13	<10	0.84	504	86	0.09	38	570	97	0.26	9	5	42
25555		<10	<1	0.19	10	0.74	490	2	0.12	50	490	12	0.14	<2	4	75
25556		<10	<1	0.24	10	0.52	607	1	0.20	32	550	20	0.02	<2	4	87
25557		<10	<1	0.24	10	0.48	427	1	0.19	32	530	18	0.02	<2	4	83
25558		10	<1	0.15	10	1.17	618	1	0.05	40	990	15	0.04	<2	4	91
25559		<10	<1	0.20	10	0.42	270	1	0.14	27	350	13	0.05	<2	3	94
25560		<10	1	0.24	10	0.44	303	2	0.18	35	380	17	0.04	<2	4	74
25561		10	1	0.27	20	0.86	1555	4	0.08	37	1770	24	0.22	<2	4	99
25562		10	<1	0.30	30	0.63	930	2	0.06	24	860	19	0.13	<2	3	60
25563		10	1	0.33	30	0.66	319	2	0.07	30	1570	18	0.08	<2	4	76
25564		10	<1	0.23	30	3.24	936	2	0.14	91	1680	2	0.10	<2	14	248
25565		10	<1	0.14	20	3.03	1030	2	0.13	65	1870	12	0.15	<2	12	437
25566		10	<1	0.11	20	2.90	1105	3	0.13	38	2870	11	0.21	<2	11	275
25567		10	1	0.24	40	1.93	635	2	0.05	32	800	19	0.09	<2	5	133
25568		10	1	0.12	20	2.74	1210	3	0.07	34	2690	2	0.25	<2	12	387
25569		10	<1	0.20	30	0.17	588	2	0.05	1	280	21	0.64	<2	2	48
25570		10	<1	0.14	<10	0.85	483	85	0.08	34	570	96	0.26	4	5	41
25571		10	1	0.17	30	0.13	600	2	0.04	<1	250	20	0.38	<2	2	45
25572		10	<1	0.22	40	0.17	595	3	0.03	<1	270	24	0.20	<2	2	26
25573		10	<1	0.21	40	0.14	504	3	0.04	1	210	23	0.18	<2	2	32
25574		10	<1	0.24	40	0.23	572	4	0.03	9	350	28	0.15	<2	2	32
25575		<10	<1	0.23	30	0.10	739	3	0.03	<1	180	29	0.46	<2	1	45
25576		<10	<1	0.22	20	0.08	622	3	0.03	<1	160	24	0.63	<2	1	32
25577		<10	1	0.15	10	1.10	598	1	0.04	32	870	13	0.06	<2	4	106
25578		10	1	0.22	30	0.09	678	4	0.04	<1	170	22	0.44	<2	1	38
25579		<10	<1	0.27	30	0.10	716	4	0.03	<1	180	23	0.51	<2	1	35
25580		10	<1	0.26	30	0.09	624	5	0.03	<1	170	36	0.59	<2	1	34

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

Finalized Date: 10-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094233

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Th	Ti	Tl	U	V	W	Zn
	Units	ppm	%	ppm	ppm	ppm	ppm	ppm
	LOR	20	0.01	10	10	1	10	2
25541		<20	<0.01	<10	<10	31	<10	80
25542		<20	<0.01	<10	<10	33	<10	83
25543		<20	0.11	<10	<10	53	40	52
25544		<20	<0.01	<10	<10	54	<10	96
25545		<20	<0.01	<10	<10	41	<10	99
25546		<20	<0.01	<10	<10	41	<10	108
25547		<20	<0.01	<10	<10	35	<10	91
25548		<20	<0.01	<10	<10	31	<10	90
25549		<20	<0.01	<10	<10	66	<10	85
25550		<20	<0.01	<10	<10	58	<10	90
25551		<20	<0.01	<10	<10	31	<10	82
25552		<20	<0.01	<10	<10	17	<10	58
25553		<20	<0.01	<10	<10	17	<10	73
25554		<20	0.13	<10	<10	62	10	195
25555		<20	<0.01	<10	<10	17	<10	69
25556		<20	<0.01	<10	<10	14	<10	97
25557		<20	<0.01	<10	<10	13	<10	86
25558		<20	0.12	<10	<10	58	<10	76
25559		<20	<0.01	<10	<10	10	<10	63
25560		<20	<0.01	<10	<10	12	<10	102
25561		<20	<0.01	<10	<10	41	<10	163
25562		<20	<0.01	<10	<10	37	<10	110
25563		<20	0.01	<10	<10	39	<10	136
25564		<20	0.08	<10	<10	149	<10	76
25565		<20	0.09	<10	<10	128	<10	77
25566		<20	0.16	<10	<10	122	<10	81
25567		<20	0.01	<10	<10	50	<10	89
25568		<20	0.02	<10	<10	113	<10	78
25569		<20	<0.01	<10	<10	6	<10	102
25570		<20	0.13	<10	<10	60	10	192
25571		<20	<0.01	<10	<10	4	<10	96
25572		<20	<0.01	<10	<10	5	<10	110
25573		<20	<0.01	<10	<10	6	<10	97
25574		20	<0.01	<10	<10	13	<10	125
25575		<20	<0.01	<10	<10	3	<10	117
25576		<20	<0.01	<10	<10	2	<10	107
25577		<20	0.08	<10	<10	49	<10	91
25578		<20	<0.01	<10	<10	3	<10	102
25579		20	<0.01	<10	<10	3	<10	101
25580		20	<0.01	<10	<10	2	<10	104

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

Finalized Date: 10-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094233

Sample Description	Method	WEI-21	Au-AA23	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu	Fe
	Units	kg	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	%
	LOR	0.02	0.005	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1	0.01
25581		4.32	<0.005	<0.2	0.75	6	<10	50	1.0	<2	0.94	<0.5	1	4	4	2.40
25582		4.32	0.020	0.3	0.38	37	<10	70	1.0	<2	0.32	<0.5	1	1	7	2.49
25583		1.26	0.020	0.2	0.38	50	<10	100	1.0	<2	0.56	<0.5	3	2	14	2.81
25584		5.00	<0.005	<0.2	1.42	18	<10	130	2.4	<2	4.27	<0.5	22	36	24	5.44
25585		4.12	0.005	<0.2	0.30	17	<10	50	0.6	<2	0.27	<0.5	1	2	4	2.53
25586		5.44	0.030	<0.2	0.52	32	<10	50	0.8	<2	0.51	<0.5	5	6	8	3.14
25587		0.10	9.74	0.4	1.52	4030	<10	60	0.5	<2	0.84	<0.5	14	71	67	3.64
25588		4.44	0.011	<0.2	0.35	38	<10	60	0.8	<2	0.49	<0.5	4	4	15	2.85
25589		0.80	<0.005	<0.2	1.24	4	<10	340	<0.5	<2	2.56	0.8	11	46	25	2.43
25590		8.40	0.013	<0.2	0.32	31	<10	50	0.6	<2	0.71	<0.5	2	5	6	2.51
25591		4.20	0.044	0.2	0.41	39	<10	60	0.7	<2	0.74	<0.5	1	3	4	2.53
25592		2.52	<0.005	<0.2	0.40	14	<10	50	0.5	<2	0.71	<0.5	1	4	4	2.74
25593		3.84	0.008	<0.2	0.42	23	<10	50	0.6	<2	0.75	<0.5	1	3	5	2.47
25594		4.28	0.025	<0.2	0.33	46	<10	50	1.0	<2	0.88	<0.5	2	2	7	2.02
25595		4.92	0.018	<0.2	0.40	67	<10	60	1.1	<2	0.98	<0.5	2	1	11	2.46
25596		4.28	0.011	0.2	0.42	61	<10	50	0.9	<2	1.00	<0.5	2	3	10	2.58
25597		4.10	0.006	0.2	0.44	51	<10	50	0.7	<2	1.00	<0.5	2	4	7	2.43
25598		4.28	0.012	<0.2	0.47	63	<10	50	0.9	<2	1.07	<0.5	2	2	5	2.47
25599		4.84	0.015	<0.2	0.47	68	<10	50	0.7	<2	0.98	<0.5	2	3	4	2.46
25600		3.10	0.011	<0.2	0.27	48	<10	50	0.5	<2	0.80	<0.5	1	2	3	1.77
25601		3.36	0.011	0.2	0.42	50	<10	50	0.8	<2	2.05	<0.5	1	3	2	1.99
25602		4.54	0.014	0.2	0.40	53	<10	60	0.9	<2	1.36	<0.5	2	2	4	2.47
25603		4.36	0.006	<0.2	0.46	37	<10	60	0.9	<2	0.98	<0.5	2	2	6	2.66
25604		4.06	0.039	0.3	0.37	92	<10	60	1.0	<2	1.12	<0.5	2	2	4	2.61
25605		0.10	9.83	0.6	1.47	3950	<10	60	0.5	<2	0.82	<0.5	13	69	65	3.55
25606		4.08	0.041	0.2	0.24	113	<10	60	1.1	<2	1.08	<0.5	1	1	5	2.72
25607		4.34	0.025	<0.2	0.46	37	<10	60	0.8	<2	1.08	<0.5	2	3	7	2.52
25608		1.42	0.012	<0.2	0.84	39	<10	170	2.6	<2	1.67	<0.5	11	10	16	3.29
25609		0.76	<0.005	<0.2	1.29	5	<10	710	<0.5	<2	2.78	0.8	9	63	25	2.23
25610		4.28	<0.005	<0.2	2.91	16	<10	130	2.0	<2	4.39	<0.5	27	39	22	6.67
25611		2.14	<0.005	<0.2	1.22	17	<10	240	3.6	<2	0.58	0.5	12	11	21	1.96
25612		1.40	<0.005	<0.2	2.68	46	<10	140	2.2	2	3.46	<0.5	25	38	25	6.56
25613		4.12	0.006	<0.2	0.58	19	<10	100	1.2	<2	2.23	<0.5	10	7	12	3.61
25614		4.70	<0.005	<0.2	0.81	43	<10	120	2.0	<2	4.61	<0.5	22	11	16	6.06
25615		3.92	<0.005	<0.2	0.82	26	<10	140	2.5	<2	4.69	<0.5	25	8	21	6.97
25616		3.58	<0.005	<0.2	1.09	23	<10	150	2.6	<2	4.15	<0.5	20	16	21	5.48
25617		2.96	<0.005	<0.2	0.60	7	<10	40	0.5	<2	0.84	<0.5	2	6	3	2.73
25618		4.02	<0.005	<0.2	0.78	13	<10	40	0.5	<2	0.85	<0.5	2	5	3	2.92
25619		3.84	0.005	0.2	0.48	33	<10	50	0.7	<2	0.79	<0.5	2	4	4	2.77
25620		2.84	<0.005	<0.2	0.60	14	<10	50	0.5	<2	0.73	<0.5	2	5	3	2.68

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

Finalized Date: 10-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094233

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc	Sr
	Units	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm	ppm
	LOR	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1	1
25581		<10	<1	0.29	30	0.09	626	4	0.03	<1	170	34	0.54	<2	1	47
25582		<10	<1	0.28	20	0.09	426	4	0.04	<1	180	20	1.38	3	1	22
25583		<10	<1	0.28	20	0.16	570	3	0.05	3	260	19	1.22	5	1	37
25584		10	<1	0.30	30	2.05	1145	3	0.10	32	1840	6	0.16	8	10	259
25585		<10	1	0.22	30	0.14	589	3	0.05	1	190	12	0.44	<2	1	18
25586		<10	<1	0.25	20	0.27	569	3	0.04	5	650	13	1.05	<2	1	29
25587		<10	<1	0.17	10	0.91	387	6	0.06	60	480	6	0.88	36	5	40
25588		<10	1	0.26	20	0.28	622	3	0.04	3	500	32	0.40	<2	1	32
25589		<10	1	0.13	10	1.38	515	1	0.04	53	920	12	0.05	<2	4	88
25590		<10	<1	0.23	20	0.11	566	3	0.04	<1	180	21	0.56	<2	1	27
25591		<10	<1	0.26	30	0.10	570	3	0.04	<1	170	23	0.87	<2	1	40
25592		<10	1	0.20	30	0.13	668	3	0.05	<1	220	30	0.36	<2	1	33
25593		<10	1	0.22	30	0.12	587	3	0.04	<1	200	20	0.58	2	1	36
25594		<10	<1	0.29	20	0.07	478	3	0.03	<1	170	16	1.17	<2	1	54
25595		<10	1	0.33	20	0.06	599	5	0.03	1	220	25	1.70	<2	1	58
25596		<10	<1	0.31	20	0.07	612	3	0.03	1	220	27	1.62	<2	1	49
25597		<10	1	0.28	20	0.08	641	4	0.04	<1	210	12	1.21	<2	1	46
25598		<10	<1	0.30	20	0.05	529	5	0.03	1	220	20	1.82	<2	1	61
25599		<10	1	0.30	20	0.07	640	5	0.04	<1	190	24	1.39	<2	1	49
25600		<10	1	0.23	20	0.05	486	2	0.04	<1	170	14	0.97	<2	1	37
25601		<10	<1	0.30	20	0.06	711	3	0.04	<1	200	23	1.06	<2	1	123
25602		<10	<1	0.32	20	0.07	700	4	0.04	<1	220	22	1.32	3	1	74
25603		<10	<1	0.30	30	0.09	704	5	0.04	2	210	28	0.92	<2	1	52
25604		<10	<1	0.32	20	0.04	422	4	0.04	<1	190	27	2.27	<2	1	64
25605		<10	1	0.16	10	0.88	377	6	0.05	59	470	5	0.87	33	5	39
25606		<10	<1	0.24	10	0.02	306	7	0.04	1	220	27	2.86	2	1	64
25607		<10	<1	0.26	20	0.07	569	3	0.05	<1	200	21	1.29	3	1	62
25608		<10	1	0.32	30	0.65	754	3	0.11	15	880	15	0.71	3	4	115
25609		<10	<1	0.18	10	1.32	606	1	0.05	43	630	13	0.11	<2	5	121
25610		10	1	0.24	20	2.37	1115	2	0.07	36	2230	2	0.18	<2	8	294
25611		<10	1	0.34	40	0.35	279	2	0.12	28	510	13	0.02	<2	3	69
25612		10	1	0.24	20	1.94	947	3	0.08	36	2040	14	1.28	<2	7	239
25613		<10	1	0.27	20	0.78	930	3	0.06	13	860	9	0.37	9	4	137
25614		<10	<1	0.38	20	1.74	1185	3	0.07	26	2530	4	0.28	18	7	291
25615		<10	<1	0.44	20	2.01	1290	3	0.06	26	2970	5	0.30	19	8	304
25616		<10	<1	0.35	30	1.69	1155	3	0.08	24	2030	7	0.33	8	7	261
25617		10	<1	0.17	40	0.16	654	3	0.05	<1	270	22	0.22	<2	2	28
25618		10	1	0.18	30	0.15	655	3	0.06	<1	260	24	0.59	<2	2	29
25619		<10	1	0.22	30	0.11	594	3	0.05	<1	220	27	0.93	<2	2	33
25620		<10	1	0.19	30	0.12	578	3	0.05	<1	230	27	0.59	<2	2	24

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

Finalized Date: 10-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094233

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Th	Ti	Tl	U	V	W	Zn
	Units	ppm	%	ppm	ppm	ppm	ppm	ppm
	LOR	20	0.01	10	10	1	10	2
25581		<20	<0.01	<10	<10	2	<10	108
25582		<20	<0.01	<10	<10	1	<10	102
25583		<20	<0.01	<10	<10	2	<10	102
25584		<20	0.02	<10	<10	65	<10	75
25585		<20	<0.01	<10	<10	1	<10	104
25586		<20	<0.01	<10	<10	6	<10	97
25587		<20	0.11	<10	<10	52	40	51
25588		<20	<0.01	<10	<10	3	<10	103
25589		<20	0.12	<10	<10	58	<10	79
25590		<20	<0.01	<10	<10	1	<10	104
25591		<20	<0.01	<10	<10	1	<10	106
25592		<20	<0.01	<10	<10	2	<10	118
25593		<20	<0.01	<10	<10	2	<10	109
25594		<20	<0.01	<10	<10	1	<10	89
25595		<20	<0.01	<10	<10	1	<10	116
25596		<20	<0.01	<10	<10	1	<10	112
25597		<20	<0.01	<10	<10	2	<10	101
25598		<20	<0.01	<10	<10	1	<10	111
25599		<20	<0.01	<10	<10	1	<10	105
25600		<20	<0.01	<10	<10	1	<10	87
25601		<20	<0.01	<10	<10	1	<10	101
25602		<20	<0.01	<10	<10	1	<10	113
25603		20	<0.01	<10	<10	2	<10	113
25604		<20	<0.01	<10	<10	1	<10	111
25605		<20	0.11	<10	<10	51	40	50
25606		<20	<0.01	<10	<10	<1	<10	108
25607		<20	<0.01	<10	<10	1	<10	106
25608		<20	<0.01	10	<10	16	<10	105
25609		<20	0.09	<10	<10	45	<10	72
25610		<20	0.01	<10	<10	94	<10	85
25611		<20	<0.01	<10	<10	17	<10	137
25612		<20	<0.01	<10	<10	87	<10	105
25613		<20	<0.01	<10	<10	11	<10	86
25614		<20	<0.01	<10	<10	23	<10	82
25615		<20	<0.01	<10	<10	25	<10	96
25616		<20	<0.01	<10	<10	29	<10	87
25617		<20	<0.01	<10	<10	5	<10	104
25618		<20	<0.01	<10	<10	5	<10	111
25619		<20	<0.01	<10	<10	2	<10	113
25620		<20	<0.01	<10	<10	3	<10	103

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd.
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

Finalized Date: 10-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094233

Sample Description	Method	WEI-21	Au-AA23	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt.	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu	Fe
	Units	kg	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	%
	LOR	0.02	0.005	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1	0.01
25621		4.00	<0.005	<0.2	0.48	13	<10	40	0.5	<2	0.61	<0.5	2	5	3	2.37
25622		3.88	<0.005	<0.2	0.63	17	<10	40	<0.5	<2	0.71	<0.5	2	6	11	2.66
25623		3.50	<0.005	<0.2	0.65	16	<10	40	<0.5	<2	0.92	<0.5	1	4	4	2.64
25624		3.66	<0.005	<0.2	0.82	7	<10	40	<0.5	<2	1.14	<0.5	1	6	3	2.70
25625		3.58	<0.005	0.2	0.79	10	<10	40	<0.5	<2	1.09	<0.5	1	6	3	2.59
25626		2.36	<0.005	<0.2	0.77	11	<10	40	<0.5	<2	0.82	<0.5	2	6	3	2.54
25627		0.10	1.095	9.0	1.69	460	<10	110	<0.5	<2	0.85	1.4	9	39	277	3.25
25628		4.90	<0.005	<0.2	0.76	21	<10	40	<0.5	<2	1.01	<0.5	2	5	3	2.72
25629		4.06	0.010	<0.2	0.65	24	<10	50	<0.5	<2	0.99	<0.5	2	4	6	2.81
25630		1.76	0.015	0.2	0.52	38	<10	90	0.7	<2	0.62	<0.5	2	2	5	2.57
25631		3.38	0.005	0.3	2.09	23	<10	410	1.5	<2	1.85	0.5	15	36	27	3.82
25632		0.88	<0.005	<0.2	1.30	8	<10	390	<0.5	<2	3.74	1.2	8	35	53	2.24
25633		3.56	0.025	<0.2	1.11	7	<10	510	1.1	<2	2.24	<0.5	10	13	19	2.71
25634		3.38	<0.005	<0.2	1.07	6	<10	610	0.7	<2	3.29	<0.5	8	18	18	2.16
25635		4.02	<0.005	<0.2	2.18	16	<10	530	1.3	<2	2.26	<0.5	14	41	27	3.82
25636		3.76	<0.005	<0.2	2.29	17	<10	630	1.3	<2	2.23	<0.5	14	40	28	3.64
25637		3.40	<0.005	<0.2	2.38	20	<10	550	1.4	<2	1.90	<0.5	14	44	29	3.62
25638		2.72	<0.005	<0.2	2.11	17	<10	520	1.3	<2	2.00	<0.5	14	39	28	3.39
25639		3.12	<0.005	<0.2	2.30	18	<10	560	1.5	<2	1.39	<0.5	13	37	28	3.51
25640		3.52	<0.005	<0.2	2.15	19	<10	610	1.4	<2	2.53	<0.5	13	36	27	3.30
25641		4.72	<0.005	<0.2	2.20	17	<10	530	1.3	<2	2.34	<0.5	13	38	26	3.30
25642		4.24	<0.005	<0.2	0.71	6	<10	360	1.1	<2	0.44	<0.5	11	15	31	2.97
25643		3.58	<0.005	<0.2	0.63	8	<10	270	0.8	<2	0.66	<0.5	9	12	21	2.26
25644		3.52	<0.005	<0.2	0.66	5	<10	310	1.0	<2	0.60	<0.5	7	12	24	2.55
25645		1.90	<0.005	<0.2	0.75	10	<10	300	1.0	<2	0.39	<0.5	9	15	21	2.83
25646		4.64	<0.005	<0.2	0.75	10	<10	330	1.1	<2	0.50	0.5	13	15	26	2.55
25647		2.34	<0.005	<0.2	0.61	14	<10	300	0.9	<2	0.53	<0.5	9	12	22	2.28
25648		2.70	<0.005	<0.2	0.73	25	<10	360	1.2	<2	0.38	0.5	12	14	31	2.43
25649		4.32	<0.005	<0.2	0.73	13	<10	330	1.1	<2	0.47	<0.5	9	15	25	2.73
25650		4.04	<0.005	<0.2	0.74	15	<10	350	1.1	<2	0.59	0.5	11	13	26	2.98

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

Finalized Date: 10-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094233

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc	Sr
	Units	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm	ppm
	LOR	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1	1
25621		<10	1	0.19	30	0.11	511	3	0.04	<1	220	22	0.52	<2	1	24
25622		<10	<1	0.18	30	0.12	563	3	0.05	<1	230	25	0.64	<2	1	28
25623		10	<1	0.19	30	0.12	611	3	0.04	<1	210	23	0.67	<2	2	40
25624		10	1	0.16	40	0.13	658	2	0.06	<1	230	24	0.30	<2	2	31
25625		10	<1	0.15	30	0.12	605	3	0.05	<1	210	24	0.41	<2	2	32
25626		10	<1	0.15	40	0.12	558	3	0.05	<1	210	22	0.44	<2	2	26
25627		<10	1	0.14	<10	0.85	483	84	0.08	35	560	96	0.26	6	5	41
25628		10	1	0.16	30	0.14	676	3	0.05	<1	230	24	0.56	<2	2	45
25629		<10	1	0.22	30	0.12	673	3	0.06	<1	220	25	0.89	2	2	55
25630		<10	<1	0.27	30	0.14	715	4	0.06	1	250	24	0.75	<2	1	43
25631		10	1	0.32	20	0.98	670	2	0.29	37	860	23	0.19	<2	6	178
25632		<10	<1	0.14	10	1.20	492	1	0.08	35	730	13	0.05	<2	4	132
25633		<10	1	0.36	20	0.77	649	<1	0.19	16	500	23	0.26	<2	5	172
25634		<10	<1	0.32	30	0.69	629	<1	0.15	16	420	20	0.24	<2	4	253
25635		<10	<1	0.32	20	1.11	787	1	0.31	40	990	13	0.16	<2	7	222
25636		10	<1	0.31	20	1.09	726	1	0.31	45	910	15	0.15	<2	7	228
25637		10	<1	0.35	20	1.07	685	1	0.32	48	870	21	0.17	<2	7	207
25638		10	<1	0.32	20	0.94	702	1	0.30	45	820	16	0.13	<2	6	218
25639		10	1	0.36	30	0.96	625	1	0.35	44	840	17	0.14	<2	6	178
25640		10	<1	0.35	20	0.91	777	1	0.30	43	790	14	0.15	2	6	253
25641		10	1	0.33	20	0.99	693	1	0.30	42	870	14	0.14	2	6	234
25642		<10	<1	0.27	10	0.51	424	1	0.20	37	680	17	0.03	<2	5	78
25643		<10	<1	0.23	10	0.45	289	1	0.17	30	510	14	0.03	<2	4	88
25644		<10	<1	0.27	10	0.45	324	<1	0.17	27	550	16	0.02	<2	4	89
25645		<10	<1	0.26	10	0.47	349	<1	0.18	30	290	14	0.04	<2	4	64
25646		<10	<1	0.26	10	0.45	391	1	0.19	38	490	14	0.04	2	4	76
25647		<10	<1	0.23	10	0.40	345	1	0.17	30	440	13	0.03	<2	3	74
25648		<10	<1	0.27	10	0.43	305	1	0.22	45	500	17	0.06	2	4	77
25649		<10	<1	0.27	10	0.46	394	<1	0.20	33	450	17	0.03	2	4	79
25650		<10	<1	0.27	10	0.50	465	1	0.21	39	750	18	0.03	<2	5	91

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone. 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
830 - 555 BURRARD STREET
VANCOUVER BC V6C 2G8

Finalized Date: 10-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094233

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Th	Ti	Tl	U	V	W	Zn
	Units	ppm	%	ppm	ppm	ppm	ppm	ppm
	LOR	20	0 01	10	10	1	10	2
25621		<20	<0.01	<10	<10	3	<10	93
25622		<20	<0.01	<10	<10	4	<10	97
25623		<20	<0.01	<10	<10	4	<10	102
25624		<20	<0.01	<10	<10	5	<10	104
25625		<20	<0.01	<10	<10	4	<10	99
25626		<20	<0.01	<10	<10	5	<10	99
25627		<20	0.13	<10	<10	61	10	196
25628		<20	<0.01	<10	<10	4	<10	104
25629		<20	<0.01	<10	<10	3	<10	103
25630		<20	<0.01	<10	<10	2	<10	100
25631		<20	<0.01	<10	<10	39	<10	127
25632		<20	0.08	<10	<10	47	<10	83
25633		20	<0.01	<10	<10	16	<10	53
25634		20	<0.01	<10	<10	15	<10	50
25635		<20	<0.01	<10	<10	41	<10	93
25636		<20	<0.01	<10	<10	42	<10	95
25637		<20	<0.01	<10	<10	41	<10	99
25638		<20	<0.01	<10	<10	36	<10	100
25639		<20	<0.01	<10	<10	36	<10	102
25640		<20	<0.01	<10	<10	37	<10	98
25641		<20	<0.01	<10	<10	39	<10	93
25642		<20	<0.01	<10	<10	16	<10	100
25643		<20	<0.01	<10	<10	13	<10	75
25644		<20	<0.01	<10	<10	13	<10	84
25645		<20	<0.01	<10	<10	15	<10	84
25646		<20	<0.01	<10	<10	15	<10	98
25647		<20	<0.01	<10	<10	12	<10	76
25648		<20	<0.01	<10	<10	14	<10	109
25649		<20	<0.01	<10	<10	14	<10	91
25650		<20	<0.01	<10	<10	14	<10	98

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax. 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 18-SEP-2009
This copy reported on 28-SEP-2009
Account: EMERES

CERTIFICATE VA09094232

Project: Canyon Gold

P.O. No.:

This report is for 141 Drill Core samples submitted to our lab in Vancouver, BC, Canada on 28-AUG-2009.

The following have access to data associated with this certificate:

SARA PUBLICOVER	SIMON RIDGWAY	

SAMPLE PREPARATION

ALS CODE	DESCRIPTION
WEI-21	Received Sample Weight
LOG-22	Sample login - Rcd w/o BarCode
CRU-QC	Crushing QC Test
PUL-QC	Pulverizing QC Test
CRU-31	Fine crushing - 70% <2mm
SPL-21	Split sample - riffle splitter
PUL-31	Pulverize split to 85% <75 um
LOG-24	Pulp Login - Rcd w/o Barcode

ANALYTICAL PROCEDURES

ALS CODE	DESCRIPTION	INSTRUMENT
ME-ICP41	35 Element Aqua Regia ICP-AES	ICP-AES
Au-AA23	Au 30g FA-AA finish	AAS

To: EMERICK RESOURCES LTD.
ATTN: SIMON RIDGWAY
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

This is the Final Report and supersedes any preliminary report with this certificate number. Results apply to samples as submitted. All pages of this report have been checked and approved for release.

Signature:

Colin Ramshaw, Vancouver Laboratory Manager

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 18-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094232

Sample Description	Method	WEI-21	Au-AA23	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu	Fe
	Units	kg	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	%
	LOR	0.02	0.005	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1	0.01
25651		4.16	<0.005	0.2	1.86	15	<10	440	1.5	<2	1.27	<0.5	16	44	34	3.59
25652		0.10	0.951	9.2	1.68	437	<10	110	<0.5	<2	0.85	1.1	9	37	274	3.23
25653		4.18	0.041	0.3	1.98	9	<10	390	1.3	<2	1.46	<0.5	15	49	35	3.74
25654		3.48	0.007	<0.2	1.96	7	<10	400	1.3	<2	1.37	<0.5	15	52	35	3.75
25655		4.20	<0.005	0.2	1.55	42	<10	320	1.0	<2	1.15	<0.5	12	41	28	2.89
25656		1.38	0.007	0.3	1.67	7	10	430	1.3	<2	1.04	0.5	16	41	34	3.34
25657		3.80	<0.005	0.2	0.83	5	<10	380	1.2	<2	0.33	0.8	13	18	23	2.40
25658		3.74	<0.005	0.3	0.84	6	<10	330	1.2	<2	0.16	1.0	10	17	20	2.47
25659		0.82	<0.005	<0.2	0.75	3	<10	620	<0.5	<2	2.69	0.6	7	21	19	2.01
25660		1.60	<0.005	<0.2	1.35	13	<10	780	1.4	<2	0.63	0.5	5	8	14	2.26
25661		3.50	<0.005	0.2	0.96	2	<10	370	1.1	<2	0.16	0.8	11	16	22	2.64
25662		3.46	<0.005	0.3	0.94	3	<10	380	1.1	<2	0.14	0.8	9	16	21	2.63
25663		2.90	<0.005	0.2	0.96	16	<10	400	1.1	<2	0.29	0.8	10	15	23	2.37
25664		0.10	9.82	0.7	1.40	3840	<10	60	<0.5	<2	0.76	<0.5	13	65	64	3.44
25665		3.34	0.016	0.3	0.94	4	<10	360	1.1	<2	0.11	0.9	15	16	24	2.63
25666		2.92	0.006	0.2	0.93	3	<10	340	1.1	<2	0.11	0.8	15	21	28	2.81
25667		2.74	<0.005	0.2	0.94	6	<10	340	1.1	<2	0.11	0.7	15	21	27	2.97
25668		3.44	<0.005	0.2	0.96	4	<10	360	1.2	<2	0.12	0.8	17	22	28	3.17
25669		2.94	<0.005	0.3	0.91	10	<10	370	1.2	<2	0.21	0.9	14	18	27	3.36
25670		1.26	0.005	0.3	0.80	19	10	560	1.3	<2	0.72	1.4	11	15	36	3.30
25671		2.38	<0.005	0.2	0.91	9	<10	400	1.3	<2	0.28	0.8	15	19	28	3.43
25672		2.98	<0.005	<0.2	0.92	11	<10	430	1.6	<2	1.09	0.7	14	18	30	4.46
25673		2.98	<0.005	0.2	0.94	4	<10	420	1.5	<2	0.44	0.5	15	21	32	4.38
25674		0.82	<0.005	0.3	1.04	9	<10	380	<0.5	<2	2.36	0.5	8	40	23	1.99
25675		3.96	<0.005	0.2	0.71	20	<10	360	1.2	<2	0.24	0.9	13	15	27	2.60
25676		2.54	<0.005	0.3	0.56	<2	10	360	0.8	<2	0.17	0.8	5	9	21	0.87
25677		3.40	<0.005	0.2	0.81	4	<10	320	1.2	<2	0.63	0.7	11	17	18	5.01
25678		3.28	<0.005	<0.2	0.79	3	<10	310	0.9	<2	0.76	0.7	6	17	21	1.43
25679		2.92	<0.005	0.2	0.77	3	<10	290	1.0	<2	0.20	<0.5	9	18	15	2.76
25680		3.58	<0.005	0.2	0.95	<2	<10	290	1.1	<2	0.96	0.5	9	24	28	3.60
25681		3.90	<0.005	0.2	0.88	19	<10	350	1.2	<2	0.92	<0.5	10	16	19	2.84
25682		1.60	<0.005	<0.2	2.85	12	<10	280	1.1	2	2.82	<0.5	28	66	40	7.34
25683		2.70	0.010	0.2	1.62	24	<10	430	2.1	<2	1.03	0.5	16	27	38	4.69
25684		4.04	0.010	<0.2	2.59	29	<10	190	1.5	2	4.72	<0.5	26	117	35	7.13
25685		0.74	<0.005	<0.2	1.24	5	<10	400	<0.5	<2	2.82	0.9	9	56	28	2.33
25686		3.54	<0.005	0.3	2.83	2	<10	200	1.2	<2	3.87	<0.5	29	131	39	7.16
25687		4.20	<0.005	0.3	2.78	4	<10	190	1.3	<2	3.93	<0.5	27	135	37	7.31
25688		4.26	<0.005	0.2	3.30	4	<10	230	1.4	<2	3.49	<0.5	30	144	40	7.64
25689		3.48	<0.005	0.3	2.80	5	<10	190	1.1	<2	3.43	<0.5	26	136	38	7.60
25690		3.88	0.009	0.3	1.63	21	<10	680	3.1	<2	1.40	0.5	17	35	31	4.19

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 18-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094232

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc	Sr
	Units	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm	ppm
	LOR	10	1	0 01	10	0.01	5	1	0.01	1	10	2	0 01	2	1	1
25651		10	<1	0.27	20	0.88	601	1	0.30	51	840	18	0.10	<2	7	132
25652		10	<1	0.13	10	0.84	495	80	0.09	37	540	92	0.25	7	5	42
25653		10	<1	0.26	20	1.01	633	1	0.28	50	770	17	0.12	<2	8	123
25654		10	<1	0.25	20	0.97	613	1	0.28	51	720	15	0.09	<2	8	124
25655		10	<1	0.21	20	0.79	469	1	0.21	41	580	13	0.21	<2	6	101
25656		10	<1	0.24	20	0.80	534	1	0.27	50	700	18	0.08	<2	7	114
25657		<10	<1	0.17	20	0.29	322	2	0.16	42	940	20	0.03	<2	5	91
25658		<10	<1	0.16	20	0.28	330	1	0.13	30	460	20	0.02	<2	5	77
25659		<10	<1	0.11	10	1.20	484	1	0.02	28	720	26	0.05	<2	3	78
25660		<10	<1	0.20	20	0.44	340	2	0.79	16	1440	18	0.05	<2	6	200
25661		<10	<1	0.19	20	0.34	387	1	0.23	30	250	18	0.02	<2	5	67
25662		<10	<1	0.20	20	0.33	371	1	0.24	28	250	18	0.03	<2	5	66
25663		<10	<1	0.20	20	0.33	348	2	0.25	34	650	19	0.05	2	5	79
25664		<10	<1	0.15	10	0.84	374	6	0.06	61	450	6	0.84	32	4	37
25665		<10	<1	0.19	20	0.31	401	1	0.21	38	220	22	0.04	<2	5	61
25666		<10	<1	0.20	20	0.33	365	1	0.16	61	280	22	0.03	<2	5	54
25667		<10	<1	0.21	20	0.33	364	1	0.16	56	280	21	0.03	<2	5	54
25668		<10	<1	0.21	20	0.35	422	2	0.16	64	290	21	0.03	<2	5	56
25669		<10	<1	0.20	20	0.36	540	1	0.18	46	580	22	0.04	<2	6	68
25670		<10	<1	0.16	30	0.32	680	2	0.17	36	2140	20	0.09	<2	6	150
25671		<10	1	0.21	20	0.38	663	2	0.19	44	690	21	0.05	<2	6	80
25672		<10	<1	0.21	20	0.47	1305	2	0.22	35	1060	19	0.06	<2	7	117
25673		<10	<1	0.21	20	0.52	1125	2	0.20	40	1000	19	0.04	<2	8	106
25674		<10	<1	0.10	10	1.05	535	1	0.04	32	730	17	0.05	<2	4	87
25675		<10	1	0.17	20	0.31	500	2	0.17	45	590	19	0.08	<2	5	73
25676		<10	<1	0.14	20	0.17	94	2	0.14	18	320	22	0.02	<2	3	81
25677		<10	<1	0.17	20	0.47	533	1	0.14	31	830	19	0.01	<2	5	67
25678		<10	<1	0.17	20	0.30	315	1	0.15	27	240	18	0.02	<2	4	74
25679		<10	<1	0.17	20	0.38	321	<1	0.13	30	290	19	0.01	<2	6	55
25680		<10	1	0.18	20	0.63	502	<1	0.12	34	520	18	0.01	<2	6	82
25681		<10	<1	0.20	10	0.46	680	1	0.22	29	550	16	0.23	2	4	93
25682		10	1	0.12	30	1.63	1095	4	0.51	59	2210	6	0.09	<2	10	207
25683		10	1	0.30	10	0.80	882	3	0.33	47	1710	22	0.09	2	6	123
25684		10	1	0.07	30	3.31	1350	4	0.71	62	2720	2	0.14	<2	11	230
25685		<10	<1	0.11	10	1.49	606	1	0.04	50	1020	15	0.08	2	4	95
25686		10	<1	0.06	30	3.07	1280	<1	0.64	67	2730	3	0.08	<2	12	224
25687		10	1	0.05	30	2.80	1275	<1	0.59	67	3260	4	0.08	<2	10	220
25688		10	2	0.07	30	2.64	1160	<1	0.65	71	2710	2	0.06	<2	13	258
25689		10	1	0.06	30	2.87	1255	<1	0.45	67	2590	3	0.09	<2	11	224
25690		<10	1	0.27	10	0.93	723	1	0.32	47	1490	18	0.12	<2	7	140

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 18-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094232

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Th	Ti	Tl	U	V	W	Zn
	Units	ppm	%	ppm	ppm	ppm	ppm	ppm
	LOR	20	0.01	10	10	1	10	2
25651		<20	0.01	<10	<10	41	<10	111
25652		<20	0.13	<10	<10	61	10	193
25653		<20	0.01	<10	<10	45	<10	103
25654		<20	0.01	<10	<10	46	<10	116
25655		<20	0.01	<10	<10	37	<10	82
25656		<20	0.01	<10	<10	39	<10	113
25657		<20	0.01	<10	<10	26	<10	137
25658		<20	0.01	<10	<10	25	<10	148
25659		<20	0.05	<10	<10	30	<10	68
25660		<20	<0.01	<10	<10	16	<10	124
25661		<20	0.01	<10	<10	23	<10	146
25662		<20	0.01	<10	<10	22	<10	135
25663		<20	0.01	<10	<10	22	<10	142
25664		<20	0.10	<10	<10	48	40	49
25665		<20	0.01	<10	<10	24	<10	150
25666		<20	0.01	<10	<10	26	<10	161
25667		<20	0.01	<10	<10	26	<10	158
25668		<20	0.01	<10	<10	28	<10	163
25669		<20	0.01	<10	<10	28	<10	159
25670		<20	0.01	<10	<10	32	<10	175
25671		<20	0.01	<10	<10	29	<10	153
25672		<20	0.01	<10	<10	33	<10	136
25673		<20	0.01	<10	<10	35	<10	136
25674		<20	0.09	<10	<10	46	<10	72
25675		<20	0.01	<10	<10	24	<10	154
25676		<20	0.01	<10	<10	24	<10	87
25677		<20	0.01	<10	<10	26	<10	150
25678		<20	0.01	<10	<10	25	<10	118
25679		<20	0.01	<10	<10	26	<10	126
25680		<20	0.01	<10	<10	36	<10	112
25681		<20	<0.01	<10	<10	19	<10	91
25682		<20	<0.01	<10	<10	124	<10	88
25683		<20	<0.01	<10	<10	39	<10	137
25684		<20	0.01	<10	<10	133	<10	74
25685		<20	0.06	<10	<10	47	<10	98
25686		<20	0.01	<10	<10	148	<10	81
25687		<20	0.01	<10	<10	157	<10	77
25688		<20	0.02	<10	<10	163	<10	85
25689		<20	0.01	<10	<10	147	<10	74
25690		<20	<0.01	<10	<10	43	<10	120

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 18-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094232

Sample Description	Method	WEI-21	Au-AA23	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt.	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu	Fe
	Units	kg	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	%
	LOR	0.02	0.005	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1	0.01
25691		0.10	1.040	11.2	1.73	463	<10	110	<0.5	<2	0.88	1.1	9	38	280	3.34
25692		3.34	0.007	0.2	1.99	22	<10	430	3.1	<2	2.19	<0.5	18	76	33	4.75
25693		3.70	<0.005	0.3	1.04	14	<10	280	2.2	<2	1.24	<0.5	15	23	29	3.73
25694		3.76	0.005	0.2	1.14	21	<10	330	2.1	<2	0.55	0.6	13	18	29	3.25
25695		3.68	<0.005	0.2	1.34	20	<10	360	1.6	<2	0.68	0.6	14	23	30	3.23
25696		4.02	<0.005	<0.2	1.14	21	<10	370	1.5	<2	1.00	<0.5	12	16	26	3.15
25697		3.88	<0.005	0.2	1.01	12	<10	330	1.2	<2	0.73	0.5	11	18	26	3.07
25698		3.74	<0.005	0.2	1.55	12	<10	350	1.3	<2	0.99	0.5	15	35	31	3.31
25699		3.58	<0.005	0.3	1.50	20	<10	310	1.3	<2	1.03	<0.5	15	35	31	3.75
25700		3.92	<0.005	<0.2	1.32	9	<10	430	1.3	<2	1.77	<0.5	10	32	25	3.14
25701		0.74	<0.005	<0.2	0.90	4	<10	210	0.7	<2	1.84	<0.5	9	15	19	1.62
25702		2.08	<0.005	<0.2	1.43	15	<10	430	1.5	2	1.69	0.5	10	17	21	2.75
25703		3.74	<0.005	<0.2	0.52	<2	<10	380	<0.5	<2	1.40	<0.5	4	6	4	1.54
25704		3.60	<0.005	<0.2	1.22	12	<10	530	1.6	2	2.13	<0.5	8	13	15	2.39
25705		4.22	<0.005	<0.2	1.28	7	<10	420	1.3	<2	2.81	<0.5	9	15	20	2.66
25706		3.96	0.012	<0.2	1.58	12	<10	580	1.3	<2	3.63	<0.5	11	22	21	3.20
25707		2.80	<0.005	0.2	1.42	18	<10	520	1.3	<2	2.74	<0.5	11	23	20	3.03
25708		3.38	<0.005	<0.2	1.49	15	<10	390	1.3	2	2.38	<0.5	11	20	18	3.12
25709		0.10	1.020	10.9	2.42	475	<10	160	<0.5	2	1.23	1.3	10	45	290	3.73
25710		5.00	<0.005	<0.2	1.83	16	<10	440	1.3	<2	2.46	<0.5	10	17	18	3.16
25711		3.20	<0.005	<0.2	1.48	10	<10	430	1.3	2	2.58	<0.5	9	17	16	2.92
25712		3.32	0.008	0.2	1.43	12	<10	490	1.4	<2	1.80	<0.5	9	15	17	2.73
25713		1.38	<0.005	<0.2	1.62	13	<10	430	1.3	<2	3.14	<0.5	11	48	24	3.15
25714		0.80	<0.005	0.2	0.24	4	<10	260	<0.5	<2	1.84	<0.5	1	4	3	0.52
25715		3.92	<0.005	0.4	1.44	16	<10	330	1.1	<2	2.24	<0.5	11	22	24	2.93
25716		3.74	<0.005	0.3	1.24	9	<10	360	1.1	<2	2.16	<0.5	8	18	19	2.57
25717		3.98	<0.005	<0.2	1.25	12	<10	360	1.1	<2	2.05	<0.5	9	16	19	2.69
25718		2.22	<0.005	<0.2	1.40	8	<10	410	1.0	<2	2.43	<0.5	11	19	23	2.90
25719		0.78	<0.005	0.3	1.01	5	<10	460	<0.5	<2	4.49	0.8	6	26	2160	1.83
25720		1.96	0.005	<0.2	1.04	5	<10	690	0.5	<2	10.95	<0.5	64	631	15	4.00
25721		3.98	<0.005	0.2	1.74	5	<10	40	0.5	<2	0.68	<0.5	11	36	26	2.94
25722		3.72	<0.005	<0.2	1.70	<2	<10	50	0.6	<2	0.67	<0.5	11	35	26	3.03
25723		3.40	<0.005	0.3	1.61	2	<10	30	0.7	<2	1.00	<0.5	11	27	25	2.97
25724		3.92	<0.005	0.4	1.83	2	<10	40	0.7	<2	0.91	<0.5	11	32	26	3.13
25725		4.30	<0.005	<0.2	1.85	<2	<10	40	0.6	<2	1.11	<0.5	12	31	27	3.20
25726		3.28	<0.005	0.3	1.98	<2	<10	50	0.7	5	0.82	<0.5	12	33	36	3.30
25727		3.62	<0.005	<0.2	1.74	<2	<10	60	0.7	2	0.94	<0.5	12	27	33	3.12
25728		0.10	1.045	10.4	1.79	457	<10	110	<0.5	<2	0.87	1.2	10	39	284	3.34
25729		3.60	0.006	<0.2	1.86	<2	<10	70	0.7	<2	0.87	<0.5	10	26	44	2.90
25730		4.26	<0.005	<0.2	1.61	<2	<10	40	0.8	2	1.36	<0.5	11	34	26	3.09

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 18-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094232

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc	Sr
	Units	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm	ppm
	LOR	10	1	0 01	10	0 01	5	1	0 01	1	10	2	0 01	2	1	1
25691		10	<1	0.14	10	0.86	512	83	0.09	38	570	93	0.26	8	5	42
25692		10	<1	0.26	20	1.07	955	2	0.39	66	1100	16	0.13	<2	7	184
25693		<10	<1	0.28	20	0.92	608	3	0.21	33	740	16	0.11	<2	6	92
25694		<10	<1	0.24	10	0.53	513	2	0.29	39	640	23	0.16	<2	5	84
25695		<10	<1	0.24	10	0.57	501	2	0.29	42	600	23	0.23	<2	5	94
25696		<10	<1	0.24	10	0.52	658	2	0.31	32	630	21	0.15	<2	5	119
25697		<10	1	0.24	10	0.50	567	1	0.25	35	640	21	0.09	<2	5	95
25698		10	1	0.26	10	0.80	577	1	0.26	45	660	24	0.09	<2	6	98
25699		<10	<1	0.25	10	0.80	693	1	0.24	48	750	19	0.13	<2	7	91
25700		10	<1	0.25	10	0.87	630	1	0.23	34	570	17	0.14	<2	6	141
25701		<10	<1	0.38	20	0.66	590	<1	0.15	11	330	5	0.08	<2	8	123
25702		10	<1	0.34	10	0.67	589	2	0.29	25	590	20	0.28	<2	6	150
25703		<10	<1	0.30	10	0.31	365	<1	0.13	4	230	4	0.04	<2	4	98
25704		<10	1	0.35	10	0.51	581	2	0.24	14	450	22	0.19	<2	5	188
25705		<10	<1	0.34	10	0.75	669	2	0.23	19	510	17	0.22	<2	7	226
25706		10	1	0.33	10	1.16	815	2	0.22	28	870	16	0.34	<2	7	245
25707		<10	1	0.31	10	0.88	673	2	0.24	28	860	20	0.36	<2	7	216
25708		<10	1	0.32	20	0.83	637	2	0.24	26	1030	16	0.31	<2	6	198
25709		10	<1	0.25	10	0.95	585	88	0.21	41	590	97	0.29	6	7	70
25710		10	1	0.32	10	0.81	596	2	0.25	22	810	16	0.34	<2	7	226
25711		10	1	0.32	10	0.79	701	2	0.22	21	730	17	0.23	<2	6	218
25712		<10	1	0.32	10	0.63	516	2	0.25	20	620	18	0.25	<2	6	169
25713		10	1	0.33	10	1.18	751	2	0.23	42	630	20	0.29	<2	8	214
25714		<10	<1	0.14	10	0.21	253	<1	0.07	2	60	14	0.08	<2	1	152
25715		<10	<1	0.28	10	0.90	578	2	0.22	30	840	19	0.37	<2	7	154
25716		<10	<1	0.29	10	0.69	537	1	0.22	21	620	17	0.17	<2	6	166
25717		<10	<1	0.28	10	0.65	572	1	0.22	18	680	15	0.11	<2	6	171
25718		<10	<1	0.29	10	0.75	634	1	0.21	22	570	17	0.20	<2	7	188
25719		<10	<1	0.12	10	0.81	440	1	0.04	30	890	14	0.06	<2	3	190
25720		<10	<1	0.15	10	3.75	1500	1	0.06	1020	190	3	0.17	<2	6	860
25721		<10	<1	0.36	30	0.99	445	2	0.05	39	310	9	0.20	<2	3	26
25722		10	<1	0.44	30	0.99	466	1	0.05	35	340	6	0.26	<2	4	32
25723		10	<1	0.23	40	0.99	515	1	0.05	33	350	9	0.15	<2	3	42
25724		<10	<1	0.33	30	1.00	520	1	0.05	34	350	7	0.23	<2	3	36
25725		10	1	0.24	40	1.07	553	1	0.05	32	360	6	0.26	<2	4	40
25726		10	1	0.30	40	1.03	557	1	0.05	34	350	6	0.23	<2	4	31
25727		10	1	0.29	30	0.92	532	1	0.04	33	300	17	0.38	<2	3	36
25728		10	<1	0.14	10	0.85	508	86	0.09	39	580	95	0.29	6	5	44
25729		10	1	0.38	40	0.86	482	1	0.05	30	290	8	0.32	<2	4	34
25730		10	1	0.20	40	1.10	565	2	0.04	40	350	10	0.11	<2	3	65

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 18-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094232

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Th	Ti	Tl	U	V	W	Zn
	Units	ppm	%	ppm	ppm	ppm	ppm	ppm
	LOR	20	0.01	10	10	1	10	2
25691		<20	0.13	<10	<10	63	10	200
25692		<20	<0.01	<10	<10	51	<10	119
25693		<20	0.01	<10	<10	32	<10	107
25694		<20	<0.01	<10	<10	22	<10	140
25695		<20	<0.01	<10	<10	25	<10	136
25696		<20	<0.01	<10	<10	20	<10	114
25697		<20	<0.01	<10	<10	22	<10	127
25698		<20	<0.01	<10	<10	31	<10	110
25699		<20	<0.01	<10	<10	33	<10	119
25700		<20	<0.01	<10	<10	30	<10	94
25701		<20	<0.01	<10	<10	27	<10	37
25702		<20	<0.01	<10	<10	21	<10	107
25703		<20	<0.01	<10	<10	10	<10	23
25704		<20	<0.01	<10	<10	16	<10	82
25705		<20	<0.01	<10	<10	21	<10	74
25706		<20	<0.01	<10	<10	27	<10	85
25707		<20	<0.01	<10	<10	25	<10	92
25708		<20	<0.01	<10	<10	27	<10	100
25709		<20	0.19	<10	<10	79	<10	201
25710		<20	<0.01	<10	<10	35	<10	85
25711		<20	<0.01	<10	<10	26	<10	77
25712		<20	<0.01	<10	<10	21	<10	90
25713		<20	<0.01	<10	<10	28	<10	85
25714		<20	<0.01	<10	<10	2	<10	10
25715		<20	<0.01	<10	<10	25	<10	85
25716		<20	<0.01	<10	<10	20	<10	83
25717		<20	<0.01	<10	<10	20	<10	81
25718		<20	<0.01	<10	<10	23	<10	79
25719		<20	0.04	<10	<10	32	<10	69
25720		<20	0.01	<10	<10	26	<10	33
25721		<20	0.04	<10	<10	34	<10	54
25722		<20	0.06	<10	<10	38	<10	58
25723		20	0.01	<10	<10	28	<10	55
25724		<20	0.03	<10	<10	34	<10	57
25725		20	0.02	<10	<10	33	<10	58
25726		20	0.02	<10	<10	34	<10	58
25727		20	0.02	<10	<10	31	<10	65
25728		<20	0.13	<10	<10	63	10	197
25729		20	0.03	<10	<10	31	<10	52
25730		20	0.01	<10	<10	34	<10	60

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 18-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094232

Sample Description	Method	WEI-21	Au-AA23	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu	Fe
	Units	kg	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	%
	LOR	0.02	0.005	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1	0.01
25731		4.86	<0.005	<0.2	0.94	<2	<10	60	0.9	2	1.39	<0.5	10	16	27	2.70
25732		3.54	<0.005	<0.2	1.42	<2	<10	40	0.9	<2	1.14	<0.5	12	24	27	3.00
25733		2.56	<0.005	<0.2	1.60	<2	<10	40	0.9	2	0.87	<0.5	12	27	24	3.37
25734		2.42	<0.005	<0.2	1.29	<2	<10	60	1.1	<2	1.88	<0.5	11	24	26	3.17
25735		3.06	<0.005	<0.2	1.27	<2	<10	60	1.0	3	1.33	<0.5	12	26	28	2.88
25736		3.76	<0.005	<0.2	1.66	<2	<10	30	0.8	3	1.50	<0.5	11	34	23	3.16
25737		0.80	<0.005	0.3	1.05	7	<10	1360	<0.5	<2	3.20	0.7	9	39	24	2.09
25738		3.36	<0.005	0.3	1.73	2	<10	40	0.8	<2	1.80	<0.5	10	40	34	3.11
25739		4.28	0.009	0.3	1.55	4	<10	40	0.6	2	2.45	<0.5	9	39	37	2.81
25740		4.66	<0.005	<0.2	1.86	2	<10	40	0.6	<2	2.18	<0.5	10	53	16	3.17
25741		3.76	0.006	0.3	1.47	5	<10	50	0.6	<2	2.15	<0.5	11	47	43	3.01
25742		3.46	<0.005	<0.2	1.59	4	<10	40	0.6	<2	2.20	<0.5	9	47	15	2.74
25743		3.36	<0.005	0.2	1.49	5	<10	30	0.5	<2	1.87	<0.5	8	23	30	2.61
25744		3.78	<0.005	0.2	1.67	<2	<10	30	0.5	<2	1.87	<0.5	9	24	29	2.94
25745		4.10	<0.005	<0.2	1.52	3	<10	30	0.5	<2	1.66	<0.5	8	19	29	2.80
25746		3.94	<0.005	0.3	1.71	6	<10	130	0.8	<2	2.03	<0.5	11	28	37	3.12
25747		3.64	<0.005	<0.2	1.76	3	<10	30	0.8	<2	1.45	<0.5	12	31	25	3.16
25748		2.42	<0.005	0.2	1.66	<2	<10	40	0.8	<2	1.88	<0.5	10	28	26	2.87
25749		3.40	<0.005	0.3	1.92	3	<10	40	0.9	<2	2.55	<0.5	10	40	23	2.94
25750		0.80	<0.005	0.6	1.02	24	<10	560	<0.5	2	2.26	0.8	7	31	40	1.91
25751		3.36	<0.005	0.3	1.88	3	<10	30	0.9	<2	2.76	<0.5	11	40	26	2.84
25752		4.00	<0.005	0.3	1.85	2	<10	30	0.9	<2	3.08	<0.5	10	39	31	2.83
25753		0.10	1.115	9.3	1.72	467	<10	110	<0.5	<2	0.80	1.3	10	38	293	3.27
25754		3.10	0.006	0.3	1.74	5	<10	30	0.8	<2	2.93	<0.5	9	36	23	2.65
25755		2.38	<0.005	<0.2	1.71	4	<10	30	0.7	<2	1.86	<0.5	10	28	25	2.82
25756		2.88	<0.005	0.2	1.73	3	<10	30	0.8	<2	1.86	<0.5	11	29	28	2.82
25757		2.52	<0.005	0.2	1.58	4	<10	40	0.6	<2	1.71	0.6	8	22	28	2.64
25758		3.86	0.005	0.3	1.12	7	<10	70	1.0	<2	2.60	0.6	9	18	23	2.68
25759		3.32	<0.005	0.2	1.32	7	<10	90	0.9	<2	2.03	0.5	8	17	30	2.48
25760		3.38	<0.005	0.2	1.60	7	<10	40	0.7	<2	1.59	<0.5	9	24	26	2.68
25761		3.82	<0.005	<0.2	1.81	5	<10	30	0.7	<2	1.69	<0.5	11	30	26	2.98
25762		3.34	<0.005	0.3	1.88	5	<10	30	0.7	<2	1.68	<0.5	11	33	27	3.09
25763		3.56	<0.005	0.2	1.75	8	<10	50	0.7	<2	2.22	<0.5	10	35	26	2.82
25764		4.24	<0.005	0.2	1.66	5	<10	30	0.6	<2	2.29	<0.5	10	32	23	2.74
25765		3.78	<0.005	0.2	1.67	5	<10	40	0.7	<2	1.90	<0.5	10	31	27	2.75
25766		3.68	<0.005	0.2	1.82	3	<10	100	0.8	<2	2.17	<0.5	11	32	22	2.92
25767		0.10	9.77	0.7	1.47	3980	<10	60	<0.5	<2	0.75	<0.5	14	65	67	3.48
25768		3.48	0.006	0.3	1.67	8	<10	80	0.8	<2	1.85	<0.5	10	27	17	2.79
25769		4.66	<0.005	0.2	1.54	5	<10	80	0.8	<2	2.00	<0.5	8	25	15	2.57
25770		3.44	<0.005	0.3	1.65	5	<10	100	0.9	<2	2.08	<0.5	9	29	20	2.67

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 18-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094232

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc	Sr
	Units	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm	ppm
	LOR	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1	1
25731		<10	1	0.22	40	0.89	498	1	0.04	25	350	13	0.31	<2	3	88
25732		10	<1	0.25	40	0.87	538	1	0.03	36	380	9	0.18	<2	3	55
25733		10	<1	0.22	40	1.01	589	1	0.04	35	410	10	0.18	<2	3	46
25734		10	<1	0.26	30	1.18	618	1	0.05	29	350	13	0.17	<2	3	109
25735		<10	<1	0.29	30	0.99	574	1	0.04	36	300	13	0.05	<2	3	81
25736		10	1	0.22	40	0.97	548	1	0.03	30	340	14	0.09	<2	3	69
25737		<10	1	0.11	10	1.58	505	1	0.04	44	1150	16	0.08	2	4	111
25738		10	<1	0.21	30	1.04	502	1	0.04	24	450	12	0.07	<2	4	70
25739		10	<1	0.11	20	1.20	578	1	0.04	26	770	17	0.04	<2	5	91
25740		10	<1	0.14	30	1.28	554	2	0.04	34	590	9	0.02	<2	4	76
25741		10	<1	0.13	20	1.17	569	5	0.03	47	550	13	0.10	2	4	89
25742		10	<1	0.15	20	1.24	478	1	0.05	31	520	9	0.05	<2	4	83
25743		10	<1	0.13	30	0.93	512	1	0.04	13	450	13	0.07	<2	3	64
25744		10	<1	0.13	20	1.09	511	1	0.05	12	600	13	0.04	<2	5	60
25745		10	<1	0.11	20	1.05	506	<1	0.05	11	400	11	0.05	<2	4	57
25746		10	1	0.18	30	1.13	584	1	0.04	28	470	12	0.03	<2	4	107
25747		10	1	0.20	30	1.09	510	1	0.04	34	440	13	0.03	<2	3	73
25748		10	<1	0.19	30	1.03	530	1	0.04	28	410	21	0.02	<2	2	104
25749		10	<1	0.17	20	1.27	581	1	0.05	33	530	26	0.05	<2	3	108
25750		<10	<1	0.14	10	1.06	455	2	0.03	36	820	286	0.07	<2	4	92
25751		10	<1	0.18	20	1.23	566	1	0.06	32	530	24	0.06	<2	3	108
25752		10	<1	0.16	20	1.25	584	1	0.05	32	530	21	0.06	<2	3	127
25753		10	1	0.14	<10	0.82	493	88	0.08	39	560	98	0.27	8	5	42
25754		10	<1	0.19	20	1.10	561	1	0.04	30	520	21	0.03	<2	3	139
25755		10	1	0.21	30	0.96	511	1	0.05	28	480	19	0.04	<2	2	89
25756		10	1	0.23	30	0.97	506	1	0.04	30	460	22	0.04	<2	2	87
25757		10	1	0.20	30	0.85	485	1	0.05	22	470	23	0.05	<2	2	88
25758		10	<1	0.18	30	1.10	556	1	0.04	23	440	29	0.11	<2	2	174
25759		10	<1	0.22	30	0.82	495	2	0.04	21	490	28	0.05	<2	2	118
25760		10	<1	0.23	30	0.84	491	2	0.04	27	400	18	0.06	<2	2	75
25761		10	<1	0.21	30	1.04	496	1	0.04	33	430	16	0.06	2	3	79
25762		10	<1	0.20	30	1.10	530	1	0.04	32	450	15	0.02	<2	3	78
25763		10	<1	0.18	20	1.08	571	1	0.04	24	420	16	0.06	<2	4	97
25764		10	1	0.15	20	1.04	549	1	0.04	21	460	15	0.04	<2	4	85
25765		10	<1	0.19	30	0.97	507	2	0.04	26	390	16	0.03	<2	3	82
25766		10	1	0.21	30	1.05	562	1	0.04	27	450	19	0.02	<2	3	95
25767		10	<1	0.16	10	0.83	375	6	0.06	63	470	6	0.89	35	5	38
25768		10	<1	0.26	30	0.92	530	1	0.05	26	500	24	0.05	<2	2	99
25769		10	<1	0.24	30	0.90	525	1	0.05	26	490	26	0.06	<2	2	104
25770		10	<1	0.27	30	1.02	516	1	0.05	31	500	27	0.07	<2	3	109

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 18-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094232

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Th	Ti	Tl	U	V	W	Zn
	Units	ppm	%	ppm	ppm	ppm	ppm	ppm
	LOR	20	0.01	10	10	1	10	2
25731		20	0.01	<10	<10	26	<10	65
25732		20	0.01	<10	<10	27	<10	61
25733		20	0.01	<10	<10	33	<10	64
25734		20	0.01	<10	<10	29	<10	61
25735		20	0.01	<10	<10	27	<10	60
25736		20	<0.01	<10	<10	32	<10	61
25737		<20	0.05	<10	<10	40	<10	89
25738		20	<0.01	<10	<10	43	<10	66
25739		<20	<0.01	<10	<10	59	<10	65
25740		20	<0.01	<10	<10	56	<10	72
25741		<20	<0.01	<10	<10	71	<10	96
25742		<20	<0.01	<10	<10	46	<10	64
25743		20	<0.01	<10	<10	37	<10	63
25744		<20	<0.01	<10	<10	48	<10	70
25745		20	<0.01	<10	<10	38	<10	56
25746		20	<0.01	<10	<10	41	<10	67
25747		<20	<0.01	<10	<10	35	<10	70
25748		<20	<0.01	<10	<10	32	<10	71
25749		<20	0.01	<10	<10	39	<10	78
25750		<20	0.05	<10	<10	41	<10	114
25751		<20	0.01	<10	<10	36	<10	74
25752		<20	0.01	<10	<10	38	<10	76
25753		<20	0.13	<10	<10	61	<10	196
25754		<20	<0.01	<10	<10	32	<10	67
25755		<20	0.01	<10	<10	30	<10	66
25756		<20	<0.01	<10	<10	30	<10	67
25757		20	<0.01	<10	<10	27	<10	82
25758		20	<0.01	<10	<10	21	<10	79
25759		20	<0.01	<10	<10	21	<10	73
25760		20	<0.01	<10	<10	25	<10	61
25761		20	0.01	<10	<10	33	<10	66
25762		<20	0.01	<10	<10	38	<10	69
25763		<20	<0.01	<10	<10	41	<10	62
25764		20	<0.01	<10	<10	40	<10	60
25765		20	<0.01	<10	<10	34	<10	61
25766		<20	<0.01	<10	<10	35	<10	68
25767		<20	0.10	<10	<10	49	40	50
25768		20	<0.01	<10	<10	27	<10	65
25769		<20	<0.01	<10	<10	24	<10	63
25770		<20	<0.01	<10	<10	26	<10	70

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 18-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094232

Sample Description	Method / Analyte / Units / LOR	WEI-21 Recvd Wt. kg 0.02	Au-AA23 Au ppm 0.005	ME-ICP41 Ag ppm 0.2	ME-ICP41 Al % 0.01	ME-ICP41 As ppm 2	ME-ICP41 B ppm 10	ME-ICP41 Ba ppm 10	ME-ICP41 Be ppm 0.5	ME-ICP41 Bi ppm 2	ME-ICP41 Ca % 0.01	ME-ICP41 Cd ppm 0.5	ME-ICP41 Co ppm 1	ME-ICP41 Cr ppm 1	ME-ICP41 Cu ppm 1	ME-ICP41 Fe % 0.01
25771		3.54	<0.005	0.3	1.68	6	<10	80	0.9	<2	2.24	<0.5	10	31	25	2.77
25772		2.84	<0.005	0.3	1.70	8	<10	190	0.9	<2	1.47	<0.5	10	31	25	2.88
25773		4.14	<0.005	0.3	1.13	19	<10	320	1.3	<2	3.11	<0.5	16	80	26	3.00
25774		4.10	<0.005	0.2	1.05	18	<10	260	1.2	<2	2.40	<0.5	11	26	22	2.87
25775		4.32	<0.005	0.2	1.03	19	<10	210	1.3	<2	2.43	<0.5	12	22	23	2.69
25776		3.84	<0.005	0.2	0.85	18	<10	250	1.3	<2	3.11	<0.5	12	25	27	2.73
25777		4.04	<0.005	0.2	0.41	9	<10	200	0.8	<2	3.33	0.5	9	7	23	2.49
25778		4.32	<0.005	0.2	0.38	8	<10	240	0.9	<2	5.14	<0.5	12	6	24	3.03
25779		4.00	<0.005	0.4	0.47	12	<10	210	0.9	<2	2.50	1.1	10	7	30	2.29
25780		0.96	<0.005	0.4	1.00	9	<10	370	<0.5	<2	2.50	0.8	8	44	27	1.96
25781		4.14	<0.005	0.3	1.02	15	<10	300	1.3	<2	1.94	<0.5	10	18	26	2.70
25782		3.26	<0.005	0.3	0.85	19	<10	330	1.4	<2	2.60	<0.5	11	14	26	2.78
25783		3.62	<0.005	0.3	1.15	13	<10	380	1.1	<2	1.69	<0.5	9	16	19	2.48
25784		3.12	<0.005	0.2	1.22	16	<10	370	1.3	<2	1.77	<0.5	10	15	18	2.50
25785		3.18	<0.005	0.2	1.31	14	<10	430	1.3	<2	2.09	<0.5	10	19	25	2.73
25786		3.46	<0.005	0.3	1.29	11	<10	410	1.4	<2	1.74	<0.5	11	22	24	2.90
25787		3.62	<0.005	0.3	1.31	16	<10	380	1.2	<2	0.78	0.6	14	25	32	3.29
25788		4.06	<0.005	0.3	1.05	15	<10	260	1.2	<2	1.14	<0.5	9	25	25	2.70
25789		0.10	0.951	8.6	1.74	486	<10	110	<0.5	<2	0.82	1.2	9	38	293	3.28
25790		2.32	0.011	0.2	0.57	19	<10	300	0.9	<2	0.57	<0.5	11	12	27	2.43
25791		1.40	0.006	0.5	0.52	10	<10	220	0.5	<2	19.7	5.5	2	36	11	0.68

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd.
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone. 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 18-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094232

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc	Sr
	Units	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm	ppm
	LOR	10	1	0 01	10	0.01	5	1	0.01	1	10	2	0 01	2	1	1
25771		10	1	0.22	30	1.03	556	1	0.04	30	500	24	0.07	<2	3	126
25772		10	<1	0.25	20	0.97	403	2	0.05	34	520	27	0.45	<2	3	83
25773		<10	<1	0.23	<10	1.54	681	3	0.20	162	520	21	0.35	2	8	378
25774		<10	<1	0.24	10	1.09	548	2	0.20	47	650	21	0.32	<2	6	204
25775		<10	<1	0.23	<10	1.10	483	2	0.24	52	460	23	0.35	<2	7	192
25776		<10	1	0.22	<10	1.35	481	3	0.22	58	520	19	0.36	2	7	210
25777		<10	<1	0.18	<10	1.26	347	1	0.17	19	460	19	0.24	2	7	141
25778		<10	1	0.17	<10	1.94	408	1	0.18	16	330	8	0.34	<2	8	188
25779		<10	<1	0.18	<10	0.97	286	4	0.17	32	640	30	0.25	2	5	110
25780		<10	<1	0.09	10	1.20	471	1	0.03	50	1040	14	0.06	<2	3	114
25781		<10	<1	0.22	10	0.74	545	2	0.23	29	610	19	0.30	<2	6	145
25782		<10	<1	0.22	<10	0.94	602	2	0.29	28	550	19	0.25	2	7	160
25783		<10	<1	0.23	10	0.63	484	2	0.23	22	540	15	0.23	<2	6	153
25784		<10	<1	0.23	10	0.69	514	2	0.24	21	520	18	0.23	<2	6	160
25785		<10	<1	0.23	10	0.77	553	2	0.24	26	570	17	0.25	<2	6	183
25786		<10	<1	0.25	10	0.64	627	2	0.26	28	510	18	0.16	<2	6	172
25787		<10	1	0.27	10	0.67	606	1	0.31	43	730	22	0.13	2	6	110
25788		<10	<1	0.21	20	0.72	400	1	0.12	29	540	14	0.12	<2	6	71
25789		10	<1	0.14	<10	0.84	496	90	0.09	39	570	101	0.28	8	5	44
25790		<10	1	0.16	10	0.40	432	3	0.06	40	510	15	0.02	<2	3	75
25791		<10	1	0.17	10	1.28	175	4	0.07	18	>10000	3	0.8	<2	3	638

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 18-SEP-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09094232

Sample Description	Method / Analyte / Units / LOR	ME-ICP41 Th ppm 20	ME-ICP41 Ti % 0.01	ME-ICP41 Tl ppm 10	ME-ICP41 U ppm 10	ME-ICP41 V ppm 1	ME-ICP41 W ppm 10	ME-ICP41 Zn ppm 2
25771		<20	<0.01	<10	<10	28	<10	68
25772		<20	<0.01	<10	<10	25	<10	71
25773		<20	<0.01	<10	<10	19	<10	106
25774		<20	<0.01	<10	<10	17	<10	100
25775		<20	<0.01	<10	<10	14	<10	102
25776		<20	<0.01	<10	<10	18	<10	112
25777		<20	<0.01	<10	<10	18	<10	109
25778		<20	<0.01	<10	<10	11	<10	81
25779		<20	<0.01	<10	<10	22	<10	198
25780		<20	0.06	<10	<10	38	<10	83
25781		<20	<0.01	<10	<10	19	<10	97
25782		<20	<0.01	<10	<10	17	<10	115
25783		<20	<0.01	<10	<10	17	<10	78
25784		<20	<0.01	<10	<10	17	<10	81
25785		<20	<0.01	<10	<10	20	<10	84
25786		<20	<0.01	<10	<10	22	<10	92
25787		<20	<0.01	<10	<10	29	<10	130
25788		<20	0.03	<10	<10	35	<10	88
25789		<20	0.13	<10	<10	62	<10	200
25790		<20	<0.01	<10	<10	11	<10	85
25791		<20	<0.01	<10	<10	34	<10	93

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 4-OCT-2009
This copy reported on 5-OCT-2009
Account: EMERES

CERTIFICATE VA09104183

Project: Canyon Gold

P.O. No.:

This report is for 113 Drill Core samples submitted to our lab in Vancouver, BC, Canada on 18-SEP-2009.

The following have access to data associated with this certificate:

SARA PUBLICOVER	SIMON RIDGWAY	

SAMPLE PREPARATION

ALS CODE	DESCRIPTION
WEI-21	Received Sample Weight
LOG-22	Sample login - Rcd w/o BarCode
LOG-24	Pulp Login - Rcd w/o Barcode
CRU-QC	Crushing QC Test
PUL-QC	Pulverizing QC Test
CRU-31	Fine crushing - 70% <2mm
SPL-21	Split sample - riffle splitter
PUL-31	Pulverize split to 85% <75 um

ANALYTICAL PROCEDURES

ALS CODE	DESCRIPTION	INSTRUMENT
ME-ICP41	35 Element Aqua Regia ICP-AES	ICP-AES
Au-AA23	Au 30g FA-AA finish	AAS

To: EMERICK RESOURCES LTD.
ATTN: SIMON RIDGWAY
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

This is the Final Report and supersedes any preliminary report with this certificate number. Results apply to samples as submitted. All pages of this report have been checked and approved for release.

Signature:

Colin Ramshaw, Vancouver Laboratory Manager

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 4-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09104183

Sample Description	Method	WEI-21	Au-AA23	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu	Fe
	Units	kg	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	%
	LOR	0.02	0.005	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1	0.01
25792		1.84	0.007	0.2	0.96	7	<10	510	0.9	<2	1.39	<0.5	14	10	18	4.21
25793		2.88	0.005	<0.2	0.97	3	<10	200	1.1	<2	0.75	<0.5	10	7	18	3.47
25794		2.08	0.005	<0.2	0.96	<2	<10	330	1.1	<2	0.45	<0.5	10	7	18	2.68
25795		1.52	0.006	<0.2	0.85	<2	<10	280	0.8	<2	2.25	<0.5	7	7	11	4.43
25796		2.22	0.007	<0.2	0.99	2	<10	420	1.2	<2	0.40	<0.5	10	7	21	2.84
25797		2.38	0.005	<0.2	0.80	3	<10	400	1.0	<2	0.96	<0.5	9	7	13	2.96
25798		2.06	<0.005	<0.2	0.96	2	<10	500	1.3	<2	0.38	<0.5	9	7	19	3.14
25799		2.32	0.008	0.2	0.71	3	<10	330	0.8	<2	1.32	<0.5	7	26	22	2.63
25800		1.32	<0.005	<0.2	0.55	8	<10	200	<0.5	<2	1.85	<0.5	8	24	10	2.00
25801		2.26	0.008	0.3	0.59	22	<10	220	0.5	<2	1.34	<0.5	8	27	14	2.10
25802		2.12	0.006	0.2	0.76	17	<10	370	1.0	<2	1.12	<0.5	10	25	22	2.51
25803		1.72	0.006	<0.2	0.45	46	<10	190	<0.5	<2	1.95	<0.5	9	38	9	2.01
25804		1.38	0.008	<0.2	0.84	6	<10	480	1.2	<2	0.36	<0.5	11	10	18	3.23
25805		1.24	<0.005	<0.2	0.53	12	<10	220	0.5	<2	2.10	<0.5	6	15	8	2.51
25806		2.40	0.008	<0.2	0.97	6	<10	490	1.2	<2	0.88	<0.5	15	21	30	3.91
25807		1.84	0.006	0.2	0.51	13	<10	170	<0.5	<2	1.67	<0.5	8	30	16	2.18
25808		0.10	1.035	9.6	1.84	475	<10	120	<0.5	<2	0.90	1.4	9	40	288	3.43
25809		2.64	0.008	<0.2	0.50	13	<10	160	<0.5	<2	1.32	<0.5	6	24	12	1.80
25810		1.82	0.008	<0.2	0.57	19	<10	210	0.5	<2	1.05	<0.5	8	18	12	2.00
25811		1.82	0.007	0.3	0.91	<2	<10	490	1.1	<2	0.58	0.5	14	27	44	3.90
25812		2.00	0.005	<0.2	0.52	7	<10	190	0.5	<2	1.40	<0.5	8	29	16	2.66
25813		0.70	0.006	<0.2	1.09	7	<10	580	<0.5	<2	2.85	1.1	7	39	22	1.94
25814		1.68	0.007	<0.2	0.49	18	<10	170	<0.5	<2	1.04	<0.5	6	21	12	1.94
25815		1.62	0.006	<0.2	0.54	36	<10	220	0.5	<2	1.62	<0.5	9	26	16	2.73
25816		2.38	0.006	<0.2	0.45	15	<10	190	<0.5	<2	1.08	<0.5	6	26	10	1.93
25817		1.36	0.010	<0.2	0.59	14	<10	350	0.8	<2	1.27	<0.5	11	24	19	3.69
25818		3.76	0.009	0.3	0.53	25	<10	220	0.8	<2	1.50	0.5	13	23	31	3.33
25819		2.38	0.010	0.3	0.56	2	<10	400	1.0	<2	0.55	<0.5	14	20	46	4.09
25820		2.36	0.008	0.2	0.58	2	<10	290	0.7	<2	1.97	<0.5	14	22	32	4.00
25821		2.06	0.005	0.2	0.56	<2	<10	330	0.8	<2	1.66	<0.5	18	20	38	4.18
25822		1.98	0.009	<0.2	0.48	3	<10	240	0.5	<2	2.02	<0.5	13	20	25	3.35
25823		2.06	0.009	0.2	0.57	<2	<10	340	0.7	<2	0.97	0.5	17	18	34	3.35
25824		1.76	0.010	0.3	0.63	5	<10	450	1.0	<2	0.50	0.5	19	18	45	3.62
25825		0.10	1.195	9.7	1.75	460	<10	110	<0.5	<2	0.85	1.3	9	39	278	3.19
25826		1.78	0.014	0.2	0.62	12	<10	480	1.1	<2	0.38	0.6	19	19	50	3.44
25827		1.96	0.011	0.2	0.57	4	<10	330	0.8	<2	0.81	0.7	15	20	33	3.89
25828		2.74	0.007	0.3	0.54	4	<10	450	1.1	<2	0.42	0.5	17	10	31	3.69
25829		2.06	0.006	0.2	0.72	<2	<10	390	0.9	<2	0.64	<0.5	8	4	10	4.51
25830		1.62	0.006	0.2	0.64	5	<10	560	1.2	<2	0.12	<0.5	12	3	25	2.03
25831		2.04	0.007	<0.2	0.63	7	<10	450	1.0	<2	0.27	0.5	11	4	19	2.93

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 4-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09104183

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc	Sr
	Units	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm	ppm
	LOR	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1	1
25792		<10	<1	0.19	10	0.78	955	1	0.06	14	800	11	0.05	<2	9	101
25793		<10	<1	0.27	10	0.62	623	<1	0.06	11	570	13	0.02	<2	7	71
25794		<10	<1	0.29	10	0.54	178	<1	0.09	12	120	13	<0.01	<2	7	74
25795		<10	<1	0.22	10	0.95	1830	<1	0.09	7	1770	19	0.03	2	7	177
25796		<10	<1	0.29	10	0.50	172	<1	0.12	14	320	14	<0.01	2	7	80
25797		<10	<1	0.24	<10	0.68	236	<1	0.17	11	230	11	0.01	<2	8	111
25798		<10	<1	0.30	10	0.59	212	<1	0.23	12	640	11	<0.01	<2	9	101
25799		<10	<1	0.22	10	0.80	475	<1	0.12	38	530	10	0.02	<2	7	95
25800		<10	<1	0.14	10	0.87	485	<1	0.08	31	580	9	0.03	<2	5	135
25801		<10	1	0.16	10	0.77	384	<1	0.10	42	520	8	0.12	2	5	80
25802		<10	<1	0.25	<10	0.75	367	<1	0.18	39	560	12	0.11	<2	6	91
25803		<10	<1	0.13	<10	0.87	444	2	0.09	43	560	10	0.27	2	4	98
25804		<10	<1	0.26	<10	0.66	437	<1	0.23	25	230	9	0.03	<2	7	74
25805		<10	<1	0.15	10	1.04	793	<1	0.09	27	640	9	0.06	<2	5	164
25806		<10	<1	0.31	10	0.90	620	<1	0.20	35	430	11	0.02	<2	10	108
25807		<10	<1	0.14	10	0.75	397	<1	0.07	35	460	8	0.07	<2	6	83
25808		10	<1	0.14	<10	0.87	523	89	0.09	40	610	101	0.28	8	5	45
25809		<10	<1	0.14	10	0.65	327	<1	0.07	33	450	9	0.05	2	4	71
25810		<10	<1	0.15	10	0.60	262	<1	0.09	33	820	9	0.10	<2	5	72
25811		<10	<1	0.33	10	1.15	444	<1	0.21	60	530	12	<0.01	<2	10	99
25812		<10	<1	0.15	10	0.76	446	<1	0.08	34	520	8	0.02	2	5	82
25813		<10	<1	0.15	10	0.99	468	1	0.05	38	1390	14	0.05	2	4	111
25814		<10	<1	0.15	10	0.57	390	<1	0.07	29	450	8	0.07	2	4	58
25815		<10	<1	0.18	10	0.89	543	1	0.09	37	520	11	0.17	3	6	93
25816		<10	<1	0.15	10	0.70	353	<1	0.11	37	540	8	0.06	2	5	82
25817		<10	1	0.19	10	0.95	1055	<1	0.16	36	680	11	0.05	3	7	96
25818		<10	<1	0.19	10	1.10	658	3	0.06	47	440	16	0.09	5	8	124
25819		<10	<1	0.24	10	1.21	521	<1	0.11	62	550	15	<0.01	<2	10	85
25820		<10	<1	0.23	10	1.55	1170	<1	0.10	52	790	14	<0.01	<2	9	152
25821		<10	<1	0.23	10	1.43	977	<1	0.13	60	870	15	0.01	3	8	114
25822		<10	<1	0.19	10	1.33	558	<1	0.10	45	540	12	<0.01	<2	7	103
25823		<10	<1	0.22	10	1.09	544	<1	0.15	55	730	13	<0.01	2	8	96
25824		<10	<1	0.25	10	1.06	403	<1	0.20	67	620	17	0.01	2	9	89
25825		10	<1	0.13	<10	0.84	500	86	0.08	39	580	98	0.26	8	5	43
25826		<10	<1	0.25	10	1.01	473	<1	0.23	71	580	18	0.02	2	9	87
25827		<10	<1	0.21	10	1.16	407	<1	0.17	64	640	20	0.04	3	9	87
25828		<10	<1	0.21	10	0.83	413	<1	0.27	39	390	20	0.05	<2	8	83
25829		<10	<1	0.21	10	0.71	929	<1	0.25	9	1490	14	0.02	<2	6	96
25830		<10	<1	0.23	10	0.40	151	<1	0.35	13	160	18	0.04	2	7	89
25831		<10	<1	0.21	10	0.66	351	<1	0.31	16	210	17	0.03	<2	7	86

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 4-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09104183

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Th	Ti	Tl	U	V	W	Zn
	Units	ppm	%	ppm	ppm	ppm	ppm	ppm
	LOR	20	0.01	10	10	1	10	2
25792		<20	<0.01	<10	<10	43	<10	89
25793		<20	<0.01	<10	<10	33	<10	77
25794		<20	<0.01	<10	<10	33	<10	86
25795		<20	<0.01	<10	<10	52	<10	87
25796		<20	<0.01	<10	<10	33	<10	85
25797		<20	<0.01	<10	<10	53	<10	83
25798		<20	<0.01	<10	<10	40	<10	83
25799		<20	<0.01	<10	<10	36	<10	72
25800		<20	<0.01	<10	<10	35	<10	46
25801		<20	<0.01	<10	<10	30	<10	44
25802		<20	<0.01	<10	<10	33	<10	73
25803		<20	<0.01	<10	<10	30	<10	42
25804		<20	<0.01	<10	<10	31	<10	78
25805		<20	<0.01	<10	<10	34	<10	47
25806		<20	<0.01	<10	<10	48	<10	95
25807		<20	<0.01	<10	<10	36	<10	49
25808		<20	0.14	<10	<10	66	10	205
25809		<20	<0.01	<10	<10	27	<10	40
25810		<20	<0.01	<10	<10	31	<10	44
25811		<20	<0.01	<10	<10	47	<10	108
25812		<20	<0.01	<10	<10	35	<10	56
25813		<20	0.05	<10	<10	46	<10	99
25814		<20	<0.01	<10	<10	28	<10	43
25815		<20	<0.01	<10	<10	37	<10	59
25816		<20	<0.01	<10	<10	27	<10	46
25817		<20	<0.01	<10	<10	43	<10	74
25818		<20	<0.01	<10	<10	38	<10	102
25819		<20	<0.01	<10	<10	38	<10	112
25820		<20	<0.01	<10	<10	44	<10	93
25821		<20	<0.01	<10	<10	40	<10	104
25822		<20	<0.01	<10	<10	38	<10	79
25823		<20	<0.01	<10	<10	34	<10	98
25824		<20	<0.01	<10	<10	32	<10	114
25825		<20	0.13	<10	<10	62	10	195
25826		<20	<0.01	<10	<10	30	<10	125
25827		<20	<0.01	<10	<10	34	<10	145
25828		<20	<0.01	<10	<10	26	<10	99
25829		<20	<0.01	<10	<10	36	<10	73
25830		<20	<0.01	<10	<10	17	<10	101
25831		<20	<0.01	<10	<10	24	<10	100

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 4-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09104183

Sample Description	Method	WEI-21	Au-AA23	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu	Fe
	Units	kg	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	%
	LOR	0.02	0.005	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1	0.01
25832		2.10	0.006	0.2	0.57	<2	<10	460	1.0	<2	0.27	<0.5	6	7	22	3.08
25833		2.18	0.008	<0.2	0.65	7	<10	480	1.3	<2	0.41	0.5	14	9	20	6.64
25834		1.74	0.007	0.3	0.56	4	<10	340	0.9	<2	1.05	0.6	19	26	41	4.23
25835		2.64	0.006	0.3	0.47	2	<10	290	0.8	<2	1.55	<0.5	14	22	32	3.56
25836		1.46	<0.005	0.2	0.39	3	<10	230	0.7	<2	1.70	<0.5	11	18	21	3.13
25837		1.72	<0.005	0.2	0.40	8	<10	200	0.5	<2	1.59	<0.5	8	26	12	2.65
25838		0.50	0.005	0.2	0.90	5	<10	570	<0.5	<2	2.09	1.0	8	48	20	1.89
25839		1.62	<0.005	0.2	0.42	13	<10	210	0.5	<2	1.33	<0.5	8	20	13	2.47
25840		2.46	<0.005	0.2	0.32	22	<10	180	<0.5	<2	1.39	<0.5	8	18	13	2.07
25841		1.84	0.007	0.3	0.64	4	<10	370	1.1	<2	0.98	0.5	14	20	36	3.72
25842		1.82	0.005	0.2	0.44	5	<10	280	0.8	<2	1.61	<0.5	12	21	29	3.60
25843		2.68	<0.005	0.3	0.56	13	<10	250	0.7	<2	1.44	<0.5	11	25	23	3.19
25844		2.32	<0.005	0.2	0.28	14	<10	170	<0.5	<2	1.31	<0.5	7	21	12	1.94
25845		2.54	<0.005	0.2	0.30	13	<10	180	0.5	<2	1.29	<0.5	9	22	14	1.83
25846		2.26	<0.005	0.2	0.26	10	<10	150	<0.5	<2	1.41	<0.5	7	23	12	1.98
25847		0.66	<0.005	0.2	1.12	8	<10	420	<0.5	<2	2.70	1.0	10	33	21	2.45
25848		2.80	<0.005	<0.2	0.28	18	<10	160	<0.5	<2	1.09	<0.5	8	26	10	1.95
25849		2.40	<0.005	0.2	0.25	11	<10	130	<0.5	<2	1.23	<0.5	8	29	13	1.60
25850		1.96	<0.005	0.3	0.68	5	<10	450	1.2	<2	0.36	0.6	19	21	65	3.78
25851		2.48	0.007	0.3	0.64	<2	<10	430	1.0	<2	0.39	<0.5	17	20	39	3.96
25852		1.88	0.005	0.3	0.75	5	<10	420	0.9	<2	2.25	0.6	15	25	40	3.89
25853		2.28	0.006	0.4	0.69	<2	<10	490	1.1	<2	0.35	0.5	17	21	50	3.61
25854		2.00	0.006	0.4	0.62	<2	<10	360	0.7	<2	1.69	0.5	14	23	39	3.75
25855		1.88	0.006	0.3	0.51	<2	<10	360	0.9	<2	0.94	0.5	14	22	37	4.41
25856		2.46	0.006	0.2	0.69	<2	<10	320	0.6	<2	1.52	<0.5	11	26	28	3.42
25857		2.02	0.007	0.3	0.95	6	<10	480	1.2	<2	0.96	0.5	15	24	37	3.59
25858		2.84	<0.005	<0.2	1.02	5	<10	440	1.3	<2	2.22	<0.5	21	24	22	5.17
25859		0.10	1.025	9.7	1.79	462	<10	110	<0.5	<2	0.85	1.5	10	39	280	3.42
25860		2.00	0.006	0.3	1.12	13	<10	500	1.1	<2	1.93	0.5	19	43	34	4.91
25861		2.86	<0.005	0.2	1.10	6	<10	460	1.2	<2	2.21	<0.5	20	27	28	5.20
25862		2.90	0.007	0.2	0.62	10	<10	300	0.5	<2	1.31	<0.5	10	23	22	2.22
25863		2.30	0.005	0.2	0.48	19	<10	200	<0.5	<2	2.16	<0.5	6	23	13	2.67
25864		1.84	0.008	<0.2	0.63	15	<10	300	0.6	<2	1.63	<0.5	8	28	20	3.25
25865		1.96	0.038	0.2	0.73	10	<10	360	0.8	<2	1.54	<0.5	10	18	25	2.66
25866		2.12	0.006	<0.2	0.70	3	<10	360	0.8	<2	1.20	<0.5	16	28	30	3.48
25867		2.08	0.014	<0.2	0.48	4	<10	230	<0.5	<2	0.70	<0.5	6	26	19	2.04
25868		0.10	1.060	8.9	1.71	455	<10	110	<0.5	<2	0.83	1.4	9	38	277	3.16
25869		1.32	0.006	0.2	0.48	3	<10	220	<0.5	<2	1.24	<0.5	7	27	16	2.30
25870		1.76	<0.005	0.3	0.50	3	<10	240	<0.5	<2	0.82	<0.5	6	23	18	2.04
25871		1.94	0.006	0.2	0.76	<2	<10	400	0.9	<2	0.66	<0.5	13	27	30	3.33

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09104183

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc	Sr
	Units	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm	ppm
	LOR	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1	1
25832		<10	<1	0.21	10	0.72	267	<1	0.30	24	190	17	0.03	<2	7	85
25833		<10	<1	0.24	10	0.87	1700	<1	0.30	34	490	17	0.05	<2	7	91
25834		<10	<1	0.22	10	1.15	886	<1	0.19	83	970	16	0.02	<2	7	119
25835		<10	<1	0.18	10	1.13	648	<1	0.15	57	660	16	0.02	<2	7	131
25836		<10	<1	0.14	10	1.03	529	<1	0.14	42	700	14	0.01	<2	6	125
25837		<10	<1	0.13	10	0.86	516	<1	0.13	45	760	10	0.03	<2	5	110
25838		<10	<1	0.09	10	1.01	387	1	0.05	48	1230	18	0.06	<2	3	87
25839		<10	<1	0.13	10	0.89	439	<1	0.15	44	850	11	0.06	2	5	95
25840		<10	<1	0.10	<10	0.87	434	<1	0.13	40	700	9	0.08	<2	5	97
25841		<10	<1	0.24	10	1.18	601	1	0.22	57	520	16	0.07	<2	9	105
25842		<10	<1	0.16	10	1.21	810	1	0.16	46	550	13	0.05	<2	8	114
25843		<10	<1	0.19	10	1.08	648	2	0.14	48	550	11	0.11	<2	7	103
25844		<10	<1	0.10	<10	0.98	406	<1	0.11	48	440	8	0.08	<2	5	88
25845		<10	<1	0.10	<10	0.94	362	1	0.12	51	450	10	0.06	<2	5	86
25846		<10	<1	0.10	<10	1.00	345	<1	0.09	44	350	9	0.04	<2	4	73
25847		<10	<1	0.09	10	1.26	524	1	0.05	36	1420	17	0.07	<2	3	98
25848		<10	<1	0.10	<10	0.87	341	1	0.10	60	470	9	0.07	<2	4	72
25849		<10	<1	0.09	<10	0.86	357	1	0.07	50	430	12	0.06	<2	3	86
25850		<10	<1	0.26	10	1.07	702	<1	0.23	65	450	19	0.03	<2	9	74
25851		<10	<1	0.23	10	1.10	883	<1	0.22	63	520	13	0.01	<2	9	76
25852		<10	<1	0.29	10	1.83	911	<1	0.21	61	590	12	0.01	<2	9	158
25853		<10	<1	0.30	10	1.14	512	<1	0.24	73	380	13	0.01	<2	9	80
25854		<10	<1	0.26	10	1.51	630	<1	0.18	64	470	16	0.01	<2	8	129
25855		<10	<1	0.21	10	1.18	1080	<1	0.17	61	590	12	0.02	<2	8	88
25856		<10	<1	0.25	10	1.30	570	1	0.14	45	440	12	0.02	<2	8	105
25857		<10	<1	0.35	<10	1.10	507	<1	0.24	56	520	14	0.03	<2	9	101
25858		<10	<1	0.30	10	1.91	947	1	0.27	43	1360	5	0.09	<2	10	127
25859		<10	<1	0.14	<10	0.85	506	87	0.10	39	590	97	0.29	8	5	43
25860		<10	<1	0.38	10	1.70	879	1	0.26	60	1270	10	0.08	<2	10	153
25861		<10	<1	0.35	10	1.93	980	1	0.27	49	1590	4	0.12	2	10	159
25862		<10	<1	0.22	<10	0.79	447	1	0.15	41	560	11	0.08	<2	5	92
25863		<10	<1	0.16	<10	1.09	471	<1	0.11	32	490	11	0.08	2	4	120
25864		<10	<1	0.22	10	1.01	599	<1	0.14	41	510	11	0.06	<2	7	107
25865		<10	<1	0.25	10	1.04	522	<1	0.16	36	530	13	0.07	<2	7	126
25866		<10	<1	0.27	10	1.03	617	<1	0.15	58	530	13	0.01	2	7	96
25867		<10	<1	0.16	10	0.66	404	<1	0.10	40	480	9	0.02	<2	4	70
25868		<10	<1	0.13	<10	0.82	494	85	0.08	37	570	97	0.25	7	5	41
25869		<10	<1	0.15	10	0.84	494	<1	0.09	45	530	10	0.01	<2	5	99
25870		<10	<1	0.16	<10	0.62	409	<1	0.09	37	500	8	0.01	<2	4	74
25871		<10	<1	0.28	10	0.87	513	<1	0.16	58	620	12	0.01	2	7	77

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 4-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09104183

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Th	Ti	Tl	U	V	W	Zn
	Units	ppm	%	ppm	ppm	ppm	ppm	ppm
	LOR	20	0.01	10	10	1	10	2
25832		<20	<0.01	<10	<10	21	<10	96
25833		<20	<0.01	<10	<10	25	<10	92
25834		<20	<0.01	<10	<10	35	<10	112
25835		<20	<0.01	<10	<10	38	<10	94
25836		<20	<0.01	<10	<10	36	<10	72
25837		<20	<0.01	<10	<10	33	<10	47
25838		<20	0.03	<10	<10	44	<10	87
25839		<20	<0.01	<10	<10	32	<10	48
25840		<20	<0.01	<10	<10	29	<10	48
25841		<20	<0.01	<10	<10	36	<10	101
25842		<20	<0.01	<10	<10	38	<10	88
25843		<20	<0.01	<10	<10	37	<10	72
25844		<20	<0.01	<10	<10	24	<10	41
25845		<20	<0.01	<10	<10	23	<10	41
25846		<20	<0.01	<10	<10	23	<10	42
25847		<20	0.07	<10	<10	47	<10	89
25848		<20	<0.01	<10	<10	21	<10	40
25849		<20	<0.01	<10	<10	17	<10	35
25850		<20	<0.01	<10	<10	35	<10	123
25851		<20	<0.01	<10	<10	39	<10	101
25852		<20	<0.01	<10	<10	41	<10	98
25853		<20	<0.01	<10	<10	35	<10	115
25854		<20	<0.01	<10	<10	41	<10	98
25855		<20	<0.01	<10	<10	32	<10	90
25856		<20	<0.01	<10	<10	38	<10	76
25857		<20	<0.01	<10	<10	36	<10	97
25858		<20	<0.01	<10	<10	81	<10	82
25859		<20	0.13	<10	<10	63	<10	199
25860		<20	<0.01	<10	<10	55	<10	86
25861		<20	<0.01	<10	<10	68	<10	77
25862		<20	<0.01	<10	<10	27	<10	57
25863		<20	<0.01	<10	<10	33	<10	41
25864		<20	<0.01	<10	<10	36	<10	63
25865		<20	<0.01	<10	<10	34	<10	75
25866		<20	<0.01	<10	<10	35	<10	83
25867		<20	<0.01	<10	<10	24	<10	46
25868		<20	0.13	<10	<10	62	10	191
25869		<20	<0.01	<10	<10	27	<10	46
25870		<20	<0.01	<10	<10	24	<10	44
25871		<20	<0.01	<10	<10	33	<10	87

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 4-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09104183

Sample Description	Method	WEI-21	Au-AA23	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu	Fe
	Units	kg	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	%
	LOR	0.02	0.005	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1	0.01
25872		1.08	0.008	<0.2	0.60	3	<10	320	0.7	<2	1.27	<0.5	12	25	25	3.04
25873		2.26	0.006	0.2	0.46	12	<10	220	<0.5	<2	1.29	<0.5	7	31	16	2.44
25874		2.10	0.005	0.2	0.78	16	<10	510	1.0	<2	0.99	<0.5	12	24	31	3.11
25875		0.62	<0.005	0.2	1.50	6	<10	550	<0.5	<2	2.22	1.2	9	37	26	2.66
25876		2.00	0.006	0.2	0.77	3	<10	430	0.8	<2	1.02	<0.5	13	28	32	3.77
25877		2.22	0.006	0.2	0.78	4	<10	410	0.8	<2	1.21	0.5	16	32	38	3.91
25878		1.86	0.006	0.3	0.73	3	<10	350	0.6	<2	1.36	<0.5	15	29	33	3.38
25879		1.84	0.006	0.3	0.93	4	<10	460	0.8	<2	0.88	<0.5	19	29	36	3.23
25880		2.50	0.005	0.2	0.84	2	<10	500	1.0	<2	0.87	<0.5	11	29	36	4.29
25881		2.00	0.006	0.2	0.89	16	<10	550	1.1	<2	0.66	0.7	15	29	46	4.82
25882		2.08	0.005	<0.2	0.85	8	<10	470	0.8	<2	0.72	<0.5	10	23	33	3.24
25883		2.44	0.005	0.2	0.73	7	<10	390	0.7	<2	1.65	<0.5	11	23	25	3.25
25884		1.58	0.005	<0.2	0.97	5	<10	450	1.0	<2	2.97	<0.5	11	36	32	5.53
25885		2.24	<0.005	<0.2	0.63	7	<10	310	0.5	<2	1.55	<0.5	8	31	26	3.46
25886		2.04	<0.005	0.2	0.57	10	<10	280	<0.5	<2	1.53	<0.5	12	23	18	2.66
25887		0.56	<0.005	<0.2	1.10	11	<10	650	<0.5	<2	2.59	1.1	8	41	23	2.14
25888		2.42	0.005	<0.2	0.78	4	<10	410	0.7	<2	1.44	<0.5	7	31	30	3.63
25889		2.14	0.007	0.2	0.99	7	<10	640	1.0	<2	0.42	0.6	20	20	45	3.05
25890		2.12	0.006	<0.2	0.85	2	<10	520	0.9	<2	1.03	<0.5	11	21	32	4.17
25891		1.92	0.007	<0.2	0.98	4	<10	580	0.9	<2	0.54	0.5	18	28	38	3.61
25892		2.82	0.005	<0.2	0.34	4	<10	230	<0.5	<2	1.84	<0.5	8	27	21	3.46
25893		1.84	0.006	0.2	0.40	2	<10	270	<0.5	<2	1.50	<0.5	9	25	23	3.50
25894		1.90	<0.005	0.2	0.37	10	<10	270	<0.5	<2	1.46	<0.5	20	18	18	2.14
25895		1.58	0.007	<0.2	0.44	6	<10	320	0.5	<2	1.32	<0.5	20	23	22	3.16
25896		0.10	9.73	0.5	1.54	4110	<10	60	0.5	<2	0.82	<0.5	14	69	66	3.52
25897		1.32	0.012	<0.2	0.39	41	<10	420	0.6	2	2.23	<0.5	9	27	24	4.91
25898		1.56	<0.005	0.2	0.71	3	<10	850	1.0	<2	2.96	<0.5	24	27	28	6.44
25899		1.96	<0.005	<0.2	0.52	3	<10	410	0.8	<2	1.87	<0.5	12	17	27	4.62
25900		2.06	0.005	<0.2	0.28	16	<10	210	<0.5	<2	1.46	<0.5	7	21	15	2.15
25901		1.80	0.007	0.2	0.24	19	<10	190	<0.5	<2	1.11	<0.5	6	26	14	2.82
25902		2.26	0.006	<0.2	0.29	12	<10	210	<0.5	<2	0.84	<0.5	8	24	15	1.95
25903		2.04	0.005	0.2	0.28	22	<10	200	<0.5	<2	1.43	<0.5	8	21	16	1.84
25904		1.42	0.005	0.2	0.45	3	<10	410	0.9	<2	0.75	<0.5	15	19	32	3.41

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 4-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09104183

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc	Sr
	Units	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm	ppm
	LOR	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1	1
25872		<10	<1	0.23	10	1.00	551	<1	0.12	54	560	9	0.01	<2	6	102
25873		<10	<1	0.16	<10	0.92	516	<1	0.08	50	430	7	0.07	3	4	77
25874		<10	<1	0.27	10	1.02	539	1	0.20	53	440	14	0.14	<2	7	84
25875		10	<1	0.27	10	1.11	509	1	0.04	39	1040	13	0.06	3	5	100
25876		<10	<1	0.27	10	1.15	666	<1	0.16	54	520	16	0.01	<2	8	93
25877		<10	<1	0.26	10	1.30	684	2	0.13	69	580	16	0.03	2	8	126
25878		<10	<1	0.25	10	1.09	702	<1	0.12	64	690	14	0.02	<2	7	119
25879		<10	<1	0.31	10	0.93	595	<1	0.16	60	720	16	0.04	3	8	93
25880		<10	<1	0.30	10	1.09	876	<1	0.19	49	780	10	0.01	3	9	82
25881		<10	<1	0.34	10	1.19	766	<1	0.19	67	580	17	<0.01	2	9	88
25882		<10	<1	0.31	10	1.02	333	<1	0.18	47	550	12	<0.01	<2	8	99
25883		<10	<1	0.26	10	1.20	524	<1	0.15	41	530	13	0.01	<2	7	123
25884		<10	<1	0.34	10	1.95	1335	<1	0.18	46	660	12	<0.01	2	10	107
25885		<10	<1	0.22	10	1.15	732	<1	0.12	36	690	10	0.01	3	7	91
25886		<10	<1	0.19	10	0.92	545	<1	0.13	40	700	12	0.03	2	6	100
25887		<10	<1	0.15	10	1.11	495	1	0.03	40	1010	44	0.04	2	4	110
25888		<10	<1	0.28	10	1.09	794	<1	0.17	37	700	13	<0.01	2	8	80
25889		<10	<1	0.37	10	0.96	336	8	0.24	57	590	18	0.04	<2	10	73
25890		<10	<1	0.32	10	1.26	668	<1	0.19	40	690	14	<0.01	2	9	91
25891		<10	<1	0.35	10	1.09	489	1	0.20	55	620	14	0.03	<2	10	71
25892		<10	<1	0.13	<10	1.39	548	<1	0.11	35	560	11	0.02	<2	7	100
25893		<10	<1	0.15	<10	1.33	540	<1	0.13	37	610	12	0.01	2	7	94
25894		<10	<1	0.14	<10	0.93	363	<1	0.13	47	590	11	0.02	2	5	89
25895		<10	<1	0.17	10	1.16	449	<1	0.15	51	650	10	0.01	2	7	90
25896		10	<1	0.16	10	0.88	396	6	0.06	65	490	6	0.88	32	4	40
25897		<10	<1	0.17	10	1.82	1165	<1	0.14	39	610	11	0.33	4	9	99
25898		<10	2	0.20	20	2.37	1265	<1	0.24	35	2660	3	0.08	<2	12	173
25899		<10	1	0.20	10	1.52	728	<1	0.17	31	850	13	0.01	<2	10	129
25900		<10	<1	0.11	<10	0.91	436	2	0.07	37	370	8	0.09	<2	4	93
25901		<10	1	0.10	<10	0.96	509	4	0.07	40	310	6	0.15	2	4	74
25902		<10	1	0.10	<10	0.68	350	1	0.08	42	350	7	0.07	<2	4	66
25903		<10	1	0.10	<10	0.83	377	1	0.09	42	450	9	0.19	2	5	107
25904		<10	<1	0.19	10	1.13	485	1	0.19	51	460	13	0.05	<2	9	82

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 4-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09104183

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Th	Ti	Tl	U	V	W	Zn
	Units	ppm	%	ppm	ppm	ppm	ppm	ppm
	LOR	20	0.01	10	10	1	10	2
25872		<20	<0.01	<10	<10	29	<10	64
25873		<20	<0.01	<10	<10	22	<10	42
25874		<20	<0.01	<10	<10	32	<10	85
25875		<20	0.09	<10	<10	52	<10	94
25876		<20	<0.01	<10	<10	40	<10	94
25877		<20	<0.01	<10	<10	42	<10	108
25878		<20	<0.01	<10	<10	39	<10	86
25879		<20	<0.01	<10	<10	41	<10	104
25880		<20	<0.01	<10	<10	42	<10	105
25881		<20	<0.01	<10	<10	43	<10	120
25882		<20	<0.01	<10	<10	38	<10	96
25883		<20	<0.01	<10	<10	40	<10	80
25884		<20	<0.01	<10	<10	62	<10	99
25885		<20	<0.01	<10	<10	43	<10	64
25886		<20	<0.01	<10	<10	35	<10	62
25887		<20	0.05	<10	<10	46	<10	136
25888		<20	<0.01	<10	<10	41	<10	81
25889		<20	<0.01	<10	<10	43	<10	114
25890		<20	<0.01	<10	<10	48	<10	83
25891		<20	<0.01	<10	<10	44	<10	103
25892		<20	<0.01	<10	<10	42	<10	61
25893		<20	<0.01	<10	<10	39	<10	67
25894		<20	<0.01	<10	<10	30	<10	63
25895		<20	<0.01	<10	<10	39	<10	63
25896		<20	0.11	<10	<10	52	40	51
25897		<20	<0.01	<10	<10	45	<10	71
25898		<20	0.01	<10	<10	88	<10	77
25899		<20	<0.01	<10	<10	51	<10	85
25900		<20	<0.01	<10	<10	21	<10	48
25901		<20	<0.01	<10	<10	27	<10	48
25902		<20	<0.01	<10	<10	21	<10	49
25903		<20	<0.01	<10	<10	20	<10	51
25904		<20	<0.01	<10	<10	32	<10	89

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 15-OCT-2009
This copy reported on 3-DEC-2009
Account: EMERES

CERTIFICATE VA09107059

Project: Canyon Gold

P.O. No.:

This report is for 150 Rock samples submitted to our lab in Vancouver, BC, Canada on 29-SEP-2009.

The following have access to data associated with this certificate:

SARA PUBLICOVER	SIMON RIDGWAY	

SAMPLE PREPARATION

ALS CODE	DESCRIPTION
WEI-21	Received Sample Weight
LOG-22	Sample login - Rcd w/o BarCode
LOG-24	Pulp Login - Rcd w/o Barcode
CRU-QC	Crushing QC Test
PUL-QC	Pulverizing QC Test
CRU-31	Fine crushing - 70% <2mm
SPL-21	Split sample - riffle splitter
PUL-31	Pulverize split to 85% <75 um

ANALYTICAL PROCEDURES

ALS CODE	DESCRIPTION	INSTRUMENT
ME-ICP41	35 Element Aqua Regia ICP-AES	ICP-AES
Au-AA23	Au 30g FA-AA finish	AAS
Au-GRA21	Au 30g FA-GRAV finish	WST-SIM

To: EMERICK RESOURCES LTD.
ATTN: SARA PUBLICOVER
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

This is the Final Report and supersedes any preliminary report with this certificate number. Results apply to samples as submitted. All pages of this report have been checked and approved for release.

Signature:

Colin Ramshaw, Vancouver Laboratory Manager

ALS Chemex

EXCELLENCE IN ANALYTICAL CHEMISTRY

ALS Canada Ltd

2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 15-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107059

Sample Description	Method	WEI-21	Au-AA23	Au-GRA21	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt.	Au	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu
	Units	kg	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm
	LOR	0.02	0.005	0.05	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1
25905		3.86	0.006		<0.2	0.64	19	<10	70	2.0	<2	1.21	<0.5	4	6	7
25906		3.58	<0.005		<0.2	0.78	21	<10	80	2.4	<2	1.66	<0.5	6	12	7
25907		2.72	0.008		<0.2	0.58	20	<10	90	2.5	2	1.34	<0.5	7	10	7
25908		3.66	0.013		<0.2	0.70	33	<10	80	2.3	<2	1.76	<0.5	5	6	8
25909		1.94	0.006		<0.2	0.91	20	<10	100	2.3	<2	1.70	<0.5	6	14	10
25910		0.44	<0.005		<0.2	1.19	9	<10	710	<0.5	<2	2.40	1.0	7	42	22
25911		1.42	0.006		<0.2	0.70	25	<10	110	2.2	<2	1.70	<0.5	7	13	11
25912		Not Recvd														
25913		2.90	0.151		<0.2	0.71	116	<10	90	1.9	2	0.82	<0.5	3	3	5
25914		2.62	0.019		<0.2	0.60	22	<10	50	2.0	2	1.98	<0.5	4	5	5
25915		3.48	0.014		<0.2	0.65	21	<10	40	2.2	<2	2.18	<0.5	5	4	7
25916		0.10	0.851		9.1	1.72	450	<10	110	<0.5	<2	0.83	1.2	10	37	278
25917		4.12	0.013		<0.2	0.98	19	<10	80	2.4	<2	1.93	<0.5	8	11	9
25918		3.58	0.024		<0.2	0.86	26	<10	80	2.3	2	1.33	<0.5	7	10	7
25919		3.72	0.012		<0.2	0.62	18	<10	70	2.0	<2	1.65	<0.5	5	7	10
25920		3.50	0.007		<0.2	0.77	15	<10	70	2.1	<2	1.55	<0.5	5	9	7
25921		3.92	0.007		<0.2	0.62	12	<10	60	2.0	<2	1.61	<0.5	5	7	7
25922		3.64	0.024		<0.2	0.68	27	<10	70	2.3	<2	1.24	<0.5	5	7	7
25923		0.10	>10.0	9.83	0.4	1.55	3940	<10	60	0.5	2	0.83	<0.5	15	69	69
25924		3.24	0.011		<0.2	0.83	19	<10	70	2.2	<2	1.36	<0.5	6	9	5
25925		3.74	0.006		<0.2	0.57	8	<10	70	2.2	<2	1.22	<0.5	4	6	11
25926		4.06	0.005		<0.2	0.61	8	<10	70	2.3	<2	1.12	<0.5	5	5	13
25927		3.78	<0.005		<0.2	0.91	18	<10	90	2.3	<2	1.61	<0.5	12	25	14
25928		4.28	<0.005		<0.2	0.63	5	<10	90	1.9	<2	1.48	<0.5	7	11	22
25929		4.10	<0.005		<0.2	0.94	17	<10	110	2.5	<2	2.80	<0.5	18	38	16
25930		4.22	<0.005		0.3	1.01	12	<10	100	2.3	<2	2.88	<0.5	18	42	13
25931		4.00	0.014		<0.2	0.86	25	<10	110	2.5	<2	2.09	<0.5	10	12	14
25932		5.52	0.008		<0.2	0.67	20	<10	90	1.6	<2	1.67	<0.5	5	5	6
25933		3.44	<0.005		<0.2	0.86	18	<10	100	2.0	2	3.99	<0.5	17	40	15
25934		4.50	<0.005		<0.2	0.88	3	<10	250	2.5	<2	4.34	<0.5	22	37	34
25935		5.22	<0.005		<0.2	1.69	2	<10	540	1.7	2	4.25	<0.5	26	57	40
25936		0.62	<0.005		0.2	1.18	12	<10	590	<0.5	<2	2.08	1.0	8	45	25
25937		4.18	<0.005		<0.2	3.22	3	<10	320	1.0	2	4.23	<0.5	32	65	43
25938		4.72	<0.005		<0.2	1.84	<2	<10	340	0.5	2	5.03	<0.5	25	45	32
25939		4.26	<0.005		<0.2	3.15	<2	<10	260	0.5	2	3.50	<0.5	33	51	39
25940		4.70	<0.005		<0.2	3.09	<2	<10	210	0.6	<2	2.96	<0.5	31	40	41
25941		4.54	<0.005		<0.2	3.32	<2	<10	190	0.5	<2	3.09	<0.5	31	41	41
25942		4.88	<0.005		<0.2	2.25	<2	<10	310	0.6	<2	3.79	<0.5	32	57	39
25943		4.86	<0.005		<0.2	2.91	2	<10	240	2.0	<2	3.88	<0.5	37	65	42
25944		4.34	<0.005		<0.2	1.20	6	<10	210	2.9	2	4.86	<0.5	31	60	37

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax. 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 15-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107059

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Fe	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc
	Units	%	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm
	LOR	0.01	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1
25905		2.40	<10	<1	0.36	10	0.29	491	4	0.02	5	130	31	0.02	<2	1
25906		2.81	<10	<1	0.42	10	0.45	622	4	0.02	8	330	26	0.01	<2	2
25907		3.02	<10	<1	0.32	10	0.43	658	5	0.02	8	360	25	0.09	<2	2
25908		2.61	<10	<1	0.40	10	0.33	614	4	0.03	6	240	27	0.17	<2	1
25909		2.91	<10	<1	0.47	10	0.33	587	4	0.03	10	310	24	0.10	<2	2
25910		2.12	<10	<1	0.20	10	1.22	454	2	0.06	40	890	14	0.05	<2	4
25911		3.01	<10	<1	0.36	10	0.32	548	5	0.04	11	370	28	0.07	<2	2
25912																
25913		2.17	<10	<1	0.39	10	0.26	367	4	0.06	3	100	29	0.59	<2	1
25914		2.30	<10	<1	0.35	10	0.33	612	4	0.05	6	220	27	0.25	<2	1
25915		2.47	<10	<1	0.37	10	0.46	657	4	0.07	6	230	27	0.19	<2	1
25916		3.26	<10	<1	0.14	10	0.87	495	86	0.09	37	540	95	0.25	6	5
25917		3.01	<10	<1	0.50	10	0.63	641	3	0.11	10	490	24	0.09	<2	2
25918		3.01	<10	<1	0.45	10	0.58	606	3	0.11	8	370	23	0.17	<2	2
25919		2.63	<10	<1	0.37	10	0.42	601	3	0.10	7	250	27	0.10	<2	1
25920		2.65	<10	<1	0.42	10	0.41	571	3	0.11	7	280	26	0.08	<2	1
25921		2.70	<10	<1	0.36	10	0.43	592	3	0.10	7	250	25	0.09	<2	1
25922		2.52	<10	<1	0.38	10	0.42	524	3	0.12	7	260	28	0.16	<2	1
25923		3.63	10	<1	0.17	10	0.92	396	7	0.07	63	470	6	0.88	35	5
25924		2.69	<10	<1	0.44	10	0.43	572	4	0.11	7	290	26	0.05	<2	2
25925		2.43	<10	<1	0.34	10	0.41	515	3	0.10	5	140	32	0.05	<2	1
25926		2.50	<10	<1	0.34	10	0.54	483	3	0.11	6	120	25	0.05	<2	1
25927		3.93	<10	<1	0.44	10	0.93	753	3	0.14	16	690	18	0.01	<2	4
25928		3.03	<10	<1	0.34	10	0.74	648	3	0.11	10	320	20	0.02	<2	2
25929		4.94	<10	<1	0.44	10	1.49	958	2	0.14	25	990	14	0.05	<2	5
25930		4.95	<10	<1	0.46	20	1.51	877	2	0.15	23	1350	14	0.10	<2	6
25931		3.43	<10	<1	0.40	10	1.03	658	2	0.15	13	710	14	0.25	2	3
25932		2.40	<10	<1	0.36	10	0.76	492	1	0.12	6	260	23	0.17	<2	1
25933		4.61	<10	<1	0.35	20	2.38	925	1	0.16	23	1090	10	0.13	<2	5
25934		4.99	<10	<1	0.32	20	3.09	1030	1	0.25	28	940	4	0.13	<2	15
25935		6.05	<10	1	0.25	20	3.15	1130	1	0.40	30	1060	2	0.04	<2	26
25936		2.03	<10	<1	0.19	10	1.16	445	2	0.05	44	1110	24	0.06	<2	4
25937		5.72	<10	<1	0.17	10	2.45	933	1	0.74	39	1090	2	0.04	<2	26
25938		5.46	<10	<1	0.25	10	4.03	1080	1	0.41	43	840	2	0.01	<2	18
25939		5.69	<10	<1	0.18	10	3.56	1035	1	0.70	71	1010	2	0.02	<2	13
25940		5.32	<10	1	0.13	10	3.23	863	1	0.72	74	1060	2	0.03	<2	8
25941		5.37	<10	1	0.10	10	3.34	902	1	0.78	72	1060	<2	0.03	<2	6
25942		5.80	<10	1	0.20	10	3.87	937	1	0.53	64	1020	<2	0.02	<2	19
25943		6.12	<10	1	0.23	10	3.14	998	1	0.65	84	1080	3	0.07	<2	16
25944		5.17	<10	<1	0.42	10	3.54	973	1	0.33	62	1010	<2	0.05	<2	19

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 15-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107059

Sample Description	Method / Analyte / Units / LOR	ME-ICP41 Sr ppm 1	ME-ICP41 Th ppm 20	ME-ICP41 Ti % 0.01	ME-ICP41 Tl ppm 10	ME-ICP41 U ppm 10	ME-ICP41 V ppm 1	ME-ICP41 W ppm 10	ME-ICP41 Zn ppm 2
25905		36	<20	<0.01	<10	<10	7	<10	101
25906		48	<20	<0.01	<10	<10	14	<10	92
25907		46	<20	<0.01	<10	<10	13	<10	101
25908		52	<20	<0.01	<10	<10	8	<10	104
25909		53	<20	<0.01	<10	<10	13	<10	100
25910		95	<20	0.05	<10	<10	48	<10	97
25911		52	<20	<0.01	<10	<10	17	<10	101
25912									
25913		29	<20	<0.01	<10	<10	4	<10	95
25914		49	<20	<0.01	<10	<10	6	<10	91
25915		58	<20	<0.01	<10	<10	6	<10	93
25916		42	<20	0.13	<10	<10	61	10	191
25917		62	<20	<0.01	<10	<10	15	<10	101
25918		49	<20	<0.01	<10	<10	14	<10	95
25919		46	<20	<0.01	<10	<10	9	<10	93
25920		45	<20	<0.01	<10	<10	10	<10	93
25921		43	<20	<0.01	<10	<10	10	<10	94
25922		42	<20	<0.01	<10	<10	10	<10	97
25923		41	<20	0.11	<10	<10	52	40	51
25924		43	<20	<0.01	<10	<10	11	<10	91
25925		40	<20	<0.01	<10	<10	8	<10	94
25926		41	<20	<0.01	<10	<10	9	<10	90
25927		57	<20	<0.01	<10	<10	33	<10	92
25928		49	<20	<0.01	<10	<10	17	<10	87
25929		84	<20	<0.01	<10	<10	52	<10	94
25930		84	<20	<0.01	<10	<10	52	<10	100
25931		69	<20	<0.01	<10	<10	23	<10	79
25932		55	<20	<0.01	<10	<10	8	<10	88
25933		156	<20	<0.01	<10	<10	54	<10	84
25934		193	<20	<0.01	<10	<10	57	<10	62
25935		213	<20	0.01	<10	<10	77	<10	63
25936		85	<20	0.05	<10	<10	52	<10	126
25937		269	<20	0.04	<10	<10	73	<10	65
25938		303	<20	0.01	<10	<10	55	<10	51
25939		238	<20	0.03	<10	<10	47	<10	62
25940		208	<20	0.04	<10	<10	35	<10	62
25941		241	<20	0.05	<10	<10	32	<10	59
25942		264	<20	0.02	<10	<10	57	<10	50
25943		255	<20	0.03	<10	<10	61	<10	66
25944		262	<20	<0.01	<10	<10	69	<10	67

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax. 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 15-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107059

Sample Description	Method	WEI-21	Au-AA23	Au-GRA21	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt	Au	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu
	Units	kg	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm
	LOR	0.02	0.005	0.05	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1
25945		4.90	0.009		<0.2	0.73	24	<10	100	1.6	<2	4.10	<0.5	7	16	11
25946		1.92	0.008		<0.2	0.81	15	<10	90	1.1	<2	2.49	<0.5	4	5	8
25947		3.76	0.007		<0.2	0.74	21	<10	100	1.2	<2	2.07	<0.5	8	9	11
25948		4.94	0.008		<0.2	0.66	15	<10	100	1.2	<2	1.41	<0.5	6	6	6
25949		4.46	<0.005		<0.2	0.97	16	<10	120	1.3	<2	2.81	<0.5	13	24	13
25950		3.80	<0.005		<0.2	0.82	15	<10	130	1.7	<2	2.26	<0.5	12	17	18
25951		0.10	9.63		0.4	1.47	3880	<10	60	0.5	2	0.76	<0.5	14	65	67
25952		5.04	0.006		<0.2	0.76	18	<10	130	1.5	2	2.36	<0.5	7	9	12
25953		2.46	<0.005		<0.2	0.82	7	<10	130	1.9	<2	2.46	<0.5	5	6	9
25954		4.06	<0.005		<0.2	1.05	8	<10	240	2.6	<2	4.95	<0.5	24	35	35
25955		2.54	0.009		<0.2	0.96	29	<10	200	2.3	<2	5.61	<0.5	18	21	19
25956		3.78	<0.005		<0.2	0.90	5	<10	120	1.1	<2	1.27	<0.5	3	6	7
25957		2.02	<0.005		0.8	0.87	10	<10	190	2.1	<2	2.91	<0.5	14	27	24
25958		0.58	<0.005		0.2	0.82	10	<10	530	<0.5	<2	3.80	0.5	5	22	16
25959		5.68	<0.005		<0.2	1.15	<2	<10	240	0.8	<2	4.44	<0.5	27	54	40
25960		4.16	<0.005		<0.2	0.90	<2	<10	220	0.8	2	4.21	<0.5	27	46	36
25961		5.02	<0.005		<0.2	1.00	4	<10	200	1.2	<2	4.44	<0.5	30	44	38
25962		4.02	<0.005		<0.2	1.14	10	<10	230	2.3	<2	4.70	<0.5	33	45	38
25963		3.58	0.028		<0.2	1.29	74	<10	230	3.3	<2	4.75	<0.5	33	65	41
25964		4.60	0.020		<0.2	0.94	91	<10	190	4.2	<2	6.06	<0.5	26	63	34
25965		3.18	0.023		0.2	1.17	58	<10	210	5.6	<2	4.78	<0.5	21	44	24
25966		4.42	0.038		<0.2	0.87	56	<10	180	4.4	<2	2.71	<0.5	15	25	16
25967		3.46	0.020		<0.2	1.12	44	<10	170	5.3	2	2.61	<0.5	18	31	18
25968		3.88	0.014		<0.2	0.85	41	<10	140	3.7	<2	3.06	<0.5	17	35	16
25969		0.56	<0.005		0.2	0.99	10	<10	820	<0.5	<2	2.37	0.6	5	21	19
25970		4.00	<0.005		<0.2	0.88	19	<10	120	3.0	<2	3.07	<0.5	13	26	13
25971		0.10	1.110		13.3	1.67	440	<10	110	<0.5	<2	0.81	1.3	9	37	280
25972		4.78	0.005		0.2	0.95	22	<10	120	3.7	<2	1.82	<0.5	13	19	12
25973		3.96	<0.005		<0.2	0.64	5	<10	110	2.9	<2	1.42	<0.5	2	4	4
25974		3.66	<0.005		<0.2	0.80	7	<10	110	3.2	<2	0.65	<0.5	3	5	3
25975		3.52	<0.005		<0.2	0.61	8	<10	160	2.0	<2	0.23	<0.5	<1	2	2
25976		1.96	<0.005		<0.2	0.65	7	<10	160	2.0	<2	0.19	<0.5	1	3	1
25977		5.32	0.005		<0.2	0.84	9	<10	120	3.4	<2	1.56	<0.5	7	13	5
25978		3.92	<0.005		<0.2	0.82	9	<10	110	3.5	<2	2.27	<0.5	11	21	9
25979		1.90	<0.005		<0.2	0.81	15	<10	140	4.0	<2	1.30	<0.5	15	26	16
25980		4.60	0.024		<0.2	0.86	20	<10	150	2.6	<2	0.41	<0.5	6	10	8
25981		1.92	0.008		<0.2	0.96	26	<10	160	4.2	<2	2.91	<0.5	18	33	20
25982		2.80	<0.005		0.2	0.87	16	<10	120	3.5	<2	3.21	<0.5	11	20	10
25983		2.00	<0.005		0.2	0.82	4	<10	80	2.2	2	0.30	<0.5	4	10	2
25984		4.32	0.005		<0.2	0.89	14	<10	130	3.1	<2	2.37	<0.5	12	19	12

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107059

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Fe	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc
	Units	%	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm
	LOR	0.01	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1
25945		2.78	<10	<1	0.31	10	1.95	660	1	0.15	13	330	18	0.32	<2	4
25946		2.23	<10	<1	0.39	10	1.11	494	1	0.14	7	170	22	0.26	<2	2
25947		2.75	<10	<1	0.36	10	0.99	547	1	0.13	10	470	22	0.18	<2	2
25948		2.52	<10	<1	0.34	10	0.75	476	2	0.14	8	260	26	0.10	<2	2
25949		3.74	<10	<1	0.43	10	1.45	684	2	0.17	17	830	14	0.05	<2	5
25950		3.18	<10	<1	0.38	10	1.15	588	3	0.16	17	640	18	0.08	<2	4
25951		3.50	<10	<1	0.16	10	0.87	379	7	0.06	61	460	6	0.86	35	5
25952		2.63	<10	<1	0.36	10	1.08	536	2	0.16	10	370	20	0.05	<2	3
25953		2.36	<10	<1	0.38	10	1.07	523	3	0.16	9	240	20	0.03	<2	3
25954		5.40	<10	1	0.37	10	2.70	1040	1	0.27	39	940	6	0.11	<2	18
25955		5.27	<10	2	0.35	10	2.94	991	2	0.24	27	1080	4	0.27	2	9
25956		2.19	<10	<1	0.45	30	0.60	441	1	0.14	6	200	25	0.07	<2	1
25957		3.04	<10	<1	0.35	30	1.42	541	2	0.16	19	640	12	0.18	<2	6
25958		1.51	<10	<1	0.16	10	1.19	372	1	0.05	22	540	35	0.07	<2	3
25959		5.97	<10	<1	0.35	10	3.26	1100	1	0.27	36	1040	<2	0.03	<2	19
25960		5.45	<10	<1	0.28	10	3.30	1040	1	0.27	45	970	<2	0.02	<2	16
25961		5.60	<10	<1	0.35	10	3.63	890	1	0.28	54	1000	<2	0.08	<2	13
25962		6.13	<10	<1	0.36	10	3.62	1130	1	0.31	62	1010	2	0.18	<2	17
25963		6.04	<10	<1	0.43	10	2.92	1145	2	0.30	63	1100	2	0.21	<2	17
25964		6.19	<10	<1	0.35	10	3.02	1500	3	0.28	57	1010	3	0.24	<2	14
25965		5.05	<10	<1	0.47	30	2.19	1225	3	0.26	36	1180	11	0.32	<2	10
25966		4.33	<10	<1	0.37	20	0.97	840	2	0.23	20	1150	15	0.34	<2	7
25967		4.75	<10	<1	0.50	20	1.11	851	2	0.19	28	1030	15	0.27	<2	8
25968		4.79	<10	<1	0.36	30	1.12	1010	2	0.19	25	1200	14	0.30	<2	8
25969		1.70	<10	<1	0.15	10	0.88	400	2	0.06	21	680	35	0.07	<2	3
25970		3.77	<10	<1	0.40	30	0.82	889	3	0.16	21	910	18	0.10	<2	6
25971		3.17	<10	1	0.14	10	0.84	481	83	0.09	37	530	92	0.25	7	5
25972		3.73	<10	1	0.42	20	0.68	636	3	0.18	13	630	24	0.07	<2	5
25973		2.17	<10	<1	0.34	20	0.30	490	2	0.14	1	70	28	0.06	<2	2
25974		2.46	<10	1	0.42	20	0.28	439	3	0.14	<1	50	29	0.06	<2	2
25975		1.13	<10	<1	0.37	50	0.12	186	2	0.10	<1	10	56	0.05	<2	1
25976		1.15	<10	<1	0.41	40	0.12	181	4	0.10	<1	20	56	0.06	2	1
25977		2.93	<10	<1	0.41	20	0.52	531	5	0.15	7	360	32	0.05	<2	3
25978		3.86	<10	<1	0.36	10	0.73	700	3	0.17	12	820	23	0.03	<2	5
25979		4.12	<10	1	0.34	20	0.79	545	4	0.19	18	1060	21	0.04	<2	5
25980		1.88	<10	1	0.40	40	0.34	248	3	0.15	4	330	45	0.08	<2	2
25981		5.07	<10	<1	0.39	20	1.10	876	2	0.21	22	1650	19	0.14	<2	8
25982		3.60	<10	<1	0.37	20	1.04	856	3	0.19	13	1030	23	0.05	<2	5
25983		2.43	<10	<1	0.36	40	0.42	379	5	0.15	7	260	23	0.02	<2	3
25984		3.61	<10	<1	0.38	10	1.05	669	3	0.18	13	860	21	0.21	<2	5

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 15-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107059

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Sr	Th	Ti	Tl	U	V	W	Zn
	Units	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm
	LOR	1	20	0 01	10	10	1	10	2
25945		148	<20	<0.01	<10	<10	23	<10	78
25946		87	<20	<0.01	<10	<10	8	<10	81
25947		76	<20	<0.01	<10	<10	13	<10	90
25948		61	<20	<0.01	<10	<10	11	<10	90
25949		101	<20	<0.01	<10	<10	34	<10	83
25950		95	<20	<0.01	<10	<10	27	<10	79
25951		38	<20	0.10	<10	<10	50	40	48
25952		95	<20	<0.01	<10	<10	15	<10	82
25953		98	<20	<0.01	<10	<10	11	<10	77
25954		214	<20	<0.01	<10	<10	49	<10	69
25955		224	<20	<0.01	<10	<10	39	<10	55
25956		51	<20	<0.01	<10	<10	7	<10	90
25957		115	<20	<0.01	<10	<10	35	<10	121
25958		93	<20	0.04	<10	<10	27	<10	81
25959		200	<20	<0.01	<10	<10	80	<10	60
25960		189	<20	<0.01	<10	<10	73	<10	48
25961		176	<20	<0.01	<10	<10	80	<10	49
25962		214	<20	<0.01	<10	<10	73	<10	60
25963		222	<20	<0.01	<10	<10	82	<10	75
25964		259	<20	<0.01	<10	<10	74	<10	74
25965		267	<20	<0.01	<10	<10	55	<10	85
25966		126	<20	<0.01	<10	<10	42	<10	88
25967		132	<20	<0.01	<10	<10	45	<10	106
25968		148	<20	<0.01	<10	<10	48	<10	90
25969		108	<20	0.04	<10	<10	36	<10	86
25970		125	<20	<0.01	<10	<10	40	<10	86
25971		41	<20	0.13	<10	<10	60	10	189
25972		89	<20	<0.01	<10	<10	33	<10	97
25973		67	<20	<0.01	<10	<10	4	<10	97
25974		42	<20	<0.01	<10	<10	5	<10	96
25975		28	60	<0.01	<10	10	<1	<10	57
25976		25	60	<0.01	<10	10	1	<10	54
25977		90	20	<0.01	<10	<10	18	<10	87
25978		112	<20	<0.01	<10	<10	31	<10	92
25979		76	<20	<0.01	<10	<10	42	<10	107
25980		49	30	<0.01	<10	<10	10	<10	104
25981		116	<20	<0.01	<10	<10	60	<10	104
25982		146	<20	<0.01	<10	<10	33	<10	94
25983		30	<20	<0.01	<10	<10	18	<10	102
25984		121	<20	<0.01	<10	<10	35	<10	95

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 15-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107059

Sample Description	Method	WEI-21	Au-AA23	Au-GRA21	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt.	Au	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu
	Units	kg	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm
	LOR	0.02	0.005	0.05	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1
25985		3.60	<0.005		<0.2	0.75	9	<10	120	2.8	<2	2.30	<0.5	9	18	11
25986		3.74	<0.005		0.3	0.86	10	<10	130	3.2	<2	3.17	<0.5	12	20	12
25987		4.08	<0.005		<0.2	0.89	14	<10	120	3.1	<2	3.15	<0.5	13	30	13
25988		2.86	0.027		<0.2	0.40	22	<10	100	2.0	2	0.49	<0.5	3	6	7
25989		4.66	<0.005		<0.2	0.74	18	<10	160	4.6	<2	4.02	<0.5	31	77	42
25990		3.34	<0.005		<0.2	0.49	12	<10	100	2.8	<2	3.67	<0.5	11	22	11
25991		0.10	>10.0	9.06	0.5	1.60	4250	<10	60	0.5	<2	0.87	<0.5	14	73	70
25992		4.58	0.019		<0.2	0.40	23	<10	100	2.2	<2	0.55	<0.5	1	1	1
25993		3.86	0.007		<0.2	0.44	7	<10	80	2.5	<2	0.23	<0.5	<1	2	<1
25994		3.38	0.024		<0.2	0.44	23	<10	80	2.8	<2	0.24	<0.5	<1	2	1
25995		3.80	0.039		<0.2	0.42	44	<10	70	2.5	<2	0.21	<0.5	<1	2	1
25996		4.22	0.014		<0.2	0.42	24	<10	70	2.4	<2	0.44	<0.5	<1	1	1
25997		4.38	0.007		<0.2	0.40	10	<10	80	2.0	<2	0.24	<0.5	<1	2	1
25998		3.64	0.014		<0.2	0.36	17	<10	110	2.1	<2	0.61	<0.5	4	8	6
25999		0.70	<0.005		0.2	0.91	5	<10	550	<0.5	<2	4.61	<0.5	4	15	14
26000		3.86	<0.005		<0.2	0.39	4	<10	110	2.1	<2	2.43	<0.5	4	5	6
26001		4.66	<0.005		<0.2	0.53	12	<10	140	2.6	<2	2.86	<0.5	11	23	13
26002		3.46	<0.005		<0.2	0.49	5	<10	150	2.8	<2	2.21	<0.5	8	14	8
26003		3.70	<0.005		0.3	0.68	4	<10	160	3.2	<2	3.32	<0.5	11	29	19
26004		4.42	<0.005		<0.2	0.75	3	<10	450	3.5	<2	5.77	<0.5	17	70	34
26005		4.58	<0.005		<0.2	0.75	3	<10	780	2.9	<2	4.65	<0.5	20	71	32
26006		4.14	<0.005		<0.2	0.69	7	<10	510	2.9	<2	5.96	<0.5	22	62	25
26007		3.90	<0.005		<0.2	0.83	3	<10	190	2.2	<2	4.41	<0.5	26	102	31
26008		4.08	<0.005		0.3	0.69	3	<10	700	2.5	<2	5.48	<0.5	24	112	33
26009		4.14	<0.005		<0.2	0.81	2	<10	310	2.2	<2	4.85	<0.5	19	107	21
26010		0.10	1.095		8.7	1.75	438	<10	110	<0.5	<2	0.91	1.4	10	39	273
26011		4.52	<0.005		0.2	0.69	2	<10	220	1.9	<2	4.69	<0.5	20	86	28
26012		3.70	<0.005		<0.2	0.86	3	<10	220	2.5	<2	5.82	<0.5	19	81	17
26013		4.82	<0.005		<0.2	0.74	<2	<10	210	2.2	<2	4.70	<0.5	25	99	29
26014		4.44	<0.005		<0.2	0.76	<2	<10	210	2.0	<2	5.40	<0.5	24	109	31
26015		4.20	<0.005		0.3	0.74	<2	<10	180	2.0	<2	5.40	<0.5	24	100	40
26016		4.34	<0.005		0.2	0.79	<2	<10	390	2.2	<2	3.42	<0.5	25	20	26
26017		4.24	<0.005		<0.2	0.82	<2	<10	280	2.1	<2	5.14	<0.5	25	13	28
26018		4.18	<0.005		0.2	0.72	<2	<10	230	2.1	<2	4.97	<0.5	17	33	15
26019		5.00	<0.005		0.2	0.57	3	<10	180	1.8	<2	4.81	<0.5	14	32	8
26020		0.72	<0.005		0.4	0.83	9	<10	810	<0.5	<2	1.71	0.5	5	17	15
26021		4.24	<0.005		0.2	0.68	3	<10	220	1.5	<2	4.31	<0.5	17	52	31
26022		3.56	<0.005		0.2	0.76	2	<10	240	1.8	<2	5.36	<0.5	20	69	34
26023		4.80	<0.005		<0.2	0.75	3	<10	230	1.9	<2	4.25	<0.5	23	80	40
26024		4.18	<0.005		0.2	0.77	<2	<10	240	1.9	<2	3.70	<0.5	25	86	42

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 15-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107059

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Fe	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc
	Units	%	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm
	LOR	0.01	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1
25985		3.45	<10	<1	0.34	20	1.12	600	4	0.16	11	590	26	0.04	<2	4
25986		3.66	10	<1	0.36	10	1.14	752	3	0.18	13	730	23	0.09	<2	6
25987		4.37	<10	1	0.38	20	0.99	748	2	0.18	20	1140	21	0.06	<2	6
25988		1.87	<10	<1	0.23	90	0.31	200	4	0.12	2	100	38	0.11	<2	2
25989		6.11	<10	1	0.29	10	1.87	1065	1	0.26	46	1540	4	0.10	<2	13
25990		3.61	<10	<1	0.22	20	1.25	691	3	0.15	13	590	20	0.04	<2	5
25991		3.79	<10	<1	0.17	10	0.92	403	7	0.07	62	510	6	0.96	36	5
25992		1.64	<10	<1	0.24	150	0.18	116	3	0.11	<1	30	35	0.13	<2	2
25993		1.51	<10	<1	0.33	150	0.09	99	4	0.09	<1	30	38	0.05	<2	1
25994		1.32	<10	<1	0.37	140	0.07	82	2	0.09	<1	30	42	0.31	2	1
25995		1.59	<10	<1	0.38	150	0.06	89	3	0.08	<1	20	42	0.52	<2	1
25996		1.39	<10	1	0.37	130	0.06	89	2	0.07	<1	20	39	0.40	3	1
25997		1.25	<10	<1	0.32	90	0.08	85	2	0.08	<1	20	38	0.09	<2	1
25998		2.41	<10	<1	0.22	70	0.30	289	3	0.11	5	160	30	0.07	<2	2
25999		1.48	<10	<1	0.20	10	1.22	348	2	0.05	13	570	23	0.09	<2	3
26000		2.43	<10	<1	0.20	10	0.79	528	3	0.13	3	120	29	0.03	<2	2
26001		3.18	<10	<1	0.24	20	1.11	668	3	0.15	17	660	22	0.04	<2	5
26002		3.28	<10	<1	0.23	20	0.99	954	5	0.15	16	600	28	0.02	<2	3
26003		3.78	<10	1	0.34	20	1.43	1285	3	0.17	33	1030	52	0.11	<2	5
26004		3.72	<10	3	0.37	10	2.21	890	1	0.18	67	1920	3	0.05	<2	9
26005		4.28	<10	3	0.40	10	1.98	969	1	0.18	86	1930	5	0.11	<2	10
26006		4.26	<10	3	0.35	10	2.56	1035	1	0.18	88	1670	5	0.14	<2	9
26007		5.48	<10	4	0.34	10	2.47	1015	1	0.20	126	2060	5	0.20	<2	12
26008		4.68	10	3	0.31	10	2.03	1090	1	0.18	107	2370	5	0.06	<2	11
26009		4.17	<10	15	0.38	10	1.76	817	<1	0.18	77	2080	6	0.02	4	9
26010		3.30	<10	<1	0.14	<10	0.85	495	86	0.09	36	560	94	0.25	9	5
26011		3.91	<10	1	0.34	10	1.90	822	1	0.17	81	1870	2	<0.01	<2	10
26012		4.25	<10	2	0.39	10	2.53	886	1	0.19	72	1900	3	0.01	<2	8
26013		4.91	<10	2	0.32	10	2.66	1005	1	0.19	119	1950	4	0.08	<2	12
26014		4.66	<10	2	0.30	10	2.26	990	1	0.21	115	2130	3	0.16	2	12
26015		4.78	<10	2	0.31	10	2.05	1010	1	0.19	109	2150	3	0.22	<2	12
26016		6.39	<10	<1	0.33	20	2.00	1150	2	0.23	42	2320	3	0.06	3	9
26017		6.48	<10	1	0.30	20	2.23	1230	1	0.21	32	2820	3	0.20	3	11
26018		4.72	<10	<1	0.26	20	2.12	947	2	0.20	21	1590	13	0.04	2	8
26019		4.14	<10	<1	0.21	20	1.85	890	3	0.16	16	1080	14	<0.01	<2	7
26020		1.68	<10	<1	0.14	10	0.79	385	1	0.03	15	570	45	0.07	3	2
26021		3.91	<10	1	0.29	10	1.42	746	1	0.19	24	1760	4	0.10	3	9
26022		4.58	<10	2	0.29	10	1.98	1010	1	0.22	30	1830	6	0.30	<2	12
26023		4.74	<10	3	0.31	10	1.67	1010	1	0.20	42	1930	4	0.14	<2	12
26024		4.94	<10	2	0.32	10	1.55	1020	1	0.22	49	2080	8	0.22	3	13

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 15-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107059

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Sr	Th	Ti	Tl	U	V	W	Zn
	Units	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm
	LOR	1	20	0.01	10	10	1	10	2
25985		141	<20	<0.01	<10	<10	30	<10	89
25986		140	<20	<0.01	<10	<10	36	<10	92
25987		141	<20	<0.01	<10	<10	43	<10	97
25988		35	40	<0.01	<10	<10	6	<10	84
25989		180	<20	<0.01	<10	<10	92	<10	88
25990		164	<20	<0.01	<10	<10	33	<10	88
25991		42	<20	0.11	<10	<10	54	40	52
25992		37	50	<0.01	<10	<10	1	<10	76
25993		26	50	<0.01	<10	<10	1	<10	76
25994		25	50	<0.01	<10	<10	<1	<10	74
25995		23	50	<0.01	<10	<10	<1	<10	73
25996		31	50	<0.01	<10	<10	<1	<10	59
25997		23	40	<0.01	<10	<10	<1	<10	57
25998		39	30	<0.01	<10	<10	11	<10	81
25999		144	<20	0.03	<10	<10	30	<10	61
26000		121	<20	<0.01	<10	<10	11	<10	96
26001		150	<20	<0.01	<10	<10	27	<10	83
26002		113	<20	<0.01	<10	<10	24	<10	94
26003		141	<20	<0.01	<10	<10	38	<10	106
26004		267	<20	<0.01	<10	<10	60	<10	54
26005		218	<20	<0.01	<10	<10	63	<10	62
26006		250	<20	<0.01	<10	<10	61	<10	66
26007		207	<20	<0.01	<10	<10	86	<10	64
26008		229	<20	<0.01	<10	<10	91	<10	69
26009		198	<20	0.01	<10	<10	89	<10	44
26010		43	<20	0.14	<10	<10	64	<10	189
26011		206	<20	0.01	<10	<10	86	<10	43
26012		260	<20	0.01	<10	<10	82	<10	46
26013		237	<20	<0.01	<10	<10	89	<10	65
26014		230	<20	<0.01	<10	<10	88	<10	61
26015		257	<20	<0.01	<10	<10	91	<10	63
26016		163	<20	<0.01	<10	<10	71	<10	88
26017		273	<20	<0.01	<10	<10	71	<10	91
26018		277	<20	<0.01	<10	<10	55	<10	89
26019		276	<20	<0.01	<10	<10	49	<10	77
26020		74	<20	0.02	<10	<10	23	<10	80
26021		197	<20	<0.01	<10	<10	73	<10	55
26022		257	<20	<0.01	<10	<10	89	<10	59
26023		219	<20	<0.01	<10	<10	83	<10	60
26024		185	<20	<0.01	<10	<10	99	<10	66

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 15-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107059

Sample Description	Method	WEI-21	Au-AA23	Au-GRA21	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt.	Au	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu
	Units	kg	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm
	LOR	0.02	0.005	0.05	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1
26025		4.96	<0.005		0.2	0.69	2	<10	210	1.9	<2	4.87	<0.5	22	74	35
26026		4.24	<0.005		0.2	0.75	<2	<10	230	2.0	<2	5.46	<0.5	22	86	29
26027		4.32	<0.005		<0.2	0.84	2	<10	230	2.0	<2	4.34	<0.5	23	86	31
26028		5.68	<0.005		0.2	0.66	<2	<10	160	1.8	<2	5.06	<0.5	21	71	36
26029		0.10	9.56		0.8	1.45	3840	<10	60	0.5	<2	0.83	<0.5	14	66	61
26030		4.32	0.005		0.3	0.69	20	<10	160	1.7	<2	3.16	<0.5	21	54	25
26031		2.96	<0.005		0.2	0.67	14	<10	170	1.9	<2	4.22	<0.5	23	65	27
26032		0.50	<0.005		0.2	0.89	6	<10	790	<0.5	<2	3.27	0.7	6	34	14
26033		4.30	<0.005		0.2	0.70	<2	<10	180	2.0	<2	5.22	<0.5	20	72	28
26034		4.24	0.005		<0.2	0.76	<2	<10	170	1.9	<2	3.48	<0.5	25	106	32
26035		2.40	0.005		0.2	0.73	<2	<10	200	2.7	<2	4.35	<0.5	17	76	49
26036		3.82	0.007		<0.2	0.58	<2	<10	160	2.4	<2	2.55	<0.5	11	19	10
26037		3.84	0.008		<0.2	0.49	<2	<10	130	2.2	<2	2.73	<0.5	9	17	19
26038		3.60	0.005		0.3	0.50	<2	<10	130	2.3	<2	1.96	<0.5	12	24	9
26039		3.98	<0.005		0.3	0.52	<2	<10	120	2.6	<2	3.44	<0.5	11	19	8
26040		5.18	<0.005		0.3	0.55	<2	<10	150	3.3	<2	4.15	<0.5	18	32	13
26041		3.30	<0.005		<0.2	0.88	<2	<10	200	5.2	<2	4.46	<0.5	31	33	17
26042		3.00	<0.005		<0.2	0.78	<2	<10	210	4.4	<2	5.01	<0.5	29	31	17
26043		4.22	<0.005		<0.2	0.94	<2	<10	200	4.9	<2	4.76	<0.5	32	45	19
26044		3.34	<0.005		0.2	0.46	2	<10	110	2.7	<2	2.10	<0.5	8	13	13
26045		3.58	<0.005		0.2	0.52	2	<10	460	1.0	<2	2.91	<0.5	7	9	<1
26046		3.14	0.005		<0.2	0.54	2	<10	460	1.0	<2	2.85	<0.5	5	7	<1
26047		2.12	<0.005		<0.2	0.54	<2	<10	510	1.3	<2	2.68	<0.5	7	5	1
26048		2.64	<0.005		0.2	0.56	<2	<10	310	1.3	<2	2.84	<0.5	9	6	5
26049		3.94	<0.005		0.3	0.53	<2	<10	430	1.2	<2	2.13	<0.5	5	5	<1
26050		3.18	<0.005		0.2	0.50	<2	<10	390	1.4	<2	1.93	<0.5	6	4	4
26051		2.98	<0.005		<0.2	0.61	<2	<10	350	1.2	<2	2.82	<0.5	5	2	<1
26052		3.58	<0.005		<0.2	0.63	<2	<10	570	1.1	<2	2.77	<0.5	6	2	<1
26053		3.76	<0.005		<0.2	0.58	<2	<10	480	1.0	<2	2.84	<0.5	6	2	<1
26054		4.36	<0.005		<0.2	0.66	<2	<10	610	1.3	<2	3.53	<0.5	7	2	<1

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 15-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107059

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Fe	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc
	Units	%	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm
	LOR	0.01	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1
26025		4.27	<10	2	0.29	10	1.79	940	1	0.20	43	1660	6	0.21	<2	12
26026		4.67	<10	2	0.29	10	1.94	1120	1	0.23	47	1870	9	0.40	4	13
26027		4.84	<10	2	0.32	10	1.66	1115	1	0.23	48	2100	6	0.48	2	14
26028		4.80	<10	2	0.26	10	1.88	1070	1	0.18	45	1990	5	0.49	<2	11
26029		3.48	<10	<1	0.15	10	0.84	373	6	0.06	59	460	5	0.84	34	5
26030		4.92	<10	2	0.27	10	1.39	828	1	0.19	40	1950	5	0.51	2	9
26031		5.16	<10	2	0.26	10	1.77	859	3	0.20	47	1750	5	0.84	2	11
26032		1.70	<10	<1	0.13	10	1.09	445	1	0.03	28	780	21	0.06	2	3
26033		4.33	<10	2	0.26	10	2.02	810	1	0.20	45	1850	5	0.25	<2	10
26034		4.84	<10	3	0.30	10	1.62	757	1	0.21	66	1920	6	0.51	2	11
26035		4.19	<10	<1	0.29	10	1.70	823	3	0.24	32	1660	9	0.14	<2	13
26036		3.62	<10	1	0.25	10	1.00	711	3	0.17	13	820	22	0.02	<2	6
26037		3.23	<10	<1	0.22	30	1.01	651	4	0.15	9	700	23	<0.01	3	4
26038		3.88	<10	<1	0.22	20	0.88	596	3	0.14	14	880	20	0.01	<2	5
26039		3.66	<10	<1	0.23	20	1.10	755	5	0.15	12	810	13	0.02	<2	5
26040		4.61	<10	<1	0.22	10	1.89	917	1	0.18	20	1210	10	0.01	3	8
26041		5.92	<10	<1	0.37	10	2.18	946	1	0.22	29	1540	4	0.07	<2	15
26042		5.89	<10	<1	0.33	10	2.86	870	1	0.23	29	1520	2	0.05	<2	15
26043		7.39	<10	<1	0.37	10	2.41	1180	1	0.24	32	1720	2	0.07	<2	16
26044		2.91	<10	<1	0.24	10	0.64	595	3	0.13	12	410	24	0.02	<2	3
26045		2.10	<10	<1	0.25	20	0.44	496	<1	0.07	6	720	21	0.01	2	4
26046		1.58	<10	<1	0.26	20	0.43	387	1	0.08	4	580	19	0.01	<2	3
26047		1.64	<10	<1	0.29	20	0.47	485	1	0.09	7	500	16	0.01	<2	3
26048		2.08	<10	<1	0.30	20	0.46	588	4	0.08	10	460	20	0.01	<2	3
26049		1.99	<10	<1	0.28	20	0.35	435	<1	0.09	2	580	14	0.01	2	3
26050		1.96	<10	<1	0.27	10	0.39	572	2	0.08	5	690	13	0.01	<2	3
26051		3.55	<10	<1	0.28	20	0.64	773	1	0.10	<1	1650	20	0.01	2	5
26052		3.48	<10	<1	0.28	20	0.64	790	1	0.10	<1	1610	18	0.01	2	5
26053		3.49	<10	<1	0.26	20	0.69	776	1	0.10	<1	1510	15	0.01	<2	6
26054		3.36	<10	<1	0.31	20	0.82	913	<1	0.10	<1	1560	15	0.02	2	7

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 15-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107059

Sample Description	Method / Analyte / Units / LOR	ME-ICP41 Sr ppm 1	ME-ICP41 Th ppm 20	ME-ICP41 Ti % 0.01	ME-ICP41 Tl ppm 10	ME-ICP41 U ppm 10	ME-ICP41 V ppm 1	ME-ICP41 W ppm 10	ME-ICP41 Zn ppm 2
26025		238	<20	<0.01	<10	<10	79	<10	60
26026		267	<20	<0.01	<10	<10	91	<10	71
26027		217	<20	<0.01	<10	<10	97	<10	67
26028		248	<20	<0.01	<10	<10	88	<10	55
26029		39	<20	0.10	<10	<10	49	40	45
26030		156	<20	<0.01	<10	<10	88	<10	73
26031		193	<20	<0.01	<10	<10	91	<10	82
26032		114	<20	0.04	<10	<10	36	<10	58
26033		283	<20	<0.01	<10	<10	84	<10	66
26034		194	<20	<0.01	<10	<10	91	<10	70
26035		211	<20	<0.01	<10	<10	82	<10	73
26036		132	<20	<0.01	<10	<10	32	<10	84
26037		140	<20	<0.01	<10	<10	28	<10	87
26038		105	<20	<0.01	<10	<10	32	<10	94
26039		176	<20	<0.01	<10	<10	37	<10	77
26040		212	<20	<0.01	<10	<10	58	<10	87
26041		246	<20	<0.01	<10	<10	79	<10	85
26042		303	<20	<0.01	<10	<10	80	<10	79
26043		242	<20	<0.01	<10	<10	99	<10	88
26044		106	<20	<0.01	<10	<10	19	<10	98
26045		492	<20	0.02	<10	<10	42	<10	51
26046		523	<20	0.01	<10	<10	33	<10	44
26047		449	<20	0.01	<10	<10	20	<10	52
26048		459	<20	0.01	<10	<10	23	<10	58
26049		325	<20	0.01	<10	<10	27	<10	33
26050		243	<20	<0.01	<10	<10	19	<10	57
26051		416	<20	0.04	<10	<10	64	<10	49
26052		413	<20	0.04	<10	<10	66	<10	52
26053		404	<20	0.05	<10	<10	65	<10	57
26054		521	<20	0.04	<10	<10	59	<10	61

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 19-OCT-2009
This copy reported on 3-DEC-2009
Account: EMERES

CERTIFICATE VA09107058

Project: Canyon Gold

P.O. No.:

This report is for 120 Rock samples submitted to our lab in Vancouver, BC, Canada on 29-SEP-2009.

The following have access to data associated with this certificate:

SARA PUBLICOVER	SIMON RIDGWAY	

SAMPLE PREPARATION

ALS CODE	DESCRIPTION
WEI-21	Received Sample Weight
LOG-22	Sample login - Rcd w/o BarCode
CRU-QC	Crushing QC Test
PUL-QC	Pulverizing QC Test
CRU-31	Fine crushing - 70% <2mm
SPL-21	Split sample - riffle splitter
PUL-31	Pulverize split to 85% <75 um
LOG-24	Pulp Login - Rcd w/o Barcode

ANALYTICAL PROCEDURES

ALS CODE	DESCRIPTION	INSTRUMENT
ME-ICP41	35 Element Aqua Regia ICP-AES	ICP-AES
Au-AA23	Au 30g FA-AA finish	AAS
Au-GRA21	Au 30g FA-GRAV finish	WST-SIM

To: **EMERICK RESOURCES LTD.**
ATTN: SARA PUBLICOVER
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

This is the Final Report and supersedes any preliminary report with this certificate number. Results apply to samples as submitted. All pages of this report have been checked and approved for release.

Signature:

Colin Ramshaw, Vancouver Laboratory Manager

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 19-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107058

Sample Description	Method	WEI-21	Au-AA23	Au-GRA21	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt	Au	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu
	Units	kg	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm
	LOR	0.02	0.005	0.05	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1
26055		0.10	9.78		0.5	1.52	4070	<10	60	0.5	2	0.82	<0.5	14	69	67
26056		3.90	<0.005		<0.2	0.53	4	<10	400	1.3	<2	2.51	<0.5	5	3	1
26057		3.00	<0.005		<0.2	0.51	<2	<10	350	1.0	<2	3.57	<0.5	5	2	<1
26058		4.22	<0.005		<0.2	0.48	2	<10	470	1.1	<2	3.53	<0.5	5	2	<1
26059		0.50	<0.005		0.2	0.85	14	<10	510	<0.5	<2	2.44	0.6	5	24	17
26060		4.04	<0.005		0.3	0.49	3	<10	1260	1.1	<2	4.06	<0.5	7	2	<1
26061		3.56	<0.005		0.2	0.59	2	<10	680	1.0	<2	2.78	<0.5	6	3	<1
26062		2.88	<0.005		0.2	0.64	<2	<10	380	1.5	<2	2.53	<0.5	5	2	<1
26063		2.76	<0.005		0.2	0.65	<2	<10	520	1.4	<2	2.39	<0.5	6	3	<1
26064		2.38	<0.005		0.2	0.60	<2	<10	510	1.0	<2	2.56	<0.5	6	3	<1
26065		2.28	<0.005		0.2	0.55	<2	<10	530	0.9	<2	3.15	<0.5	5	2	<1
26066		3.48	<0.005		0.3	0.52	2	<10	160	2.2	<2	2.67	<0.5	8	13	3
26067		4.24	<0.005		<0.2	0.45	6	<10	150	1.8	<2	3.18	<0.5	11	19	12
26068		3.46	0.005		0.2	0.47	15	<10	180	2.4	<2	2.28	<0.5	11	20	9
26069		0.36	<0.005		0.3	0.95	9	<10	570	<0.5	<2	1.87	0.5	5	16	15
26070		1.80	0.031		0.3	0.46	53	<10	170	2.2	<2	1.95	<0.5	10	19	11
26071		1.78	0.041		0.4	0.82	74	<10	360	5.2	<2	4.07	<0.5	12	16	12
26072		1.60	0.053		0.3	0.50	94	<10	160	3.7	<2	2.70	<0.5	8	6	6
26073		3.70	0.005		0.3	0.51	19	<10	360	4.6	<2	2.58	<0.5	13	14	14
26074		5.22	<0.005		0.2	0.48	25	<10	210	2.9	<2	3.44	<0.5	11	19	11
26075		3.30	0.027		0.3	0.35	21	<10	80	1.8	<2	0.31	<0.5	1	1	4
26076		0.10	1.155		10.2	1.70	477	<10	110	<0.5	<2	0.82	1.3	9	38	270
26077		2.28	0.012		0.2	0.36	8	<10	70	1.6	<2	0.25	<0.5	<1	2	3
26078		4.46	0.039		0.2	0.73	74	<10	230	3.8	<2	4.22	<0.5	22	40	16
26079		3.84	0.088		0.5	0.70	114	<10	180	4.0	<2	5.85	<0.5	26	51	3
26080		3.72	<0.005		<0.2	0.55	27	<10	150	3.1	<2	3.08	<0.5	13	27	18
26081		2.24	<0.005		0.2	0.48	31	<10	150	3.2	<2	2.32	<0.5	14	19	17
26082		3.96	0.041		0.3	0.33	75	<10	90	2.0	<2	0.61	<0.5	1	1	2
26083		4.14	0.016		0.2	0.33	41	<10	80	2.4	<2	0.77	<0.5	1	2	3
26084		3.70	<0.005		0.2	0.32	7	<10	70	2.1	<2	0.73	<0.5	1	2	2
26085		4.36	<0.005		<0.2	0.58	32	<10	180	4.5	<2	4.04	<0.5	23	28	16
26086		4.02	<0.005		0.2	0.37	12	<10	100	3.1	<2	1.74	<0.5	4	6	4
26087		2.76	0.012		<0.2	0.35	12	<10	60	2.6	<2	0.42	<0.5	<1	1	6
26088		3.48	0.006		0.3	0.39	9	<10	60	2.5	<2	0.35	<0.5	1	2	4
26089		3.60	0.012		0.2	0.40	12	<10	60	2.7	<2	0.34	<0.5	1	2	4
26090		3.64	0.005		0.2	0.37	10	<10	60	2.6	2	0.53	<0.5	<1	1	4
26091		0.10	0.996		10.9	1.73	464	<10	110	<0.5	<2	0.85	1.5	9	39	271
26092		2.10	<0.005		<0.2	0.50	25	<10	150	5.0	<2	3.01	<0.5	21	36	17
26093		0.82	<0.005		<0.2	0.25	4	<10	40	0.8	<2	1.78	<0.5	1	3	4
26094		1.42	<0.005		<0.2	0.41	6	<10	110	2.5	<2	2.05	<0.5	7	12	11

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd.
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 19-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107058

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Fe	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc
	Units	%	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm
	LOR	0.01	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1
26055		3.55	<10	<1	0.16	10	0.89	389	6	0.06	62	490	6	0.91	33	5
26056		3.23	<10	<1	0.24	20	0.59	785	<1	0.09	<1	1630	12	0.02	<2	6
26057		3.19	<10	<1	0.24	20	0.81	1050	<1	0.09	<1	1640	11	0.02	<2	6
26058		3.32	<10	<1	0.22	20	0.79	915	<1	0.09	<1	1650	10	0.02	2	6
26059		1.56	<10	<1	0.12	10	0.74	363	1	0.04	18	420	19	0.08	<2	3
26060		2.73	<10	<1	0.23	20	1.19	1040	<1	0.09	<1	1590	9	0.05	<2	6
26061		3.46	<10	<1	0.26	20	0.72	907	<1	0.11	<1	1730	11	0.03	2	7
26062		3.34	<10	<1	0.30	20	0.68	891	<1	0.10	<1	1640	13	0.02	2	6
26063		3.41	<10	<1	0.30	20	0.58	863	<1	0.11	<1	1510	14	0.02	<2	6
26064		3.19	<10	<1	0.25	20	0.54	697	1	0.12	<1	1430	13	0.03	<2	7
26065		3.05	<10	<1	0.23	20	0.71	805	<1	0.12	<1	1350	13	0.03	2	7
26066		3.21	<10	<1	0.25	20	0.84	901	2	0.10	7	1190	16	0.08	<2	4
26067		3.55	<10	<1	0.18	20	0.69	751	2	0.12	12	950	16	0.03	3	4
26068		3.36	<10	<1	0.19	20	0.80	679	3	0.14	12	870	18	0.09	<2	4
26069		1.74	<10	<1	0.13	10	0.62	374	1	0.04	13	2240	28	0.06	2	3
26070		3.34	<10	<1	0.18	20	0.63	635	2	0.14	11	700	18	0.33	3	3
26071		5.27	<10	<1	0.42	50	1.37	1290	4	0.31	8	1460	32	0.74	3	6
26072		3.39	<10	<1	0.28	30	0.88	855	2	0.13	6	780	15	0.53	3	3
26073		3.82	<10	1	0.26	30	0.86	831	4	0.15	15	1370	9	0.14	4	5
26074		3.22	<10	<1	0.21	20	1.21	643	2	0.15	14	780	11	0.11	<2	4
26075		0.89	<10	1	0.23	50	0.12	177	4	0.08	<1	50	45	0.16	3	<1
26076		3.23	<10	<1	0.13	<10	0.83	489	84	0.08	35	560	89	0.28	9	5
26077		0.65	<10	1	0.24	50	0.11	165	5	0.07	<1	70	44	0.07	<2	<1
26078		6.15	<10	<1	0.27	20	2.06	1210	1	0.19	26	2390	<2	0.40	4	9
26079		6.66	<10	<1	0.29	30	2.27	1325	<1	0.15	29	2970	2	1.10	2	9
26080		3.73	<10	<1	0.24	20	1.26	772	2	0.13	16	1470	9	0.06	2	5
26081		3.66	<10	<1	0.21	10	1.04	810	2	0.15	15	950	16	0.10	<2	5
26082		0.91	<10	<1	0.20	50	0.15	185	7	0.09	<1	30	45	0.60	2	<1
26083		1.10	<10	<1	0.21	40	0.09	246	7	0.08	<1	30	45	0.44	3	1
26084		1.00	<10	<1	0.22	50	0.10	268	7	0.07	<1	60	36	0.06	<2	1
26085		5.65	<10	<1	0.24	10	1.38	1080	2	0.16	24	1580	9	0.11	<2	8
26086		2.02	<10	<1	0.21	10	0.46	473	2	0.10	2	290	32	0.07	<2	2
26087		0.64	<10	<1	0.25	60	0.06	156	6	0.05	2	20	54	0.11	<2	<1
26088		0.50	<10	<1	0.28	60	0.03	140	5	0.05	<1	10	49	0.12	<2	<1
26089		0.55	<10	<1	0.28	60	0.04	138	5	0.05	<1	10	53	0.16	<2	<1
26090		0.58	<10	<1	0.26	60	0.06	154	5	0.05	<1	10	51	0.12	<2	<1
26091		3.28	10	<1	0.14	<10	0.86	490	86	0.09	37	570	94	0.34	6	5
26092		5.13	<10	<1	0.24	10	0.87	1065	1	0.14	28	1470	21	0.10	2	6
26093		1.13	<10	1	0.16	10	0.21	283	1	0.05	3	490	8	0.02	<2	1
26094		2.90	<10	<1	0.20	10	0.57	607	3	0.11	10	560	28	0.02	<2	3

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 19-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107058

Sample Description	Method / Analyte / Units / LOR	ME-ICP41 Sr ppm 1	ME-ICP41 Th ppm 20	ME-ICP41 Ti % 0.01	ME-ICP41 Tl ppm 10	ME-ICP41 U ppm 10	ME-ICP41 V ppm 1	ME-ICP41 W ppm 10	ME-ICP41 Zn ppm 2
26055		40	<20	0.11	<10	<10	51	40	52
26056		424	<20	0.04	<10	<10	55	<10	51
26057		621	<20	0.04	<10	<10	63	<10	55
26058		575	<20	0.04	<10	<10	61	<10	48
26059		109	<20	0.04	<10	<10	25	<10	53
26060		522	<20	0.02	<10	<10	47	<10	80
26061		391	<20	0.04	<10	<10	68	<10	60
26062		322	<20	0.03	<10	<10	61	<10	53
26063		336	<20	0.03	<10	<10	63	<10	48
26064		428	<20	0.02	<10	<10	69	<10	53
26065		487	<20	0.02	<10	<10	69	<10	53
26066		339	<20	<0.01	<10	<10	33	<10	76
26067		250	<20	<0.01	<10	<10	31	<10	87
26068		260	<20	<0.01	<10	<10	29	<10	88
26069		93	<20	0.05	<10	<10	36	<10	73
26070		206	<20	<0.01	<10	<10	24	<10	89
26071		581	20	<0.01	<10	<10	34	<10	126
26072		343	<20	<0.01	<10	<10	17	<10	78
26073		253	<20	<0.01	<10	<10	24	<10	89
26074		413	<20	<0.01	<10	<10	30	<10	72
26075		44	30	<0.01	<10	<10	1	<10	74
26076		42	<20	0.13	<10	<10	61	10	192
26077		40	30	<0.01	<10	<10	1	<10	74
26078		294	<20	<0.01	<10	<10	55	<10	90
26079		364	<20	<0.01	<10	<10	33	<10	104
26080		222	<20	<0.01	<10	<10	39	<10	91
26081		179	<20	<0.01	<10	<10	35	<10	90
26082		60	20	<0.01	<10	<10	<1	<10	82
26083		64	20	<0.01	<10	<10	1	<10	87
26084		48	20	<0.01	<10	<10	1	<10	78
26085		252	<20	<0.01	<10	<10	61	<10	100
26086		113	<20	<0.01	<10	<10	10	<10	78
26087		39	30	<0.01	<10	<10	<1	<10	77
26088		35	30	<0.01	<10	<10	<1	<10	63
26089		34	30	<0.01	<10	<10	<1	<10	66
26090		37	30	<0.01	<10	<10	<1	<10	74
26091		43	<20	0.13	<10	<10	61	10	198
26092		154	<20	<0.01	<10	<10	41	<10	123
26093		168	<20	<0.01	<10	10	3	<10	37
26094		128	<20	<0.01	<10	<10	17	<10	87

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 19-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107058

Sample Description	Method	WEI-21	Au-AA23	Au-GRA21	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt	Au	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu
	Units	kg	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm
	LOR	0.02	0.005	0.05	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1
26095		2.64	0.006		0.2	0.36	10	<10	100	2.1	<2	0.31	<0.5	1	2	6
26096		4.22	<0.005		<0.2	0.32	6	<10	110	2.4	<2	0.99	<0.5	4	6	6
26097		4.54	<0.005		<0.2	0.29	4	<10	100	2.0	<2	0.91	<0.5	2	3	4
26098		5.58	0.015		0.2	0.49	44	<10	170	3.4	<2	1.65	<0.5	17	17	20
26099		3.94	<0.005		<0.2	0.64	22	<10	210	4.2	<2	2.94	<0.5	32	47	24
26100		0.14	1.040		9.1	1.78	485	<10	120	<0.5	<2	0.85	1.4	10	39	291
26101		4.16	<0.005		<0.2	0.46	14	<10	140	3.0	<2	2.84	<0.5	17	24	19
26102		3.82	<0.005		<0.2	0.53	19	<10	160	2.9	<2	2.91	<0.5	19	38	14
26103		2.82	<0.005		<0.2	0.76	21	<10	200	3.9	<2	4.27	<0.5	19	31	19
26104		4.78	0.011		<0.2	0.87	44	<10	220	4.7	<2	5.14	<0.5	27	35	23
26105		3.20	<0.005		0.2	0.81	30	<10	220	4.6	<2	5.05	<0.5	25	34	23
26106		0.10	>10.0	10.35	0.8	1.44	3950	<10	60	<0.5	2	0.75	<0.5	14	67	64
26107		4.34	0.014		<0.2	0.81	43	<10	220	4.5	<2	3.59	<0.5	27	32	23
26108		3.56	0.006		<0.2	0.75	29	<10	210	3.9	<2	3.02	<0.5	24	32	20
26109		3.14	<0.005		<0.2	0.59	9	<10	210	4.2	<2	3.81	<0.5	26	41	23
26110		3.28	0.005		<0.2	0.51	4	<10	170	3.3	<2	5.51	<0.5	28	37	18
26111		1.68	0.010		<0.2	0.39	17	<10	140	2.1	<2	2.06	<0.5	7	11	7
26112		1.54	0.028		<0.2	0.31	44	<10	120	1.6	<2	0.42	<0.5	2	1	5
26113		0.54	<0.005		<0.2	0.87	7	<10	650	<0.5	<2	2.77	0.5	6	21	20
26114		1.08	<0.005		<0.2	0.47	11	<10	140	2.6	<2	3.29	<0.5	15	26	15
26115		1.66	<0.005		<0.2	0.49	17	<10	160	2.9	<2	3.00	<0.5	17	29	13
26116		1.68	0.005		<0.2	0.44	14	<10	160	2.4	<2	1.83	<0.5	13	16	14
26117		1.22	0.009		<0.2	0.39	15	<10	150	2.2	<2	1.15	<0.5	5	9	9
26118		0.90	0.019		<0.2	0.45	27	<10	180	2.4	<2	0.68	<0.5	7	10	7
26119		1.22	0.042		<0.2	0.35	37	<10	140	1.5	<2	0.16	<0.5	1	1	4
26120		1.30	0.024		<0.2	0.32	28	<10	130	1.3	<2	0.12	<0.5	1	2	3
26121		2.04	0.057		<0.2	0.31	70	<10	130	1.3	<2	0.06	<0.5	1	1	3
26122		0.96	0.086		0.2	0.34	93	<10	140	1.4	<2	0.06	<0.5	1	1	3
26123		1.38	0.094		<0.2	0.32	94	<10	130	1.3	<2	0.23	<0.5	<1	1	3
26124		1.56	0.077		<0.2	0.35	98	<10	110	1.3	<2	0.26	<0.5	<1	1	2
26125		1.56	0.121		<0.2	0.31	143	<10	80	1.2	<2	0.24	<0.5	1	1	2
26126		1.78	0.039		<0.2	0.33	54	<10	90	1.2	<2	0.11	<0.5	1	1	3
26127		2.16	0.010		<0.2	0.29	9	<10	110	1.3	<2	0.09	<0.5	<1	1	3
26128		1.72	0.010		<0.2	0.33	10	<10	110	1.4	<2	0.17	<0.5	<1	1	3
26129		1.76	0.009		<0.2	0.33	11	<10	110	1.4	<2	0.42	<0.5	<1	1	3
26130		0.10	0.908		9.8	1.74	449	<10	110	<0.5	<2	0.82	1.2	9	36	285
26131		1.48	0.015		<0.2	0.32	12	<10	110	1.6	<2	0.67	<0.5	<1	1	3
26132		1.58	0.011		<0.2	0.31	17	<10	110	1.5	<2	0.76	<0.5	<1	2	3
26133		1.46	0.029		<0.2	0.31	31	<10	100	1.3	<2	0.33	<0.5	1	1	3
26134		2.40	0.021		<0.2	0.32	22	<10	110	1.7	<2	0.59	<0.5	1	1	3

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 19-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107058

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Fe	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc
	Units	%	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm
	LOR	0 01	10	1	0.01	10	0.01	5	1	0 01	1	10	2	0 01	2	1
26095		1.11	<10	<1	0.22	40	0.11	229	6	0.09	1	50	54	0.06	<2	1
26096		2.35	<10	<1	0.19	20	0.30	484	4	0.10	6	200	27	0.03	2	2
26097		1.76	<10	<1	0.19	20	0.20	391	4	0.08	3	40	32	0.01	<2	1
26098		4.18	<10	<1	0.24	10	0.79	866	3	0.13	22	1160	23	0.17	<2	5
26099		7.10	<10	<1	0.27	10	2.12	1120	<1	0.18	44	1710	5	0.06	<2	9
26100		3.35	10	<1	0.14	<10	0.86	505	88	0.09	40	580	98	0.27	7	5
26101		4.76	<10	1	0.22	20	1.13	890	2	0.11	25	1450	18	0.11	<2	6
26102		4.88	<10	<1	0.23	10	1.30	954	2	0.13	28	1520	15	0.06	<2	6
26103		5.51	<10	<1	0.28	20	1.86	1135	3	0.16	22	3390	11	0.07	3	8
26104		8.02	<10	<1	0.31	30	2.55	1530	2	0.16	33	4910	4	0.20	3	11
26105		7.99	<10	<1	0.29	30	2.54	1565	2	0.16	32	4820	6	0.16	2	11
26106		3.48	10	<1	0.15	10	0.84	375	6	0.05	65	480	10	0.88	34	4
26107		8.34	<10	<1	0.29	30	2.28	1470	2	0.16	36	4900	8	0.18	<2	11
26108		7.17	<10	<1	0.29	20	1.91	1170	1	0.16	33	3620	11	0.13	<2	9
26109		5.99	<10	<1	0.25	10	2.07	1215	1	0.18	37	1440	9	0.05	<2	14
26110		6.32	<10	<1	0.24	10	2.90	1200	<1	0.16	34	1660	3	0.08	<2	18
26111		2.84	<10	1	0.20	10	0.85	549	2	0.11	12	430	20	0.06	<2	4
26112		1.86	<10	<1	0.18	20	0.28	319	1	0.09	1	120	23	0.14	<2	2
26113		1.59	<10	<1	0.10	10	0.61	392	1	0.03	22	670	38	0.07	<2	3
26114		4.55	<10	<1	0.22	20	1.25	843	2	0.13	21	1300	16	0.04	<2	6
26115		4.55	<10	<1	0.24	20	1.32	844	2	0.13	22	1280	22	0.04	<2	6
26116		4.04	<10	<1	0.22	20	0.84	646	2	0.12	17	1040	21	0.04	<2	5
26117		2.51	<10	<1	0.25	40	0.42	446	3	0.10	8	380	27	0.07	<2	2
26118		3.46	<10	<1	0.28	50	0.34	553	4	0.12	7	600	28	0.16	<2	2
26119		1.56	<10	<1	0.28	60	0.07	313	4	0.08	1	40	31	0.21	<2	1
26120		1.34	<10	<1	0.26	70	0.05	262	3	0.07	1	30	29	0.18	<2	1
26121		1.27	<10	<1	0.26	70	0.05	255	3	0.07	1	40	29	0.27	2	<1
26122		1.52	<10	<1	0.27	70	0.05	297	3	0.07	<1	40	32	0.40	<2	<1
26123		1.34	<10	<1	0.28	70	0.04	265	3	0.07	1	40	33	0.39	<2	<1
26124		1.33	<10	<1	0.31	70	0.04	257	3	0.05	1	50	31	0.42	<2	1
26125		1.22	<10	<1	0.30	80	0.03	190	3	0.04	1	50	29	0.60	<2	<1
26126		1.41	<10	<1	0.32	80	0.05	283	2	0.05	1	50	31	0.28	<2	1
26127		1.41	<10	<1	0.30	70	0.05	285	3	0.06	<1	30	32	0.12	<2	1
26128		1.49	<10	<1	0.31	70	0.06	296	3	0.06	1	30	35	0.12	<2	1
26129		1.52	<10	<1	0.31	60	0.06	299	3	0.06	<1	30	31	0.12	<2	1
26130		3.26	10	<1	0.14	<10	0.82	501	84	0.08	36	570	93	0.27	7	5
26131		1.62	<10	1	0.30	70	0.06	348	3	0.06	<1	30	35	0.12	2	1
26132		1.53	<10	<1	0.29	70	0.06	374	3	0.06	<1	40	33	0.13	<2	1
26133		1.36	<10	<1	0.28	70	0.05	299	3	0.05	1	40	32	0.15	<2	1
26134		1.44	<10	<1	0.28	70	0.07	354	3	0.06	<1	50	32	0.17	<2	1

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 19-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107058

Sample Description	Method / Analyte / Units / LOR	ME-ICP41 Sr ppm 1	ME-ICP41 Th ppm 20	ME-ICP41 Ti % 0.01	ME-ICP41 Tl ppm 10	ME-ICP41 U ppm 10	ME-ICP41 V ppm 1	ME-ICP41 W ppm 10	ME-ICP41 Zn ppm 2
26095		45	20	<0.01	<10	<10	1	<10	99
26096		83	<20	<0.01	<10	<10	8	<10	91
26097		62	<20	<0.01	<10	<10	3	<10	89
26098		119	<20	<0.01	<10	<10	40	<10	150
26099		181	<20	<0.01	<10	<10	90	<10	104
26100		43	<20	0.13	<10	<10	63	<10	202
26101		124	<20	<0.01	<10	<10	42	<10	102
26102		148	<20	<0.01	<10	<10	49	<10	107
26103		219	<20	<0.01	<10	<10	68	<10	106
26104		254	<20	<0.01	<10	<10	101	<10	125
26105		240	<20	<0.01	<10	<10	101	<10	123
26106		37	<20	0.10	<10	<10	48	40	50
26107		210	<20	<0.01	<10	<10	98	<10	124
26108		182	<20	<0.01	<10	<10	79	<10	119
26109		222	<20	<0.01	<10	<10	49	<10	108
26110		327	<20	<0.01	<10	<10	43	<10	100
26111		122	<20	<0.01	<10	<10	18	<10	78
26112		43	<20	<0.01	<10	<10	5	<10	66
26113		118	<20	0.06	<10	<10	31	<10	73
26114		156	<20	<0.01	<10	<10	44	<10	95
26115		153	<20	<0.01	<10	<10	50	<10	101
26116		114	<20	<0.01	<10	<10	31	<10	99
26117		87	<20	<0.01	<10	<10	14	<10	88
26118		73	<20	<0.01	<10	<10	15	<10	116
26119		33	20	<0.01	<10	<10	1	<10	93
26120		31	20	<0.01	<10	<10	1	<10	90
26121		26	20	<0.01	<10	<10	1	<10	89
26122		27	20	<0.01	<10	<10	<1	<10	99
26123		37	20	<0.01	<10	<10	<1	<10	96
26124		36	20	<0.01	<10	<10	1	<10	91
26125		35	20	<0.01	<10	<10	<1	<10	88
26126		25	20	<0.01	<10	<10	<1	<10	97
26127		26	20	<0.01	<10	<10	<1	<10	94
26128		32	20	<0.01	<10	<10	1	<10	95
26129		50	20	<0.01	<10	<10	1	<10	97
26130		44	<20	0.13	<10	<10	60	10	188
26131		57	20	<0.01	<10	<10	1	<10	91
26132		60	20	<0.01	<10	<10	1	<10	103
26133		39	20	<0.01	<10	<10	1	<10	88
26134		57	20	<0.01	<10	<10	1	<10	95

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 19-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107058

Sample Description	Method	WEI-21	Au-AA23	Au-GRA21	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Recvd Wt	Au	Au	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Co	Cr	Cu
	Units	kg	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm
	LOR	0.02	0.005	0.05	0.2	0.01	2	10	10	0.5	2	0.01	0.5	1	1	1
26135		2.34	0.043		0.2	0.32	43	<10	100	1.9	2	0.30	<0.5	1	1	3
26136		0.48	0.007		<0.2	1.47	8	<10	380	<0.5	<2	1.82	<0.5	10	30	30
26137		1.48	0.030		<0.2	0.31	37	<10	90	1.3	<2	0.40	<0.5	<1	1	3
26138		1.74	0.032		<0.2	0.30	41	<10	90	1.3	<2	0.87	<0.5	<1	2	3
26139		1.16	0.019		<0.2	0.32	26	<10	100	1.3	<2	0.31	<0.5	<1	1	3
26140		1.76	0.011		<0.2	0.32	13	<10	110	1.2	<2	0.14	<0.5	<1	1	2
26141		1.90	0.012		<0.2	0.36	18	<10	100	1.3	<2	0.63	<0.5	1	1	2
26142		2.04	0.018		0.2	0.29	26	<10	100	1.2	<2	0.61	<0.5	1	1	2
26143		1.48	0.015		0.2	0.31	21	<10	90	1.4	2	0.74	<0.5	1	1	3
26144		1.94	0.005		<0.2	0.30	9	<10	120	1.5	2	0.90	<0.5	<1	1	3
26145		1.88	<0.005		0.2	0.32	9	<10	110	1.4	2	0.48	<0.5	<1	1	4
26146		2.14	<0.005		<0.2	0.31	4	<10	130	1.5	2	0.55	<0.5	<1	1	2
26147		1.56	<0.005		<0.2	0.34	<2	<10	140	1.6	<2	0.53	<0.5	<1	1	2
26148		2.38	<0.005		<0.2	0.34	<2	<10	140	1.8	<2	0.77	<0.5	<1	1	2
26149		1.60	<0.005		<0.2	0.34	<2	<10	150	1.7	<2	0.63	<0.5	1	1	2
26150		1.88	<0.005		<0.2	0.33	<2	<10	150	1.7	<2	0.71	<0.5	<1	1	1
26151		2.10	<0.005		<0.2	0.38	2	<10	150	1.9	<2	0.85	<0.5	<1	1	2
26152		2.02	<0.005		<0.2	0.34	<2	<10	140	2.1	<2	1.23	<0.5	<1	1	2
26153		1.18	<0.005		<0.2	0.36	2	<10	140	2.2	<2	2.12	<0.5	1	1	3
26154		0.10	9.87		0.4	1.51	4020	<10	60	0.5	<2	0.78	<0.5	14	68	67
26155		1.74	0.015		<0.2	0.37	4	<10	200	2.4	<2	1.09	<0.5	1	2	2
26156		1.14	0.012		<0.2	0.38	<2	<10	230	2.8	<2	0.91	<0.5	2	4	7
26157		2.26	0.005		<0.2	0.56	2	<10	700	4.0	<2	4.33	<0.5	17	40	7
26158		0.90	<0.005		<0.2	0.53	4	<10	1410	3.7	<2	5.63	<0.5	18	51	2
26159		0.52	<0.005		<0.2	0.92	7	<10	590	<0.5	<2	2.50	0.6	5	18	19
26160		1.42	<0.005		<0.2	0.55	<2	<10	1310	4.0	<2	5.50	<0.5	18	53	1
26161		1.74	<0.005		<0.2	0.53	2	<10	290	3.2	<2	4.66	<0.5	15	55	4
26474		0.48	<0.005		0.2	0.47	<2	<10	60	<0.5	<2	2.08	<0.5	3	9	2
26475		0.84	<0.005		<0.2	0.41	3	<10	160	<0.5	<2	18.6	0.7	2	7	8
26476		6.36	0.005		<0.2	1.21	<2	<10	1000	<0.5	<2	4.21	<0.5	10	6	110
26477		3.12	<0.005		<0.2	0.40	72	<10	340	0.8	<2	8.81	<0.5	21	68	33
26478		0.54	<0.005		<0.2	0.32	8	<10	100	0.8	<2	0.10	<0.5	<1	3	1
26479		0.56	<0.005		<0.2	1.35	3	<10	50	<0.5	<2	6.69	<0.5	24	74	115
26480		0.88	<0.005		<0.2	0.24	2	<10	80	<0.5	<2	1.39	<0.5	1	4	2
26481		2.66	0.006		0.7	0.15	84	<10	20	<0.5	<2	8.23	<0.5	2	1	8
26482		4.12	<0.005		0.2	0.21	49	<10	60	<0.5	<2	0.88	<0.5	2	5	4
26483		2.90	<0.005		0.2	0.21	120	<10	70	<0.5	<2	0.23	<0.5	<1	3	1
26484		4.48	<0.005		<0.2	1.42	17	<10	320	<0.5	<2	1.54	<0.5	9	7	59
26485		2.00	<0.005		<0.2	1.65	<2	<10	110	<0.5	<2	4.14	<0.5	8	6	94
26486		4.56	<0.005		<0.2	0.67	<2	<10	770	<0.5	<2	2.41	<0.5	4	5	23

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone. 604 984 0221 Fax. 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 19-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107058

Sample Description	Method	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41	ME-ICP41
	Analyte	Fe	Ga	Hg	K	La	Mg	Mn	Mo	Na	Ni	P	Pb	S	Sb	Sc
	Units	%	ppm	ppm	%	ppm	%	ppm	ppm	%	ppm	ppm	ppm	%	ppm	ppm
	LOR	0.01	10	1	0.01	10	0.01	5	1	0.01	1	10	2	0.01	2	1
26135		1.55	<10	<1	0.27	70	0.06	349	4	0.06	1	40	31	0.28	<2	1
26136		2.90	10	<1	0.10	10	0.93	536	1	0.03	28	720	26	0.08	<2	7
26137		1.46	<10	<1	0.29	80	0.05	348	2	0.05	1	60	29	0.23	<2	1
26138		1.35	<10	<1	0.27	80	0.04	355	2	0.05	<1	50	28	0.30	<2	1
26139		1.50	<10	<1	0.29	70	0.05	340	3	0.06	1	50	30	0.19	2	1
26140		1.33	<10	<1	0.29	70	0.04	275	3	0.06	<1	40	29	0.13	<2	1
26141		1.61	<10	<1	0.33	70	0.05	353	3	0.06	1	50	28	0.15	<2	1
26142		1.33	<10	<1	0.27	70	0.04	303	3	0.05	<1	40	30	0.15	<2	1
26143		1.24	<10	<1	0.28	70	0.04	306	3	0.05	<1	40	30	0.13	2	1
26144		1.36	<10	<1	0.26	60	0.04	343	3	0.08	<1	30	35	0.10	<2	1
26145		1.56	<10	<1	0.27	70	0.04	317	5	0.06	1	40	34	0.09	<2	1
26146		1.58	<10	<1	0.26	80	0.04	352	4	0.07	<1	50	34	0.10	<2	1
26147		1.42	<10	<1	0.29	80	0.04	319	2	0.07	1	50	34	0.10	<2	1
26148		1.41	<10	<1	0.30	80	0.05	365	2	0.07	<1	30	34	0.05	<2	1
26149		1.47	<10	<1	0.31	80	0.06	351	2	0.07	1	40	17	0.04	<2	1
26150		1.42	<10	<1	0.31	70	0.05	347	2	0.07	1	20	18	0.03	<2	1
26151		1.11	<10	<1	0.36	70	0.05	276	2	0.07	<1	10	27	0.04	<2	1
26152		0.98	<10	<1	0.34	70	0.05	284	2	0.06	1	20	22	0.07	<2	1
26153		1.18	<10	<1	0.34	60	0.08	331	1	0.06	2	10	23	0.04	<2	1
26154		3.57	10	<1	0.16	10	0.86	386	6	0.06	65	500	8	0.92	34	5
26155		1.58	<10	1	0.32	30	0.10	406	1	0.09	1	140	19	0.06	<2	1
26156		1.81	<10	<1	0.30	30	0.30	384	2	0.10	4	180	32	0.05	<2	2
26157		4.52	<10	<1	0.32	10	1.54	1090	<1	0.15	29	2080	20	0.23	2	10
26158		4.65	<10	<1	0.28	10	2.32	1020	<1	0.14	40	1750	13	0.27	<2	8
26159		1.65	<10	<1	0.14	10	0.80	398	1	0.04	21	570	30	0.07	<2	3
26160		4.54	<10	1	0.28	10	2.26	925	<1	0.15	37	1870	14	0.21	<2	8
26161		3.84	<10	<1	0.29	10	1.70	950	<1	0.14	22	1980	11	0.02	<2	9
26474		1.03	<10	<1	0.14	10	0.18	365	<1	0.02	6	160	9	0.02	<2	1
26475		0.69	<10	<1	0.04	<10	0.36	1170	<1	0.01	3	280	4	<0.01	<2	3
26476		2.29	<10	<1	0.17	10	0.71	815	<1	0.03	9	540	3	0.04	<2	4
26477		4.06	<10	1	0.24	10	3.81	1240	<1	0.02	114	710	5	0.20	2	12
26478		0.23	<10	<1	0.27	10	0.06	33	<1	0.02	1	10	23	0.01	<2	<1
26479		2.65	<10	1	0.05	<10	1.18	468	1	0.03	24	400	<2	0.27	<2	3
26480		1.13	<10	<1	0.09	<10	0.26	272	<1	<0.01	4	150	4	0.02	<2	2
26481		6.17	<10	2	0.26	10	0.01	777	5	0.01	7	80	103	7.24	7	2
26482		2.98	<10	1	0.32	10	0.01	115	2	0.01	3	210	15	1.37	<2	2
26483		5.64	<10	1	0.56	10	0.02	34	6	0.14	1	200	4	2.14	<2	1
26484		2.57	<10	1	0.19	10	0.77	893	<1	0.01	17	520	8	0.07	<2	3
26485		2.95	10	3	0.19	<10	0.78	1440	<1	0.01	6	560	2	0.07	<2	5
26486		1.43	<10	1	0.10	<10	0.30	594	<1	0.03	2	230	<2	0.03	<2	2

ALS Chemex
EXCELLENCE IN ANALYTICAL CHEMISTRY
ALS Canada Ltd
2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alschemex.com

To: EMERICK RESOURCES LTD.
355 BURRARD ST SUITE 830
VANCOUVER BC V6C 2G8

Finalized Date: 19-OCT-2009
Account: EMERES

Project: Canyon Gold

CERTIFICATE OF ANALYSIS VA09107058

Sample Description	Method / Analyte / Units / LOR	ME-ICP41 Sr ppm 1	ME-ICP41 Th ppm 20	ME-ICP41 Ti % 0.01	ME-ICP41 Tl ppm 10	ME-ICP41 U ppm 10	ME-ICP41 V ppm 1	ME-ICP41 W ppm 10	ME-ICP41 Zn ppm 2
26135		36	20	<0.01	<10	<10	<1	<10	91
26136		57	<20	0.09	<10	<10	69	<10	80
26137		49	20	<0.01	<10	<10	1	<10	97
26138		72	20	<0.01	<10	<10	<1	<10	87
26139		47	20	<0.01	<10	<10	1	<10	95
26140		29	20	<0.01	<10	<10	1	<10	88
26141		64	20	<0.01	<10	<10	<1	<10	94
26142		61	20	<0.01	<10	<10	<1	<10	91
26143		49	20	<0.01	<10	<10	<1	<10	86
26144		83	20	<0.01	<10	<10	<1	<10	89
26145		50	20	<0.01	<10	<10	<1	<10	96
26146		61	20	<0.01	<10	<10	1	<10	94
26147		56	20	<0.01	<10	<10	1	<10	92
26148		76	20	<0.01	<10	<10	<1	<10	82
26149		59	20	<0.01	<10	<10	1	<10	85
26150		73	20	<0.01	<10	<10	<1	<10	73
26151		94	20	<0.01	<10	<10	<1	<10	55
26152		137	20	<0.01	<10	<10	1	<10	51
26153		252	20	<0.01	<10	<10	1	<10	54
26154		39	<20	0.10	<10	<10	50	40	52
26155		130	<20	<0.01	<10	<10	4	<10	86
26156		73	<20	<0.01	<10	<10	7	<10	88
26157		246	<20	<0.01	<10	<10	45	<10	104
26158		367	<20	<0.01	<10	<10	53	<10	93
26159		104	<20	0.05	<10	<10	31	<10	67
26160		399	<20	<0.01	<10	<10	59	<10	85
26161		233	<20	0.03	<10	<10	64	<10	68
26474		87	<20	<0.01	<10	<10	7	<10	16
26475		386	<20	<0.01	<10	10	12	<10	19
26476		80	<20	0.01	<10	<10	36	<10	55
26477		568	<20	<0.01	<10	<10	33	<10	71
26478		6	20	<0.01	<10	<10	1	<10	10
26479		122	<20	0.30	<10	<10	47	<10	34
26480		43	<20	<0.01	<10	<10	2	<10	22
26481		232	<20	<0.01	50	<10	2	<10	94
26482		71	<20	<0.01	10	<10	5	<10	25
26483		53	<20	<0.01	<10	<10	6	<10	27
26484		39	<20	<0.01	<10	<10	20	<10	67
26485		110	<20	<0.01	<10	<10	30	<10	52
26486		93	<20	0.01	<10	<10	28	<10	23

APPENDIX 4

WORK HISTORY

GREW CREEK PROJECT

A. Carlos (owner)
Whitehorse, Yukon
Phone (867) 668-6309

PROJECT STATUS
Optioned to Emerick Resources Corp.



Location
35 km west of Ross River

Ownership
A. Carlos

Commodity
Gold, silver

Ore type
Oxide

Mineral resource (cut-off grade of 0.2 g/t Au)*
0.773 million tonnes grading 33 g/t Ag and 8.9 g/t Au

*Historical resource; not NI 43-101 compliant

Proposed mining method
Open-pit, 365 days per year

Processing method
Conventional mill, dore bar, 365 days per year

Power
Yukon Energy's Faro-Ross River powerline crosses the property

HISTORY

The original Grew Creek claims were staked by Whitehorse prospector A. Carlos in 1983 and optioned by the Mincan JV (Hudson Bay Mining and Minerals), which carried out an extensive exploration program from 1984 to 1986.

In 1987, the claims were optioned by Noranda, which subsequently signed a joint-venture agreement with Golden Nevada Resources and Brenda Mines. Results of the 1987 program triggered a flurry of claim-staking and exploration activity in the area. A large-scale exploration program continued in 1988. In 1989, Golden Nevada changed its name to Goldnev Resources and renegotiated the joint venture agreement to give it a 100% interest in the property.

In 1992, Wheaton River Minerals took an option to conduct an underground development program, however, the option was dropped shortly after.

YGC Resources Ltd. optioned the property in 1993, and completed a $150 000 drilling program at Grew Creek in 1995, and a 17 diamond-drill hole program in 1996. YGC terminated its option agreement with Carlos in January, 1997.

In 2000, a total of $36 000 was spent by A. Carlos exploring a new area 1.8 km from the main zone. He returned in 2001 to drill an additional five holes totalling 262 m, and continued to drill another six holes totalling 415 m in 2002. In 2003, he drilled a further 450 m in seven holes.

In July, 2004, Freegold Ventures Limited entered an option agreement to acquire up to a 100% interest in the project. The company reinterpreted the geology and proposed that the major direction of mineralization was sub-parallel to previous drilling which had been generally north/south in orientation. The company began a 12-hole confirmation drill program in October within the Main Zone using an east-west drilling orientation. This drilling program tended to intersect the veining at a truer width than was seen in the past.

In late 2005 Freegold conducted its own induced polarization survey over the Main Zone in order to determine if a geophysical signature could be associated with the mineralization. A well defined chargeability anomaly was identified that coincided very well with

Reserves/resources are from a variety of sources and may not be compliant with National Instrument 43-101 Standards, unless specified.

the horizontal extents of the known mineralization. An additional 2 km of IP surveys were conducted, and two new areas were identified that contained geophysical signatures similar to those seen in the Main Zone. Freegold's most recent drilling in late 2005 and early 2006 tested these two new anomalies in the Rat Creek and Tarn zones with 13 holes.

In 2007, Freegold relinquished its option on the property. In January, 2008, the property was optioned by Emerick Resources Corporation, which prepared a summary geological report that reviewed exploration work carried out on the property to date. During the summer of 2008, A. Carlos carried out further enzyme leach soil sample surveys.

PROJECT SUMMARY

The Grew Creek deposit can be mined by open-pit methods with a stripping ratio of 9:1, waste to ore. Metallurgical testing by Noranda in 1988 indicated that recoveries of 92% to 94% are possible using simple cyanide processing.

The Grew Creek property is located approximately 35 km west of Ross River and 1 km from the Robert Campbell Highway and the Whitehorse power grid. The property consists of 192 claims and is owned by A. Carlos of Whitehorse.

The 2004 drill program evaluated a new interpretation of the structural controls on the mineralized vein system within the deposit and nearby targets.

Geology, mineralogy and ore reserves

The Grew Creek epithermal gold deposit is hosted by Eocene volcanic and sedimentary rocks deposited in a pull-apart basin within the Tintina fault zone. The gold occurs in stockwork quartz veins and hydrothermal breccias cutting hydrothermally altered rhyolite.

In the main zone, rhyolitic tuffs are juxtaposed by an east-trending fault against a cyclic sequence of fluvial sedimentary rocks. The faulted contact is partly intruded by a quartz-feldspar porphyry dyke. The pyroclastic rocks, dyke, fault and sedimentary rocks all dip steeply to the north. The volcanic rocks are hydrothermally altered to illite-quartz and illite-quartz-adularia assemblages, with an outer propylitic halo.

The mineralized zone contains pyrite, marcasite, arsenopyrite, chalcopyrite, argentite, electrum, silver selenides, galena and sphalerite. Fluorite is also present in the Tarn zone. Gangue minerals include quartz, adularia, carbonates, and quartz pseudomorphs after calcite. In the main zone, gold and silver occur as micron-size grains in chalcedony stringer stockworks and adjacent silicified tuffs. There is a good correlation between gold and silver, with a gold:silver ratio of about 1:4 for ore-grade mineralization, which occurs in an elongated zone trending west-northwest. Arsenic and mercury are strongly anomalous in the mineralized rock, but mercury shows only a weak correlation with gold and silver. Most high mercury values lie along the fault, above the gold-silver zone.

Initial drilling on the main zone gave a best intersection of 11.7 g/t Au and 150.9 g/t Ag across 31.4 m, while the best section exposed in a trench assayed 3.6 g/t Au and 15.3 g/t Ag across 13 m. The 1989 drilling focused on the main zone, with the best hole returning 10.5 g/t Au over 13 m.

The Tarn zone, located 2 km to the east, consists of quartz-fluorite-chalcedony stockwork and localized silicification within a 900 x 100 m zone of sericitized rhyolite dykes and tuff. The best assays were 150 ppb Au across 2.0 m in a trench and 520 ppb Au over 1.5 m in a drill hole.

Prospecting in the area is difficult due to a thick cover of glacial till. Plouffe (1989) showed that gold is concentrated in the silt- and clay-size fraction down-ice from the Grew Creek deposit, but the common pathfinder elements Ag, Sb, As and Hg show little correlation with the gold distribution.

In 1991, a trench in the K410 zone, 15 km northwest of the deposit, uncovered intensely iron-stained, highly fractured acid-leached volcanic rocks. Carlos excavated four hand pits to bedrock in 1992 and encountered intensely clay-altered Eocene sediments with hematite-rich bands. Samples from the pits returned anomalous values of mercury and barium, and a heavy mineral concentrate from 45 kg of glacial till in Pit #2 assayed 9320 ppb Au.

The 1993 diamond drilling intersected strongly altered volcanic rocks beneath a zone of hydrothermal alteration exposed in a surface trench.

The 1994 drilling showed that the South zone consists of an extensive quartz-adularia stringer stockwork of low-grade gold-silver values. The best intersections were 2.33 g/t Au and 4.1 g/t Ag over 10.4 m. The South zone appears to be connected with the Main zone, but

Reserves/resources are from a variety of sources and may not be compliant with National Instrument 43-101 Standards, unless specified.

further drilling between the two mineralized zones needs to be carried out to confirm this theory. Drilling in the Main zone confirmed earlier reported grades. The best intersection was 1.69 g/t Au and 3.0 g/t Ag over 24 m.

In 2000, a total of 450 soil samples were grid-collected over a 2 km area and analysed by the enzyme-leach method. Three new geochemical targets were delineated in a favourable structural area north of the Tarn zone, adjacent to the Robert Campbell Highway.

In 2001, five holes were drilled and a hydrothermal breccia was intersected.

In 2002, 1200 grid soil samples were collected on the Maverick prospect, located 7 km northwest of the Grew Creek deposit along the graben trend. The samples were analysed using the enzyme leach technique. Results from the sampling prompted the drilling of four holes totaling 268 m. An additional 365 fill-in and grid expansion soil samples were also collected.

In 2004, significant intercepts from Freegold's drilling included: 10.9 m (true width) grading 6.8 g/tonne, including 1.5 m (true width) @ 17.8 g/tonne in hole GC-04-225, and 4.4 m (true width) grading 22.1 g/tonne in hole GC-04-227.

While drilling in 2005 and 2006 intersected favourable alteration and evidence of hydrothermal activities similar to that seen in the Main Zone, only anomalous gold levels were encountered over broad areas. The recent identification of uranium in drill core has led the company to reassess the project's potential. A single interval of core from hole GC-06-248 (112.78 to 114.3 m) in the Tarn zone was reassayed and returned a grade of 0.1% U_3O_8 over a 1.52-metre interval. The significance of this uranium mineralization and its relationship to new depositional models remains uncertain. Previous glacial till concentrate samples from the eastern portion of the Tarn area identified large areas of anomalous rare-earth elements, including thorium (up to 58 ppm), lanthanum (up to 270 ppm) and uranium (up to 270 ppm).

Production plans

In 1989, Orcan Mineral Associates estimated a geological resource of 773 012 tonnes grading 8.9 g/t Au and 33.6 g/t Ag at a cut-off grade of 0.2 g/t Au and containing a higher grade resource of 184 947 tonnes grading 12.1 g/t Au. This resource estimate is not NI 43-101 compliant.

Reserves/resources are from a variety of sources and may not be compliant with National Instrument 43-101 Standards, unless specified.

HYLAND PROPERTY

StrataGold Corporation

President and Chief Executive Officer: Terry Tucker

Corporate headquarters
2250-1066 West Hastings Street
Vancouver, British Columbia V6C 3X2

Phone	(604) 682-5122
Toll free	1-877-682-5122
Fax	(604) 682-5232
E-mail	info@stratagold.com
Website	*www.stratagold.com*

Stock symbol: SGV (TSX.V)

PROJECT STATUS

Inactive

Location
70 km northeast of Watson Lake

Ownership
StrataGold Corporation

Commodity
Gold (lead, silver)

Ore type
Oxide and sulphide

Resource estimate*
3.1 million tonnes grading 1.1 g/t Au

*Historical calculation; not NI 43-101 compliant



HISTORY

The property was originally staked and explored in the early to mid 1950s including 365 m of diamond drilling in four holes. In the mid 1970s the property was staked (Porker) and explored once again, resulting in 303 m of drilling in four holes. Exploration picked up in the 1980s when Kidd Creek Mines Ltd. tied on Quiver claims to the east in June of 1982. They explored with geological mapping and grid soil sampling later in the year. Archer, Cathro & Associates (1981) Ltd. staked the Piglet in March 1984, performing geological mapping, soil sampling and prospecting. They acquired the remaining Quiver claims and sold the property to Silverquest Resources Ltd., which performed geological mapping, soil sampling and prospecting in 1986.

In 1987, Silverquest entered the Hyland Joint Venture (with NDU Resources Ltd. and Novamin Resources Inc.) which explored with mapping, bulldozer trenching and sampling. After Novamin dropped its interest and was replaced by Adrian Resources Ltd., the partners added more claims and explored with bulldozer trenching, soil sampling, geophysical surveying, four holes (376 m) and road construction in 1988. A winter road was built to the property from the Alaska Highway in 1989, and 41 reverse circulation percussion holes totalling 3800 m were drilled in 1990.

In May, 1994, Westmin Resources Ltd. staked claims surrounding this occurrence and the Cuz occurrence, located 3 km to the south. During the summer and fall of 1994, Westmin carried out airborne EM, Mag/VLF and radiometric geophysical surveys, property-scale geological mapping, prospecting, rock, soil and stream sampling and grid development on its claims. In December, 1994, Hemlo Gold Mines Ltd. acquired an option on the Piglet, Quiver and Sow claims from Adrian Resources, NDU Resources and Cash Resources.

In July, 1995, Hemlo drilled three diamond drill holes (439.2 m) along the northern extension of the Main zone. Westmin did more staking and soil geochemistry, geological mapping, and rock and auger sampling during the 1995 and 1996 exploration seasons.

In March of 1998, Westmin Resources was acquired by Boliden Ltd. and in April of 1999, Expatriate Resources Ltd. purchased the Ver and CJ claims from Boliden. Expatriate subsequently formed the Hyland Gold Joint Venture (Cash Resources Ltd. 55%, Expatriate 31% and

Reserves/resources are from a variety of sources and may not be compliant with National Instrument 43-101 Standards, unless specified.

YUKON MINFILE
YUKON GEOLOGICAL SURVEY
WHITEHORSE

MINFILE # 105K 009
NAME: GREW CREEK
DEPOSIT TYPE: EPITHERMAL AU-AG: LOW SULPHIDATION
STATUS: DEPOSIT
TECTONIC ELEMENT: POST-AMALGAMATION PLUTONIC ROCKS

NTS MAP SHEET: 105K\2
LATITUDE: 62° 2' 47" N
LONGITUDE: 132° 51' 15" W

OTHER NAME(S): MAIN ZONE
MAJOR COMMODITIES: GOLD, SILVER
MINOR COMMODITIES:
TRACE COMMODITIES: ARSENIC, MERCURY

CLAIMS (PREVIOUS & CURRENT)

CAN, CANYON, CARLIN, ERN, GREW, HELL, RAN, TAR

WORK HISTORY

The original claims were staked as Grew cl 1-48 (94550) between Nov/65 and Feb/66 by General Enterprises Ltd and optioned to Gaylord Mines Ltd in 1967, which carried out magnetometer, EM and IP surveying later in the year. Three drill holes reportedly planned in 1968 were apparently never drilled. The nearby Carlin cl 1-32 (Y5762) were staked in May 66 by S. Young and examined briefly by Scope Mining and Exploration Consultants later that year.

A. Carlos, unaware of any previous staking became interested in the area following reports of Faro residents hand mining and recovering placer gold from Grew Creek. Prospecting the area, Carlos noted the presence of Tertiary volcanics and strong structural features furthering his interest. In May/83 Carlos discovered gold mineralization in outcrop and restaked the occurrence area within Canyon cl 1-40 (YA75717) in Jun/83. Carlos carried out geological mapping and geochemical sampling later in the year. The Canyon group was optioned late in 1983 by Mincan joint venture (Hudson Bay Exploration and Development Company Ltd and Minorco Canada Ltd), which staked more claims and carried out geological mapping, VLF-EM and magnetometer surveying and geochemical sampling in 1984 and 1985; trenching and drilled 13 holes (1732 m) in 1984; drilled 19 percussion holes (1660 m) in 1985; and geochemical sampling, EM and magnetometer surveying in 1986, before dropping the option.

The Ren cl 1-2 (YA75799), Tar cl 1-8 (YA75786), Hell cl 1-8 (YA75778) and Ern cl 1-8 (YA75749) were staked contiguously with the southern corner of the original Canyon claims in Jul/83 by Ezee Golds Ltd, which carried out trenching in 1983, 1984 and 1986. In 1987 Ezee Golds drilled one hole (51.3 m) for assessment on the Ern etc claims; carried out trenching, road work and additional drilling in 1989 and 1990; and trenching and road work in 1992. In Oct/93, Ezee Golds performed trenching on the Ern, Hell, Tar, and Ren, claims and on fractional Vac, JSC and TMP claims.

The Canyon claims were reoptioned in 1987 by a joint venture between Noranda Exploration Company Ltd, Golden Nevada Resources Inc and Brenda Mines Ltd, which carried out property wide geochemical sampling, ground magnetometer, airborne geophysical surveying and drilled 17 holes (2972 m) 500 m west of Grew Creek on Canyon cl 3 and 4 (Main Zone) in 1987; geophysical surveying, geochemical sampling and drilled 30 core holes (13 156.5 m) in the Main Zone, 10 core holes (3045 m) in the Tarn Zone (east of Grew Creek) and 12 rotary holes (1448 m) between the two zones in 1988; and drilled 10 holes (1165 m) in 1989. Golden Nevada Resources Inc changed its name to Goldnev Resources Inc in Jun/89 and excavated 18 backhoe trenches and 4 pits in 1991 before

dropping its option later in the year.

Noranda Exploration Company Ltd tied on Can cl 1-168 (YB7880) to the northwest in Sep/87 and optioned them to Mintel International Development Corporation, which carried out geochemical sampling later in the year. Mintel staked the Ran cl 1-1 040 (YB08978) adjacent to and northwest of the Can claims in 1987. Mintel changed its name to Golden Trump Resources Ltd in Apr/89 and transferred the Ran claims to Prime Equities Inc in Nov/91. The Can claims were transferred to Prime Equities International Corporation in Dec/91. Both the Can and Ran claim groups were later transferred to A. Carlos in Apr/92.

In 1992, Wheaton River Minerals signed a letter of agreement to acquire the Grew Creek deposit but the terms of the option agreement were not fulfilled and the core claims reverted to Carlos. By the end of 1992, all of the Canyon and Grand claims previously optioned by other companies were also returned to Carlos.

In Feb/93 YGC Resources Ltd optioned the Grew Creek property (Minfile Occurrences #105K 008, 093, 113, this occurrence and 105F 047) and later in the year drilled 17 holes (1944 m) on the Canyon claims and carried out trenching on the Ran claims.

In Apr/94 YGC purchased the Ketza River property (Minfile Occurrence #105F 019) including a 400 metric tonnes per day mill from Wheaton Rivers Minerals Ltd. The sale was paid for with YGC shares and resulted in Wheaton River becoming controlling shareholder in YGC. YGC planned to truck Grew Creek ore to the Ketza River mill for processing, starting in 1995. Projected production was expected to be 30 000 oz (930 000 gm) Au per year for 3 years, with a 93% recovery. The plan never proceeded.

During the 1994 exploration season YGC drilled 14 holes (1307 m) in the South and Main Zones. Nine holes were drilled in the South Zone to identify and sample the mineralization along the zone. The remaining 5 holes were drilled to fill in, test continuity and determine the upper level of bedrock mineralization at the eastern end of the Main Zone. In Oct/94 Carlos transferred the Grand, Ran, Can and Canyon claim groups to YGC.

In 1995 YGC drilled 14 diamond drill holes (1530 m) on the Grew Creek property. Twelve of the holes were drilled to test various targets in and adjoining the Main Zone. One hole was drilled at the Main West Zone located 2 km to the west on Canyon cl 48 (YA81167). The remaining hole was drilled on Canyon cl 221 (YA81340) located approximately 16 km to the west (Minfile Occurrence #105K 113).

In the spring of 1996 YGC drilled 17 diamond drill holes (1560.7 m) to systematically drill test the continuity of the Main Zone mineralization on intermediate sections between 10+175E and 10+287.5E. Following completion of the program, the company carried out a compilation study which included surveying the location of all known drill holes and calculating an updated resources estimate for the Main Zone. At the end of 1996 YGC elected not to complete the final year of the option agreement and returned the various claim groups to Carlos.

Carlos staked Canon cl 1-6 (YC08793) in May/98 and Canon cl 7-14 (YC08939) in Jul/98, 2.5 km north of this occurrence location and contiguous with the existing Grew Creek claim block. Later that year Carlos carried out VLF-EM and magenetometer surveying, prospecting, soil sampling and trenching on the Canon claims.

In 2000 Carlos carried out an enzyme leach sampling program on a grid located between this occurrence location and the Robert Campbell Highway (located to the north). In 2001 and 2002 Carlos drilled 4 holes (191.1 m) and 6 holes (416.7 m), respectively, to test one of the anomalies (E) which is located immediately east of the occurrence location. Carlos also collected additional enzyme leach samples to increase his sampling density. In 2003 Carlos collared 3 diamond drill holes (150.9 m) on anomaly E and 4 diamond drill holes on the Maverick prospect's anomaly B (Minfile Occurrence #105K 093) located approximately 10 km to the northwest. In 2004, before Carlos optioned the Grew Creek property, Carlos drilled 5 additional diamond drill holes (219.80 m) on anomaly B.

In Jul/2004 Carlos optioned the entire Grew Creek property to Freegold Ventures Ltd which drilled 12 diamond drill holes (633.4 m) on the Main zone. In 2005 Freegold Ventures carried out IP surveys on the Maverick prospect (Minfile Occurrence #105K 093), the Main zone, and the Rat Creek and Tarn zones (they adjoin the Main zone on the southeast side). The company followed up by drilling 6 diamond drill holes (960 m) on the Tarn and Rat Creek zones; 5 holes targeted the Tarn zone and 1 hole targeted the Rat Creek zone. Two of the Tarn zone drill holes were collared in overburden. The diamond drilling was conducted in two parts; mid to late March and November to mid-December.

In 2006 the company drilled 5 diamond drill holes (798 m) on the Tarn zone to test various IP chargeability targets. In the third quarter of 2007 Freegold Ventures dropped its option and returned the Grew Creek property to

Carlos.

In Jan/2008 Carlos optioned the Grew Creek property to Emerick Resources Corporation which completed a compilation report in May/2008. Carlos carried out additional enzyme leach sampling in 2008.

In 2009, Emerick completed nine diamond drillholes on the Sleeper, RAT and Barium zones for a total of 1600 m. These holes tested enzyme leach soil anomalies distal to the historic gold resource at Grew Creek. No significant drill results were achieved.

GEOLOGY

The Grew Creek epithermal gold deposit is hosted by Eocene Ross Assemblage volcanic and sedimentary rocks deposited in a pull-apart basin within the Tintina Fault zone. The gold occurs in stockwork quartz veins and hydrothermal breccias cutting hydrothermally altered rhyolite. In Dec/89 Goldnev Resources Ltd reported that the Main Zone contained drill indicated reserves of 773 020 tonnes grading 8.92 g/t gold and 33.6 g/t silver. Within this deposit Goldnev identified a high grade core containing a drill indicated reserve of 184 950 tonnes grading 12.14 g/t gold. Metallurgical testing by Noranda in 1988 indicated that recoveries of 92-94% are possible using simple cyanide processing.

In the Main Zone, rhyolitic tuffs are juxtaposed against a cyclic sequence of Carboniferous and Permian aged fluvial sediments along the northwest-southeast trending Grew Creek fault. The faulted contact is partly intruded by a quartz-feldspar porphyry dyke. The pyroclastic rocks, dyke, fault and sediments all dip steeply to the north. The volcanic rocks are hydrothermally altered to illite-quartz and illite-quartz-adularia assemblages, with an outer propylitic halo.

Mineralization consists of pyrite, marcasite, arsenopyrite, chalcopyrite, argentite, electrum, silver selenides, galena and sphalerite. Fluorite is also present in the Tarn zone, 2 km southeast of the Main zone. Gangue minerals include quartz, adularia, carbonates, and quartz pseudomorphs after calcite. In the main zone, gold and silver occur as micron-size grains in chalcedony stringer stockworks and adjacent silicified tuffs. There is a good correlation between gold and silver assays, with a gold: silver ratio of about 1:4 for ore-grade mineralization, which occurs in an elongated zone trending west-northwest. The mineralization is strongly anomalous in arsenic and mercury, but mercury shows only a weak correlation with gold and silver. Most high mercury values lie along the fault, above the gold-silver zone.

Initial drilling on the Main Zone returned a best intersection of 11.7 g/t gold and 150.9 g/t silver across 31.4 m, while the best section exposed in a trench assayed 3.6 g/t gold and 15.3 g/t silver across 13 m. The 1989 drilling focused on the Main Zone, with the best intersection returning 10.5 g/t gold over 13 m.

The Tarn Zone, located 2 km to the east, consists of quartz-fluorite-chalcedony stockworks and localized silicification within a 900 x 100 m zone of sericitized rhyolite dykes and tuff. The best assays were 150 ppb gold across 2.0 m in a trench and 520 ppb gold over 1.5 m in a drill hole.

Prospecting in the area is difficult due to a thick cover of glacial till. Plouffe (1989) showed that gold is concentrated in the silt and clay size fraction down-ice from the Grew Creek deposit, but the common pathfinder elements silver, antimony, arsenic and mercury show little correlation with the gold distribution.

On the Ern claims, Ezee's 1987 drill hole cut silicified, argillized crystal-lithic felsic tuff stained with limonite, but returned only trace gold.

YGC's 1993 diamond drilling intersected strongly altered volcanic rocks beneath a zone of hydrothermal alteration exposed in a surface trench. The 1994 drilling showed that mineralization in the South Zone consists of an extensive quartz-adularia stringer stockwork of low grade gold-silver values. The best intersections were 2.33 g/t gold and 4.1 g/t silver over 10.4 m. The South Zone mineralization appears to be connected with the Main Zone mineralization, but further drilling in between the two zones needs to be carried out to confirm this theory. The drilling in the Main Zone confirmed earlier reported grades. The best intersection was 1.69 g/t gold and 3.0 g/t silver over 24 m. In Oct/94 YGC calculated an open pit mineable reserve for the Main zone of 173 000 tonnes grading 12 g/t gold and 32.3 g/t silver.

The best results recorded in 1995 were returned from the Main Zone, where hole #181 intersected ore grade gold-silver bearing quartz-adularia vein stockwork mineralization. The hole drilled near the eastern end of the zone

returned 15.0 m assaying 7.63 g/t gold and 8.6 g/t silver. Other holes drilled on the Rat Creek Grid, Knoll Zone and in the contact area of a pyroclastic tuff and rhyolite flow dome located immediately east of Rat Creek returned anomalous gold values up to 633 ppb gold.

Twelve of the 1996 drill holes intersected significant gold mineralization in the Main Zone. The best result was recorded in hole GC-94-196 which returned 28.55 g/t gold over 17.0 m including 4.5 m grading 41.3 g/t and 6.59 m grading 41.95 g/t. The hole intersected thick banded quartz vein mineralization at the 795 m elevation which YGC believed represented a central core or feeder zone of the Main Zone deposit. The mineralization occurs within the phyllic alteration zone and is directly related to strong quartz-adularia alteration.

At the end of the 1996 drilling program YGC completed an updated resource estimate for the Main Zone. Employing a 1 g/t gold cutoff grade, a block model estimation calculated a total resource of 527 360 tonnes grading 5.27 g/t gold to the 710 metre level. Within this total resource the company estimated an open pit resource of 382 000 tonnes grading 5.08 g/t gold above the 750 metre elevation.

Samples from the 2000 sampling program were analyzed using Enzyme Leach technology, revealing several anomalous zones just south of and parallel to the Danger Creek Fault and although no report of this work was ever filed for assessment purposes geochemical anomaly maps produced from this sampling accompanied subsequent reports on the 2001 and 2002 drill programs. Drilling intersected altered and brecciated quartz feldspar porphyry, mixed sedimentary and volcanic lithologies and basalt. Samples of core from both years were submitted for analysis and generally returned values for gold below the detection limit of the analytical techniques employed, the highest reported value was 109 ppb gold over 0.6 m from sericitically altered quartz feldspar porphyry near the bottom of Hole #CGGC-8.

The 2003 and 2004 drilling of the Maverick enzyme leach anomaly B intersected mafic volcanic complex rocks but did not detect any significant gold values. The 2004 drilling program completed by Freegold Ventures indicated that the dominant vein trend is north.

Four diamond drill holes were collared on the Tarn zone in mid Mar/2005 before the IP survey was undertaken. The holes intersected intense phyllitic alteration associated with anomalous values in gold, silver, mercury and arsenic. The holes also intersected local fine quartz-adularia zones up to 40 m in length that yielded anomalous values up to 0.174 g/t gold and 2.3 g/t silver. (news release 10 May/2005). The second phase of drilling collared 1 diamond drill hole on the Tarn zone and 1 hole on the Rat Creek zone. Two other holes were abandoned in overburden.

The 2006 diamond drill holes were completed between January and early Mar/2006 and were an extension of the second phase of the 2005 drill program. The 2006 drill holes targeted IP anomalies on the Tarn zone. The single hole collared on the Tarn zone in late 2005 and the five 2006 drill holes all intersected favorable alteration and displayed evidence of hydrothermal activity similar to that found at the Main zone but did not intersect any economic intervals.

REFERENCES

ARCHER, CATHRO AND ASSOCIATES (1981) LTD, Nov/93. Assessment Report #093153 by R.W. Stroshein.

ARCHER, CATHRO AND ASSOCIATES (1981) LTD, Dec/93. Assessment Report #093154 by R.W. Stroshein.

ARGO DEVELOPMENT CORPORATION, May/88. Assessment Report #062293 by J.P. Sorbara.

CARLOS, A., Nov/92. Assessment Report #093055 by A. Carlos.

CARLOS, A., Jan/99. Assessment Report #093915 by A. Carlos.

CARLOS, A., Apr/2002. Assessment Report #094332 by A. Carlos.

CARLOS, A., Feb/2003. Assessment Report #094321 by A. Carlos.

CARLOS, A., Feb/2003. Assessment Report #094380 by A. Carlos and G.T. Hill.

CARLOS, A., Jan/2004. Assessment Report #094453 by A. Carlos.

CARLOS, A., Jan/2004. Assessment Report #094454 volume 1 by A. Carlos

CARLOS, A., Jan/2004. Assessment Report #094454 volume 2 by G.T. Hill.

CHRISTIE, A.R., DUKE, J. AND RUSHTON, R., 1989. Grew Creek Gold Deposit, Tintina Trench, Yukon. Poster presented at Whitehorse Geoscience Forum, 1989.

CHRISTIE, A.R., 1992. Grew Creek epithermal gold-silver deposit, Tintina Trench, Yukon. In: Yukon Geology, Vol. 3, p. 223-259.

DUKE, J.L., 1989. The Grew Creek Au-Ag Deposit in South-Central Yukon. In: The Gangue, Geological Association of Canada Newsletter No. 27, May/89.

DUKE, J.L., 1990. The Grew Creek Gold-Silver Deposit in South-Central Yukon Territory. In: Mineral Deposits of the Northern Canadian Cordillera, Yukon-Northeastern British Columbia, J.G. Abbott and R.J.W. Turner (eds), 8th IAGOD Symposium Field Trip No. 14 Guidebook, Geological Survey of Canada Open File 2169, p. 309-313.

EMERICK RESOURCES CORPORATION, 15 May/2008. Summary Geological Report on the Grew Creek Property, Yukon Territory, Canada. By R.Stroshein. (available on SEDAR).

EMERICK RESOURCES CORPORATION, News Release, 16 Jan/2008; 10 Nov/2009.

EZEE GOLDS LTD, Aug/87. Assessment Report #091733 by S.B. Cheeseman.

FREEGOLD VENTURES LTD, Jun/2006. Assessment Report #094694 Volune 1 by R. Stroshein.

FREEGOLD VENTURES LTD, Jun/2006. Assessment Report #094694 Volune 2 by P.Walcott.

FREEGOLD VENTURES LTD, Jan2007. Assessment Report #094749 by R. Stroshein.

FREEGOLD VENTURES LTD, News Release, 14 Jul/2004, 10 May/2005, 27 Sep/2005, 3 Nov/2005, 11 May/2006, 10 Apr/2007, 13 Nov/2007 (Consolidated Financial Statements).

GAYLORD MINES LTD, Feb/68. Assessment Report #017738 by P.E. Walcott.

GAYLORD MINES LTD, Nov/68. Assessment Report #018960 by P.E. Walcott.

GEOLOGICAL SURVEY OF CANADA, Memoir 208.

GEORGE CROSS NEWSLETTER, 8 Jan, 14 Apr, 26 May/88; 30 May, 4 Jul, 26 Sep, 7 Dec/89; 18 Feb/93; 14 Dec/93, 10 May/96, 11 Jun/96, 21 Jan/97.

GOLDNEV RESOURCES LTD, Nov/91. Assessment Report #092988 by L.R. Haynes.

GORDEY, S.P. and IRWIN, S.E.B., 1987. Geology, Sheldon Lake and Tay River map areas, Yukon Territory,

scale 1:250 000. Geological Survey of Canada, Map 19-1987.

GORDEY, S.P., 1990. Geology of Tenas Creek (105K/1), Swim Lakes (105K/2) and Faro (105K/3 map areas, Yukon Territory, scale 1:50 000. Energy Mines and Resources Canada, Geological Survey of Canada Open File 2249.

GORDEY, S.P. and MAKEPEACE, A.J., 2003. Yukon Digital Geology, version 2.0, S.P Gordey and A.J. Makepeace (comp); Geological Survey of Canada, Open File 1749 and Yukon Geological Survey, Open File 2003-9(D).

HUDSON BAY EXPLORATION AND DEVELOPMENT COMPANY LTD, Jun/84. Assessment Report #091543 by R. Stroshein.

HUDSON BAY EXPLORATION AND DEVELOPMENT COMPANY LTD, Dec/84. Assessment Report #091587 by R. Stroshein.

HUDSON BAY EXPLORATION AND DEVELOPMENT COMPANY LTD, Feb/85. Assessment Report #091611 by R. Stroshein.

HUDSON BAY EXPLORATION AND DEVELOPMENT COMPANY LTD, Jan/86. Assessment Report #091727 by T. Garagan.

HUDSON BAY EXPLORATION AND DEVELOPMENT COMPANY LTD, Nov/86. Assessment Report #091885 by R. Stroshein.

NORANDA EXPLORATION COMPANY LTD, Jan/88. Assessment Report #092002 by H. Copland.

NORANDA EXPLORATION COMPANY LTD, Feb/88. Assessment Report #092099 by H. Copland.

NORANDA EXPLORATION COMPANY LTD, Feb/88. Assessment Report #092106 by H. Copland.

NORANDA EXPLORATION COMPANY LTD, Jan/89. Assessment Report #092634 by J. Duke.

NORTHERN MINER, 18 Jan/88; 24 Feb/92, 20 May/96, 17 Jun/96.

ORCAN MINERAL ASSOCIATES LTD, Apr/92. Mining Resources of the Grew Creek Deposit. (Available in EMR Library, Whitehorse, Yukon).

PLOUFFE, A., 1989. Drift prospecting and till geochemistry in Tintina Trench, southeastern Yukon. Unpublished M.Sc. thesis, Carleton University, Ottawa, Ontario.

PRIDE, M.J., 1988. Bimodal volcanism along the Tintina Trench near Faro and Ross River: in Yukon Geology, Vol. 2; Exploration and Geological Services Division, Yukon, Indian and Northern Affairs Canada, p. 69-80.

WHEATON RIVER MINERALS LIMITED, Jun/92. Advanced Exploration Program Grew Creek Project. (Available in EMR Library, Whitehorse, Yukon).

YGC RESOURCES LTD, Dec/93. Assessment Report #093154 by R. Stroshein.

YGC RESOURCES LTD, Mar/95. Assessment Report #092239 by R. Stroshein.

YGC RESOURCES LTD, Jan/96. Assessment Report #093416 by R. Stroshein.

YGC RESOURCES LTD, Mar/97. Assessment Report #093627 by R. Stroshein.

YUKON EXPLORATION 1984, p. 109-111; 1985-86, p. 251-252; 1987, p. 182-183; 1988, p. 110-113.

YUKON EXPLORATION AND GEOLOGY 1983, p. 193; 1993, p. 7, 8; 1994, p. 5, 10, 12; 1995, p. 16, 18; 1996, p. 28, 30, 32; 2000, p. 22, 25; 2001, p. 18-19, 24, 25; 2002, p. 12-13,24, 26; 2003, p. 24-25; 2004, p. 14, 30, 33; 2005, p. 33, 38, 40.

APPENDIX 5

ACTIVE CLAIM LIST

Yukon
ergy, Mines and Resources

Claim Status Report

10 March 2010

	Claim Name and Nbr.	Grant No.	Expiry Date	Registered Owner	% Owned	NTS #'s
R	CANON 1 - 4	YC08793 - YC08796	2024/12/27	A.M. Carlos	100.00	105K02
R	CANON 5 - 6	YC08797 - YC08798	2028/12/27	A.M. Carlos	100.00	105K02
R	CANON 7 - 14	YC08939 - YC08946	2024/12/27	A.M. Carlos	100.00	105K02
R	CANON 15 - 24	YC30113 - YC30122	2017/12/27	A.M. Carlos	100.00	105K02
R	CANYON 1 - 16	YA75717 - YA75732	2035/12/27	A.M. Carlos	100.00	105K02
R	CANYON 17 - 26	YA75733 - YA75742	2033/12/27	A.M. Carlos	100.00	105K02
R	CANYON 27 - 32	YA75743 - YA75748	2035/12/27	A.M. Carlos	100.00	105K02
R	CANYON 33 - 40	YA75753 - YA75760	2035/12/27	A.M. Carlos	100.00	105K02
R	CANYON 41 - 50	YA81160 - YA81169	2035/12/27	A.M. Carlos	100.00	105K02
R	CANYON 51 - 56	YA81170 - YA81175	2036/12/27	A.M. Carlos	100.00	105K02
R	CANYON 57 - 60	YA81176 - YA81179	2032/12/27	A.M. Carlos	100.00	105K02
R	CANYON 61 - 62	YA81180 - YA81181	2031/12/27	A.M. Carlos	100.00	105K02
R	CANYON 63 - 66	YA81182 - YA81185	2027/12/27	A.M. Carlos	100.00	105K02
R	CANYON 73 - 78	YA81192 - YA81197	2035/12/27	A.M. Carlos	100.00	105K02
R	CANYON 79 - 84	YA81198 - YA81203	2036/12/27	A.M. Carlos	100.00	105K02
R	CANYON 85 - 88	YA81204 - YA81207	2032/12/27	A.M. Carlos	100.00	105K02
R	CANYON 89	YA81208	2027/12/27	A.M. Carlos	100.00	105K02
R	CANYON 90	YA81209	2031/12/27	A.M. Carlos	100.00	105K02
R	CANYON 91 - 92	YA81210 - YA81211	2027/12/27	A.M. Carlos	100.00	105K02
R	CANYON 93 - 94	YA81212 - YA81213	2026/12/27	A.M. Carlos	100.00	105K02
R	CANYON 293 - 300	YA85398 - YA85405	2030/12/27	A.M. Carlos	100.00	105K02
R	DOZER 1 - 14	YC18135 - YC18148	2013/12/27	A.M. Carlos	100.00	105K03
R	GRAND 91	YA85326	2024/12/27	A.M. Carlos	100.00	105K02
R	GRAND 92	YA85327	2025/12/27	A.M. Carlos	100.00	105K02
R	GRAND 93 - 98	YA85328 - YA85333	2028/12/27	A.M. Carlos	100.00	105K02
R	GRAND 141	YA85376	2025/12/27	A.M. Carlos	100.00	105K02
R	GRAND 142	YA85377	2024/12/27	A.M. Carlos	100.00	105K02
R	GRAND 143 - 148	YA85378 - YA85383	2028/12/27	A.M. Carlos	100.00	105K02
R	GRAND 159	YA85394	2024/12/27	A.M. Carlos	100.00	105K02
R	GRAND 160 - 162	YA85395 - YA85397	2028/12/27	A.M. Carlos	100.00	105K02
R	KAOLIN 1 - 3	YC18762 - YC18764	2017/12/27	A.M. Carlos	100.00	105K03
R	KAOLIN 4 - 10	YC19300 - YC19306	2016/12/27	A.M. Carlos	100.00	105K03
R	KAOLIN 11 - 12	YC19374 - YC19375	2016/12/27	A.M. Carlos	100.00	105K03
R	MAVERICK 1 - 12	YC19362 - YC19373	2022/12/27	A.M. Carlos	100.00	105K02
R	MAVERICK 13 - 16	YC26055 - YC26058	2018/12/27	A.M. Carlos	100.00	105K02
R	MAVERICK 17 - 23	YC26059 - YC26065	2019/12/27	A.M. Carlos	100.00	105K02
R	MAVERICK 24	YC26066	2018/12/27	A.M. Carlos	100.00	105K02

Total claims selected : 351

Left column indicator legend:

R - Indicates the claim is on one or more pending renewal(s).

P - Indicates the claim is pending.

Right column indicator legend:

L - Indicates the Quartz Lease.

F - Indicates Full Quartz fraction (25+ acres)

P - Indicates Partial Quartz fraction (<25 acres)

D - Indicates Placer Discovery

C - Indicates Placer Codiscovery

B - Indicates Placer Fraction

Yukon
Energy, Mines and Resources

Claim Status Report

10 March 2010

	Claim Name and Nbr.	Grant No.	Expiry Date	Registered Owner	% Owned	NTS #'s
R	MAVERICK 25 - 28	YC26067 - YC26070	2019/12/27	A.M. Carlos	100.00	105K02
R	MAVERICK 29	YC26071	2018/12/27	A.M. Carlos	100.00	105K02
R	MAVERICK 30 - 36	YC26072 - YC26078	2019/12/27	A.M. Carlos	100.00	105K02
R	MAVERICK 37 - 42	YC30101 - YC30106	2017/12/27	A.M. Carlos	100.00	105K02
R	MAVERICK 43 - 48	YC30107 - YC30112	2016/12/27	A.M. Carlos	100.00	105K02, 105K03
R	RAIL 51 - 54	YC37856 - YC37859	2018/12/27	A.M. Carlos	100.00	105K02
R	RAIL 56	YC37861	2018/12/27	A.M. Carlos	100.00	105K02
R	RAIL 58	YC37863	2018/12/27	A.M. Carlos	100.00	105K02
R	RAIL 61 - 70	YC37866 - YC37875	2018/12/27	A.M. Carlos	100.00	105K02
R	RAIL 73 - 74	YC37878 - YC37879	2018/12/27	A.M. Carlos	100.00	105K02
R	RAIL 75 - 115	YC37880 - YC37920	2014/12/27	A.M. Carlos	100.00	105K03
R	SLEEPER 1 - 10	YC29987 - YC29996	2019/12/27	A.M. Carlos	100.00	105F15
R	SLEEPER 11 - 24	YC53920 - YC53933	2015/12/27	A.M. Carlos	100.00	105F15
R	TINTINA 1 - 54	YC94562 - YC94615	2013/12/27	A.M. Carlos	100.00	105K03

Criteria(s) used for search:

CLAIM STATUS: ACTIVE & PENDING OWNER(S): CARLOS A.M. REGULATION TYPE: QUARTZ

Total claims selected : 351

Left column indicator legend:
- R - Indicates the claim is on one or more pending renewal(s).
- P - Indicates the claim is pending.

Right column indicator legend:
- L - Indicates the Quartz Lease
- F - Indicates Full Quartz fraction (25+ acres)
- P - Indicates Partial Quartz fraction (<25 acres)
- D - Indicates Placer Discovery
- C - Indicates Placer Codiscovery
- B - Indicates Placer Fraction

APPENDIX 6

STATEMENT OF QUALIFICATIONS

Statement of Qualifications

I, Shane A. Carlos of the city of Whitehorse, Yukon Territory, do hereby certify that:

1. I graduated from the Faculty of Science, University of British Columbia in 2009, with a Bachelor's degree in Earth and Ocean Sciences.

2. I have worked on the Grew Creek property for the past 10 summers, helping to carry out mineral exploration.

Signed,

Shane Allen Carlos

March 10, 2010.