

GEOLOCHEMICAL and GEOPHYSICAL ASSESSMENT REPORT ON THE ROAM PROJECT

Claims: Watson 1-6 (Y029789-Y029794), Watson 7-12 (Y029795-Y029800), Watson 13-36 (Y0119077-Y0119100), Watson 37 (Y0123887)

**Watson Lake, Liard River Area
Watson Lake Mining District, Yukon**

**NTS 105A/2
60°02'30" N Latitude, 128°38' W Longitude
6651297N + 522994E**

**for
Homegold Resources Ltd.
Unit 5 – 2330 Tyner Street,
Port Coquitlam, BC
V3C 2Z1**

**by
J. T. Shearer, M.Sc., P.Geo. (BC & Ontario)**

March 16, 2013

Work Completed between June 1, 2012 and October 30, 2012

Table of Contents

	page
SUMMARY	iii
INTRODUCTION	1
LOCATION and ACCESS	4
ENVIRONMENTAL LIABILITIES	4
PERMITS	4
ACCESS	5
CLIMATE	5
PHYSIOGRAPHY	5
HISTORY	6
REGIONAL GEOLOGY	7
REGIONAL GEOLOGICAL SETTING	9
PROPERTY GEOLOGY	12
DEPOSIT and MODEL CONSIDERATIONS	20
MINERALIZATION	24
PREVIOUS EXPLORATION in 2011	27
PREVIOUS DRILLING	29
GEOLOGICAL INVESTIGATIONS 2012	33
SOIL GEOCHEMISTRY 2012	34
GROUND GEOPHYSICS 2012	42
CONCLUSIONS and RECOMMENDATIONS	48
REFERENCES	51
APPENDICES	
Appendix I Statement of Qualifications, J. T. Shearer, M.Sc., P.Ge	52
Appendix II Statement of Costs	53
Appendix III Assay Certificates	54
Appendix IV Sample Descriptions	55
Appendix V Magnetometer Data	59

FIGURES

	<u>page</u>
1 PROPERTY LOCATION.....	v
2a CLAIM MAP	2
2b CLAIM MAP	3
3a. REGIONAL GEOLOGY	8
3b REGIONAL GEOLOGY.....	10
4a. SEDEX DEPOSIT MODEL	20
5a EAST ZONE – PLAN VIEW	25
5b TRAVERSE MAP	11
6 EAST ZONE – SCHEMATIC SECTION	26
7 DRILL HOLES 4 & 5 (Historical Data)	32
8 ROAM NORTH, MAP 1a.....	35
9 ROAM NORTH, MAP 2a.....	36
10 ROAM NORTH, MAP 3a.....	37
11 ROAM NORTH, MAP 4a.....	38
12 ROAM NORTH, MAP 5a.....	39
13 WEST GRID	40
14 MAIN GRID	41
15 ROAM WEST GRID.....	43
16 MAIN SHOWING.....	44
17 ROAM NORH GRID	45
18 ROAM NORTH, MAP 3a.....	46
19 ROAM NORTH, MAP 4a.....	47

TABLES

	<u>page</u>
1. ROAM - WATSON CLAIMS (Table I)	4
2. GRADE AND TONNAGES SEDEX DEPOSITS	21
3. SUMMARY of PREVIOUS DRILL RESULTS (Table III)	31

PHOTOS

1. MAIN & EAST ZONES (Photo 2).....	vi
2. MAIN ZONE (Photo 1)	13

SUMMARY

Homegold Resources Ltd. has retained J. T. Shearer, M.Sc., P.Geo. to complete an independent review of the Roam Project and document the fieldwork completed in 2012. The purpose of this technical report is to document the 2012 work, review the exploration potential of the Roam Project, and to provide recommendations for future work.

The claims are contiguous located on both sides of the Liard River, on the north side of the Yukon – British Columbia border, about 8 air km southeast of the town of Watson Lake, Yukon [Figure I]. The centre of the claim ground lies at 59°59'30" N. latitude, 128°37'45" W. longitude in 104P.098 in British Columbia.

The Main Showing is hosted by units of phyllite, sandstone with quartzite, and black shale. The showing is located on the south bank and consists of lenses of massive, very fine-grained galena and sphalerite, hosted in grey calcareous mudstones. The lenses are 20 cm wide, and exposed above the river for about 10 m in length. A typical assay from these lenses is 8.94 oz./ton Ag, 46.3% Pb, 22.6% Zn. About 100 m east, a zone of silicification at the contact between shales and quartzite contains patches of galena, sphalerite, and tetrahedrite. A channel sample across 0.6 m from this zone returned values of 9.1 oz/ton Ag, 0.2% Cu, 24.95% Pb, and 2.23% Zn. On the north shore opposite the Main Showing, a 15 m thick unit of chert and calcareous grit occur at a shale-sandstone interface. The grit contains rounded chert pebbles and elongate shale clasts in a sandy matrix. Quartz lenses and cross fractures in phyllite are mineralized with argentiferous galena and locally with tetrahedrite.

At the West Showing, zinc and lead sulphide mineralization occurs in a barite vein, oriented at 340°/85°W and with a true thickness of 2.25 metres. Localized, highly irregular patches and streaks of massive brown sphalerite, up to at least 5 cm and medium to coarse galena up to at least 4 cm occurs within the barite. A high grade sample of galena in barite (RW12) assayed 10.8% Pb, 44.2 g/T Ag, and 42.3% Ba. A piece of float containing sphalerite in massive barite assayed 5.80% Zn and 41.3% Ba. On the north side of the river, a boulder (RW20) of massive coarse crystalline galena and barite returned 70.20% Pb and 44.5 g/T Ag.

Five diamond drill holes totalling 748.0 metres (2454 ft.) were completed on the Roam Property during May and June of 1997. Holes 1, 2 & 3 were drilled to test geophysical anomalies along the west side of the Liard Canyon. Holes 4 and 5 were drilled on strike with a barite vein exposed on the south cliff face of the Liard River.

Anomalous Gold Values in soil were detected to the east of the 1997 drilling.


In the B.C. portion of the property mineralization of possible stratiform nature occurs at the Main Showing consisting of bands of lead-zinc sulphides in graphitic slate and silty limestone, which was previously mapped and described by Logan Mines in 1981. Billiton Canada also examined the showing in 1984 and suggested that the area may be close to a sedex vent or feeder zone due to the nature of the veining, alteration, metal ratios and massive, brecciated sulphides. Recent mapping by the B.C. Geological Survey (Ferri et al., 1997) on the opposite side of the river describes veins related to regional folding, but did not rule out the possibility that some of these veins represent a syn-sedimentary feeder system.

Further work on the property should include trenching to expose the zones intersected in Holes 4 and 5, where the overburden appears to be thin. Hole 4, which stopped short of the second and third zones of

mineralization intersected in the fifth hole, should also be deepened. South of the border, the broad gravity anomaly should be further delineated with a survey expanding the area covered by Samarkand's program.

The author and D. G. Cardinal, P.Geo., conducted a series of reconnaissance mapping surveys on the Roam-Watson claim group. Two different parts of the claim group were examined, the northern portion, which cover the 'Barite Zone, or 'West Zone' and the 'Main Zone' located further to the south, just across the Yukon-BC border, on the BC side. Both of these zones are well exposed along the steep banks of the Liard Canyon.

Respectfully submitted,

A handwritten signature in black ink, appearing to read 'J. T. Shearer', is written over a light gray rectangular background.

J. T. Shearer, M.Sc., P.Geo. (BC & Ontario)






Photo 2.
Looking up stream (north westerly) on the Liard River from the Alaska Highway approximately 10-11 km south of Watson Lake.

INTRODUCTION

Homegold Resources Ltd. has retained J. T. Shearer, M.Sc., P.Geo. to document the 2012 work and complete an independent review of the Roam Project. The purpose of this technical report is to document the 2012 work, review the exploration potential of the Roam Project, and to provide recommendations for future work.

Information used in the preparation of this report is listed in the section entitled "Item 27: References". Public information used in the preparation of this report includes maps and reports prepared by private geophysical consulting firms, government geologic surveys, assessment reports by private resource companies, and various academic publications.

Previously, a short field examination of the Roam Project by Homegold crew was completed in June and August 2011.


A 1997 five-hole diamond drill program totalling 748.0 metres (2,454 ft.) was completed on the Roam Property during May and June of 1997 by KRL Resources Corp. The purpose of this program was to investigate several geophysical anomalies outlined in a previous investigation and to test a barite showing. Prospecting and geological mapping was also conducted during this period, followed by a brief soil geochemistry survey in July west of the grid area. The property is considered prospective for sedex type zinc-lead-silver mineralization.

In 2012, the author and D. G. Cardinal, P.Geo., conducted a series of reconnaissance mapping surveys on the Roam-Watson claim group. Two different parts of the claim group were examined, the northern portion, which cover the 'Barite Zone, or 'West Zone' and the 'Main Zone' located further to the south, just across the Yukon-BC border, on the BC side. Both of these zones are well exposed along the steep banks of the Liard Canyon. In fact, it is quite likely that Dawson would have observed the characteristic iron-bleached alteration zones during his mapping expedition down the river in 1887.

A helicopter supported base camp was established near the centre of the 2 zones from which, a small exploration crew consisting of 2 experienced prospectors and 1 field assistant, conducted daily field surveys. The camp was conveniently located along a historical (1980-84) caterpillar constructed exploration trail that connects to both zones.

The author was able to easily examine both of the zones from camp, about 1-1.5 hour walk to either zone.

The claims are heavily vegetated with mixed stands of lodge pole pine, poplar and spruce and alder willow with undulating to flat lying (poor drainage) topography. There is essentially no bedrock outcrop on the property other than along the banks of the river. Unfortunately, access is limited to much of the outcrops due to steep and rugged nature of the cliff faces, some access to the bedrock was reached mainly along the river's edge to examine and sample some of the faces. A power boat or zodiac-type of water craft would be advantageous to properly examine the alteration and mineral zones in future exploration work.



ROAM CLAIM GROUP – BC-YUKON (Watson Lake)

Figure 2.




Figure 2b Claim Map

LOCATION and ACCESS

The claims are contiguous located on both sides of the Liard River, on the north side of the Yukon – British Columbia border, about 8 air km southeast of the town of Watson Lake, Yukon [Figure I]. The centre of the claim ground lies at 60°01'00" N. latitude, 128°37'45" W. longitude on mapsheet 105A/2 in the Watson Lake Mining District.

The Yukon portion of the Watson Property consists of 37 claims covering an area of approximately 2,167 hectares in the Watson Lake Mining District with the adjacent 4 claims in B.C. covering an area of 1,943.62 ha. The claims are listed below in Table I and illustrated in Figure 2.

TABLE I

Yukon Claims	
Claim Name	Tenure No.
Watson 1-6	YO29789-YO29794
Watson 7-12	YO29795-YO29800
Watson 13-36	YO119077-YO119100
Watson 37	YO123887

37 Claims @ 25 ha each = 925 ha

BC Claims (104P.098)		Size	Current Anniversary Date	Area (ha)	Registered Owner
Claim Name	Tenure No.				
Roam 1	843728	24 cells	April 18, 2018	388.57	J.T. Shearer
Roam 2	843730	24 cells	April 18, 2018	184.38	J.T. Shearer
Roam 3	843904	24 cells	April 18, 2018	129.56	J.T. Shearer
Roam 4	843906	1 cell	April 18, 2018	97.21	J.T. Shearer
				799.72 ha	

Total ha 1724.72

All the claims are owned 100% by J. T. Shearer

Environmental Liabilities

Presently, there are no known environmental liabilities. The Liard River cuts through the Property, and the majority of the historical exploration work was conducted adjacent to river without any environment impact. Any future work to be conducted would be carried out in approximately the same areas with no expected environmental concerns. The area is generally habited by black bear and ungulates, mainly deer and moose. The topography is relatively flat with the occasional swampy muskeg and small stream.

Permits

Presently, there are no permit applications in place. Any future exploration work such as drilling and ground disturbance (e.g. trenching, etc.), necessary exploration permits would need be applied for through the various Yukon and British Columbia government ministries.

Access

Several access options are available. Helicopter out of Watson Lake takes about 5 minutes, with a number of helicopter pads on the property. Road access is available by a 4x4 road from Upper Liard along the south side of the Liard River. The Alaska Highway passes through the northeast corner of the property. The claims can also be reached by boat from Upper Liard along the Liard River, which flows southeasterly through the property.

Climate

The climate is typical of northern continental regions, with long cold winters and short warm summers. Temperatures range from about -25° in January to +21° C in July. Total annual snowfall averages 219 cm. Field work is ideally carried out from May to October.

Physiography

The Property occurs on the western part of the Liard Plain, a physiographic division of the Interior Plateau, a broad, low lying and relatively flat region through which the Liard River flows. Elevations on the Property range from 600m to 710m. The steep walls of the Liard Canyon are exposed for a distance of 2.5 km on the east side of the property. The terrain is relatively flat with low sand and gravel terraces flanking the river. Much of the property is covered by glacial deposits of silt, sand and gravel up to 50 m thick, producing local eskers and kettles hummocky terrain. These deposits are classified as glaciofluvial and glaciolacustrine in origin, while the terraces adjacent the river are classified as modern alluvial terraces.

Vegetation is light to moderately dense, consisting of mainly lodgepole pine, spruce, poplar, cottonwood and underbrush of willow and ground cover labrador tea. In places, swampy muskeg and meadow areas occur.

The Property is mainly drained by the southeasterly-flowing Liard River as well as some minor tributaries.

The Property is strategically situated, a major transportation corridor – the Alaska Highway, runs along the eastern portion of the claims. Local resources including electrical power and a skilled labour force is readily available from the town of Watson Lake. Historically, the town has and continues to service various mining and exploration companies working in the regional area.

HISTORY

The following chronology is modified from Rainsford (1984) and Scott (1987). The earliest reference to exploration in the area was made by G.M. Dawson in 1886, who noted argentiferous galena in the lower Liard Canyon. More recent history includes:

- 1962: The Jim and Moose claims are staked by F. Lutz to cover 2 showings on the Liard River.
- 1965-75: Claims restaked several times under different names. Minor trenching in 1969, 1971 and 1973.
- 1979: Restaked as Roman 1-16 claims by Jake Melnychuck and optioned to St. Joseph Exploration. Geological mapping and geochemical soil sampling is performed in the Barite Showing area.
- 1980: Logan Mines optioned the property and diamond drilled 2 holes from one set-up totalling 123.1 m at the Barite Showing. A limited EM-16 survey was performed around the Main Showing.
- 1981: Logan Mines conducted 9.2 km of soil sampling and magnetic surveying in the Barite and Main Showing areas. Detailed geological mapping and sampling of showings are also performed.
- 1983: The Rom and Man claims in the Yukon and the Rom 2 and Vent 19 claims in British Columbia are staked adjacent to the original Roman 1-16 and Rom 50 claims.
- 1984: Billiton Canada Ltd. optioned the property and carried out 65 km of grid linecutting, IP, resistivity, VLF-EM, HLEM, magnetometer and gravity surveys over a major part of the property. A geochemical orientation survey was also completed.
- 1985: Access road from Lucky Lake on Alaska Highway to the West Showing constructed by J. Melnychuck.
- 1986: Samarkand Resources optioned the property and performed 46 km of line cutting, Genie EM (horizontal loop), VLF-EM and proton magnetometer surveying. Geological mapping and sampling are also conducted.
JM 1 & 2 claims staked by Melnychuck in British Columbia, to south of existing claim group.
- 1996: KRL Resources Corp. restakes the ground and performs airborne and ground geophysics, soil geochemistry, and minor prospecting. The Luck 1-10 and Lee 1-20 claims adjoining KRL's ground are optioned from Nu-Lite Industries. A program of follow-up backhoe trenching is conducted in the fall.
- 1997: Diamond drilling by KRL Resources totalling 748m (2,454 ft.) in 5 holes, plus trenching and soil sampling.

REGIONAL GEOLOGY

Regional mapping by H. Gabrielse of the McDame (1963) and Watson Lake (1967) map areas have identified predominantly Proterozoic to Mississippian marine sedimentary rocks with some Jurassic to Tertiary intrusions (Figure 3). The geology is not well understood due to the complex tectonic history of the region and the general lack of bedrock exposure in the broad drift covered plains.

The region lies within the Omineca tectonic belt of the Canadian Cordillera, to the east of the Tintina-Northern Rocky Mountain Trench. The tectonic assemblage compilation map by Wheeler and McFeely (1991) shows 3 different assemblages in the Watson Lake area:

- (1) Cassiar Terrane: Cambrian to Devonian passive continental margin sediments consisting of mainly dolomite, limestone, and shale deposited in platformal and basinal environments; includes the Kechika, Road River, Sandpile, Askin, and McDame Groups. The Cassiar Terrane is considered to be a displaced part of autochthonous North America.
- (2) Earn Group: Devonian to Mississippian fault trough clastic wedge consisting of chert pebble conglomerate, chert quartz sandstone, pebbly mudstone, shale and volcanics.
- (3) Slide Mountain Terrane: Devonian to Triassic oceanic marginal basin volcanics and sediments included in the Sylvester Group, which form a stack of fault-bounded slices emplaced eastward onto the Cassiar Terrane.

Proterozoic and Paleozoic basinal and platformal marine sedimentary rocks are important hosts of sedimentary exhalative lead-zinc-silver deposits worldwide and within the Canadian Cordillera. Some major producers include the Sullivan mine in southeast British Columbia and Faro in the Yukon. Other important occurrences include deposits of the Anvil, Howard's Pass and MacMillan Pass districts in the Yukon, and the Cirque deposit in northeast British Columbia (MacIntyre, 1991). All major sedex deposits known in the Cordillera occur in rocks of ancestral North America, hosted within intracratonic basins and miogeoclinal. The most economically important sedex deposits are found in the Selwyn and Purcell basins and in platformal sequences of the Cassiar Terrane and equivalents to the west.

The Earn Group is host to some of the largest sedex deposits including the Tom and Jason of the Macmillan Pass district and the Cirque of the Gataga district. The lower Earn is distinguished regionally by its blue weathering siliceous shale and chert and the upper Earn by mainly brown weathering shale (not highly siliceous) and common bedded chert (Gordy et al., 1982). Coarse clastics consisting of chert pebble conglomerate, quartz-chert sandstone, and conglomeratic mudstone are found in both Upper and Lower Earn groups. Bedded barite occurs within the siliceous shale facies of the lower and possibly upper Earn Group at MacMillan Pass, and sedex zinc-lead-silver-barite deposits occur within clastic facies of the lower Earn Group.

The Road River Group which underlies the Earn Group is also host to several mid- Ordovician to mid-Devonian deposits including Howard's Pass and the Aikie. Black graptolitic mudstone and chert of the Road River Group was deposited throughout the Selwyn Basin and Kechika Trough during mid to late Ordovician time in response to a major marine transgression.





Figure 3: Simplified geologic map of the study area. The southern part of the area, south of Horneline Creek, overlaps with the northern part of the 1995 field area (Ferri *et al.*, 1996a, b). Cross-section A-A' is shown as an inset at the top of the diagram. Please note that this structural section is not at the same scale as shown on the map.

REGIONAL GEOLOGICAL SETTING


The region lies within the Omineca tectonic belt of the Canadian Cordillera, to the east of the Tintina-Northern Rocky Mountain Trench. The tectonic assemblage compilation map by Wheeler and McFeely (1991) shows 3 different assemblages in the Watson Lake area (Figure 3a and 3b):

- (1) Cassiar Terrane: Cambrian to Devonian passive continental margin sediments consisting of mainly dolomite, limestone, and shale deposited in platformal and basinal environments; includes the Kechika, Road River, Sandpile, Askin, and McDame Groups. The Cassiar Terrane is considered to be a displaced part of autochthonous North America.
- (2) Earn Group: Devonian to Mississippian fault trough clastic wedge consisting of chert pebble conglomerate, chert quartz sandstone, pebbly mudstone, shale and volcanics.
- (3) Slide Mountain Terrane: Devonian to Triassic oceanic marginal basin volcanics and sediments included in the Sylvester Group, which form a stack of fault-bounded slices emplaced eastward onto the Cassiar Terrane.



REGIONAL GEOLOGY – WATSON LAKE AREA
(after GSC Terrane Map – Canadian Cordillera Map 1713A)

Figure 3b



Map shows areas (in red line) traversed and examined by the author with GPS survey points.

MS-02R – 149 ppm Ag/4.39% Pb/ 5.75% Zn
MS-04 – 361g/tonne Ag/3.88% Pb/2.70% Zn

Figure 5b

PROPERTY GEOLOGY

Bedrock exposure on the property is limited to shorelines and in the Liard Canyon, where beds of predominantly shale, argillite, slate, mudstone, and sandstone are well exposed along the steep canyon walls. Outcrops along the canyon on the BC side of the border were first mapped as Sylvester Group by Gabrielse (1963) and described as being similar to the limestone-quartzite-siltstone-slate sequence on the Alaska Highway. The same outcrop in the canyon on the adjoining mapsheet to the north was subsequently mapped by Gabrielse (1967) as Cambro-Ordovician dark grey and black, non-calcareous argillite, slate, and phyllite. Recent mapping by the B.C. Geological Survey has identified Devonian-Miss. age Earn Group strata in the Liard Canyon and an overlying chert unit of possible Miss.-Permian age (Ferri et al., 1997).

Previous mapping of the property geology was performed by T. Scott of Samarkand Resources in 1986, as well as detailed mapping of the Barite Showing by St. Joseph Explorations Ltd. in 1979 and the Main Showing just south of the border by Logan Mines Ltd. in 1981. Available reports on property geology are summarized from D.G. Mark (1988), V. Cukor (1981), and D. Rainsford (1984).

At the Barite Showing (also referred to as the West Showing) located in the north central part of the property, carbonaceous black shales with calcareous and siliceous beds, and minor carbonaceous sandstone units are present. A 2 m wide conformable barite lens and a 0.4 m wide cross-cutting barite vein are found in black shales on the south bank of the river. Isolated patches of base metal and silver mineralization is reported within the barite. As well, pyrite occurs as a bedded horizon in excess of 20 m thick within shales and in quartz-barite cemented breccia zones. On the north bank, numerous barite-quartz lenses and veins up to 20 cm wide are also found in black shales.

In the Liard Canyon, rocks are described as intercalated black shale and buff-weathering, phyllitic, grey calcareous mudstone. Half way along the canyon, mudstone with a distinctive ochre to brown weathering is present.

During the author's brief Property examination, evidence of ductile and brittle deformation (D1) structures were noted. Thin bedded phyllites, carbonaceous-calcareous shales and siltstones display predominately shallow (10-15 degrees) dip east, possibly reflecting recumbent folding (F1 & F2). This folding may also be reflecting simple monoclinial folding. More detail structural mapping would be needed to ascertain the types of folds and fault structures on the Property. A series of stacked, sooty-carbonaceous gouges and surface linear features indicate probable shallow east dipping local thrust faults along bedding planes.

Dominant schistosity (S1 & S2) is parallel to fold axis and bedding planes. Regional, lower greenschist facies metamorphism is evident in most rock types which would have manifested during and syn-deformational (D1) tectonic event.



Photo 1 Looking across the Liard River from the East Zone to the Main Zone

Barite Zone:

The Barite Zone is located along the north portion of the claim group and partly exposed along the south banks of the Liard Canyon. The author was able to examine the zone by traversing down a steep embankment and walking along the banks of the river. However only small section of the exposed rock face was accessible as the level of the river was still quite high.

The zone is dominantly hosted in intensely contorted, thrust fault-sheared, black-sooty, carbonaceous argillite, limy, flaggy phyllite and lesser shale. The carbonaceous sediments characteristically display sheen slickensides along planes of schistosity and are also characteristically cut by numerous quartz-calcite micro-veinlets sometimes associated with fine cubic pyrite salvages.

Photo 1 below shows typically exposed rock face and terrain along the river bank.



Looking downstream (easterly) with creamy coloured, bedded chert in fault-contact with intensely, sheared, carbonaceous argillite, phyllite and shale.

Mineralization: The barite zone exposed along the river bank is a northwesterly, steeply dipping zone about 3.0 metres wide. It consists of 1.5 m wide quart-silica-pyrite zone, which structurally underlies 1.5 m thick bed of creamy-white, sugary-textured barite. The barite invariably hosts fine irregular seams, blebs of galena and sphalerite. Several samples including a 1.5 m chip sample were collected from the barite zone (WZ-B01R to WZ-B03R).



Photo 2

'Barite Zone'
(GPS: 520489N – 6653301E)



Mineralized Barite (galena + malachite staining)

The bedded chert formation outlined in Photo 1 above (close-up Photo 3) may be part of the same horizon BC Geological Survey identified in the Liard Canyon as a Mississippian – Permian age chert unit. This may also be part of allochthonous Slide Mountain Terrane ocean floor.



Light green-creamy colour chert beds striking 353° dipping 45°-50° east.

Main Zone: Access and terrain to reach the Main Zone is very similar with challenge of mapping and sampling the steep rock faces. What is immediately noticeable at this zone is the high degree of alteration and bleached, iron oxidation compared to the Barite Zone. Both zones have very similar structural deformation, shearing and thrust faulting. The author did not observe any barite mineralization however, the zone hosts irregular large patches and structurally controlled seams of galena, silver mineral (argentite), sphalerite and minor chalcopyrite.

The Main Zone is hosted within a more clastic unit of altered fine grain sandstone and siltstone with minor interbeds of carbonaceous shales. The zone, in particular the sandstone unit, is highly silicified hosting a network of quartz veinlets.





Photo 5 (looking west-northwesterly) shows intense deformation with ductile shearing and stacked thrust faults.

Mineralization: Sulphide assemblage is galena (argentite), sphalerite dominate with minor chalcopyrite. The sulphides are hosted in irregular quartz veins with thin, fracture-controlled seams or veinlets of Pb-Zn (Photo 6 below) or sometimes in the form of irregular patches (Photo 7). Several selected grab samples were collected numbered: MS-01R to MS-04R. Sample M-02 assayed 149 g/Ag, 4.39% Pb and 5.65% Zn and also MS-04 assayed 361 g/Ag, 3.88% Pb and 2.70% Zn.



Deformation: The Barite and Main zones are hosted in fine (shale-argillite) to coarser (sandstone-siltstone) and limy (calcareous phyllite) basinal clastics deposited along the edge of the North American passive platform. This area was subjected to intense deformation. Initial deformation would have occurred during the docking and accretion of the Cache Creek-Quesnellia-Stikinia superterrane (Jurassic-Cretaceous) and, subsequently (Tertiary), directly impacted by the proximal (located just a few thousand metres to west of property) dextral tranpressional movement that formed the Tintina Fault. Evidence of poly-deformational phases can be observed along much of the Liard Canyon, which cuts into, and partly parallels the zone of deformation.




Calcareous argillite with tightly crinkled recumbent folds.

DEPOSIT and MODEL CONSIDERATIONS

The following model best fits the Roam property mineralization, based on the historical data and current field data the author has examined. The Roam mineralization occurs along the northern end of what is referred to as the Kechika basin. The basin is made of thick sedimentary sequences that reflect passive margin setting which is made of Cambrian, Lower Silurian and Upper Devonian strata, in addition to the Earn Group underlying the Property. The Kechika and Selwyn basins are host to several large deposits and numerous prospects listed in the Table 3 below. The Anvil camp alone hosts 5 deposits with a total tonnage of 120.9 million tonnes.

The passive margin-like sediments hosting the lead-zinc-silver mineralization as well as the barite found on the Property, suggests sedex environment much similar to the deposit model described below. The potential exists for discovering a massive, sedimentary-bedded Pb-Zn-Ag sulphide deposit on the Property.

Sedimentary Exhalative Deposits (SEDEX):



. Schematic representation of a typical sedimentary exhalative mineralizing system in Lower Paleozoic rocks of the Selwyn and Kechika basins. Modified from: Lydon (1996), MacIntyre (1991), Turner et al. (1989). Figure 4A.

TABLE 2
TYPICAL GRADE AND TONNAGES FOR PALEOZOIC SEDEX MASSIVE SULPHIDE DEPOSITS
WITHIN THE KECHIKA AND SELWYN BASINS

Age	Name	Size (million tonnes)	Zn (per cent)	Pb (per cent)	Cu (per cent)	Ag (grams per tonne)	Au (grams per tonne)
Cambro-Ordovician	Swim ¹	4.3	4.7	3.8		42	
Cambro-Ordovician	Grum ¹	30.8	4.9	3.1		49	
Cambro-Ordovician	Dy ¹	21.1	6.7	5.5	0.12	84	0.95
Cambro-Ordovician	Vangorda ¹	7.1	4.3	3.4		48	
Cambro-Ordovician	Faro ¹	57.6	4.7	3.4		36	
Early Silurian	Howards Pass District ²	425	5	2		9	
Late Devonian	Cirque	38.5	8	2.2		47.2	
Late Devonian	South Cirque	15.5	6.9	1.4		32	
Late Devonian	Driftvale Creek	2.4	11.9	3.1			
Late Devonian	Tom	15.7	7	4.6		49.1	
Late Devonian	Jason	15.5	6.6	7.1		79	
¹ Anvil District ² Anniv and XY Data from MacIntyre (1991), Lydon (1965), Goodfellow and Jonsson (1986)							

“Sedimentary exhalative” (sedex) deposits as the name implies, these deposits are believed to have formed in a sedimentary sequence by the exhalation of hot, metalliferous brines along fissures on the seafloor, resulting in precipitation of ore and gangue minerals.

The principal ore minerals are sphalerite and galena (containing silver) which are found with varying amounts of pyrite, barite, pyrrhotite and clastic sedimentary gangue minerals. Copper is rarely present and only in very minor amounts. The deposits are lensoidal and, where it can be recognized, sit above a mineralized stockwork system believed to represent the underground conduits that fed metal-bearing fluids to surface vents (Figure 4).

Some of the key characteristics of sedex deposits:

Settings of Sedex Deposits

- Thick to very thick sequences (5-15km) of continental derived clastics that are considered indicative of either intracontinental rifts or passive continental margins.
- Basins form as either fault-controlled embayments in continental margins, or as intracratonic rift basins.
- Sedimentary rocks include black shales, siltstones, carbonates, and turbidites.
- Deposits lie mostly close to remnants of basinal structures.
- Stacked lens aspect of many sediment-hosted lead-zinc deposits reflects the episodic nature of earthquake-related basin dewatering events.
- Question of water-depth during formation of sedex deposits is controversial.
 - Stromatolites + evaporates suggests shallow water depths.
 - Delicate banding in some ores indicates tranquil bottom conditions associated with deeper marine environments.

Mineralization

- Multiple stacked lenses of pyrite-galena-sphalerite ore.
- Majority contain economically important amounts of silver; without exception they contain little or no copper or gold.
- Lateral extent of mineralization is considerable in the larger deposits and ore zones can extend for several km.
- Conformable mineralization occurs over vertical interval of up to 650m (e.g. Sullivan and Faro mines).
- In such cases shale beds are interlayered with massive or semi-massive sulphides.

(cont.)

- Slow mineralization, several millions of years.
- Ores are fine-grained; deformation, both syndepositional and post-lithification, produced in some deposits spectacular fold and flowage structures.
- Certain sedex deposits have significant amounts of barite associated with the ore.
 - However, certain deposits such as the Sullivan is nearly barite free.
- Ore exhibits zonation of metals in either lateral or vertical directions or both.
 - Sullivan mine, lateral zonation with increasing Zn/Pb ratios towards the margins of orebodies.

MINERALIZATION

The Main Showing is hosted by units of phyllite, sandstone with quartzite, and black shale have been described. The showing is located on the south bank and consists of lenses of massive, very fine-grained galena and sphalerite, hosted in grey calcareous mudstones. The lenses are 20 cm wide, and exposed above the river for about 10 m in length. A typical assay from these lenses is 8.94 oz./ton Ag, 46.3% Pb, 22.6% Zn. About 100 m east, a zone of silicification at the contact between shales and quartzite contains patches of galena, sphalerite, and tetrahedrite. A channel sample across 0.6 m from this zone returned values of 9.1 oz/ton Ag, 0.2% Cu, 24.95% Pb, and 2.23% Zn. On the north shore opposite the Main Showing, a 15 m thick unit of chert and calcareous grit occur at a shale-sandstone interface. The grit contains rounded chert pebbles and elongate shale clasts in a sandy matrix. Quartz lenses and cross fractures in phyllite are mineralized with argentiferous galena, locally with tetrahedrite.

Mineralization observed elsewhere on the property include traces of galena, sphalerite, chalcopyrite and tetrahedrite, associated with narrow quartz veins and quartz stockwork. These veins generally strike east to northeast and dip steeply, or are concordant with bedding.

A zone of intense, upright folding is coincident with the Liard River canyon. These folds are described as trending south-southeast and plunging gently north. Bedding is generally steep and parallels the canyon walls. West of the canyon, beds dip gently to steeply southwest. Normal faults with minor displacements were observed, as well as some intense fracturing.

Minor intrusive rocks on the property include andesitic dykes, 1 to 5 m wide, striking sub-parallel to the shales at the west end of the Liard Canyon.




Figure 5a East Zone – Plan View




Figure 6 East Zone – Schematic Section

PREVIOUS EXPLORATION in 2011

The author and D. G. Cardinal, P.Geo., examined and briefly surveyed an eastern portion of the Roam-Watson mineral claims (BC side) in 2011. The reconnaissance surveys consisted of preliminary mapping and sampling.

The surveys were conducted along the eastern banks of the Liard River and across from a mineralized zone referred to in assessment reports as the 'Main Zone' (Figure 2). Both the Main and Barite zones are presently not accessible due to poor road conditions, which will require some brushing and rehabbing in order to access these sites.

A short grid with a base line extending for 200 meters, with cross lines every 50 meters was laid out in order to conduct some preliminary mapping and sampling control. Previous (1980s-90s) work is evident in this area with an old road that leads from the Alaska Highway (Figure 1), a distance of about 2.5 km. A trench and open-cuts are visible and were mapped to the grid.

Surveys were conducted at a scale of 1:1000 with rock outcrops, roads and approximate position of the Liard River plotted on to the grid map (Figure 3). Several weakly mineralized quartz veins hosted in siliceous phyllite rocks were encountered during the mapping, here in referred to as the 'East Zone'.

Rocks underlying the East Zone comprise of 2 main rock types: (i) phyllites and shales which include – characteristically orange weathered phyllite, siliceous phyllite; flaggy, thin-bedded shaley limestone, calcareous shale, black sooty-silty shale and occasional round-shaped stromatolite-like fossils and; (ii) grey, brittle, fine grain, quartzite and carbonaceous quartzite.

Structurally, the sedimentary rocks noted above appear to represent a recumbent fold this is supported by the characteristically shallow dipping nature of the bedding, ranging between 10-15 degrees north easterly. The phyllite unit has experienced ductile deformation while the quartzite and unit has gone brittle deformation and displays numerous quartz unmineralized veinlets. Carbonaceous fault gouge and surface expression of structural features suggest stacked thrust fault slices along recumbent fold limbs of the sedimentary rocks (Figures 3 & 4).

The orange weathered phyllite and iron oxidized shales host cross-cutting, weakly mineral-bearing quartz veins which carry sporadic patches of malachite staining and occasional fine grain galena and tetrahedrite. The largest vein is up to 0.5 meters wide and is traceable for at least 75 meters striking northerly (Figure 3). A second type of vein system was noted along the river bank escarpment. This vein tends to be massive and iron stained and appears to carry only minor pyrite. No other sulphides were noted during the cursory examination of this vein.

Directly across (west side) of the river is the Main Zone (Photo 1). The East and Main zones are related and are of the same alteration and structural controlled mineral system. These 2 zones also appear to be stratabound related, and suggest to be hosted a long more favourable sulphide-bearing horizon.

Limited additional mapping was conducted along the Alaska Highway, along the eastern portion of the claim group and just south of the town of Watson Lake. A small outcrop about 15m by 15m was noted about 4 km south of the town on the north side of the highway. It is composed of mafic to ultramafic greenstone with weak listwanitic alteration. This may be part of a fault slice of Slide Mountain terrane. About 2 kilometers further, cut the highway, is a large section exposing thinly bedded, orange coloured

cherty phyllite and black argillite, shale and shaley limestone. A photo was taken (Photo 2) from this point on the highway, looking up stream to the Main and East zones.

PREVIOUS DRILLING

1997 DRILL PROGRAM

Five diamond drill holes totalling 748.0 metres (2454 ft.) were completed on the Watson Property during May and June of 1997. Holes 1, 2 & 3 were drilled to test geophysical anomalies along the west side of the Liard Canyon. Holes 4 and 5 were drilled on strike with a barite vein exposed on the south cliff face of the Liard River.

The dominant rock type intersected in the holes are bedded sequences of dolomitic slates, siltstone, and argillite with lesser sandstone. Sulphide mineralization consists of minor sphalerite and galena mainly within veins and as recrystallized grains in surrounding rocks. Minor disseminated pyrite is also common in all holes within veins and hostrock, and as fine laminations in hole 5.

The drill core was sampled at intermittent intervals, with continuous sampling only within mineralized zones. The standard sample length was approximately 1.5 metres. Samples were split and bagged on site, and taken to Eco-Tech Labs in Kamloops, B.C. for analysis. A multielement ICP analysis was performed on all samples with selected samples also analyzed for gold by fire assay/AA finish and total barium. The remainder of the core was stored in racks at the southern end of the Watson 25 claim.

A summary of observations from each drill hole follows:

Hole KW97-1

This hole was abandoned at 45.1 metres in a gravel-filled channel. The hole was targeted at an airborne magnetic high anomaly, adjacent to a soil geochemical gold anomaly on the Watson 29 claim.

Holes KW97-2 & 3

These holes were drilled 200 metres apart on the Lee 7 & 9 claims (optioned from Nu-Lite Industries Ltd.), along strike of a coincident magnetic and VLF-EM anomaly. Bedding is folded, which is consistent with observations in the canyon outcrops where intense upright folds occur. A major zone of irregular quartz-carbonate veining was intersected over the entire length of the holes, with intervals up to 60 metres of 15-25% veining, and individual veins up to 1.5 metres core length. These veins are mainly concordant with bedding. Minor sphalerite occurs locally as recrystallized grains in dolomitic veins and beds. The source of the VLF-EM conductor intersected by Hole 2 appears to be a carbonaceous dolomitic siltstone unit from 80.8 - 92.1 metres with abundant graphitic gougy intervals, including a 1.3 metre interval of 90% graphite. The lower part of both holes intersected a metamorphosed argillite/siltstone unit displaying weak magnetism, which is likely the source of the high magnetic anomaly.

Hole KW97-4

Hole 4 was drilled on strike with the Barite Showing exposed on the south side of the Liard River. The hole is located on the Watson 17 claim, about 1 km west of the first three holes. The dominant lithologies encountered here are slate, phyllite, argillite, siltstone and lesser sandstone. The upper 25 m of this hole was highly sheared and broken, underlain by shale which grades into slate. At 36.7 m, one metre of barite was intersected, including 0.5 m of massive barite with about 10% sphalerite in stringy patches and coarse crystalline clots up to 3cm by 1.5 cm. The best assay returned 4.04% Zn from a 20 cm sample of this

mineralization. Minor galena is also present as fine disseminations and patches in the barite and within the silicified, pyritic wall rock. The enclosing black slate contains pyrite laminations and minor sphalerite in quartz veinlets. Forty metres below the barite, a clastic (sandstone?) unit containing bluish quartz grains and sulphide clasts was intersected over 3.4 m.

Fourteen samples were analyzed from this hole, representing 15% of the total length of core drilled. Values in zinc range from 29 ppm to 4.04% Zn, with 4 samples from 100-300 ppm, 6 samples from 300-700 ppm, and 3 samples above 700 ppm.

Hole KW97-5

Hole 5 was completed as a 200 metre step-out, on strike with Hole 4 to the south. Three zones of interest were intersected in this hole. The barite zone intersected in Hole 4 was projected to occur at an interval of 20.7 to 37.7 metres in this hole, where only 30% of the core was recovered. White staining on fractures may be due to secondary zinc minerals, although no visible sphalerite or barite was recovered. The second zone of interest occurs from 142.6 - 147.7 metres, where sandstone has been silicified and intensely quartz-veined and brecciated. Local seams and coarse-grained patches of sphalerite and galena, as well as trace chalcopyrite occur in this unit. The last 0.5 m of this interval is semi-massive pyrite. Several very thin, altered pyritic quartz porphyritic dykes were also intersected in this zone. A third mineralized interval, from 229.8 - 230.7 m, contains several percent sphalerite in a pyritic breccia of probable hydrothermal origin. The enclosing black slate contains minor sphalerite and galena in quartz veins as well as a broad zone with white staining on fractures. Thin beds of pyritic sandstone similar to that in Hole 4 were intersected at 74 m and 235 m. Fine-grained pyrite laminations in argillite, including beds up to 1.5 cm thick, first appears at 92m.

A total of 78 core samples were analyzed, representing 36% of the total length of core drilled. Twenty-one samples were in the range of 100-300 ppm Zn, 12 samples from 300-700 ppm, and 13 samples were above 700 ppm Zn. Elevated zinc values are associated with samples containing abundant quartz veining and in many of the intervals where white staining was noted.

Table III: Summary Drill Results

Hole Number	Grid Co-ord. Bearing/Dip	Total Length (m)	Interval (m)	Width (m)	Zn (ppm)	Pb (ppm)
KW97-1	3750N, 5350E 090°/-45°	44.5				
KW97-2	4600N, 5325E 090°/-45°	159.7	116.3-116.8	0.5	4976	
KW97-3	4800N, 5360E 090°/-45°	181.4				
KW97-4	4560N, 4340E 080°/-45°	106.7	35.6 – 36.7 36.7 – 38.7 includes: 36.9 – 37.1 37.1 – 37.7	1.1 2.0 0.2 0.6	5071 4.04% 2840	2394 1250 488
KW97-5	4335N, 4375E 062°/-45°	255.1	10.7 – 11.9 25.3 – 32.7 29.2 – 32.3 59.9 – 60.6 122.8 – 123.9 139.4 – 141.4 145.6 – 146.8 149.6 – 150.2 182.9 – 192.9 191.7 – 192.9 208.0 – 214.0 217.0 – 220.0 222.2 – 232.3 222.2 – 226.2 229.8 – 230.7	1.2 7.0 3.1 0.7 1.1 2.0 1.2 0.6 10.0 1.2 6.0 3.0 10.1 4.0 0.9	390 668 1369 987 2763 2271 3832 4552 314 426 454 1003 2803 2.67%	1234 1270 308




Figure 7 Drill Holes 4 & 5 (Historical Data)

GEOLOGICAL INVESTIGATIONS 2012

Several days were spent prospecting and mapping outcrops along the Liard River and particularly around the Main and Barite Showings.

In the area of the Main Showing south of the border, sphalerite and galena occurs along a fault contact between graphitic argillite and an overlying black chert unit. This fault zone, which strikes 090° and dips 35°S., is exposed along an old trench about 80 ft. above the south bank of the river. A chip sample across 1 metre true thickness (RW7A) returned 3.06% Zn and 3.08% Pb, and a selected high grade sample (RW6) produced 7.98% Zn and 5.53% Pb. A sample of pale yellowish-green stain (RW5) which covers large areas of outcrop in the area returned elevated values of 385 ppm Zn, 760 ppm As, and >10% Fe.

Examination of outcrops along the bluffs at the north end of the grid located sandstone containing fine disseminated pyrite with elevated values of 236 ppm Zn and 512 ppm Pb. A chip sample of argillite at the contact with the tuff returned 1159 ppm Zn. Barite veinlets were also noted to occur in sandstone/quartzite.

At the West Showing, zinc and lead sulphide mineralization occurs in a barite vein, oriented at 340°/85°W and with a true thickness of 2.25 metres. Localized, highly irregular patches and streaks of massive brown sphalerite, up to at least 5 cm and medium to coarse galena up to at least 4 cm occurs within the barite. A high grade sample of galena in barite (RW12) assayed 10.8% Pb, 44.2 g/T Ag, and 42.3% Ba. A piece of float containing sphalerite in massive barite assayed 5.80% Zn and 41.3% Ba. On the north side of the river, a boulder (RW20) of massive coarse crystalline galena and barite returned 70.20% Pb and 44.5 g/T Ag.

SOIL GEOCHEMISTRY 2012

A previous reconnaissance soil geochemical survey was undertaken in July of 1997 in the southwestern claim area. A 7.5 km grid consisting of three northwest trending lines, spaced 200 m apart was established in the southwestern claim area. A total of 148 soil samples were collected at 50 m intervals. The grid is located to the east of an aeromagnetic high anomaly. This anomaly is approximately 800 m wide by 2,200m long and may represent an intrusive source.


Samples were collected from the "B" horizon by digging a hole with a grub-hoe or round nosed shovel. The soils were placed in a kraft sample bag, and numbered with the grid coordinate location of the sample. The samples were dried before shipping to Acme Analytical Laboratories Ltd. in Vancouver, B.C. for analysis. A 30-element ICP analysis was conducted on all soil samples.

Values in base metals are generally low, with the exception of a few isolated zinc anomalies (Figure 5). Lead values range from <3 to 14 ppm (avg. 7 ppm), zinc from 3 to 158 ppm (avg. 64 ppm), and copper from 2 to 16 (avg. 7 ppm). Silver values are all below detection limit of 0.3 ppm, except for one value at 1.2 ppm. There does not appear to be any correlation between values.

In 2012 soils samples were collected on the following grids:

- a) Roam North Map 1a, Figure 8
- b) Roam North Map 2a, Figure 9
- c) Roam North Map 3a, Figure 10
- d) Roam North Map 4a, Figure 11
- e) Roam North Map 5a, Figure 12
- f) West Grid, Figure 13
- g) Main Grid, Figure 14

The soil results are plotted on Figures 8 to 14, on 2 grids the samples were not assayed. Results are contained in Appendix III.






Figure 10 Roam North Map 3a




Figure 11 Roam North Map 4a

Figure 12 Roam North Map 5a





Figure 13 West Grid






Figure 14 Main Grid

GROUND GEOPHYSICS 2012

Several grids were ground surveyed with a Sharpe MF Fluxgate Magnetometer Serial #7032709. Readings were collected at 15m interval. Loops were completed throughout the survey period to calculate a diurnal correction (refer to Appendix IV).

The grids completed are:

- (1) Roam West Grid, Figure 15
- (2) Main Showing, Figure 16
- (3) Roam North Grid (baseline 0+00 is at 220°), Figure 17
- (4) Roam North 3A, Figure 18
- (5) Roam North 4A, Figure 19

On both the Roam West Grid and Main Showing Grid all readings were 2700 gammas and as a result the magnetic pattern is flat and featureless.

The Roam North Grid, 3A Grid and 4A Grid – the only change in magnetic readings is a drop of 50 gammas to the east end of the grid.

Figure 15 Roam West Grid





Figure 17 Roam North Grid






Figure 18 Roam North Map 3a

CONCLUSIONS and RECOMMENDATIONS

The sedimentary rock unit mapped, characteristically displays passive margin-like setting and is probably part of an assemblage that makes up the Sylvester Group of the thrust-faulted Cassiar platform terrane. The rocks underlying the property are conducive to hosting Sedex mineralization.

The Barite, Main and East zones appear to occur along the same stratigraphic horizon. Although, based on preliminary observations, the East zone hosts epigenetic type quartz mineralization, the phyllitic host rocks do carry fine pyrite mineralization that may suggest some relation to a possible distal, exhalite-syngenetic type environment.

Both structural and stratigraphic mapping of these zones is recommended, in order to interpret their relationship and structural positions, which could be used as a guide to vectoring towards and possibly defining potential Sedex-type massive sulphide mineralization.

Although the drilling on the Roam Project did not intersect stratiform zinc-lead mineralization, there are several indications of an exhalative environment and the potential for nearby sulphide accumulations. Holes 2 and 3 tested coincident airborne and ground geophysical anomalies which are concluded to result from graphitic horizons producing the VLF-EM response and a deeper metamorphosed unit which generated the magnetic high anomaly. The intense quartz carbonate veining found in these two holes and the minor zinc occurrences in the veins suggests a remobilization of sulphides during the folding of the strata. Holes 4 and 5, drilled on strike of the Barite Showing provide further indications of the presence of minerals associated with a sedimentary exhalative environment. Hole 4 intersected sphalerite and galena within the barite vein and within quartz veins and patches in the surrounding slates. Most of the samples from this hole also contained high background levels of zinc in the slate (several hundred ppm). Similarly, hole 5 intersected zinc and lesser galena in several different lithologies, including hydrothermally brecciated sandstone, an andesitic dyke, and a pyritic breccia with about 10% sphalerite. Several large intervals of slate with coatings of possible zinc bloom also produced elevated zinc values of several hundred ppm. Bedded fine-grained pyrite was found in much of the argillite, including locally minor semi-massive pyrite up to 3 cm thick.

Geological mapping and prospecting in the bluffs along the Liard River provided some additional hints to the nature of the geology and mineralization in the property. Outcrops on the south side of the river include units of sandstone and slate with elevated zinc and lead, and veinlets of barite in sandstone. Historical high grade samples from the Barite Showing returned several percent zinc and lead. On the north side of the river across from the showing, a thick unit (> 20m) of fine-grained bedded pyrite in carbonaceous shales was examined, and has been previously described by Scott, 1987. The presence of such mineralization is indicative of restricted basinal conditions which are favourable for sedex deposits. A high-grade boulder of coarse crystalline galena in barite found nearby may have originated from the till above the cliffs, as previous work by St. Joseph's in 1979 recognized basal till ferricrete with barite boulders in this area.

In the B.C. portion of the property mineralization of possible stratiform nature occurs at the Main Showing consisting of bands of lead-zinc sulphides in graphitic slate and silty limestone, which was previously mapped and described by Logan Mines in 1981. Billiton Canada also examined the showing in 1984 and suggested that the area may be close to a sedex vent or feeder zone due to the nature of the veining, alteration, metal ratios and massive, brecciated sulphides. Recent mapping by the B.C. Geological Survey

(Ferri et al., 1997) on the opposite side of the river describes veins related to regional folding, but did not rule out the possibility that some of these veins represent a syn-sedimentary feeder system.

Extensive geophysical surveys by Billiton in 1984 indicated a broad zone of coincident VLF-EM, horizontal loop EM, induced polarization, and resistivity low anomalies from at least the north end of the river extending south across the border over a width of about 700 m. A gravity survey indicated two small anomalies on the southernmost end of the grid, but a subsequent survey by Samarkand Resources in 1987 detected a broader, more subtle anomaly. The discrepancies are due to the use of a different terrain correction factor. It was concluded that the anomaly may consist of one gravity anomaly up to 2 milligals in strength which increases to the north, and may be due to a deep source.

Further work on the property should include trenching to expose the zones intersected in Holes 4 and 5, where the overburden appears to be thin. Hole 4, which stopped short of the second and third zones of mineralization intersected in the fifth hole, should also be deepened. South of the border, the broad gravity anomaly should be further delineated with a survey expanding the area covered by Samarkand's program.

Based on the author's recent Property examination combined with historical exploration data, the Property merits a follow-up exploration program as outlined below.

Discussion

The Barite and Main zones appear to occur in 2 different lithological, clastic sequences. The Barite zone displays a stratabound-type barite bed, carrying irregular patches and seams of Pb-Zn hosted in fine grain, carbonaceous shale-argillite unit. The Main zone is hosted in coarser clastic, sandstone-siltstone unit.

The sulphide assemblage in both zones are the same and are structurally controlled epigenetic veins, and suggest to have formed during the same mineralizing event. The Main zone hosts abundant mineral-free quartz veinlets however, other larger, irregular quartz veins tend to host the mineralization and may be syn-post dextral, transpressional movement.

In conclusion, the barite horizon, along with the Pb-Zn epigenetic veinlets, is suggestive of a partly remobilized and dismembered and mineralized sedimentary exhalative environment. More work would have to be conducted to unravel the structural complexity of this area.

Estimated Cost of the Recommended First-phase Exploration Program

Item	Costs	Accumulated Cost
Wages Senior Geologist & Project Manager, 25 days @ \$700/day 2 Geologists; 25 days #@ \$650/day each, including fieldwork, data manipulation and reporting 2 Sampling-technicians; 25 days @ \$300/day	\$ 17,500 \$ 32,500 \$ 15,000	\$ 65,000
Transport: 2 1-ton 4x4 pickup trucks, 25 days each 1 all-terrain vehicle (Quad); 25 days Gasoline and camp fuel Boat from Watson Lake	\$ 3,000 \$ 4,000 \$ 800 \$ 2,000	\$ 8,800
Camp & Crew Costs Accommodation, 100 man days @ \$50/man day Hotel; 20 man nights Camp Food; 100 man days @ \$30/man day Meals in transit; 10 man days @ \$50	\$ 5,000 \$ 1,000 \$ 3,000 \$ 500	\$ 9,500
Communications Costs: Satellite Phone Rental; 3 weeks 2 FM truck radios; 1 month	\$ 1,000 \$ 500	\$ 1,500
Sample Analysis 60 rocks analyzed by ICP @ \$30/sample 40 rocks assayed by fire assay @ \$50/sample 600 Soils analyzed by ICP @ \$35/sample	\$ 2,100 \$ 2,200 \$ 21,000	\$ 25,300
Report Costs and Office Expenses: Program Management Digital Map Drafting Interpretation of Data & Compilation Physical and Electronic Assessment Report Production Costs	\$ 8,000 \$ 3,000 \$ 7,000 \$ 800	\$ 18,800
Environmental and Compliance Costs:	\$ 10,000	\$ 10,000
Subtotal		\$ 138,900
HST		\$ 16,668
Itemized Budget		\$ 155,568
Contingency; 10% of Itemized Budget		\$ 15,000
Total Estimated Cost		\$ 170,568

REFERENCES

- Cardinal, D. G. (2011): Technical Report on the Roam Project; for Homegold Resources Ltd. July 2, 2011
- CUKOR, V. (1980): Roman Claims, Report on Diamond Drill Program; for Logan Mines Ltd.; Yukon Assessment Report #9689; 8 p. -
- CUKOR, V. (1981): Geochemical and Geophysical Report, Roman Group for Logan Mines Ltd.; BC MEMPR Assessment Report #9855; 12p.
- FERRI, F., REES, C., NELSON, J. & LEGUN, A. (1997a): Geology of the Northern Kechika Trough; *in* Geological Fieldwork 1996, B.C Ministry of Employment and Investment, Paper 1997-1, pp.125-144.
- GABRIELSE, H. (1963): McDame Map-Area, Cassiar District, British Columbia; GSC Memoir 319; 138p.
- GABRIELSE, H. (1967): Watson Lake Geology, GSC Map 19-1966, scale 1:253,440
- GABRIELSE, H. and YORATH, C.J. (1992): Geology of the Cordilleran Orogen in Canada; Geological Survey of Canada.
- GORDEY, S.P., ABBOTT, J.G., ORCHARD, M.J. (1982): Devono-Mississippian (Earn Group) and younger strata in east-central Yukon; *in* Current Research, Part B, Geological Survey of Canada, Paper 82-1 6, p.93-100.
- KLASSEN, R.W. (1978): A unique stratigraphic record of late Tertiary-Quaternary events in southeastern Yukon; Canadian Journal of Earth Sciences, v.15, pp.1884-1886.
- KLASSEN, R.W. and MORISON, S.R. (1982): Watson Lake Surficial Geology, 1:250,000 scale; GSC Map 21-1981.
- MACINTYRE, D.G. (1991): Sedex- Sedimentary-Exhalative Deposits; *in* Ore Deposits, Tectonics and Metallogeny in the Canadian Cordillera; BC MEMPR Paper 1991 -4, pp.25-70.
- MARK, D.G. (1988): Geophysical Report on the Roman Property for Samarkand Resources; BC MEMPR Assessment Report #1 761 8; 56p.
- RAINSFORD, D.R.B (1984): Geophysical Report on Val, Roman 50, Rom I , Rom 2, Vent 19 Claims for Billiton Canada Ltd.; BC MEMPR Assessment Report #12731; 26p.
- SCOTT, T.C. (1987): Report on the Roman Property, Watson Lake Mining District, Yukon and Liard Mining Division, British Columbia; for Samarkand Resources Inc; Yukon Assessment Report #62273.
- SHEARER, J. T. (2012): Prospecting and Geological Assessment Report on the Roam Project, Watson Lake, Liard River Area, British Columbia: for Homegold Resources Ltd. January 29, 2012.
- WHEELER, J.O. and McFEELY, P. (1991): Tectonic assemblage map of the Canadian Cordillera and adjacent parts of the United States of America; Geological Survey of Canada, Map 1712A, scale 1 :2,000,000.

Appendix I

Statement of Qualifications


March 16, 2013

STATEMENT of QUALIFICATIONS

I, Johan T. Shearer of Unit 5 – 2330 Tyner Street, in the City of Port Coquitlam, in the Province of British Columbia, do hereby certify:

1. I graduated in Honours Geology (B.Sc., 1973) from the University of British Columbia and the University of London, Imperial College, (M.Sc. 1977).
2. I have practiced my profession as an Exploration Geologist continuously since graduation and have been employed by such mining companies as McIntyre Mines Ltd., J.C. Stephen Explorations Ltd., Carolin Mines Ltd. and TRM Engineering Ltd. I am presently employed by Homegold Resources Ltd.
3. I am a fellow of the Geological Association of Canada (Fellow No. F439). I am also a member of the Canadian Institute of Mining and Metallurgy, the Geological Society of London and the Mineralogical Association of Canada. I am a member in good standing of the Association of Professional Engineers and Geoscientists of British Columbia (P.Geo., Member Number 19,279).
4. I am an independent consulting geologist employed since December 1986 by Homegold Resources Ltd. At Unit #5 2330 Tyner Street, Port Coquitlam, British Columbia.
5. I am the author of the report entitled “Geochemical and Geophysical Assessment Report on the Roam Project” dated March 16, 2013.
6. I have visited the property between August 4 and 11, 2012 and supervised the crew in August, 2012. I have carried out mapping and sample collection and am familiar with the regional geology and geology of nearby properties. I have become familiar with the previous work conducted on the Roam Project by examining in detail the available reports and maps and have discussed previous work with persons knowledgeable of the area.

Dated at Port Coquitlam, British Columbia, this 16th day of March, 2013.



J.T. Shearer, M.Sc., P. Geo.

Appendix II

Statement of Costs

March 16, 2013

STATEMENT of COSTS
Roam Property 2013 – Yukon

Wages	Without HST
J.T. Shearer, M.Sc., P.Geo., Aug. 4-7, 2012, 3 days @ \$700/day	\$ 2,100.00
D. G. Cardinal, B.Sc., P.Geo. August 4-10, 2012, 5 days @ \$650/day	\$ 3,250.00
Subtotal	\$ 5,350.00
Expenses	
Transportation:	
Truck #1, fully equipped 4x4, 4 days @ \$120/day	480.00
Truck #2, Fully equipped 4x4, 6 days @ \$120/day	720.00
Fuel	430.00
Campground, 6 days @\$110/day	660.00
Food & Meals	825.00
Supplies	50.00
Helicopter	1,500.00
Denis Delisle, Wages, 5 days @ \$350/day, August 4-10, 2012	1,750.00
Eric MacKenzie, Wages, 5 days @ \$450/day, August 4-10, 2012	2,250.00
Chad Bucknell, Wages, 5 days @ \$300/day, August 4-10, 2012	1,500.00
Magnetometer Rental, 5 days @ \$50/day	250.00
Chainsaw Rental, 5 days @ \$20/day	100.00
Analytical, ALS Minerals	900.00
Report Preparation	1,400.00
Word Process and Reproduction,	300.00
Subtotal	\$ 13,115.00
Total	\$ 18,465.00

Filed \$15,000.00

Appendix III

Assay Certificates

March 16, 2013

CLIENT NAME: HOMEGOLD RESOURCES LTD.
UNIT# 5-2330 TYNER STREET
PORT COQUITLAM, BC V3C2Z1
(604) 696-1022

ATTENTION TO: JO SHEARER

PROJECT NO: ROAM

AGAT WORK ORDER: 12V620127

SOLID ANALYSIS REVIEWED BY: Kevin Motomura, ICP Supervisor

DATE REPORTED: Aug 09, 2012

PAGES (INCLUDING COVER): 9

Should you require any information regarding this analysis please contact your client services representative at (905) 501-9998

*NOTES



Certificate of Analysis

AGAT WORK ORDER: 12V620127

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Jul 13, 2012

DATE RECEIVED: Jul 12, 2012

DATE REPORTED: Aug 09, 2012

SAMPLE TYPE: Soil

Analyte:	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Ce	Co	Cr	Cu	Fe
Unit:	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%
RDL:	0.2	0.01	1	5	1	0.5	1	0.01	0.5	1	0.5	0.5	0.5	0.01
Sample Description														
R-N-1	<0.2	0.75	17	<5	395	<0.5	<1	6.35	<0.5	24	6.2	22.4	16.5	1.47
R-N-2	<0.2	0.84	20	<5	316	<0.5	1	4.69	<0.5	25	6.7	22.6	18.1	1.57
R-N-3	<0.2	0.83	18	<5	185	<0.5	2	1.77	<0.5	26	6.7	27.5	18.2	1.72
R-N-4	<0.2	0.98	21	<5	312	<0.5	2	4.96	0.5	26	7.6	27.5	25.0	1.82
R-N-5	<0.2	1.08	20	<5	288	0.5	2	3.59	<0.5	29	7.6	31.4	26.1	1.98
R-N-6	<0.2	0.89	21	<5	330	<0.5	2	6.47	0.5	27	6.6	25.7	19.8	1.61
R-N-7	<0.2	1.04	21	<5	400	<0.5	2	7.55	0.6	26	7.6	27.0	23.4	1.83
R-N-8	<0.2	1.09	19	<5	216	0.7	3	0.51	<0.5	33	9.0	35.4	27.4	2.27
R-N-9	<0.2	1.01	14	<5	199	0.6	2	0.24	<0.5	25	7.7	28.3	20.5	2.01
R-N-10	<0.2	1.00	20	<5	393	<0.5	2	5.26	<0.5	24	6.3	25.2	18.0	1.60
R-N-11	<0.2	0.77	17	<5	390	<0.5	1	6.02	<0.5	26	6.0	21.2	17.3	1.46
R-N-12	<0.2	1.11	13	<5	168	0.5	1	0.26	<0.5	34	6.9	30.7	15.8	2.12
R-N-13	<0.2	0.99	15	<5	189	0.5	2	0.24	0.5	33	6.7	28.1	14.2	1.95
R-N-14	<0.2	1.22	13	<5	213	0.6	1	0.26	<0.5	38	6.3	29.4	11.6	1.92
R-N-15	<0.2	1.16	17	<5	339	0.5	2	2.29	<0.5	31	7.7	31.3	23.4	2.11
R-N-16	<0.2	1.20	17	<5	439	<0.5	2	4.88	0.6	32	7.6	31.0	24.3	2.05
R-N-17	<0.2	0.34	13	<5	440	<0.5	2	0.62	2.1	12	3.8	11.2	12.2	1.13
R-N-18	<0.2	0.30	11	<5	411	<0.5	1	0.47	1.7	12	3.4	10.3	10.6	1.03
R-N-19	<0.2	0.57	12	<5	195	<0.5	2	0.89	0.5	30	4.9	16.1	10.4	1.27
R-N-20	<0.2	0.44	12	<5	178	<0.5	2	0.68	<0.5	25	3.9	15.1	7.3	1.10

Certified By:



Certificate of Analysis

AGAT WORK ORDER: 12V620127

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Jul 13, 2012

DATE RECEIVED: Jul 12, 2012

DATE REPORTED: Aug 09, 2012

SAMPLE TYPE: Soil

Analyte:	Ga	Hg	In	K	La	Li	Mg	Mn	Mo	Na	Ni	P	Pb	Rb
Unit:	ppm	ppm	ppm	%	ppm	ppm	%	ppm	ppm	%	ppm	ppm	ppm	ppm
RDL:	5	1	1	0.01	1	1	0.01	1	0.5	0.01	0.5	10	0.5	10
Sample Description														
R-N-1	<5	<1	2	0.06	12	10	1.03	366	2.0	0.02	20.7	647	7.9	19
R-N-2	<5	<1	<1	0.09	13	11	0.96	333	1.9	0.02	26.4	623	8.8	23
R-N-3	<5	<1	<1	0.10	13	8	0.51	279	1.5	0.01	29.1	525	8.9	18
R-N-4	<5	<1	1	0.13	15	10	0.71	348	2.0	0.02	34.0	611	10.0	27
R-N-5	<5	<1	2	0.13	15	10	0.65	375	2.2	0.01	35.6	656	11.4	29
R-N-6	<5	<1	<1	0.10	13	9	0.84	324	2.2	0.02	23.8	608	8.7	27
R-N-7	<5	<1	1	0.10	13	11	0.90	377	2.2	0.02	31.0	633	10.2	26
R-N-8	<5	<1	2	0.11	17	10	0.47	413	1.2	0.01	45.4	612	13.3	22
R-N-9	<5	<1	1	0.11	13	10	0.36	351	2.5	<0.01	35.0	524	11.2	19
R-N-10	<5	<1	1	0.10	12	11	0.57	312	2.8	0.01	31.0	460	9.5	27
R-N-11	<5	<1	<1	0.07	13	10	1.01	312	2.2	0.02	20.4	634	7.8	21
R-N-12	<5	<1	<1	0.12	16	11	0.37	269	1.1	0.01	31.8	496	10.8	24
R-N-13	<5	<1	2	0.12	15	10	0.34	371	2.3	0.01	32.3	480	10.2	22
R-N-14	5	<1	<1	0.11	19	13	0.36	221	<0.5	0.01	25.8	467	10.2	25
R-N-15	<5	<1	5	0.13	16	14	0.73	515	2.3	0.01	33.7	786	11.4	25
R-N-16	6	<1	<1	0.15	16	14	1.32	404	2.4	0.02	33.0	740	10.7	31
R-N-17	<5	<1	7	0.05	7	3	0.18	128	6.3	<0.01	26.4	632	27.4	<10
R-N-18	<5	<1	3	0.04	7	3	0.15	98	6.2	<0.01	23.0	573	26.7	<10
R-N-19	<5	<1	<1	0.06	15	8	0.35	259	2.1	0.01	20.3	609	6.8	12
R-N-20	<5	<1	<1	0.05	13	6	0.31	208	2.2	<0.01	17.3	561	5.8	<10

Certified By:



Certificate of Analysis

AGAT WORK ORDER: 12V620127

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Jul 13, 2012

DATE RECEIVED: Jul 12, 2012

DATE REPORTED: Aug 09, 2012

SAMPLE TYPE: Soil

Analyte:	S	Sb	Sc	Se	Sn	Sr	Ta	Te	Th	Ti	Tl	U	V	W
Unit:	%	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm
RDL:	0.005	1	0.5	10	5	0.5	10	10	5	0.01	5	5	0.5	1
Sample Description														
R-N-1	0.090	4	3.9	<10	<5	155	<10	<10	6	0.05	6	<5	31.1	<1
R-N-2	0.061	3	4.2	<10	<5	139	<10	<10	5	0.06	6	<5	34.3	<1
R-N-3	0.027	3	4.7	<10	<5	44.9	<10	<10	<5	0.06	6	<5	36.6	<1
R-N-4	0.065	4	5.0	<10	<5	89.0	<10	<10	<5	0.06	7	<5	42.8	<1
R-N-5	0.049	4	5.7	<10	<5	77.4	<10	<10	6	0.07	8	<5	48.6	<1
R-N-6	0.089	4	4.5	<10	<5	159	<10	<10	6	0.06	6	<5	39.5	<1
R-N-7	0.108	5	5.0	<10	<5	156	<10	<10	<5	0.06	5	<5	40.4	<1
R-N-8	0.012	1	7.5	<10	<5	24.8	<10	<10	7	0.06	7	<5	47.6	<1
R-N-9	0.006	<1	5.6	<10	<5	16.8	<10	<10	<5	0.05	<5	<5	37.5	<1
R-N-10	0.065	4	4.1	<10	<5	113	<10	<10	<5	0.05	7	<5	36.9	<1
R-N-11	0.079	5	4.1	<10	<5	170	<10	<10	<5	0.06	6	<5	32.1	<1
R-N-12	0.007	<1	4.6	<10	<5	16.8	<10	<10	6	0.07	<5	<5	40.4	<1
R-N-13	0.006	<1	4.3	<10	<5	14.7	<10	<10	7	0.06	<5	<5	36.6	<1
R-N-14	0.007	<1	4.0	<10	<5	17.5	<10	<10	6	0.07	<5	<5	40.0	<1
R-N-15	0.035	2	4.8	<10	<5	70.1	<10	<10	6	0.06	7	<5	45.1	<1
R-N-16	0.065	3	5.5	<10	<5	159	<10	<10	<5	0.07	8	<5	49.3	<1
R-N-17	0.036	3	2.3	<10	<5	126	<10	<10	<5	<0.01	5	<5	46.3	<1
R-N-18	0.030	3	2.1	<10	<5	111	<10	<10	<5	<0.01	5	<5	40.8	<1
R-N-19	0.042	2	2.3	<10	<5	51.0	<10	<10	<5	0.03	6	<5	33.3	<1
R-N-20	0.025	2	1.9	<10	<5	41.8	<10	<10	5	0.03	5	<5	29.3	<1

Certified By:



Certificate of Analysis

AGAT WORK ORDER: 12V620127

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Jul 13, 2012

DATE RECEIVED: Jul 12, 2012

DATE REPORTED: Aug 09, 2012

SAMPLE TYPE: Soil

Sample Description	Analyte:	Y	Zn	Zr
	Unit:	ppm	ppm	ppm
	RDL:	1	0.5	5
R-N-1		8	44.1	<5
R-N-2		8	49.0	<5
R-N-3		9	50.6	<5
R-N-4		12	58.2	<5
R-N-5		12	62.4	<5
R-N-6		9	48.8	<5
R-N-7		10	55.4	<5
R-N-8		15	69.7	6
R-N-9		10	66.4	6
R-N-10		7	53.5	<5
R-N-11		8	43.2	<5
R-N-12		6	65.3	5
R-N-13		6	101	<5
R-N-14		7	70.8	<5
R-N-15		11	69.9	<5
R-N-16		12	61.4	<5
R-N-17		6	264	<5
R-N-18		5	245	<5
R-N-19		7	84.8	<5
R-N-20		6	63.7	<5

Comments: RDL - Reported Detection Limit

Certified By:



AGAT Laboratories

Certificate of Analysis

AGAT WORK ORDER: 12V620127

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Fire Assay - Trace Au, AAS finish (202051)

DATE SAMPLED: Jul 13, 2012

DATE RECEIVED: Jul 12, 2012

DATE REPORTED: Aug 09, 2012

SAMPLE TYPE: Soil

Sample Description	Analyte:	Sample Login Weight	Au
	Unit:	kg	ppm
	RDL:	0.01	0.002
R-N-1		0.24	0.002
R-N-2		0.26	0.002
R-N-3		0.34	0.003
R-N-4		0.18	0.006
R-N-5		0.21	0.002
R-N-6		0.24	0.003
R-N-7		0.21	0.003
R-N-8		0.32	0.004
R-N-9		0.24	0.004
R-N-10		0.29	0.003
R-N-11		0.24	0.005
R-N-12		0.21	0.002
R-N-13		0.23	0.109
R-N-14		0.27	0.003
R-N-15		0.31	0.003
R-N-16		0.23	<0.002
R-N-17		0.34	<0.002
R-N-18		0.44	<0.002
R-N-19		0.47	<0.002
R-N-20		0.51	0.008

Comments: RDL - Reported Detection Limit

Certified By:

Quality Assurance

CLIENT NAME: HOMEGOLD RESOURCES LTD.

AGAT WORK ORDER: 12V620127

PROJECT NO: ROAM

ATTENTION TO: JO SHEARER

Solid Analysis											
RPT Date: Aug 09, 2012		REPLICATE				Method Blank	REFERENCE MATERIAL				
PARAMETER	Batch	Sample Id	Original	Rep #1	RPD		Result Value	Expect Value	Recovery	Acceptable Limits	
										Lower	Upper

Fire Assay - Trace Au, AAS finish (202051)

Au	1		0.030	0.023	26.4%	< 0.002	1.5	1.52	98%	90%	110%
----	---	--	-------	-------	-------	---------	-----	------	-----	-----	------

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

Ag	1	3513814	< 0.2	< 0.2	0.0%	< 0.2				80%	120%
Al	1	3513814	0.75	0.74	1.3%	< 0.01				80%	120%
As	1	3513814	17	17	0.0%	< 1				80%	120%
B	1	3513814	< 5	< 5	0.0%	< 5				80%	120%
Ba	1	3513814	395	383	3.1%	< 1				80%	120%
Be	1	3513814	< 0.5	< 0.5	0.0%	< 0.5				80%	120%
Bi	1	3513814	< 1	< 1	0.0%	< 1				80%	120%
Ca	1	3513814	6.35	6.17	2.9%	< 0.01				80%	120%
Cd	1	3513814	< 0.5	< 0.5	0.0%	< 0.5				80%	120%
Ce	1	3513814	24	23	4.3%	< 1				80%	120%
Co	1	3513814	6.15	5.85	5.0%	< 0.5				80%	120%
Cr	1	3513814	22.4	21.1	6.0%	< 0.5				80%	120%
Cu	1	3513814	16.5	15.7	5.0%	< 0.5	3724	3800	98%	80%	120%
Fe	1	3513814	1.47	1.41	4.2%	< 0.01				80%	120%
Ga	1	3513814	< 5	< 5	0.0%	< 5				80%	120%
Hg	1	3513814	< 1	< 1	0.0%	< 1				80%	120%
In	1	3513814	2	< 1		< 1				80%	120%
K	1	3513814	0.06	0.06	0.0%	< 0.01				80%	120%
La	1	3513814	12	11	8.7%	< 1				80%	120%
Li	1	3513814	10	9	10.5%	< 1				80%	120%
Mg	1	3513814	1.03	1.00	3.0%	< 0.01				80%	120%
Mn	1	3513814	366	346	5.6%	< 1				80%	120%
Mo	1	3513814	2.0	1.6	22.2%	< 0.5				80%	120%
Na	1	3513814	0.02	0.02	0.0%	< 0.01				80%	120%
Ni	1	3513814	20.7	19.6	5.5%	< 0.5				80%	120%
P	1	3513814	647	613	5.4%	< 10	535	600	89%	80%	120%
Pb	1	3513814	7.9	7.5	5.2%	0.6				80%	120%
Rb	1	3513814	19	18	5.4%	< 10	14	13	104%	80%	120%
S	1	3513814	0.090	0.089	1.1%	< 0.005				80%	120%
Sb	1	3513814	4	4	0.0%	< 1				80%	120%
Sc	1	3513814	3.9	3.7	5.3%	< 0.5				80%	120%
Se	1	3513814	< 10	< 10	0.0%	< 10				80%	120%
Sn	1	3513814	< 5	< 5	0.0%	< 5				80%	120%
Sr	1	3513814	155	153	1.3%	< 0.5				80%	120%
Ta	1	3513814	< 10	< 10	0.0%	< 10				80%	120%
Te	1	3513814	< 10	< 10	0.0%	< 10				80%	120%
Th	1	3513814	6	< 5		< 5				80%	120%
Ti	1	3513814	0.05	0.05	0.0%	< 0.01				80%	120%
Tl	1	3513814	6	6	0.0%	< 5				80%	120%
U	1	3513814	< 5	< 5	0.0%	< 5				80%	120%
V	1	3513814	31.1	30.5	1.9%	< 0.5				80%	120%



Quality Assurance

CLIENT NAME: HOMEGOLD RESOURCES LTD.

AGAT WORK ORDER: 12V620127

PROJECT NO: ROAM

ATTENTION TO: JO SHEARER

Solid Analysis (Continued)

RPT Date: Aug 09, 2012		REPLICATE				Method Blank	REFERENCE MATERIAL			
PARAMETER	Batch	Sample Id	Original	Rep #1	RPD		Result Value	Expect Value	Recovery	Acceptable Limits
										Lower Upper
W	1	3513814	< 1	< 1	0.0%	< 1				80% 120%
Y	1	3513814	8	8	0.0%	< 1				80% 120%
Zn	1	3513814	44.1	42.2	4.4%	< 0.5				80% 120%
Zr	1	3513814	< 5	< 5	0.0%	< 5				80% 120%
Fire Assay - Trace Au, AAS finish (202051)										
Au	1	3513827	0.003	< 0.002		< 0.002				90% 110%
Aqua Regia Digest - Metals Package, ICP-OES finish (201073)										
Cu	1					< 0.5	3668	3800	96%	80% 120%
Hg	1					< 1	1.6	1.3	120%	80% 120%
P	1					< 10	533	600	89%	80% 120%
Rb	1					< 10	13	13	103%	80% 120%
Sr	1					< 0.5	314	390	81%	80% 120%

Certified By:

Method Summary

CLIENT NAME: HOMEGOLD RESOURCES LTD.

AGAT WORK ORDER: 12V620127

PROJECT NO: ROAM

ATTENTION TO: JO SHEARER

PARAMETER	AGAT S.O.P	LITERATURE REFERENCE	ANALYTICAL TECHNIQUE
Solid Analysis			
Ag	MIN-200-12020		ICP/OES
Al	MIN-200-12020		ICP/OES
As	MIN-200-12020		ICP/OES
B	MIN-200-12020		ICP/OES
Ba	MIN-200-12020		ICP/OES
Be	MIN-200-12020		ICP/OES
Bi	MIN-200-12020		ICP/OES
Ca	MIN-200-12020		ICP/OES
Cd	MIN-200-12020		ICP/OES
Ce	MIN-200-12020		ICP/OES
Co	MIN-200-12020		ICP/OES
Cr	MIN-200-12020		ICP/OES
Cu	MIN-200-12020		ICP/OES
Fe	MIN-200-12020		ICP/OES
Ga	MIN-200-12020		ICP/OES
Hg	MIN-200-12020		ICP/OES
In	MIN-200-12020		ICP/OES
K	MIN-200-12020		ICP/OES
La	MIN-200-12020		ICP/OES
Li	MIN-200-12020		ICP/OES
Mg	MIN-200-12020		ICP/OES
Mn	MIN-200-12020		ICP/OES
Mo	MIN-200-12020		ICP/OES
Na	MIN-200-12020		ICP/OES
Ni	MIN-200-12020		ICP/OES
P	MIN-200-12020		ICP/OES
Pb	MIN-200-12020		ICP/OES
Rb	MIN-200-12020		ICP/OES
S	MIN-200-12020		ICP/OES
Sb	MIN-200-12020		ICP/OES
Sc	MIN-200-12020		ICP/OES
Se	MIN-200-12020		ICP/OES
Sn	MIN-200-12020		ICP/OES
Sr	MIN-200-12020		ICP/OES
Ta	MIN-200-12020		ICP/OES
Te	MIN-200-12020		ICP/OES
Th	MIN-200-12020		ICP/OES
Ti	MIN-200-12020		ICP/OES
Tl	MIN-200-12020		ICP/OES
U	MIN-200-12020		ICP/OES
V	MIN-200-12020		ICP/OES
W	MIN-200-12020		ICP/OES
Y	MIN-200-12020		ICP/OES
Zn	MIN-200-12020		ICP/OES
Zr	MIN-200-12020		ICP/OES
Sample Login Weight	MIN-12009		BALANCE
Au	MIN-200-12019	BUGBEE, E: A Textbook of Fire Assaying	AAS

CLIENT NAME: HOMEGOLD RESOURCES LTD.
UNIT# 5-2330 TYNER STREET
PORT COQUITLAM, BC V3C2Z1
(604) 696-1022

ATTENTION TO: JO SHEARER

PROJECT NO: ROAM

AGAT WORK ORDER: 12V620086

SOLID ANALYSIS REVIEWED BY: Kevin Motomura, ICP Supervisor

DATE REPORTED: Aug 09, 2012

PAGES (INCLUDING COVER): 6

Should you require any information regarding this analysis please contact your client services representative at (905) 501-9998

*NOTES



Certificate of Analysis

AGAT WORK ORDER: 12V620086

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP/ICP-MS finish (201074)

DATE SAMPLED: Jul 13, 2012			DATE RECEIVED: Jul 12, 2012				DATE REPORTED: Aug 09, 2012				SAMPLE TYPE: Other				
	Analyte:	Sample Login Weight	Ag	Al	As	Au	B	Ba	Be	Bi	Ca	Cd	Ce	Co	Cr
	Unit:	kg	ppm	%	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm
Sample Description	RDL:	0.01	0.01	0.01	0.1	0.01	5	1	0.05	0.01	0.01	0.01	0.01	0.1	0.5
DDRM 01		0.23	0.35	0.08	2.7	<0.01	191	4970	<0.05	0.02	>25	12.1	1.40	2.0	1.6
DDRM 04		0.26	0.20	0.14	2.7	<0.01	189	5650	<0.05	0.02	>25	1.82	1.80	2.4	2.3
DDRM 05		0.60	0.08	0.04	0.7	<0.01	196	3570	<0.05	<0.01	>25	0.80	0.51	1.7	0.8
DDRM 06		0.41	0.30	0.20	2.5	<0.01	299	5140	<0.05	0.03	>25	8.76	2.46	5.3	7.0
DDRM 07		0.36	0.78	0.17	3.3	0.02	384	6580	0.05	0.03	>25	7.68	1.75	4.2	6.5
	Analyte:	Cs	Cu	Fe	Ga	Ge	Hf	Hg	In	K	La	Li	Mg	Mn	Mo
	Unit:	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	%	ppm	ppm
Sample Description	RDL:	0.05	0.1	0.01	0.05	0.05	0.02	0.01	0.005	0.01	0.1	0.1	0.01	1	0.05
DDRM 01		0.57	89.2	0.12	0.23	<0.05	0.03	0.40	<0.005	5.69	0.8	1.7	1.04	2390	1.18
DDRM 04		1.09	113	0.13	0.36	0.10	0.02	0.27	<0.005	8.97	1.1	1.5	1.16	4020	1.12
DDRM 05		0.39	105	0.04	0.11	<0.05	<0.02	0.16	<0.005	9.50	0.3	0.7	1.12	1850	0.85
DDRM 06		0.94	112	0.20	0.85	0.17	0.03	0.22	<0.005	4.21	1.4	2.2	1.90	>10000	2.07
DDRM 07		0.86	207	0.15	0.66	0.32	0.03	0.38	<0.005	5.26	1.0	2.2	1.64	>10000	1.60
	Analyte:	Na	Nb	Ni	P	Pb	Rb	Re	S	Sb	Sc	Se	Sn	Sr	Ta
	Unit:	%	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	ppm
Sample Description	RDL:	0.01	0.05	0.2	10	0.1	0.1	0.001	0.005	0.05	0.1	0.2	0.2	0.2	0.01
DDRM 01		0.05	0.19	5.6	4420	37.5	48.7	0.002	0.859	0.65	0.2	0.9	1.4	1440	<0.01
DDRM 04		0.07	0.13	8.4	6430	6.2	101	0.001	0.803	0.19	0.2	0.4	0.8	858	<0.01
DDRM 05		0.05	0.10	6.4	6160	2.6	70.0	0.001	0.683	0.17	<0.1	0.5	1.1	1590	<0.01
DDRM 06		0.10	0.15	17.5	7290	9.7	75.0	0.002	0.943	0.26	0.3	0.2	1.6	518	<0.01
DDRM 07		0.12	0.13	19.1	7800	9.5	76.6	0.003	1.13	0.40	0.2	<0.2	2.8	731	<0.01

Certified By:



AGAT Laboratories

Certificate of Analysis

AGAT WORK ORDER: 12V620086

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP/ICP-MS finish (201074)

DATE SAMPLED: Jul 13, 2012		DATE RECEIVED: Jul 12, 2012				DATE REPORTED: Aug 09, 2012				SAMPLE TYPE: Other	
Analyte:	Te	Th	Ti	Tl	U	V	W	Y	Zn	Zr	
Unit:	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	ppm	ppm	
Sample Description	RDL:	0.01	0.1	0.005	0.01	0.05	0.5	0.05	0.05	0.5	0.5
DDRM 01		<0.01	0.2	<0.005	0.22	0.10	7.4	0.07	0.75	3330	0.8
DDRM 04		<0.01	0.3	<0.005	0.07	0.09	8.2	0.06	0.68	2090	0.8
DDRM 05		<0.01	0.1	<0.005	0.03	0.07	5.0	<0.05	0.19	2060	<0.5
DDRM 06		<0.01	0.5	<0.005	0.15	0.14	14.2	0.08	0.96	2620	1.2
DDRM 07		<0.01	0.5	<0.005	0.21	0.10	15.7	0.08	0.84	3090	1.2

Comments: RDL - Reported Detection Limit

Certified By:

Quality Assurance

CLIENT NAME: HOMEGOLD RESOURCES LTD.

AGAT WORK ORDER: 12V620086

PROJECT NO: ROAM

ATTENTION TO: JO SHEARER

Solid Analysis										
RPT Date: Aug 09, 2012			REPLICATE			Method Blank	REFERENCE MATERIAL			
PARAMETER	Batch	Sample Id	Original	Rep #1	RPD		Result Value	Expect Value	Recovery	Acceptable Limits
										Lower Upper

Aqua Regia Digest - Metals Package, ICP/ICP-MS finish (201074)

Ag	1		0.455	0.432	5.2%	< 0.01				80%	120%
As	1		12.1	11.8	2.5%	< 0.1				80%	120%
Au	1		1.76	1.79	1.7%	< 0.01				80%	120%
B	1		< 5	< 5	0.0%	< 5				80%	120%
Be	1		0.753	0.776	3.0%	< 0.05				80%	120%
Bi	1		0.31	0.31	0.0%	< 0.01				80%	120%
Cd	1		0.376	0.373	0.8%	< 0.01				80%	120%
Ce	1		25.0	24.7	1.2%	< 0.01				80%	120%
Co	1		4.16	4.02	3.4%	< 0.1				80%	120%
Cs	1		0.17	0.17	0.0%	< 0.05				80%	120%
Cu	1					< 0.1	3756	3800	98%	80%	120%
Ga	1		1.22	1.19	2.5%	< 0.05				80%	120%
Ge	1		0.151	0.142	6.1%	0.08				80%	120%
Hf	1		< 0.02	< 0.02	0.0%	< 0.02				80%	120%
Hg	1		0.459	0.424	7.9%	0.05				80%	120%
In	1		0.012	0.012	0.0%	< 0.005				80%	120%
La	1		13.6	13.6	0.0%	< 0.1				80%	120%
Li	1		0.6	0.6	0.0%	< 0.1				80%	120%
Mo	1		35.8	35.3	1.4%	< 0.05	341	380	89%	80%	120%
Nb	1		0.11	0.12	8.7%	< 0.05				80%	120%
Pb	1		15.9	15.4	3.2%	< 0.1				80%	120%
Rb	1		6.67	6.49	2.7%	< 0.1				80%	120%
Re	1		< 0.001	< 0.001	0.0%	< 0.001				80%	120%
Sb	1		4.80	4.80	0.0%	< 0.05				80%	120%
Sc	1		2.0	2.0	0.0%	< 0.1				80%	120%
Se	1		2.3	2.2	4.4%	< 0.2				80%	120%
Sn	1		< 0.2	< 0.2	0.0%	< 0.2				80%	120%
Sr	1		18.5	18.3	1.1%	< 0.2				80%	120%
Ta	1		< 0.01	< 0.01	0.0%	< 0.01				80%	120%
Te	1		0.142	0.134	5.8%	< 0.01				80%	120%
Th	1		6.7	6.7	0.0%	< 0.1				80%	120%
Tl	1		0.045	0.044	2.2%	< 0.01				80%	120%
U	1		4.04	3.98	1.5%	< 0.05				80%	120%
W	1		0.19	0.19	0.0%	< 0.05				80%	120%
Y	1		8.06	7.79	3.4%	< 0.05				80%	120%
Zr	1		1.1	1.1	0.0%	< 0.5				80%	120%

Certified By:



Method Summary

CLIENT NAME: HOMEGOLD RESOURCES LTD.

AGAT WORK ORDER: 12V620086

PROJECT NO: ROAM

ATTENTION TO: JO SHEARER

PARAMETER	AGAT S.O.P	LITERATURE REFERENCE	ANALYTICAL TECHNIQUE
Solid Analysis			
Sample Login Weight	MIN-12009		BALANCE
Ag	MIN-200-12017		ICP-MS
Al	MIN-200-12017		ICP/OES
As	MIN-200-12017		ICP-MS
Au	MIN-200-12017		ICP-MS
B	MIN-200-12017		ICP/OES
Ba	MIN-200-12017		ICP-MS
Be	MIN-200-12017		ICP-MS
Bi	MIN-200-12017		ICP-MS
Ca	MIN-200-12017		ICP/OES
Cd	MIN-200-12017		ICP-MS
Ce	MIN-200-12017		ICP-MS
Co	MIN-200-12017		ICP-MS
Cr	MIN-200-12017		ICP/OES
Cs	MIN-200-12017		ICP-MS
Cu	MIN-200-12017		ICP-MS
Fe	MIN-200-12017		ICP/OES
Ga	MIN-200-12017		ICP-MS
Ge	MIN-200-12017		ICP-MS
Hf	MIN-200-12017		ICP-MS
Hg	MIN-200-12017		ICP-MS
In	MIN-200-12017		ICP-MS
K	MIN-200-12017		ICP/OES
La	MIN-200-12017		ICP-MS
Li	MIN-200-12017		ICP-MS
Mg	MIN-200-12017		ICP/OES
Mn	MIN-200-12017		ICP/OES
Mo	MIN-200-12017		ICP-MS
Na	MIN-200-12017		ICP/OES
Nb	MIN-200-12017		ICP-MS
Ni	MIN-200-12017		ICP-MS
P	MIN-200-12017		ICP/OES
Pb	MIN-200-12017		ICP-MS
Rb	MIN-200-12017		ICP-MS
Re	MIN-200-12017		ICP-MS
S	MIN-200-12017		ICP/OES
Sb	MIN-200-12017		ICP-MS
Sc	MIN-200-12017		ICP-MS
Se	MIN-200-12017		ICP-MS
Sn	MIN-200-12017		ICP-MS
Sr	MIN-200-12017		ICP-MS
Ta	MIN-200-12017		ICP-MS
Te	MIN-200-12017		ICP-MS
Th	MIN-200-12017		ICP-MS
Ti	MIN-200-12017		ICP/OES
Tl	MIN-200-12017		ICP-MS
U	MIN-200-12017		ICP-MS
V	MIN-200-12017		ICP/OES
W	MIN-200-12017		ICP-MS

Method Summary

CLIENT NAME: HOMEGOLD RESOURCES LTD.

AGAT WORK ORDER: 12V620086

PROJECT NO: ROAM

ATTENTION TO: JO SHEARER

PARAMETER	AGAT S.O.P	LITERATURE REFERENCE	ANALYTICAL TECHNIQUE
Y	MIN-200-12017		ICP-MS
Zn	MIN-200-12017		ICP-MS
Zr	MIN-200-12017		ICP-MS

CLIENT NAME: HOMEGOLD RESOURCES LTD.
UNIT# 5-2330 TYNER STREET
PORT COQUITLAM, BC V3C2Z1
(604) 696-1022

ATTENTION TO: JO SHEARER

PROJECT NO: ROAM

AGAT WORK ORDER: 12V620068

SOLID ANALYSIS REVIEWED BY: Kevin Motomura, ICP Supervisor

DATE REPORTED: Aug 09, 2012

PAGES (INCLUDING COVER): 6

Should you require any information regarding this analysis please contact your client services representative at (905) 501-9998

*NOTES



Certificate of Analysis

AGAT WORK ORDER: 12V620068

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)															
DATE SAMPLED: Jul 13, 2012				DATE RECEIVED: Jul 12, 2012				DATE REPORTED: Aug 09, 2012				SAMPLE TYPE: Rock			
	Analyte:	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Ce	Co	Cr	Cu	Fe
	Unit:	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	%
Sample Description	RDL:	0.2	0.01	1	5	1	0.5	1	0.01	0.5	1	0.5	0.5	0.5	0.01
DDROAM 1		<0.2	0.06	32	<5	21	<0.5	<1	0.12	0.9	2	1.6	220	2.9	0.59
DDROAM 2		<0.2	0.14	16	<5	127	<0.5	<1	0.25	8.0	10	1.3	147	22.6	0.51
DDROAM 3		0.3	0.05	17	<5	46	<0.5	<1	1.10	1.0	5	2.1	159	4.4	0.45
	Analyte:	Ga	Hg	In	K	La	Li	Mg	Mn	Mo	Na	Ni	P	Pb	Rb
	Unit:	ppm	ppm	ppm	%	ppm	ppm	%	ppm	ppm	%	ppm	ppm	ppm	ppm
Sample Description	RDL:	5	1	1	0.01	1	1	0.01	1	0.5	0.01	0.5	10	0.5	10
DDROAM 1		<5	<1	<1	0.03	<1	<1	<0.01	88	2.0	<0.01	9.3	567	2.4	<10
DDROAM 2		<5	<1	2	0.09	4	1	0.03	108	2.4	<0.01	5.9	331	57.4	<10
DDROAM 3		<5	<1	<1	0.02	3	<1	0.51	503	2.8	<0.01	8.0	559	2.9	<10
	Analyte:	S	Sb	Sc	Se	Sn	Sr	Ta	Te	Th	Ti	Tl	U	V	W
	Unit:	%	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm
Sample Description	RDL:	0.005	1	0.5	10	5	0.5	10	10	5	0.01	5	5	0.5	1
DDROAM 1		0.013	1	<0.5	<10	<5	15.3	<10	<10	<5	<0.01	<5	<5	7.8	<1
DDROAM 2		0.012	25	1.1	<10	<5	23.6	<10	<10	<5	<0.01	<5	<5	4.1	<1
DDROAM 3		<0.005	2	0.8	<10	<5	69.6	<10	<10	<5	<0.01	<5	<5	2.1	<1
	Analyte:	Y	Zn	Zr											
	Unit:	ppm	ppm	ppm											
Sample Description	RDL:	1	0.5	5											
DDROAM 1		2	78.9	<5											
DDROAM 2		2	650	<5											
DDROAM 3		4	31.1	<5											

Comments: RDL - Reported Detection Limit

Certified By:



AGAT Laboratories

Certificate of Analysis

AGAT WORK ORDER: 12V620068

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Fire Assay - Trace Au, AAS finish (202051)

DATE SAMPLED: Jul 13, 2012

DATE RECEIVED: Jul 12, 2012

DATE REPORTED: Aug 09, 2012

SAMPLE TYPE: Rock

Analyte:	Sample Login Weight	Au
Unit:	kg	ppm
Sample Description	RDL:	0.01 0.002
DDROAM 1	1.98	0.002
DDROAM 2	1.30	<0.002
DDROAM 3	1.71	<0.002

Comments: RDL - Reported Detection Limit

Certified By:

Quality Assurance

CLIENT NAME: HOMEGOLD RESOURCES LTD.

AGAT WORK ORDER: 12V620068

PROJECT NO: ROAM

ATTENTION TO: JO SHEARER

Solid Analysis											
RPT Date: Aug 09, 2012		REPLICATE				Method Blank	REFERENCE MATERIAL				
PARAMETER	Batch	Sample Id	Original	Rep #1	RPD		Result Value	Expect Value	Recovery	Acceptable Limits	
										Lower	Upper

Fire Assay - Trace Au, AAS finish (202051)

Au	1	3513379	0.002	0.002	0.0%	< 0.002	0.277	0.263	105%	90%	110%
----	---	---------	-------	-------	------	---------	-------	-------	------	-----	------

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

Ag	1	3513379	< 0.2	< 0.2	0.0%	< 0.2					80%	120%
Al	1	3513379	0.062	0.070	12.1%	< 0.01					80%	120%
As	1	3513379	32	28	13.3%	< 1					80%	120%
B	1	3513379	< 5	< 5	0.0%	< 5					80%	120%
Ba	1	3513379	21	23	9.1%	< 1					80%	120%
Be	1	3513379	< 0.5	< 0.5	0.0%	< 0.5					80%	120%
Bi	1	3513379	< 1	< 1	0.0%	< 1					80%	120%
Ca	1	3513379	0.117	0.108	8.0%	< 0.01					80%	120%
Cd	1	3513379	0.9	0.6		< 0.5					80%	120%
Ce	1	3513379	2	2	0.0%	< 1					80%	120%
Co	1	3513379	1.6	1.6	0.0%	< 0.5					80%	120%
Cr	1	3513379	220	230	4.4%	< 0.5					80%	120%
Cu	1	3513379	2.86	2.74	4.3%	< 0.5	3642	3800	95%		80%	120%
Fe	1	3513379	0.59	0.57	3.4%	< 0.01					80%	120%
Ga	1	3513379	< 5	< 5	0.0%	< 5					80%	120%
Hg	1	3513379	< 1	< 1	0.0%	< 1					80%	120%
In	1	3513379	< 1	< 1	0.0%	< 1					80%	120%
K	1	3513379	0.03	0.03	0.0%	< 0.01					80%	120%
La	1	3513379	< 1	< 1	0.0%	< 1					80%	120%
Li	1	3513379	< 1	< 1	0.0%	< 1					80%	120%
Mg	1	3513379	< 0.01	< 0.01	0.0%	< 0.01					80%	120%
Mn	1	3513379	88	78	12.0%	< 1					80%	120%
Mo	1	3513379	2.01	1.83	9.4%	< 0.5	357	380	93%		80%	120%
Na	1	3513379	< 0.01	< 0.01	0.0%	< 0.01					80%	120%
Ni	1	3513379	9.3	9.0	3.3%	< 0.5					80%	120%
P	1	3513379	567	544	4.1%	< 10	482	600	80%		80%	120%
Pb	1	3513379	2.4	2.0	18.2%	< 0.5					80%	120%
Rb	1	3513379	< 10	< 10	0.0%	< 10					80%	120%
S	1	3513379	0.013	0.009		< 0.005	0.95	0.80	119%		80%	120%
Sb	1	3513379	1	2		< 1					80%	120%
Sc	1	3513379	< 0.5	< 0.5	0.0%	< 0.5					80%	120%
Se	1	3513379	< 10	< 10	0.0%	< 10					80%	120%
Sn	1	3513379	< 5	< 5	0.0%	< 5					80%	120%
Sr	1	3513379	15.3	16.4	6.9%	< 0.5					80%	120%
Ta	1	3513379	< 10	< 10	0.0%	< 10					80%	120%
Te	1	3513379	< 10	< 10	0.0%	< 10					80%	120%
Th	1	3513379	< 5	< 5	0.0%	< 5	1.2	1.4	83%		80%	120%
Ti	1	3513379	< 0.01	< 0.01	0.0%	< 0.01					80%	120%
Tl	1	3513379	< 5	< 5	0.0%	< 5					80%	120%
U	1	3513379	< 5	< 5	0.0%	< 5					80%	120%
V	1	3513379	7.80	8.25	5.6%	< 0.5					80%	120%



Quality Assurance

CLIENT NAME: HOMEGOLD RESOURCES LTD.

AGAT WORK ORDER: 12V620068

PROJECT NO: ROAM

ATTENTION TO: JO SHEARER

Solid Analysis (Continued)

RPT Date: Aug 09, 2012		REPLICATE				Method Blank	REFERENCE MATERIAL			
PARAMETER	Batch	Sample Id	Original	Rep #1	RPD		Result Value	Expect Value	Recovery	Acceptable Limits
										LowerUpper
W	1	3513379	< 1	< 1	0.0%	< 1				80%120%
Y	1	3513379	2	2	0.0%	< 1				80%120%
Zn	1	3513379	78.9	70.4	11.4%	< 0.5				80%120%
Zr	1	3513379	< 5	< 5	0.0%	< 5				80%120%

Certified By:

Method Summary

CLIENT NAME: HOMEGOLD RESOURCES LTD.

AGAT WORK ORDER: 12V620068

PROJECT NO: ROAM

ATTENTION TO: JO SHEARER

PARAMETER	AGAT S.O.P	LITERATURE REFERENCE	ANALYTICAL TECHNIQUE
Solid Analysis			
Ag	MIN-200-12020		ICP/OES
Al	MIN-200-12020		ICP/OES
As	MIN-200-12020		ICP/OES
B	MIN-200-12020		ICP/OES
Ba	MIN-200-12020		ICP/OES
Be	MIN-200-12020		ICP/OES
Bi	MIN-200-12020		ICP/OES
Ca	MIN-200-12020		ICP/OES
Cd	MIN-200-12020		ICP/OES
Ce	MIN-200-12020		ICP/OES
Co	MIN-200-12020		ICP/OES
Cr	MIN-200-12020		ICP/OES
Cu	MIN-200-12020		ICP/OES
Fe	MIN-200-12020		ICP/OES
Ga	MIN-200-12020		ICP/OES
Hg	MIN-200-12020		ICP/OES
In	MIN-200-12020		ICP/OES
K	MIN-200-12020		ICP/OES
La	MIN-200-12020		ICP/OES
Li	MIN-200-12020		ICP/OES
Mg	MIN-200-12020		ICP/OES
Mn	MIN-200-12020		ICP/OES
Mo	MIN-200-12020		ICP/OES
Na	MIN-200-12020		ICP/OES
Ni	MIN-200-12020		ICP/OES
P	MIN-200-12020		ICP/OES
Pb	MIN-200-12020		ICP/OES
Rb	MIN-200-12020		ICP/OES
S	MIN-200-12020		ICP/OES
Sb	MIN-200-12020		ICP/OES
Sc	MIN-200-12020		ICP/OES
Se	MIN-200-12020		ICP/OES
Sn	MIN-200-12020		ICP/OES
Sr	MIN-200-12020		ICP/OES
Ta	MIN-200-12020		ICP/OES
Te	MIN-200-12020		ICP/OES
Th	MIN-200-12020		ICP/OES
Ti	MIN-200-12020		ICP/OES
Tl	MIN-200-12020		ICP/OES
U	MIN-200-12020		ICP/OES
V	MIN-200-12020		ICP/OES
W	MIN-200-12020		ICP/OES
Y	MIN-200-12020		ICP/OES
Zn	MIN-200-12020		ICP/OES
Zr	MIN-200-12020		ICP/OES
Sample Login Weight	MIN-12009		BALANCE
Au	MIN-200-12019	BUGBEE, E: A Textbook of Fire Assaying	AAS

CLIENT NAME: HOMEGOLD RESOURCES LTD.
UNIT# 5-2330 TYNER STREET
PORT COQUITLAM, BC V3C2Z1
(604) 696-1022

ATTENTION TO: JO SHEARER

PROJECT NO: ROAM

AGAT WORK ORDER: 13V694091

SOLID ANALYSIS REVIEWED BY: Yufei Chen, Analyst

DATE REPORTED: Mar 12, 2013

PAGES (INCLUDING COVER): 24

Should you require any information regarding this analysis please contact your client services representative at (905) 501-9998

*NOTES



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013

DATE RECEIVED: Mar 05, 2013

DATE REPORTED: Mar 12, 2013

SAMPLE TYPE: Soil

Analyte:	Sample Login Weight	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Ce	Co	Cr	Cu
Unit:	kg	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm
RDL:	0.01	0.2	0.01	1	5	1	0.5	1	0.01	0.5	1	0.5	0.5	0.5
Sample ID (AGAT ID)														
L0+00 NE 0+15S (4170518)	0.19	0.2	0.70	26	<5	197	0.6	13	0.58	2.1	27	9.8	17.9	7.0
L0+00 NE 0+30S (4170519)	0.31	0.3	1.13	35	<5	162	0.6	5	0.19	<0.5	26	8.3	21.0	11.7
L0+0 NE 0+45S (4170520)	0.30	0.7	1.22	20	<5	557	0.5	9	0.17	2.1	16	7.3	22.1	11.0
L0+30N 0+25E (4170521)	0.26	<0.2	1.30	11	<5	318	0.7	5	0.41	<0.5	33	10.9	33.8	16.9
L0+30N 0+70E (4170522)	0.24	0.4	1.26	14	5	361	0.6	5	2.27	0.7	32	9.1	29.8	21.2
L0+30N 0+85E (4170523)	0.28	0.8	1.38	15	<5	425	0.6	9	0.45	3.9	31	11.5	30.7	22.7
L0+30N 1+00E (4170524)	0.32	0.3	1.08	77	<5	349	0.6	9	0.27	2.8	39	11.2	17.4	15.3
L0+30NE 0+15E (4170525)	0.40	<0.2	0.81	4	<5	185	<0.5	2	0.19	<0.5	24	5.8	16.7	5.2
L0+30NE 0+30E (4170526)	0.42	<0.2	0.59	6	<5	127	<0.5	4	0.14	<0.5	26	4.0	15.7	4.8
L0+30NE 0+45EA (4170527)	0.30	<0.2	0.99	6	<5	161	0.5	5	0.22	<0.5	37	8.1	27.4	12.7
L0+30NE 0+45EB (4170528)	0.43	<0.2	0.99	10	<5	160	0.6	<1	0.23	<0.5	41	8.6	27.7	13.8
L0+30NE 0+60E (4170529)	0.35	<0.2	0.71	<1	<5	267	<0.5	7	0.17	<0.5	24	4.7	15.6	4.1
L0+30NE 0+75E (4170530)	0.41	<0.2	0.73	3	<5	206	<0.5	<1	0.16	<0.5	25	5.1	18.1	5.2
L0+30NE 0+90E (4170531)	0.32	<0.2	1.15	3	<5	237	<0.5	7	0.20	<0.5	24	6.9	23.5	5.8
L0+30NE 1+05E (4170532)	0.46	0.3	0.96	14	<5	325	0.5	9	4.94	<0.5	28	8.9	27.0	23.1
L0+30W 0+40E (4170533)	0.36	0.4	1.20	11	<5	328	0.7	5	0.23	2.0	32	9.4	28.7	12.0
L0+30W 0+55E (4170534)	0.34	0.7	1.32	30	<5	310	0.7	8	0.25	1.6	32	7.9	29.5	11.6
L0+60N 0+15E (4170535)	0.27	<0.2	0.98	17	5	275	0.6	12	2.09	<0.5	34	9.6	31.4	21.3
L0+60NE 0+15E (4170536)	0.38	0.3	0.86	5	<5	225	<0.5	4	0.21	2.4	21	5.6	18.1	7.4
L0+60NE 0+30E (4170537)	0.36	<0.2	0.77	3	<5	131	<0.5	<1	0.16	0.9	22	5.8	18.6	5.2
L0+60NE 0+45E (4170538)	0.30	<0.2	0.74	7	<5	164	<0.5	2	0.18	0.8	24	6.5	17.2	4.8
L0+60NE 0+60E (4170539)	0.35	<0.2	1.14	3	<5	315	0.6	7	0.23	<0.5	26	7.5	22.9	5.3
L0+60NE 0+75E (4170540)	0.45	<0.2	0.75	<1	<5	295	<0.5	1	0.19	<0.5	23	5.6	18.3	8.4
L0+60NE 0+90E (4170541)	0.40	<0.2	0.79	4	<5	220	<0.5	6	0.19	<0.5	21	6.4	18.1	4.8
L0+60NE 1+05E (4170542)	0.51	0.4	0.74	11	<5	431	<0.5	19	11.1	<0.5	18	8.0	19.9	23.8
L0+90N 0+15E (4170543)	0.37	<0.2	0.71	<1	<5	207	<0.5	<1	0.17	0.7	23	6.0	17.4	4.7
L0+90N 0+30E (4170544)	0.57	<0.2	0.82	9	<5	198	<0.5	2	0.19	1.4	32	7.3	21.4	8.4
L0+90N 0+30W (4170545)	0.29	0.2	1.31	17	<5	180	0.9	5	0.19	8.1	28	11.3	27.7	6.4
L0+90N 0+45E (4170546)	0.39	<0.2	0.73	7	<5	194	<0.5	2	0.23	<0.5	27	6.2	19.4	6.0
L0+90N 0+45W (4170547)	0.14	0.9	0.88	9	<5	253	0.5	3	0.34	22.4	25	4.2	14.2	18.3
L0+90N 0+60EA (4170548)	0.36	<0.2	0.66	4	<5	174	<0.5	4	0.18	<0.5	25	4.9	17.8	5.2

Certified By:

Y. Chen



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013			DATE RECEIVED: Mar 05, 2013				DATE REPORTED: Mar 12, 2013				SAMPLE TYPE: Soil				
Analyte:	Sample Login Weight		Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Ce	Co	Cr	Cu
Unit:	kg		ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	0.01	0.2	0.01	1	5	1	0.5	1	0.01	0.5	1	0.5	0.5	0.5
L0+90N 0+60EB (4170549)		0.31	<0.2	0.71	2	<5	207	<0.5	2	0.21	<0.5	25	5.4	18.2	5.9
L0+90N 0+60W (4170550)		0.35	0.8	1.79	169	6	236	1.9	8	0.64	6.2	36	11.7	65.0	175
L0+90N 0+75E (4170551)		0.50	<0.2	0.63	<1	<5	260	<0.5	<1	0.69	<0.5	18	4.8	17.0	8.4
L1+05N 0+15W (4170552)		0.29	0.3	0.94	8	<5	183	<0.5	3	0.22	1.2	28	5.5	20.0	6.9
L1+05N 0+30W (4170553)		0.29	0.6	0.92	18	<5	205	<0.5	3	0.22	3.3	28	9.6	20.2	7.3
L1+05N 0+45W (4170554)		0.34	1.1	1.39	20	<5	183	1.0	6	0.38	2.4	40	12.2	29.0	11.2
L1+05N 0+60W (4170555)		0.33	1.9	0.68	40	<5	120	<0.5	3	0.08	0.9	32	3.1	12.6	12.0
L60NE 0+30E (4170556)		0.25	<0.2	1.25	12	6	419	0.6	12	3.51	<0.5	33	9.6	32.0	26.5
L60NE 0+45EA (4170557)		0.31	<0.2	1.23	12	<5	308	0.7	9	0.91	<0.5	39	10.9	34.8	18.9
L60NE 0+45EB (4170558)		0.21	<0.2	1.09	17	5	312	0.6	4	1.59	<0.5	33	9.6	30.8	19.6
L60NE 0+60E (4170559)		0.27	<0.2	1.13	11	<5	283	0.6	6	0.27	<0.5	27	7.8	26.0	11.8
L60NE 0+75E (4170560)		0.25	<0.2	0.99	5	<5	303	<0.5	3	0.32	<0.5	25	6.4	21.5	6.2
L60NE 0+90E (4170561)		0.21	<0.2	0.57	2	<5	161	<0.5	1	0.16	<0.5	17	3.9	14.9	3.9
L60NE 1+05E (4170562)		0.32	<0.2	1.00	11	<5	229	<0.5	2	0.32	<0.5	26	7.9	25.2	10.3
L60NE 1+20E (4170563)		0.26	<0.2	0.97	3	<5	323	<0.5	10	0.24	<0.5	24	7.2	20.2	6.3
L60NE 1+35E (4170564)		0.39	<0.2	0.69	<1	<5	382	<0.5	3	0.25	<0.5	19	5.1	16.6	3.8
L60NE 1+50E (4170565)		0.32	<0.2	0.90	4	<5	223	0.5	11	1.40	<0.5	33	8.0	27.2	16.0
L60NE 1+65E (4170566)		0.33	0.4	1.13	10	6	196	0.6	11	4.89	<0.5	31	11.6	28.1	33.8
L60NE 1+80E (4170567)		0.30	0.5	1.04	10	13	295	0.6	21	4.08	0.8	26	11.2	35.4	41.8
L60NE 1+95E (4170568)		NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS
L60NE 0H5E (4170569)		0.27	0.2	0.88	4	7	355	<0.5	18	4.50	<0.5	27	8.0	26.4	19.6
L90NE 15E (4170570)		0.35	<0.2	0.77	7	<5	183	<0.5	4	0.19	<0.5	24	4.9	18.8	6.0
L90NE 30E (4170571)		0.29	<0.2	1.07	6	<5	301	0.5	5	0.31	<0.5	32	8.0	28.1	14.2
L90NE 45E (4170572)		0.28	<0.2	1.13	13	5	418	0.6	5	1.13	<0.5	33	9.7	29.7	15.2
L90NE 60E (4170573)		0.30	<0.2	0.85	11	<5	212	<0.5	<1	0.21	<0.5	30	6.1	24.9	7.5
L90NE 75EA (4170574)		0.37	<0.2	1.02	8	<5	369	<0.5	5	0.27	<0.5	23	6.7	20.9	9.0
L90NE 75EB (4170575)		0.35	<0.2	1.06	7	<5	374	<0.5	6	0.26	<0.5	24	6.6	21.7	8.8
L90NE 90E (4170576)		0.34	<0.2	1.16	13	<5	406	0.5	<1	0.32	<0.5	23	7.0	22.2	10.2
L90NE 105E (4170577)		0.33	<0.2	0.98	13	<5	291	<0.5	5	0.23	<0.5	28	6.8	23.4	11.2
L90NE 120E (4170578)		0.32	<0.2	0.94	4	<5	373	<0.5	<1	0.31	<0.5	23	6.3	19.2	5.6
L90NE 135E (4170579)		0.33	<0.2	0.79	6	<5	199	<0.5	5	0.17	<0.5	27	5.9	22.1	5.0

Certified By:

Y. Chen



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013

DATE RECEIVED: Mar 05, 2013

DATE REPORTED: Mar 12, 2013

SAMPLE TYPE: Soil

Analyte:	Sample Login Weight	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Ce	Co	Cr	Cu
Unit:	kg	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm
RDL:	0.01	0.2	0.01	1	5	1	0.5	1	0.01	0.5	1	0.5	0.5	0.5
Sample ID (AGAT ID)														
L90NE 150E (4170580)	0.28	0.2	1.58	14	8	409	0.7	16	4.51	0.6	36	12.4	45.9	43.1
L90NE 165E (4170581)	0.29	<0.2	1.75	13	7	513	0.8	14	1.59	<0.5	41	13.9	47.4	34.9
L90NE 180E (4170582)	0.30	<0.2	0.83	11	<5	203	<0.5	10	1.36	<0.5	29	8.9	26.7	18.6
L90NE 195E (4170583)	0.28	<0.2	1.17	14	6	299	0.6	9	1.11	<0.5	29	11.4	32.9	25.4
L120NE 152 (4170584)	0.36	<0.2	0.66	6	<5	149	<0.5	4	0.23	<0.5	24	6.0	16.2	5.8
L120NE 165EA (4170585)	0.27	<0.2	0.78	6	<5	176	<0.5	7	0.26	<0.5	24	6.2	19.1	6.5
L120NE 165EB (4170586)	0.42	<0.2	0.73	9	<5	188	<0.5	9	0.26	<0.5	24	6.0	18.7	6.4
L120NE 180E (4170587)	0.33	<0.2	0.71	7	<5	209	<0.5	3	0.39	<0.5	27	7.4	23.0	11.1
L120NE 195E (4170588)	0.31	<0.2	0.88	12	<5	297	<0.5	7	1.07	<0.5	27	8.5	25.1	16.9
L120NE 210E (4170589)	0.46	<0.2	0.79	11	<5	262	<0.5	11	3.33	<0.5	26	9.1	25.7	20.8
L120NE 225E (4170590)	0.38	<0.2	0.91	12	<5	277	0.5	10	0.39	<0.5	30	8.6	24.4	12.7
L120NE 240E (4170591)	0.31	<0.2	0.96	14	7	452	0.6	<1	0.70	<0.5	27	10.5	26.1	21.7
L120NE 255E (4170592)	0.40	<0.2	0.40	11	<5	74	<0.5	<1	1.38	<0.5	21	6.1	15.4	7.7
L120NE 270E (4170593)	0.30	<0.2	0.72	1	<5	182	<0.5	2	1.20	<0.5	24	7.8	21.1	16.0
L120NE 285E (4170594)	0.27	<0.2	0.68	7	<5	147	<0.5	4	0.22	<0.5	28	6.7	18.8	6.9
L120NE 300E (4170595)	0.28	<0.2	0.69	7	<5	189	<0.5	5	0.26	<0.5	27	6.3	18.9	7.8
NSL150NE 150E (4170596)	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS
L150NE 165E (4170597)	0.31	<0.2	0.61	2	<5	78	<0.5	3	0.15	<0.5	25	5.1	19.6	5.3
L150NE 180E (4170598)	0.28	<0.2	0.78	5	<5	239	<0.5	2	0.25	<0.5	29	7.0	21.3	8.3
L150NE 195E (4170599)	0.35	<0.2	0.70	9	<5	184	<0.5	3	0.21	<0.5	23	5.4	17.3	5.5
L150NE 210E (4170600)	0.35	<0.2	0.61	6	<5	247	<0.5	3	0.23	<0.5	25	5.8	17.9	5.8
L150NE 225E (4170601)	0.35	<0.2	0.68	6	<5	280	<0.5	6	0.23	<0.5	27	6.0	18.6	5.9
L150NE 240EA (4170602)	0.37	<0.2	0.78	8	<5	258	<0.5	4	0.33	<0.5	29	7.6	21.6	10.3
L150NE 240EB (4170603)	0.37	<0.2	0.78	9	<5	253	<0.5	5	0.33	<0.5	28	7.7	21.0	11.3
L150NE 255E (4170604)	0.33	<0.2	0.39	4	<5	67	<0.5	5	1.35	<0.5	19	5.7	12.2	7.9
L150NE 270E (4170605)	0.30	<0.2	0.73	2	<5	269	<0.5	6	0.22	<0.5	25	6.5	17.9	6.2
L150NE 285E (4170606)	0.35	<0.2	0.62	3	<5	166	<0.5	4	0.19	<0.5	27	6.2	18.0	6.3
L150NE 300E (4170607)	0.31	<0.2	0.78	13	<5	228	<0.5	3	0.29	<0.5	30	7.7	21.4	11.1
BL 0+30N (4170608)	0.20	0.5	1.06	2	5	467	0.6	6	0.52	2.3	30	9.3	27.0	20.8
BL 0+60NA (4170609)	0.19	0.4	0.38	38	<5	126	<0.5	<1	0.13	2.3	23	6.0	6.5	10.5
BL 0+60NB (4170610)	0.25	<0.2	0.76	<1	6	277	<0.5	7	1.91	0.6	26	7.7	25.4	19.1

Certified By:

Y. Chen.



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013			DATE RECEIVED: Mar 05, 2013				DATE REPORTED: Mar 12, 2013				SAMPLE TYPE: Soil				
	Analyte:	Sample Login Weight	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Ce	Co	Cr	Cu
	Unit:	kg	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	0.01	0.2	0.01	1	5	1	0.5	1	0.01	0.5	1	0.5	0.5	0.5
BL 0+60NC (4170611)		0.42	0.2	0.73	<1	<5	240	<0.5	13	1.76	0.8	25	7.8	25.3	20.1
BL 0+90NA (4170612)		0.26	<0.2	1.03	4	<5	289	0.6	4	0.47	<0.5	33	9.6	31.3	18.4
BL 0+90NB (4170613)		0.30	<0.2	1.05	8	<5	274	0.6	4	0.40	0.8	23	7.6	22.4	8.7
BL 1+05N (4170614)		0.47	<0.2	0.77	11	<5	87	<0.5	5	0.16	<0.5	24	5.2	20.8	6.6
BL 1+20N (4170615)		0.34	<0.2	0.88	2	<5	225	<0.5	2	0.19	<0.5	21	5.3	21.0	4.6
BL 1+50NA (4170616)		0.50	<0.2	0.75	<1	<5	258	<0.5	6	0.16	<0.5	20	5.3	18.3	3.7
BL 1+50NB (4170617)		0.31	<0.2	0.73	<1	<5	234	<0.5	5	0.15	<0.5	18	4.9	18.2	3.8
REDS 1 (4170618)		0.35	<0.2	0.83	19	5	282	<0.5	7	1.96	0.6	31	8.1	21.1	15.1
REDS 2 (4170619)		0.23	<0.2	0.67	<1	<5	256	<0.5	9	2.93	<0.5	27	7.2	21.5	13.2
REDS 3 (4170620)		0.31	<0.2	0.53	16	<5	238	<0.5	5	2.64	<0.5	24	6.5	17.5	13.7
REDS 4 (4170621)		0.29	<0.2	0.84	13	<5	279	0.5	13	2.66	0.5	29	9.8	23.1	20.0
REDS 5 (4170622)		0.26	<0.2	0.84	12	<5	323	0.5	13	0.75	0.6	25	10.2	21.6	18.6
REDS 6 (4170623)		0.30	2.4	0.36	72	10	258	<0.5	21	0.38	<0.5	12	4.4	17.0	30.8
REDS 42 (4170624)		0.33	<0.2	0.51	298	40	683	<0.5	27	1.79	1.0	19	7.8	15.3	27.7
RO-E-S1 (4170625)		0.35	<0.2	1.06	16	<5	210	0.6	5	0.37	<0.5	30	10.1	27.0	14.0
RO-E-S2 (4170626)		0.28	<0.2	0.65	<1	<5	161	<0.5	5	0.18	<0.5	17	5.4	18.5	4.2
RO-E-S3 (4170627)		0.26	<0.2	0.68	6	<5	201	<0.5	<1	0.16	<0.5	19	4.7	14.4	3.6
RO-E-S4 (4170628)		0.24	<0.2	0.75	4	<5	263	<0.5	2	0.22	<0.5	21	6.1	17.4	6.5

Certified By:

Y. Chen



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013		DATE RECEIVED: Mar 05, 2013					DATE REPORTED: Mar 12, 2013					SAMPLE TYPE: Soil			
	Analyte:	Fe	Ga	Hg	In	K	La	Li	Mg	Mn	Mo	Na	Ni	P	Pb
	Unit:	%	ppm	ppm	ppm	%	ppm	ppm	%	ppm	ppm	%	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	0.01	5	1	1	0.01	1	1	0.01	1	0.5	0.01	0.5	10	0.5
L0+00 NE 0+15S (4170518)		2.54	<5	<1	3	0.05	12	9	0.09	171	4.7	<0.01	40.8	1610	33.9
L0+00 NE 0+30S (4170519)		2.53	<5	<1	3	0.04	12	9	0.22	162	3.1	<0.01	38.2	325	122
L0+0 NE 0+45S (4170520)		1.93	<5	<1	3	0.04	7	8	0.17	318	3.6	<0.01	20.8	221	60.3
L0+30N 0+25E (4170521)		2.55	<5	<1	5	0.16	14	13	0.46	401	2.3	0.01	33.9	666	22.6
L0+30N 0+70E (4170522)		2.21	<5	3	<1	0.11	14	14	0.67	369	3.4	0.01	31.6	785	25.9
L0+30N 0+85E (4170523)		2.28	<5	2	<1	0.10	13	14	0.43	1050	3.2	0.01	32.4	826	95.8
L0+30N 1+00E (4170524)		2.52	<5	<1	4	0.07	17	11	0.16	290	6.3	<0.01	27.7	367	462
L0+30NE 0+15E (4170525)		1.22	<5	<1	5	0.06	11	9	0.23	312	2.9	<0.01	12.1	349	19.2
L0+30NE 0+30E (4170526)		1.14	<5	<1	5	0.05	12	8	0.16	203	1.5	<0.01	10.1	607	11.8
L0+30NE 0+45EA (4170527)		1.89	<5	<1	3	0.09	14	10	0.34	233	2.0	<0.01	25.3	408	14.2
L0+30NE 0+45EB (4170528)		1.90	<5	<1	3	0.10	14	10	0.34	247	1.4	<0.01	26.3	396	13.3
L0+30NE 0+60E (4170529)		1.09	<5	<1	4	0.05	11	8	0.18	349	1.3	<0.01	10.4	847	12.0
L0+30NE 0+75E (4170530)		1.35	<5	<1	<1	0.06	11	9	0.23	415	1.3	<0.01	13.9	639	11.3
L0+30NE 0+90E (4170531)		1.85	<5	<1	3	0.08	10	11	0.28	522	2.6	<0.01	14.9	312	18.0
L0+30NE 1+05E (4170532)		1.90	<5	1	<1	0.11	13	10	0.65	369	4.3	0.01	29.5	583	16.9
L0+30W 0+40E (4170533)		2.56	<5	<1	4	0.05	15	11	0.24	319	2.5	<0.01	23.4	1100	132
L0+30W 0+55E (4170534)		2.56	<5	1	2	0.05	14	12	0.29	219	3.1	<0.01	28.0	630	365
L0+60N 0+15E (4170535)		2.09	<5	<1	1	0.08	15	10	0.89	427	4.3	0.01	33.4	1030	16.4
L0+60NE 0+15E (4170536)		1.41	<5	<1	3	0.07	10	8	0.19	430	1.7	<0.01	13.4	598	16.5
L0+60NE 0+30E (4170537)		1.48	<5	<1	<1	0.06	10	8	0.19	215	1.8	<0.01	13.8	713	13.8
L0+60NE 0+45E (4170538)		1.40	<5	<1	5	0.06	11	8	0.19	286	1.9	<0.01	12.6	694	14.3
L0+60NE 0+60E (4170539)		1.90	<5	1	<1	0.09	11	10	0.26	637	1.6	<0.01	18.9	1330	18.6
L0+60NE 0+75E (4170540)		1.41	<5	<1	<1	0.07	10	8	0.21	615	1.9	<0.01	15.6	417	12.8
L0+60NE 0+90E (4170541)		1.41	<5	<1	<1	0.07	9	10	0.22	607	1.9	<0.01	16.6	233	12.5
L0+60NE 1+05E (4170542)		1.42	<5	<1	<1	0.09	9	8	1.14	362	8.3	0.02	25.6	688	13.2
L0+90N 0+15E (4170543)		1.24	<5	<1	2	0.06	10	9	0.16	385	1.8	<0.01	10.3	733	14.7
L0+90N 0+30E (4170544)		1.72	<5	<1	1	0.07	15	13	0.27	277	1.2	<0.01	17.5	1090	23.3
L0+90N 0+30W (4170545)		2.63	<5	<1	<1	0.07	13	15	0.27	390	1.4	<0.01	20.4	1680	58.2
L0+90N 0+45E (4170546)		1.47	<5	1	4	0.07	12	9	0.28	284	2.1	<0.01	17.7	971	11.9
L0+90N 0+45W (4170547)		1.12	<5	<1	<1	0.10	11	5	0.10	524	1.9	0.01	14.7	1450	29.2
L0+90N 0+60EA (4170548)		1.28	<5	<1	<1	0.07	11	8	0.22	194	1.0	<0.01	14.3	560	10.8
L0+90N 0+60EB (4170549)		1.39	<5	<1	<1	0.07	11	8	0.23	321	1.9	<0.01	15.1	699	12.5

Certified By:

Y. Chen



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013		DATE RECEIVED: Mar 05, 2013					DATE REPORTED: Mar 12, 2013					SAMPLE TYPE: Soil			
	Analyte:	Fe	Ga	Hg	In	K	La	Li	Mg	Mn	Mo	Na	Ni	P	Pb
	Unit:	%	ppm	ppm	ppm	%	ppm	ppm	%	ppm	ppm	%	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	0.01	5	1	1	0.01	1	1	0.01	1	0.5	0.01	0.5	10	0.5
L0+90N 0+60W (4170550)		3.57	10	<1	1	0.05	14	8	0.13	444	11.9	<0.01	63.7	5010	118
L0+90N 0+75E (4170551)		1.25	<5	<1	1	0.07	8	8	0.25	448	2.3	<0.01	14.6	347	11.5
L1+05N 0+15W (4170552)		1.50	<5	<1	<1	0.07	12	12	0.27	350	2.0	<0.01	14.2	690	26.8
L1+05N 0+30W (4170553)		1.84	<5	<1	3	0.07	13	9	0.17	821	3.3	<0.01	10.3	1050	37.6
L1+05N 0+45W (4170554)		2.78	6	<1	4	0.07	18	18	0.38	873	2.4	<0.01	30.0	2250	45.8
L1+05N 0+60W (4170555)		1.22	<5	<1	3	0.03	14	4	0.06	121	2.4	<0.01	13.6	320	32.3
L60NE 0+30E (4170556)		2.16	<5	<1	<1	0.11	15	15	0.95	562	3.5	0.02	37.7	645	21.2
L60NE 0+45EA (4170557)		2.40	<5	2	7	0.18	17	13	0.50	367	3.8	0.01	37.3	363	19.0
L60NE 0+45EB (4170558)		2.09	<5	3	3	0.15	15	11	0.49	347	4.1	0.01	33.6	393	17.5
L60NE 0+60E (4170559)		2.04	<5	<1	2	0.15	11	10	0.31	484	1.5	<0.01	25.3	248	16.9
L60NE 0+75E (4170560)		1.71	<5	<1	2	0.13	10	9	0.24	659	2.7	<0.01	15.6	257	15.3
L60NE 0+90E (4170561)		1.13	<5	<1	5	0.07	8	7	0.17	443	1.6	<0.01	9.8	314	9.9
L60NE 1+05E (4170562)		1.93	<5	<1	2	0.14	10	9	0.29	631	2.4	<0.01	21.0	220	15.2
L60NE 1+20E (4170563)		1.64	<5	<1	<1	0.11	9	10	0.23	742	2.3	<0.01	16.4	485	19.3
L60NE 1+35E (4170564)		1.21	<5	<1	<1	0.07	8	8	0.19	648	1.4	<0.01	12.4	1060	11.4
L60NE 1+50E (4170565)		1.83	<5	1	6	0.10	14	9	0.43	351	2.8	0.01	27.4	392	14.9
L60NE 1+65E (4170566)		2.38	<5	2	2	0.14	14	17	0.99	511	3.8	0.02	43.6	955	23.2
L60NE 1+80E (4170567)		2.25	<5	2	2	0.16	11	13	0.69	574	4.8	0.02	43.7	840	42.5
L60NE 1+95E (4170568)		NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS
L60NE 0H5E (4170569)		1.83	<5	<1	<1	0.09	12	11	1.04	337	4.3	0.01	28.8	939	14.1
L90NE 15E (4170570)		1.37	<5	2	3	0.07	11	9	0.24	111	2.2	<0.01	15.7	140	11.3
L90NE 30E (4170571)		2.03	<5	1	<1	0.13	13	11	0.35	290	1.8	0.01	26.3	231	16.2
L90NE 45E (4170572)		2.10	<5	<1	2	0.21	14	11	0.43	504	2.7	0.01	31.9	422	18.7
L90NE 60E (4170573)		1.59	<5	<1	<1	0.09	12	8	0.24	245	3.2	<0.01	20.3	291	12.6
L90NE 75EA (4170574)		1.65	<5	1	3	0.09	9	9	0.24	503	1.8	<0.01	21.6	456	16.3
L90NE 75EB (4170575)		1.68	<5	<1	1	0.09	10	9	0.25	468	2.3	<0.01	21.8	414	16.7
L90NE 90E (4170576)		1.78	<5	<1	1	0.12	9	9	0.25	735	3.2	0.01	19.4	422	18.9
L90NE 105E (4170577)		1.78	<5	<1	<1	0.11	12	10	0.29	305	2.5	<0.01	20.8	191	17.6
L90NE 120E (4170578)		1.46	<5	<1	2	0.13	9	9	0.22	800	2.5	<0.01	16.3	217	15.6
L90NE 135E (4170579)		1.35	<5	<1	2	0.09	11	9	0.22	373	1.4	<0.01	15.6	194	13.0
L90NE 150E (4170580)		2.77	5	2	<1	0.25	16	19	1.50	645	4.0	0.02	46.4	953	20.7
L90NE 165E (4170581)		2.97	5	<1	2	0.30	18	17	0.91	789	2.6	0.02	45.4	469	24.3

Certified By:

Y. Chen



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013		DATE RECEIVED: Mar 05, 2013					DATE REPORTED: Mar 12, 2013					SAMPLE TYPE: Soil			
	Analyte:	Fe	Ga	Hg	In	K	La	Li	Mg	Mn	Mo	Na	Ni	P	Pb
	Unit:	%	ppm	ppm	ppm	%	ppm	ppm	%	ppm	ppm	%	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	0.01	5	1	1	0.01	1	1	0.01	1	0.5	0.01	0.5	10	0.5
L90NE 180E (4170582)		1.92	<5	2	2	0.11	13	10	0.63	394	2.2	0.01	30.0	703	14.9
L90NE 195E (4170583)		2.41	<5	3	<1	0.20	13	11	0.64	575	3.2	0.01	36.1	546	19.7
L120NE 152 (4170584)		1.23	<5	<1	3	0.06	11	9	0.22	181	1.9	0.01	16.0	247	11.4
L120NE 165EA (4170585)		1.37	<5	<1	<1	0.09	11	10	0.27	245	2.6	<0.01	19.3	260	13.5
L120NE 165EB (4170586)		1.32	<5	<1	3	0.08	11	10	0.26	233	2.2	<0.01	18.7	231	13.5
L120NE 180E (4170587)		1.92	<5	<1	2	0.10	11	7	0.30	410	2.3	0.01	19.7	351	15.4
L120NE 195E (4170588)		1.84	<5	3	3	0.15	12	10	0.46	418	2.9	0.01	28.8	529	15.8
L120NE 210E (4170589)		1.77	<5	2	1	0.10	12	9	0.88	412	3.0	0.01	30.0	738	14.2
L120NE 225E (4170590)		1.97	<5	<1	<1	0.20	13	10	0.39	506	2.9	0.01	25.5	413	17.1
L120NE 240E (4170591)		2.20	<5	<1	1	0.16	11	10	0.42	731	3.2	0.01	31.7	573	20.1
L120NE 255E (4170592)		1.07	<5	3	<1	0.04	10	7	0.48	216	1.6	<0.01	20.2	470	9.0
L120NE 270E (4170593)		1.56	<5	<1	1	0.11	10	10	0.50	385	3.0	0.01	26.0	606	12.8
L120NE 285E (4170594)		1.39	<5	<1	1	0.08	12	10	0.29	236	1.7	<0.01	18.5	337	11.7
L120NE 300E (4170595)		1.40	<5	<1	2	0.15	12	9	0.27	417	2.2	<0.01	18.1	459	11.8
NSL150NE 150E (4170596)		NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS
L150NE 165E (4170597)		1.32	<5	<1	2	0.06	12	8	0.24	152	1.2	<0.01	15.6	315	9.8
L150NE 180E (4170598)		1.62	<5	<1	5	0.13	12	9	0.30	355	2.3	0.01	22.4	403	14.1
L150NE 195E (4170599)		1.35	<5	<1	<1	0.09	10	9	0.24	298	2.7	<0.01	15.9	237	9.4
L150NE 210E (4170600)		1.33	<5	<1	4	0.12	11	8	0.25	312	1.8	<0.01	17.3	516	11.8
L150NE 225E (4170601)		1.43	<5	1	<1	0.12	12	9	0.25	354	1.5	<0.01	18.0	404	11.6
L150NE 240EA (4170602)		1.65	<5	<1	3	0.13	12	9	0.30	381	1.7	<0.01	21.8	329	12.3
L150NE 240EB (4170603)		1.66	<5	1	<1	0.13	12	10	0.30	377	1.6	<0.01	23.4	346	13.1
L150NE 255E (4170604)		1.05	<5	<1	<1	0.04	9	7	0.48	205	2.5	<0.01	19.0	417	7.0
L150NE 270E (4170605)		1.41	<5	3	3	0.11	11	9	0.26	410	3.0	<0.01	18.2	435	10.4
L150NE 285E (4170606)		1.33	<5	<1	3	0.09	12	10	0.27	241	0.8	<0.01	18.6	440	10.6
L150NE 300E (4170607)		1.67	<5	<1	2	0.13	13	9	0.32	402	1.5	0.01	23.0	361	13.8
BL 0+30N (4170608)		2.25	<5	1	6	0.15	13	8	0.39	446	3.4	0.01	29.0	1250	25.2
BL 0+60NA (4170609)		1.62	<5	<1	3	0.07	8	2	0.04	339	2.1	<0.01	16.0	479	32.0
BL 0+60NB (4170610)		1.76	<5	<1	1	0.09	11	9	0.62	365	3.2	0.01	27.4	1200	13.4
BL 0+60NC (4170611)		1.74	<5	<1	1	0.09	11	8	0.62	409	3.1	0.01	28.1	1150	14.8
BL 0+90NA (4170612)		2.24	<5	2	<1	0.11	14	11	0.50	421	3.2	0.01	29.5	615	15.6
BL 0+90NB (4170613)		1.69	<5	1	1	0.14	10	10	0.27	460	1.7	<0.01	19.9	1050	19.2

Certified By:



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013

DATE RECEIVED: Mar 05, 2013

DATE REPORTED: Mar 12, 2013

SAMPLE TYPE: Soil

	Analyte:	Fe	Ga	Hg	In	K	La	Li	Mg	Mn	Mo	Na	Ni	P	Pb
	Unit:	%	ppm	ppm	ppm	%	ppm	ppm	%	ppm	ppm	%	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	0.01	5	1	1	0.01	1	1	0.01	1	0.5	0.01	0.5	10	0.5
BL 1+05N (4170614)		1.50	<5	<1	3	0.08	11	9	0.28	130	1.9	<0.01	15.4	255	15.7
BL 1+20N (4170615)		1.41	<5	<1	1	0.06	9	8	0.24	230	1.8	<0.01	14.1	280	12.8
BL 1+50NA (4170616)		1.27	<5	<1	3	0.09	8	7	0.17	544	1.6	<0.01	14.7	427	10.8
BL 1+50NB (4170617)		1.23	<5	<1	<1	0.07	8	7	0.17	384	1.0	<0.01	14.6	297	10.9
REDS 1 (4170618)		1.74	<5	<1	5	0.10	14	10	0.45	322	4.3	0.01	23.9	475	15.6
REDS 2 (4170619)		1.59	<5	<1	2	0.08	12	9	0.83	284	3.6	0.01	22.7	736	14.2
REDS 3 (4170620)		1.35	<5	<1	3	0.06	11	8	0.75	268	4.9	0.01	21.8	636	11.8
REDS 4 (4170621)		1.99	<5	<1	<1	0.08	13	12	0.55	347	3.9	0.01	29.9	378	17.7
REDS 5 (4170622)		2.11	<5	<1	5	0.06	11	8	0.34	394	3.1	0.01	28.7	398	19.1
REDS 6 (4170623)		9.72	<5	3	<1	0.17	5	4	0.11	104	8.6	0.02	15.8	771	157
REDS 42 (4170624)		22.7	14	3	<1	0.06	7	9	0.48	1660	12.8	0.01	16.9	3490	18.9
RO-E-S1 (4170625)		2.19	<5	<1	<1	0.14	12	9	0.31	477	2.8	0.01	27.4	231	21.3
RO-E-S2 (4170626)		1.26	<5	<1	2	0.10	7	5	0.17	249	1.1	<0.01	14.7	188	10.1
RO-E-S3 (4170627)		1.32	<5	<1	1	0.05	9	7	0.13	276	1.9	<0.01	8.1	725	13.5
RO-E-S4 (4170628)		1.49	<5	<1	3	0.07	9	8	0.18	559	2.0	<0.01	14.1	533	13.7

Certified By:



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013		DATE RECEIVED: Mar 05, 2013					DATE REPORTED: Mar 12, 2013					SAMPLE TYPE: Soil			
	Analyte:	Rb	S	Sb	Sc	Se	Sn	Sr	Ta	Te	Th	Ti	Tl	U	V
	Unit:	ppm	%	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	10	0.005	1	0.5	10	5	0.5	10	10	5	0.01	5	5	0.5
L0+00 NE 0+15S (4170518)		<10	0.018	11	3.7	<10	<5	24.8	<10	<10	6	<0.01	<5	<5	23.6
L0+00 NE 0+30S (4170519)		14	0.012	14	2.9	<10	<5	13.8	<10	<10	7	0.02	<5	<5	40.0
L0+0 NE 0+45S (4170520)		<10	0.008	11	2.6	<10	<5	13.8	<10	<10	<5	<0.01	<5	<5	42.4
L0+30N 0+25E (4170521)		28	0.013	6	4.9	<10	<5	20.5	<10	<10	9	0.05	<5	<5	49.8
L0+30N 0+70E (4170522)		21	0.040	4	4.5	<10	12	66.3	<10	<10	8	0.04	<5	<5	48.9
L0+30N 0+85E (4170523)		23	0.013	7	4.6	<10	<5	26.8	<10	<10	8	0.03	<5	<5	48.4
L0+30N 1+00E (4170524)		12	0.012	24	2.7	<10	<5	15.7	<10	<10	7	<0.01	<5	<5	39.1
L0+30NE 0+15E (4170525)		15	0.006	2	1.6	<10	<5	10.3	<10	<10	5	0.03	<5	<5	28.6
L0+30NE 0+30E (4170526)		<10	0.005	1	1.3	<10	<5	7.1	<10	<10	5	0.03	<5	<5	24.4
L0+30NE 0+45EA (4170527)		15	0.007	3	4.1	<10	<5	12.8	<10	<10	8	0.06	<5	<5	37.7
L0+30NE 0+45EB (4170528)		18	0.008	2	4.8	<10	<5	12.8	<10	<10	9	0.06	<5	<5	36.9
L0+30NE 0+60E (4170529)		10	0.006	2	1.5	<10	<5	8.6	<10	<10	5	0.02	<5	<5	24.5
L0+30NE 0+75E (4170530)		13	0.006	<1	1.7	<10	<5	8.6	<10	<10	6	0.03	<5	<5	28.4
L0+30NE 0+90E (4170531)		18	0.011	<1	2.1	<10	<5	13.1	<10	<10	5	0.04	<5	<5	43.7
L0+30NE 1+05E (4170532)		22	0.066	7	4.4	<10	24	91.1	<10	<10	8	0.05	<5	<5	40.3
L0+30W 0+40E (4170533)		12	0.009	6	3.0	<10	<5	15.2	<10	<10	6	0.03	<5	<5	50.6
L0+30W 0+55E (4170534)		20	0.009	11	3.0	<10	<5	14.2	<10	<10	8	0.06	<5	<5	51.2
L0+60N 0+15E (4170535)		19	0.041	<1	4.7	<10	12	66.9	<10	<10	9	0.06	<5	<5	49.7
L0+60NE 0+15E (4170536)		20	0.009	<1	1.6	<10	<5	12.4	<10	<10	5	0.03	<5	<5	34.5
L0+60NE 0+30E (4170537)		16	0.006	2	1.6	<10	<5	7.9	<10	<10	5	0.04	<5	<5	31.6
L0+60NE 0+45E (4170538)		15	0.007	2	1.4	<10	<5	8.6	<10	<10	5	0.03	<5	<5	29.8
L0+60NE 0+60E (4170539)		19	0.011	3	2.3	<10	5	13.0	<10	<10	6	0.05	<5	<5	38.2
L0+60NE 0+75E (4170540)		15	0.007	2	1.6	<10	<5	11.6	<10	<10	<5	0.04	<5	<5	28.5
L0+60NE 0+90E (4170541)		16	0.007	<1	1.5	<10	<5	12.8	<10	<10	<5	0.03	<5	<5	29.2
L0+60NE 1+05E (4170542)		24	0.141	7	3.7	<10	53	245	<10	<10	7	0.04	<5	<5	33.2
L0+90N 0+15E (4170543)		19	0.005	<1	1.5	<10	<5	8.6	<10	<10	<5	0.03	<5	<5	27.6
L0+90N 0+30E (4170544)		21	0.008	2	2.0	<10	<5	11.7	<10	<10	8	0.04	<5	<5	32.0
L0+90N 0+30W (4170545)		29	0.007	3	2.2	<10	<5	12.4	<10	<10	7	0.03	<5	<5	53.1
L0+90N 0+45E (4170546)		18	0.006	2	2.0	<10	<5	11.9	<10	<10	7	0.03	<5	<5	26.3
L0+90N 0+45W (4170547)		26	0.019	4	1.8	<10	<5	28.2	<10	<10	<5	0.01	<5	<5	34.9
L0+90N 0+60EA (4170548)		14	0.006	2	1.5	<10	<5	10.0	<10	<10	6	0.03	<5	<5	25.8
L0+90N 0+60EB (4170549)		15	0.007	2	1.7	<10	<5	12.2	<10	<10	5	0.03	<5	<5	27.1

Certified By:



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013		DATE RECEIVED: Mar 05, 2013					DATE REPORTED: Mar 12, 2013					SAMPLE TYPE: Soil			
	Analyte:	Rb	S	Sb	Sc	Se	Sn	Sr	Ta	Te	Th	Ti	Tl	U	V
	Unit:	ppm	%	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	10	0.005	1	0.5	10	5	0.5	10	10	5	0.01	5	5	0.5
L0+90N 0+60W (4170550)		23	0.037	19	14.2	<10	<5	1640	<10	<10	16	0.01	<5	7	73.9
L0+90N 0+75E (4170551)		14	0.017	2	1.8	<10	<5	20.0	<10	<10	<5	0.03	<5	<5	29.0
L1+05N 0+15W (4170552)		25	0.011	2	1.8	<10	<5	16.1	<10	<10	6	0.03	<5	<5	33.9
L1+05N 0+30W (4170553)		21	0.015	3	1.4	<10	<5	18.0	<10	<10	5	0.02	<5	<5	44.1
L1+05N 0+45W (4170554)		38	0.020	3	3.1	<10	<5	26.7	<10	<10	10	0.03	<5	5	51.8
L1+05N 0+60W (4170555)		<10	0.014	9	1.2	<10	<5	20.2	<10	<10	6	0.01	<5	<5	36.5
L60NE 0+30E (4170556)		29	0.053	3	5.0	<10	16	110	<10	<10	10	0.06	<5	<5	48.6
L60NE 0+45EA (4170557)		28	0.019	4	6.4	<10	7	30.2	<10	<10	10	0.06	<5	<5	47.4
L60NE 0+45EB (4170558)		27	0.034	4	5.1	<10	9	41.0	<10	<10	9	0.05	<5	<5	42.7
L60NE 0+60E (4170559)		20	0.011	1	4.5	<10	<5	14.8	<10	<10	7	0.04	<5	<5	44.6
L60NE 0+75E (4170560)		22	0.016	<1	2.2	<10	<5	17.4	<10	<10	<5	0.04	<5	<5	38.8
L60NE 0+90E (4170561)		<10	0.008	2	1.0	<10	<5	8.5	<10	<10	<5	0.02	<5	<5	25.1
L60NE 1+05E (4170562)		33	0.012	3	3.2	<10	<5	17.7	<10	<10	6	0.07	<5	<5	39.5
L60NE 1+20E (4170563)		19	0.011	1	1.9	<10	<5	13.5	<10	<10	5	0.04	<5	<5	35.7
L60NE 1+35E (4170564)		15	0.008	2	1.4	<10	<5	12.9	<10	<10	<5	0.03	<5	<5	23.5
L60NE 1+50E (4170565)		19	0.023	1	4.5	<10	8	32.9	<10	<10	9	0.05	<5	<5	40.2
L60NE 1+65E (4170566)		29	0.064	4	5.4	<10	25	141	<10	<10	10	0.05	<5	<5	41.1
L60NE 1+80E (4170567)		40	0.110	4	4.2	<10	19	122	<10	<10	7	0.05	<5	<5	43.4
L60NE 1+95E (4170568)		NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS
L60NE 0H5E (4170569)		23	0.069	2	4.1	<10	22	118	<10	<10	8	0.05	<5	<5	40.9
L90NE 15E (4170570)		11	0.006	3	2.3	<10	<5	10.7	<10	<10	6	0.03	<5	<5	32.2
L90NE 30E (4170571)		20	0.008	2	4.9	<10	<5	16.9	<10	<10	9	0.06	<5	<5	40.5
L90NE 45E (4170572)		22	0.018	<1	5.3	<10	8	26.0	<10	<10	9	0.06	<5	<5	41.0
L90NE 60E (4170573)		16	0.006	<1	3.5	<10	<5	11.4	<10	<10	7	0.05	<5	<5	34.1
L90NE 75EA (4170574)		18	0.009	2	2.6	<10	<5	13.3	<10	<10	5	0.03	<5	<5	36.1
L90NE 75EB (4170575)		18	0.010	2	2.7	<10	<5	13.5	<10	<10	6	0.03	<5	<5	37.1
L90NE 90E (4170576)		21	0.011	2	2.6	<10	<5	17.3	<10	<10	5	0.04	<5	<5	40.4
L90NE 105E (4170577)		19	0.009	2	3.5	<10	<5	14.1	<10	<10	7	0.05	<5	<5	39.8
L90NE 120E (4170578)		26	0.014	3	2.2	<10	<5	18.7	<10	<10	<5	0.03	<5	<5	33.0
L90NE 135E (4170579)		18	0.006	3	2.2	<10	<5	10.7	<10	<10	6	0.04	<5	<5	33.2
L90NE 150E (4170580)		42	0.058	4	7.4	<10	26	136	<10	<10	11	0.10	<5	<5	63.8
L90NE 165E (4170581)		40	0.031	2	8.0	<10	11	54.1	<10	<10	13	0.10	<5	<5	65.1

Certified By:



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013		DATE RECEIVED: Mar 05, 2013					DATE REPORTED: Mar 12, 2013					SAMPLE TYPE: Soil			
	Analyte:	Rb	S	Sb	Sc	Se	Sn	Sr	Ta	Te	Th	Ti	Tl	U	V
	Unit:	ppm	%	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	10	0.005	1	0.5	10	5	0.5	10	10	5	0.01	5	5	0.5
L90NE 180E (4170582)		18	0.028	3	3.7	<10	10	37.8	<10	<10	8	0.05	<5	<5	38.0
L90NE 195E (4170583)		27	0.036	2	5.0	<10	7	40.7	<10	<10	8	0.06	<5	<5	46.3
L120NE 152 (4170584)		18	0.012	2	1.6	<10	<5	12.9	<10	<10	6	0.03	<5	<5	24.4
L120NE 165EA (4170585)		19	0.009	2	2.0	<10	<5	12.9	<10	<10	6	0.03	<5	<5	28.7
L120NE 165EB (4170586)		17	0.010	3	1.8	<10	<5	13.8	<10	<10	6	0.03	<5	<5	26.9
L120NE 180E (4170587)		15	0.011	<1	3.8	<10	<5	17.7	<10	<10	7	0.05	<5	<5	34.8
L120NE 195E (4170588)		18	0.028	1	3.4	<10	7	33.0	<10	<10	7	0.04	<5	<5	37.8
L120NE 210E (4170589)		19	0.042	2	3.8	<10	17	77.7	<10	<10	8	0.05	<5	<5	37.6
L120NE 225E (4170590)		26	0.011	<1	4.0	<10	<5	19.4	<10	<10	8	0.04	<5	<5	38.6
L120NE 240E (4170591)		22	0.028	4	4.2	<10	<5	28.7	<10	<10	7	0.04	<5	<5	39.4
L120NE 255E (4170592)		<10	0.017	2	1.6	<10	6	38.3	<10	<10	6	0.03	<5	<5	17.7
L120NE 270E (4170593)		17	0.027	2	2.8	<10	6	34.5	<10	<10	6	0.03	<5	<5	30.6
L120NE 285E (4170594)		16	0.007	3	2.2	<10	<5	11.7	<10	<10	7	0.03	<5	<5	27.2
L120NE 300E (4170595)		17	0.007	<1	2.4	<10	<5	13.1	<10	<10	7	0.03	<5	<5	27.2
NSL150NE 150E (4170596)		NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS	NSS
L150NE 165E (4170597)		12	<0.005	2	1.7	<10	<5	6.7	<10	<10	7	0.04	<5	<5	26.1
L150NE 180E (4170598)		18	0.011	1	2.8	<10	<5	12.2	<10	<10	7	0.04	<5	<5	32.6
L150NE 195E (4170599)		18	0.008	1	2.1	<10	<5	9.7	<10	<10	6	0.03	<5	<5	25.4
L150NE 210E (4170600)		16	0.007	<1	2.1	<10	<5	13.0	<10	<10	6	0.03	<5	<5	24.5
L150NE 225E (4170601)		14	0.007	1	2.3	<10	<5	14.7	<10	<10	7	0.03	<5	<5	26.1
L150NE 240EA (4170602)		17	0.009	1	3.0	<10	<5	16.6	<10	<10	7	0.04	<5	<5	31.3
L150NE 240EB (4170603)		17	0.010	1	3.0	<10	<5	17.3	<10	<10	7	0.04	<5	<5	31.5
L150NE 255E (4170604)		<10	0.018	1	1.4	<10	5	38.6	<10	<10	6	0.02	<5	<5	16.7
L150NE 270E (4170605)		16	0.007	2	2.2	<10	<5	12.3	<10	<10	6	0.03	<5	<5	25.6
L150NE 285E (4170606)		14	0.005	<1	2.4	<10	<5	11.2	<10	<10	7	0.03	<5	<5	24.6
L150NE 300E (4170607)		17	0.007	<1	3.4	<10	<5	14.5	<10	<10	8	0.04	<5	<5	32.0
BL 0+30N (4170608)		23	0.018	3	4.6	<10	<5	27.6	<10	<10	8	0.04	<5	<5	44.3
BL 0+60NA (4170609)		<10	0.008	12	1.5	<10	<5	8.2	<10	<10	<5	<0.01	<5	<5	16.3
BL 0+60NB (4170610)		19	0.040	4	3.4	<10	9	57.2	<10	<10	8	0.04	<5	<5	37.7
BL 0+60NC (4170611)		19	0.044	3	3.1	<10	10	50.0	<10	<10	7	0.04	<5	<5	36.6
BL 0+90NA (4170612)		21	0.014	5	4.4	<10	<5	23.8	<10	<10	9	0.05	<5	<5	48.3
BL 0+90NB (4170613)		26	0.015	2	2.7	<10	<5	28.8	<10	<10	6	0.03	<5	6	34.5

Certified By:

Y. Chen



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013		DATE RECEIVED: Mar 05, 2013					DATE REPORTED: Mar 12, 2013				SAMPLE TYPE: Soil				
	Analyte:	Rb	S	Sb	Sc	Se	Sn	Sr	Ta	Te	Th	Ti	Tl	U	V
	Unit:	ppm	%	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	10	0.005	1	0.5	10	5	0.5	10	10	5	0.01	5	5	0.5
BL 1+05N (4170614)		23	0.007	2	1.8	<10	<5	12.2	<10	<10	6	0.04	<5	<5	32.4
BL 1+20N (4170615)		13	0.005	2	2.0	<10	<5	10.0	<10	<10	5	0.03	<5	<5	34.2
BL 1+50NA (4170616)		17	0.005	2	1.5	<10	<5	9.2	<10	<10	<5	0.04	<5	<5	27.6
BL 1+50NB (4170617)		15	0.005	3	1.4	<10	<5	8.4	<10	<10	<5	0.04	<5	<5	26.9
REDS 1 (4170618)		20	0.036	4	3.5	<10	10	45.3	<10	<10	8	0.04	<5	<5	30.5
REDS 2 (4170619)		18	0.049	4	3.5	<10	15	72.1	<10	<10	9	0.04	<5	<5	29.4
REDS 3 (4170620)		15	0.052	3	2.8	<10	13	68.5	<10	<10	9	0.04	<5	<5	26.8
REDS 4 (4170621)		21	0.046	2	4.5	<10	15	61.4	<10	<10	9	0.04	<5	<5	36.5
REDS 5 (4170622)		12	0.021	1	4.3	<10	<5	25.4	<10	<10	7	0.03	<5	<5	39.8
REDS 6 (4170623)		12	0.708	22	3.2	<10	<5	33.2	<10	<10	9	0.05	<5	<5	36.0
REDS 42 (4170624)		17	0.036	3	1.9	<10	9	73.5	<10	16	14	0.03	<5	11	29.1
RO-E-S1 (4170625)		27	0.013	4	5.4	<10	<5	16.7	<10	<10	7	0.05	<5	<5	43.0
RO-E-S2 (4170626)		16	0.006	1	2.0	<10	<5	9.7	<10	<10	<5	0.05	<5	<5	26.1
RO-E-S3 (4170627)		<10	0.006	<1	1.2	<10	<5	6.9	<10	<10	<5	0.02	<5	<5	28.9
RO-E-S4 (4170628)		21	0.010	2	1.6	<10	<5	10.3	<10	<10	<5	0.02	<5	<5	31.7

Certified By:



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013

DATE RECEIVED: Mar 05, 2013

DATE REPORTED: Mar 12, 2013

SAMPLE TYPE: Soil

Analyte:	W	Y	Zn	Zr
Unit:	ppm	ppm	ppm	ppm
RDL:	1	1	0.5	5
Sample ID (AGAT ID)				
L0+00 NE 0+15S (4170518)	<1	21	253	<5
L0+00 NE 0+30S (4170519)	<1	4	208	<5
L0+0 NE 0+45S (4170520)	<1	2	311	<5
L0+30N 0+25E (4170521)	<1	8	98.6	<5
L0+30N 0+70E (4170522)	<1	9	151	<5
L0+30N 0+85E (4170523)	<1	7	887	<5
L0+30N 1+00E (4170524)	<1	3	828	<5
L0+30NE 0+15E (4170525)	<1	2	158	<5
L0+30NE 0+30E (4170526)	<1	3	75.9	<5
L0+30NE 0+45EA (4170527)	<1	5	58.6	<5
L0+30NE 0+45EB (4170528)	<1	5	57.3	<5
L0+30NE 0+60E (4170529)	<1	2	58.9	<5
L0+30NE 0+75E (4170530)	<1	3	44.4	<5
L0+30NE 0+90E (4170531)	<1	2	56.6	<5
L0+30NE 1+05E (4170532)	<1	10	54.7	<5
L0+30W 0+40E (4170533)	<1	6	446	<5
L0+30W 0+55E (4170534)	<1	5	634	<5
L0+60N 0+15E (4170535)	<1	11	88.4	<5
L0+60NE 0+15E (4170536)	<1	2	291	<5
L0+60NE 0+30E (4170537)	<1	3	152	<5
L0+60NE 0+45E (4170538)	<1	3	125	<5
L0+60NE 0+60E (4170539)	<1	3	145	<5
L0+60NE 0+75E (4170540)	<1	3	58.4	<5
L0+60NE 0+90E (4170541)	<1	2	49.5	<5
L0+60NE 1+05E (4170542)	<1	9	43.7	<5
L0+90N 0+15E (4170543)	<1	2	160	<5
L0+90N 0+30E (4170544)	<1	4	249	<5
L0+90N 0+30W (4170545)	<1	3	1170	<5
L0+90N 0+45E (4170546)	<1	4	53.4	<5
L0+90N 0+45W (4170547)	<1	4	1010	<5
L0+90N 0+60EA (4170548)	<1	3	37.3	<5
L0+90N 0+60EB (4170549)	<1	3	44.5	<5

Certified By:



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013

DATE RECEIVED: Mar 05, 2013

DATE REPORTED: Mar 12, 2013

SAMPLE TYPE: Soil

Analyte:	W	Y	Zn	Zr
Unit:	ppm	ppm	ppm	ppm
RDL:	1	1	0.5	5
Sample ID (AGAT ID)				
L0+90N 0+60W (4170550)	<1	22	1080	<5
L0+90N 0+75E (4170551)	<1	3	33.6	<5
L1+05N 0+15W (4170552)	<1	3	393	<5
L1+05N 0+30W (4170553)	<1	3	480	<5
L1+05N 0+45W (4170554)	<1	10	606	<5
L1+05N 0+60W (4170555)	<1	3	133	<5
L60NE 0+30E (4170556)	<1	11	75.9	<5
L60NE 0+45EA (4170557)	<1	13	50.6	5
L60NE 0+45EB (4170558)	<1	11	46.2	<5
L60NE 0+60E (4170559)	<1	7	54.4	<5
L60NE 0+75E (4170560)	<1	2	48.3	<5
L60NE 0+90E (4170561)	<1	2	41.0	<5
L60NE 1+05E (4170562)	<1	4	59.1	<5
L60NE 1+20E (4170563)	<1	2	110	<5
L60NE 1+35E (4170564)	<1	2	75.2	<5
L60NE 1+50E (4170565)	<1	9	51.6	<5
L60NE 1+65E (4170566)	<1	11	110	<5
L60NE 1+80E (4170567)	<1	12	141	<5
L60NE 1+95E (4170568)	NSS	NSS	NSS	NSS
L60NE 0H5E (4170569)	<1	9	72.8	<5
L90NE 15E (4170570)	<1	4	26.7	<5
L90NE 30E (4170571)	<1	7	49.7	5
L90NE 45E (4170572)	<1	10	57.9	5
L90NE 60E (4170573)	<1	6	43.7	<5
L90NE 75EA (4170574)	<1	4	70.7	<5
L90NE 75EB (4170575)	<1	4	70.8	<5
L90NE 90E (4170576)	<1	3	83.6	<5
L90NE 105E (4170577)	<1	4	54.2	<5
L90NE 120E (4170578)	<1	3	58.1	<5
L90NE 135E (4170579)	<1	3	43.2	<5
L90NE 150E (4170580)	<1	12	100	6
L90NE 165E (4170581)	<1	13	94.8	9

Certified By:

Y. Chen.



Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013

DATE RECEIVED: Mar 05, 2013

DATE REPORTED: Mar 12, 2013

SAMPLE TYPE: Soil

Analyte:	W	Y	Zn	Zr
Unit:	ppm	ppm	ppm	ppm
RDL:	1	1	0.5	5
Sample ID (AGAT ID)				
L90NE 180E (4170582)	<1	9	61.2	<5
L90NE 195E (4170583)	<1	11	81.1	<5
L120NE 152 (4170584)	<1	3	35.1	<5
L120NE 165EA (4170585)	<1	5	43.8	<5
L120NE 165EB (4170586)	<1	4	41.0	<5
L120NE 180E (4170587)	<1	6	52.0	<5
L120NE 195E (4170588)	<1	8	67.1	<5
L120NE 210E (4170589)	<1	8	63.2	<5
L120NE 225E (4170590)	<1	8	65.6	<5
L120NE 240E (4170591)	<1	9	109	<5
L120NE 255E (4170592)	<1	5	32.3	<5
L120NE 270E (4170593)	<1	7	56.5	<5
L120NE 285E (4170594)	<1	4	46.1	<5
L120NE 300E (4170595)	<1	5	75.3	<5
NSL150NE 150E (4170596)	NSS	NSS	NSS	NSS
L150NE 165E (4170597)	<1	3	40.4	<5
L150NE 180E (4170598)	<1	6	48.0	<5
L150NE 195E (4170599)	<1	4	39.7	<5
L150NE 210E (4170600)	<1	5	58.7	<5
L150NE 225E (4170601)	<1	5	45.9	<5
L150NE 240EA (4170602)	<1	7	50.8	<5
L150NE 240EB (4170603)	<1	8	52.6	<5
L150NE 255E (4170604)	<1	5	30.3	<5
L150NE 270E (4170605)	<1	5	51.9	<5
L150NE 285E (4170606)	<1	6	41.3	<5
L150NE 300E (4170607)	<1	8	50.4	<5
BL 0+30N (4170608)	<1	9	202	<5
BL 0+60NA (4170609)	<1	1	284	<5
BL 0+60NB (4170610)	<1	8	97.8	<5
BL 0+60NC (4170611)	<1	8	102	<5
BL 0+90NA (4170612)	<1	8	73.1	<5
BL 0+90NB (4170613)	<1	4	199	<5

Certified By:



AGAT Laboratories

Certificate of Analysis

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013

DATE RECEIVED: Mar 05, 2013

DATE REPORTED: Mar 12, 2013

SAMPLE TYPE: Soil

Analyte:	W	Y	Zn	Zr
Unit:	ppm	ppm	ppm	ppm
RDL:	1	1	0.5	5
Sample ID (AGAT ID)				
BL 1+05N (4170614)	<1	3	85.1	<5
BL 1+20N (4170615)	<1	2	35.2	<5
BL 1+50NA (4170616)	<1	2	40.8	<5
BL 1+50NB (4170617)	<1	2	39.1	<5
REDS 1 (4170618)	<1	8	67.3	<5
REDS 2 (4170619)	<1	8	66.3	<5
REDS 3 (4170620)	<1	7	52.2	<5
REDS 4 (4170621)	<1	9	61.8	<5
REDS 5 (4170622)	<1	9	98.3	<5
REDS 6 (4170623)	<1	2	65.6	8
REDS 42 (4170624)	<1	6	27.4	<5
RO-E-S1 (4170625)	<1	9	64.3	<5
RO-E-S2 (4170626)	<1	2	29.8	<5
RO-E-S3 (4170627)	<1	2	66.5	<5
RO-E-S4 (4170628)	<1	2	65.0	<5

Comments: RDL - Reported Detection Limit
NSS - Not Sufficient Sample

Certified By:

Y. Chen



CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

Parameter	REPLICATE #1				REPLICATE #2				REPLICATE #3				REPLICATE #4			
	Sample ID	Original	Replicate	RPD	Sample ID	Original	Replicate	RPD	Sample ID	Original	Replicate	RPD	Sample ID	Original	Replicate	RPD
Ag	4170518	0.20	0.27	29.8%	4170530	< 0.2	< 0.2	0.0%	4170543	< 0.2	< 0.2	0.0%	4170555	1.85	1.84	0.5%
Al	4170518	0.70	0.69	1.4%	4170530	0.73	0.69	5.6%	4170543	0.715	0.722	1.0%	4170555	0.68	0.68	0.0%
As	4170518	26	22	16.7%	4170530	3	< 1		4170543	< 1	< 1	0.0%	4170555	40	41	2.5%
B	4170518	< 5	< 5	0.0%	4170530	< 5	< 5	0.0%	4170543	< 5	< 5	0.0%	4170555	< 5	< 5	0.0%
Ba	4170518	197	192	2.6%	4170530	206	202	2.0%	4170543	207	208	0.5%	4170555	120	121	0.8%
Be	4170518	0.6	0.7	15.4%	4170530	< 0.5	< 0.5	0.0%	4170543	< 0.5	< 0.5	0.0%	4170555	< 0.5	< 0.5	0.0%
Bi	4170518	13	13	0.0%	4170530	< 1	< 1	0.0%	4170543	< 1	< 1	0.0%	4170555	3	< 1	
Ca	4170518	0.58	0.58	0.0%	4170530	0.16	0.16	0.0%	4170543	0.17	0.17	0.0%	4170555	0.08	0.08	0.0%
Cd	4170518	2.1	2.7	25.0%	4170530	< 0.5	< 0.5	0.0%	4170543	0.7	0.6	15.4%	4170555	0.92	0.99	7.3%
Ce	4170518	27	32	16.9%	4170530	25	23	8.3%	4170543	23	23	0.0%	4170555	32	32	0.0%
Co	4170518	9.8	11.5	16.0%	4170530	5.13	5.05	1.6%	4170543	6.02	6.05	0.5%	4170555	3.05	2.93	4.0%
Cr	4170518	17.9	20.9	15.5%	4170530	18.1	17.7	2.2%	4170543	17.4	17.8	2.3%	4170555	12.6	12.2	3.2%
Cu	4170518	7.01	8.01	13.3%	4170530	5.2	5.1	1.9%	4170543	4.66	4.57	2.0%	4170555	12.0	12.1	0.8%
Fe	4170518	2.54	2.53	0.4%	4170530	1.35	1.33	1.5%	4170543	1.24	1.24	0.0%	4170555	1.22	1.24	1.6%
Ga	4170518	< 5	< 5	0.0%	4170530	< 5	< 5	0.0%	4170543	< 5	< 5	0.0%	4170555	< 5	< 5	0.0%
Hg	4170518	< 1	< 1	0.0%	4170530	< 1	< 1	0.0%	4170543	< 1	< 1	0.0%	4170555	< 1	< 1	0.0%
In	4170518	3	7		4170530	< 1	< 1	0.0%	4170543	2	< 1		4170555	3	3	0.0%
K	4170518	0.05	0.05	0.0%	4170530	0.057	0.054	5.4%	4170543	0.06	0.06	0.0%	4170555	0.03	0.03	0.0%
La	4170518	12	15	22.2%	4170530	11	10	9.5%	4170543	10	10	0.0%	4170555	14	14	0.0%
Li	4170518	9	9	0.0%	4170530	9	8	11.8%	4170543	9	9	0.0%	4170555	4	4	0.0%
Mg	4170518	0.089	0.085	4.6%	4170530	0.228	0.220	3.6%	4170543	0.164	0.165	0.6%	4170555	0.06	0.06	0.0%
Mn	4170518	171	202	16.6%	4170530	415	403	2.9%	4170543	385	379	1.6%	4170555	121	117	3.4%
Mo	4170518	4.7	4.3	8.9%	4170530	1.3	1.8		4170543	1.8	1.7	5.7%	4170555	2.39	2.35	1.7%
Na	4170518	< 0.01	< 0.01	0.0%	4170530	< 0.01	< 0.01	0.0%	4170543	< 0.01	< 0.01	0.0%	4170555	< 0.01	< 0.01	0.0%
Ni	4170518	40.8	48.0	16.2%	4170530	13.9	13.0	6.7%	4170543	10.3	10.3	0.0%	4170555	13.6	13.6	0.0%
P	4170518	1610	1890	16.0%	4170530	639	613	4.2%	4170543	733	727	0.8%	4170555	320	324	1.2%
Pb	4170518	33.9	40.4	17.5%	4170530	11.3	11.4	0.9%	4170543	14.7	13.7	7.0%	4170555	32.3	31.3	3.1%
Rb	4170518	9	11	20.0%	4170530	13	12	8.0%	4170543	19	19	0.0%	4170555	< 10	< 10	0.0%
S	4170518	0.018	0.018	0.0%	4170530	0.006	0.006	0.0%	4170543	0.0055	0.0060	8.7%	4170555	0.014	0.014	0.0%
Sb	4170518	11	9	20.0%	4170530	< 1	< 1	0.0%	4170543	< 1	1		4170555	9	9	0.0%
Sc	4170518	3.75	4.49	18.0%	4170530	1.7	1.6	6.1%	4170543	1.5	1.5	0.0%	4170555	1.2	1.2	0.0%



CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Se	4170518	< 10	< 10	0.0%	4170530	< 10	< 10	0.0%	4170543	< 10	< 10	0.0%	4170555	< 10	< 10	0.0%
Sn	4170518	< 5	< 5	0.0%	4170530	< 5	< 5	0.0%	4170543	< 5	< 5	0.0%	4170555	< 5	< 5	0.0%
Sr	4170518	24.8	24.4	1.6%	4170530	8.6	8.1	6.0%	4170543	8.64	9.11	5.3%	4170555	20.2	20.3	0.5%
Ta	4170518	< 10	< 10	0.0%	4170530	< 10	< 10	0.0%	4170543	< 10	< 10	0.0%	4170555	< 10	< 10	0.0%
Te	4170518	< 10	< 10	0.0%	4170530	< 10	< 10	0.0%	4170543	< 10	< 10	0.0%	4170555	< 10	< 10	0.0%
Th	4170518	6	9		4170530	6	5	18.2%	4170543	< 5	< 5	0.0%	4170555	6	6	0.0%
Ti	4170518	< 0.01	< 0.01	0.0%	4170530	0.03	0.03	0.0%	4170543	0.03	0.03	0.0%	4170555	0.01	0.01	0.0%
Tl	4170518	< 5	< 5	0.0%	4170530	< 5	< 5	0.0%	4170543	< 5	< 5	0.0%	4170555	< 5	< 5	0.0%
U	4170518	< 5	< 5	0.0%	4170530	< 5	< 5	0.0%	4170543	< 5	< 5	0.0%	4170555	< 5	< 5	0.0%
V	4170518	23.6	28.0	17.1%	4170530	28.4	27.1	4.7%	4170543	27.6	27.7	0.4%	4170555	36.5	34.9	4.5%
W	4170518	< 1	< 1	0.0%	4170530	< 1	< 1	0.0%	4170543	< 1	< 1	0.0%	4170555	< 1	< 1	0.0%
Y	4170518	21	25	17.4%	4170530	3	3	0.0%	4170543	2	2	0.0%	4170555	3	3	0.0%
Zn	4170518	253	297	16.0%	4170530	44.4	42.0	5.6%	4170543	160	159	0.6%	4170555	133	132	0.8%
Zr	4170518	< 5	< 5	0.0%	4170530	< 5	< 5	0.0%	4170543	< 5	< 5	0.0%	4170555	< 5	< 5	0.0%

	REPLICATE #5				REPLICATE #6				REPLICATE #7				REPLICATE #8			
Parameter	Sample ID	Original	Replicate	RPD	Sample ID	Original	Replicate	RPD	Sample ID	Original	Replicate	RPD	Sample ID	Original	Replicate	RPD
Ag	4170569	0.2	0.2	0.0%	4170581	< 0.2	< 0.2	0.0%	4170593	< 0.2	< 0.2	0.0%	4170605	< 0.2	< 0.2	0.0%
Al	4170569	0.885	0.891	0.7%	4170581	1.75	1.79	2.3%	4170593	0.72	0.72	0.0%	4170605	0.73	0.73	0.0%
As	4170569	4	6		4170581	13	9		4170593	1	< 1		4170605	2	5	
B	4170569	7	6	15.4%	4170581	7	6	15.4%	4170593	< 5	< 5	0.0%	4170605	< 5	< 5	0.0%
Ba	4170569	355	360	1.4%	4170581	513	535	4.2%	4170593	182	186	2.2%	4170605	269	272	1.1%
Be	4170569	< 0.5	< 0.5	0.0%	4170581	0.8	0.8	0.0%	4170593	< 0.5	< 0.5	0.0%	4170605	< 0.5	< 0.5	0.0%
Bi	4170569	18	17	5.7%	4170581	14	14	0.0%	4170593	2	2	0.0%	4170605	6	< 1	
Ca	4170569	4.50	4.57	1.5%	4170581	1.59	1.67	4.9%	4170593	1.20	1.21	0.8%	4170605	0.22	0.22	0.0%
Cd	4170569	0.43	0.51	17.0%	4170581	< 0.5	< 0.5	0.0%	4170593	< 0.5	< 0.5	0.0%	4170605	< 0.5	< 0.5	0.0%
Ce	4170569	27	27	0.0%	4170581	41	41	0.0%	4170593	24	25	4.1%	4170605	25	24	4.1%
Co	4170569	7.95	7.92	0.4%	4170581	13.9	13.9	0.0%	4170593	7.8	7.9	1.3%	4170605	6.5	6.5	0.0%
Cr	4170569	26.4	26.1	1.1%	4170581	47.4	47.3	0.2%	4170593	21.1	20.1	4.9%	4170605	17.9	18.0	0.6%
Cu	4170569	19.6	19.5	0.5%	4170581	34.9	35.2	0.9%	4170593	16.0	15.8	1.3%	4170605	6.18	6.10	1.3%
Fe	4170569	1.83	1.85	1.1%	4170581	2.97	3.05	2.7%	4170593	1.56	1.56	0.0%	4170605	1.41	1.41	0.0%
Ga	4170569	< 5	< 5	0.0%	4170581	5	5	0.0%	4170593	< 5	< 5	0.0%	4170605	< 5	< 5	0.0%
Hg	4170569	< 1	< 1	0.0%	4170581	< 1	< 1	0.0%	4170593	< 1	< 1	0.0%	4170605	3	< 1	
In	4170569	< 1	< 1	0.0%	4170581	2	3		4170593	1	< 1		4170605	3	5	
K	4170569	0.095	0.095	0.0%	4170581	0.305	0.312	2.3%	4170593	0.11	0.11	0.0%	4170605	0.11	0.11	0.0%



CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

La	4170569	12	12	0.0%	4170581	18	18	0.0%	4170593	10	11	9.5%	4170605	11	10	9.5%
Li	4170569	11	11	0.0%	4170581	17	17	0.0%	4170593	10	10	0.0%	4170605	9	9	0.0%
Mg	4170569	1.04	1.05	1.0%	4170581	0.906	0.935	3.2%	4170593	0.50	0.50	0.0%	4170605	0.263	0.268	1.9%
Mn	4170569	337	330	2.1%	4170581	789	800	1.4%	4170593	385	383	0.5%	4170605	410	417	1.7%
Mo	4170569	4.32	4.75	9.5%	4170581	2.6	2.5	3.9%	4170593	2.99	2.72	9.5%	4170605	2.98	2.23	28.8%
Na	4170569	0.01	0.01	0.0%	4170581	0.02	0.02	0.0%	4170593	0.01	0.01	0.0%	4170605	< 0.01	< 0.01	0.0%
Ni	4170569	28.8	28.6	0.7%	4170581	45.4	45.9	1.1%	4170593	26.0	26.2	0.8%	4170605	18.2	18.4	1.1%
P	4170569	939	910	3.1%	4170581	469	467	0.4%	4170593	606	595	1.8%	4170605	435	453	4.1%
Pb	4170569	14.1	15.5	9.5%	4170581	24.3	25.6	5.2%	4170593	12.8	12.3	4.0%	4170605	10.4	11.9	13.5%
Rb	4170569	23	23	0.0%	4170581	40	41	2.5%	4170593	17	17	0.0%	4170605	16	16	0.0%
S	4170569	0.0694	0.0707	1.9%	4170581	0.031	0.032	3.2%	4170593	0.027	0.027	0.0%	4170605	0.0074	0.0083	11.5%
Sb	4170569	2	4		4170581	2	3		4170593	2	2	0.0%	4170605	2	< 1	
Sc	4170569	4.10	3.92	4.5%	4170581	8.0	8.0	0.0%	4170593	2.78	2.73	1.8%	4170605	2.2	2.2	0.0%
Se	4170569	< 10	< 10	0.0%	4170581	< 10	< 10	0.0%	4170593	< 10	< 10	0.0%	4170605	< 10	< 10	0.0%
Sn	4170569	22	21	4.7%	4170581	11	12	8.7%	4170593	6	5	18.2%	4170605	< 5	< 5	0.0%
Sr	4170569	118	121	2.5%	4170581	54.1	56.5	4.3%	4170593	34.5	35.2	2.0%	4170605	12.3	12.6	2.4%
Ta	4170569	< 10	< 10	0.0%	4170581	< 10	< 10	0.0%	4170593	< 10	< 10	0.0%	4170605	< 10	< 10	0.0%
Te	4170569	< 10	< 10	0.0%	4170581	< 10	< 10	0.0%	4170593	< 10	< 10	0.0%	4170605	< 10	< 10	0.0%
Th	4170569	8	8	0.0%	4170581	13	11	16.7%	4170593	6	7	15.4%	4170605	6	6	0.0%
Ti	4170569	0.05	0.05	0.0%	4170581	0.10	0.10	0.0%	4170593	0.03	0.03	0.0%	4170605	0.03	0.03	0.0%
Tl	4170569	< 5	< 5	0.0%	4170581	< 5	< 5	0.0%	4170593	< 5	< 5	0.0%	4170605	< 5	< 5	0.0%
U	4170569	< 5	< 5	0.0%	4170581	< 5	< 5	0.0%	4170593	< 5	< 5	0.0%	4170605	< 5	< 5	0.0%
V	4170569	40.9	40.6	0.7%	4170581	65.1	64.9	0.3%	4170593	30.6	30.4	0.7%	4170605	25.6	26.0	1.6%
W	4170569	< 1	< 1	0.0%	4170581	< 1	< 1	0.0%	4170593	< 1	< 1	0.0%	4170605	< 1	< 1	0.0%
Y	4170569	9	9	0.0%	4170581	13	13	0.0%	4170593	7	7	0.0%	4170605	5	5	0.0%
Zn	4170569	72.8	72.1	1.0%	4170581	94.8	95.2	0.4%	4170593	56.5	57.8	2.3%	4170605	51.9	53.7	3.4%
Zr	4170569	< 5	< 5	0.0%	4170581	9	8	11.8%	4170593	< 5	< 5	0.0%	4170605	< 5	< 5	0.0%

REPLICATE #9																			
Parameter	Sample ID	Original	Replicate	RPD															
Ag	4170618	< 0.2	< 0.2	0.0%															
Al	4170618	0.825	0.821	0.5%															
As	4170618	19	12																
B	4170618	5	5	0.0%															
Ba	4170618	282	274	2.9%															



CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Be	4170618	< 0.5	< 0.5	0.0%												
Bi	4170618	7	8	13.3%												
Ca	4170618	1.96	1.93	1.5%												
Cd	4170618	0.60	0.69	14.0%												
Ce	4170618	31	32	3.2%												
Co	4170618	8.1	8.5	4.8%												
Cr	4170618	21.1	21.3	0.9%												
Cu	4170618	15.1	14.7	2.7%												
Fe	4170618	1.74	1.73	0.6%												
Ga	4170618	< 5	< 5	0.0%												
Hg	4170618	< 1	< 1	0.0%												
In	4170618	5	4	22.2%												
K	4170618	0.10	0.10	0.0%												
La	4170618	14	14	0.0%												
Li	4170618	10	10	0.0%												
Mg	4170618	0.449	0.433	3.6%												
Mn	4170618	322	323	0.3%												
Mo	4170618	4.3	3.6	17.7%												
Na	4170618	0.01	0.01	0.0%												
Ni	4170618	23.9	23.8	0.4%												
P	4170618	475	456	4.1%												
Pb	4170618	15.6	15.8	1.3%												
Rb	4170618	20	20	0.0%												
S	4170618	0.0358	0.0355	0.8%												
Sb	4170618	4	1													
Sc	4170618	3.5	3.5	0.0%												
Se	4170618	< 10	< 10	0.0%												
Sn	4170618	10	11	9.5%												
Sr	4170618	45.3	44.7	1.3%												
Ta	4170618	< 10	< 10	0.0%												
Te	4170618	< 10	< 10	0.0%												
Th	4170618	8	8	0.0%												
Ti	4170618	0.04	0.04	0.0%												
Tl	4170618	< 5	< 5	0.0%												



AGAT Laboratories

Quality Assurance - Replicate

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

U	4170618	< 5	< 5	0.0%												
V	4170618	30.5	30.6	0.3%												
W	4170618	< 1	< 1	0.0%												
Y	4170618	8	8	0.0%												
Zn	4170618	67.3	67.5	0.3%												
Zr	4170618	< 5	< 5	0.0%												



CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

	CRM #1 (CU186)				CRM #2 (CU186)				CRM #3 (CU186)				CRM #4 (CU186)			
Parameter	Expect	Actual	Recovery	Limits	Expect	Actual	Recovery	Limits	Expect	Actual	Recovery	Limits	Expect	Actual	Recovery	Limits
Ag	14	15	105%	80% - 120%	14	15	105%	80% - 120%	14	14	100%	80% - 120%	14	14	100%	80% - 120%
Cu	6000	6396	107%	80% - 120%	6000	6507	108%	80% - 120%	6000	6377	106%	80% - 120%	6000	6246	104%	80% - 120%
Mo	360	385	107%	80% - 120%	360	390	108%	80% - 120%	360	375	104%	80% - 120%	360	366	102%	80% - 120%
	CRM #5 (CU186)				CRM #6 (CU186)				CRM #7 (CU186)				CRM #8 (CU186)			
Parameter	Expect	Actual	Recovery	Limits	Expect	Actual	Recovery	Limits	Expect	Actual	Recovery	Limits	Expect	Actual	Recovery	Limits
Ag	14	14	98%	80% - 120%	14	13	96%	80% - 120%	14	14	98%	80% - 120%	14	14	103%	80% - 120%
Cu	6000	6389	106%	80% - 120%	6000	6285	105%	80% - 120%	6000	6258	104%	80% - 120%	6000	6455	108%	80% - 120%
Mo	360	377	105%	80% - 120%	360	370	103%	80% - 120%	360	368	102%	80% - 120%	360	387	108%	80% - 120%

Method Summary

CLIENT NAME: HOMEGOLD RESOURCES LTD.

AGAT WORK ORDER: 13V694091

PROJECT NO: ROAM

ATTENTION TO: JO SHEARER

PARAMETER	AGAT S.O.P	LITERATURE REFERENCE	ANALYTICAL TECHNIQUE
Solid Analysis			
Sample Login Weight	MIN-12009		BALANCE
Ag	MIN-200-12020		ICP/OES
Al	MIN-200-12020		ICP/OES
As	MIN-200-12020		ICP/OES
B	MIN-200-12020		ICP/OES
Ba	MIN-200-12020		ICP/OES
Be	MIN-200-12020		ICP/OES
Bi	MIN-200-12020		ICP/OES
Ca	MIN-200-12020		ICP/OES
Cd	MIN-200-12020		ICP/OES
Ce	MIN-200-12020		ICP/OES
Co	MIN-200-12020		ICP/OES
Cr	MIN-200-12020		ICP/OES
Cu	MIN-200-12020		ICP/OES
Fe	MIN-200-12020		ICP/OES
Ga	MIN-200-12020		ICP/OES
Hg	MIN-200-12020		ICP/OES
In	MIN-200-12020		ICP/OES
K	MIN-200-12020		ICP/OES
La	MIN-200-12020		ICP/OES
Li	MIN-200-12020		ICP/OES
Mg	MIN-200-12020		ICP/OES
Mn	MIN-200-12020		ICP/OES
Mo	MIN-200-12020		ICP/OES
Na	MIN-200-12020		ICP/OES
Ni	MIN-200-12020		ICP/OES
P	MIN-200-12020		ICP/OES
Pb	MIN-200-12020		ICP/OES
Rb	MIN-200-12020		ICP/OES
S	MIN-200-12020		ICP/OES
Sb	MIN-200-12020		ICP/OES
Sc	MIN-200-12020		ICP/OES
Se	MIN-200-12020		ICP/OES
Sn	MIN-200-12020		ICP/OES
Sr	MIN-200-12020		ICP/OES
Ta	MIN-200-12020		ICP/OES
Te	MIN-200-12020		ICP/OES
Th	MIN-200-12020		ICP/OES
Ti	MIN-200-12020		ICP/OES
Tl	MIN-200-12020		ICP/OES
U	MIN-200-12020		ICP/OES
V	MIN-200-12020		ICP/OES
W	MIN-200-12020		ICP/OES
Y	MIN-200-12020		ICP/OES
Zn	MIN-200-12020		ICP/OES
Zr	MIN-200-12020		ICP/OES

CLIENT NAME: HOMEGOLD RESOURCES LTD.
UNIT# 5-2330 TYNER STREET
PORT COQUITLAM, BC V3C2Z1
(604) 696-1022

ATTENTION TO: JO SHEARER

PROJECT NO: ROAM

AGAT WORK ORDER: 13V693961

SOLID ANALYSIS REVIEWED BY: Kevin Motomura, ICP Supervisor

DATE REPORTED: Mar 21, 2013

PAGES (INCLUDING COVER): 15

Should you require any information regarding this analysis please contact your client services representative at (905) 501-9998

*NOTES



Certificate of Analysis

AGAT WORK ORDER: 13V693961

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013

DATE RECEIVED: Mar 05, 2013

DATE REPORTED: Mar 21, 2013

SAMPLE TYPE: Rock

Analyte:	Sample Login Weight	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Ce	Co	Cr	Cu
Unit:	kg	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm
RDL:	0.01	0.2	0.01	1	5	1	0.5	1	0.01	0.5	1	0.5	0.5	0.5
Sample ID (AGAT ID)														
RED 1 (4169610)	1.61	<0.2	0.09	28	<5	46	<0.5	3	0.53	1.2	3	1.9	126	3.7
RED 2 (4169611)	1.36	<0.2	0.05	6	<5	31	<0.5	1	0.12	2.9	4	1.7	164	3.5
RED 3 (4169612)	1.14	<0.2	0.29	5	<5	2570	<0.5	3	0.05	<0.5	34	5.6	17.0	12.1
RED 4 (4169613)	0.99	<0.2	0.11	87	<5	163	<0.5	2	0.32	<0.5	10	3.0	107	20.1
RED 5 (4169614)	1.07	0.3	0.18	1	<5	99	<0.5	<1	0.01	<0.5	11	<0.5	74.0	2.5
RED 6 (4169615)	0.62	0.6	0.10	33	<5	112	<0.5	<1	0.39	<0.5	5	2.0	132	15.1
RED 7 (4169616)	0.95	<0.2	2.18	8	<5	67	0.8	<1	1.32	<0.5	83	26.7	34.1	56.9
RED 8 (4169617)	1.14	<0.2	1.82	6	<5	95	0.7	<1	0.12	<0.5	86	8.6	13.9	44.0
RED 9 (4169618)	0.83	<0.2	1.42	5	<5	83	0.6	6	0.17	<0.5	47	16.2	6.2	38.1
RED 10 (4169619)	1.00	0.3	0.13	6	<5	15	<0.5	10	2.79	0.6	2	10.1	118	13.3
RED 12 (4169620)	1.26	0.5	0.08	13	<5	47	<0.5	14	9.74	<0.5	11	1.5	47.9	1.5
RED 13 (4169621)	0.90	0.3	0.07	4	<5	30	<0.5	8	4.65	<0.5	7	1.5	85.1	2.3
RED 14 (4169622)	1.35	0.2	0.12	12	<5	49	<0.5	1	0.95	<0.5	7	2.4	87.3	4.3
RED 15 (4169623)	1.28	<0.2	0.05	5	<5	30	<0.5	2	0.11	<0.5	5	1.5	125	6.5
RED 16 (4169624)	1.37	<0.2	0.07	10	<5	53	<0.5	3	1.64	<0.5	5	1.0	102	5.6
RED 17 (4169625)	1.07	<0.2	0.12	28	<5	55	<0.5	<1	0.15	<0.5	25	2.1	116	3.0
RED 18 (4169626)	1.65	<0.2	0.06	2	<5	32	<0.5	4	0.80	0.9	3	1.9	125	3.1
RED 19 (4169627)	1.53	<0.2	0.04	6	<5	26	<0.5	1	0.52	2.1	4	2.2	146	3.5
RED 20 (4169628)	1.56	<0.2	0.09	19	<5	29	<0.5	6	0.12	6.3	1	1.8	161	8.9
RED 21 (4169629)	0.84	0.3	1.70	19	<5	53	<0.5	12	7.55	<0.5	38	15.2	25.4	23.8
RED 22 (4169630)	0.64	0.5	0.17	<1	<5	209	<0.5	<1	0.06	<0.5	1	<0.5	64.1	1.7
RED 23 (4169631)	0.69	0.6	0.11	1	<5	241	<0.5	<1	0.03	<0.5	2	0.6	147	3.6
RED 24 (4169632)	0.75	0.4	0.10	<1	<5	163	<0.5	<1	0.01	<0.5	<1	<0.5	142	2.9
RED 25 (4169633)	0.64	0.2	0.10	<1	<5	70	<0.5	<1	<0.01	<0.5	7	<0.5	110	2.5
RED 26 (4169634)	0.64	1.3	0.19	21	<5	150	<0.5	31	>25	<0.5	7	6.4	5.7	22.2
RED 27 (4169635)	0.64	<0.2	1.94	10	<5	45	<0.5	5	6.13	<0.5	34	8.2	19.8	11.6
RED 30 (4169636)	0.54	<0.2	1.25	6	<5	57	0.6	<1	1.31	<0.5	57	11.6	20.0	23.9
RED 31 (4169637)	1.13	<0.2	0.09	18	<5	2970	<0.5	<1	0.07	<0.5	4	2.1	167	10.6
RED 32 (4169638)	0.78	2.2	0.10	122	<5	8	<0.5	<1	0.26	0.5	1	3.9	123	84.8
RED 33 (4169639)	0.82	>100	0.03	35	<5	40	<0.5	9	0.59	21.0	1	1.1	154	15.4
RED 34 (4169640)	0.94	5.6	0.09	104	<5	149	<0.5	7	4.29	69.4	3	9.5	141	419

Certified By:



AGAT Laboratories

Certificate of Analysis

AGAT WORK ORDER: 13V693961

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013			DATE RECEIVED: Mar 05, 2013				DATE REPORTED: Mar 21, 2013				SAMPLE TYPE: Rock				
	Analyte:	Sample Login Weight	Ag	Al	As	B	Ba	Be	Bi	Ca	Cd	Ce	Co	Cr	Cu
	Unit:	kg	ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	0.01	0.2	0.01	1	5	1	0.5	1	0.01	0.5	1	0.5	0.5	0.5
RED 35 (4169641)		0.59	0.4	0.07	41	<5	234	<0.5	4	0.63	0.7	3	3.2	131	13.5
RED 36 (4169642)		0.75	0.2	0.02	2	<5	21	<0.5	3	2.42	2.3	<1	1.3	147	4.6
RED 37 (4169643)		0.77	0.4	0.09	17	<5	72	<0.5	16	4.48	3.9	3	6.8	121	8.6
RED 38 (4169644)		0.83	0.7	0.06	26	<5	40	<0.5	10	3.61	10.9	2	6.3	122	116
RED 39 (4169645)		0.60	0.3	0.32	25	<5	112	0.6	<1	0.08	1.0	12	8.8	17.8	33.9
RCD 1 (4169646)		1.25	<0.2	0.11	36	<5	119	<0.5	<1	0.14	1.0	14	5.3	80.0	6.7
RCD 2 (4169647)		1.49	<0.2	0.10	52	<5	105	<0.5	9	1.43	0.8	11	4.5	79.0	8.5
RCD 3 (4169648)		1.62	<0.2	0.09	34	<5	96	<0.5	5	1.06	0.9	12	4.3	102	7.5
RCD 4 (4169649)		3.28	<0.2	0.07	18	<5	83	<0.5	9	1.94	1.0	10	4.3	78.6	9.6
RCD 5 (4169650)		1.95	0.2	0.10	22	<5	110	<0.5	5	0.77	<0.5	10	4.6	71.6	29.3
RCD 6 (4169651)		1.78	<0.2	0.11	23	<5	116	<0.5	<1	0.40	<0.5	11	3.7	95.6	23.3
RCD 7 (4169652)		1.46	0.6	0.13	44	<5	141	<0.5	2	0.26	1.1	11	12.7	64.9	56.9
RCD 8 (4169653)		1.79	<0.2	0.06	14	<5	73	<0.5	<1	0.12	28.2	6	2.8	100	6.4
RCD 9 (4169654)		2.89	<0.2	0.05	42	<5	50	<0.5	<1	0.04	48.4	5	2.1	162	568
RCD 10 (4169655)		1.87	0.4	0.10	45	<5	112	<0.5	<1	0.07	52.2	15	4.1	91.4	10.9
RCD 11 (4169656)		1.44	0.2	0.08	25	<5	73	<0.5	9	0.52	148	9	4.9	127	17.1
RCD 12 (4169657)		2.34	0.3	0.08	29	<5	74	<0.5	11	1.71	196	9	6.1	124	19.9
MS-01R (4169658)		1.78	98.5	0.08	381	<5	55	<0.5	<1	0.44	12.0	3	7.5	79.4	>10000
MS-02R (4169659)		1.74	>100	0.07	262	<5	60	<0.5	17	1.10	581	5	3.9	61.0	6769
MS-03R (4169660)		1.01	88.4	0.10	81	<5	73	<0.5	14	0.99	161	2	2.8	129	1527
MS-04R (4169661)		2.49	>100	0.10	103	<5	39	<0.5	22	0.57	301	2	2.0	74.8	1656
RO-E-1 (4169662)		0.98	1.0	0.05	8	<5	10	<0.5	3	0.29	8.4	<1	1.2	167	36.0
RO-E-3 (4169663)		0.73	0.5	1.21	3	<5	75	0.8	<1	0.31	<0.5	49	13.6	22.2	29.0
RO-E-5 (4169664)		0.84	0.8	0.06	17	<5	25	<0.5	17	13.5	<0.5	11	2.2	84.1	5.1
RO-E-7 (4169665)		0.92	0.7	0.12	10	<5	56	<0.5	16	3.80	<0.5	12	1.8	85.1	3.2
RO-E-9 (4169666)		0.86	<0.2	0.06	19	<5	31	<0.5	6	0.32	<0.5	11	2.0	156	4.2

Certified By:



Certificate of Analysis

AGAT WORK ORDER: 13V693961

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013		DATE RECEIVED: Mar 05, 2013					DATE REPORTED: Mar 21, 2013					SAMPLE TYPE: Rock			
	Analyte:	Fe	Ga	Hg	In	K	La	Li	Mg	Mn	Mo	Na	Ni	P	Pb
	Unit:	%	ppm	ppm	ppm	%	ppm	ppm	%	ppm	ppm	%	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	0.01	5	1	1	0.01	1	1	0.01	1	0.5	0.01	0.5	10	0.5
RED 1 (4169610)		0.60	<5	2	<1	0.04	<1	<1	0.01	161	5.5	<0.01	11.2	776	3.0
RED 2 (4169611)		0.49	<5	<1	<1	0.02	<1	<1	<0.01	137	2.5	<0.01	8.9	523	2.1
RED 3 (4169612)		1.85	<5	<1	<1	0.20	13	3	0.05	632	0.8	<0.01	14.1	236	3.4
RED 4 (4169613)		0.75	<5	<1	<1	0.06	2	<1	0.01	702	3.6	<0.01	13.9	1340	1.3
RED 5 (4169614)		0.26	<5	<1	<1	0.08	5	2	<0.01	22	3.7	0.02	2.0	39	4.6
RED 6 (4169615)		3.01	<5	<1	3	0.05	2	1	0.02	121	10.5	<0.01	9.9	136	37.8
RED 7 (4169616)		5.83	6	4	<1	0.12	39	123	0.60	262	3.4	0.01	34.0	2840	16.8
RED 8 (4169617)		6.31	8	2	4	0.25	37	92	0.42	203	1.2	<0.01	19.0	1280	25.8
RED 9 (4169618)		4.42	<5	<1	<1	0.21	14	69	0.38	105	1.7	<0.01	30.8	574	23.5
RED 10 (4169619)		1.46	<5	3	<1	0.02	<1	7	0.05	614	5.5	<0.01	24.3	236	64.4
RED 12 (4169620)		0.46	<5	<1	<1	0.04	5	<1	0.04	548	8.3	<0.01	3.3	1110	5.6
RED 13 (4169621)		0.67	<5	1	<1	0.04	3	<1	0.05	688	6.2	<0.01	6.7	930	7.4
RED 14 (4169622)		1.21	<5	<1	<1	0.06	2	<1	0.04	616	3.7	<0.01	16.5	754	5.5
RED 15 (4169623)		0.69	<5	<1	<1	0.03	2	<1	<0.01	216	3.4	<0.01	8.1	414	18.0
RED 16 (4169624)		0.57	<5	1	<1	0.03	2	<1	0.02	233	4.7	<0.01	10.0	489	8.3
RED 17 (4169625)		0.75	<5	<1	<1	0.07	10	<1	<0.01	180	2.7	<0.01	14.4	594	4.1
RED 18 (4169626)		0.81	<5	2	<1	0.03	<1	<1	0.09	378	4.9	<0.01	8.8	779	5.6
RED 19 (4169627)		0.64	<5	2	<1	0.02	1	<1	0.10	262	4.3	<0.01	9.1	713	23.2
RED 20 (4169628)		1.14	<5	<1	<1	0.03	<1	<1	<0.01	469	3.6	<0.01	14.3	511	10.2
RED 21 (4169629)		3.39	6	4	<1	0.16	18	64	1.30	454	5.3	0.02	24.0	447	17.9
RED 22 (4169630)		0.13	<5	<1	<1	0.09	<1	2	0.01	11	1.5	<0.01	1.2	<10	11.8
RED 23 (4169631)		0.26	<5	1	2	0.05	<1	<1	<0.01	23	4.2	<0.01	3.3	<10	15.2
RED 24 (4169632)		0.19	<5	<1	2	0.05	<1	<1	<0.01	18	2.4	<0.01	3.0	<10	14.1
RED 25 (4169633)		0.16	<5	<1	<1	0.05	2	<1	<0.01	13	1.6	<0.01	2.2	16	6.6
RED 26 (4169634)		1.45	<5	4	5	0.11	3	3	0.19	723	13.8	0.02	15.8	213	1.0
RED 27 (4169635)		2.70	5	5	<1	0.11	16	79	1.27	342	4.8	<0.01	17.5	494	16.7
RED 30 (4169636)		3.40	<5	1	1	0.11	25	47	0.73	598	3.4	0.01	28.1	377	10.2
RED 31 (4169637)		0.95	<5	<1	2	0.03	1	1	0.02	162	2.6	<0.01	9.3	235	53.9
RED 32 (4169638)		18.7	11	8	4	0.05	<1	<1	0.01	79	2.3	<0.01	33.4	53	88.0
RED 33 (4169639)		0.75	<5	3	<1	0.02	<1	<1	0.12	327	3.8	<0.01	5.5	52	>10000
RED 34 (4169640)		3.04	<5	3	4	0.06	1	2	0.94	1740	10.3	<0.01	18.5	135	6470
RED 35 (4169641)		0.68	<5	2	<1	0.04	<1	<1	0.25	797	4.2	<0.01	16.5	229	261

Certified By:



Certificate of Analysis

AGAT WORK ORDER: 13V693961

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013		DATE RECEIVED: Mar 05, 2013					DATE REPORTED: Mar 21, 2013					SAMPLE TYPE: Rock			
	Analyte:	Fe	Ga	Hg	In	K	La	Li	Mg	Mn	Mo	Na	Ni	P	Pb
	Unit:	%	ppm	ppm	ppm	%	ppm	ppm	%	ppm	ppm	%	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	0.01	5	1	1	0.01	1	1	0.01	1	0.5	0.01	0.5	10	0.5
RED 36 (4169642)		1.96	<5	1	<1	0.01	<1	<1	0.50	732	5.2	<0.01	10.8	126	53.2
RED 37 (4169643)		3.40	<5	3	1	0.05	1	1	0.82	1850	5.6	<0.01	26.6	196	48.3
RED 38 (4169644)		3.41	<5	1	2	0.03	1	<1	0.60	1500	5.6	<0.01	20.4	229	362
RED 39 (4169645)		2.41	<5	<1	5	0.15	3	1	0.02	235	60.5	0.02	55.4	214	29.9
RCD 1 (4169646)		0.90	<5	<1	2	0.07	3	1	<0.01	195	2.7	<0.01	12.6	245	14.9
RCD 2 (4169647)		1.03	<5	1	<1	0.06	2	<1	0.02	315	5.2	<0.01	9.6	238	28.8
RCD 3 (4169648)		1.01	<5	2	<1	0.05	2	<1	0.01	358	4.2	<0.01	11.7	233	32.6
RCD 4 (4169649)		1.44	<5	2	<1	0.05	2	<1	0.05	431	6.8	<0.01	11.3	222	17.7
RCD 5 (4169650)		1.05	<5	2	<1	0.06	2	1	0.02	330	3.3	<0.01	11.1	241	5.1
RCD 6 (4169651)		1.02	<5	<1	3	0.07	2	<1	0.01	213	2.4	<0.01	8.9	223	9.8
RCD 7 (4169652)		1.32	<5	<1	<1	0.08	2	1	0.01	405	3.3	<0.01	19.5	314	38.7
RCD 8 (4169653)		1.08	<5	2	<1	0.04	1	<1	0.01	543	2.1	<0.01	7.9	126	47.5
RCD 9 (4169654)		0.76	<5	<1	<1	0.03	1	<1	<0.01	261	1.7	<0.01	7.7	126	2140
RCD 10 (4169655)		1.01	<5	<1	<1	0.06	3	<1	0.02	322	1.7	<0.01	8.1	102	373
RCD 11 (4169656)		1.28	<5	1	<1	0.04	2	<1	0.13	440	3.8	<0.01	11.5	128	186
RCD 12 (4169657)		2.13	<5	3	<1	0.05	2	<1	0.20	1360	5.8	<0.01	16.2	193	408
MS-01R (4169658)		1.77	<5	<1	3	0.04	<1	<1	0.07	269	3.4	<0.01	18.3	105	>10000
MS-02R (4169659)		1.91	<5	9	<1	0.04	1	<1	0.30	459	2.6	<0.01	19.3	156	>10000
MS-03R (4169660)		1.33	<5	6	<1	0.05	<1	<1	0.27	538	3.6	<0.01	8.8	70	>10000
MS-04R (4169661)		0.96	<5	7	<1	0.06	<1	<1	0.16	283	2.4	<0.01	7.6	120	>10000
RO-E-1 (4169662)		0.48	<5	<1	<1	<0.01	<1	<1	0.02	128	2.7	<0.01	10.5	308	827
RO-E-3 (4169663)		3.67	<5	4	<1	0.16	19	52	0.27	152	1.9	0.01	24.2	1320	508
RO-E-5 (4169664)		0.81	<5	2	<1	0.04	4	<1	0.10	334	12.9	<0.01	5.8	368	58.3
RO-E-7 (4169665)		0.35	<5	<1	<1	0.05	4	<1	0.02	399	5.9	<0.01	6.4	2310	60.4
RO-E-9 (4169666)		0.71	<5	3	<1	0.03	4	<1	<0.01	142	3.5	<0.01	12.8	373	26.8

Certified By:



AGAT Laboratories

Certificate of Analysis

AGAT WORK ORDER: 13V693961

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013		DATE RECEIVED: Mar 05, 2013					DATE REPORTED: Mar 21, 2013					SAMPLE TYPE: Rock			
	Analyte:	Rb	S	Sb	Sc	Se	Sn	Sr	Ta	Te	Th	Ti	Tl	U	V
	Unit:	ppm	%	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	10	0.005	1	0.5	10	5	0.5	10	10	5	0.01	5	5	0.5
RED 1 (4169610)		<10	0.014	<1	0.8	<10	<5	21.9	<10	<10	<5	<0.01	<5	<5	2.6
RED 2 (4169611)		<10	<0.005	<1	0.5	<10	<5	11.1	<10	<10	<5	<0.01	<5	<5	5.5
RED 3 (4169612)		14	0.069	<1	2.1	<10	<5	11.5	<10	<10	<5	<0.01	<5	<5	5.0
RED 4 (4169613)		<10	0.032	8	2.0	<10	<5	52.1	<10	<10	<5	<0.01	<5	<5	1.7
RED 5 (4169614)		<10	0.024	1	0.8	<10	<5	5.4	<10	<10	<5	<0.01	6	<5	6.0
RED 6 (4169615)		<10	0.128	11	1.6	<10	<5	6.5	<10	<10	<5	<0.01	<5	<5	6.1
RED 7 (4169616)		17	0.069	<1	4.0	<10	7	67.5	<10	<10	<5	<0.01	<5	<5	24.0
RED 8 (4169617)		26	0.049	5	4.3	<10	<5	15.0	<10	<10	7	<0.01	<5	<5	18.8
RED 9 (4169618)		18	0.168	17	3.0	<10	<5	11.7	<10	<10	<5	<0.01	8	<5	13.7
RED 10 (4169619)		<10	0.091	2	4.9	10	13	109	<10	<10	<5	<0.01	<5	<5	6.6
RED 12 (4169620)		14	0.118	<1	1.4	<10	42	241	<10	<10	<5	<0.01	9	<5	9.9
RED 13 (4169621)		11	0.056	<1	1.8	<10	20	166	<10	<10	<5	<0.01	<5	<5	9.6
RED 14 (4169622)		<10	0.024	<1	1.4	<10	<5	25.3	<10	<10	<5	<0.01	<5	<5	9.8
RED 15 (4169623)		<10	<0.005	<1	0.6	<10	<5	8.7	<10	<10	<5	<0.01	<5	<5	4.9
RED 16 (4169624)		<10	0.022	2	1.3	<10	6	40.9	<10	<10	<5	<0.01	<5	<5	6.3
RED 17 (4169625)		<10	0.010	<1	1.6	<10	<5	20.4	<10	<10	<5	<0.01	5	<5	10.4
RED 18 (4169626)		<10	0.014	1	1.1	<10	<5	37.8	<10	<10	<5	<0.01	<5	<5	8.7
RED 19 (4169627)		<10	0.013	<1	1.1	<10	<5	33.2	<10	<10	<5	<0.01	<5	<5	9.0
RED 20 (4169628)		<10	0.006	4	1.1	<10	<5	14.4	<10	<10	<5	<0.01	<5	<5	9.7
RED 21 (4169629)		23	0.140	6	5.4	<10	35	174	<10	<10	11	<0.01	<5	<5	15.2
RED 22 (4169630)		<10	0.023	2	0.7	<10	<5	7.2	<10	<10	<5	<0.01	7	<5	6.7
RED 23 (4169631)		<10	0.045	4	<0.5	<10	<5	4.6	<10	<10	<5	<0.01	<5	<5	3.8
RED 24 (4169632)		<10	0.034	2	<0.5	<10	<5	5.0	<10	<10	<5	<0.01	<5	<5	5.0
RED 25 (4169633)		<10	0.020	10	0.7	<10	<5	1.8	<10	<10	<5	<0.01	<5	<5	7.6
RED 26 (4169634)		26	0.312	16	8.3	<10	121	712	<10	<10	<5	<0.01	15	<5	9.6
RED 27 (4169635)		16	0.080	4	3.1	12	28	178	<10	<10	6	<0.01	<5	<5	15.5
RED 30 (4169636)		12	0.022	3	4.5	<10	<5	38.2	<10	<10	11	<0.01	7	<5	13.1
RED 31 (4169637)		<10	0.105	2	0.9	<10	<5	30.7	<10	<10	<5	<0.01	<5	<5	2.3
RED 32 (4169638)		<10	>10	60	0.6	102	<5	35.1	<10	<10	<5	<0.01	<5	6	7.3
RED 33 (4169639)		<10	2.84	197	<0.5	<10	5	33.0	<10	<10	<5	<0.01	<5	<5	4.1
RED 34 (4169640)		12	0.792	269	4.7	<10	19	297	<10	<10	<5	<0.01	<5	<5	11.8
RED 35 (4169641)		<10	0.099	7	1.4	<10	<5	46.3	<10	<10	<5	<0.01	7	<5	4.3

Certified By:



Certificate of Analysis

AGAT WORK ORDER: 13V693961

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013		DATE RECEIVED: Mar 05, 2013					DATE REPORTED: Mar 21, 2013					SAMPLE TYPE: Rock			
	Analyte:	Rb	S	Sb	Sc	Se	Sn	Sr	Ta	Te	Th	Ti	Tl	U	V
	Unit:	ppm	%	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm
Sample ID (AGAT ID)	RDL:	10	0.005	1	0.5	10	5	0.5	10	10	5	0.01	5	5	0.5
RED 36 (4169642)		<10	0.041	1	2.7	<10	9	38.3	<10	<10	<5	<0.01	<5	<5	8.7
RED 37 (4169643)		12	0.119	7	6.9	<10	19	94.5	<10	<10	<5	<0.01	<5	5	14.6
RED 38 (4169644)		<10	0.211	161	5.0	12	16	133	<10	<10	<5	<0.01	<5	<5	12.3
RED 39 (4169645)		12	0.016	18	4.9	<10	<5	8.9	<10	<10	7	<0.01	<5	<5	57.3
RCD 1 (4169646)		<10	0.048	3	2.6	<10	<5	14.3	<10	<10	<5	<0.01	<5	<5	2.4
RCD 2 (4169647)		<10	0.057	7	2.7	10	<5	96.4	<10	<10	<5	<0.01	8	<5	2.1
RCD 3 (4169648)		<10	0.045	5	3.3	<10	<5	44.7	<10	<10	<5	<0.01	<5	<5	2.2
RCD 4 (4169649)		<10	0.063	11	3.4	<10	7	60.6	<10	<10	<5	<0.01	8	<5	2.3
RCD 5 (4169650)		<10	0.044	15	2.2	<10	<5	27.1	<10	<10	<5	<0.01	<5	<5	1.2
RCD 6 (4169651)		<10	0.028	9	2.4	10	<5	16.3	<10	<10	<5	<0.01	<5	<5	1.4
RCD 7 (4169652)		<10	0.035	17	3.1	<10	<5	16.3	<10	<10	<5	<0.01	<5	<5	1.8
RCD 8 (4169653)		<10	0.033	3	2.6	<10	<5	8.4	<10	<10	<5	<0.01	<5	<5	1.5
RCD 9 (4169654)		<10	0.066	1140	1.2	<10	<5	5.0	<10	<10	<5	<0.01	<5	<5	1.0
RCD 10 (4169655)		<10	0.053	9	2.3	11	<5	8.6	<10	<10	<5	<0.01	<5	<5	1.8
RCD 11 (4169656)		<10	0.044	15	3.6	<10	<5	54.8	<10	<10	<5	<0.01	<5	<5	3.8
RCD 12 (4169657)		<10	0.078	22	4.6	<10	8	111	<10	<10	<5	<0.01	<5	<5	5.6
MS-01R (4169658)		<10	3.51	>10000	0.8	242	<5	55.1	14	<10	<5	<0.01	8	<5	4.1
MS-02R (4169659)		<10	7.74	6720	<0.5	46	14	73.1	<10	<10	<5	<0.01	<5	<5	5.9
MS-03R (4169660)		<10	2.76	822	<0.5	<10	21	46.0	<10	<10	<5	<0.01	<5	<5	5.5
MS-04R (4169661)		<10	6.29	1840	<0.5	73	18	35.6	<10	<10	<5	<0.01	<5	<5	4.8
RO-E-1 (4169662)		<10	0.028	15	<0.5	<10	<5	23.0	<10	<10	<5	<0.01	<5	<5	3.1
RO-E-3 (4169663)		16	0.021	8	3.3	<10	<5	31.3	<10	<10	<5	<0.01	<5	<5	18.6
RO-E-5 (4169664)		16	0.169	10	1.9	<10	61	777	<10	<10	<5	<0.01	15	<5	7.6
RO-E-7 (4169665)		<10	0.050	5	3.4	<10	16	138	<10	<10	<5	<0.01	<5	<5	18.6
RO-E-9 (4169666)		<10	0.008	4	0.8	<10	<5	18.6	<10	<10	<5	<0.01	<5	<5	5.2

Certified By:



AGAT Laboratories

Certificate of Analysis

AGAT WORK ORDER: 13V693961

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013

DATE RECEIVED: Mar 05, 2013

DATE REPORTED: Mar 21, 2013

SAMPLE TYPE: Rock

Sample ID (AGAT ID)	Analyte: Unit: RDL:	W ppm 1	Y ppm 1	Zn ppm 0.5	Zr ppm 5	Ag-Grav g/t 5	Pb-OL % 0.05	Zn-OL % 0.01	Sb-OL % 0.01	Cu-OL %
RED 1 (4169610)		<1	5	185	<5					
RED 2 (4169611)		<1	3	182	<5					
RED 3 (4169612)		<1	3	17.8	<5					
RED 4 (4169613)		<1	5	36.1	<5					
RED 5 (4169614)		<1	<1	2.9	<5					
RED 6 (4169615)		<1	2	45.7	<5					
RED 7 (4169616)		<1	16	69.1	<5					
RED 8 (4169617)		<1	5	46.4	<5					
RED 9 (4169618)		<1	5	36.9	<5					
RED 10 (4169619)		<1	7	111	<5					
RED 12 (4169620)		<1	7	54.8	<5					
RED 13 (4169621)		<1	7	27.3	<5					
RED 14 (4169622)		<1	10	39.7	<5					
RED 15 (4169623)		<1	3	79.1	<5					
RED 16 (4169624)		<1	8	103	<5					
RED 17 (4169625)		<1	4	25.1	<5					
RED 18 (4169626)		<1	5	100	<5					
RED 19 (4169627)		<1	3	423	<5					
RED 20 (4169628)		<1	4	228	<5					
RED 21 (4169629)		<1	8	63.6	<5					
RED 22 (4169630)		<1	<1	2.9	<5					
RED 23 (4169631)		<1	<1	5.7	<5					
RED 24 (4169632)		<1	<1	3.0	<5					
RED 25 (4169633)		<1	<1	2.5	<5					
RED 26 (4169634)		<1	23	8.9	8					
RED 27 (4169635)		<1	6	44.7	<5					
RED 30 (4169636)		<1	8	25.6	<5					
RED 31 (4169637)		<1	1	98.1	<5					
RED 32 (4169638)		<1	<1	36.2	<5					
RED 33 (4169639)		<1	1	114	<5	128	6.54			
RED 34 (4169640)		10	6	7120	<5					
RED 35 (4169641)		<1	2	149	<5					

Certified By:



AGAT Laboratories

Certificate of Analysis

AGAT WORK ORDER: 13V693961

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

DATE SAMPLED: Mar 05, 2013		DATE RECEIVED: Mar 05, 2013				DATE REPORTED: Mar 21, 2013				SAMPLE TYPE: Rock	
	Analyte:	W	Y	Zn	Zr	Ag-Grav	Pb-OL	Zn-OL	Sb-OL	Cu-OL	
	Unit:	ppm	ppm	ppm	ppm	g/t	%	%	%	%	
Sample ID (AGAT ID)	RDL:	1	1	0.5	5	5	0.05	0.01	0.01		
RED 36 (4169642)		<1	4	301	<5						
RED 37 (4169643)		<1	7	1180	<5						
RED 38 (4169644)		<1	7	2080	<5						
RED 39 (4169645)		<1	6	79.7	14						
RCD 1 (4169646)		<1	2	531	<5						
RCD 2 (4169647)		<1	2	205	<5						
RCD 3 (4169648)		<1	2	316	<5						
RCD 4 (4169649)		<1	3	183	<5						
RCD 5 (4169650)		<1	3	160	<5						
RCD 6 (4169651)		<1	2	72.6	<5						
RCD 7 (4169652)		<1	4	321	<5						
RCD 8 (4169653)		<1	2	2610	<5						
RCD 9 (4169654)		1	1	4040	<5						
RCD 10 (4169655)		1	1	2360	<5						
RCD 11 (4169656)		<1	2	9580	<5						
RCD 12 (4169657)		<1	5	>10000	<5			1.58			
MS-01R (4169658)		<1	2	913	<5		2.82		1.69	1.17	
MS-02R (4169659)		<1	3	>10000	<5	149	4.39	5.65			
MS-03R (4169660)		<1	2	>10000	<5		2.77	1.63			
MS-04R (4169661)		<1	1	>10000	<5	361	3.88	2.70			
RO-E-1 (4169662)		<1	<1	194	<5						
RO-E-3 (4169663)		<1	7	81.5	<5						
RO-E-5 (4169664)		<1	14	84.3	<5						
RO-E-7 (4169665)		<1	11	54.0	<5						
RO-E-9 (4169666)		<1	3	145	<5						

Comments: RDL - Reported Detection Limit

Certified By:



CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

Parameter	REPLICATE #1				REPLICATE #2				REPLICATE #3				REPLICATE #4			
	Sample ID	Original	Replicate	RPD	Sample ID	Original	Replicate	RPD	Sample ID	Original	Replicate	RPD	Sample ID	Original	Replicate	RPD
Ag	4169610	< 0.2	< 0.2	0.0%	4169629	0.3	0.3	0.0%	4169635	< 0.2	< 0.2	0.0%	4169651	< 0.2	< 0.2	0.0%
Al	4169610	0.09	0.09	0.0%	4169629	1.70	1.64	3.6%	4169635	1.94	1.70	13.2%	4169651	0.108	0.104	3.8%
As	4169610	21	16	27.0%	4169629	19	13		4169635	10	2		4169651	23	26	12.2%
B	4169610	< 5	< 5	0.0%	4169629	< 5	< 5	0.0%	4169635	< 5	< 5	0.0%	4169651	< 5	< 5	0.0%
Ba	4169610	46	49	6.3%	4169629	53	53	0.0%	4169635	45	40	11.8%	4169651	116	111	4.4%
Be	4169610	< 0.5	< 0.5	0.0%	4169629	< 0.5	< 0.5	0.0%	4169635	< 0.5	< 0.5	0.0%	4169651	< 0.5	< 0.5	0.0%
Bi	4169610	3	3	0.0%	4169629	12	10	18.2%	4169635	5	13		4169651	< 1	< 1	0.0%
Ca	4169610	0.53	0.55	3.7%	4169629	7.55	7.32	3.1%	4169635	6.13	5.38	13.0%	4169651	0.40	0.37	7.8%
Cd	4169610	1.2	1.2	0.0%	4169629	< 0.5	< 0.5	0.0%	4169635	< 0.5	< 0.5	0.0%	4169651	< 0.5	< 0.5	0.0%
Ce	4169610	3	3	0.0%	4169629	38	36	5.4%	4169635	34	35	2.9%	4169651	11	11	0.0%
Co	4169610	1.9	2.0	5.1%	4169629	15.2	14.4	5.4%	4169635	8.2	8.5	3.6%	4169651	3.73	3.90	4.5%
Cr	4169610	126	121	4.0%	4169629	25.4	24.3	4.4%	4169635	19.8	20.8	4.9%	4169651	95.6	91.5	4.4%
Cu	4169610	3.7	3.5	5.6%	4169629	23.8	23.3	2.1%	4169635	10.5	11.0	4.7%	4169651	23.3	23.2	0.4%
Fe	4169610	0.60	0.63	4.9%	4169629	3.39	3.25	4.2%	4169635	2.70	2.38	12.6%	4169651	1.02	0.96	6.1%
Ga	4169610	< 5	< 5	0.0%	4169629	6	5	18.2%	4169635	5	5	0.0%	4169651	< 5	< 5	0.0%
Hg	4169610	2	1		4169629	4	2		4169635	5	5	0.0%	4169651	< 1	2	
In	4169610	< 1	< 1	0.0%	4169629	< 1	2		4169635	< 1	< 1	0.0%	4169651	3	< 1	
K	4169610	0.04	0.04	0.0%	4169629	0.16	0.16	0.0%	4169635	0.11	0.10	9.5%	4169651	0.066	0.064	3.1%
La	4169610	< 1	< 1	0.0%	4169629	18	18	0.0%	4169635	16	17	6.1%	4169651	2	2	0.0%
Li	4169610	< 1	< 1	0.0%	4169629	64	62	3.2%	4169635	79	70	12.1%	4169651	< 1	< 1	0.0%
Mg	4169610	0.01	0.01	0.0%	4169629	1.30	1.25	3.9%	4169635	1.27	1.12	12.6%	4169651	0.01	0.01	0.0%
Mn	4169610	161	161	0.0%	4169629	454	438	3.6%	4169635	342	339	0.9%	4169651	213	200	6.3%
Mo	4169610	5.51	4.21	26.7%	4169629	5.3	5.6	5.5%	4169635	4.8	3.5		4169651	2.44	2.68	9.4%
Na	4169610	< 0.01	< 0.01	0.0%	4169629	0.02	0.02	0.0%	4169635	< 0.01	< 0.01	0.0%	4169651	< 0.01	< 0.01	0.0%
Ni	4169610	11.2	11.1	0.9%	4169629	24.0	23.4	2.5%	4169635	17.5	17.1	2.3%	4169651	8.9	8.5	4.6%
P	4169610	776	782	0.8%	4169629	447	430	3.9%	4169635	494	503	1.8%	4169651	223	219	1.8%
Pb	4169610	3.0	3.9	26.1%	4169629	17.9	17.6	1.7%	4169635	16.7	16.2	3.0%	4169651	9.85	9.90	0.5%
Rb	4169610	< 10	< 10	0.0%	4169629	23	22	4.4%	4169635	16	17	6.1%	4169651	< 10	< 10	0.0%
S	4169610	0.0135	0.0134	0.7%	4169629	0.140	0.135	3.6%	4169635	0.0800	0.0691	14.6%	4169651	0.0277	0.0286	3.2%
Sb	4169610	< 1	< 1	0.0%	4169629	6	2		4169635	4	2		4169651	9	6	
Sc	4169610	0.8	0.7	13.3%	4169629	5.41	5.22	3.6%	4169635	3.1	3.1	0.0%	4169651	2.4	2.4	0.0%



CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Se	4169610	9	12	28.6%	4169629	< 10	< 10	0.0%	4169635	12	< 10		4169651	10	< 10	
Sn	4169610	< 5	< 5	0.0%	4169629	35	34	2.9%	4169635	28	24	15.4%	4169651	< 5	< 5	0.0%
Sr	4169610	21.9	22.7	3.6%	4169629	174	167	4.1%	4169635	178	158	11.9%	4169651	16.3	14.8	9.6%
Ta	4169610	< 10	< 10	0.0%	4169629	< 10	< 10	0.0%	4169635	< 10	< 10	0.0%	4169651	< 10	< 10	0.0%
Te	4169610	< 10	< 10	0.0%	4169629	< 10	< 10	0.0%	4169635	< 10	< 10	0.0%	4169651	< 10	< 10	0.0%
Th	4169610	< 5	< 5	0.0%	4169629	11	12	8.7%	4169635	6	7	15.4%	4169651	< 5	< 5	0.0%
Ti	4169610	< 0.01	< 0.01	0.0%	4169629	< 0.01	< 0.01	0.0%	4169635	< 0.01	< 0.01	0.0%	4169651	< 0.01	< 0.01	0.0%
Tl	4169610	< 5	< 5	0.0%	4169629	< 5	8		4169635	< 5	< 5	0.0%	4169651	< 5	12	
U	4169610	< 5	< 5	0.0%	4169629	< 5	< 5	0.0%	4169635	< 5	< 5	0.0%	4169651	< 5	< 5	0.0%
V	4169610	2.61	2.34	10.9%	4169629	15.2	14.8	2.7%	4169635	15.5	15.5	0.0%	4169651	1.4	1.7	19.4%
W	4169610	< 1	< 1	0.0%	4169629	< 1	< 1	0.0%	4169635	< 1	< 1	0.0%	4169651	< 1	< 1	0.0%
Y	4169610	5	5	0.0%	4169629	8	8	0.0%	4169635	6	6	0.0%	4169651	2	2	0.0%
Zn	4169610	185	187	1.1%	4169629	63.6	61.6	3.2%	4169635	44.7	45.0	0.7%	4169651	72.6	69.9	3.8%
Zr	4169610	< 5	< 5	0.0%	4169629	< 5	< 5	0.0%	4169635	< 5	< 5	0.0%	4169651	< 5	< 5	0.0%

REPLICATE #5																
Parameter	Sample ID	Original	Replicate	RPD												
Ag	4169660	88.4	84.5	4.5%												
Al	4169660	0.10	0.11	9.5%												
As	4169660	81	92	12.7%												
B	4169660	< 5	< 5	0.0%												
Ba	4169660	73	82	11.6%												
Be	4169660	< 0.5	< 0.5	0.0%												
Bi	4169660	14	13	7.4%												
Ca	4169660	0.99	1.10	10.5%												
Cd	4169660	161	192	17.6%												
Ce	4169660	2	3													
Co	4169660	2.8	3.3	16.4%												
Cr	4169660	129	152	16.4%												
Cu	4169660	1527	1420	7.3%												
Fe	4169660	1.33	1.48	10.7%												
Ga	4169660	< 5	< 5	0.0%												
Hg	4169660	6	3													
In	4169660	< 1	< 1	0.0%												
K	4169660	0.053	0.058	9.0%												



CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

La	4169660	< 1	< 1	0.0%												
Li	4169660	< 1	< 1	0.0%												
Mg	4169660	0.269	0.298	10.2%												
Mn	4169660	538	634	16.4%												
Mo	4169660	3.60	3.55	1.4%												
Na	4169660	< 0.01	< 0.01	0.0%												
Ni	4169660	8.8	10.6	18.6%												
P	4169660	70	85	19.4%												
Pb	4169660	> 10000	> 10000	0.0%												
Rb	4169660	< 10	< 10	0.0%												
S	4169660	2.76	3.05	10.0%												
Sb	4169660	822	966	16.1%												
Sc	4169660	< 0.5	< 0.5	0.0%												
Se	4169660	< 10	< 10	0.0%												
Sn	4169660	21	24	13.3%												
Sr	4169660	46.0	51.2	10.7%												
Ta	4169660	< 10	< 10	0.0%												
Te	4169660	< 10	< 10	0.0%												
Th	4169660	< 5	< 5	0.0%												
Ti	4169660	< 0.01	< 0.01	0.0%												
Tl	4169660	< 5	7													
U	4169660	< 5	< 5	0.0%												
V	4169660	5.51	6.47	16.0%												
W	4169660	< 1	< 1	0.0%												
Y	4169660	2	2	0.0%												
Zn	4169660	> 10000	> 10000	0.0%												
Zr	4169660	< 5	< 5	0.0%												



AGAT Laboratories

Quality Assurance - Certified Reference materials

AGAT WORK ORDER: 13V693961

PROJECT NO: ROAM

5623 McADAM ROAD
MISSISSAUGA, ONTARIO
CANADA L4Z 1N9
TEL (905)501-9998
FAX (905)501-0589
<http://www.agatlabs.com>

CLIENT NAME: HOMEGOLD RESOURCES LTD.

ATTENTION TO: JO SHEARER

Aqua Regia Digest - Metals Package, ICP-OES finish (201073)

Parameter	CRM #1 (CU186)				CRM #2 (CU186)				CRM #3 (CU186)							
	Expect	Actual	Recovery	Limits	Expect	Actual	Recovery	Limits	Expect	Actual	Recovery	Limits				
Ag	14	12	84%	80% - 120%	14	13	96%	80% - 120%	14	13	91%	80% - 120%				
Cu	6000	5570	92%	80% - 120%	6000	5854	98%	80% - 120%	6000	5737	95%	80% - 120%				
Mo	360	309	86%	80% - 120%	360	364	101%	80% - 120%	360	321	89%	80% - 120%				

Method Summary

CLIENT NAME: HOMEGOLD RESOURCES LTD.

AGAT WORK ORDER: 13V693961

PROJECT NO: ROAM

ATTENTION TO: JO SHEARER

PARAMETER	AGAT S.O.P	LITERATURE REFERENCE	ANALYTICAL TECHNIQUE
Solid Analysis			
Sample Login Weight	MIN-12009		BALANCE
Ag	MIN-200-12020		ICP/OES
Al	MIN-200-12020		ICP/OES
As	MIN-200-12020		ICP/OES
B	MIN-200-12020		ICP/OES
Ba	MIN-200-12020		ICP/OES
Be	MIN-200-12020		ICP/OES
Bi	MIN-200-12020		ICP/OES
Ca	MIN-200-12020		ICP/OES
Cd	MIN-200-12020		ICP/OES
Ce	MIN-200-12020		ICP/OES
Co	MIN-200-12020		ICP/OES
Cr	MIN-200-12020		ICP/OES
Cu	MIN-200-12020		ICP/OES
Fe	MIN-200-12020		ICP/OES
Ga	MIN-200-12020		ICP/OES
Hg	MIN-200-12020		ICP/OES
In	MIN-200-12020		ICP/OES
K	MIN-200-12020		ICP/OES
La	MIN-200-12020		ICP/OES
Li	MIN-200-12020		ICP/OES
Mg	MIN-200-12020		ICP/OES
Mn	MIN-200-12020		ICP/OES
Mo	MIN-200-12020		ICP/OES
Na	MIN-200-12020		ICP/OES
Ni	MIN-200-12020		ICP/OES
P	MIN-200-12020		ICP/OES
Pb	MIN-200-12020		ICP/OES
Rb	MIN-200-12020		ICP/OES
S	MIN-200-12020		ICP/OES
Sb	MIN-200-12020		ICP/OES
Sc	MIN-200-12020		ICP/OES
Se	MIN-200-12020		ICP/OES
Sn	MIN-200-12020		ICP/OES
Sr	MIN-200-12020		ICP/OES
Ta	MIN-200-12020		ICP/OES
Te	MIN-200-12020		ICP/OES
Th	MIN-200-12020		ICP/OES
Ti	MIN-200-12020		ICP/OES
Tl	MIN-200-12020		ICP/OES
U	MIN-200-12020		ICP/OES
V	MIN-200-12020		ICP/OES
W	MIN-200-12020		ICP/OES
Y	MIN-200-12020		ICP/OES
Zn	MIN-200-12020		ICP/OES
Zr	MIN-200-12020		ICP/OES
Pb-OL	MIN-200-12032		AA
Zn-OL	MIN-200-12032		AA
Ag-Grav			GRAVIMETRIC

Method Summary

CLIENT NAME: HOMEGOLD RESOURCES LTD.

AGAT WORK ORDER: 13V693961

PROJECT NO: ROAM

ATTENTION TO: JO SHEARER

PARAMETER	AGAT S.O.P	LITERATURE REFERENCE	ANALYTICAL TECHNIQUE
Sb-OL			AA
Cu-OL			ICP/OES

Appendix IV

Sample Descriptions

March 16, 2013

APPENDIX IV
SAMPLE DESCRIPTIONS

0015	N59 59.880 W128 35.201	636 m	23/06/2012 12:32:58 PM
0021	N60 01.674 W128 51.592	694 m	04/07/2012 8:18:00 AM
0031	N59 59.880 W128 35.203	614 m	25/06/2012 10:18:47 AM
249+00N - 9+50E	N59 59.964 W128 34.961		04/07/2012 8:32:10 AM
Base station B/L 250 N 10+50E	N60 00.015 W128 35.193		04/07/2012 8:33:21 AM
BL 0+50	N59 59.881 W128 35.193	637 m	04/07/2012 10:20:41 AM
BL250L7E	N60 00.016 W128 34.801	678 m	23/06/2012 4:56:21 PM
Current Track: 23 JUN 2012 11:543	N60 00.014 W128 35.301		04/07/2012 12:04:11 PM
Current Track: 25 JUN 2012 09:24	N59 59.930 W128 34.951		04/07/2012 10:05:55 AM
Current Track: 25 JUN 2012 09:241	N59 59.930 W128 34.951		04/07/2012 10:06:00 AM
DD RM 06	N59 59.930 W128 34.951		04/07/2012 10:07:34 AM
DDRM01	N59 59.859 W128 35.143	611 m	04/07/2012 9:22:25 AM
DDRM02	N59 59.854 W128 35.092	611 m	04/07/2012 9:56:29 AM
DDRM04	N59 59.859 W128 34.990	625 m	04/07/2012 10:04:41 AM
DDRM05	N59 59.910 W128 35.253	627 m	25/06/2012 1:49:03 PM
DDRM07	N60 00.019 W128 34.822	671 m	25/06/2012 2:46:52 PM
DDROAM1	N59 59.894 W128 35.229	635 m	04/07/2012 10:36:01 AM
L249+00N-11+00E	N59 59.957 W128 35.176		04/07/2012 8:31:36 AM
Line 9+50 B/L 250N	N60 00.012 W128 34.968		04/07/2012 8:33:49 AM
NORTH GRID	N59 59.908 W128 35.245	641 m	23/06/2012 11:55:10 AM
ROAM LAST WASH	N60 01.674 W128 51.595	694 m	04/07/2012 8:23:06 AM
ROAM RD END	N60 02.133 W128 53.474	610 m	04/07/2012 8:26:23 AM

WAP ROA

582	08-AUG-12 5:42:25PM	N54 32.559 W120 33.929	1164 m
584	14-AUG-12 11:49:52AM	N60 00.168 W128 35.586	650 m
585	14-AUG-12 1:44:17PM	N59 59.948 W128 35.458	625 m
586	15-AUG-12 1:45:34PM	N59 59.868 W128 34.888	649 m
587	18-AUG-12 8:53:09AM	N60 00.012 W128 36.271	653 m
BL-0+30N	14-AUG-12 9:35:33AM	N59 59.879 W128 35.129	607 m
BL0+00-2+00S	17-AUG-12 3:45:12PM	N59 59.782 W128 35.278	645 m
CAMP	17-AUG-12 1:04:14PM	N60 00.266 W128 36.815	686 m
CBLO+00W-0+00S	20-AUG-12 10:19:25AM	N60 00.903 W128 37.270	678 m
CBLO+60W-0+00S	20-AUG-12 11:14:31AM	N60 00.901 W128 37.314	676 m
CBL1+20W0+00S	20-AUG-12 3:00:18PM	N60 00.894 W128 37.372	683 m
CL0+30W0+00S	20-AUG-12 3:52:30PM	N60 00.899 W128 37.275	675 m
CL0+60W-0+00S	20-AUG-12 3:49:44PM	N60 00.901 W128 37.340	678 m
HELI	21-AUG-12 2:43:57PM	N60 00.899 W128 37.620	689 m
L2+00S0+00E	18-AUG-12 10:45:25AM	N59 59.779 W128 35.273	644 m
L2+30S-0+00W	18-AUG-12 1:46:12PM	N59 59.765 W128 35.294	654 m
L2+60-0+00W	18-AUG-12 2:40:19PM	N59 59.746 W128 35.321	658 m
OC-1	10-AUG-12 10:12:38AM	N54 28.148 W120 39.006	1163 m
OC2	10-AUG-12 10:43:48AM	N54 28.161 W120 39.046	1177 m
RO-0+00BL-NW	14-AUG-12 9:14:11AM	N59 59.875 W128 35.130	595 m
RO-E-1	14-AUG-12 3:13:23PM	N59 59.886 W128 35.304	624 m
RO-E-3	14-AUG-12 1:36:56PM	N59 59.941 W128 35.451	625 m
RO-E-4	14-AUG-12 1:37:41PM	N59 59.948 W128 35.448	625 m
RO-E-6	14-AUG-12 2:21:38PM	N59 59.914 W128 35.354	626 m
RO-E-7	14-AUG-12 2:48:31PM	N59 59.906 W128 35.316	627 m
RO-E-8	14-AUG-12 3:04:48PM	N59 59.897 W128 35.285	626 m
RO-E-9	14-AUG-12 3:27:10PM	N59 59.888 W128 35.287	626 m
RO-E-S1	14-AUG-12 12:40:41PM	N60 00.089 W128 35.544	647 m
RO-E-S2	14-AUG-12 12:52:32PM	N60 00.090 W128 35.519	649 m
RO-E-S3	14-AUG-12 1:02:58PM	N60 00.068 W128 35.536	644 m
RO-E-S4	14-AUG-12 1:09:10PM	N60 00.048 W128 35.537	638 m
SWA-E3	10-AUG-12 12:38:13PM	N54 28.157 W120 38.991	1151 m
SWAP-6	10-AUG-12 1:02:06PM	N54 28.136 W120 39.009	1153 m
SWAP-E1	10-AUG-12 12:27:25PM	N54 28.149 W120 39.002	1152 m
SWAP-E2	10-AUG-12 12:32:03PM	N54 28.161 W120 39.000	1154 m
SWAP-E4	10-AUG-12 12:43:19PM	N54 28.159 W120 38.974	1147 m
SWAP-E5	10-AUG-12 12:49:03PM	N54 28.149 W120 38.974	1143 m
SWAP-E7	10-AUG-12 1:19:01PM	N54 28.136 W120 39.029	1153 m
SWAP-E8	10-AUG-12 1:30:42PM	N54 28.133 W120 39.030	1152 m
SWAP-E9	10-AUG-12 1:39:45PM	N54 28.141 W120 39.043	1149 m
TR-HI-GRADE	09-AUG-12 12:28:47PM	N54 27.900 W120 38.660	1231 m
WAP-E-10	10-AUG-12 1:13:55PM	N54 28.135 W120 39.026	1152 m
WAP-E-11	10-AUG-12 1:55:54PM	N54 28.174 W120 39.038	1162 m
WAP-E-6	10-AUG-12 9:25:27AM	N54 28.123 W120 38.984	1146 m
WAP-E1,2,3,4,5	09-AUG-12 1:48:34PM	N54 27.774 W120 38.505	1232 m

Roam Property

0015		N59 59.880 W128 35.201	636 m	23/06/2012 12:32:58 PM
0021		N60 01.674 W128 51.592	694 m	04/07/2012 8:18:00 AM
0031		N59 59.880 W128 35.203	614 m	25/06/2012 10:18:47 AM
249+00N - 9+50E		N59 59.964 W128 34.961		04/07/2012 8:32:10 AM
Base station B/L 250 N 10+50E		N60 00.015 W128 35.193		04/07/2012 8:33:21 AM
BL 0+50		N59 59.881 W128 35.193	637 m	04/07/2012 10:20:41 AM
BL250L7E		N60 00.016 W128 34.801	678 m	23/06/2012 4:56:21 PM
Current Track: 23 JUN 2012 11:543	Western point of mag survey	N60 00.014 W128 35.301		04/07/2012 12:04:11 PM
Current Track: 25 JUN 2012 09:24		N59 59.930 W128 34.951		04/07/2012 10:05:55 AM
Current Track: 25 JUN 2012 09:241		N59 59.930 W128 34.951		04/07/2012 10:06:00 AM
DD RM 06	Spruce Bark sample, diameter 16"	N59 59.930 W128 34.951		04/07/2012 10:07:34 AM
DDRM01	Spruce bark sample- 2 trees 14" diameter	N59 59.859 W128 35.143	611 m	04/07/2012 9:22:25 AM
DDRM02	Rock sample taken from bedding of limestone and phyllitic shist	N59 59.854 W128 35.092	611 m	04/07/2012 9:56:29 AM
DDRM04	Spruce bark sample from 16" diameter tree. Nearby outcrops are a rusty	N59 59.859 W128 34.990	625 m	04/07/2012 10:04:41 AM
DDRM05		N59 59.910 W128 35.253	627 m	25/06/2012 1:49:03 PM
DDRM07		N60 00.019 W128 34.822	671 m	25/06/2012 2:46:52 PM
DDROAM1	Sample out crop of limestone saturated by quartz veins. Ridge runs	N59 59.894 W128 35.229	635 m	04/07/2012 10:36:01 AM
L249+00N-11+00E		N59 59.957 W128 35.176		04/07/2012 8:31:36 AM
Line 9+50 B/L 250N		N60 00.012 W128 34.968		04/07/2012 8:33:49 AM
NORTH GRID		N59 59.908 W128 35.245	641 m	23/06/2012 11:55:10 AM
ROAM LAST WASH	Unable to pass with ATV because of quicksand, and river flowing over road.	N60 01.674 W128 51.595	694 m	04/07/2012 8:23:06 AM

ROAM RD END	Likely as far as a truck could drive to because of sand deposited on road.	N60 02.133 W128 53.474	610 m	04/07/2012 8:26:23 AM
-------------	--	------------------------	-------	-----------------------

Appendix V

Magnetometer Data

March 16, 2013

L3+50S	L3+20S	L2+90S	L2+60E	L2+30S	L2+00S	L1+70S	L1+40S
	2+10W	2700					
	1+80W	2700					
	1+65W	2700	1+65W	2700	1+65W	2700	
	1+50W	2700	1+50W	2700	1+50W	2700	
	1+35W	2700	1+35W	2700	1+35W	2700	1+05W 2700
	0+90W	2700	0+90W	2700	0+90W	2700	0+90W 2700
	0+75W	2700	0+75W	2700	0+75W	2700	0+75W 2700
	0+60W	2700	0+60W	2700	0+60W	2700	0+60W 2700
	0+45W	2700	0+45W	2700	0+45W	2700	0+45W 2700
	0+30W	2700	0+30W	2700	0+30W	2700	0+30W 2700
	0+15W	2700	0+15W	2700	0+15W	2700	0+15W 2700
0+00	2700	0+00	2700	0+00	2700	0+00	2700
			0+00	2700	0+00	2700	0+00
			0+15E	2700	0+15E	2700	0+15E 2700
			0+30E	2700	0+30E	2700	0+30E 2700
			0+45E	2700	0+45E	2700	0+45E 2700
			0+60E	2700	0+60E	2700	0+60E 2700
			0+75E	2700	0+75E	2700	0+75E 2700
			0+90E	2700	0+90E	2675	0+90E 2700
			1+35E	2700	1+35E	2700	1+35E 2700
			1+20E	2700	1+20E	2700	1+20E 2700
			1+35E	2700	1+35E	2700	1+35E 2700
			1+50E	2700	1+50E	2700	1+50E 2700
			1+65E	2700	1+65E	2700	1+65E 2700
			1+80E	2700	1+80E	2700	1+80E 2700
			1+95E	2700	1+95E	2700	1+95E 2700
			2+10E	2700	2+10E	2700	2+10E 2700
			2+25E	2700	2+25E	2700	
			2+40E	2700	2+40E	2700	
		L3+90S	L2+60E	L2+30S	L2+00S	L1+70S	

STATION	READING	COMMENTS
	30x gammas	MF-1 Serial # 703270

Line 0+90N

0+00	2650
0+15W	2650
0+30W	2550
0+45W	2500
0+60W	2650

Line 0+90N

0+00	2650
0+15W	2650
0+30W	2550
0+45W	2500
0+60W	2650

LINE 0+60N

0+00	2600
0+15W	2600
0+30W	2600

LINE 0+60N

0+00	2600
0+15W	2600
0+30W	2600

LINE 0+30N

0+00	2650
0+15W	2650
0+30W	2650
0+45W	2650

LINE 0+30N

0+00	2650
0+15W	2650
0+30W	2650
0+45W	2650

LINE 0+60N

0+00	2675
0+15E	2675 road
0+45E	2650
0+60E	2650 hill starts up
0+75E	2675
0+90E	2675
1+05E	2675 road
1+20E	2675
1+35E	2675
1+50E	2650
1+65E	2650
1+80E	2650
1+95E	2650
2+10E	2650
2+25E	2650
2+40E	2650
2+55E	2675
2+70E	2675
2+85E	2650
3+00E	2650
3+15E	2650
3+30E	2650 BC Yukon Border

LINE 0+30N

0+00	2675
0+15E	2675
0+30E	2675
0+45E	2650
0+60E	2650
0+75E	2675
0+90E	2675
1+35E	2675 ROAD
1+20E	2675
1+35E	2675
1+50E	2675
1+65E	2675 crest of hill

LINE
 0+00
 0+15W
 0+30W
 0+45W
 0+60W
 0+75W
 0+90W
 1+35W
 1+20W
 1+35W
 1+50W
 1+65W
 1+80W
 1+95W
 2+10W
 2+25W
 2+40W

LINE 0+90N

0+00	2675
0+15E	2650
0+45E	2650
0+60E	2675
0+75E	2675
0+90E	2650
1+05E	2650
1+20E	2650
1+35E	2650

1+65E	2650
1+80E	2650
1+95E	2650
2+10E	2650
Eric's Lines	50 meter stationing

0+00NE	2675
0+50NE	2675
1+00NE	2675
1+50NE	2675
2+00NE	2675

Line 90 NE

0+00NE	2675
0+50NE	2675
1+00NE	2675
1+50NE	2675
2+00NE	2675
2+50NE	2675
3+00NE	2675

Line 1+80N top end of Line 0+00N

0+00NE	2675
0+50NE	2675
1+00NE	2675
1+50NE	2675
2+00NE	2675
2+50NE	2675
3+00NE	2675

STATION	READING	COMMENTS
	30x gammas	MF-1 Serial # 703270
		LINE 0+60N
		3+30E 2650 BCYuko border
		3+15E 2650
		3+00E 2650
		2+85E 2650
		2+70E 2675
		2+55E 2675
		2+40E 2650
		2+25E 2650
	2+10E 2675	2+10E 2650 B/L
	1+95E 2675	1+95E 2650 2675 2675 2675 2675 2675 2675 2675
	1+80E 2675	1+80E 2650 0+00NE 0+50NE 1+00NE 1+50NE 2+00NE 2+50NE 3+00NE
	1+65E 2675	1+65E 2650 1+65E 2675 2675 2675 2675 2675 2675 2675
	1+50E 2675	1+50E 2650 1+50E 2675 0+00NE 0+50NE 1+00NE 1+50NE 2+00NE 2+50NE 3+00NE
	1+35E 2675	1+35E 2675 1+35E 2675 2675 2675 2675 2675 2675 2675
	1+20E 2675	1+20E 2675 1+20E 2650 0+00NE 0+50NE 1+00NE 1+50NE 2+00NE 2+50NE 3+00NE
	1+05E 2675	1+05E 2675 1+05E 2650 2675 2675 2675 2675 2675 2675
	0+90E 2675	0+90E 2675 0+90E 2675 0+00NE 0+50NE 1+00NE 1+50NE 2+00NE 2+50NE 3+00NE
	0+75E 2675	0+75E 2675 0+75E 2675 2675 2675 2675 2675 2675
	0+60E 2675	0+60E 2675 0+60E 2650 0+00NE 0+50NE 1+00NE 1+50NE 2+00NE 2+50NE
	0+45E 2650	0+45E 2650 0+45E 2675 2675 2675 2675 2675
	0+30E 2650	0+30E 2675 0+30E 2675 0+00NE 0+50NE 1+00NE 1+50NE 2+00NE
	0+15E 2675	0+15E 2675 0+15E 2675
B/L	0+00 2650	0+00 2600 0+00 2675
	0+15W 2650	0+15W 2600 0+00
	0+30W 2550	0+30W 2600 0+15W
	0+45W 2500	0+30W
	0+60W 2650	0+45W
	Line 0+90N	L 0+60N L0+30N 0+00NE
		B/L

LINE
0+00
0+15W
0+30W
0+45W
0+60W
0+75W
0+90W
1+35W
1+20W
1+35W
1+50W
1+65W
1+80W
1+95W
2+10W
2+25W
2+40W

Eric's Lines 50 meter stationing

0+00NE	2675
0+50NE	2675
1+00NE	2675
1+50NE	2675
2+00NE	2675

Line 90 NE	
0+00NE	2675
0+50NE	2675
1+00NE	2675
1+50NE	2675
2+00NE	2675
2+50NE	2675
3+00NE	2675

Line 1+80N	top end of Line 0+00N
0+00NE	2675
0+50NE	2675
1+00NE	2675
1+50NE	2675
2+00NE	2675
2+50NE	2675
3+00NE	2675

STATION	READING	COMMENTS
LINE 2+60S		
0+00	2700	
0+15W	2700	cliff
0+30W	2700	
0+45W	2700	
0+60W	2700	
0+75W	2700	
0+90W	2700	
1+35W	2700	
1+20W	2700	
1+35W	2700	
1+50W	2700	
1+65W	2700	
LINE 2+30S		
0+00	2700	
0+15W	2700	
0+30W	2700	
0+45W	2700	
0+60W	2700	
0+75W	2700	
0+90W	2700	
1+35W	2700	
1+20W	2700	
1+35W	2700	
1+50W	2700	CLIFF
LINE 2+00S		
0+00	2700	
0+15E	2700	
0+30E	2700	
0+45E	2700	
0+60E	2700	
0+75E	2700	
0+90E	2675	
1+35E	2700	
1+20E	2700	
1+35E	2700	
1+50E	2700	
1+65E	2700	
1+80E	2700	
1+95E	2700	
2+10E	2700	
2+25E	2700	
2+40E	2700	
LINE1+70S		
0+00	2700	
0+15E	2700	
0+30E	2700	
0+45E	2700	
0+60E	2700	
0+75E	2700	
0+90E	2700	

1+35E	2700
1+20E	2700
1+35E	2700
1+50E	2700
1+65E	2700
1+80E	2700
1+95E	2700
2+10E	2700

LINE 2+60E

0+00	2700
0+15E	2700
0+30E	2700
0+45E	2700
0+60E	2700
0+75E	2700
0+90E	2700
1+35E	2700
1+20E	2700
1+35E	2700
1+50E	2700
1+65E	2700
1+80E	2700
1+95E	2700
2+10E	2700
2+25E	2700
2+40E	2700

LINE 3+10S

MAIN GRID

0+00	2650
0+15W	2550
0+30W	2550
0+45W	2659
0+60W	2600
0+75W	2625
0+90W	2675
1+35W	2675
1+20W	2650
1+35W	2700
1+50W	2675
1+65W	2650
1+80W	2700
1+95W	2675
2+10W	2700

Line 2+00S

0+00	2700
0+15W	2700
0+30W	2700
0+45W	2700
0+60W	2700
0+75W	2700
0+90W	2700

1+35W	2700
1+20W	2700
1+35W	2700
1+50W	2700
1+65W	2700
<i>Line 2+00S</i>	
<i>B/L0+00</i>	2700 ????
1+85	2700
1+70	2700
1+55	2700

Line 2+30 S

0+00	2700
0+15E	2700
0+30E	2700
0+45E	2700
0+60E	2700
0+75E	2700
0+90E	2700
1+35E	2700
1+20E	2700
1+35E	2700
1+50E	2700
1+65E	2700
1+80E	2700
1+95E	2700
2+10E	2700
2+25E	2700
2+40E	2700

Line 11+00E

V

Station	Base Line 250 N	>>>>>	11+50E	11+25E	11+00E	10+75E	10+00E	10+25E	10+50	10+75E
Mag reading			100,280	100,280	100,280	100,280	100,280	100,280	100,280	100,280
GPS Reading			9 V 522961 6651509		100,265					
					100,265					
					100,265					
					100,265					
					100,265	100,265	100,265	100,265	100,265	100,265

^

Line 11+00E

Line

Line 9+50

Base Station

V

10+50E	10+25E	10+00E	9+75E	9+50E	9+25E	9+00E	8+75E	8+50E	8+25E	8+00E	7+75E	7+50E	7+25E
100,280			100,280	100,280	100,280	100,280	100,280	100,280				100,260	100,260
9 V 523061 6651511			*****	*****	*****	*****							

Mag reading

249+75N	275	100,260
249+50N	260	100,260
249+25N	265	100,260
5 249+00N	265 < Line 249N	100,260

 $\wedge$

Line 9+50E

Base Station

Line 5+25E

V

7+00E	6+75E	6+50E	6+25E	6+00E	5+75E	5+50E	5+25E	5+00E	<<B/L 250N
100,270	100,270	100,260	100,270	100,260	100,270	100,260	100,270	100,270	
									Station
									100,270 249+75N
									100,270 249+50N
									100,270 249+25N
100,260	100,260	100,260	100,260	100,260	100,270	100,270	100,270	249+00N	<< Line 249N