

09671-9



GEOLOGICAL AND GEOCHEMICAL REPORT

KELLI CLAIM GROUPING HW07560

Whitehorse Mining Division

NTS: 115G/12 61°33' N Lat., 139°37' W Long.

Report by: G. Gutrath, Geologist, P.Eng.

Date: February 10, 2015

INTRODUCTION AND ACKNOWLEDGEMENTS

This report is written on behalf of the claim owners listed in Appendix H.

The time spent on the property and the cost of the program is outlined in Appendix G. This program has been filed as assessment work on the claims.

The writer carried out geological mapping and sampling programs on the property in 2011 and 2013. This work continued in 2014 and was expanded to include geochemical soil and silt sampling. This report summarizes the general property information that is given in much greater detail in the 2012 Geological Report, dated January 16, 2012. The focus of this report is on the results of the 2014 field work.

The writer was ably assisted in the field by Mr. Fred Erler, one of the claim owners, Mr. Lorne Smith of Haines Junction, Mr. Denis Dixon of Burwash Landing and Mrs. Louis Bouvier of Destruction Bay provided transportation and logistical support for the field program.

INDEX

	Page No.
Introduction and Acknowledgements	1
Index	i
Location	1
Physiography	1
Climate.....	1
Access	1
History	2
Regional Geology	2
2014 Exploration Program.....	3
Geological Mapping, Geochemical Soil and Silt Sampling	3
Property Geology	4
General.....	4
Statigraphy.....	4
Intrusive Rocks	4
2014 Mapping of Outcrop Geology in Lower Canyon Reed-Kelli Creek and Geology noted while carrying out the Geochemical Sampling, Sample Location and Analysis, Hand Specimen Location and Description, Structure, Metamorphism and Mineralization	5
Geology Observed on Geochemical Soil and Silt Sampling Traverses.....	7
Plotted on Map 2, 1:3000.....	8
Geochemical Soil and Silt Sampling	9
General.....	9
Soil Sampling Map 1, 1:000	10
Soil Sampling Map 2, 1:3000	12
Silt Sampling Map 1, 1:1000	13
Silt Sampling Map 2, 1:3000	14
Conclusion	16
Recommendations.....	18
References.....	19

Appendices:

- Appendix A Statement of Qualifications
- Appendix B Silt Sampling with Elevated/Anomalous Values
- Appendix C Soil Sampling with Elevated/Anomalous Values
- Appendix D Rock Samples with Elevated/Anomalous Values
- Appendix E Method of Silt and Soil Sample Collection
Acme Labs Sample Analysis for Silt, Soil and Rock Samples
- Appendix F Rock Specimens
- Appendix G Cost of 2014 Exploration Program
- Appendix H List of Claims, Expiry Dates and Owners

List of Maps (in pocket)

- Map 1, 1: 1000
Geology and Geochemical Map
- Map 2, 1: 3000
Geochemical Soil and Silt Sampling Map

Figures in Report

- Figure 1 Location Map 1:100,000
- Figure 1 Claim Map 1:10,000





Figure 1



LOCATION

The Kelli Claim Group is located on the northwest facing slope of the Kluane Range and is within the Kluane Game Sanctuary. The centre of the Kelli Claim Group is approximately UTM Coordinate 682400 N 573000 E, Zone 7, NAD 83 located on NTS Map 115/12.

PHYSIOGRAPHY

The Kelli Claim Group is centred on a north-northwesterly flowing tributary of Reed Creek (Kelli-Reed Creek) that joins the westerly flowing Reed Creek proper on the south side of Shakwak Trench. The south boundary of the Kelli Claim Group is at an elevation of 4,500 feet (1,372 m) and the north boundary is at an elevation of 2,600 feet (792 m).

The primary focus of historic mineral exploration and placer gold mining has been within the steep 'V' walled canyon referred to as the Lower, Middle and Upper Canyon that extend over a distance of 1000 m and over an elevation interval of 150 m.

Vegetation is predominantly stunted black spruce in areas of muskeg (permafrost). Tall, large diameter spruce border the thawed outwash channel. The Canyon area of Kelli-Reed Creek is bordered by thick alder as well as the adjoining slopes to an elevation of 4,000 feet (1,220 m). At an elevation above 5,000 feet (1,524 m) open grassland and willow predominate representing an alpine environment.

CLIMATE

The Kelli Claim Group is located on the east flank of the St. Elias Mountains and in theory is protected from direct coastal weather. However, weather is funneled from the coast along the low valleys that follow the Denali Fault/Shakwak Trench. As a result, there is considerable yearly variation in summer rainfall. Both the summer of 2011 and starting in July, 2013 the rainfall was abnormally high. In 2014, during the August exploration program weather conditions were ideal. There were only a few rain showers and the creek levels were low.

The range of annual temperature in the Kluane Lake area is -20°C in December, the coldest month to +13°C in July, the warmest month of the year.

The average annual rainfall is 20 cm and snowfall is 18 cm. The Kelli-Reed Creek area is at a higher elevation and will have colder winter weather and greater accumulated snowfall and rain.

ACCESS

The turnoff from the Alaska Highway to the winter heavy equipment trail/summer ATV trail is at UTM coordinate 580651 E 6830392 N, 340 km west of Whitehorse or 170 km from Haines Junction. The trail crosses 10 km of the Shakwak Trench through continuous swamp, skirting small lakes and crossing three streams reaching the Kelli-Reed Creek gravel fan at approximately 3 km from the campsite.

Helicopter service is available from Haines Junction with a suitable staging area on the Alaska Highway at Mile 1118. There is a good helicopter pad at the campsite.

In 2014 access from the Alaska Highway was provided by an 8 wheel Argo off-road vehicle rented from Mr. Denis Dixon of Burwash Landing. Mr. Lloyd Smith operated the Argo, carrying approximately 300 kilos of supplies and navigating the Shakwak Swamp and the washed out road to the Kelli Camp with no problems. The road from the Reed-Kelli Creek fan to the camp was built in the 1990s and was in good condition in 2011. However, in 2013 the road was 90% destroyed by a flash flood making it very slow and difficult to gain access to the Kelli Camp. On site transportation was provided by two ATVs that followed the Argo into the property.

The access trail from Highway 1 to the Kelli Camp is shown on Map 3.

HISTORY

The Kelli-Reed Creek has had a long history of placer gold mining starting in the early 1900s and again in the period 1935 to 1939. The more recent mining was carried out by Dublin Gulch Placers under the onsite direction of Darrel Duensing between 1983 and 1988. Overall production from the creek gravels is very uncertain but is probably in the range of 3,000 to 5,000 oz. of gold.

Larry Tremblay, project manager and claim owner, carried out an extensive trenching program in the Lower and Middle Canyons. In 2004 Mr. Tremblay and associates drilled five BQ holes in the Lower Canyon.

Some additional historical information was provided by Mr. Lorne Smith of Haines Junction, a long time resident of the area. Mr. Smith has placer and quartz claims on Swede Johnson Creek 4 km to the southwest of Kelli-Reed Creek. In 2003 – 2004 Mr. Smith carried out some bulk placer tests between the Lower Canyon and campsite and found areas of good placer gold values. In 2004 his equipment was used to move the drill. He was very helpful in confirming the location of the 2004 drill holes. In addition, he stated that when Larry Tremblay first located the property there were numerous old placer workings and possibly underground workings. Mr. Smith referred to the location of a ladder at WP66 573393 E 6824638 N on the east side of the creek that went up the edge of the large outcrop and led to underground mine workings 7 m to 10 m above the level of the creek gravels.

The History section pages 3, 4 and 5 in the writer's 2012 Report gives a more detailed description of the early work done on the Kelli-Reed Claim Group area.

REGIONAL GEOLOGY

The Kluane Range forms the northeast margin of the St. Elias Mountains that are predominantly underlain by a thick sequence of mainly layered Paleozoic strata that have been highly altered and deformed. The property is bordered to the north by the Denali Fault that occupies the Shakwak Trench. To the southwest of the Shakwak Trench in the Quill Creek – Dondjak River area the strata has been intruded by granitic to ultramafic bodies. The Quill Creek ultramafic hosts a nickel-copper deposit with PGE values.

In the Kelli Claim Group area of the Kluane Range the predominant rocks are Permian Pennsylvanian andesites covered by shales and thin bedded limestone. These units are repeated by a complex series of faults. Oligocene dikes in the area have been sheared indicating that the faulting is Tertiary or younger (T. Bremner, 1990).

The Denali Fault has formed the northeast facing slope of the front range of the St. Elias Mountains in the Kelli Claim Group area and has influenced the emplacement of the sub-parallel intrusive bodies in the Lower to Upper Canyon of Kelli-Reed Creek. These intrusive bodies are related to a 'structural kink' in the stream drainage both to the west and east of Kelli-Reed Creek over a distance of 8 km and sub-parallel the trend of the Denali Fault. This "kink" is an important reference point for the start of placer gold deposits in these creeks.

2014 EXPLORATION PROGRAM

The 2014 exploration program on the Kelli Claim Group is made up of three overlapping programs. Geological Mapping on a scale of 1:000, Geochemical Soil and Silt Sampling plotted on a 1:3000 base map, and also on the 1:000 scale map. The 1:3000 scale base contour map with 2014 UTM waypoints was prepared by Underfill Geomatics, Whitehorse, YT. The first phase of the 2014 program was an evaluation of the placer gold potential with data plotted on a scale of 1:2000. The placer gold evaluation is the subject of a separate report.

Geological Mapping, Geochemical Soil and Silt Sampling

The geological mapping program was carried out between August 20 and August 28, 2014. Survey control for mapping the outcrop geology and surficial features was by Garmin 78S attached to a Garmin antennae mounted in a pocket on the back of a field survey vest. The GPS is strapped to the forearm and is in continuous operation to minimize the time to get maximum satellite reception. The outline of rock outcrops, physical features and geology are plotted directly in the field on prepared mylar grid sheets in an aluminum folder. Waypoints are recorded to establish the location of data describing geological observations, sample locations, etc. and are recorded in a field notebook.

The geochemical soil and silt sampling program was carried out in part with the geological mapping. Soil and silt sample locations were surveyed using the Garmin 78S. Sample locations were marked and flagged.

In 2014 the geological mapping on a scale of 1:1000 was primarily in the Lower Canyon by Reed-Kelli Creek. A total of 15 samples were collected for analysis by Acme Labs.

A total of 55 soil samples and 43 silt samples were collected for analysis by Acme Labs. The sample locations are plotted on the 1:1000 scale Map 1 and the 1:3000 scale Map 2.

Weather conditions were very good with only a few rain showers. Water levels in the creeks were low allowing stream crossings.

PROPERTY GEOLOGY

General

The primary objective of the 2014 program was to continue the geological mapping on a scale of 1:1000 through the Lower Canyon and sample prospective mineralized zones. The division of the geology into Stratigraphy and Intrusive units was outlined in the 2012 and 2013 reports and supported by the work done by Dr. Getsinger and Mr. Bremner.

Stratigraphy

The layered rocks exposed from the camp area upstream to the Middle Canyon (Geology Map 1 1:1000, 2013) are divided into four units designated **pc** (phyllitic carbonate), **gs** (greenstone/meta volcanic), **gs (fp)** (subvolcanic greenstone and/or an intrusive feldspar porphyry), and **bgpl** (black graphitic phyllite with interbedded limestone). These units have been interpreted as being Pennsylvanian to Permian in age and part of the Skolai Group. The writer divided the **gs** unit into **gs** and **gs(fp)** to differentiate the marked contrast between the two units:

gs dark brown andesite often foliated to a chloritic schist, highly fractured with pyrite content from 1% to 10%, pyrrhotite trace to 1% and magnetite 1%. Widely spaced, flat pyritic quartz veins of variable width cut across the unit.

gs(fp) grey, possibly subvolcanic fine-grained to porphyritic andesite or intrusive with blocky, coarse fracturing with pyrite, less than 1%.

The **bgpl** unit is the principal unit downstream from the Lower Canyon to the campsite.

Intrusive Rocks

The layered rocks are intruded by dikes and sills of Oligocene to Miocene age (date of 23 Ma, ref. Bremner, 1991). Both Getsinger and Bremner agree that this intrusive is a feldspar hornblende porphyry. The writer mapped the intrusives as two separate rock types.

dd light orange weathering dacite dike, fine grained to aphanitic with an absence of porphyritic texture. In the fresh, fine grained dacite crystalline hornblende "blades" make up 1% to 2% of the ground mass

fp light grey subhedral medium grained feldspar phenocrysts in an aphanitic to fine grained feldspar rich ground mass

2014 MAPPING OF OUTCROP GEOLOGY IN LOWER CANYON REED-KELLI CREEK AND GEOLOGY NOTED WHILE CARRYING OUT THE GEOCHEMICAL SAMPLING, SAMPLE LOCATION AND ANALYSIS, HAND SPECIMEN LOCATION AND DESCRIPTION, STRUCTURE, METAMORPHISM AND MINERALIZATION

Detailed outcrop geology mapped on a scale of 1:1000 was limited to the Lower Canyon of Reed-Kelli Creek. At the downstream (north) start of the Lower Canyon massive cliffs rise on both sides of the creek. The first resistant unit is an andesite/chlorite schist interlayered to the north with platy (bedded) light grey-brown siltstone, fissile biotite-mica schist and beds of graphitic argillaceous schist. The schistosity is predominantly 295° dipping 80° to 85° to the north. Fine grained pyrite, 1% to 3%, is disseminated in these units or associated with thin irregular quartz veining.

The andesite/chlorite schist unit is in contact to the south with a dacite dike swarm interlayered with fissile graphitic limey argillite from 1 m to 1.5 m thick. The overall thickness of the dike swarm is in the order of 20 m and strikes 290° and dips steeply. It is part of Structure 1 outlined on Map 1 and is part of a regional structure that forms a “kink” in the drainages both to the northwest and southeast. In all these drainages such as Reed-Allen Creek (Map 2) and Swede Johnson Creek the “kink” is associated with placer gold deposits.

The overall width of Structure 1 in the Lower Canyon, including the dacite dike swarm just described, is in the order of 60 m. It is bordered on the south by a competent feldspar porphyry dike and andesite/chlorite schist. The central “core” of Structure 1 borders the dacite dike swarm to the south and is in the order of 30 m thick. It is very well exposed on the steep outcrop face on the west side of the Lower Canyon. It is a major zone of deformation with massive large scale cataclastic brecciation of the more competent altered dacite dikes and beds of limey graphitic sediments that have been ‘folded’ and dislocated. Both south and north contacts of this deformational “core” are bordered by steep, +30° to 40° gullies. The north contact with the massive dacite dike is very distinct on the east side of the creek and is in the order of 5 m wide. On the lower part of the outcrop the contact zone is largely obscured by talus but at a higher elevation the talus thins and the contact zone can be seen and is composed of narrow, broken lenticular dacite dikes, largely altered to a quartz sericite carbonate, a cream coloured rock interbedded with black limey argillaceous schist. Thin quartz veinlets are common with 1% to 2% fine grained pyrite associated with quartz and disseminated in the ground mass.

The Lower Canyon on the east side of the creek has been the focus of a great deal of exploration. Larry Tremblay reported that there were old workings in this part of the Lower Canyon that could be seen prior to the mechanized placer mining in the 1980s. One of the more notable workings was a drift accessible from the canyon floor by a ladder located in the area of the Pautler Trench shown on Map 1. The trench was sampled over 8.25 m to test the general area of the drift (Pautler, 2001). The writer cleaned out the trench and resampled it as well as the talus slope section between the trench and the massive dacite dike to the north. Pautler took 8 samples from the trench and the gold values ranged from 5 ppb Au to 30 ppb Au. The 30 ppb Au was associated with 110 ppm As and was taken over a width of 0.8 m.

The 2014 sampling of the Pautler Trench consisted of 5 channel samples with a low value of 0.5 ppb Au and a high value of 56.5 ppb Au associated with 161 ppm As.

Sample Width	Sample Number	Analysis
1.22 m	H1	3.4 ppb Au
1.82 m	H2	0.5 ppb Au
1.06 m	H3	11.7 ppb Au
1.21 m	H4	56.5 ppb Au 160.6 ppm As
1.21 m	H5	1.2 ppb Au

H6 was a large representative series of grab samples across the talus slope-contact zone over a width of 6 m. The grade of H6 was 2.5 ppb Au.

There is one silt sample KSI2 taken from the stream gully 2 m to 3 m south of the Pautler Trench. This sample gave 638.1 ppb Au, the highest Au value of all the samples collected. One soil sample KSO2 was taken 2 m upslope from the Pautler Trench and gave 137 ppm Cu, 54 ppm As, 44 ppb Au.

A diamond drilling program was carried out in the Lower Canyon in 2004. The collar of one hole, DH3, has been located and the 2014 UTM coordinates match the 2004 UTM coordinates. The hole was drilled at 210° at a dip of -50°. The hole would have intersected the west extension of the Pautler Trench geology. From 14 m to 47 m the hole intersected black graphitic schist/quartz sericite schist, fault gouge shearing and brecciation. The gold analysis ranged from 11 ppb Au to 148 ppb Au with an average of 45 ppb Au.

On the west side of the Lower Canyon 2 rock samples, H12 and H13, were collected from the talus slope-contact zone located between the massive dacite dike on the north and the major structural-deformation zone to the south. This zone is the equivalent of the Pautler zone sampled on the east side of the Lower Canyon. Both samples are very low grade, 0.6 ppb Au and 0.7 ppb Au.

Two samples, H10 and H14, were taken from the structural deformation zone 10 m from the north contact zone sampled by H12 and H13. H14 is a sample taken over 1 m of sooty grey-black weathering graphitic argillite with 3% to 5% fine grained pyrite. The sample had a low value of 2.4 ppb Au. H10 is from graphitic limey schist and altered dacite dike, pyrite is associated with quartz veinlets. Low grade, 8.2 ppb Au.

On the south side of the structural deformation zone there is a wide (10 m) contact zone largely obscured by talus. On the south side of the contact zone-talus slope is a grey feldspar porphyry dike with 10% to 15% medium grained hornblende laths (Specimen 12). A number of samples were collected from this contact zone as well as specimens and soil samples.

Rock Sample H7 chlorite schist cut by irregular discontinuous quartz veinlets with $\pm 5\%$ fine grained pyrite, very low grade, 2.7 ppb Au

- H8 20 m up 35° slope from H7. North side of contact zone, limonitic-oxidized, thin quartz veinlets interlayered and cutting chlorite schist. Pyrite %5. 174.6 ppm Cu, 5ppb Au
- H9 From south contact zone of talus slope +30°. Chlorite schist, quartz veinlets oxidized fine grained pyrite. Very low grade, 3.3 ppb Au
- H11 From north contact of talus slope. Green, moderately foliated massive chlorite schist cut by irregular crosscutting hairlike quartz veinlets. Pyrite is fine to medium grained, discrete clots. Low grade, 6.7 ppb Au
- Silt Sample 3 From the dry talus slope and is a mix of silt, soil and fine rock fragments. This sample has higher values than the rock samples; **30.1 As, 31 ppb Au**

The feldspar porphyry dike bordering the contact zone continues upstream to the southwest to WP187 (573303 E, 6824616 N) over a width of 10 m. The dike is in contact to the southwest with intensely sheared (275°/steep to 75° north) chlorite schist derived from andesite. At WP188 (573296 E, 6824609 N) there is a steep +35° narrow gully representing a fault zone (290°/80° south). From WP188 to WP191 (573284 E, 24578 N) the chlorite schist is cut by a feldspar porphyry dike 12 m wide and subparalleling the schistosity at 275°/70° N. From WP192 (573283 E, 6824571 N) to WP194 (573271 E, 682453 N) the fissile chlorite schist is cut by numerous irregular discontinuous quartz veinlets associated with fine disseminated pyrite both in the veins and in the chlorite schist (2% to 5% pyrite). WP194 marks the contact with a feldspar porphyry dike to the south and a major fault-contact zone represented by a steep (+35°) gully trending 185° from the road and at 60 m upslope curves to 300° to the top of the outcrop-cliff. The feldspar porphyry dike is 15 m wide and strikes 185° and dips 80° north.

Two silt samples KSI 4 and KSI 5 taken from the gully at 10 m and 20 m up the gully from the road. These samples are a mix of silt, soil and fine rock fragments. KSI4 has a value of **66 ppb Au** and KSI 5 has a value of **69.8 Au**.

The feldspar porphyry dike marks the end of the detailed 2014 geological mapping of the Lower Canyon. The outcrop geology going upstream to the southwest has been integrated with mapping from 2011 and 2013. This provides a larger scale base map for plotting soil and silt sample locations.

Geology Observed on Geochemical Soil and Silt Sampling Traverses

Structure 2, plotted on Map 1, 1:000 occupies the trace of stream valleys on both sides of Reed-Kelli Creek. A short traverse was made up the creek on the west side of the valley. There is extensive outcrop in the creek at WP61 (572897 E, 6824679 N) of light coloured grey-green limestone altered to phyllitic carbonate in part and strongly folded. Going up the tributary creek to the west at WP196 (572371 E, 6823868 N) there is good outcrop in the creek of grey limestone strongly sheared at 325° dipping 75° to the south. The creek channel is in a fold axis striking 325° and plunging 10° east.

At WP199 (572855 E, 6823874 N) there is good outcrop and a change in geology from limestone to a blocky (SP 15) dark black-green coloured moderately foliated andesite-crystal tuff or a diorite with a fine grained crystalline

texture. There is less than 1% disseminated fine grained pyrite and no magnetite. Just upstream from this outcrop silt sample KSI40 gave a value of **319 ppb Au**, the second highest gold value collected during the silt sampling program.

At WP201 (572818 E, 6823905 N) there is massive outcrop on the south side of the creek of dark green chlorite schist (andesite) with 1% to 2% fine grained disseminated pyrite. Specimen 16 is a light grey-green quartz (60%) chlorite foliated schist with 1% to 2% fine grained pyrrhotite (slightly magnetic) and is associated with thin discontinuous hairlike quartz veinlets and as discrete disseminations.

The small outcrop in the creek is a cream coloured weathering bedded limestone (Specimen 17) striking 315° and dipping 30° south (effervescent in dilute hydrochloric acid).

A soil sampling traverse continued from the creek at WP201 to WP 207 (572790 E, 6823810 N) that is located at the top of a 2013 or 2014 'tree-muskeg slide' that continues down into the Reed-Kelli Creek valley. The slide exposed continuous glacial cobble till over the total extent of the slide area.

Plotted on Map 2, 1:3000

The geochemical soil and silt sampling traverse starting on the west side of Map 1 follows the ridge from WP64 (572562 E, 6824208 N) subparalleling Structure 2 until it reaches WP65 (572502 E, 6824389 N) located on sloping bench cut by a small dry stream. Specimen 3 is from an angular float boulder at WP65 and is a light grey-green on a fresh surface, feldspathic aphanitic groundmass cut by 1% fine hairlike white carbonate veinlets. Less than 1% fine grained pyrite disseminated in the groundmass and up to 5% pyrite on fracture planes that weather to a dark limonite orange. The traverse contours to the west and at WP 67 (572422 E, 6824389 N) there is a small outcrop area (2 m by 6 m) of dark green foliated tuffaceous andesite. Chloritic shear planes, fine grained pyrite, less than 1% and no magnetite. It is cut by numerous hair-like irregular/crosscutting carbonate fracture fillings that are highly effervescent in dilute HCl (Specimen 4).

At WP71 (572355 E, 6824524 N) there is outcrop 10 m by 5 m represented by Specimen 6. Dark green chlorite schist, irregular foliation cut by numerous thin siderite veinlets, 1% disseminated fine grained pyrite with no magnetite.

In the creek canyon at WP75 (572154 E, 682549 N) there is extensive outcrop of a light grey fissile schist, possibly a silty limestone with bedding striking 285° and dipping 30° to 40° south. WP76 (572098 E, 6824606 N) is on the canyon wall going into the next creek. Massive outcrop light and dark banded, graphitic limy argillite. Quartz veining subparalleling the bedding with some highly oxidized layers up to 1 m thick with 10% to 15% pyrite. WP77 (572052 E, 6824622 N) is on the footwall of a 5 m thick fine to medium grained dark weathering sill striking 250° and dipping 30° south. Specimen 7 is from this sill and is a dark grey-green, fine grained diorite, slightly foliated, less than 1% fine pyrite, no magnetite and cut by numerous fine carbonate veinlets.

WP78 (571997 E, 6824630 N) is in the creek canyon on a long talus filled stream channel with a slope of -35°. There are numerous outcrops in the stream channel and canyon walls primarily of grey, finally bedded and foliated limestone. At WP83 (572087 E, 6824770 N) there is a waterfall flowing over limestone and at the base of the

falls there is a black basic sill, possibly a gabbro, 5m to 7 m thick. On the west side of the creek at WP84 (572097 E, 6824796 N) the sill/dike is exposed over 20 m, probably not true width. It appears to be cut off by a fault as it does not continue on the higher canyon wall to the northwest. At WP85 (572101 E, 24812 N) the limey sediments are highly contorted with irregular quartz veining. There is another waterfall at WP86 (572126 E, 6824893 N) composed of limey sediments cut at the base of the falls by a sill/dike of an interbedded andesitic crystal tuff with a strike of 330° and dipping 40° south. It is dark green-black fine grained groundmass, minor quartz veinlets with 1% fine grained pyrite, 1% magnetite and slightly foliated. At WP87 (572144 E, 4926 N) there is a small outcrop in the creek surrounded by talus. It is fine to medium grained diorite with irregular jointing similar to the grey feldspar porphyry in Reed-Kelli Creek. On the west bank of the canyon is an outcrop 3 m by 4 m of graphitic schist, strong foliation striking 350° and dipping 60° south. At WP90 (572163 E, 6824970 N) there is an outcrop area on the west side of the creek, 15 m x 8 m of blocky, massive crystalline limestone with numerous irregular discontinuous fractures partially filled with secondary carbonate. Hand Specimen 9, from the outcrop area, is probably a sill and is a dark greenish-grey, fine grained diorite, minor magnetite and less than 1% fine grained pyrite (Very similar groundmass to Specimen 7). The specimen is cut by hair-like white carbonate veinlets (5%) and carbonate filled fractures up to 5 mm thick. The groundmass does not effervesce in dilute HCl. Downstream there is no more outcrop but a large outwash talus fan extends down slope for hundreds of metres.

On the east side of the Kelli Claim Group the silt samples were taken from a short section of Reed-Allen Creek. Between WP46 (574780 E, 6824387 N), and WP48 (574813 E, 6824318 N) there is a very prominent, landmark outcrop that borders the east side of Reed-Allen Creek. Specimen 2 at WP46 is a feldspar porphyry intrusive, fine to medium grain, subhedral orange feldspar phenocrysts in a light grey aphanitic to subhedral plagioclase groundmass. No pyrite or magnetite. This is the same intrusive found on the west side of Reed-Kelli Creek cutting across the grey feldspar porphyry bordering the road.

Extensive mechanized placer gold mining has been carried out over a distance of 300 m to 400 m. These workings are obscured by windfalls of spruce and thick secondary growth alder. At the present time Bill Allen is hand placer mining in the area of WP46 at the base of the feldspar porphyry outcrop.

WP127 (574812 E, 6823778 N) marks the start of an outcrop-canyon in Reed-Allen Creek. Specimen 10 at WP127 is a weakly foliated fine grained diorite (andesite-crystal tuff?) no magnetite or pyrite. WP131 (574886 E, 6823675 N) is at the base of cliffs on the east side of the creek where it takes a sharp turn forming the structural "kink" related to placer gold deposition. The weathered cliffs have a distinct orange colour as a result of siderite forming as a thin coating on fracture and shear planes. The outcrop (Specimen 11) is a dark grey-green, moderately foliated chlorite schist.

GEOCHEMICAL SOIL AND SILT SAMPLING

General

The 2014 geochemical program was initially conceived to be 1 or 2 soil sample lines subparalleling both the east and west side of Reed-Kelli Creek. The objective was to see if the soil sampling could trace the gold and/or

copper mineralized zones in the Reed-Kelli Creek Canyon. It was recognized from the outset that soil sampling using a 3 inch diameter 4 foot long hand auger may have difficulty in collecting representative samples. A mattock was used to dig through the surface moss, organics and roots that blankets the slopes in the Kelli Claim area. This organic layer is from 0.1 m to as much as 0.5 m thick. Directly below this layer is a white, fine grained granular volcanic ash layer approximately 0.3 m thick. The ash is very dilutive of the elements in a soil sample so it is important to get through this ash layer and minimize its inclusion in a soil sample at depth. Often the auger could not penetrate the ash layer because of permafrost. If the auger could cut through the ash layer the soil sample was often taken on the surface of the frozen soil layer. The sample depth would vary from a few cm below the organic/ash layer to a maximum of 1 m.

The next problem with the soil sampling was determining what was being sampled, soil from decomposed bedrock or glacial till. Glacial outwash gravels and till occur at the south fork of Reed-Kelli Creek at an elevation of approximately 4,100 feet. A surface 'organic slide' exposed a slope of underlying glacial till at WP207 (57290 E, 3810 N), elevation 3,800 feet that extends down slope to the creek. The majority of the soil collected on both sides of Reed-Kelli Creek could easily fall within an underlying layer of glacial till masking bedrock. In addition, pebbles were observed in a large number of the soil samples indicating possible glacial till.

As a result of the problems associated with the soil sampling the sampling became an opportunistic search for thawed sites, such as soil beneath upturned tree stumps and shallow gullies often dry that may have cut through the volcanic ash layer. In addition, the sampling program was extended to silt sample collection from small discontinuous often dry stream channels cutting the surface organic layer and volcanic ash. These samples were often diluted with 5% to 20% volcanic ash. It was hoped that the silt samples would reflect a larger dispersion area from a potential underlying, relatively localized mineralized bedrock.

A total of 55 soil samples and 43 silt samples were collected for analysis by Acme Labs Ltd.

Histograms were drawn for gold analysis for both soil and silt samples. Because of the small number of samples and highly variable nature of the samples the histograms are of little value in determining anomalous values. For the silt samples a value of plus 70 ppb Au, for a total of 6 samples would be anomalous. For soil samples a value of plus 24 ppb Au, for a total of 7 samples would be anomalous. Considering the variable nature of the sampling a great deal of judgment is required to evaluate the potential anomalous value of a sample.

The soil and silt sample results are reviewed in part with the geological mapping.

Soil Sampling Map 1, 1:000

Soil samples KSO 23, 24, 25 and 26 are taken from a known arsenic-gold mineralized formation in the Lower Canyon on the east side of the creek in the area of the Pautler Trench (Map 1). These samples are not overly representative of the majority of the soil samples taken since they are from an area of little or no organic material, volcanic ash, permafrost or glacial till. The samples are from a steep, +30° slope bordering the south side of the dacite dike swarm. The samples are a mix of soil, silt and rock chips.

KSO	23	137 ppm Cu,	54 ppm As,	45 ppb Au	
	24	135 ppm Cu,	8 ppm Mo, 135 ppm Ni,	169 ppm As,	38 ppb Au
	25	93 ppm Cu,	9 ppm Mo,	78 ppm As,	23 ppm Au
	26	81 ppm Cu	6 ppm Mo,	94 ppm As	18 ppb Au

The copper, molybdenum and nickel values are very low amplitude but they are somewhat elevated and associated with arsenic, an important pathfinder element and gold, the primary element of economic interest.

Soil samples KSO 6, 153 ppm Cu and KSO 7, 120 ppm Cu WP 6 (573237 E, 6824386 N) are from the outlet area of a stream gully and probably fault/shear contact zone. The copper values are low but may be related to chalcopyrite mineralization reported in hand trenches much further upslope around the 3,900 foot to 4,000 foot elevation (Getsinger, 1998).

There are 14 soil samples taken on the west side of Reed-Kelli Creek starting at WP 99 (573367 E, 6824733 N) HSO 8 and continuing around the rim of the Lower and Middle Canyon. This is a southeast facing slope covered by open grass, scattered buckbrush and tall spruce trees. The permafrost is patchy above the Lower and Middle Canyon allowing for better soil samples below the volcanic ash layers.

WP 99 (573367 E, 6824733 N) is the location of KSO 9, 10 and 11 with the samples taken from different depths.

KSO	9	1.0 ppb Au	depth: 0 to 0.45 m; moss and roots, sample taken at base of organics 0.45 m to 0.60 m; volcanic ash
	10	77 ppm Cu, 19 ppb Au	depth: 0.70 m; good soil sample of sandy, pebbly soil and some rock fragments
	11	80 ppm Cu, 11 ppb Au	depth: 1.2 m total depth, start of permafrost

Samples KSO 12, WP 100 (573312 E, 6824700 N) to KSO 15 at WP 107 (573189 E, 6824663 N) are directly upslope to the west from the dacite dike swarm and are within the width of Structure 1. The four samples range from 20 ppb Au to 27 ppb Au with one sample having a value of 107 ppm Cu. The possibility of glacial till was noted.

The next three samples KSO 16, 17 and 18 are from the outcrop-canyon rim and have no anomalous values. These samples are taken directly upslope from a section of feldspar porphyry dikes and andesite volcanic.

The next three samples, KSO 19 to KSO 21 are taken upslope from the Middle Canyon composed of massive andesite/chlorite schist cut by numerous crenulated quartz veins with associated copper and gold values. KSO 19, WP 115 (572974 E, 6824320 N) has a value of 112 ppm Cu and 65 ppb Au. KSO 20 has very low values and was

taken from a shallow gully. KSO 21, WP 117 (572901 E, 6824258 N) was taken to the south of the gully and has a value of 119 ppm Cu and 78 ppb Au.

Sample KSO 22, WP 118 (572944 E, 6824155 N) is taken on the north side of a deep gully that is the contact zone between the Middle Canyon and andesite/chlorite schist and a formation of limey sediments (pc) extending to the south. The sample had a value of 6.6 ppm Mo, 140.1 ppm Cu and 8.9 ppb Au. The Mo value is very low but still elevated compared with the rest of the samples and combined with the Cu value could result from the close proximity of the feldspar porphyry dike down slope.

The soil sampling on the east side of Reed-Kelli Creek are plotted on Map 1 and start upstream at WP 150 (573055 E, 6824032 N), KSO 27 and is a poor soil sample mixed with volcanic ash. KSO 28, WP 151 (573064 E, 6824023 N) is 10 m upslope from KSO 27 (Cu 101 ppm) and is a better soil sample taken from under an uprooted spruce tree. The next sample is KSO 29, WP 152 (5731370 E, 6823997 N) at an elevation of 3,800 feet (1,159 m) has a value of 66.7 ppb Au. KSO 31, WP 154 (573244 E, 6824036 N) is from a small, dry shallow gully and has a value of 22 ppb Au. From KSO 32, WP 155 (573304 E, 6824098 N) the next 4 samples had very low values and 5 of the samples hit permafrost directly below the moss-organic layer. KSO 38, WP 167 (573475 E, 6824365 N) gave a value of 23 ppb Au. This is the last of the samples going northeast on the 3,800 foot contour. Starting at KSO 39, WP 168 (573480E, 6824395 N) the traverse goes down the ridge (KSO 41) to the north and then crosses from WP 172 (573506 E, 6824507 N) to WP 173 (573423 E, 6824530 N) to KSO 42 located in the south fault contact zone of Structure 1. KSO 42 has a value of 24 ppb Au. KSO 43 is 15 m southwest of KSO 42 and is taken from a small dry stream gully and has a value of 34 ppb Au. Going down slope to the west there is a prominent small point that drops off very steeply into the Lower Canyon with three early 1900s hand dug pits. Two of the pits were sampled by cutting down the wall with a mattock. The bottom of the pits were in permafrost. KSO 45 and KSO 46 have very low values for Cu and Au. This point is well to the south of Structure 1 and judging from the geology on the west side of the creek would be underlain by chlorite schist/andesite and is poorly mineralized except for minor disseminated pyrite.

The last small area of soil sampling located on Map 1 is in the area where Structure 2 crosses Reed-Kelli Creek. Sample KSO 5, WP 201 (572867 E, 6823871 N) is taken from under the upturned roots of a spruce tree on the north side of the creek. The sample has a value of 92 ppm Cu and 48 ppb Au. KSO 51, WP 203 (572814 E, 6823927 N) is taken from the same area as KSO 50 and has a value of 78 ppm Cu and 28 ppb Au. Going to the south on the south side of the creek KSO 52, WP 206 (572799 E, 6823860 N) has a value of 26 ppb Au, KSO 53 has a value of 77 ppm Cu and 24 ppb Au. KSO 54 is located on contour 10 m north of KSO 55, and is very low grade and is expected to have been a sample of glacial till. KSO 55, WP 207 (572790 E, 6823810 N) is taken from the top of an 'organic slide' exposing a long slope of glacial till. KSO 55 had a value of 22 ppb Au.

Soil Sampling Map 2, 1:3000

Soil and silt samples were collected along a traverse starting at WP 65 (572502 E, 6824389 N) at an elevation of approximately 4,400 feet and contouring to the west into a small steep gully and continuing east into a larger gully-stream tentatively named Reed-Erler Creek. The only soil samples are KSO 3, 4, 5 and 6 along the contour going into

the first gully. KSO 3, WP 66 (572446 E, 6824477 N) gave a value of 135 ppm Cu. KSO 4, WP 69 (572395 E, 6824510 N) gave a value of 92 ppm Cu and 27.6 ppb Au. KSO 5, WP 70 (572367 E, 6824520 N) gave a value of 226 ppm Cu, 71.7 ppm As and 59.9 ppb Au. KSO 6, WP 73 (572192 E, 6824541 N) is the last soil just on the west side of the gully and has a value of 141.6 ppm Cu but very low value for Au.

Silt Sampling Map 1, 1:1000

KSI 1 WP 2 (573392 E, 6824657 N) is a sample of silt and rock fragments of argillaceous-limey sediments on the east side of Reed-Kelli Creek at the start of the Lower Canyon and from a steep dry gully on the north side of the dacite dike swarm and within Structure 1. The sample value is 31 ppb Au.

KSI 2 is a sample composed of dark grey-black silt, soil and fine rock chips from a dry narrow stream channel, normally with a small flow of water and is located down slope from the south end of the Pautler Trench. This stream channel is the fault-contact between a dacite dike on the south and limey argillaceous graphitic schist on the north. KSI 2 has a value of **638.1 ppb Au**, the highest gold value of all the soil, silt and rock samples collected. The copper value of 83 ppm is background for the Lower Canyon and arsenic, a pathfinder element is low, 28 ppm.

KSI 3, 4 and 5 are from talus filled contact-fault zones on the west side of the Lower Canyon. These steep, +30° gullies were dry in August and the samples were a mix of silt, soil and rock chips. The sample values are 28 ppb Au, 66 ppb Au and 70 ppb Au. KSI 3 has a value of 34.3 ppm As and the other 2 samples have very low As values.

KSI 8, WP 12 (573018 E, 6824115 N) is from a contact-fault zone between Middle Canyon andesites/chlorite schist and Upper Canyon limestone. The sample is from the base of the contact zone on the road and had low values for base metals, arsenic and gold.

KSI 9, WP 13 (573004 E, 6824052 N) is silt from a small stream (spring) flowing out of the road bank and has very low values similar to KSI 8.

There were 3 silt samples taken from the bulldozer trench on the east side of the creek in the Upper Canyon.

WP 15, KSI 11	63.4 ppb Au
WP 17, KSI 12	18.3 ppb Au
WP 18, KSI 13	<u>253.6 ppb Au</u>

Arsenic values are low for all three samples. KSI 13 is the third highest gold value in the sample program.

The silt samples collected from the stream on the west side of Reed-Kelli Creek is the trace of Structure 2. KSI 39, WP 196 (5728715 E, 6823868 N) is the first sample from the creek and has a value of 96 ppb Au and 23 ppm As. KSI 40 and KSI 41 are approximately 15 m upstream. KSI 40 has a value of **319 ppb Au** and is the second highest value sample collected. The arsenic value is 29 ppm. KSI 41 has a value of 50 ppb Au and 26.6 ppm As. Seventy metres up the stream KSI 42 has a value of 39 ppb Au and 30.8 ppm As.

Silt Sampling Map 2, 1:3000

Silt and soil samples were collected on a traverse starting with KSI 30, WP 65 (572502 E, 682447 N) and contouring west and then going down Reed-Erler Creek. KSI 3 has a value of 131 ppm Cu, 102 ppm Ni and 174 ppm Cr. It is a sample from a small dry stream gully originating from the steep +35° to 40°, talus slope to the west. This traverse is above the 'timber line' and crosses an open moss-heather alpine environment. The next series of samples KSI 31 to KSI 34 are good silt samples from the largely talus filled Reed-Erler Creek.

KSI 31, WP 31	103 ppm Cu,	98 ppm Ni,	101 ppm Cr
KSI 32, WP 80	49 ppm Cu,	92 ppm Ni,	100 ppm Cr
KSI 33, WP 83	106 ppm Cu,	81 ppm Ni,	85 ppm Cr
KSI 34, WP 85	102 ppm Cu,	82 ppm Ni,	90 ppm cr

The gold values are very low for all four samples.

KSI 35 and KSI 36 were poor silt samples from the outwash fan and there were insufficient fines for analysis. KSI 37 is a poor silt sample mixed with volcanic ash and has a value of 73 ppm Cu and 19 ppb Au.

The traverse continued east contouring back to Reed-Kelli Creek through stunted black spruce, muskeg and permafrost. A silt sample, KSI 38, from a small stream gave a value of 125 ppb Au.

The next traverse starts at KSI 14, WP 23 (573590 E, 6824489 N) and has a value of 27 ppb Au. KSI 15 25 m to the west has a value of 24.1 Au. Between KSI 15 and KSI 16, WP 26 (573837 E, 6823886 N) the traverse is to the southwest crossing a slope in the order of +25° covered in stunted black spruce and a thick surface layer of moss/organics on permafrost. The small streams crossed were full of volcanic ash and were not sampled. At WP 26 (573837 E, 6823886 N) there is a small stream with good silt and minimal volcanic ash. KSI 16 was collected and gave very low values of 78.3 ppm Cu and 17.3 ppb Au. The traverse goes southeast following the 4,300 foot contour in an alpine environment. KSI 17 samples a small stream and has very low values. KSI 18, WP 29 (574256 E, 6823840 N) is from a small stream channel and has a value of 43 ppb Au. From WP 19 the traverse goes down slope (-20°) through open spruce, scattered alder and thick moss. KSI 20, WP 35 (574424 E, 6824316 N) has a value of 81 ppb Au. The traverse then heads northwest contouring along the lower slope (+5° to +10°) through stunted black spruce and muskeg. KSI 21, 30 m to the west of KSI 20, is a good silt sample from a small stream and gave values of 105.3 ppm Cu, 19 ppm As and **135.4 ppb Au**. KSI 22 is from a small creek 15 m west of KSI 21 and has high values in Mn, greater than 10,000 ppm and 574 ppm Ba. This is the only sample with such a high value of manganese and barite. The Cu value is 105 ppm and Au is 58.4 ppb. KSI 23, WP 38 (574242 E, 6824641 N) is a good silt sample from a flowing stream 20 m west of KSI 23 and has a very low gold value and the next two silt samples from small streams have low values. KSI 26, WP 41 (573990 E, 6824893 N) is a good silt sample from a deep stream gully with spruce and alder. KSI 26 has a very low gold value. Sample KSI 27, 15 m to the west gave a value of 55.7 ppb Au.

These following silt samples were collected from Reed-Allen Creek on the east side of the Kelli Claim Group. KSI 28, WP 49 (574812 E, 6824308 N) is a good silt sample from the creek in the area of the Allen placer gold

workings. The sample has a value of 44 ppb Au and low As, 16.5 ppm. ASI 1, WP 125 (574836 E, 6823976 N) is a good silt sample from the creek and has a value of 70 ppm Cu and 16 ppb Au. ASI 2, WP 131 (574086 E, 6823675 N) is a good silt sample at the start of a major outcrop-canyon going up Reed-Allen Creek and gave values of 103 ppm Cu and 21.9 ppb Au.

CONCLUSION

The initial concept of the soil sampling program was to see if the sampling could trace the gold mineralization associated with lesser copper and arsenic elements known to occur in at least three different geological settings in the Reed-Kelli Creek Lower to Upper Canyons.

The gold values in the Lower Canyon are in a highly metamorphosed, complex assemblage of dikes, sediments and volcanic rocks that are caught up in a major regional fault structure subparalleling the Denali Fault (Shakwak Trench) located immediately to the north. This structure (Structure 1) is well documented and has been traced in creek drainages for many kilometers both to the northwest and southeast of the Kelli Claim Group. These drainages have gold placer deposits associated with the fault structure.

This soil sampling was initially planned for two subparallel lines on each side of the Reed-Kelli Creek drainage in the canyon area that had been extensively placer gold mined. Sampling was to be at approximately 50 m spacing with samples taken by hand auger. This plan was soon abandoned because the auger could not penetrate beneath the surface moss-organic mat and collect representative soil samples. The soil sampling became an opportunistic search for sample sites that were thawed enough to allow the auger to obtain soil samples below the volcanic ash. The soil sampling was supplemented by silt samples from small stream channels, often dry and often contaminated with variable amounts of volcanic ash. The other problem is the suspected extent of glacial till of unknown thickness masking underlying weathered bedrock.

Because so much is known of the trend of the mineralization formations, such as Structure 1 the Lower Canyon area soil sample values along the Structure can be extrapolated to fit the geology. As a result, gold values of 16 ppb Au to 27 ppb Au can be considered elevated gold values tracing Structure 1. However, the quality of the soil samples are very erratic so sample KSO 48 and KSO 49 further to the east of the Lower Canyon and taken along the trace of Structure 1 gave very low values of 5 ppb Au and 4 ppb Au. These two samples do not mean the gold mineralization in Structure 1 ends but only indicates a better sampling method and greater density of samples is required. However, it can be concluded that this reconnaissance soil sampling was of value as an orientation/learning tool but it also indicated some gold anomalous values in areas that had been considered low priority.

Structure 2 crosses Reed-Kelli Creek at the south end of the Upper Canyon. Initially this was considered to be a low priority exploration area as the predominant formation (PC) is a poorly mineralized, folded limestone. However, the soil and silt samples did locate anomalous silt values in the area of the bulldozer trench on the west side of Reed-Kelli Creek. KSI 13 has a value of 254 ppb gold, KSI 11 a value of 63 ppb gold. The tributary stream on the west side of Reed-Kelli Creek that is the trace of Structure 2 has 5 gold anomalous silt values as high as 319 ppb. A short soil sample line to the south of the creek has gold values from 22 ppb to 26 ppb. It is concluded that this area warrants additional exploration.

Soil and silt sampling to the west of Reed-Kelli Creek (Map 2) from the traverse crossing the ridge and going down Reed-Kelli Creek gave low amplitude but elevated values for copper, nickel and chrome. These values are

probably related to low copper and nickel mineralization associated with basic dikes that have been mapped in the area. Only one sample, KSO 5, was gold anomalous with 226 ppm copper, 72 ppm arsenic and 60 ppb gold.

The traverse west to Reed-Allen Creek did locate extensive mechanized placer gold mining in the creek and a large outcrop-ridge of feldspar porphyry, the same intrusive as found in Reed-Kelli Creek. It is also interesting to note the three gold anomalous silt samples: KSI 20, 81 ppb gold; KSI 21, 135 ppb gold; and KSI 22, 58 ppb gold are located down slope from the projection of Structure 1 to Reed-Allen Creek. There are also two more silt samples further to the west from the same traverse, KSI 23, 46 ppm gold and KSI 27, 56 ppb gold that are considered elevated gold values.

The rock sampling was focused on Structure 1 crossing the Lower Canyon in Reed-Kelli Creek. Fifteen rock samples were collected for analysis with five of them, H1 to H5, being a continuous channel sample from the Pautler Trench. One of the samples, H4, gave a value of 160 ppm arsenic and 56.5 ppb gold. The pathfinder mineral arsenic is anomalous and so is the gold value but not of economic value. The remaining ten samples were from various locations within Structure 1 and were selected to test different rock types and related structures for gold. These samples were very low grade in arsenic and gold. Two samples had elevated values for copper of 175 ppm and 141 ppm, but gold values of only 5 ppb and 9 ppb. It is concluded that Structure 1 has elevated gold values where it crosses Reed-Kelli Creek but has limited economic potential. However, sampling by Teck Corporation in 2000 and by Jean Pautler in 2001 of a trench located on the west side of the road and 40 m north of the dacite dike swarm had very positive results. Teck, over 18 m obtained 0.4 grams/t gold. Pautler's sampling gave consistent elevated values in gold and arsenic with a weighted average over 21.5 m of trench of 0.34 g/t gold (Pautler, 2001). This section has not been trenched during the latest exploration program. The trench has been obscured by downhill erosional creep and thick alders.

The Middle Canyon is underlain by highly altered dark green chlorite schist of andesite origin and cut by numerous quartz veins with widths up to 2 m that are highly fractured and folded and erratically mineralized with chalcopyrite and pyrite. A grab sample taken in 2011 from this area had a gold value of 2.28 g/t. This is a prospective unit for gold mineralization and has not been adequately mapped and sampled.

It is concluded that the Kelli Claim Group is in a very early stage of exploration and that ongoing work to evaluate its gold potential is warranted.

RECOMMENDATIONS

- 1) Continue the geological mapping on a scale of 1:1000 from where it ended in the Lower Canyon, up through the Middle Canyon and Upper Canyon to Structure 2. The mapping will include extensive sampling of prospective sulfide-mineralized structures in the Middle Canyon.
- 2) Map on a scale of 1:2000 from Structure 2 where it crosses Reed-Kelli Creek upstream to the forks a distance of 1 kilometre. Collect soil samples along the banks of the creek where there is thawed soil. Silt sample springs coming out of the bank.
- 3) Map Structure 2 up its trace along the tributary streams both to the east and west of Reed-Kelli Creek. Collect silt samples and soil samples where possible.
- 4) Trench and sample the Pautler Trench 01-6 referred to under Conclusion and continue the trenching and sampling to the north to connect with the section trenched in 2012.

Respectfully submitted



Gordon Gutrath, P.Eng

REFERENCES

- Bremner, T. 1991, *Reed Creek, INAC, 1991, Yukon Exploration 1990*, p. 60-64
- Dodds, C.I. and Campbell, R.B. 1992, Overview, legend and mineral deposit tabulations for *Geological Survey of Canada* Open files 2188, 2189, 2190 and 2191
- Getsinger, J.S. 1998, *Preliminary Field Evaluation of the Kelli Property Area, Reed Creek, Y.T.* (unpublished)
- Pautler, J., P.Geo. 2001, *Geological, Geochemical and Trenching Report on the Kelli Property* (unpublished)
- McFaul, J. 2004, *Kelli Creek Group, Diamond Drilling Program* filed Yukon Mining Incentives Program
- Tremblay, L. 1983 to 2007, Extensive reports, memos, maps, sampling data and photographs of geology related to mineralized zones (private collection)
- Gutrath, G. 2012, *Geological Report Kelli Claim Group*, assessment work filing
- Gutrath, G. 2014, *Geological Report Kelli Claim Group*, assessment work filing

APPENDIX A

STATEMENT OF QUALIFICATIONS

ENGINEER'S CERTIFICATE

I, GORDON GUTRATH, of 702 – 181 Athlete's Way in the city of Vancouver in the Province of British Columbia, DO HEREBY CERTIFY:-

1. That I am a geologist with a business address of 702 – 181 Athlete's Way, Vancouver BC V5Y 0E5
2. That I am a graduate of the University of British Columbia where I obtained by B.Sc., in geological science in 1960.
3. That I am a Registered Professional Engineer in the Geological Section of the Association of Professional Engineers in the Province of British Columbia
4. That I have practiced my profession as a geologist for the past fifty-five years.

DATED at the city of Vancouver, Province of British Columbia, this 11th day of February, 2015.



Gordon G. Gutrath, B.Sc., P.Eng.

APPENDIX B

SILT SAMPLING WITH ELEVATED/ANOMALOUS VALUES

SILT SAMPLE				
Sample # KSI	Waypoint #	UTM Coordinates		Description
		East	North	
				Plotted on Map 1 and 2
1	2	3392	4657	Mix of rock chips, soil and silt (talus)
2	2	3392	4657	Upstream from 1 in steep narrow talus filled gully, damp silt <u>638 ppb Au</u>
3	3	3298	4638	Dry, minor silt, rock chips and soil <u>28 ppb Au</u>
4	4	3265	4536	Damp silt fines, rock chips, + 25 to 30° gully – contact Zn <u>66 ppb Au</u>
5	5	3251	4573	Damp silt – rock chips +30° gully, upslope from KSI 1 <u>70 ppb Au</u>
6	6	3273	4386	Damp silt at mouth of narrow stream, gully +15° slope, 20% volcanic ash <u>153 ppm Cu, 69 ppb Au</u>
7	7	3279	4378	Wet silt, 10 m upstream gully from KSI 6, 20% volcanic ash <u>120 ppm Cu, 46 ppb Au</u>
8	12	3018	4115	Damp silt at outlet of steep gully, +25° slope
9	13	3004	4052	Damp silt, small spring, thick alder
10	14	2889	3822	Damp, sandy-silt, flowing stream, large boulders
11	15	3003	4014	Damp sandy-silt, small stream flowing out of trees <u>43 ppb Au</u>
12	17	3010	3990	Damp silt, trickle of spring into bulldozer trench <u>63 ppb Au</u>
13	19	3019	3994	Damp silt, flowing spring running into bulldozer trench <u>254 ppb Au</u>
14	23	3590	4489	Damp silt, +50% volcanic ash, small stream incised 2 to 3 m into muskeg <u>27 ppb Au</u>

SILT SAMPLE				
Sample # KSI	Waypoint #	UTM Coordinates		Description
		East	North	
15	24	3608	4416	Damp sandy-silt, rock fines/chips, 10% volcanic ash, alder/muskeg slope +20°
				Plotted on Map 2
16	26	3837	3886	Network of small streams at base of steep slope +30°, heather, damp sandy silt
17	28	3977	3776	Damp sandy-silt, dry stream bed in large angular talus boulders, slope +25°, at top of gully trending 20°
18	29	4165	3671	Damp sandy-silt, steep talus filled gully <u>43 ppb Au</u>
19	31	4334	3975	Damp-wet sandy-silt, small stream, alder <u>53 ppb Au</u>
20	35	4424	4316	Damp silt, running stream in broad gully <u>81 ppb Au</u>
21	36	3547	4681	Damp silt, small stream, +20° slope <u>135 ppb Au</u>
22	37	4362	4428	Wet silt in running stream, cobble gravels <u>105 ppm Cu, 10,000 Mn, 574 ppm barite, 58 ppb Au</u>
23	38	4242	4641	Brown, sandy-silt, wet, flowing stream <u>46 ppb Au</u>
24	39	4195	4678	Sandy-silt, pebble gravels, small stream flowing
25	40	4114	4746	Damp silt, small stream
26	41	3990	4893	Silt from running stream channel, deep gully

SILT SAMPLE				
Sample # KSI	Waypoint #	UTM Coordinates		Description
		East	North	
27	42	3956	4908	Silt from deep incised stream channel <u>56 ppb Au</u>
28	49	4812	4308	Damp silt from Reed-Allen Creek <u>44 ppb Au</u>
30	65	2502	4389	Damp grey silt from dry small creek bed, pebbles, slope on edge of small bench +15° <u>131 ppm Cu, 102 ppm Ni, 174 ppm Cr</u>
31	78	1997	4630	Damp grey silt, running stream, talus +25° grey limestone (pc) outcrop in creek <u>103 ppm Cu, 98 ppm Ni, 101 ppm Cr</u>
32	80	2037	4686	Poor silt sample, flaky grey granular, stream under talus canyon 8 to 10 m wide, +25° <u>99 ppm Cu, 92 ppm Ni, 100 ppm Cr</u>
33	83	2087	4770	Good silt, grey, 15 m downstream from foot of waterfall, 'basic' sill 5 – 7 m cuts waterfall underlain by limestone (pc) <u>106 ppm Cu, 81 ppm Ni, 85 ppm Cr</u>
34	85	2126	4893	Good silt, damp, flowing stream, +30° <u>102 ppm Cu, 82 ppm Ni, 90 ppm Cr, 23 ppb Au</u>
35	91	2168	4991	Grey, poor silt, creek flows under large outwash, talus fern (insufficient sample for analysis)
36	93	2353	5040	Damp sandy-silt from small dry creek (insufficient sample for analysis (?))
37	93	2353	5040	Damp sandy-silt from small shallow stream channel, some volcanic ash
38	94	3394	5080	Sandy-silt sample, damp, small flow of water from shallow, narrow stream <u>125 ppb Au</u>

SILT SAMPLE				
Sample # KSI	Waypoint #	UTM Coordinates		Description
		East	North	
39	196	2871	3868	Good silt sample at base of waterfall stream flowing ± 5 gal/m. <u>96 ppb Au</u>
40	199	2855	3874	Good silt sample from stream channel <u>319 ppb Au</u>
41	200	2867	3871	Good silt sample from wide stream channel running under angular boulders <u>50 ppb Au</u>
42	203	2814	3927	Good silt sample in creek channel, highly oxidized cobbles of pyritic argillite <u>39 ppb Au</u>
Sample # ASI				
1	125	4836	3976	Good silt sample from Reed-Allen Creek <u>70 ppm Cu, 15.8 ppb Au</u>
2	131	4886	3675	Good silt sample from Reed-Allen Creek at the start of a deep canyon/outcrop <u>103 ppm Cu, 21.9 ppb Au</u>

APPENDIX C

SOIL SAMPLING WITH ELEVATED/ANOMALOUS VALUES

SOIL SAMPLES				
Sample # KSO	Waypoint #	UTM Coordinates		Description
		East	North	
				Plotted on Map 1 and 2
1	62	2847	3952	+0.30 m organic, 0.45 m layered organic and ash 0.76 m gravelly damp soil on perma frost (PF), open spruce, +20° slope
2	63	2787	4011	0 to .03 m moss-organic, 0.3 m to 0.6 m mixed organic-sandy gravel to 0.9 m - frozen (PF) damp, grey-brown sandy soil sample, large spruce trees, muskeg, +20° slope
				Plotted on Map 2
3	66	2446	4477	0 to 0.15 m organic/heather, 0.15 m to 0.60 m mix pebble- soil sample, permafrost, +35° slope <u>135 ppm Cu</u>
4	69	2395	4510	0 to 0.15 m to permafrost. Poor soil development, mixed with talus, sample damp, dark brown, some organic and ash content. +45° slope heather <u>92 ppm Cu, 28 ppb Au</u>
5	70	2367	4520	Thawed talus slope, sample depth 0.60 m cumulative rock fines, soil poor, heather, +40° slope <u>226 ppm Cu, 72 ppm As, 60 ppb Au</u>
6	73	2192	4541	Scattered organic mat mixed with talus, sample is a mix of rock fines and dark soil taken at 0.45 m <u>141 ppm Cu</u>
				Plotted on Map 1 and 2
7	97	3463	4732	0 to 0.45 m, organic/moss, 0.30 m volcanic ash, 0.10 m sandy-gravelly soil. Located 2 m from bank of creek, thawed.
8	98	3422	4767	0 to 0.3 m moss, 0.45 m of volcanic ash, sample from 0.15 m of dark brown mix of ash and soil with small rock fragments, permafrost at 0.91 m depth, +10° slope

SOIL SAMPLES

Sample # KSO	Waypoint #	UTM Coordinates		Description
9 10 11	99	3367	4793	Large 'blow-down' spruce uplifted root system exposing 0.45 m moss over 0.60 m volcanic ash, then layer of dark brown soil getting more sandy-gravelly to a depth of 1.2 m, +15 to 20° slope. Sample 9: top of ash directly below moss 1.0 ppb Au 10: dark grey pebbly soil below volcanic ash 19 ppb Au 11: bottom of auger hole wet clay (till?), pebbly on top of permafrost 11 ppb Au
12	100	3312	4700	Auger hole below uprooted tree 10 m to east of rim of canyon. Sample of thawed pebble-clay material at a depth of 0.76 m (glacial till?), +20° slope <u>20 ppb Au</u>
13	103	3273	4676	0 to 0.20 m moss, 0.30 m of volcanic ash, dark grey-brown sandy soil with moss-clay at bottom of hole at 0.61 m (sample). Open ridge with spruce 10 m to east, +45° slope <u>22 ppb Au</u>
14	105	3216	4675	0 to 0.24 m, 0.15' of ash, pebbly-sandy, gravelly soil, damp grey-brown sample at 0.76 m. WP105 is 2 m east of ridge and outcrop, canyon rim is ±30 m to east
15	107	3189	4663	0 to 0.15 m organic/moss dry, 0.45 m of volcanic ash, dry light brown, sample from pebbly-sandy soil at depth of 0.9 m, thawed, open spruce, slope -30° to east. <u>107 ppm Cu, 27 ppb Au</u>
16	111	3180	4567	0 to 0.30 moss, 0.30 m of volcanic ash, 0.30 m of organic-ash mix. Sample from 1.07 m, damp pebbly-silty soil. Ridge is 30 m to west, outcrop rim is ±20 m to east at -30° slope. Open spruce.

SOIL SAMPLES

Sample # KSO	Waypoint #	UTM Coordinates		Description
17	112	3150	4464	0.30 m moss and roots, sample from depth of 0.9 m from pebbly-grey soil with clay and organic layers. No volcanic ash. -30° slope, outcrop rim ± 30 m to east. Tall spruce and scattered alder.
18	113	3060	4395	0 to 0.15 m moss, 0.15 m to 0.46 m volcanic ash, 0.46 m to 0.90 m dark blackish-brown damp silty soil. Sample from 0.90 m, location is on ridge with spruce and scattered alder. Outcrop rim is ±40 m to east at -25° slope.
19	115	2974	4320	0 to 0.30 m moss and surface organics, 0.3 m to 0.60 m volcanic ash, 0.60 m to 0.90 m damp pebbly-clay soil. Sampled at 0.90 m depth. Slope to east at -25°, tall spruce. <u>112 ppm Cu, 65 ppb Au</u>
20	116	2910	4294	0 to 0.15 m moss and roots, 0.15 m to 0.60 m damp pebbly-sandy gravel sampled at 0.60 m. Slope -20° to east. ±50 m to rim in gully with thick alders.
21	117	2901	4258	Angular rock forming talus slope. Dry sample of sandy soil between rock fragments. No volcanic ash. <u>119 ppm Cu, 78 ppb Au</u>
22	118	2944	4155	0 to 0.30 m moss-organics, 0.30 m to 0.60 m mixed ash, muck and at 0.60 m the sample is from damp sandy-pebbly soil. Open spruce, mixed alder. Slope is -35°. <u>140 ppm Cu, 6.6 ppm Mo</u>
23	122	3387	4621	Slide material/soil on alder slope -30°. Sample taken at 0.30 m directly above bedrock. 25% fine grained graphitic-argillaceous chips mixed with dark grey-black sandy soil. Sample is just up slope from trench (Pautler 01-5) and 2014 rock samples H1 to H5. <u>137 ppm Cu, 54 ppm As, 44 ppb Au</u>

SOIL SAMPLES

Sample # KSO	Waypoint #	UTM Coordinates		Description
24	(221)	3395	4623	Sample of fine rock (soil) from talus slope between trench and massive dacite dike outcrop. <u>135 ppm Cu, 7.6 ppm Mo, 135 ppm Ni, 170 ppm As, 38 ppb Au</u>
25	(221)	3395	4623	Sample taken from same talus slope as KSO24 but of different material across the talus slope (+30°). Black damp soil from talus slope that is made up of small angular fragments of graphitic limey argillaceous schist and altered dacite dike. <u>94 ppm Cu, 9 ppm Mo, 78 ppm As, 23 ppb Au</u>
26	(221)	3395	4623	Sample from black sandy soil material on top of black graphitic limey argillaceous outcrop 1 m south of massive dacite dike. Narrow, discontinuous quartz veinlets are common in the outcrop. Fine pyrite. <u>82 ppm Cu, 6 ppm Mo, 94 ppm As, 15 ppb Au</u>
27	150	3055	4032	0 to 0.30 m organic, 0.30 to 0.60 mix of organic and volcanic ash, 0.60 m – poor soil sample, damp, pebbly clay permafrost.
28	151	3064	4023	Damp pebbly-clay soil, minor ash, sample from depth of 0.45 m under a fallen spruce tree stump. Small spruce and alder, muskeg +25° slope. <u>101 ppm Cu</u>
29	152	3170	3997	0 to 0.30 m moss-organics, 0.30 m to 0.46 m mix of organics-volcanic ash, 0.46 to 0.91 m dark brown silty-pebbly sample, no permafrost. Scattered spruce, alder and buckbrush, +30° slope. <u>66 ppb Au</u>
30	153	3202	4014	In dry shallow gully, 0 to 0.45 m moss-organics, 0.45 m to 0.76 mixed volcanic ash. Sample from damp, dark brown pebbly soil at 0.76 m. Alder, scattered spruce and buckbrush, +25° slope.

SOIL SAMPLES				
Sample # KSO	Waypoint #	UTM Coordinates		Description
31	154	3244	4036	0 to 0.45 m of muskeg, organics layered with volcanic ash. Sample taken at 0.90 m from dark brown damp soil with pebble layers. Small shallow gully, dry muskeg alder, scattered mid-size spruce on both sides of gully. +35° slope. <u>22 ppb Au</u>
32	155	3304	4098	0 to 0.15 m shallow moss-organics, sample from 0.30 m of mix of ash, clay pebbles and organic material permafrost at 0.30 m, buckbrush, widely scattered spruce, +20° slope.
33	156	3357	4173	0 to 0.90 m layered organics and volcanic ash. Sample from gummy clay soil between 0.90 m and 1 m. Permafrost. Buckbrush, widely scattered spruce, -30° slope.
34	158	3363	4195	0 to 0.45 m moss-organics. Sample from 0.45 m of damp clay, organics, no volcanic ash (poor sample), buckbrush, +25° slope.
35	163	3411	4265	0 to 0.45 m organic with volcanic ash, 0.45 m to 0.76 m, sample of wet, sandy-pebbly soil. Shallow gully, no water, scattered spruce, willow and alder.
36	165	3447	4327	Fallen spruce tree, roots upturned, 0 to 0.90 m a mix of organics and volcanic ash into poor soil – permafrost at 0.90 m, sample from 0.85 m. On a ridge, buckbrush, +15° slope.
37	166	3462	4355	0 to 0.30 m moss-organics, 0.30 to 0.45 m volcanic ash, 0.45 m to 0.50 m damp brown soil mixed with volcanic ash (poor sample), permafrost at 0.50 m. Scattered spruce going down slope at -25°, buckbrush.
38	167	3475	4365	0 to 0.30 m moss-organics, 0.30 to 0.60 m volcanic ash, 0.60 to 0.76 m dark brown, damp, sticky soil. Sample at 0.76 m on permafrost, scattered spruce, alder, buckbrush, slope -25°. <u>23 ppb Au</u>

SOIL SAMPLES				
Sample # KSO	Waypoint #	UTM Coordinates		Description
39	168	3480	4395	0 to 0.30 m moss-organics, 0.30 to 0.60 m volcanic ash and 70% brown damp soil on permafrost, buckbrush, scattered spruce, -30° slope.
40	169	3488	4417	0 to 0.30 m moss, 0.30 m to 0.60 m volcanic ash, damp brown pebbly soil, sample at 0.60 m on permafrost. Scattered spruce and buckbrush on -30° slope.
41	170	3494	4465	0 to 0.30 m moss, 0.30 to 0.60 m volcanic ash, gummy dark brown mix of volcanic ash, organics and soil (poor sample). Buckbrush and scattered spruce on -30° slope.
42	173	3423	4530	0 to 0.45 m sandy, pebble cobble glacial till sampled at 0.45 m, damp. -35° to -45° slope in a broad gully. Alder, willow, scattered spruce. <u>24 ppb Au</u>
43	174	3403	4527	0 to 0.30 m moss-organics, 0.30 m to 0.60 m gravelly-pebbly till, damp sample. Fork in gully but no stream. <u>34 ppb Au</u>
44	175	3364	4535	0 to 0.45 m wet organics, 0.45 m to 0.60 m mix dark brown soil/organics but no volcanic ash. Open muskeg, small spruce, -25° slope.
45	176	3344	4540	(Early 1900s hand dug pit 1.5 m deep). Grubhoe cut made on south side of pit to a depth of 1.2 m where sample was taken. Dark brown, damp soil, good sample and does not appear to be glacial till. Second cut was made on north side of pit with 0.30 m of volcanic ash at surface, then into organics for 0.40 m, then back into volcanic ash for 0.30 m on permafrost – no soil.
46	178	3335	4552	(1900s pit 1.52 m deep by 2 m by 3 m) 0 to 0.9 m organics-pit material mixed, 0.9 m to 1.2 m volcanic ash, 1.2 m to 1.5 m at bottom of pit, pebble gravel till? sampled. Only 2 to 4 m from edge of rim and canyon on edge of creek at -45° to -60° slope. Pits are on a small bench (point), +15° slope.

SOIL SAMPLES

Sample # KSO	Waypoint #	UTM Coordinates		Description
47	180	3417	4537	Sample location in a broad gully. Soil-silt at depth of 0.30 m, sample of pebbly-sand-gravel-rock fragments.
48	181	3489	4603	0 to 0.3 m moss-organics, thin layer of volcanic ash 0.15 m thick. Sampled at 0.45 m of damp pebbly-sandy dark brown soil. Poor sample on permafrost.
49	182	3522	4625	0 to 0.30 m moss-organics, 0.3 m to 0.6 m irregular volcanic ash layer, poor soil, wet silty-sandy pebbly barely thawed layer on permafrost, slope -35°, scattered spruce.
50	201	2867	3871	Large spruce fallen across creek. Roots exposed, good soil at 0.45 m depth, pebbles grey-brown, +20° slope, spruce and alder. <u>92 ppm Cu, 48 ppb Au</u>
51	203	2814	3927	Went up north bank of creek +25° slope, thin organic layer. Sample of good sandy-pebbly soil at a depth of 0.30 m, spruce and alder. <u>78 ppm Cu, 28 ppb Au</u>
52	206	2799	3860	0 to 0.35 m mixed muck organics and volcanic ash. Sample at 0.60 m of grey ground pebbly soil. Tall spruce, willow and alder at +30° slope. <u>26 ppb Au</u>
53	---	3842	3695	Between sample 52 and 54. Same material as KSO 52. <u>77 ppm Cu, 24 ppb Au</u>

APPENDIX D

ROCK SAMPLES WITH ELEVATED/ANOMALOUS VALUES

ROCK SAMPLES

Specimen #	Waypoint #	UTM Coordinates		Description Start of Sampling North end of Pautler Trench		
		East	North	Interval	Number	Width
H1	219	3388	4625	0.00 to 1.22 m	H1	(1.22 m)
H2				1.22 to 3.04 m	H2	(1.82 m)
H3				3.00 to 4.10 m	H3	(1.06 m)
H4				4.10 to 5.31 m	H4	(1.21 m)
H5	218	3388	4617	5.31 to 6.53 m	H5	(1.21 m)
				Talus slope sample	H6	
H6	220 221	3395 3395	4621 4623	H6 (most northerly sample in series) WP 220 to 221 (H6) is a collection of talus fragments between WP 219 and the massive dacite dike to the north. The sample is made up of graphitic-limey argillaceous fragments and highly altered felsic dacite dike, quartz stringers, fine grained pyrite 1% - 5%. 21.4 ppm As, 2.5 ppb Au		
H1				Black platy limey argillite with quartz veinlets 1 cm to 10 cm in width. 1% to 3% pyrite. 60.8 ppm As, 3.4 ppb Au		
H2				50% orange-cream irregular felsic highly altered dacite dike and 50% black limey argillite, quartz veinlets, pyrite 2%. 37.0 ppm As, 0.5 ppb Au		
H3				Brittle platy black argillaceous graphitic schist, thin irregular quartz veins 10%, pyrite 3% to 4%. 46.9 ppm As, 11.7 ppb Au		
H4				Interlayered mix of brittle black limey argillaceous graphitic schist and altered dacite dike, pyrite 2% to 4%. 18 ppm Pb, 101 ppm Zn, 161 ppm As, 56.5 ppb Au		
H5				Highly crenulated, platy sheared limey argillaceous schist with limonitic-siderite coating on shear planes $\pm 3\%$ discontinuous quartz veinlets. 34.5 ppm As, 1.2 ppb Au		

ROCK SAMPLES				
Specimen #	Waypoint #	UTM Coordinates		Description Start of Sampling North end of Pautler Trench
H7	183	3303	4639	Sample from bottom of a +30° talus slope – contact zone between massive feldspar porphyry on the south to intensely sheared chloritic andesite on the north. The schist is cut by quartz veinlets with ±5% fine grained pyrite.
H8	183	3303	4639	Sample taken up the talus slope 20 m from WP 183. H8 is on north side of contact zone from limonitic-oxidized weathering thin quartz veins in chlorite schist. Pyrite 5%. <u>175 ppm Cu</u>
H9	183	3303	4639	H9 is from same area of talus slope as H8 but sample is taken to south contact of talus slope +30°. Chlorite schist, quartz veinlets, oxidized fine pyrite.
H10	185	3337	4645	Sample of highly altered graphitic limey schist and dacite dike on north contact of major structural zone of massive brecciation/folded graphitic limey argillaceous sediments. Irregular quartz veinlets, pyrite 2% to 5% 37.6 As, 8.2 ppb Au
H11	184	3304	4641	Fine grained green moderately foliated massive chloritic schist cut by irregular cross-cutting hair-like quartz veinlets. Pyrite in fine to medium grained discrete clots and crystals. No magnetite.
H12	146	3355	4601	Sample is from talus slope contact zone between massive dacite dike on the north and major structural-deformation zone to the south. H12 is taken at base of +30° slope from quartz veined, limey-graphitic argillaceous schist with 5% fine grained pyrite disseminated and associated with irregular thin quartz veinlets.
H13	146	3355	4601	H13 is taken upslope +30° from south wall of contact zone from 0.20 to 0.50 m of oxidized quartz veining in black/green limey-carbonaceous graphitic schist.
H14	147	3339	4638	Sooty grey black weathering argillite, 3% to 5% fine cubic pyrite, effervescent white salts on weather surfaces 1 m thick.

ROCK SAMPLES

Specimen #	Waypoint #	UTM		Description
		Coordinates		Start of Sampling North end of Pautler Trench
H15	148	3310	4630	Selected sample from base of talus slope of highly altered dacite dike with oxidized quartz veinlets on fractures. Pyrite 3%, no magnetite. 141 ppm Cu, 2.4 ppb Au

APPENDIX E

METHOD OF SILT AND SOIL SAMPLE COLLECTION

ACME LABS SAMPLE ANALYSIS FOR SILT, SOIL AND ROCK SAMPLES

METHOD OF SILT AND SOIL SAMPLE COLLECTION

Silt samples were collected using a stainless steel trowel from areas away from the running stream. The samples were damp, not wet, and placed in Kraft paper bags.

Soil samples were collected with a stainless steel 3 inch diameter hand auger on a four foot long collapsible shaft. The soil was removed from the auger using a trowel and placed on a sheet of plastic. The sample was then transferred to a Kraft paper bag.

At the end of the field day the samples were sorted and stacked separately under cover.

Bureau Veritas Commodities Canada Ltd.
9050 Shaughnessy St Vancouver BC V6P 6E5 CANADA
PHONE (604) 253-3158

Client: **Atled Exploration Management Ltd.**
702-181 Athletes Way
Vancouver BC V5Y 0E5 CANADA

Submitted By: Gutrath Gordon
Receiving Lab: Canada-Whitehorse
Received: August 28, 2014
Report Date: September 19, 2014
Page: 1 of 5

CERTIFICATE OF ANALYSIS

WHI14000150.1

CLIENT JOB INFORMATION

Project: Kelli Project
Shipment ID:
P.O. Number
Number of Samples: 98

SAMPLE DISPOSAL

DISP-PLP Dispose of Pulp After 90 days
DISP-RJT-SOIL Immediate Disposal of Soil Reject

Acme does not accept responsibility for samples left at the laboratory after 90 days without prior written instructions for sample storage or return.

Invoice To: **Atled Exploration Management Ltd.**
702-181 Athletes Way
Vancouver BC V5Y 0E5
CANADA

CC:

SAMPLE PREPARATION AND ANALYTICAL PROCEDURES

Procedure Code	Number of Samples	Code Description	Test Wgt (g)	Report Status	Lab
Dry at 60C	98	Dry at 60C			WHI
SS80	98	Dry at 60C sieve 100g to -80 mesh			WHI
AQ201	94	1:1:1 Aqua Regia digestion ICP-MS analysis	15	Completed	VAN
DISP2	98	Heat treatment of Soils and Sediments			VAN

ADDITIONAL COMMENTS



This report supersedes all previous preliminary and final reports with this file number dated prior to the date on this certificate. Signature indicates final approval; preliminary reports are unsigned and should be used for reference only. All results are considered the confidential property of the client. Acme assumes the liabilities for actual cost of analysis only. Results apply to samples as submitted.
*** asterisk indicates that an analytical result could not be provided due to unusually high levels of interference from other elements.

CERTIFICATE OF ANALYSIS

WHI14000150.1

Method	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201
Analyte	Mo	Cu	Pb	Zn	Ag	Ni	Co	Mn	Fe	As	Au	Th	Sr	Cd	Sb	Bi	V	Ca	P	La
Unit	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppb	ppm	ppm	ppm	ppm	ppm	ppm	%	%	ppm
MDL	0.1	0.1	0.1	1	0.1	0.1	0.1	1	0.01	0.5	0.5	0.1	1	0.1	0.1	0.1	2	0.01	0.001	1
KSO1	Soil	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.
KSO2	Soil	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.
KSO3	Soil	2.5	135.0	34.4	170	0.5	40.9	29.9	773	5.55	32.6	9.5	1.2	39	1.0	0.9	0.3	37	1.00	0.068
KSO4	Soil	1.4	92.2	14.2	141	0.2	36.4	23.6	720	3.39	19.5	27.6	0.6	40	0.6	0.8	0.2	42	1.58	0.074
KSO5	Soil	2.4	226.1	18.6	107	0.4	79.8	42.5	919	5.98	71.7	59.9	0.5	42	0.4	0.6	0.2	53	2.69	0.050
KSO6	Soil	1.5	141.6	13.8	108	0.3	75.8	25.5	682	4.12	15.1	4.7	1.1	36	0.2	0.6	0.1	49	1.39	0.068
KSO7	Soil	0.8	29.7	6.1	79	<0.1	19.0	10.5	351	2.02	9.3	13.8	0.7	27	0.1	0.4	<0.1	33	0.74	0.046
KSO8	Soil	1.6	56.9	5.4	82	<0.1	30.2	12.7	620	2.36	8.2	14.4	0.8	37	0.3	0.6	<0.1	40	1.11	0.051
KSO9	Soil	0.5	19.4	2.4	70	<0.1	10.1	3.8	76	1.58	2.5	1.0	0.4	23	<0.1	0.2	<0.1	39	0.59	0.028
KSO10	Soil	0.7	77.4	6.1	100	0.2	53.3	19.0	632	3.55	10.8	19.0	1.4	34	0.3	0.6	<0.1	59	0.84	0.080
KSO11	Soil	1.0	79.9	6.0	105	0.2	58.4	19.9	693	3.66	11.0	11.3	1.5	61	0.3	0.6	<0.1	62	2.38	0.077
KSO12	Soil	1.4	91.7	6.1	74	0.2	42.1	19.2	729	3.13	10.4	20.1	1.4	61	0.2	0.7	0.1	44	2.22	0.075
KSO13	Soil	1.0	78.5	5.9	85	0.1	42.5	18.6	737	3.53	13.7	21.6	1.0	47	0.2	0.7	<0.1	55	2.16	0.063
KSO14	Soil	1.1	75.4	5.8	78	0.1	46.1	18.7	704	3.38	14.1	16.5	1.1	72	0.2	0.8	<0.1	51	3.23	0.071
KSO15	Soil	1.1	106.6	8.1	85	0.2	46.7	21.0	714	3.82	23.3	27.3	1.1	63	0.3	0.7	0.1	48	2.65	0.063
KSO16	Soil	0.9	79.2	6.6	99	0.1	41.5	17.5	628	3.12	11.4	14.7	0.8	44	0.2	0.6	<0.1	46	1.69	0.062
KSO17	Soil	1.2	77.7	7.1	72	0.2	39.0	17.0	1076	2.85	10.9	11.3	0.9	29	0.3	0.6	0.1	43	0.84	0.058
KSO18	Soil	1.1	74.2	6.8	131	0.2	46.4	19.5	741	3.54	7.1	12.7	1.2	27	0.3	0.5	<0.1	53	1.01	0.072
KSO19	Soil	1.4	112.3	14.7	237	0.4	30.2	23.3	838	4.28	4.4	65.1	1.5	32	1.1	0.3	0.2	65	1.15	0.078
KSO20	Soil	1.1	47.4	12.8	113	0.1	29.3	14.9	724	2.89	6.3	5.1	0.8	34	0.2	0.3	0.1	47	1.20	0.062
KSO21	Soil	1.2	118.8	8.4	77	0.2	33.4	17.3	890	3.03	8.8	78.2	0.8	33	0.5	0.4	0.1	41	1.41	0.056
KSO22	Soil	8.6	140.1	5.1	87	0.2	37.6	22.0	689	4.14	3.3	8.9	0.6	38	<0.1	0.2	<0.1	78	1.14	0.069
KSO23	Soil	1.9	137.4	13.6	95	0.9	52.8	24.3	783	3.89	53.7	44.2	1.6	81	0.5	0.7	0.2	31	1.78	0.082
KSO24	Soil	7.6	134.7	21.2	181	1.2	134.6	33.1	560	4.48	169.1	38.3	0.7	453	0.7	2.5	0.1	29	6.16	0.072
KSO25	Soil	8.5	93.7	13.3	144	0.8	96.3	22.4	509	4.02	77.8	23.5	0.6	508	0.8	2.4	0.2	23	9.03	0.081
KSO26	Soil	5.6	81.8	14.8	123	0.8	87.9	21.1	446	3.40	94.0	14.6	0.5	333	0.6	2.0	0.1	24	6.44	0.073
KSO27	Soil	0.8	52.7	6.0	111	0.1	24.8	14.1	731	2.42	6.8	16.4	0.8	32	0.2	0.4	<0.1	39	1.04	0.058
KSO28	Soil	0.9	101.0	8.2	90	0.1	32.5	18.7	944	3.03	7.7	19.0	1.1	31	0.3	0.4	0.2	47	0.93	0.058
KSO29	Soil	0.8	73.7	6.2	102	0.2	31.7	16.5	740	2.83	6.9	65.7	1.0	37	0.3	0.4	<0.1	41	1.20	0.070
KSO30	Soil	1.3	46.1	10.9	111	<0.1	29.3	15.8	921	3.01	7.7	14.4	0.8	28	0.2	0.4	<0.1	47	0.87	0.068

Bureau Veritas Commodities Canada Ltd.

9050 Shaughnessy St Vancouver BC V6P 6E5 CANADA

PHONE (604) 253-3158

Client: **Atled Exploration Management Ltd.**
702-181 Athletes Way
Vancouver BC V5Y 0E5 CANADA

Project: Kelli Project
Report Date: September 19, 2014

Page: 2 of 5

Part: 2 of 2

CERTIFICATE OF ANALYSIS

WHI14000150.1

Method	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201
Analyte	Cr	Mg	Ba	Ti	B	Al	Na	K	W	Hg	Sc	Tl	S	Ga	Se	Te
Unit	ppm	%	ppm	%	ppm	%	%	%	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm
MDL	1	0.01	1	0.001	1	0.01	0.001	0.01	0.1	0.01	0.1	0.1	0.05	1	0.5	0.2
KSO1	Soil	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.
KSO2	Soil	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.
KSO3	Soil	26	0.67	48	0.018	3	1.13	0.011	0.05	<0.1	0.02	7.7	<0.1	0.12	3	1.9
KSO4	Soil	35	0.78	85	0.034	6	1.31	0.015	0.05	0.1	0.08	5.2	<0.1	0.13	4	0.7
KSO5	Soil	80	1.90	27	0.012	2	1.75	0.005	0.02	<0.1	0.01	11.0	<0.1	<0.05	4	1.0
KSO6	Soil	110	1.52	65	0.019	3	1.81	0.008	0.05	<0.1	0.03	5.7	<0.1	0.05	4	1.2
KSO7	Soil	26	0.47	75	0.046	5	0.84	0.018	0.05	<0.1	0.02	2.6	<0.1	0.07	3	<0.5
KSO8	Soil	31	0.57	106	0.046	3	0.99	0.019	0.04	<0.1	0.02	3.3	<0.1	0.05	3	<0.5
KSO9	Soil	13	0.16	57	0.067	4	0.46	0.021	0.03	<0.1	0.02	1.1	<0.1	0.07	3	<0.5
KSO10	Soil	56	1.21	104	0.066	4	1.55	0.012	0.09	0.1	0.03	7.1	<0.1	<0.05	4	0.6
KSO11	Soil	62	1.46	96	0.080	5	1.65	0.017	0.11	<0.1	0.03	7.0	<0.1	<0.05	5	<0.5
KSO12	Soil	43	1.12	94	0.049	4	1.23	0.016	0.04	<0.1	0.02	5.1	<0.1	<0.05	3	0.9
KSO13	Soil	54	1.27	84	0.053	3	1.63	0.011	0.06	<0.1	0.02	6.3	<0.1	0.05	4	0.6
KSO14	Soil	51	1.32	66	0.065	4	1.36	0.011	0.06	<0.1	0.02	5.9	<0.1	<0.05	4	<0.5
KSO15	Soil	50	1.15	61	0.057	4	1.28	0.010	0.04	<0.1	0.02	6.9	<0.1	0.17	4	0.7
KSO16	Soil	46	1.08	93	0.051	4	1.37	0.011	0.07	<0.1	0.03	5.3	<0.1	0.08	4	0.5
KSO17	Soil	44	0.78	117	0.041	2	1.40	0.016	0.04	0.1	0.03	5.2	<0.1	<0.05	4	0.5
KSO18	Soil	55	1.25	90	0.046	3	1.72	0.010	0.05	<0.1	0.02	6.5	<0.1	<0.05	4	<0.5
KSO19	Soil	39	1.28	63	0.011	2	2.01	0.008	0.05	<0.1	0.05	11.6	<0.1	<0.05	5	<0.5
KSO20	Soil	37	0.86	70	0.050	4	1.34	0.013	0.05	0.2	0.02	4.1	<0.1	0.09	4	<0.5
KSO21	Soil	39	0.81	82	0.033	2	1.41	0.018	0.04	0.1	0.03	4.7	<0.1	0.07	4	<0.5
KSO22	Soil	63	1.78	119	0.074	2	2.65	0.136	0.34	<0.1	<0.01	7.9	0.1	<0.05	6	<0.5
KSO23	Soil	28	0.81	92	0.004	2	0.84	0.004	0.04	<0.1	0.02	6.8	<0.1	0.10	2	1.5
KSO24	Soil	54	0.88	102	0.007	3	0.56	0.006	0.05	0.4	0.04	6.9	<0.1	0.39	2	9.0
KSO25	Soil	37	0.94	93	0.009	2	0.49	0.005	0.04	0.4	0.04	4.8	<0.1	0.33	1	4.1
KSO26	Soil	35	0.66	94	0.007	3	0.49	0.007	0.03	0.3	0.05	5.1	<0.1	0.29	1	4.1
KSO27	Soil	33	0.75	68	0.041	2	1.23	0.022	0.05	<0.1	0.03	4.0	<0.1	<0.05	3	<0.5
KSO28	Soil	39	0.94	88	0.041	2	1.50	0.020	0.05	<0.1	0.03	5.5	<0.1	<0.05	4	<0.5
KSO29	Soil	36	0.89	90	0.042	3	1.44	0.014	0.05	0.1	0.03	4.9	<0.1	0.08	4	<0.5
KSO30	Soil	40	0.95	69	0.040	5	1.39	0.012	0.05	<0.1	0.04	4.7	<0.1	0.07	4	<0.5

CERTIFICATE OF ANALYSIS

WHI14000150.1

	Method	Analyte	Unit	MDL	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201			
					Mo	Cu	Pb	Zn	Ag	Ni	Co	Mn	Fe	As	Au	Th	Sr	Cd	Sb	Bi	V	Ca	P	La
					ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppb	ppm	ppm	ppm	ppm	ppm	ppm	%	%	ppm
					0.1	0.1	0.1	1	0.1	0.1	0.1	1	0.01	0.5	0.5	0.1	1	0.1	0.1	0.1	2	0.01	0.001	1
KSO31	Soil		0.9	50.0	5.9	94	<0.1	28.2	14.5	857	2.72	5.7	21.5	0.8	29	0.3	0.3	<0.1	42	0.95	0.065	7		
KSO32	Soil		1.4	46.7	6.8	106	0.1	29.2	16.6	1306	2.69	9.0	8.6	0.9	33	0.4	0.5	0.1	40	0.96	0.064	8		
KSO33	Soil		1.1	34.7	5.5	98	<0.1	23.6	11.9	707	2.18	6.9	7.9	0.7	32	0.3	0.4	0.1	35	0.89	0.061	7		
KSO34	Soil		1.9	42.8	9.4	114	0.1	28.6	15.3	1146	2.47	10.7	10.6	0.8	37	0.3	0.6	0.1	41	1.05	0.072	8		
KSO35	Soil		0.9	41.6	5.7	112	0.1	32.6	14.6	688	2.51	7.1	12.2	0.8	34	0.3	0.4	<0.1	40	1.02	0.059	7		
KSO36	Soil		1.5	35.8	6.2	78	<0.1	22.8	11.2	308	2.26	8.5	6.0	0.9	21	0.2	0.6	0.1	40	0.49	0.050	8		
KSO37	Soil		1.4	27.8	4.8	55	<0.1	20.6	9.2	328	1.84	6.5	4.7	0.5	31	0.2	0.6	<0.1	33	0.80	0.063	10		
KSO38	Soil		2.0	53.6	8.5	86	0.2	38.6	16.6	1031	3.33	14.7	23.1	1.1	34	0.3	0.8	0.1	48	0.83	0.056	10		
KSO39	Soil		0.4	39.5	2.7	50	<0.1	11.2	3.6	121	0.92	2.8	2.1	0.5	22	<0.1	0.3	<0.1	17	0.55	0.033	5		
KSO40	Soil		0.3	52.3	3.9	61	<0.1	18.7	3.3	73	1.40	4.8	2.2	0.7	49	0.2	0.4	<0.1	18	1.20	0.041	7		
KSO41	Soil		0.7	35.8	3.6	65	<0.1	15.9	2.9	64	1.77	5.0	1.2	0.4	28	0.1	0.4	<0.1	33	0.81	0.064	8		
KSO42	Soil		1.5	50.6	7.8	132	0.3	46.9	21.1	854	3.85	15.4	24.4	1.2	34	0.4	0.5	0.1	57	0.89	0.078	7		
KSO43	Soil		1.2	69.8	7.1	109	0.2	50.6	20.7	1005	3.94	11.5	34.2	1.3	40	0.4	0.5	0.1	57	1.32	0.084	8		
KSO44	Soil		2.1	18.8	6.6	77	0.1	17.0	8.3	344	2.11	8.7	5.5	0.6	34	0.1	0.6	0.1	38	0.87	0.076	8		
KSO45	Soil		4.1	30.6	7.3	102	0.1	24.2	18.2	1218	2.79	12.7	6.7	0.7	41	0.3	0.9	0.1	50	1.18	0.084	12		
KSO46	Soil		1.5	41.1	6.8	86	0.1	24.1	9.9	405	2.22	12.2	12.5	0.7	36	0.2	0.6	<0.1	38	1.42	0.041	7		
KSO47	Soil		2.0	56.1	6.9	134	0.2	40.9	20.6	682	3.71	12.6	16.2	1.3	45	0.3	0.5	0.1	59	1.18	0.086	8		
KSO48	Soil		2.8	20.8	5.7	120	<0.1	27.2	16.9	553	2.44	8.5	4.8	1.0	31	0.1	0.7	0.1	45	0.74	0.067	8		
KSO49	Soil		1.2	23.7	6.1	104	<0.1	25.4	13.2	586	2.62	8.6	4.4	0.8	27	0.2	0.4	<0.1	48	0.65	0.068	8		
KSO50	Soil		1.3	91.8	9.4	78	0.2	41.3	23.2	946	4.07	10.8	47.8	1.3	34	0.3	0.4	0.2	61	1.05	0.070	8		
KSO51	Soil		1.4	78.1	9.3	79	0.2	42.9	21.8	848	4.08	14.5	27.6	1.4	34	0.2	0.5	0.1	56	1.34	0.077	8		
KSO52	Soil		0.9	66.7	7.3	67	0.2	41.6	19.0	796	3.50	10.2	25.5	0.9	36	0.2	0.4	0.1	51	1.34	0.060	7		
KSO53	Soil		1.2	76.9	7.5	67	0.2	41.2	20.7	1090	3.71	11.6	24.0	1.0	41	0.3	0.4	0.1	52	1.71	0.070	8		
KSO54	Soil		1.5	69.2	9.0	67	0.2	36.5	20.4	993	3.51	12.8	11.9	1.0	44	0.3	0.5	<0.1	51	1.73	0.078	8		
KSO55	Soil		1.1	72.1	7.4	76	0.1	37.2	21.1	732	3.89	11.2	22.4	1.7	44	0.2	0.4	0.1	63	1.76	0.083	8		
KSI1	Silt		2.0	83.1	14.1	98	0.4	47.2	24.7	792	3.90	30.1	31.0	1.6	62	0.4	0.6	0.2	40	1.59	0.088	8		
KSI2	Silt		1.9	83.3	11.4	112	0.4	48.8	23.6	665	3.89	28.0	638.1	1.4	53	0.4	0.7	0.1	42	1.59	0.084	7		
KSI3	Silt		2.8	74.0	9.7	96	0.3	60.0	27.8	768	3.85	34.3	27.7	1.0	122	0.4	0.7	<0.1	55	3.99	0.075	5		
KSI4	Silt		3.1	90.7	5.9	68	0.3	27.0	23.0	673	3.77	8.5	66.0	1.0	109	0.2	0.2	0.2	39	2.73	0.083	7		
KSI5	Silt		3.4	69.9	8.2	76	0.3	25.7	21.6	641	3.82	9.7	69.8	1.3	61	0.2	0.1	0.1	36	2.68	0.093	7		

CERTIFICATE OF ANALYSIS

WHI14000150.1

	Method	Analyte	Unit	MDL	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201			
					Cr	Mg	Ba	Tl	B	Al	Na	K	W	Hg	Sc	Tl	S	Ga	Se	Te
					ppm	%	ppm	%	ppm	%	%	%	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm
					1	0.01	1	0.001	1	0.01	0.001	0.01	0.1	0.01	0.1	0.1	0.05	1	0.5	0.2
KSO31	Soil	35	0.85	77	0.036	2	1.25	0.009	0.03	<0.1	0.02	4.1	<0.1	0.07	4	<0.5	<0.2			
KSO32	Soll	35	0.74	114	0.031	2	1.27	0.017	0.04	0.1	0.03	4.0	<0.1	0.08	4	<0.5	<0.2			
KSO33	Soll	29	0.63	103	0.035	3	1.10	0.020	0.04	0.1	0.03	2.9	<0.1	0.07	3	<0.5	<0.2			
KSO34	Soll	32	0.67	119	0.032	3	1.20	0.019	0.04	0.1	0.05	3.3	<0.1	0.09	3	<0.5	<0.2			
KSO35	Soil	38	0.81	100	0.041	3	1.28	0.019	0.04	0.1	0.03	3.8	<0.1	0.06	4	<0.5	<0.2			
KSO36	Soll	30	0.51	90	0.042	2	1.01	0.020	0.05	0.1	0.02	3.3	<0.1	0.05	4	<0.5	<0.2			
KSO37	Soil	21	0.37	122	0.031	2	0.92	0.022	0.03	0.1	0.03	2.0	<0.1	0.08	3	<0.5	<0.2			
KSO38	Soil	40	0.70	143	0.032	3	1.44	0.017	0.04	<0.1	0.03	5.4	<0.1	0.05	4	<0.5	<0.2			
KSO39	Soil	13	0.21	65	0.024	2	0.46	0.029	0.03	<0.1	0.02	1.3	<0.1	0.06	2	<0.5	<0.2			
KSO40	Soil	20	0.29	133	0.033	5	0.74	0.019	0.03	0.1	0.03	2.2	<0.1	0.14	3	0.7	<0.2			
KSO41	Soil	17	0.21	98	0.037	4	0.78	0.018	0.03	0.1	0.03	1.5	<0.1	0.14	3	0.5	<0.2			
KSO42	Soil	55	1.16	106	0.038	3	1.60	0.016	0.06	<0.1	0.11	6.6	<0.1	0.05	4	1.3	<0.2			
KSO43	Soll	54	1.33	97	0.051	4	1.72	0.012	0.07	<0.1	0.02	6.8	<0.1	0.05	4	<0.5	<0.2			
KSO44	Soil	28	0.45	80	0.036	4	0.90	0.016	0.05	<0.1	0.04	2.4	<0.1	0.15	4	0.6	<0.2			
KSO45	Soll	31	0.42	204	0.031	5	1.17	0.016	0.03	0.2	0.06	3.0	0.2	0.14	4	0.5	<0.2			
KSO46	Soil	28	0.46	98	0.031	4	0.96	0.013	0.04	0.1	0.03	3.0	<0.1	0.10	3	<0.5	<0.2			
KSO47	Soil	54	1.20	105	0.044	3	1.71	0.020	0.07	<0.1	0.03	6.4	<0.1	0.08	5	1.0	<0.2			
KSO48	Soll	36	0.69	88	0.040	2	1.15	0.021	0.04	0.1	0.05	3.3	<0.1	0.08	4	<0.5	<0.2			
KSO49	Soil	33	0.67	95	0.040	3	1.13	0.019	0.04	0.1	0.03	3.1	<0.1	0.07	4	<0.5	<0.2			
KSO50	Soll	52	1.29	84	0.047	2	1.85	0.022	0.05	<0.1	0.02	7.0	<0.1	<0.05	5	<0.5	<0.2			
KSO51	Soil	58	1.17	89	0.047	3	1.68	0.019	0.08	<0.1	0.01	6.2	<0.1	<0.05	5	0.5	<0.2			
KSO52	Soil	52	1.13	84	0.036	3	1.58	0.011	0.04	<0.1	0.02	6.8	<0.1	0.06	4	0.6	<0.2			
KSO53	Soll	49	1.16	80	0.038	3	1.67	0.013	0.05	<0.1	0.02	6.4	<0.1	<0.05	4	<0.5	<0.2			
KSO54	Soll	42	1.04	70	0.043	4	1.49	0.015	0.06	<0.1	0.02	6.5	<0.1	0.12	4	0.8	<0.2			
KSO55	Soil	50	1.23	72	0.060	2	1.72	0.023	0.08	<0.1	0.02	6.7	<0.1	<0.05	5	<0.5	<0.2			
KSI1	Silt	38	1.02	71	0.019	3	1.17	0.010	0.04	<0.1	0.02	5.4	<0.1	0.13	3	1.6	0.2			
KSI2	Silt	41	0.97	64	0.020	3	1.11	0.009	0.04	<0.1	0.02	5.8	<0.1	0.16	3	1.9	0.2			
KSI3	Silt	55	1.38	86	0.033	3	1.34	0.008	0.07	<0.1	0.02	7.1	<0.1	0.18	4	1.1	<0.2			
KSI4	Silt	38	1.15	43	0.006	2	1.51	0.006	0.04	<0.1	0.01	5.0	<0.1	0.17	4	0.5	<0.2			
KSI5	Silt	33	1.14	43	0.003	3	1.55	0.005	0.04	<0.1	<0.01	4.4	<0.1	0.18	4	<0.5	0.2			

CERTIFICATE OF ANALYSIS

WHI14000150,1

		Method	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	
		Analyte	Mo	Cu	Pb	Zn	Ag	Ni	Co	Mn	Fe	As	Au	Th	Sr	Cd	Sb	Bi	V	Ca	P	La
		Unit	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppb	ppm	ppm	ppm	ppm	ppm	ppm	%	%	ppm
		MDL	0.1	0.1	0.1	1	0.1	0.1	0.1	1	0.01	0.5	0.5	0.1	1	0.1	0.1	0.1	2	0.01	0.001	1
KSI6	Silt		2.2	152.5	4.8	56	0.3	24.7	16.4	811	2.71	4.7	68.8	0.7	61	0.3	0.3	0.2	41	1.23	0.061	6
KSI7	Silt		1.8	119.8	5.4	55	0.3	22.1	15.1	509	2.71	3.7	46.4	0.6	41	0.2	0.3	0.2	46	1.02	0.057	5
KSI8	Silt		1.1	40.0	2.9	61	<0.1	23.9	14.1	552	2.94	5.5	6.9	0.8	24	0.1	0.2	<0.1	50	0.64	0.047	5
KSI9	Silt		1.2	38.2	4.7	66	<0.1	22.8	14.9	469	3.04	4.5	5.1	0.6	29	0.1	0.1	<0.1	58	0.66	0.051	4
KSI10	Silt		2.5	74.5	14.9	104	0.2	34.0	23.2	885	4.28	13.5	43.3	0.8	65	0.3	0.4	<0.1	51	2.10	0.077	6
KSI11	Silt		1.0	29.3	8.8	70	<0.1	28.4	14.8	523	3.28	5.8	63.4	0.9	26	0.1	0.2	<0.1	58	0.60	0.061	6
KSI12	Silt		0.8	23.9	3.9	59	<0.1	24.2	13.3	512	2.74	5.0	18.3	0.7	19	0.1	0.2	<0.1	43	0.48	0.052	5
KSI13	Silt		1.2	61.1	7.2	72	0.2	32.1	18.2	795	3.26	9.1	253.6	1.0	29	0.2	0.3	0.1	51	0.93	0.074	7
KSI14	Silt		0.8	18.1	4.3	90	<0.1	25.8	12.7	467	2.57	4.8	27.4	0.9	21	0.1	0.3	<0.1	48	0.54	0.058	6
KSI15	Silt		1.8	62.0	5.4	94	0.1	32.6	19.2	656	3.79	6.7	24.1	1.0	41	0.1	0.3	<0.1	65	1.72	0.084	6
KSI16	Silt		1.9	78.3	14.9	115	0.2	29.0	21.5	792	3.94	8.4	17.3	1.2	50	0.4	0.3	<0.1	47	1.10	0.092	10
KSI17	Silt		3.2	92.7	16.5	106	0.3	38.3	24.8	960	5.01	12.5	6.8	1.4	53	0.3	0.5	0.1	49	1.08	0.078	8
KSI18	Silt		0.9	60.8	7.1	98	0.1	32.4	19.6	777	3.55	9.3	43.4	1.4	77	0.2	0.6	<0.1	61	1.36	0.085	9
KSI19	Silt		2.2	74.0	9.8	97	0.2	31.6	22.5	857	4.22	14.7	53.3	1.1	50	0.3	0.6	<0.1	76	1.05	0.081	8
KSI20	Silt		1.3	44.3	9.1	89	<0.1	26.9	17.1	820	3.85	11.4	81.0	1.1	34	0.2	0.3	<0.1	85	0.66	0.096	8
KSI21	Silt		2.4	105.3	10.6	107	0.3	44.6	28.5	972	4.35	19.0	135.4	1.3	62	0.4	0.5	0.1	65	1.03	0.087	9
KSI22	Silt		2.5	105.1	8.4	101	0.2	44.7	41.2	>10000	3.88	12.8	58.4	1.2	99	0.8	0.6	0.1	50	1.98	0.090	9
KSI23	Silt		0.9	49.2	6.9	116	<0.1	35.4	20.0	802	5.22	10.4	46.0	0.9	36	0.1	0.5	<0.1	145	0.94	0.100	7
KSI24	Silt		0.9	30.5	7.5	70	<0.1	28.6	14.1	464	3.28	7.2	8.8	1.0	28	0.1	0.3	<0.1	81	0.64	0.070	6
KSI25	Silt		1.1	31.5	4.9	78	<0.1	33.5	16.8	482	4.09	8.0	13.0	1.0	31	0.1	0.4	<0.1	112	0.81	0.077	7
KSI26	Silt		1.3	24.2	5.0	80	<0.1	31.6	15.4	520	3.88	8.3	5.3	1.0	26	<0.1	0.4	<0.1	94	0.58	0.066	6
KSI27	Silt		1.0	35.8	7.9	86	<0.1	32.8	17.3	589	4.13	8.3	55.7	1.2	33	0.2	0.5	<0.1	114	0.77	0.076	8
KSI28	Silt		1.1	74.8	6.5	81	0.1	50.0	24.6	744	4.14	16.5	44.0	0.9	47	0.3	1.0	<0.1	94	1.67	0.080	6
KSI30	Silt		1.3	130.7	11.6	131	0.2	102.1	33.2	865	5.62	16.0	3.7	1.0	24	0.2	0.6	0.1	101	0.52	0.070	7
KSI31	Silt		2.4	102.8	17.1	217	0.3	97.5	31.5	694	5.48	34.0	17.5	2.7	80	0.4	0.9	0.3	51	2.35	0.078	8
KSI32	Silt		2.1	98.7	15.6	177	0.3	92.1	30.9	675	5.18	32.4	7.3	2.2	76	0.3	0.9	0.2	49	2.31	0.076	6
KSI33	Silt		2.8	105.5	16.7	166	0.3	80.8	33.3	690	5.68	37.1	10.7	1.9	85	0.4	1.1	0.3	47	2.99	0.088	5
KSI34	Silt		2.2	101.8	17.9	180	0.3	81.7	31.6	717	5.69	33.4	22.8	2.1	89	0.3	1.0	0.2	52	2.80	0.083	7
KSI35	Silt		I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.
KSI36	Silt		I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.

CERTIFICATE OF ANALYSIS

WHI14000150.1

	Method	Analyte	Unit	MDL	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201			
					Cr	Mg	Ba	Ti	B	Al	Na	K	W	Hg	Sc	Ti	S	Ga	Se	Te
					%	%		%	ppm	%	%	%	ppm	ppm	ppm	%	ppm	ppm	ppm	
					1	0.01	1	0.001	1	0.01	0.001	0.01	0.1	0.01	0.1	0.1	0.05	1	0.5	0.2
KSI6	Silt	30	0.78	57	0.025	4	1.04	0.016	0.04	<0.1	0.03	5.2	<0.1	0.11	3	0.8	0.2			
KSI7	Silt	28	0.82	49	0.030	3	1.00	0.015	0.03	<0.1	0.02	4.8	<0.1	0.11	3	<0.5	0.4			
KSI8	Silt	34	0.99	55	0.044	2	1.37	0.021	0.08	<0.1	<0.01	3.9	<0.1	<0.05	4	<0.5	<0.2			
KSI9	Silt	32	1.02	50	0.054	4	1.42	0.033	0.08	<0.1	<0.01	4.1	<0.1	<0.05	4	<0.5	<0.2			
KSI10	Silt	43	1.35	42	0.038	4	1.54	0.007	0.08	<0.1	0.01	5.2	<0.1	0.19	4	0.6	<0.2			
KSI11	Silt	37	1.06	39	0.057	3	1.40	0.010	0.04	<0.1	<0.01	4.0	<0.1	<0.05	4	<0.5	<0.2			
KSI12	Silt	30	0.96	40	0.032	3	1.29	0.010	0.03	<0.1	0.01	3.3	<0.1	<0.05	4	<0.5	<0.2			
KSI13	Silt	42	1.08	73	0.039	3	1.59	0.019	0.06	<0.1	0.02	5.1	<0.1	<0.05	4	<0.5	<0.2			
KSI14	Silt	36	0.86	72	0.046	2	1.24	0.017	0.04	0.1	0.02	3.3	<0.1	<0.05	4	<0.5	<0.2			
KSI15	Silt	43	1.22	53	0.053	3	1.35	0.009	0.04	<0.1	0.02	5.3	<0.1	0.08	4	<0.5	<0.2			
KSI16	Silt	41	1.12	41	0.009	2	1.55	0.007	0.04	<0.1	0.03	7.3	<0.1	0.08	4	0.8	<0.2			
KSI17	Silt	43	1.08	65	0.004	2	1.46	0.010	0.04	<0.1	0.02	8.1	<0.1	0.14	4	0.7	<0.2			
KSI18	Silt	36	1.15	58	0.041	3	1.42	0.013	0.05	0.1	0.01	6.4	<0.1	0.07	4	<0.5	<0.2			
KSI19	Silt	39	0.94	66	0.060	1	1.18	0.011	0.06	0.1	0.01	6.1	<0.1	0.12	4	<0.5	<0.2			
KSI20	Silt	35	0.84	52	0.077	<1	1.07	0.012	0.04	<0.1	0.01	3.9	<0.1	0.06	4	<0.5	<0.2			
KSI21	Silt	63	1.44	70	0.026	<1	1.62	0.010	0.08	<0.1	0.01	9.0	<0.1	0.07	4	<0.5	<0.2			
KSI22	Silt	43	1.07	574	0.026	2	1.29	0.016	0.06	<0.1	0.02	7.0	<0.1	0.08	4	<0.5	<0.2			
KSI23	Silt	47	0.96	67	0.154	4	1.06	0.014	0.04	<0.1	0.02	4.4	<0.1	0.12	6	<0.5	<0.2			
KSI24	Silt	37	0.86	53	0.091	3	1.13	0.014	0.04	0.1	0.01	3.9	<0.1	<0.05	4	<0.5	<0.2			
KSI25	Silt	45	0.98	62	0.131	3	1.19	0.014	0.04	<0.1	<0.01	4.2	<0.1	0.07	5	<0.5	<0.2			
KSI26	Silt	43	1.05	60	0.123	4	1.31	0.015	0.04	0.1	<0.01	4.1	<0.1	0.08	5	<0.5	<0.2			
KSI27	Silt	46	0.99	78	0.138	5	1.37	0.018	0.05	0.1	0.03	4.9	<0.1	0.11	6	<0.5	<0.2			
KSI28	Silt	73	1.72	43	0.158	4	1.95	0.008	0.05	<0.1	0.01	7.1	<0.1	0.17	6	<0.5	<0.2			
KSI30	Silt	174	2.55	34	0.029	<1	2.69	0.007	0.04	<0.1	0.01	13.0	<0.1	0.07	7	<0.5	<0.2			
KSI31	Silt	101	1.76	24	0.010	2	2.05	0.005	0.05	<0.1	0.01	6.2	<0.1	0.44	5	1.0	0.2			
KSI32	Silt	100	1.56	20	0.008	<1	1.85	0.004	0.04	<0.1	<0.01	6.1	<0.1	0.37	4	0.7	<0.2			
KSI33	Silt	85	1.49	20	0.008	1	1.73	0.005	0.03	<0.1	0.01	6.2	<0.1	0.57	4	0.5	<0.2			
KSI34	Silt	90	1.59	24	0.012	2	1.80	0.005	0.04	<0.1	<0.01	6.6	<0.1	0.55	5	<0.5	<0.2			
KSI35	Silt	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.			
KSI36	Silt	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.	I.S.			

CERTIFICATE OF ANALYSIS

WHI14000150.1

	Method Analyte Unit MDL	AQ201																			
		Mo	Cu	Pb	Zn	Ag	Ni	Co	Mn	Fe	As	Au	Th	Sr	Cd	Sb	Bi	V	Ca	P	La
		ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppb	ppm	ppm	ppm	ppm	ppm	ppm	%	%	ppm
		0.1	0.1	0.1	1	0.1	0.1	0.1	1	0.01	0.5	0.5	0.1	1	0.1	0.1	0.1	2	0.01	0.001	1
KSI37	Silt	1.1	73.8	7.3	102	0.1	36.0	16.1	574	2.91	10.0	18.6	1.5	45	0.3	0.6	0.1	61	1.15	0.076	10
KSI38	Silt	2.0	61.3	19.8	105	0.1	46.5	17.9	782	3.88	16.8	124.7	1.4	59	0.3	0.8	<0.1	77	1.30	0.078	9
KSI39	Silt	1.7	87.2	12.1	92	0.2	40.7	22.3	800	3.93	23.3	96.2	1.2	53	0.4	0.7	0.1	56	1.60	0.079	7
KSI40	Silt	1.7	87.2	15.1	98	0.3	43.3	25.4	802	4.40	29.4	319.0	1.1	62	0.4	0.7	0.1	61	1.94	0.080	6
KSI41	Silt	2.0	92.7	15.7	98	0.2	42.7	23.7	890	4.12	26.6	50.0	1.1	60	0.5	0.8	0.1	56	1.74	0.076	7
KSI42	Silt	2.1	86.9	23.2	102	0.2	46.8	24.8	916	4.58	30.8	38.5	1.3	61	0.4	0.7	0.1	65	1.88	0.077	8
ASI1	Soil	1.3	70.0	6.8	91	<0.1	47.1	22.9	773	4.26	16.6	15.8	0.9	48	0.2	0.7	<0.1	82	1.66	0.077	6
ASI2	Soil	1.5	103.0	6.9	94	0.2	68.2	28.0	795	4.56	35.6	21.9	0.8	44	0.3	1.4	<0.1	89	1.89	0.076	5

Bureau Veritas Commodities Canada Ltd.

9050 Shaughnessy St Vancouver BC V6P 6E5 CANADA

PHONE (604) 253-3158

Client: Atled Exploration Management Ltd.
702-181 Athletes Way
Vancouver BC V5Y 0E5 CANADA

Project: Kelli Project
Report Date: September 19, 2014

Page: 5 of 5

Part: 2 of 2

CERTIFICATE OF ANALYSIS

WHI14000150.1

	Method	Analyte	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	
			Cr	Mg	Ba	Tl	B	Al	Na	K	W	Hg	Sc	Tl	S	Ga	Se	Te
			Unit															
			MDL	1	0.01	1	0.001	1	0.01	0.001	0.01	0.1	0.01	0.1	0.1	0.05	1	0.5
KSI37	Silt	44	0.89	97	0.088	4	1.32	0.019	0.06	<0.1	0.04	5.3	<0.1	0.08	4	<0.5	<0.2	
KSI38	Silt	52	1.08	138	0.091	6	1.24	0.019	0.06	0.2	0.02	6.3	<0.1	0.12	4	<0.5	<0.2	
KSI39	Silt	46	1.15	52	0.036	<1	1.42	0.013	0.05	<0.1	0.01	6.6	<0.1	0.19	4	<0.5	<0.2	
KSI40	Silt	49	1.30	51	0.032	2	1.55	0.012	0.05	<0.1	0.02	8.0	<0.1	0.24	4	<0.5	<0.2	
KSI41	Silt	51	1.17	56	0.027	2	1.42	0.012	0.05	<0.1	0.01	7.3	<0.1	0.20	4	<0.5	<0.2	
KSI42	Silt	54	1.31	68	0.042	4	1.61	0.013	0.06	<0.1	0.01	7.8	<0.1	0.32	4	<0.5	<0.2	
ASI1	Soil	73	1.73	43	0.113	5	1.97	0.008	0.05	<0.1	0.02	6.5	<0.1	0.12	5	<0.5	<0.2	
ASI2	Soil	91	1.97	47	0.120	2	2.19	0.007	0.04	<0.1	0.03	7.4	<0.1	0.09	6	<0.5	<0.2	

Bureau Veritas Commodities Canada Ltd.

9050 Shaughnessy St Vancouver BC V6P 6E5 CANADA

PHONE (604) 253-3158

QUALITY CONTROL REPORT

WHI14000150.1

		Method	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	
		Analyte	Mo	Cu	Pb	Zn	Ag	Ni	Co	Mn	Fe	As	Au	Th	Sr	Cd	Sb	Bi	V	Ca	P	La
		Unit	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppb	ppm	ppm	ppm	ppm	ppm	ppm	%	%	ppm
		MDL	0.1	0.1	0.1	1	0.1	0.1	0.1	1	0.01	0.5	0.5	0.1	1	0.1	0.1	0.1	2	0.01	0.001	1
Pulp Duplicates																						
KSO29	Soil		0.8	73.7	6.2	102	0.2	31.7	16.5	740	2.83	6.9	65.7	1.0	37	0.3	0.4	<0.1	41	1.20	0.070	8
REP KSO29	QC		0.8	72.0	6.2	107	0.1	31.8	16.6	750	2.78	6.8	15.5	1.0	38	0.3	0.4	0.1	43	1.22	0.068	8
KSI12	Silt		0.8	23.9	3.9	59	<0.1	24.2	13.3	512	2.74	5.0	18.3	0.7	19	0.1	0.2	<0.1	43	0.48	0.052	5
REP KSI12	QC		0.8	23.3	4.0	61	<0.1	24.9	13.7	507	2.75	5.0	43.9	0.8	20	0.1	0.2	<0.1	44	0.48	0.053	5
KSI19	Silt		2.2	74.0	9.8	97	0.2	31.6	22.5	857	4.22	14.7	53.3	1.1	50	0.3	0.6	<0.1	76	1.05	0.081	8
REP KSI19	QC		2.2	80.4	10.2	100	0.2	32.8	22.6	886	4.16	15.4	131.0	1.1	53	0.3	0.6	0.1	71	1.06	0.080	9
Reference Materials																						
STD DS10	Standard		13.6	154.8	152.0	360	1.7	73.1	12.6	792	2.54	44.7	63.8	7.4	66	2.5	10.4	12.8	40	0.97	0.070	17
STD DS10	Standard		13.6	132.6	148.6	343	1.8	72.2	11.3	837	2.60	38.7	85.9	6.5	61	2.3	8.5	11.3	36	1.00	0.062	15
STD DS10	Standard		13.0	168.2	148.3	345	1.9	72.5	11.1	826	2.55	37.6	92.1	6.4	55	2.3	8.5	11.2	35	0.97	0.060	15
STD OXC109	Standard		1.6	38.5	11.5	41	<0.1	71.2	18.9	398	2.93	0.6	169.8	1.6	136	<0.1	<0.1	<0.1	48	0.67	0.106	13
STD OXC109	Standard		1.4	31.4	10.3	41	<0.1	69.2	17.2	388	2.77	<0.5	202.1	1.3	128	<0.1	<0.1	<0.1	40	0.60	0.089	11
STD OXC109	Standard		1.4	36.8	9.9	39	<0.1	68.0	16.6	376	2.73	<0.5	194.3	1.3	120	<0.1	<0.1	<0.1	39	0.57	0.087	11
STD DS10 Expected			14.69	154.61	150.55	370	2.02	74.6	12.9	875	2.7188	43.7	91.9	7.5	67.1	2.49	8.23	11.65	43	1.0625	0.073	17.5
STD OXC109 Expected			201																			
BLK	Blank		<0.1	<0.1	<0.1	<1	<0.1	<0.1	<0.1	<1	<0.01	<0.5	<0.5	<0.1	<1	<0.1	<0.1	<0.1	<2	<0.01	<0.001	<1
BLK	Blank		<0.1	<0.1	<0.1	<1	<0.1	<0.1	<0.1	<1	<0.01	<0.5	<0.5	<0.1	<1	<0.1	<0.1	<0.1	<2	<0.01	<0.001	<1
BLK	Blank		<0.1	<0.1	<0.1	<1	<0.1	<0.1	<0.1	<1	<0.01	<0.5	<0.5	<0.1	<1	<0.1	<0.1	<0.1	<2	<0.01	<0.001	<1

QUALITY CONTROL REPORT

WHI14000150.1

	Method	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201
	Analyte	Cr	Mg	Ba	Tl	B	Al	Na	K	W	Hg	Sc	Tl	S	Ga	Se	Te
	Unit	ppm	%	ppm	%	ppm	%	%	%	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm
	MDL	1	0.01	1	0.001	1	0.01	0.001	0.01	0.1	0.01	0.1	0.1	0.05	1	0.5	0.2
Pulp Duplicates																	
KSO29	Soil	36	0.89	90	0.042	3	1.44	0.014	0.05	0.1	0.03	4.9	<0.1	0.08	4	<0.5	<0.2
REP KSO29	QC	37	0.89	90	0.042	3	1.41	0.014	0.05	0.1	0.03	5.0	<0.1	0.10	4	<0.5	<0.2
KSI12	Silt	30	0.96	40	0.032	3	1.29	0.010	0.03	<0.1	0.01	3.3	<0.1	<0.05	4	<0.5	<0.2
REP KSI12	QC	32	0.95	40	0.036	2	1.29	0.010	0.03	<0.1	<0.01	3.4	<0.1	<0.05	4	<0.5	<0.2
KSI19	Silt	39	0.94	66	0.060	1	1.18	0.011	0.06	0.1	0.01	6.1	<0.1	0.12	4	<0.5	<0.2
REP KSI19	QC	38	0.92	68	0.056	2	1.17	0.011	0.06	0.1	0.02	6.4	<0.1	0.11	4	<0.5	<0.2
Reference Materials																	
STD DS10	Standard	51	0.75	323	0.075	6	0.97	0.062	0.30	3.1	0.26	2.8	5.1	0.29	4	1.2	4.8
STD DS10	Standard	53	0.74	339	0.060	6	0.98	0.062	0.32	3.2	0.29	2.5	5.0	0.30	4	2.1	5.0
STD DS10	Standard	51	0.71	326	0.075	7	0.92	0.061	0.32	3.2	0.28	2.4	5.0	0.28	4	2.1	4.8
STD OXC109	Standard	57	1.40	57	0.364	<1	1.47	0.628	0.39	0.2	<0.01	0.8	<0.1	<0.05	6	<0.5	<0.2
STD OXC109	Standard	55	1.37	56	0.346	2	1.37	0.633	0.39	0.2	<0.01	0.8	<0.1	<0.05	5	<0.5	<0.2
STD OXC109	Standard	53	1.34	52	0.371	2	1.33	0.638	0.37	0.2	<0.01	0.7	<0.1	<0.05	5	<0.5	<0.2
STD DS10 Expected		54.6	0.775	359	0.0817		1.0259	0.067	0.338	3.32	0.3	2.8	5.1	0.29	4.3	2.3	5.01
STD OXC109 Expected																	
BLK	Blank	<1	<0.01	<1	<0.001	<1	<0.01	<0.001	<0.01	<0.1	<0.01	<0.1	<0.1	<0.05	<1	<0.5	<0.2
BLK	Blank	<1	<0.01	<1	<0.001	<1	<0.01	<0.001	<0.01	<0.1	<0.01	<0.1	<0.1	<0.05	<1	<0.5	<0.2
BLK	Blank	<1	<0.01	<1	<0.001	<1	<0.01	<0.001	<0.01	<0.1	<0.01	<0.1	<0.1	<0.05	<1	<0.5	<0.2

Bureau Veritas Commodities Canada Ltd.
9050 Shaughnessy St Vancouver BC V6P 6E5 CANADA
PHONE (604) 253-3158

Client: **Atled Exploration Management Ltd.**
702-181 Athletes Way
Vancouver BC V5Y 0E5 CANADA

Submitted By: Gutrath Gordon
Receiving Lab: Canada-Whitehorse
Received: August 28, 2014
Report Date: September 16, 2014
Page: 1 of 2

CERTIFICATE OF ANALYSIS

WHI14000149.1

CLIENT JOB INFORMATION

Project: Kelli Project
Shipment ID:
P.O. Number
Number of Samples: 15

SAMPLE PREPARATION AND ANALYTICAL PROCEDURES

Procedure Code	Number of Samples	Code Description	Test Wgt (g)	Report Status	Lab
PRP70-250	15	Crush, split and pulverize 250 g rock to 200 mesh			WHI
AQ201	15	1:1:1 Aqua Regia digestion ICP-MS analysis	15	Completed	VAN

SAMPLE DISPOSAL

DISP-PLP Dispose of Pulp After 90 days
DISP-RJT Dispose of Reject After 90 days

ADDITIONAL COMMENTS

Acme does not accept responsibility for samples left at the laboratory after 90 days without prior written instructions for sample storage or return.

Invoice To: **Atled Exploration Management Ltd.**
702-181 Athletes Way
Vancouver BC V5Y 0E5
CANADA

CC:



This report supersedes all previous preliminary and final reports with this file number dated prior to the date on this certificate. Signature indicates final approval; preliminary reports are unsigned and should be used for reference only. All results are considered the confidential property of the client. Acme assumes the liabilities for actual cost of analysis only. Results apply to samples as submitted. *** asterisk indicates that an analytical result could not be provided due to unusually high levels of interference from other elements.

CERTIFICATE OF ANALYSIS

WHI14000149.1

		Method	WGHT	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	
		Analyte	Wgt	Mo	Cu	Pb	Zn	Ag	Ni	Co	Mn	Fe	As	Au	Th	Sr	Cd	Sb	BI	V	Ca	P
		Unit	kg	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppb	ppm	ppm	ppm	ppm	ppm	ppm	%	%
		MDL	0.01	0.1	0.1	0.1	1	0.1	0.1	0.1	1	0.01	0.5	0.5	0.1	1	0.1	0.1	0.1	2	0.01	0.001
H1	Rock		3.18	1.6	32.4	5.4	49	0.4	34.4	7.7	723	1.48	60.8	3.4	0.2	1729	0.5	0.5	<0.1	8	19.33	0.031
H2	Rock		3.23	2.0	32.9	7.7	57	0.3	29.1	8.0	616	1.77	37.0	0.5	0.4	1358	0.3	0.3	<0.1	10	16.32	0.057
H3	Rock		2.71	1.0	99.0	3.5	74	0.2	67.0	26.7	867	4.70	46.9	11.7	0.5	324	0.2	0.4	<0.1	101	5.52	0.051
H4	Rock		3.16	2.8	55.0	17.7	101	0.7	74.5	18.3	843	4.01	160.6	56.5	0.6	322	0.6	0.5	<0.1	32	5.85	0.087
H5	Rock		3.35	1.8	30.1	6.0	49	0.2	29.2	8.4	574	1.72	34.5	1.2	0.4	1305	0.4	0.6	<0.1	12	18.16	0.063
H6	Rock		4.01	2.4	20.4	4.2	54	0.1	24.8	8.5	567	1.86	21.4	2.5	0.3	1510	0.1	0.3	<0.1	38	19.88	0.044
H7	Rock		3.03	1.2	10.7	4.9	26	<0.1	14.8	4.5	373	1.28	16.7	2.7	0.3	1633	0.3	0.4	<0.1	18	23.13	0.044
H8	Rock		2.49	0.3	174.6	1.6	78	0.2	24.2	41.3	1292	6.65	7.4	5.0	0.2	101	<0.1	0.2	<0.1	175	2.76	0.106
H9	Rock		2.69	2.8	22.0	2.4	62	<0.1	7.7	12.3	912	3.67	0.9	3.3	1.9	104	<0.1	<0.1	<0.1	49	4.18	0.101
H10	Rock		1.87	1.9	41.5	6.9	86	0.2	21.6	17.5	882	4.05	37.6	8.2	1.9	317	0.3	0.1	<0.1	59	6.26	0.119
H11	Rock		3.36	0.4	98.0	0.8	62	0.2	61.9	32.5	1225	5.91	<0.5	6.7	0.2	168	<0.1	<0.1	<0.1	161	5.64	0.047
H12	Rock		2.60	1.9	24.4	6.0	35	0.2	21.2	5.3	574	1.24	9.2	0.6	0.3	1450	0.2	0.2	<0.1	20	22.87	0.034
H13	Rock		3.04	3.7	7.2	5.7	34	<0.1	12.2	2.4	437	1.04	21.4	0.7	0.2	1539	0.2	0.1	<0.1	13	22.61	0.037
H14	Rock		2.78	1.9	43.0	4.4	45	0.6	21.3	5.2	467	0.99	33.3	2.4	0.2	2236	0.4	0.5	<0.1	12	23.73	0.036
H15	Rock		1.74	0.1	141.0	1.7	57	0.4	44.3	33.8	1250	5.85	<0.5	9.2	0.2	270	<0.1	<0.1	<0.1	226	6.69	0.054

CERTIFICATE OF ANALYSIS

WHI14000149.1

		Method	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	
		Analyte	La	Cr	Mg	Ba	Ti	B	Al	Na	K	W	Hg	Sc	Tl	S	Ga	Se	Te
		Unit	ppm	ppm	%	ppm	%	ppm	%	%	%	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm
		MDL	1	1	0.01	1	0.001	1	0.01	0.001	0.01	0.1	0.01	0.1	0.1	0.05	1	0.5	0.2
H1	Rock		5	13	1.35	75	<0.001	1	0.10	0.005	0.05	0.3	<0.01	4.1	<0.1	0.32	<1	3.0	<0.2
H2	Rock		5	9	0.96	115	<0.001	1	0.18	0.013	0.08	0.2	<0.01	3.9	<0.1	0.43	<1	3.2	<0.2
H3	Rock		2	50	2.59	375	0.002	2	0.39	0.018	0.06	<0.1	0.02	18.4	<0.1	0.20	1	<0.5	<0.2
H4	Rock		2	44	2.80	79	<0.001	2	0.28	0.017	0.13	<0.1	<0.01	7.8	<0.1	0.25	<1	1.8	<0.2
H5	Rock		6	9	1.43	73	<0.001	<1	0.14	0.008	0.06	<0.1	<0.01	4.4	<0.1	0.48	<1	2.5	<0.2
H6	Rock		5	25	1.63	190	0.001	2	0.22	0.007	0.04	<0.1	0.03	6.6	<0.1	0.22	<1	0.7	<0.2
H7	Rock		6	13	1.26	106	<0.001	<1	0.10	0.006	0.03	<0.1	<0.01	3.3	<0.1	0.24	<1	1.2	0.2
H8	Rock		2	8	2.45	30	0.186	1	3.08	0.015	0.02	0.2	<0.01	13.6	<0.1	0.73	6	<0.5	<0.2
H9	Rock		9	7	1.31	90	0.010	2	2.12	0.051	0.12	<0.1	<0.01	3.9	<0.1	<0.05	5	<0.5	<0.2
H10	Rock		7	18	1.58	69	0.003	<1	1.30	0.020	0.14	<0.1	<0.01	6.2	<0.1	0.14	3	0.9	<0.2
H11	Rock		3	106	3.25	150	0.006	2	1.93	0.027	0.05	<0.1	<0.01	21.8	<0.1	0.28	6	0.7	<0.2
H12	Rock		6	21	1.15	91	<0.001	2	0.30	0.004	0.03	0.1	<0.01	3.7	<0.1	0.35	<1	2.0	0.2
H13	Rock		4	13	0.85	184	<0.001	2	0.14	0.007	0.02	<0.1	<0.01	3.5	<0.1	0.08	<1	0.8	<0.2
H14	Rock		7	13	0.95	45	<0.001	<1	0.11	0.006	0.05	0.2	<0.01	3.6	<0.1	0.36	<1	2.5	<0.2
H15	Rock		2	106	2.97	82	0.007	1	2.86	0.022	0.01	<0.1	<0.01	32.9	<0.1	0.48	8	0.9	<0.2

QUALITY CONTROL REPORT

WHI14000149.1

	Method	WGHT	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201
	Analyte	Wgt	Mo	Cu	Pb	Zn	Ag	Ni	Co	Mn	Fe	As	Au	Th	Sr	Cd	Sb	Bi	V	Ca	P
	Unit	kg	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppb	ppm	ppm	ppm	ppm	ppm	ppm	%	%
	MDL	0.01	0.1	0.1	0.1	1	0.1	0.1	0.1	1	0.01	0.5	0.5	0.1	1	0.1	0.1	0.1	2	0.01	0.001
Pulp Duplicates																					
H12	Rock	2.60	1.9	24.4	6.0	35	0.2	21.2	5.3	574	1.24	9.2	0.6	0.3	1450	0.2	0.2	<0.1	20	22.87	0.034
REP H12	QC		1.4	23.9	5.8	36	0.2	23.6	5.1	588	1.22	10.6	1.2	0.3	1469	0.2	0.1	<0.1	20	22.72	0.036
Reference Materials																					
STD DS10	Standard		15.9	157.8	153.6	357	1.8	74.6	13.2	873	2.76	42.9	87.7	7.9	65	2.6	9.6	11.1	45	1.07	0.074
STD OXC109	Standard		2.1	38.9	11.6	44	<0.1	79.6	21.8	408	2.90	<0.5	192.9	1.7	145	<0.1	<0.1	<0.1	48	0.68	0.108
STD DS10 Expected			14.69	154.61	150.55	370	2.02	74.6	12.9	875	2.7188	43.7	91.9	7.5	67.1	2.49	8.23	11.65	43	1.0625	0.073
STD OXC109 Expected													201								
BLK	Blank		<0.1	<0.1	<0.1	<1	<0.1	0.1	<0.1	<1	<0.01	<0.5	<0.5	<0.1	<1	<0.1	<0.1	<0.1	<2	<0.01	<0.001
Prep Wash																					
G1-WHI	Prep Blank		<0.1	3.4	3.3	48	<0.1	2.2	4.1	562	1.93	<0.5	1.5	5.6	55	<0.1	<0.1	<0.1	37	0.49	0.073
G1-WHI	Prep Blank		<0.1	3.0	3.4	43	<0.1	3.3	4.4	542	1.89	<0.5	1.9	6.0	52	<0.1	<0.1	<0.1	36	0.47	0.071

QUALITY CONTROL REPORT

WHI14000149.1

Method		AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201	AQ201
Analyte		La	Cr	Mg	Ba	Ti	B	Al	Na	K	W	Hg	Sc	Tl	S	Ga	Se
Unit		ppm	ppm	%	ppm	%	ppm	%	%	%	ppm	ppm	ppm	ppm	%	ppm	ppm
MDL		1	1	0.01	1	0.001	1	0.01	0.001	0.01	0.1	0.01	0.1	0.1	0.05	1	0.5
Pulp Duplicates																	
H12	Rock	6	21	1.15	91	<0.001	2	0.30	0.004	0.03	0.1	<0.01	3.7	<0.1	0.35	<1	2.0
REP H12	QC	6	22	1.15	85	0.001	<1	0.32	0.004	0.03	0.1	<0.01	3.8	<0.1	0.35	<1	1.5
Reference Materials																	
STD DS10	Standard	18	56	0.78	373	0.085	7	1.07	0.068	0.34	3.5	0.27	2.8	5.1	0.28	4	2.6
STD OXC109	Standard	13	62	1.46	59	0.404	1	1.52	0.685	0.42	0.2	<0.01	0.9	<0.1	<0.05	5	<0.5
STD DS10 Expected		17.5	54.6	0.775	359	0.0817		1.0259	0.067	0.338	3.32	0.3	2.8	5.1	0.29	4.3	2.3
STD OXC109 Expected																	
BLK	Blank	<1	<1	<0.01	<1	<0.001	<1	<0.01	<0.001	<0.01	<0.1	<0.01	0.2	<0.1	<0.05	<1	<0.5
Prep Wash																	
G1-WHI	Prep Blank	12	5	0.48	160	0.123	1	0.89	0.074	0.46	<0.1	<0.01	2.6	0.4	<0.05	4	<0.5
G1-WHI	Prep Blank	14	6	0.49	155	0.120	2	0.91	0.072	0.47	<0.1	<0.01	2.3	0.3	<0.05	4	<0.5

APPENDIX F

ROCK SPECIMENS

ROCK SPECIMENS

Specimen #	Waypoint #	UTM Coordinates		Description
		East	North	
1(a)	3	3298	4638	Highly foliated dark green chlorite schist (andesite), no pyrite, no magnetite, from contact fault-shear zone (Structure 2)
1(b)	3	3298	4638	Dark green, foliated massive andesite crystal tuff with chloritic surfaces similar to 1(a), less than 1% fine grained pyrite, no magnetite, 3% thin, 3 to 5 mm quartz veinlets.
2	46	4780	4387	Light orange weathering massive blocky outcrop of feldspar porphyry intrusive in Reed-Allen Creek. Fine to medium grain, subhedral orange feldspar phenocrysts in a light grey aphanitic to subhedral plagioclase groundmass, no pyrite or magnetite but the specimen is 'peppered' with a very fine grained metallic black miner ($\pm 1\%$) (not magnetic).
3	65	2502	4389	Light grey feldspathic dike, oxidized dark orange on fractures, less than 1% fine grained pyrite (angular float).
4	67	2422	4493	Dark green foliated tuffaceous andesite, chloritic partings, fine grained pyrite less than 1%, no magnetite.
5	68	2406	4508	Dark grey green, crystalline limestone cut by thin irregular carbonate veinlets. Fine pyrite less than 1%, no magnetite (angular float boulder).
6	71	2355	4524	Good outcrop 10 m by 5 m dark green chloritic schist, thin foliation, numerous orange, thin siderite fracture fillings crossing foliation. Veinlets are highly effervescent in dilute HCl. No magnetite, 1% fine grained pyrite.
7	77	2052	4627	Dark grey green, fine grained diorite, slight foliation, less than 1% fine grained pyrite and possibly chalcopyrite. No magnetite.

ROCK SPECIMENS

Specimen #	Waypoint #	UTM Coordinates		Description
8	(86)	2126	4893	Dark greenish black, fine grained groundmass, minor quartz veinlets with 1% fine grained pyrite, carbonate veinlet. 1% magnetite , slightly foliated. Possibly a crystal tuff, fine grained plagioclase in a dark groundmass.
9	90	2163	4970	Large outcrop on west side of creek 15 m x 8 m. Dark greenish grey, uniformly fine grained diorite, minor magnetite, less than 1% fine grained pyrite, same as Specimen 7.
10	127	4812	3776	Dark green weakly foliated fine grained diorite (andesite?). Distinct crystalline texture with black fine grained laths of hornblende or biotite on edge (10%), 2% to 4% subrounded fine to medium grained clots of quartz (feldspar?). No magnetite or pyrite.
11	131	4886	3675	Dark green-grey, chlorite schist, moderately foliated, a few fine magnetite grains as well as fine grained pyrite – less than 0.5% (andesite?). Possibly related to Specimen 10. Fracture surfaces are coated with thin layer of highly effervescent siderite, bright orange giving the outcrop an orange colouring from a distance.
12	183	3303	4639	Light grey-orange, subhedral light orange feldspar phenocrysts (40%) in an aphanitic grey groundmass. 15% medium grained black hornblende laths. No magnetite or pyrite.
13	183-1	3303	4639	Black, brecciated argillaceous limestone highly effervescent in dilute HCl, 20% erratic clots and veinlets of white calcite. No magnetite or pyrite.
13(a)	183-2	3303	4639	Layered, dark black to dark grey green bands, limey-argillaceous highly altered sediment, minor quartz clots and veinlets, 2% to 3% very fine grained pyrite in thin irregular-discontinuous veinlets. 1% to 3% magnetite and possible pyrrhotite (magnetic) veinlets with fine pyrite.

ROCK SPECIMENS

Specimen #	Waypoint #	UTM Coordinates		Description
14	184	3304	4641	Dark grey-green foliated chlorite schist (andesite crystal tuff) scattered fine to medium grained pyrite associated with highly irregular quartz veinlets. Calcite on fracture planes. No magnetite.
15	199	2855	3874	Dark black-green moderately foliated but with a distinct fine grained crystalline texture. Probably andesite crystal tuff or fine grained diorite. Less than 1% fine grained pyrite, no magnetite.
16	201	2818	3905	Light grey-green quartz (60%) chlorite schist. Strongly foliated. Fine grained pyrrhotite (slightly magnetite) less than 1% in thin discontinuous veinlets and disseminations.
17	202	2819	3917	Light grey fine grained crystalline limestone, no pyrite or magnetite, fine grained 'spots' of manganese(?).

APPENDIX G

COST OF 2014 EXPLORATION PROGRAM

August - September 2014 Exploration Program
Surficial Geology, Placer Gold Evaluation
Geological Mapping and Sampling
Geotechnical Soil and Silt Sampling Program

Field Work

Transportation:

Mobilization and Demobilization Whitehorse to Kelli Claim Group, Reed Creek

1 Ford 250 4 x 4 and trailer	\$ 750.00	
1 Jeep 4 x 4 and trailer	<u>500.00</u>	
		\$ 1,250.00

Transportation of fuel and fuel supplier from Alaska Highway to Kelli Claim Group

1 Argo - 8 wheeler		
	Mobilization August 13 - 14	\$200.00
	Driver	<u>150.00</u>
		350.00
	Demobilization August 15 - 16	200.00
	Driver	<u>150.00</u>
		350.00

Mobilization and demobilization from Alaska Highway to Kelli Claim Group and on-site transportation

2 ATV's August 13 - 28: 16 days @ \$80 / day	1,280.00
--	----------

Field Equipment:

Power saw, 2 sets soil augers, kraft paper geochemical sample bags, rock sample bags, grubhoes, pans, screens, flagging, Garmin GPS, satellite phone

August 13 - 28: 16 days @ \$50 / day	800.00
--------------------------------------	--------

Camp Costs:

Trailer (70' x 14') on site, Mrs. Louis Bouvier, Destruction Bay

August 13 - 28: 16 days @ \$30 / day	480.00
--------------------------------------	--------

Food

August 13 - 28: 16 days @ \$50 / day	800.00
--------------------------------------	--------

Geological Mapping

Outcrop and surficial geology; soil and silt sampling; supervision G. Gutrath, Geologist, P.Eng.

August 13 - 28: 16 days @ \$600 / day	9,600.00
---------------------------------------	----------

Geological and Geochemical Report
Kelli Claim Group

Labour/technician re: soil, silt and pan sampling August 13 - 28: 16 days @ \$200 / day		3,200.00
Sample Analysis (September, 2014) Acme Labs		
Soil and silt sample analysis	2,262.33	
Rock analysis	<u>456.02</u>	
		2,718.35
Map Preparation: UTM Plots (September, 2104) Scale 1:3,000 Underhill Geomatics, Whitehorse		569.63
Data compilation and report G. Guttrath, Geologist, P.Eng. Map preparation, drafting and printing		<u>3,000.00</u>
Total Costs		<u>\$ 24,397.98</u>

Division of Costs Into Two Exploration Programs

- 1) Evaluation of placer gold potential, surficial geology and pan sampling. Field work August 13 to 19, 2014

Seven field days allocated to evaluation of placer gold potential

- 2) Geological mapping, geochemical soil and silt sampling. Field work August 20 to August 28, 2014

Total cost field work for period August 13 to August 28
(16 days) \$18,010

- 1) Exploration program on the Kelli Quartz Claim Group of 72 claims
(Grouping Certificate No. HW07194)

and the

- 2) Placer Claim of 21 claims (Grouping Certificate No. GW01054)

Whitehorse Mining Division, Claim Sheet 115G12

Total cost of field work for both Quartz and Placer claims evaluation for the period August 13 to August 28 (16 days) is \$18,010 or \$1,125 per day

1) **Seven day field program**

Evaluation of placer gold potential, surficial geology and pan sampling costs allocated to placer claim evaluation for period August 13 to 19, 2014 is 7 days at \$1,125 / day

\$ 7,875.00

G. Gutrath, Geologist, P.Eng.

Data compilation and report

1,500.00

Total Costs

\$ 9,375.00

2) **Nine day field program:**

Geological mapping, geochemical soil and silt sampling. Costs allocated to field work August 20 to August 28, 2014 is 9 days at \$1,125 / day

\$ 10,125.00

Acme Labs sample analysis September, 2014:

Soil and silt sampling

\$2,262.33

Rock analysis

456.02

2,718.35

Map preparation - GPS/UTM Plats Scale 1:3000

September, 2014. Underhill Geomatics, Whitehorse, YT

569.63

Data compilation and report

3,000.00

\$ 16,412.98

APPENDIX H

LIST OF CLAIMS, EXPIRY DATES AND OWNERS

Claim Status Report

09 February 2015

Claim Name and Nbr.	Grant No.	Expiry Date	Registered Owner	% Owned	NTS #'s	Grouping	Permit
R ANN 1 - 4	YB35476 - YB35479	2021/01/28	Fred Erler	50.00	115G12	HW07560	
			Kelli J. Tremblay	50.00			
R BUY 1 - 12	YA96221 - YA96232	2018/01/28	Kelli J. Tremblay	33.33	115G12	HW07560	
			Sandra Erler	33.33			
			Kristy Roberts	33.34			
R FRED 3 - 5	YF46654 - YF46656	2016/01/28	Gordon Gutrath	100.00	115G12	HW07560	
R GRACE 1 - 7	YA97463 - YA97469	2018/01/28	Kluane Martin	50.00	115G12	HW07560	
			Louise Bouvier	50.00			
R JO 1	YB24070	2018/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Louise Bouvier	19.00			
			Kluane Martin	19.00			
R JOSIE 1 - 2	YA96350 - YA96351	2018/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Louise Bouvier	19.00			
			Kluane Martin	19.00			
R KELLI 1	YA93845	2021/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Kluane Martin	19.00			
			Louise Bouvier	19.00			
R KELLI 3 - 8	YA93847 - YA93852	2021/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Kluane Martin	19.00			
			Louise Bouvier	19.00			
R KELLI 9 - 18	YA95337 - YA95346	2022/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Louise Bouvier	19.00			
			Kluane Martin	19.00			

Total claims selected : 75

Left column indicator legend:

- R - Indicates the claim is on one or more pending renewal(s).
- P - Indicates the claim is pending.

Right column indicator legend:

- L - Indicates the Quartz Lease.
- F - Indicates Full Quartz fraction (25+ acres)
- P - Indicates Partial Quartz fraction (<25 acres)

- D - Indicates Placer Discovery
- C - Indicates Placer Codiscovery
- B - Indicates Placer Fraction

Claim Status Report

09 February 2015

Claim Name and Nbr.	Grant No.	Expiry Date	Registered Owner	% Owned	NTS #'s	Grouping	Permit
R ROSE 6	YA95981	2018/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Louise Bouvier	19.00			
			Kluane Martin	19.00			

Criteria(s) used for search:

CLAIM DISTRICT: 1000004 CLAIM STATUS: ACTIVE & PENDING DOCUMENT NUMBER: HW07560 REGULATION
TYPE: QUARTZ

Left column indicator legend:

- R - Indicates the claim is on one or more pending renewal(s).
- P - Indicates the claim is pending.

Right column indicator legend:

- L - Indicates the Quartz Lease.
- F - Indicates Full Quartz fraction (25+ acres)
- P - Indicates Partial Quartz fraction (<25 acres)

Total claims selected : 75

- D - Indicates Placer Discovery
- C - Indicates Placer Codiscovery
- B - Indicates Placer Fraction

Claim Status Report

09 February 2015

Claim Name and Nbr.	Grant No.	Expiry Date	Registered Owner	% Owned	NTS #'s	Grouping	Permit
R KELLI 19 - 26	YA96352 - YA96359	2018/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Louise Bouvier	19.00			
			Kluane Martin	19.00			
R KRISTY 1 - 2	YB26868 - YB26869	2021/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Louise Bouvier	19.00			
			Kluane Martin	19.00			
R KRISTY 3	YB35800	2021/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Louise Bouvier	19.00			
			Kluane Martin	19.00			
R KRISTY 5 - 14	YB35801 - YB35810	2021/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Louise Bouvier	19.00			
			Kluane Martin	19.00			
R RENO 1 - 2	YA97470 - YA97471	2018/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Louise Bouvier	19.00			
			Kluane Martin	19.00			
R ROSE 1 - 4	YA95976 - YA95979	2018/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Louise Bouvier	19.00			
			Kluane Martin	19.00			
R ROSE 5	YA95980	2021/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Louise Bouvier	19.00			
			Kluane Martin	19.00			

Total claims selected : 75

Left column indicator legend:

- R - Indicates the claim is on one or more pending renewal(s).
- P - Indicates the claim is pending.

Right column indicator legend:

- L - Indicates the Quartz Lease.
- F - Indicates Full Quartz fraction (25+ acres)
- P - Indicates Partial Quartz fraction (<25 acres)

- D - Indicates Placer Discovery
- C - Indicates Placer Codiscovery
- B - Indicates Placer Fraction

Claim Status Report

09 February 2015

Claim Name and Nbr.	Grant No.	Expiry Date	Registered Owner	% Owned	NTS #'s	Grouping	Permit
R KELLI 1	YA93845	2021/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Kluane Martin	19.00			
			Louise Bouvier	19.00			
R KELLI 3 - 8	YA93847 - YA93852	2021/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Kluane Martin	19.00			
			Louise Bouvier	19.00			
R KELLI 9 - 18	YA95337 - YA95346	2022/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Louise Bouvier	19.00			
			Kluane Martin	19.00			
R KELLI 19 - 26	YA96352 - YA96359	2018/01/28	Sulo Poystila	25.00	115G12	HW07560	
			Kelli J. Tremblay	37.00			
			Louise Bouvier	19.00			
			Kluane Martin	19.00			

Criteria(s) used for search:

CLAIM DISTRICT: 1000004 CLAIM NAME: KELLI CLAIM STATUS: ACTIVE & PENDING REGULATION TYPE: QUARTZ

Total claims selected : 25


Left column indicator legend:

- R - Indicates the claim is on one or more pending renewal(s).
- P - Indicates the claim is pending.


Right column indicator legend:

- L - Indicates the Quartz Lease.
- F - Indicates Full Quartz fraction (25+ acres)
- P - Indicates Partial Quartz fraction (<25 acres)

- D - Indicates Placer Discovery
- C - Indicates Placer Codiscovery
- B - Indicates Placer Fraction



- LEGEND**
- Geology**
- Quaternary
- Glacial deposits
- Tertiary to Miocene
- Light orange weathering dacite dikes, fine grained to aphanitic, plagioclase and lesser quartz
- Oligocene
- Light grey weathering with a blocky joint pattern. White, fine to medium grained subvolcanic plagioclase in a fine grained plagioclase groundmass with 2% to 5% fine grained mafic inclusions. The northern section of the Middle Canyon has a large volcanic area to the north-south sub-parallel the creek canyon.
- Mesozoic
- Pennsylvanian - Permian
- Stetson Group - Stetson Creek Formation
- Black graphic phyllite, often limy with interbedded limestone and quartz siltstone schist. Lower foliated greenstone, in Lower Canyon light is involved by numerous dacite dikes and subsequent intense shearing, faulting and folding has broken the dikes into irregular segments with light. Dissected fine scale 1% to 5% fine grained dacite.
 - Light cream to tan colored sericite quartz schist
- Symbols / Abbreviations**
- and andesite
 - chl sch chlorite schist
 - ser sch sericite schist
 - arg argillite
 - ox oxidized / pyritic
 - carb carbonate
 - qv quartz veins
 - lms limestone
 - py pyrite
 - mag magnetite + low% to +++high%
 - ca calcite (limy) + low% to +++high%
 - outline of rock outcrop
 - inferred outline of outcrop
 - geological contact
 - inferred geological contact
 - fault / intense shearing
 - bedding attitude
 - schistosity / foliation attitude
 - attitude of fold axis and plunge
 - joint attitude
 - slope
 - hand specimen
 - sample for analysis
 - old workings ± 1900s-40s
 - placer claim points
 - quartz claim points
 - road
 - edge of crest gravels
 - building/stepped overhang
 - building/branch
 - mask masking (permafrost)
 - skid skid black scoria
 - sp tall spruce (thicket?)
 - w willow
 - al alder
- Geochemical Soil and Silt Sampling**
- O 25 x128 Soil sample number and waypoint location
 - 15 x65 Silt sample number and waypoint location
 - 125 ppb Au Analytical values 27 ppb Au elevated or anomalous values
 - PF Could not obtain sample because of permafrost



KELLI CLAIM GROUP

WHITEHORSE MINING DIVISION

Donjek River – Reed Creek Area

Mapsheet 115 G 12 UTM Zone 7 NAD 83

Geology and Geochemical Map

By: Gordon Gutrath, geologist, P.Eng

Date: February 10, 2015

MAP 1

WHITEHORSE MINING DIVISION
DONJEK RIVER – REED CREEK AREA
Mapsheet 115 G 12 UTM Zone 7 NAD 83

BY: Gordon Gutrath, geologist P.Eng.
Date: February 10, 2015

Scale: 1 : 3000

Geochemical Soil and Silt Sampling

- 25 x128 Soil sample number and waypoint UTM location
● 15 x65 Silt sample number and waypoint UTM location
125 ppb Au Analytical values are only noted if considered anomalous
PF Could not obtain sample because of permafrost

	Rock specimen location
	Shearing attitude
	Fault / lineament often represented by a topographic feature such as a gully
	Outline of rock outcrop area
	Slope
	Small poorly defined stream channel

